

**RECLAMATION DISTRICT NO. 773
REGULAR MEETING AGENDA FOR
BOARD OF TRUSTEES
9:00 A.M. OCTOBER 4, 2022**

AGENDA

1. Call to Order/Roll Call.
2. Public comment: Under Government Code section 54954.3, members of the public may address the Board on any issue in the District's jurisdiction. The public may address any item on the agenda at the time it is taken up.
3. Consider for approval minutes of the August 2, 2022, Board meetings.
4. District Financial Report.
5. Engineers' Report; request for direction.
 - I. AB 360 Delta Levee Subventions Project
 - A. Review the District's Final Claim for Fiscal Year 2021-2022
 - B. Review the Final Phase 5 Toe Berm Plans for FY 2022-23.
 - C. Review the Levee Maintenance Project for FY 2022-23.
6. Authorize Trustee President to approve award of Phase 5 Toe Berm Project for FY 2022-2023 contract.
7. Authorize Trustee President to approve award of Levee Maintenance Project for FY 2022-2023 contract.
8. Delta Levees Investment Priorities. Discussion and direction regarding public comment on proposed rulemaking change to Sections 5001 and 5012 of Title 23 of the California Code of Regulations.
9. Discussion and Possible Action to Fill Out and Submit Ballot for 2022 Annual Meeting of the California Association of Mutual Water Companies Joint Powers Risk and Insurance Management Authority.
10. Correspondence and meeting attendance reports.
 - I. 2022 Preseason Flood Coordination Meetings
11. District Calendar.
12. Approval of bills to be paid.
13. Adjournment.

This agenda shall be made available upon request in alternative formats to persons with a disability, as required by the Americans with Disabilities Act of 1990 (42 U.S.C. § 12132) and the Ralph M. Brown Act (California Government Code §54954.2). Persons requesting a disability related modification or accommodation in order to participate in the meeting should contact Andy Pinasco at 209/948-8200 during regular business hours, at least twenty-four hours prior to the time of the meeting.

Materials related to an item on this Agenda submitted to the Trustees after distribution of the agenda packet are available for public inspection in the office of the District Secretary at Neumiller & Beardslee, 3121 West March Lane, Suite 100, Stockton, California during normal business hours.

**AGENDA PACKET
RECLAMATION DISTRICT 773
OCTOBER 4, 2022**

<u>ITEM</u>	<u>COMMENTARY</u>
1.	Self-explanatory.
2.	Self-explanatory
3.	Please see attached.
4.	Please see attached.
5.	Please see attached.
6.	Self-explanatory.
7.	Self-explanatory.
8.	Please see attached.
9.	Please see attached.
10.	Please see attached.
11.	Please see attached.
12.	Please see attached.
13.	Self-explanatory.

ITEM 3

**Minutes of Meeting of
Reclamation District 773
Held on August 2, 2022**

The regular meeting of the Board of Trustees of Reclamation District 773 was held at 9:00 a.m. on August 2, 2022, at the District's office located at 3121 West March Lane, Suite 100.

Item No. 1: The meeting was called to order at 9:00 a.m. Present were Trustee Mark Bacchetti, Trustee Joe Enos, Trustee Ryan Bacchetti. Also present were Chris Neudeck, District Engineer, Andy Pinasco, District Secretary, Mr. Muller, a member of the public.

Item No. 2: Public Comment. Mr. Muller, a member of the public, reported that a 5 MPH sign had been placed near King Island. The District's Engineer informed Mr. Muller that RD 773 had no jurisdiction to regulate the 5 MPH sign near King Island.

Item No. 3: Oath of Office. Rhonda Olmo, notary public, administered oath to Trustee Ryan Bacchetti.

Item No. 4: Minutes. The minutes of the June 7, 2022, meeting was approved unanimously by the Trustees present on a motion by Trustee Joe Enos, seconded by Trustee Ryan Bacchetti.

Item No. 5: Mr. Pinasco provided a written financial report and reviewed it with the Trustees. The financial report was accepted by unanimous vote of the Trustees present on a motion by President Mark Bacchetti, seconded by Trustee Ryan Bacchetti.

Item No. 6: Mr. Pinasco reported that District staff no longer recommends the use of District employees and prefers contracting directly with contractors to perform the work. Given such, it would no longer be necessary to carry Workers Compensation Insurance. The Trustees present, on a motion by Trustee Joe Enos, seconded by Trustee Ryan Bacchetti, authorized District staff to cancel the District's current Workers Compensation Insurance policy.

Item No. 7: Engineers' Report; request for direction. Mr. Neudeck summarized the District Engineer's written and oral report.

Item No. 7.a: Authorize Trustee President to approve award of Phase 5 Toe Berm Project contract. Mr. Neudeck provided an oral and written report regarding the Project. Mr. Neudeck reported that the Engineer estimate for the Project would be \$902,750. Mr. Neudeck reported that he would continue to monitor the project engineering and bring it back for reconsideration at a future meeting.

Item No. 7.b: Authorize Trustee President to approve award of Fiscal Year 2022-2023 Levee Maintenance Project. Mr. Neudeck provided an oral and written report regarding

the Project. Mr. Neudeck reported that the Engineer estimate for the Project would be \$181,016. Mr. reported that he would continue to monitor the project engineering and bring it back to the Trustees at a future meeting for reconsideration.

Item No. 8: There was no report on the correspondence in the agenda packet.

Item No. 9: Mr. Pinasco reviewed the District calendar with the Trustees pointing out that the next meeting was on October 3, 2022.

Item No. 10: Mr. Pinasco reported on the outstanding bills that had been received and the status of the District's accounts. On a motion by Trustee Joe Enos, seconded by President Mark Bacchetti, the Trustees present unanimously approved payment of the attached bills identified on the attached bills paid report.

Item No. 11: The meeting was adjourned at 10:00 a.m. by unanimous vote of the Trustees present on a motion by Trustee Joe Enos, seconded by President Mark Bacchetti.

Respectfully submitted,

Andy Pinasco, District Secretary

ITEM 4

RECLAMATION DISTRICT 773
FINANCIAL REPORT OCTOBER 2022 MEETING
25% OF 2022/2023 FISCAL YEAR THROUGH OCTOBER 2022

INCOME	Annual Budget Amount	Received Period TD	Received YTD	% YTD
INTEREST	\$ 2,000.00	\$ -	\$ 763.00	38.15%
ASSESSMENTS (MAX. ALLOWANCE)	\$ 235,793.00	\$ -	\$ -	0.00%
SUBVENTION REIMBURSEMENT	\$ 100,000.00	\$ -	\$ -	0.00%
Total Income	\$ 337,793.00	\$ -	\$ 763.00	0.23%
EXPENSES	Annual Budget Amount	Expended Period TD	Expended YTD	% YTD
<u>GENERAL</u>				
G1 County Assessment Administration	\$ 2,000.00	\$ 1,477.22	\$ 1,477.22	73.86%
G2 Miscellaneous Supplies	\$ 300.00	\$ -	\$ -	0.00%
G3 General Engineering	\$ 25,000.00	\$ 1,978.93	\$ 4,290.19	17.16%
G4 Legal and Accounting	\$ 25,000.00	\$ 2,127.78	\$ 4,546.56	18.19%
G5 Insurance	\$ 15,000.00	\$ 646.25	\$ 10,725.25	71.50%
G6 Contingency	\$ 4,000.00	\$ 2,868.00	\$ 2,868.00	71.70%
Account Funding Placeholder		\$ -		
Total General Expenses	\$ 71,300.00	\$ 9,098.18	\$ 23,907.22	33.53%
<u>LEVEE WORK</u>				
L1 Vegetation Control and Management	\$ 45,000.00	\$ 7,580.00	\$ 7,706.25	17.13%
L2 Rodent Control	\$ 30,000.00	\$ -	\$ -	0.00%
L3 Construct All-Weather Road Surfacing	\$ 15,000.00	\$ -	\$ -	0.00%
L4 Waterside Erosion Repair	\$ 25,000.00	\$ 816.25	\$ 816.25	3.27%
L5 Back Slope Fill Flattening	\$ 250,000.00	\$ 7,891.25	\$ 10,468.75	4.19%
L6 General Levee Maintenance	\$ 50,000.00	\$ 1,746.09	\$ 2,316.09	4.63%
L7 DWR 5 Year Plan	\$ -	\$ -	\$ -	0.00%
Total Levee Work	\$ 415,000.00	\$ 18,033.59	\$ 21,307.34	5.13%
Total Expenses	\$ 486,300.00	\$ 27,131.77	\$ 45,214.56	9.30%
	ANNUAL BUDGET AMOUNT	PTD INCOME/LOSS	YTD INCOME/LOSS	
NET INCOME (LOSS)	\$ (148,507.00)	(\$27,131.77)	\$ (44,451.56)	

Fund Balance as of Beginning of Fiscal Year 2022-2023	\$ 559,452.67
Revenues (YTD)	\$ 763.00
Expenses (YTD)	\$ 45,214.56
Total Cash in General Fund	\$ 515,001.11
Total Restricted Cash in 5 Year Plan Account	\$ 2,636.01
Bank of Stockton	\$ 32,984.39
Total Available Cash	\$ 547,985.50

ITEM 5

**RECLAMATION DISTRICT NO. 773
FABIAN TRACT
BOARD OF TRUSTEES MEETING
TUESDAY, OCTOBER 3, 2022
9:00 AM
ENGINEER'S REPORT**

I. AB 360 DELTA LEVEE SUBVENTIONS PROJECT

A. Review the District's Final Claim for Fiscal Year 2021/22.

TOTAL FINAL CLAIM	\$ 359,819.53
LESS DISTRICT SHARE (1,000/MILE @ 18.8 miles)	\$ 18,800.00
TOTAL ELIGIBLE	\$ 341,019.53
MAX REIMBURSEMENT = 75% OF ELIGIBLE	\$ 255,746.67

- B. Review the Final Phase 5 Toe Berm Plans for FY 2022-23. The project will be bid in the month of October and start in the late fall of 2022. The estimate for this project is within our \$250,000 budget (460+00 to 475+00 – 1,500 l.f.)

EXHIBIT A: Final plan set for Phase V - Toe Berm Construction along Fabian Bell Canal.

- C. Review the levee maintenance project for RD 773 for Fiscal Year 2022-23. The scope of services for the project consists of vegetation control services, erosion repairs, levee road maintenance, and miscellaneous levee grading and cleanup. The project will be bid in the month of October and start in the late fall of 2022. The estimate for the project is \$168,500

EXHIBIT B: Final plan set for levee maintenance project for RD 773 for FY 2022-2023.

Exhibit A

RECLAMATION DISTRICT NO. 773

FABIAN TRACT


SAN JOAQUIN COUNTY, CALIFORNIA

SEPTEMBER 2022

PHASE 5 - LEVEE TOE BERM PROJECT


BETWEEN

STATION 460+00 AND STATION 475+00



DWG NO.	SHEET NO.	DESCRIPTION
G-001	01	TITLE SHEET
G-002	02	NOTES
C-101	03	BASE MAP
C-201 - C-203	04-06	LEVEE SECTIONS
C-501	07	DETAIL


SHEET INDEX



FILE SPEC: P:\2089-Fabian Tract\0390_Phase_5_Toe_Berm\08_Civil\400_Plans\020_CAD_Sheets\G-001_Sht_Title.dwg
PLOT DATE: Sep 27, 2022 11:43am



SUBMITTAL	
%	Date



NO.	DESCRIPTION	DATE	APPR.

DESIGN BY	NGC
DRAWN BY	NGC
CHECK BY	JAM
HORIZONTAL DATUM	CCS83, ZONE 3
VERTICAL DATUM	NAVD88

DRAWING SCALE	N.T.S.
ORIGINAL DRAWING SCALE	0 1/2" 1"



KJELSEN
SINNOCK
NEUDECK
CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com


711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268
1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO. 773
FABIAN TRACT
SAN JOAQUIN COUNTY
PHASE 5 - LEVEE TOE BERM PROJECT
TITLE SHEET

DATE	SEPTEMBER 2022
SHEET IDENTIFICATION	G-001
SHEET 01	OF 07
KSN PROJECT FILE NO.	11 2089-0390

- PRIOR TO THE COMMENCEMENT OF WORK, A JOINT INSPECTION BETWEEN THE ENGINEER, OR HIS REPRESENTATIVE, AND THE CONTRACTOR OR HIS REPRESENTATIVE, WILL BE CONDUCTED TO REVIEW THE PRECONSTRUCTION CONDITIONS OF THE EXISTING FACILITIES IN THE VICINITY OF THE PROJECT SITE, (E.G. ROADS, PUMPS, DISCHARGE PIPES, SIPHONS, RAMPS, GATES, SIGNS, ETC.) IF SUCH EXISTING FACILITIES ARE DAMAGED BY THE CONTRACTOR'S OPERATIONS, THE CONTRACTOR, AT HIS EXPENSE, SHALL REPLACE OR RESTORE THEM TO THE CONDITION THAT EXISTED PRIOR TO THE COMMENCEMENT OF WORK.
2. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT (209) 946-0268, A MINIMUM OF 48 HOURS PRIOR TO THE COMMENCEMENT OF ANY WORK.
3. THE DISTRICT RESERVES THE RIGHT TO SUSPEND CONSTRUCTION AT ANY TIME IN THE EVENT OF EXTREME HIGH OR LOW TIDES, FLOOD EVENTS, OTHER CONDITIONS OR EMERGENCIES THAT MAY JEOPARDIZE THE INTEGRITY OF THE DISTRICT'S LEVEE AND ROAD SYSTEM.
4. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE FEDERAL, STATE, COUNTY AND LOCAL PERMITS AND OR REQUIREMENTS DURING THE PROJECT.
5. THE DISTRICT WILL FURNISH ALL RIGHT-OF-WAY FOR ALL LEVEE ROADS UNDER THE DISTRICT'S JURISDICTION. THE CONTRACTOR WILL SECURE RIGHT-OF-WAY FOR ALL OTHER AREAS NOT UNDER THE DISTRICT'S JURISDICTION.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ACCESS ALONG THE DISTRICT/COUNTY LEVEE ROADS AT ALL TIMES DURING CONSTRUCTION. ANY DAMAGE TO THE LEVEE ROADS AND ACCESS RAMPS SHALL BE IMMEDIATELY REPAIRED BY THE CONTRACTOR AT HIS EXPENSE.
7. THE CONTRACTOR SHALL NOT CLOSE ANY ROAD, STREET, OR HIGHWAY TO THE PUBLIC EXCEPT WITH THE PERMISSION OF THE ENGINEER AND THE PROPER GOVERNMENTAL AUTHORITY. TEMPORARY PROVISIONS SHALL BE MADE BY THE CONTRACTOR TO ENSURE CONTINUOUS ACCESS TO PUBLIC AND PRIVATE DRIVEWAYS, AND PROPER FUNCTIONING OF CULVERTS, DRAINAGE AND IRRIGATION DITCHES, AND NATURAL WATER COURSES.
8. NEITHER THE DISTRICT NOR THE ENGINEER MAKE ANY WARRANTY OR GUARANTEE AS TO THE ADEQUACY OF THE EXISTING NATIVE MATERIALS TO SUPPORT THE CONSTRUCTION TRAFFIC ON THE ACCESS ROADS. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR MAKING THE NECESSARY IMPROVEMENTS AND PROVIDING THE NECESSARY MEASURES REQUIRED TO ACCOMMODATE HIS ANTICIPATED NEEDS.
9. MAXIMUM SPEED LIMIT ON DISTRICT LEVEE ROADS IS 20 MPH, OR AS POSTED.
10. THE ENGINEER WILL PROVIDE LOCATIONS OF THE DESIGNATED PROJECT REPAIR SITES WITH START AND STOP POINTS, AND WILL PROVIDE 200' TEMPORARY BENCHMARKS AT EACH OF THE PROJECT SITES TO BE UTILIZED BY THE CONTRACTOR FOR SETTING ELEVATIONS.
11. THE CONTRACTOR IS RESPONSIBLE FOR SETTING ALL CONSTRUCTION STAKING AND SURVEYING.
12. THE CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND THE CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY AND HOLD THE DISTRICT AND THE DISTRICT'S ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE DISTRICT OR THE ENGINEER.
13. ANY DEFICIENCIES NOTED DURING INTERIM AND FINAL INSPECTIONS BY THE ENGINEER AND/OR DISTRICT, SHALL BE CORRECTED BY THE CONTRACTOR PRIOR TO FINAL ACCEPTANCE BY THE DISTRICT. ANY ADDITIONAL COSTS AND EXPENSES FOR MOBILIZATION AND/OR DEMOBILIZATION, LABOR, EQUIPMENT AND OTHER ASSOCIATED COSTS REQUIRED TO CORRECT THE DEFICIENCIES NOTED, EXCEPT SPECIFIED MATERIAL(S), SHALL BE BORNE BY THE CONTRACTOR.
14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY FIELD CHANGES MADE WITHOUT WRITTEN AUTHORIZATION FROM THE ENGINEER.
15. SHOULD IT APPEAR THAT THE WORK TO BE DONE, OR ANY MATTER RELATIVE THERETO, IS NOT SUFFICIENTLY DETAILED OR EXPLAINED ON THESE PLANS, THE CONTRACTOR SHALL CONTRACT THE ENGINEER AT (209) 946-0268 FOR SUCH FURTHER EXPLANATIONS AS MAY BE NECESSARY.
16. THE INTENT OF THESE PLANS ARE TO SERVE AS A GUIDE AND TO PROVIDE THE CONTRACTOR WITH INFORMATION AND DETAILS NECESSARY TO CONSTRUCT THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE DISTRICT'S ENGINEER IMMEDIATELY REGARDING ANY DISCREPANCIES AND AMBIGUITIES WHICH MAY EXIST IN THE PLANS OR SPECIFICATIONS. IF THE PLANS DESCRIBE PORTION OF THE WORK IN GENERAL TERMS BUT NOT IN COMPLETE DETAIL, IT IS UNDERSTOOD THAT ONLY THE BEST GENERAL PRACTICE IS TO PREVAIL AND THAT ONLY MATERIALS AND WORKMANSHIP OF THE FIRST QUALITY ARE TO BE USED.
17. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE OSHA REGULATIONS.
18. ALL IMPROVEMENTS TO BE DONE SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THESE PLANS AND SPECIFICATIONS.
19. THE CONTRACTOR SHALL NOTIFY THE ENGINEER WHENEVER THERE IS A CHANGE IN SITE CONDITIONS OR AN ADJUSTMENT TO BE MADE IN WORK REQUIREMENTS.
20. THE CONTRACTOR SHALL AT ALL TIMES BE RESPONSIBLE FOR THE SECURITY OF HIS PLANT AND EQUIPMENT. THE DISTRICT WILL NOT BE RESPONSIBLE FOR MISSING OR DAMAGED EQUIPMENT, TOOLS, OR PERSONAL BELONGINGS.

1. THE CONTRACTOR SHALL NOT DISCHARGE SMOKE, DUST, OR ANY OTHER AIR CONTAMINANTS INTO THE ATMOSPHERE IN SUCH QUANTITY AS WILL VIOLATE THE REGULATIONS OF ANY LEGALLY CONSTITUTED AUTHORITY. HE SHALL ALSO ABATE DUST NUISANCE BY CLEANING, SWEEPING AND SPRINKLING WITH WATER, OR OTHER MEANS AS NECESSARY. THE USE OF WATER IN AN AMOUNT WHICH RESULTS IN MUD ON PUBLIC ROADS IS NOT ACCEPTABLE AS A SUBSTITUTE FOR SWEEPING OR OTHER METHODS.

[illegible]

DESIGN BY NGC	DRAWING SCALE N.T.S.
DRAWN BY NGC	
CHECK BY JAM	
HORIZONTAL DATUM CCS83, ZONE 3	ORIGINAL DRAWING SCALE
VERTICAL DATUM NAVD88	0 1/2" 1"



**KJELDSSEN
SINNOCK
NEUDECK**
CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268

1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO. 773
FABIAN TRACT
SAN JOAQUIN COUNTY

PHASE 5 - LEVEE TOE BERM PROJECT NOTES

DATE
SEPTEMBER 2022
SHEET IDENTIFICATION
G-002
SHEET 02 OF 07
KSN PROJECT FILE NO.
12 2089-0390

FILE SPEC: P:\2089_Febian_Tract\0390_Phase_5_Toe_Berm\08_Civil\400_Plans\020_CAD_Sheets\C-101_Sht_BaseMap.dwg
PLOT DATE: Sep 27, 2022 11:44am






SUBMITTAL	
%	Date

LEGEND

 PROJECT LIMITS



NORTH ORIENTATION


PROJECT ENGINEER
9/27/2022

NO.	DESCRIPTION	DATE	APPR.

DESIGN BY	NGC
DRAWN BY	NGC
CHECK BY	JAM
HORIZONTAL DATUM	CCS83, ZONE 3
VERTICAL DATUM	NAVD88

DRAWING SCALE
N.T.S.

ORIGINAL DRAWING SCALE
0 1/2" 1"



KJELSEN SINNOCK NEUDECK
CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268
1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO. 773
FABIAN TRACT
SAN JOAQUIN COUNTY







**PHASE 5 - LEVEE TOE BERM PROJECT
BASE MAP**

DATE
SEPTEMBER 2022

SHEET IDENTIFICATION
C-101


SHEET 03 OF 07
KSN PROJECT FILE NO.
13 2089-0390

FILE SPEC: P:\2089-Fabian_Tract\0390_Phase_5_Toe_Berm\08_Civil\400_Plans\020_CAD\Sheets\220927 Cross-Section Post-Survey - Shorten.dwg
PLOT DATE: Sep 27, 2022 11:45am



SUBMITTAL	
%	Date

LEGEND	
---	PRE-CONSTRUCTION (2019 & 2022 KSN SURVEY)
---	DESIGN TEMPLATE
---	DESIGN FILL



NO.	DESCRIPTION	DATE	APPR.

DESIGN BY	NGC
DRAWN BY	NGC
CHECK BY	JAM
HORIZONTAL DATUM	CCS83, ZONE 3
VERTICAL DATUM	NAVD88

DRAWING SCALE	
VERT: 1" = 10'	
HORZ: 1" = 10'	
ORIGINAL DRAWING SCALE	
0 1/2" 1"	









CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268
1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO. 773
FABIAN TRACT
SAN JOAQUIN COUNTY
**PHASE 5 - LEVEE TOE BERM PROJECT
SECTIONS**
STA 460+00 TO STA 465+00


DATE	SEPTEMBER 2022
SHEET IDENTIFICATION	C-201
SHEET 04 OF 07	
KSN PROJECT FILE NO.	2089-0390

FILE SPEC: P:\2089-Fabian_Tract\0390_Phase_5_Toe_Berm\08_Civil\400_Plans\020_CAD\Sheets\220927 Cross-Section Post-Survey - Shorten.dwg
PLOT DATE: Sep 27, 2022 11:45am



SUBMITTAL	
%	Date

LEGEND	
---	PRE-CONSTRUCTION (2019 & 2022 KSN SURVEY)
---	DESIGN TEMPLATE
---	DESIGN FILL



NO.	DESCRIPTION	DATE	APPR.

DESIGN BY	NGC
DRAWN BY	NGC
CHECK BY	JAM
HORIZONTAL DATUM	CCS83, ZONE 3
VERTICAL DATUM	NAVD88

DRAWING SCALE	
VERT: 1" = 10'	HORZ: 1" = 10'
ORIGINAL DRAWING SCALE	
0	1/2" 1"







CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268
1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO. 773
FABIAN TRACT
SAN JOAQUIN COUNTY
**PHASE 5 - LEVEE TOE BERM PROJECT
SECTIONS**
STA 466+00 TO STA 471+00

DATE	SEPTEMBER 2022
SHEET IDENTIFICATION	C-202
SHEET 05 OF 07	
KSN PROJECT FILE NO.	2089-0390

FILE SPEC: P:\2089-Fabian_Tract\0390_Phase_5_Toe_Berm\08_Civil\400_Plans\020_CAD\Sheets\220927 Cross-Section Post-Survey - Shorten.dwg
PLOT DATE: Sep 27, 2022 11:45am





Know what's below.
Call before you dig.


SUBMITTAL	
%	Date

LEGEND

--- PRE-CONSTRUCTION
(2019 & 2022 KSN SURVEY)

— DESIGN TEMPLATE

DESIGN FILL



PROJECT ENGINEER
JEFFREY A. MULLER
NO. 73738
EXP. 6/30/2023
CIVIL ENGINEER
STATE OF CALIFORNIA
9/27/2022

NO.	DESCRIPTION	DATE	APPR.

DESIGN BY	NGC
DRAWN BY	NGC
CHECK BY	JAM
HORIZONTAL DATUM	CCS83, ZONE 3
VERTICAL DATUM	NAVD88

DRAWING SCALE
VERT: 1" = 10'
HORZ: 1" = 10'
ORIGINAL DRAWING SCALE
0 1/2" 1"




KJELDSSEN
SINNOCK
NEUDECK
CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268
1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO. 773 FABIAN TRACT SAN JOAQUIN COUNTY	DATE SEPTEMBER 2022 SHEET IDENTIFICATION C-203 SHEET 06 OF 07 KSN PROJECT FILE NO. 2089-0390
PHASE 5 - LEVEE TOE BERM PROJECT SECTIONS STA 472+00 TO STA 475+00	

FILE SPEC: P:\2089-Fabian_Tract\0390_Phase_5_Toe_Berm\08_Civil\400_Plans\020_CAD\Sheets\220927 Cross-Section Post-Survey - Shorten.dwg
PLOT DATE: Sep 27, 2022 11:46am




1 TYPICAL TOE BERM DETAIL
SCALE: N.T.S.



SUBMITTAL	
%	Date

LEGEND	
---	PRE-CONSTRUCTION (2019 & 2022 KSN SURVEY)
---	DESIGN TEMPLATE
---	DESIGN FILL



NO.	DESCRIPTION	DATE	APPR.

DESIGN BY	NGC
DRAWN BY	NGC
CHECK BY	JAM
HORIZONTAL DATUM	CCS83, ZONE 3
VERTICAL DATUM	NAVD88

DRAWING SCALE	N.T.S.
ORIGINAL DRAWING SCALE	0 1/2" 1"



CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268
1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO. 773
FABIAN TRACT
SAN JOAQUIN COUNTY

PHASE 5 - LEVEE TOE BERM PROJECT
SECTION DETAIL

DATE	SEPTEMBER 2022
SHEET IDENTIFICATION	C-501
SHEET 07 OF 07	
KSN PROJECT FILE NO.	2089-0390

Exhibit B

RECLAMATION DISTRICT NO. 773

FABIAN TRACT

SAN JOAQUIN COUNTY, CALIFORNIA

LEVEE MAINTENANCE PROJECT - FY 2022/2023

AT VARIOUS LOCATIONS
FROM STATION 0+00 TO STATION 975+25



DWG NO.	SHEET NO.	DESCRIPTION
G-001	1	TITLE SHEET
G-002	2	NOTES
C-101	3	BASE MAP
C-201 - C-205	4 - 8	PLAN VIEW
C-501	9	DETAILS
C-601	10	WORK SITE SCHEDULES

SHEET INDEX



FILE SPEC: P:\2089_Fabian_Tract\0400_Annual_Maintenance_Bid_Projects\22_FY_2022-2023\08_Civil\400_Plans\020_CAD\Sheets\G-001.dwg
PLOT DATE: Aug 09, 2022 - 3:12pm



Know what's below.
Call before you dig.

SUBMITTAL	
%	Date



NORTH ORIENTATION

PROJECT ENGINEER

PRELIMINARY
NOT FOR
CONSTRUCTION

NO.	DESCRIPTION	DATE	APPR.

DESIGN BY NGC	DRAWING SCALE
DRAWN BY NGC	N.T.S.
CHECK BY JAM	ORIGINAL DRAWING SCALE
HORIZONTAL DATUM CCS83, ZONE 3	0 1/2" 1"
VERTICAL DATUM NAVD88	



CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268

1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO. 773
LEVEE MAINTENANCE PROJECT - FY 2022/2023
SAN JOAQUIN COUNTY, CA

TITLE SHEET

DATE AUGUST 2022
SHEET IDENTIFICATION G-001
SHEET 1 OF 10 KSN PROJECT FILE NO. 2089-0400

FILE SPEC: P:\2089_Fobion_Tract\0400_Annual_Maintenance_Bid_Projects\02_FY_2022-2023\08_Civil\400_Plans\020_CAD_Sheets\G-002.dwg
PLOT DATE: Aug 09, 2022 - 3:12pm

GENERAL NOTES:

1. PRIOR TO THE COMMENCEMENT OF WORK, A JOINT INSPECTION BETWEEN THE ENGINEER, OR HIS REPRESENTATIVE, AND THE CONTRACTOR, OR HIS REPRESENTATIVE, WILL BE CONDUCTED TO REVIEW THE PRECONSTRUCTION CONDITIONS OF THE EXISTING FACILITIES IN THE VICINITY OF THE PROJECT SITE, (E.G. ROADS, PUMPS, DISCHARGE PIPES, SIPHONS, RAMPS, GATES, SIGNS, ETC.). IF SUCH EXISTING FACILITIES ARE DAMAGED BY THE CONTRACTOR'S OPERATIONS, THE CONTRACTOR, AT HIS EXPENSE, SHALL REPLACE OR RESTORE THEM TO THE CONDITION THAT EXISTED PRIOR TO THE COMMENCEMENT OF WORK.
2. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT (209) 946-0268, A MINIMUM OF 48 HOURS PRIOR TO THE COMMENCEMENT OF WORK.
3. THE DISTRICT RESERVES THE RIGHT TO SUSPEND CONSTRUCTION AT ANY TIME IN THE EVENT OF EXTREME HIGH OR LOW TIDES, FLOOD EVENTS, OTHER CONDITIONS OR EMERGENCIES THAT MAY JEOPARDIZE THE INTEGRITY OF THE DISTRICT'S LEVEE AND ROAD SYSTEM.
4. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE FEDERAL, STATE, COUNTY AND LOCAL REQUIREMENTS, AS REQUIRED FOR TRAFFIC CONTROL AND PUBLIC SAFETY DURING PROJECT CONSTRUCTION.
5. THE DISTRICT WILL FURNISH ALL RIGHT-OF-WAYS FOR ALL LEVEE ROADS AND ACCESS ROADS UNDER THE DISTRICT'S JURISDICTION. THE CONTRACTOR WILL SECURE RIGHT-OF-WAYS FOR ALL OTHER AREAS NOT UNDER THE DISTRICT'S JURISDICTION.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ACCESS FOR LOCAL TRAFFIC ALONG THE DISTRICT LEVEE ROADS AND ACCESS ROADS AT ALL TIMES DURING CONSTRUCTION. ANY DAMAGE TO THE LEVEE ROADS AND ACCESS ROADS SHALL BE IMMEDIATELY REPAIRED BY THE CONTRACTOR AT HIS EXPENSE.
7. IF DELIVERING MATERIAL OR EQUIPMENT BY TRUCK, ALL TRUCK TRAFFIC SHALL BE LIMITED TO THE DISTRICT LEVEE ROADS AND ACCESS ROADS, UNLESS OTHERWISE APPROVED.
8. MAXIMUM SPEED LIMIT ON DISTRICT LEVEE ROADS IS 30 MPH, OR AS POSTED.
9. THE ENGINEER WILL PROVIDE THE LOCATION OF THE DESIGNATED PROJECT REPAIR SITES WITH A START AND STOP POINT, AND WILL PROVIDE TEMPORARY BENCHMARKS IN THE VICINITY OF THE PROJECT SITE TO BE UTILIZED BY THE CONTRACTOR FOR SETTING ELEVATIONS.
10. THE CONTRACTOR IS RESPONSIBLE FOR SETTING ALL CONSTRUCTION STAKING AND SURVEYING, AS MAY BE REQUIRED FOR CONSTRUCTION ACTIVITIES, INCLUDING, BUT NOT LIMITED TO, SETTING ANY ELEVATIONS AS REQUIRED THROUGHOUT THE PROJECT SITE.
11. ANY DEFICIENCIES NOTED DURING INTERIM AND FINAL INSPECTIONS BY THE ENGINEER AND/OR DISTRICT, SHALL BE CORRECTED BY THE CONTRACTOR PRIOR TO FINAL ACCEPTANCE BY THE DISTRICT. ANY ADDITIONAL COSTS AND EXPENSES FOR MOBILIZATION AND/OR DEMOBILIZATION, LABOR, EQUIPMENT AND OTHER ASSOCIATED COSTS REQUIRED TO CORRECT THE DEFICIENCIES NOTED, EXCEPT SPECIFIED MATERIAL(S), SHALL BE BORNE BY THE CONTRACTOR.
12. ALL IMPROVEMENTS TO BE DONE SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THESE PLANS AND SPECIFICATIONS.
13. THE INTENT OF THESE PLANS ARE TO SERVE AS A GUIDE AND TO PROVIDE THE CONTRACTOR WITH INFORMATION AND DETAILS NECESSARY TO CONSTRUCT THE PROJECT AND FURNISH THE NECESSARY LABOR, MATERIALS, AND EQUIPMENT TO PERFORM THE WORK IN ACCORDANCE WITH THEIR TRUE INTENT AND PURPOSE. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY REGARDING ANY DISCREPANCIES AND AMBIGUITIES WHICH MAY EXIST IN THE PLANS OR SPECIFICATIONS. IF THE PLANS DESCRIBE PORTION OF THE WORK IN GENERAL TERMS BUT NOT IN COMPLETE DETAIL, IT IS UNDERSTOOD THAT ONLY THE BEST GENERAL PRACTICE IS TO PREVAIL AND THAT ONLY MATERIALS AND WORKMANSHIP OF THE FIRST QUALITY ARE TO BE USED.
14. SHOULD IT APPEAR THAT THE WORK TO BE DONE, OR ANY MATTER RELATIVE THERETO, IS NOT SUFFICIENTLY DETAILED OR EXPLAINED ON THESE PLANS, THE CONTRACTOR SHALL CONTACT THE ENGINEER AT (209) 946-0268 FOR SUCH FURTHER EXPLANATIONS AS MAY BE NECESSARY.
15. THE CONTRACTOR SHALL NOTIFY THE ENGINEER WHENEVER IT APPEARS THERE IS A CHANGE IN SITE CONDITIONS OR AN ADJUSTMENT TO BE MADE IN WORK REQUIREMENTS.
16. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY FIELD CHANGES MADE WITHOUT WRITTEN AUTHORIZATION FROM THE ENGINEER.
17. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE OSHA REGULATIONS.
18. THE CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND THE CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY AND HOLD THE DISTRICT AND THE ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE ENGINEER.
19. THE CONTRACTOR SHALL AT ALL TIMES BE RESPONSIBLE FOR THE SECURITY OF HIS PLANT AND EQUIPMENT. THE DISTRICT WILL NOT TAKE ANY RESPONSIBILITY FOR MISSING OR DAMAGED EQUIPMENT, TOOLS, OR PERSONAL BELONGINGS.
20. UNLESS NOTED OTHERWISE, THE CONTRACTOR SHALL NOT CLOSE ANY ROAD, STREET, OR HIGHWAY TO THE PUBLIC EXCEPT WITH THE PERMISSION OF THE ENGINEER AND THE PROPER GOVERNMENTAL AUTHORITY. TEMPORARY PROVISIONS SHALL BE MADE BY THE CONTRACTOR TO ENSURE CONTINUOUS ACCESS TO PUBLIC AND PRIVATE DRIVEWAYS, AND PROPER FUNCTIONING OF DRAINAGE INLETS, GUTTERS, CULVERTS, DRAINAGE AND IRRIGATION DITCHES, AND NATURAL WATER COURSES.

21. CONTRACTOR IS RESPONSIBLE FOR THE PRESERVATION OF SURVEY MONUMENTS LOCATED WITHIN THE AREA OF WORK HEREIN PERMITTED. PRIOR TO THE START OF CONSTRUCTION, CONTRACTOR SHALL ENSURE THAT SURVEY MONUMENTS THAT POTENTIALLY MAY BE DISTURBED SHALL BE LOCATED AND REFERENCED BY A LICENSED LAND SURVEY AND A CORNER RECORD BE FILED WITH THE COUNTY SURVEYOR. ANY SURVEY MONUMENTS DISTURBED DURING THE COURSE OF CONSTRUCTION SHALL BE REESTABLISHED BY A LICENSED LAND AND ANOTHER CORNER RECORD FILED WITH THE COUNTY SURVEYOR. (LAND SURVEYORS' ACT SECTION 8771)

ENVIRONMENTAL NOTES:

1. THE CONTRACTOR SHALL MAINTAIN AIR POLLUTION CONTROLS BY NOT DISCHARGING SMOKE, DUST, OR ANY OTHER AIR CONTAMINANTS INTO THE ATMOSPHERE IN SUCH QUANTITY AS WILL VIOLATE THE REGULATIONS OF ANY LEGALLY CONSTITUTED AUTHORITY. THE CONTRACTOR SHALL ALSO ABATE DUST NUISANCE BY CLEANING, SWEEPING AND SPRINKLING WITH WATER, OR OTHER MEANS AS NECESSARY. THE USE OF WATER IN AN AMOUNT WHICH RESULTS IN MUD ON PUBLIC ROADS IS NOT ACCEPTABLE AS A SUBSTITUTE FOR SWEEPING OR OTHER METHODS.
2. THE CONTRACTOR SHALL EXERCISE EVERY REASONABLE PRECAUTION AND COMPLY WITH ALL PERMITS TO PROTECT STREAMS, WATERWAYS AND OTHER BODIES OF WATER FROM POLLUTION WITH FUELS, OIL, BITUMEN'S, CALCIUM CHLORIDE, AND OTHER HARMFUL MATERIALS AND SHALL CONDUCT AND SCHEDULE HIS OPERATIONS SO AS TO AVOID OR MINIMIZE MUDDYING AND SILTING OF SAID WATERS. CARE SHALL BE EXERCISED TO PRESERVE ROADSIDE VEGETATION BEYOND THE LIMITS OF CONSTRUCTION.
3. THROUGHOUT ALL PHASES OF CONSTRUCTION, INCLUDING SUSPENSION OF WORK, AND UNTIL FINAL ACCEPTANCE OF THE PROJECT, THE CONTRACTOR SHALL KEEP THE WORK SITE CONDITIONS CLEAN AND FREE FROM RUBBISH AND DEBRIS.

DUST AND MUD CONTROL:

1. DURING THE COURSE OF CONSTRUCTION, THE CONTRACTOR SHALL KEEP ALL CONSTRUCTION AREAS, EXCAVATION AND LEVEE CROWN FILL AREAS, ACCESS ROADS, OTHER ROADWAYS, AND OTHER USE AREAS WHERE DUST IS GENERATED WELL WATERED; AND DURING WET CONDITIONS, AREAS USED BY LOCAL TRAFFIC, FREE AND CLEAR FROM MUD.

A. CROP DAMAGE: THE CONTRACTOR IS RESPONSIBLE FOR DUST CONTROL TO PREVENT CROP DAMAGE AND FOR ANY AREAS IN ADDITION TO THOSE MENTIONED THAT GENERATE DUST AND/OR OTHER CONDITIONS WHICH MIGHT DAMAGE CROPS.

B. NON-WORK DAYS: THE CONTRACTOR IS RESPONSIBLE FOR DUST CONTROL IN ANY PROJECT AREAS, ACCESS ROADS OR CROP AREAS WHICH ARE USED BY THE CONTRACTOR, UNLESS OTHERWISE APPROVED BY THE ENGINEER.
2. WATER WILL BE MADE AVAILABLE FOR THE CONSTRUCTION OPERATIONS FROM THE DISTRICT DRAINAGE CANALS OR FROM THE SURROUNDING WATERWAY. THE PUMPING FACILITY SHALL BE LOCATED IN AN AREA THAT WILL NOT CREATE A TRAFFIC OR MUD HAZARD ON THE LEVEE ROADS USED BY THE PUBLIC, LOCAL TRAFFIC, OR CONSTRUCTION ACTIVITIES.

UTILITY NOTES:

1. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES AND SHALL CONTACT THE RESPECTIVE UTILITY COMPANIES PRIOR TO COMMENCEMENT OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PRESERVATION OF ALL SUCH FACILITIES.
2. THE APPROXIMATE LOCATION OF KNOWN UTILITIES, SUBMARINE CABLES SIPHONS, FERRY CABLES, DISCHARGE PIPES, ETC., MAY BE BE SHOWN ON THE PLANS FOR THE INFORMATION OF THE CONTRACTOR. THE DISTRICT ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OR RELIABILITY OF THIS INFORMATION. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE ACTUAL LOCATION OF ALL UNDERGROUND, SURFACE, OVERHEAD, AND SUBMARINE IMPROVEMENTS, OR FACILITIES WHICH MAY BE SUBJECT TO DAMAGE BY REASON OF HIS OPERATIONS.
3. THE CONTRACTOR SHALL PRESERVE AND PROTECT ALL EXISTING IRRIGATION AND DRAINAGE FACILITIES INCLUDING, BUT NOT LIMITED TO, SIPHONS, DITCHES, CROSSINGS, DISTRIBUTION BOXES, SLIDE GATES, ETC., DURING THE TERM OF THE CONTRACT. THE EXISTING IRRIGATION AND DRAINAGE FACILITIES MUST REMAIN FULLY OPERATIONAL DURING THE PERIOD OF CONSTRUCTION.
4. CONTRACTOR SHALL COORDINATE THE RECONSTRUCTION OF EXISTING SIPHON PIPES WITH THE LANDOWNERS' IRRIGATION SCHEDULE.

POWER LINES:

1. THE CONTRACTOR SHALL TAKE NOTE OF POWER LINES WITHIN THE CONSTRUCTION ZONE. EXTREME CAUTION IS ADVISED WHILE WORKING AROUND AND NEAR THESE LIVE LINES.

CLEANUP:

1. THROUGHOUT ALL PHASES OF CONSTRUCTION, INCLUDING SUSPENSION OF WORK, AND UNTIL FINAL ACCEPTANCE OF THE PROJECT, THE CONTRACTOR SHALL KEEP THE PREMISES OCCUPIED BY HIM IN A CLEAN AND ORDERLY CONDITION, DISPOSING OF REFUSE IN A MANNER SATISFACTORY TO THE ENGINEER.
2. THE CONTRACTOR, UPON COMPLETION OF ALL WORK, SHALL RESTORE ALL LEVEE AND ACCESS ROADS, HAUL ROADS, PROJECT SITES, AND ANY OTHER DISTURBED AREAS IN A MANNER SATISFACTORY TO THE ENGINEER, DISTRICT, AND LANDOWNERS.

CONTROL OF EROSION:

1. THE CONTRACTOR SHALL MAINTAIN EARTHWORK SURFACES TRUE AND SMOOTH AND PROTECTED FROM EROSION. WHERE EROSION OCCURS, THE CONTRACTOR SHALL PROVIDE FILL OR SHALL EXCAVATE AS NECESSARY TO RETURN EARTHWORK SURFACES TO THE GRADE AND FINISH SPECIFIED.

CDFW ROUTINE MAINTENANCE AGREEMENT

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE ROUTINE MAINTENANCE AGREEMENT (RMA) AS ISSUED BY THE CALIFORNIA DEPARTMENT OF FISH AND WILDLIFE (CDFW) THAT IS MADE PART OF THE CONTRACT DOCUMENTS. THE INTENT OF THIS PROJECT IS TO CONTROL AND/OR REDUCE WHERE APPLICABLE THE AMOUNT OF VEGETATION THAT IS HINDERING VISUAL INSPECTION OF THE LEVEE CROWN, WATERSIDE SLOPE, AND LANDSIDE SLOPE AND TO PROVIDE SAFE AND UNOBSTRUCTED ACCESS TO THE LEVEE FOR MAINTENANCE AND INSPECTION.

ABBREVIATIONS:

AB	AGGREGATE BASE	LF	LINEAR FEET
AC	ASPHALTIC CONCRETE	LP	LOW POINT
BC	BEGINNING OF CURVE	LT	LEFT
BFE	BASE FLOOD ELEVATION	MAX	MAXIMUM
BM	BENCHMARK	MIN	MINIMUM
CC	CENTER TO CENTER	MHHW	MEAN HIGHER HIGH WATER
CL	CENTERLINE	MLLW	MEAN LOWER LOW WATER
CLSM	CONTROLLED LOW STRENGTH MATERIAL	N	NORTH, NORTHING
CY	CUBIC YARD	(N)	NEW
DIAM	DIAMETER	NIC	NOT IN CONTRACT
DIM	DIMENSION	NO	NUMBER
DWSE	DESIGN WATER SURFACE ELEVATION	NTS	NOT TO SCALE
E	EAST, EASTING	OC	ON CENTER
(E)	EXISTING	OD	OUTSIDE DIAMETER
EA	EACH	PL	PROPERTY LINE
EC	END OF CURVE	PRC	POINT OF REVERSE CURVATURE
EG	EXISTING GROUND	R	RADIUS
EL, ELEV	ELEVATION	RC	RELATIVE COMPACTION
EP	EDGE OF PAVEMENT	ROW	RIGHT-OF-WAY
EW	EACH WAY	RT	RIGHT
EX	EXISTING	SPEC	SPECIFICATION
FG	FINISH GRADE	SF	SQUARE FEET
FL	FLOWLINE	STA	STATION
FT	FOOT, FEET	STD	STANDARD
GB	GRADE BREAK	SY	SQUARE YARD
HDPE	HIGH DENSITY POLYETHENE	TEMP	TEMPORARY
HORIZ	HORIZONTAL	TN	TON
HP	HIGH POINT	TYP	TYPICAL
ID	INSIDE DIAMETER	UNO	UNLESS NOTED OTHERWISE
IN	INCH, INCHES	VERT	VERTICAL
INV	INVERT	YR	YEAR

CONVENTIONS:

	←	BENCHMARK - VERTICAL & HORIZONTAL
	←	BENCHMARK - VERTICAL ONLY
	←	TEMPORARY CONTROL POINT OR TEMPORARY BENCHMARK
	←	DETAIL INDICATOR
	←	DETAIL IDENTIFICATION NUMBER
	←	DRAWING NUMBER WHERE DETAIL IS SHOWN
	←	SECTION INDICATOR
	←	SECTION IDENTIFICATION NUMBER
	←	DRAWING NUMBER WHERE SECTION IS SHOWN
	←	NOTE IDENTIFICATION NUMBER
	←	REVISION NUMBER

	SUBMITTAL	
	%	Date

PROJECT ENGINEER PRELIMINARY NOT FOR CONSTRUCTION				
	NO.	DESCRIPTION	DATE	APPR.

DESIGN BY	NGC	DRAWING SCALE
DRAWN BY	NGC	
CHECK BY	JAM	
HORIZONTAL DATUM	CCS83, ZONE 3	ORIGINAL DRAWING SCALE
VERTICAL DATUM	NAVD88	
		0 1/2" 1"

KJELDSSEN
SINNOCK
NEUDECK

CIVIL ENGINEERS & LAND SURVEYORS


www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268

1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO.773 LEVEE MAINTENANCE PROJECT - FY 2022/2023 SAN JOAQUIN COUNTY, CA	DATE AUGUST 2022 SHEET IDENTIFICATION G-002 SHEET 2 OF 10 KSN PROJECT FILE NO. 2089-0400
NOTES	

FILE SPEC: P:\2089_Fabian_Tract\0400_Annual_Maintenance_Bid_Projects\22_FY_2022-2023\08_Civil\400_Plans\020_CAD_Sheets\C-101.dwg
PLOT DATE: Aug 08, 2022 - 3:11pm





SUBMITTAL	
%	Date



PROJECT ENGINEER

**PRELIMINARY
NOT FOR
CONSTRUCTION**

NO.	DESCRIPTION	DATE	APPR.


DESIGN BY	NGC
DRAWN BY	NGC
CHECK BY	JAM
HORIZONTAL DATUM	CCS83, ZONE 3
VERTICAL DATUM	NAVD88

DRAWING SCALE

1" = 2000'

ORIGINAL DRAWING SCALE

0 1/2" 1"





711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268
1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900
www.ksninc.com

RECLAMATION DISTRICT NO.773
LEVEE MAINTENANCE PROJECT - FY 2022/2023
SAN JOAQUIN COUNTY, CA

BASE MAP

DATE
AUGUST 2022

SHEET IDENTIFICATION
C-101

SHEET 3 OF 10

KSN PROJECT FILE NO.
2089-0400

FILE SPEC: P:\2089-Fabian-Tract\0400_Annual_Maintenance_Bid_Projects\22_FY_2022-2023\08_Civil\400_Plans\020_CAD_Sheets\C-201.dwg
PLOT DATE: Aug 09, 2022 - 3:03pm



LEGEND		
COLOR	WORK DESCRIPTION	DETAIL
—	SUPPLEMENTAL AGGREGATE BASE	1 C-501
—	SELECTIVE TREE & SHRUB REMOVAL & TRIMMING	2 C-501
—	ROCK SLOPE PROTECTION - EROSION	3 C-501
—	REPAIR WASHBOARD ROAD	4 C-501
—	MISCELLANEOUS GRADING	5 C-501

NOTES:

1. WORK SITE LIMITS SHOWN ON THIS SHEET AND ON SHEET C-601 ARE APPROXIMATE AND SHALL BE FIELD VERIFIED.

	SUBMITTAL
	% Date



PROJECT ENGINEER
**PRELIMINARY
NOT FOR
CONSTRUCTION**

NO.	DESCRIPTION	DATE	APPR.

DESIGN BY NGC
DRAWN BY NGC
CHECK BY JAM
HORIZONTAL DATUM
CCS83, ZONE 3
VERTICAL DATUM
NAVD88

DRAWING SCALE
1" = 500'
ORIGINAL DRAWING SCALE
0 1/2 1"



711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268
1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO.773
LEVEE MAINTENANCE PROJECT - FY 2022/2023
SAN JOAQUIN COUNTY, CA

PLAN VIEW
STA 0+00 TO STA 260+00

DATE
AUGUST 2022
SHEET IDENTIFICATION
C-201
SHEET 4 OF 10
KSN PROJECT FILE NO.
2089-0400

FILE SPEC: P:\2089_Fabian_Trect\0400_Annual_Maintenance_Bid_Projects\22_FY_2022-2023\08_Civil\400_Plans\020_CAD_Sheets\C-201.dwg
PLOT DATE: Aug 09, 2022 - 3:03pm



LEGEND		
COLOR	WORK DESCRIPTION	DETAIL
	SUPPLEMENTAL AGGREGATE BASE	1 C-501
	SELECTIVE TREE & SHRUB REMOVAL & TRIMMING	2 C-501
	ROCK SLOPE PROTECTION - EROSION	3 C-501
	REPAIR WASHBOARD ROAD	4 C-501
	MISCELLANEOUS GRADING	5 C-501

NOTES:

1. WORK SITE LIMITS SHOWN ON THIS SHEET AND ON SHEET C-601 ARE APPROXIMATE AND SHALL BE FIELD VERIFIED.



SUBMITTAL	
%	Date



PROJECT ENGINEER
**PRELIMINARY
NOT FOR
CONSTRUCTION**

NO.	DESCRIPTION	DATE	APPR.

DESIGN BY NGC	DRAWING SCALE 1" = 50'
DRAWN BY NGC	
CHECK BY JAM	ORIGINAL DRAWING SCALE 0 1/2" 1"
HORIZONTAL DATUM CCS83, ZONE 3	
VERTICAL DATUM NAVD88	



**KJELSEN
SINNOCK
NEUDECK**
inc.
CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268

1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO.773
LEVEE MAINTENANCE PROJECT - FY 2022/2023
SAN JOAQUIN COUNTY, CA

PLAN VIEW
STA 260+00 TO STA 400+00

DATE
AUGUST 2022

SHEET IDENTIFICATION
C-202
SHEET 5 OF 10
KSN PROJECT FILE NO.
2089-0400

FILE SPEC: P:\2089_Fabian_Tract\0400_Annual_Maintenance_Bid_Plan\22_FY_2022-2023\08_Civil\400_Plans\020_CAD\Sheets\C-201.dwg
PLOT DATE: Aug 09, 2022 - 3:03pm



LEGEND		
COLOR	WORK DESCRIPTION	DETAIL
Red	SUPPLEMENTAL AGGREGATE BASE	1 C-501
Green	SELECTIVE TREE & SHRUB REMOVAL & TRIMMING	2 C-501
Blue	ROCK SLOPE PROTECTION - EROSION	3 C-501
Purple	REPAIR WASHBOARD ROAD	4 C-501
Orange	MISCELLANEOUS GRADING	5 C-501

NOTES:

1. WORK SITE LIMITS SHOWN ON THIS SHEET AND ON SHEET C-601 ARE APPROXIMATE AND SHALL BE FIELD VERIFIED.



Know what's below.
Call before you dig.

SUBMITTAL	
%	Date



NORTH ORIENTATION

PROJECT ENGINEER

**PRELIMINARY
NOT FOR
CONSTRUCTION**

NO.	DESCRIPTION	DATE	APPR.

DESIGN BY NGC	DRAWING SCALE 1" = 500'
DRAWN BY NGC	
CHECK BY JAM	
HORIZONTAL DATUM CCS83, ZONE 3	
VERTICAL DATUM NAVD88	ORIGINAL DRAWING SCALE 0 1/2" 1"



**KJELDSSEN
SINNOCK
NEUDECK**
inc.
CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268

1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO.773
LEVEE MAINTENANCE PROJECT - FY 2022/2023
SAN JOAQUIN COUNTY, CA

PLAN VIEW
STA 400+00 TO STA 640+00

DATE AUGUST 2022
SHEET IDENTIFICATION C-203
SHEET 6 OF 10
KSN PROJECT FILE NO. 2089-0400

FILE SPEC: P:\2089-Fabian_Tract\0400_Annual_Maintenance_Bid_Plan\2022-2023\08_Civil\400_Plans\020_CAD_Sheets\C-201.dwg
PLOT DATE: Aug 09, 2022 - 3:03pm




LEGEND		
COLOR	WORK DESCRIPTION	DETAIL
	SUPPLEMENTAL AGGREGATE BASE	1 C-501
	SELECTIVE TREE & SHRUB REMOVAL & TRIMMING	2 C-501
	ROCK SLOPE PROTECTION - EROSION	3 C-501
	REPAIR WASHBOARD ROAD	4 C-501
	MISCELLANEOUS GRADING	5 C-501

NOTES:

1. WORK SITE LIMITS SHOWN ON THIS SHEET AND ON SHEET C-601 ARE APPROXIMATE AND SHALL BE FIELD VERIFIED.

	SUBMITTAL				DESIGN BY NGC	DRAWING SCALE		711 N. Pershing Avenue Stockton, CA 95203 209-946-0268 1550 Harbor Blvd., Suite 212 West Sacramento, CA 95691 916-403-5900	RECLAMATION DISTRICT NO.773 LEVEE MAINTENANCE PROJECT - FY 2022/2023 SAN JOAQUIN COUNTY, CA	DATE AUGUST 2022
	%	Date								
									PLAN VIEW STA 640+00 TO STA 800+00	

FILE SPEC: P:\2089_Fobion_Traffic\0400_Annual_Maintenance_Bid_Planets\22_FY_2022-2023\08_Civil\400_Plans\020_CAD_Sheets\C-201.dwg
PLOT DATE: Aug 09, 2022 - 3:02pm



LEGEND		
COLOR	WORK DESCRIPTION	DETAIL
Red	SUPPLEMENTAL AGGREGATE BASE	1 C-501
Green	SELECTIVE TREE & SHRUB REMOVAL & TRIMMING	2 C-501
Blue	ROCK SLOPE PROTECTION - EROSION	3 C-501
Purple	REPAIR WASHBOARD ROAD	4 C-501
Orange	MISCELLANEOUS GRADING	5 C-501

NOTES:
1. WORK SITE LIMITS SHOWN ON THIS SHEET AND ON SHEET C-601 ARE APPROXIMATE AND SHALL BE FIELD VERIFIED.



811
Know what's below.
Call before you dig.

SUBMITTAL	
%	Date



NORTH ORIENTATION

PROJECT ENGINEER


**PRELIMINARY
NOT FOR
CONSTRUCTION**

NO.	DESCRIPTION	DATE	APPR.

DESIGN BY NGC
DRAWN BY NGC
CHECK BY JAM
HORIZONTAL DATUM
CCS83, ZONE 3
VERTICAL DATUM
NAVD88

DRAWING SCALE
1" = 500'

ORIGINAL DRAWING SCALE
0 1/2" 1"





**KJELDSEN
SINNOCK
NEUDECK**
CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268
1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900


RECLAMATION DISTRICT NO.773
LEVEE MAINTENANCE PROJECT - FY 2022/2023
SAN JOAQUIN COUNTY, CA

PLAN VIEW
STA 800+00 TO STA 990+08

DATE
AUGUST 2022

SHEET IDENTIFICATION
C-205
SHEET 8 OF 10
KSN PROJECT FILE NO.
209-0400

FILE SPEC: P:\2089_Fabrication_Track\0400_Annual_Maintenance_Bid_P\2022-2023\020_CAD\0400_Plans\020_CAD\Sheets\C-501.dwg
PLOT DATE: Aug 09, 2022 - 2:59pm




NOTES:

1. REFER TO SHEET C-601 FOR WORK SCHEDULE.


1 SUPPLEMENTAL AGGREGATE BASE
SCALE: NTS

NOTES:

1. VEGETATION MANAGEMENT ZONE:
 - A. TREES SHALL BE TRIMMED 5' ABOVE GROUND LEVEL AND THINNED AS NOTED.
 - B. BRUSH AND WEEDS SHALL NOT BE OVER 12" HIGH AND SHALL BE TRIMMED, MOWED, THINNED, OR REMOVED FOR VISIBILITY AND ACCESS AS NOTED.
 - C. REMOVE SAPLINGS LESS THAN 2" IN DIAMETER AT BREAST HEIGHT AS NOTED, LEAVING THE ROOT SYSTEM UNDISTURBED.
2. SHADED RIVERINE AQUATIC (SRA) ZONE:
 - A. SRA ZONE SHALL GENERALLY BE DEFINED AS THE FIRST ROW OF MATURE TREES ALONG THE EDGE OF WATER.
 - B. ALL VEGETATION SHALL REMAIN UNDISTURBED, UNO.
3. REMOVE DEAD AND DOWNED TREES AND LIMBS AS NOTED.
4. ABSOLUTELY NO ELDERBERRY SHRUBS SHALL BE REMOVED AND/OR TRIMMED.
5. REFER TO SHEET C-601 FOR WORK SCHEDULE.




2 SELECTIVE TREE & SHRUB REMOVAL & TRIMMING
SCALE: NTS



NOTES:

1. CLEARING AND GRUBBING OPERATIONS SHALL INCLUDE THE REMOVAL OF ALL EXISTING RUBBLE AND BROKEN CONCRETE FROM THE ENTIRE WATERSIDE SLOPE AS NOTED.
2. REFER TO SHEET C-601 FOR WORK SCHEDULE.

3 ROCK SLOPE PROTECTION
SCALE: NTS



NOTES:

1. TYPE 'A' BACKFILL: NATIVE MATERIAL.
2. COMPACT NATIVE MATERIAL TO A MINIMUM 90%.

4 LEVEE ROAD
SCALE: NTS

- NOTES:
1. REGRADE AND COMPACT THE GROUND SURFACE AS NOTED TO REPAIR RILLS, DUGOUT STEPS, TIRE RUTS, AND OTHER SURFACE IRREGULARITIES.
 2. REFER TO SHEET C-601 FOR WORK SCHEDULE.

5 MISCELLANEOUS GRADING
SCALE: NTS

 Know what's below. Call before you dig.	SUBMITTAL	
	%	Date



PROJECT ENGINEER
PRELIMINARY
NOT FOR
CONSTRUCTION

NO.	DESCRIPTION	DATE	APPR.

DESIGN BY	NGC
DRAWN BY	NGC
CHECK BY	JAM
HORIZONTAL DATUM	CCS83, ZONE 3
VERTICAL DATUM	NAVD88

DRAWING SCALE	AS SHOWN
ORIGINAL DRAWING SCALE	0 1/2" 1"

KJELDSSEN SINNOCK NEUDECK INC.
CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com
711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268
1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO.773 LEVEE MAINTENANCE PROJECT - FY 2022/2023 SAN JOAQUIN COUNTY, CA		DATE AUGUST 2022
DETAILS		SHEET IDENTIFICATION C-501
		SHEET 9 OF 10 KSN PROJECT FILE NO. 2089-0400

FILE SPEC: F:\2089_Fishon_Tract\0400_Annual_Maintenance_Bld_Proj\02022-2023\FY_2022-2023\020_CAD\Sheets\C-601.dwg
PLOT DATE: Aug 09, 2022 2:57pm



811
Know what's below.
Call before you dig.

SUBMITTAL	
%	Date

SCHEDULE 1 SUPPLEMENTAL AGGREGATE BASE				
STATION START	STATION END	LENGTH (FEET)	APPROX NEW AB (TONS)	THICKNESS (INCHES)
410+00	415+00	500	190	MIN 3
419+00	424+00	500	190	MIN 3
439+00	447+00	800	303	MIN 3

SCHEDULE 2 VEGETATION MANAGEMENT SELECTIVE TREE & SHRUB REMOVAL & TRIMMING				
STATION START	STATION END	LENGTH (FEET)	LOCATION	DESCRIPTION
877+00	881+00	400	LANDSIDE & WATERSIDE	TRIM UP TREES AND REMOVE BRUSH AND WEEDS
885+00	894+00	900	LANDSIDE & WATERSIDE	TRIM UP TREES AND REMOVE BRUSH AND WEEDS
897+00			LANDSIDE & WATERSIDE	TRIM UP TREES AND REMOVE BRUSH AND WEEDS
899+00	900+00	100	LANDSIDE & WATERSIDE	TRIM UP TREES AND REMOVE BRUSH AND WEEDS
902+00	909+00	700	LANDSIDE & WATERSIDE	TRIM UP TREES AND REMOVE BRUSH AND WEEDS
911+75	955+00	4,325	LANDSIDE & WATERSIDE	TRIM UP TREES AND REMOVE BRUSH AND WEEDS

SCHEDULE 3 ROCK SLOPE PROTECTION EROSION				
STATION START	STATION END	APPROX NEW RIPRAP (TONS)	LOCATION	DESCRIPTION
755+60		60	WATERSIDE	REPAIR HOLE, REMOVE FALLEN TREE, AND SUPPLEMENT RIPRAP

SCHEDULE 4 REPAIR WASHBOARD ROAD				
STATION START	STATION END	LENGTH (FEET)	LOCATION	DESCRIPTION
360+00	410+00	5000	CROWN	REPAIR WASHBOARD ROAD

SCHEDULE 5 MISCELLANEOUS GRADING				
STATION START	STATION END	APPROX NEW RIPRAP (TONS)	LOCATION	DESCRIPTION
126+50		20	LANDSIDE	REPAIR RILL

ITEM	STATION	PHOTOS	
SCHEDULE 5	126+50		
SCHEDULE 4	360+00 TO 410+00		
SCHEDULE 3	755+60		

PROJECT ENGINEER

PRELIMINARY
NOT FOR
CONSTRUCTION

NO.	DESCRIPTION	DATE	APPR.

DESIGN BY NGC	DRAWING SCALE
DRAWN BY NGC	N.T.S
CHECK BY JAM	ORIGINAL DRAWING SCALE
HORIZONTAL DATUM CCS83, ZONE 3	0 1/2" 1"
VERTICAL DATUM NAVD88	



**KJELDSSEN
SINNOCK
NEUDECK**
INC.
CIVIL ENGINEERS & LAND SURVEYORS
www.ksninc.com

711 N. Pershing Avenue
Stockton, CA 95203
209-946-0268

1550 Harbor Blvd., Suite 212
West Sacramento, CA 95691
916-403-5900

RECLAMATION DISTRICT NO.773
LEVEE MAINTENANCE PROJECT - FY 2022/2023
SAN JOAQUIN COUNTY, CA

WORK SITE SCHEDULES

DATE
AUGUST 2022

SHEET IDENTIFICATION
C-601
SHEET 10 OF 10
KSN PROJECT FILE NO.
2089-0400

ITEM 8

**State of California
Delta Stewardship Council**

**California Code of Regulations, Title 23. Water Division 6. Delta
Stewardship Council**

**Article 1. Definitions Section 5001. Definitions
and**

**Article 3. Consistency with the Regulatory Policies Contained in the Delta
Plan Section 5012. Prioritization of State Investments in Delta Levees and
Risk Reduction**

Proposed Amendment to Existing Regulation

**(September 23, 2022, Notice of Extension of Written Comment Period and
Continued Hearing for OAL File No. Z2022-0816-07)**

Amend California Code of Regulations, Title 23, section 5001 and section 5012 as follows:

[Note: Set forth below are proposed amendments to Title 23 of the California Code of Regulations. Amendments to existing sections proposed and subject to comment in this rulemaking are shown in underline to indicate additions and ~~strikeout~~ to indicate deletions, compared to the preexisting regulatory language. All other portions remain unchanged and are indicated by the symbol “* * *” for reference.]

§ 5001. Definitions. As used in this division, the terms listed below shall have the meanings noted:

* * * *

(v) “High Priority islands or tracts” means the tracts of land listed under “High Priority” in the Table (Delta Levees Investment Strategy Priorities) of Section 5012 of this title and depicted in Appendix P to the Delta Plan.

(w) “Levee improvement” means any activity that is not levee operation and maintenance, and that is intended to reduce the probability of flooding or the addition of a feature that did not previously exist. Examples of levee improvements include changing levee geometry to reach a higher level of protection, increasing the height of a levee, providing riprap where none previously existed, and other similar activities.

(x) “Levee operation and maintenance” means any activity to retain or maintain the intended functions of flood control facilities and of existing encroachments or needed to keep the system functioning properly. Examples of maintenance activities include

mowing, tree and brush trimming and removal, revetment restoration, rodent control, spraying, painting, coating, patching, burning, and other similar activities but does not include any significant excavation or any excavation during flood season.

(~~vz~~) “Nonnative invasive species,” for purposes of section 5009, means species that establish and reproduce rapidly outside of their native range and may threaten the diversity or abundance of native species through competition for resources, predation, parasitism, hybridization with native populations, introduction of pathogens, or physical or chemical alteration of the invaded habitat.

(~~waa~~) “Nonproject levee” means a local levee owned or maintained by a local agency or private owner that is not a project facility under the State Water Resources Law of 1945, Chapter 1 (commencing with Water Code section 12570) and Chapter 2 (commencing with section 12639 of Part 6 of the Water Code).

(~~bb~~) “Other Priority islands or tracts” means the tracts of land listed under “Other Priority” in the Table (Delta Levees Investment Strategy Priorities) of Section 5012 of this title and depicted in Appendix P to the Delta Plan.

(~~xcc~~) “Project levee” means a federal flood control levee that is a project facility under the State Water Resources Law of 1945, Chapter 1 (commencing with Water Code section 12570) and Chapter 2 (commencing with section 12639 of Part 6 of the Water Code).

(~~ydd~~) “Proposed action” means a plan, program, or project that meets the covered action screening criteria listed in section 5001(j)(1)(A) through (D). Proposed action is also a “covered action,” and therefore subject to compliance with the regulatory policies contained in Articles 2 and 3-if the proposed action meets the covered action screening criterion listed in section 5001(j)(1)(E).

(~~zee~~) “Protection” or “protecting,” for purposes of section 5001(h)(2), means preventing harm to the ecosystem, which could include preventing the conversion of existing habitat, the degradation of water quality, irretrievable conversion of lands suitable for restoration, or the spread of invasive nonnative species.

(~~aaff~~) “Regulated stream” means those streams identified in Table 8.1 of California Code of Regulations, Title 23, section 112, under the jurisdiction of the Board.

(~~bbgg~~) “Restoration” or “restoring,” for purposes of section 5001(h)(2), has the same meaning as in Water Code section 85066. Restoration actions may include restoring interconnected habitats within the Delta and its watershed, restoring more natural Delta flows, or improving ecosystem water quality.

(~~eehh~~) “Setback levee” means a new levee constructed behind an existing levee which allows for removal of a portion of the existing levee and creation of additional floodplain connected to the stream. In the Delta, a “setback levee” may not necessarily result in removal of the existing levee.

(~~deji~~) “Significant impact” for the purpose of determining whether a project meets the definition of a “covered action” under section 5001(j)(1)(D) means a substantial positive or negative impact on the achievement of one or both of the coequal goals or the implementation of a government-sponsored flood control program to reduce

risks to people, property, and State interests in the Delta, that is directly or indirectly caused by a project on its own or when the project's incremental effect is considered together with the impacts of other closely related past, present, or reasonably foreseeable future projects. The following categories of projects will not have a significant impact for this purpose:

(1) "Ministerial" projects exempted from CEQA, pursuant to Public Resources Code section 21080(b)(1);

(2) "Emergency" projects exempted from CEQA, pursuant to Public Resources Code section 21080(b)(2) through (4);

(3) Temporary water transfers of up to one year in duration.

(4) Other projects exempted from CEQA, unless there are unusual circumstances indicating a reasonable possibility that the project will have a significant impact under Water Code section 85057.5(a)(4), as further defined by this section. Examples of unusual circumstances could arise in connection with, among other things:

(A) Local government general plan amendments for the purpose of achieving consistency with the Delta Protection Commission's Land Use and Resource Management Plan; and

(B) Small-scale habitat restoration projects, as referred to in CEQA Guidelines, section 15333 of Title 14 of the California Code of Regulations, proposed in important restoration areas, but which are inconsistent with the Delta Plan's policy related to appropriate habitat restoration for a given land elevation (section 5006 of this Chapter).

(jj) "Very-High Priority islands or tracts" means the tracts of land identified under "Very-High Priority" in the Table (Delta Levees Investment Strategy Priorities) of Section 5012 of this title and depicted in Appendix P to the Delta Plan.

(kk) "Urban area" means a developed area in which there are 10,000 residents or more.

(ll) "Urbanizing area" means a developed area or an area outside of a developed area that is planned or anticipated to have 10,000 residents or more within the next 10 years.

(mm) "Urban water management plan" means a plan prepared, adopted, and updated by an urban water supplier pursuant to the Urban Water Management Planning Act, Water Code section 10610 et seq.

(nn) "Urban water supplier" refers to both "urban retail water suppliers" and "urban wholesale water suppliers":

(1) "Urban retail water supplier" means a water supplier, either publicly or privately owned, that directly provides potable municipal water to more than 3,000 end users or that supplies more than 3,000 acre-feet of potable water annually at retail for municipal purposes.

(2) "Urban wholesale water supplier" means a water supplier, either publicly or privately owned, that provides more than 3,000 acre-feet of potable water annually at wholesale for municipal purposes.

(iioo) "Water supplier" refers to both "urban water suppliers" and "agricultural water suppliers," but for purposes of section 5003, does not include agricultural water suppliers during the time that they may be exempted by section 10853 of the Water Code from the requirements of Parts 2.55 and 2.8 of Division 6 of the Water Code.11

Note: Authority cited: Sections 85210(i), 85210(h), and 85306, Water Code.
Reference: Sections 85057.5, 85059, 85058, 85066, 85020, 85054, 85052, 85302(g), 85308, 85300, 10608.12 and 10853, Water Code.

§ 5012. Prioritization of State Investments in Delta Levees and Risk Reduction.

~~(a) Prior to the completion and adoption of the updated priorities developed pursuant to Water Code section 85306, the interim priorities listed below shall, where applicable and to the extent permitted by law, guide discretionary State investments in Delta flood risk management. Key priorities for interim funding include emergency preparedness, response, and recovery as described in paragraph (1), as well as Delta levees funding as described in paragraph (2).~~

~~(1) Delta Emergency Preparedness, Response, and Recovery: Develop and implement appropriate emergency preparedness, response, and recovery strategies, including those developed by the Delta Multi-Hazard Task Force pursuant to Water Code section 12994.5.~~

~~(2) Delta Levees Funding: The priorities shown in the following table are meant to guide budget and funding allocation strategies for levee improvements. The goals for funding priorities are all important, and it is expected that, over time, the California Department of Water Resources must balance achievement of those goals. Except on islands planned for ecosystem restoration, improvement of nonproject Delta levees to the Hazard Mitigation Plan (HMP) standard may be funded without justification of the benefits. Improvements to a standard above HMP, such as that set by the U.S. Army Corps of Engineers under Public Law 84-99, may be funded as befits the benefits to be provided, consistent with the California Department of Water Resources' current practices and any future adopted investment strategy.~~

**Priorities for State Investment in Delta Integrated Flood Management
Categories of Benefit Analysis**

Goals	Localized Flood Protection	Levee Network	Ecosystem Conservation
4	Protect existing urban and adjacent urbanizing areas by providing 200-year flood protection.	Protect water quality and water supply conveyance in the Delta, especially levees that protect freshwater aqueducts and the primary channels that carry fresh water through the Delta.	Protect existing and provide for a net increase in channel-margin habitat.
2	Protect small communities and critical infrastructure of statewide importance (located outside of urban areas).	Protect flood water conveyance in and through the Delta to a level consistent with the State Plan of Flood Control for project levees.	Protect existing and provide for net enhancement of floodplain habitat.
3	Protect agriculture and local working landscapes.	Protect cultural, historic, aesthetic, and recreational resources (Delta as	Protect existing and provide for net enhancements of wetlands.

(a) Fund levee operation and maintenance. For the purposes of Water Code Section 85306, State investments in levee operation and maintenance of Delta project levees and nonproject levees shall be prioritized as follows:

(1) For project levees, funding should be prioritized to ensure levees are operated and maintained in accordance with Code of Federal Regulations, Title 33, Part 208.10, applicable federal Operation and Maintenance manuals, active in federal Public Law 84-99 Rehabilitation Program, and consistent with Central Valley Flood Protection Board Resolution No. 2018-06 for Acceptable Operation and Maintenance of the State Plan of Flood Control.

(2) For nonproject levees, funding should be prioritized to ensure levees are operated and maintained to protect the Delta's physical characteristics.

(b) Delta levees investment strategy. The priorities listed in the Table 1 below and depicted in Delta Plan Appendix P dated August 2021, which is incorporated herein by this reference as if fully set forth, shall guide State discretionary investments in the improvement of Delta levees. The California Department of Water Resources' funding decisions are subject to its consideration of the benefits, costs, engineering considerations, and other factors. As the California Department of Water Resources selects levee improvement projects for funding through its levee funding programs, it should fund projects at the Very-High priority islands or tracts, before funding projects at High Priority or Other Priority islands or tracts. If available funds are sufficient to fully fund levee improvement projects at the Very-High Priority islands or tracts, then funds for levee improvement projects on High Priority islands or tracts should be funded and after those projects have been fully funded, then levee improvement projects at Other Priority islands or tracts may be funded.

Table 1: Delta Levees Investment Strategy Priorities

<u>Very High Priority</u>	<u>Bacon Island, Bethel Island, Bishop/DLIS-14 (North Stockton), Brannan-Andrus, Byron Tract, DLIS-19 (Grizzly Slough Area), DLIS-28, DLIS-33, DLIS-63 (Grizzly Island Area), Drexler Tract, Dutch Slough*, Hasting Tract, Hotchkiss Tract, Jersey Island, Jones Tract (Upper and Lower), Maintenance Area 9 North, Maintenance Area 9 South, McCormack-Williamson Tract*, McDonald Island, McMullin Ranch, Middle and Upper Roberts Island, New Hope Tract, North Stockton, Paradise Junction, Reclamation District 17, Ryer Island, Sherman Island, Staten Island, Terminous Tract, Twitchell Island, Upper Andrus Island, Victoria Island, Webb Tract.</u>
<u>High Priority</u>	<u>Bouldin Island, Brack Tract, Bradford Island, Cache Haas Area, Central Stockton*, Clifton Court Forebay, DLIS-01 (Pittsburg Area), DLIS-07 (Knightsen Area), DLIS-08 (Discovery Bay Area), DLIS-20 (Yolo Bypass), DLIS-22 (Rio Vista), DLIS-26 (Morrow Island), DLIS-29, DLIS-30, DLIS-31 (Garabaldi Unit), DLIS-32, DLIS-39, DLIS-41 (Joice Island Area), DLIS-44 (Hill Slough Unit), DLIS-55, DLIS-59, Egbert Tract, Fabian Tract, Glanville, Grand Island, Holland Tract, Honker Bay, Kasson District, Libby McNeil, Little Egbert Tract, Lower Roberts Island, Mandeville Island, Mossdale Island, Netherlands, Palm-Orwood, Paradise Cut, Pearson District, Pescadero District*, Rindge Tract, River Junction, Shima Tract, Stewart Tract*, Sunrise Club, Tyler Island, Union Island East, Veale Tract, Walnut Grove, Woodward Island, Yolano.</u>
<u>Other Priority</u>	<u>Atlas Tract, Bixler Tract, Canal Ranch Tract, Chipps Island, Coney Island, Dead Horse Island, DLIS- 06 (Oakley Area), DLIS-10, DLIS-15, DLIS-17, DLIS-18, DLIS-25, DLIS-27, DLIS-34, DLIS-35, DLIS-36, DLIS-37 (Chadbourne Area), DLIS-40, DLIS-43 (Potrero Hills Area), DLIS-46, DLIS-47, DLIS-48, DLIS-49, DLIS-50, DLIS-51, DLIS-52, DLIS-53, DLIS- 54, DLIS- 56, DLIS- 57, DLIS- 62, Drexler Pocket, Ehrheardt Club, Empire Tract, Fay Island, Glide District, Holt Station, Honker Lake Tract, King Island, Lisbon District, Medford Island, Mein's Landing, Merritt Island, Peters Pocket, Pico- Naglee, Prospect Island, Quimby Island, Randall Island, Rio Blanco Tract, Rough And Ready Island, Shin Kee Tract, Stark Tract, Sutter Island, Venice Island, Walthall, West Sacramento, Wetherbee Lake, Winter Island, Wright-Elmwood Tract.</u>

(c) Annual Report.

(1) The California Department of Water Resources shall submit a written annual report to the Council, as well as present the report to the Council, on State funds distributed or provided by the California Department of Water Resources for levee operation, maintenance, repair, rehabilitation, replacement and improvement projects within the legal Delta. At least 45 days prior to the oral presentation before the Council, the

California Department of Water Resources shall submit the written annual report to the Council and make the report publicly available.

(2) The report shall include:

(A) A description of State funds provided for each levee operation, maintenance, repair, rehabilitation, replacement, and improvement program funded during the reporting year;

(B) A list of each levee improvement project proposal submitted to the California Department of Water Resources for funding, regardless of whether the California Department of Water Resources awarded funding to the project;

(C) A list of the improvement projects awarded funding, the funding level awarded, the local cost share, and the applicable priority of the island or tract from Table 1 in paragraph (b)(1) where the levee improvement project is located;

(D) A description, for each awarded project, of changes (when completed) to levee geometry, the specific locations of those changes, and expected changes in the level of flood protection provided or standard achieved;

(E) If the California Department of Water Resources awards funds for any levee improvement project that is inconsistent with the priorities identified in paragraph (b)(1), the annual report shall identify for each project: how the funding is inconsistent with the priorities, describe why variation from the priorities is necessary, and explain how the funding nevertheless protects lives, property, or other State interests, such as infrastructure, agriculture, water supply reliability, Delta ecosystem, or Delta communities;


(F) A summary of The California Department of Water Resources' rationale for levee improvement project proposals submitted, but not awarded funding during the reporting year; and

(G) A summary of all previous California Department of Water Resources funded levee improvement project activities completed during the reporting year and location of those activities.

(b)(d) For purposes of Water Code section 85057.5(a)(3) and section 5001(j)(1)(E) of this Chapter, this policy covers a proposed action that involves discretionary State investments in Delta flood risk management, including levee operations, maintenance, and improvements. Nothing in this policy establishes or otherwise changes existing levee standards.

Note: Authority cited: Sections 85210(i), 85210(h), and 85306, Water Code. Reference: Sections 85020, 85022, 85054, 85057.5, 85300, 85305, and 85306, 85307, and 85309, Water Code.

Appendix P



This page left blank intentionally.

California Code of Regulations, Title 23. Waters
Division 6. Delta Stewardship Council
Chapter 2. Consistency with Regulatory Policies Contained in the
Delta Plan
Article 1. Definitions, Section 5001. Definitions
and
Article 3. Consistency with the Regulatory Policies Contained in
the Delta Plan, Section 5012. Prioritization of State Investments in
Delta Levees and Risk Reduction

Notice of Extension of Written Comment Period and Rescheduled
Hearing for OAL File No. Z-2022-0816-07

NOTICE IS HEREBY GIVEN that the Delta Stewardship Council (Council) has inadvertently filed and posted online an incorrect version of the proposed regulations text for the Office of Administrative Law (OAL) file number Z-2022-0816-07, and, is hereby extending the written comment period and rescheduling the public hearing date, as specified below. The correct version of the proposed regulatory language is available on the Delta Stewardship Council's website at <https://deltacouncil.ca.gov/delta-plan/regulations>.

The Council will conduct a public hearing at the time and place noted below to hear comments, objections, and recommendations. At a separate meeting on a future date, the Council may consider approving for adoption the proposed amendments.

Opportunity for Public Comment

- **Additional Time Extended to the Written Comment Period:** The written comment period for this proposed action is hereby extended to 11:59 p.m. on Wednesday, November 16, 2022. Interested members of the public may provide comments by mail or by electronic submittal. The extended public comment period for this regulatory action is in addition to the previously noticed written comment period. *Please note that any comments received during the originally noticed comment start date of August 26, 2022, through the date of publication of this Notice in the Register do not need to be re-submitted to the Council.* Any interested person, or her or his authorized representative, may submit written comments relevant to the proposed regulatory action.

- Submit written comments to:

Erin Mullin
Delta Stewardship Council
715 P Street, Suite 15-300
Sacramento, CA 95814
(916) 902-6482

- Electronic Submittal of Comments. Any interested person, or her or his authorized representative, may submit comments by electronic submittal at or before 11:59 p.m. on **Wednesday, November 16, 2022. The Council will consider only comments received by the Council by that time.** Electronic submittals of comments are preferred, and must be submitted to the following address to be considered:

amend.rrp1@deltacouncil.ca.gov

- Public Hearing. ****The previously noticed October 27, 2022 public hearing is rescheduled to Thursday, November 17, 2022.**** The Council will conduct a public hearing at the time and location set forth below to consider public input, comments, objections, and recommendations to this proposed action. Interested members of the public may present statements, arguments, and comments, verbally or in writing, with respect to the proposed action at the hearing prior to the closing of the hearing. This hearing will be held in accordance with the requirements set forth in Government Code section 11346.8. A remote virtual option to attend the meeting will also be provided.

Date: November 17, 2022

Time: This item will be considered at a regularly scheduled public meeting of the Council, which is anticipated to commence at **9:00 a.m.** This item may be heard at any time during the regularly scheduled meeting. The public hearing item will remain open as long as attendees are presenting testimony and will conclude after all testimony is given. Please consult the agenda, which will be available at <http://deltacouncil.ca.gov> at least ten (10) days before November 17, 2022, to determine the time at which this item will be heard and to obtain information regarding the remote virtual participation option.

Location: California Natural Resources Building, 2nd Floor Room 221, 715 P Street, Sacramento, CA 95814. The hearing room is wheelchair accessible.

If you have any questions, please contact:

Erin Mullin
Delta Stewardship Council
715 P Street, Suite 15-300
Sacramento, CA 95814
(916) 902-6482
amend.rrp1@deltacouncil.ca.gov

Authority and Reference

Water Code sections 85210(i), 85210(h), and 85306 provide the Council authority for the proposed amendments to California Code of Regulations, Title 23, sections 5001 ("Section 5001") and 5012 ("Section 5012"). Water Code section 85210(i) authorizes the Council to adopt regulations or guidelines as needed to carry out its powers and duties; Water Code section 85210(h) grants the Council the authority "to request reports from state, federal, and local governmental agencies on issues related to the implementation of the Delta Plan"; and Water Code section 85306 authorizes the Council, in consultation with the Central Valley Flood Protection Board (CVFPB), to recommend priorities for state investments in levee operation, maintenance, and improvements in the Delta. This action is proposed to implement, interpret, and make specific one or more of the following: sections 85020, 85022, 85054, 85057.5, 85225, 85300, 85305, 85306, 85307, and 85309 of the Water Code.

Contact Persons

Inquiries concerning the proposed administrative action may be directed to:

Erin Mullin
Delta Stewardship Council
715 P Street, Suite 15-300
Sacramento, CA 95814
(916) 902-6482
amend.rrp1@deltacouncil.ca.gov

The backup contact person to whom inquiries concerning the proposed administrative action may be directed to is:

Eva Bush
Delta Stewardship Council
715 P Street, Suite 15-300
Sacramento, CA 95814
(916) 284-1619
amend.rrp1@deltacouncil.ca.gov

All comments must be submitted as set forth in the "Opportunity for Public Comment" section, above.

Internet Access

Copies of this Notice, the original Notice of Proposed Action published on August 26, 2022 in the Notice Register, the Initial Statement of Reasons, the corrected text of the proposed regulations in underline and strikeout, and all materials published or distributed by the Council regarding this proposed action are available at <https://deltacouncil.ca.gov/dlis/>.

ITEM 9



NOTICE OF ANNUAL MEETING
To be held Monday and Tuesday - October 24-25, 2022

To the Members of California Association of Mutual Water Companies Joint Powers Risk and Insurance Management Authority (CalMutuals JPRIMA):

NOTICE IS HEREBY GIVEN that the Annual Meeting of the California Association of Mutual Water Companies Joint Powers Risk and Insurance Management Authority will be held in person at The Citizen Hotel, 926 J St, Sacramento, CA 95814 on Tuesday, October 25, 2022, 8:00 AM-9:00 AM.

The purpose of the Annual Meeting is to consider and act upon the election of the Board of Directors and other items as may properly come before the Authority's membership.

There will be one Director position up for election as of the date of this Notice. Lynda Noriega, President of California Domestic Water Company, has been nominated for that position and no other nominations have been received to date.

The Authority's ballot for the annual meeting is submitted herewith.

The meeting will be part of a larger two-day conference that will include the California Association of Mutual Water Companies Annual Meeting and presentations, panels, and workshops focused on needs and concerns of small water systems. The conference is scheduled to begin on Monday, October 24, 2022 at 12:00 PM and to continue through Tuesday, October 25, 2022 at 2:00 PM.

By order of the Board of Directors

Susan E. Allen
Chief Executive Officer

IMPORTANT

YOU ARE URGED TO COMPLETE, SIGN AND PROMPTLY RETURN YOUR BALLOT SO THAT YOUR VOTE WILL BE COUNTED AND SO THAT THE PRESENCE OF A QUORUM MAY BE ASSURED. A POSTAGE-PAID RETURN ENVELOPE IS ENCLOSED FOR YOUR CONVENIENCE IN RETURNING YOUR BALLOT. BALLOTS MAY ALSO BE RETURNED BY FAX AT 714-398-8819 OR EMAIL AT SUSAN@CALMUTUALS.ORG



**BALLOT FOR THE 2022 ANNUAL MEETING OF THE
CALIFORNIA ASSOCIATION OF MUTUAL WATER COMPANIES
JOINT POWERS RISK AND INSURANCE MANAGEMENT AUTHORITY**

OCTOBER 24-25, 2022

_____ [insert name
of member company or district] hereby submits its written ballot for the 2022 Annual Meeting of
the California Association of Mutual Water Companies, Joint Power Risk and Insurance
Management Authority marked as follows:

For Director, for a one-year term:

Lynda Noriega California Domestic Water Company	For ☐	Against ☐	Quorum Only ☐
--	------------------------------	----------------------------------	--------------------------------------

Dated: _____, 2022

Name of Member Company or District : _____

By _____
[Signature]

[Printed Name]

Its: _____
[Authorized Officer – Position Title]

Board of Directors Candidate Biography



Lynda Noriega

Lynda Noriega is President of California Domestic Water Company, a wholesale mutual water company based in Whittier, California—a title she's held for almost 5 years.

She began her career in 2001 with Valley County Water District (VCWD), a retail-based special district in Baldwin Park, California serving as Operations Assistant, Water Quality Specialist, Finance & Administrative Manager, and Interim General Manager prior to becoming General Manager in February 2011.

Lynda served as General Manager of VCWD until her hire as the Vice President/General Manager with CalDomestic on March 14, 2016.

She serves as Chair of the Board of Directors for the Main San Gabriel Basin Watermaster, as a member of the Board of Directors for the San Gabriel Valley Water Association, and as a member of the Board of Directors San Gabriel Basin Water Quality Authority.

She obtained her Bachelor of Arts degree in Business Administration with an emphasis in Accounting Theory from California State University, Fullerton in 2007.

ITEM 10

DEPARTMENT OF WATER RESOURCES

DIVISION OF FLOOD MANAGEMENT

P.O. BOX 219000

SACRAMENTO, CA 95821-9000

(916) 574-2605



August 4, 2022

SUBJECT: 2022 PRESEASON FLOOD COORDINATION MEETINGS

The Department of Water Resources (DWR) invites you to attend one of this year's Preseason Flood Coordination Meetings. These meetings are directed to water managers, emergency responders, and managers that deal with flood emergency preparedness and response.

You are receiving this letter because you either attended one of last year's Preseason Flood Coordination Meetings, or are included on the DWR Directory of Flood Officials contact list.

DWR, along with our local, State, and federal partners will provide information on current and future weather, local flood concerns and ER support, flood fight resources, and other related topics to better prepare our organizations for the upcoming flood season. A flyer is enclosed with the locations and times of the meetings being held this fall.

We encourage you to attend and participate in this multi-agency flood emergency preparedness effort.

If you have any questions or need further information, please contact Wendy Francis at (916) 820-7592 or wendy.francis@water.ca.gov. You may also call the Flood Operations Center at (916) 574-2619.

We look forward to working with you on flood emergency preparedness and response.

Sincerely,

A handwritten signature in black ink, appearing to read "Lance Ablang".

Lance Ablang, Manager
State-Federal Flood Operations Center
Department of Water Resources

Enclosure

Division of Flood Management

2022 California Preseason Flood Coordination Meetings



Department of Water Resources



Agenda Topics

Winter Weather Outlook

DWR Flood Operations
Updates

Regional Updates

Multi-Agency Coordination

Flood Fighting Methods and
Materials

Post Fire/Debris Flow

You are invited to join flood emergency response partners to discuss flood preparedness in your region. Hosted by County Offices of Emergency Services in partnership with the DWR's State-Federal Flood Operations Center, these in-person meetings provide regional and local updates on annual flood preparedness activities.

HUMBOLDT

Tuesday, September 27
9:00 am – 11:30 am
Fortuna Volunteer Fire Dept.
Classroom
320 Fortuna Blvd.
Fortuna

SHASTA

Wednesday, September 28
9:00 am – 11:30 am
City of Redding
Community Room
777 Cypress Avenue
Redding

YOLO

Tuesday, October 4
9:00 am – 11:30 am
City Hall Galleria
1110 W. Capitol Avenue
West Sacramento

MARIN *(Virtual option available)*

Thursday, October 20
9:00 am – 11:30 am
Marin County Sheriff's Office
1600 N. Los Gatos (Lobby A)
San Rafael

SAN JOAQUIN

Tuesday, October 25
9:00 am – 11:30 am
San Joaquin County OES
2101 E. Earhart Avenue
Stockton

SANTA CRUZ

Wednesday, October 26
9:00 am – 11:30 am
Santa Cruz County EOC
5200 Soquel Avenue
Santa Cruz

Continued on next page

Division of Flood Management

2022 California Preseason Flood Coordination Meetings



Department of Water Resources



**Preseason meetings include
scheduled presentations
from these agencies:**

National Weather Service

County Offices of Emergency
Services

California Governor's Office of
Emergency Services (Cal OES)

Department of Water
Resources

California Conservation Corps

CAL FIRE

U.S. Army Corps of Engineers

RIVERSIDE

Wednesday, November 2
9:00 am – 11:30 am
450 East Alessandro Blvd.
(Gate B, press button)
Riverside

VENTURA

Thursday, November 3
1:00 pm – 3:30 pm
Ventura Co. Watershed Dist.
800 S. Victoria Avenue
Ventura

SUTTER

Wednesday, November 9
1:00 pm – 3:30 pm
Sutter Co. Agricultural Dept.
142 Garden Highway
Yuba City

MERCED

Tuesday, November 15
9:00 am – 11:30 am
Merced County EOC
3500 Apron Avenue
Atwater

LAKE

Thursday, November 17
1:00 pm – 3:30 pm
Lake County OES
1375 Hoyt Avenue
Lakeport

FRESNO

Wednesday, November 30
9:00 am – 11:30 am
Fresno County EOC
333 W. Pontiac Way, Bldg. 6
Clovis

Who should attend these meetings?

- Managers and key emergency responders from California public agencies with primary responsibility for flood emergency response and coordination
- Counties, cities, flood control districts, reclamation districts, local maintaining agencies, and tribal agencies

**For questions please contact Wendy Francis at (916) 574-2619, or
wendy.francis@water.ca.gov.**

ITEM 11

RD 773: MASTER CALENDAR

JANUARY

FEBRUARY

- Send out Form 700s, remind Trustees of April 1 filing date
- Board Meeting
- Insurance renewal. Policy renews April.

MARCH

- Hire Employees for Seasonal Levee Work.

APRIL

- April 1: Form 700s due
- Board Meeting

MAY

- Draft Budget

JUNE

- Approve Audit Contract for expiring fiscal year
- Adopted Annual Budget
- Board Meeting
- Adopt Resolution for setting Assessments and submit to County Assessor's Office
- Adopt Annual CEQA Exemption for levee maintenance.

JULY

AUGUST

- August 1: Deadline to certify assessments for tax-roll and deliver to County (duration of current assessment: Indefinite).
- Send handbills for collection of assessments for public entity-owned properties
- In election years, opening of period for secretary to receive petitions for nomination of Trustees (75 days from date of election.) (*Cal. Wat. Code §50731.5*)
- Board Meeting

SEPTEMBER

- In election years, last legal deadline to post notice that petitions for nomination of Trustees may be received (7 days prior to close of closure.) (*Cal. Wat. Code §50731.5*).
- In election years, closing of acceptance of petitions for nomination of Trustees (54 days from date of election.) (*Cal. Wat. Code §50731.5*).
- Insurance Renewal

OCTOBER

- Publish Notice of Election, odd numbered years (once per week, 4 times, commencing at least 1 month prior to election).
- Board Meeting

NOVEMBER

- Election: to be held first Tuesday after first Monday of each odd-numbered year.

DECEMBER

- New Trustee(s) take office, outgoing Trustee(s) term(s) end on first Friday of each odd-numbered year.
- Board Meeting

Term of Current Board Members:

Name	Term Commenced	Term Ends
Ryan Bacchetti	First Friday 12/2021	First Friday of 12/2023
Joe Enos	First Friday 12/2019	First Friday of 12/2023
Mark R. Bacchetti	First Friday 12/2019	First Friday of 12/2023

No Expiration on Assessment

Trustee Ryan Bacchetti appointed to fill vacancy within first half of term. Second half of term expiring in 2025 will be filled at District's 2023 General Election.

ITEM 12

RECLAMATION DISTRICT 773
Bills for Approval of Payment
October 4, 2022 Board Meeting

NAME	INVOICE DATE	INVOICE #	AMOUNT	TOTAL \$	WARRANT #	CHECK #	RATIFICATION
Neumiller & Beardslee	8/8/2022	330843	\$1,431.00				
	9/19/2022	332058	\$696.78				
				\$2,127.78	2054		
Kjeldsen, Sinnock & Neudeck	8/26/2022	33460	\$1,477.22				
	8/26/2022	33461	\$931.23				
	8/26/2022	33462	\$1,047.70				
	8/26/2022	33463	\$65.00				
	8/26/2022	33464	\$7,826.25				
	8/26/2022	33465	\$646.25				
	8/26/2022	33466	\$470.00				
	8/26/2022	33467	\$816.25				
	8/26/2022	33468	\$110.00				
				\$13,389.90	2055		
California Central Valley Flood Control Assoc (Membership Dues)	8/22/2022	3905	\$2,868.00				
				\$2,868.00	2056		
Custom Spraying, Inc.	9/26/2022	11-2363	\$7,000.00				
				\$7,000.00	2057		
State Compensation Insurance Fund	8/11/2022	1001003513	\$1,746.09				
				\$1,746.09		372	X
NOTES:			Warrant Total	\$25,385.68			
			Check Total	\$1,746.09			
				\$27,131.77			
Fund Balance as of June 30, 2022		\$542,132.88					
Less Submitted Warrants for Payment:		\$25,385.68					
Total:		\$516,747.20					
Bank of Stockton Balance as of 8/31/2022		\$31,238.30					
		\$547,985.50					

RECLAMATION DISTRICT 773
BILLS PAID
August 2, 2022

NAME	INVOICE DATE	INVOICE #	AMOUNT	TOTAL \$	WARRANT #	CHECK #	RATIFICATION
Neumiller & Beardslee	6/9/2022	328362	\$1,105.03				
	7/7/2022	329648	\$1,283.75				
				\$2,388.78	2050		
Kjeldsen, Sinnock & Neudeck	7/22/2022	33140	\$1,327.88				
	7/22/2022	33141	\$983.38				
	7/22/2022	33142	\$2,577.50				
	7/22/2022	33143	\$570.00				
	7/22/2022	33144	\$126.25				
				\$5,585.01	2051		
Dohrmann Insurance (Package Renewal Policy)	7/14/2022	32755	\$9,153.00				
(Umbrella Renewal Policy)	7/14/2022	32756	\$926.00				
				\$10,079.00	2052		
North Valley Labor Compliance Services	7/9/2022	4948	\$30.00				
				\$30.00	2053		
NOTES:			Warrant Total	\$18,082.79			
			Check Total	\$0.00			
				\$18,082.79			
Fund Balance as of June 30, 2022		\$559,452.67					
Less Submitted Warrants for Payment:		\$18,082.79					
Total:		\$541,369.88					
Bank of Stockton Balance as of 6/30/2022		\$32,984.39					
		\$574,354.27					