

PATIO STRUCTURE - RAMADA

GENERAL CONTRACTORS NOTIFICATION

GENERAL:

- ALL CONSTRUCTION SHALL CONFORM TO THE INTERNATIONAL BUILDING CODE, (CURRENT EDITION AT THE TIME IT WAS DRAFTED), AS LOCALLY AMENDED, AND ALL APPLICABLE CODES & ORDINANCES. IT IS THE RESPONSIBILITY OF THE PURCHASER AND/OR BUILDER OF THIS PLAN TO SEE THAT THE STRUCTURE IS BUILT IN STRICT COMPLIANCE WITH ALL GOVERNING MUNICIPAL CODES (CITY, COUNTY, STATE AND FEDERAL).
- CONTRACTOR IS OBLIGATED TO OBTAIN A FULL AND CLEAR UNDERSTANDING OF THE PLANS, NOTES AND CONCEPTS CONTAINED HEREIN PRIOR TO THE START OF ANY WORK.
- AFTER THE SIGNING OF ANY WORK AGREEMENTS, THERE WILL BE NO CONSIDERATION GIVEN TO ANY CLAIM OF MISUNDERSTANDING OF THE DRAWINGS, DETAILS, CONCEPTS, ETC., AS THEY APPLY TO THE PLANS.
- CONTRACTOR SHALL FIELD VERIFY ALL CONDITIONS AND DIMENSIONS BEFORE STARTING ANY WORK.
- CONTRACTOR WILL INSURE THAT ALL MATERIALS AND WORKMANSHIP SHALL COMPLY WITH THE REQUIREMENTS OF ALL PERTINENT GOVERNMENTAL CODES AND REQUIREMENTS.
- PRIOR TO STARTING ANY EXCAVATION, CONSTRUCTION AND OR DEMOLITION WORK - THE CONTRACTOR SHALL WALK THE PROJECT SITE WITH THE OWNER TO VERIFY WHAT WORK WILL BE TAKING PLACE.
- CONTRACTOR IS OBLIGATED TO PERFORM ALL WORK IN A GOOD CRAFTSMANSHIP/WORKMANSHIP MANNER ACCORDING TO ALL MANUFACTURERS SPECIFICATIONS.
- THE DRAWINGS, INCLUDING ANY NOTES, SPECIFICATIONS, AND/OR REPORTS ARE TO BE INTERPRETED AS ONE DOCUMENT, HOWEVER, SHOULD ANY ITEM APPEAR IN ONLY ONE AND NOT THE OTHER, SUCH ITEMS ARE STILL TO BE CONSIDERED VALID COMPONENTS OF THE OVERALL DOCUMENT.
- THE CONTRACTOR SHALL NOT PROCEED WITH WORK, IF THERE IS AN ERROR, OMISSION, OR DISCREPANCY THAT IS DISCOVERED IN THE DRAWINGS UNTIL CONTACT WITH THE OWNER HAS BEEN ESTABLISHED FOR SPECIFIC INSTRUCTIONS AS HOW TO CONTINUE.
- ANY WORK THAT IS NOT EXPLICITLY ILLUSTRATED OR NOTED IN THE DRAWINGS BUT CLEARLY REQUIRED AS NECESSARY TO COMPLETE THE PROJECT SHALL BE INCLUDED AND EXECUTED AS AN INTEGRAL PART OF THE ORIGINAL SCOPE OF WORK WITH NO ADDITIONAL COST TO THE OWNER.
- SHOULD THERE BE ANY ARCHITECTURAL DISCREPANCIES BETWEEN THE ARCHITECTURAL DRAWINGS VERSUS SUPPLEMENTAL DRAWINGS (I.E. ELECTRICAL, MECHANICAL, LANDSCAPE, CIVIL, ETC.) THE ARCHITECTURAL DRAWINGS SHALL ALWAYS BE USED AS THE PREDOMINANT SOURCE OF INFORMATION.
- WHEN QUESTIONS ARISE OVER A SCALED DIMENSION VERSUS A WRITTEN DIMENSION, THE WRITTEN DIMENSION SHALL ALWAYS SUPERSEDE THE SCALED DIMENSION.
- ALL AND ANY SUBSTITUTIONS (INCLUDING BUT NOT LIMITED TO: DESIGN, METHODS, COLORS, TEXTURES AND/OR MATERIALS) THAT DEVIATE FROM THE APPROVED PERMITTED SET OF CONSTRUCTION DRAWINGS MUST BE APPROVED BY THE OWNER, FAILURE TO NOTIFY THE OWNER AND WHEN NECESSARY - CITY INSPECTORS, OF ANY DEVIATIONS FROM DRAWINGS WILL BE CAUSE FOR "STOP OF WORK" UNTIL ALL DEVIATIONS ARE RECTIFIED PER THE APPROVAL OF THE OWNER. ALL AND ANY EXPENSE INCURRED TO RECTIFY SUCH DEVIATIONS WILL BE DONE SOLELY AT THE GENERAL CONTRACTORS EXPENSE.
- IN THE EVENT THAT HAZARDOUS MATERIALS AND/OR CONDITIONS ARE ENCOUNTERED THEY MUST BE ADDRESSED & COMPLY WITH ALL PERTINENT GOVERNMENTAL CODES AND REQUIREMENTS. IF ANY SUCH REMEDIES ARE REQUIRED, COSTS SHALL BE NEGOTIATED BETWEEN OWNER AND CONTRACTOR.

CONCRETE AND FOUNDATIONS:

- ALL FOOTINGS SHALL BE 3000 PSI (28 DAY COMPRESSIVE STRENGTH CONCRETE) - SEE STRUCTURAL DRAWINGS.
- ALL FOUNDATION WALLS SHALL BE POURED CONCRETE - U.N.O. AND REINFORCED PER STRUCTURAL DRAWINGS.
- ALL SLABS ON GRADE SHALL BE 3000 PSI (28 DAY COMPRESSIVE STRENGTH CONCRETE), U.N.O. - SEE STRUCTURAL DRAWINGS.
- ALL SLABS ON GRADE SHALL BE 4" THICK (MIN.) AND REINFORCED W/ #3 REBAR AT 24" O.C. U.N.O. AND BEAR ON 4" (MIN.) COMPACTED AGGREGATE BASE COURSE (COMPACTED TO 95 %) U.N.O.
- PROVIDE PROPER EXPANSION AND CONTROL JOINTS (KEYED OR SAWCUT) NOT TO EXCEED 400 SQUARE FEET AREA OR AS PER LOCAL CODE.
- FOUNDATION WALLS ARE NOT TO BE BACKFILLED UNTIL FLOOR SYSTEM IS COMPLETELY IN PLACE.
- INSTALL 1/2" DIA. X 10' (MIN.) ANCHOR BOLTS TO 2X6 PRE-TREATED SILL PLATE OVER SILL SEALER AT 48" O.C. AND NOT MORE THAN 12" FROM ANY CORNER OR END OF PLATE.
- IN THE EVENT THAT STEPPED FOOTINGS ARE REQUIRED - HORIZONTAL DIMENSION = 48" (MIN.); VERTICAL DIMENSION = 24" (MAX.)

STEEL:

- ALL REINFORCING STEEL FOR CONCRETE SHALL COMPLY WITH ASTM SPECIFICATION A-615 GRADE 60.
- ALL STRUCTURAL STEEL FOR BEAMS AND PLATES SHALL COMPLY WITH ASTM SPECIFICATION A-36.
- ALL STRUCTURAL STEEL FOR STEEL COLUMNS SHALL COMPLY WITH ASTM SPECIFICATION A-53 GRADE B OR A-501.
- PROVIDE 12" MIN. AT BEAM JOCKET LOCATIONS.
- STEEL COLUMNS ARE TO BE 3" I.D. (INSIDE DIAMETER) UNLESS NOTED OTHERWISE.

FRAMING MEMBERS:

- ALL FRAMING LUMBER TO BE DOUGLAS FIR-LARCH #2 (DFL #2) OR BETTER U.N.O.
- CONTRACTOR TO CONFIRM THE SIZE, SPACING AND SPECIES OF ALL FRAMING AND STRUCTURAL MEMBERS TO MEET LOCAL CODE REQUIREMENTS PER LOCAL STRUCTURAL ENGINEER PRIOR TO INSTALLATION.
- ANY STRUCTURAL OR FRAMING MEMBERS NOT INDICATED ON THE PLAN ARE TO BE SIZED BY THE CONTRACTOR PER LOCAL STRUCTURAL ENGINEER.
- ALL EXTERIOR WALLS ARE 2" X 6" STUDS AT 16" O.C. & ARE DIMENSIONED FROM OUTSIDE EDGE OF WALL SHEATHING (6" DIMENSION).
- ALL INTERIOR WALLS ARE DIMENSIONED FROM EDGE OF STUD TO EDGE OF STUD.
- CALCULATED DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.
- ALL FRAMED WALLS HAVE A FINISHED HEIGHT OF 9'-1 1/8", U.N.O.
- ALL ANGLED WALLS ON FLOOR PLANS ARE AT A 45 DEGREE ANGLE, U.N.O.
- ABOVE ALL OPENINGS THAT ARE - U.N.O.:
 - (A) INTERIOR NON - LOAD BEARING LESS THAN OR EQUAL TO 3'-0" USE: (2) FLAT 2 X 4 "WALL THICKNESS" DFL #2 HEADER OR EQUIVALENT.
 - (B) INTERIOR NON - LOAD BEARING GREATER THAN 3'-0" USE: (2) 2 X 6" DFL #2 HEADER WITH A 2 X WALL THICKNESS BOTTOM HEADER PLATE OR EQUIVALENT.
 - (C) INTERIOR LOAD BEARING OR EXTERIOR LESS THAN OR EQUAL TO 8'-0" USE: (2) 2 X 10" DFL #2 HEADER WITH A 2 X WALL THICKNESS BOTTOM HEADER PLATE.
 - (D) INTERIOR LOAD BEARING OR EXTERIOR 8'-0" - 10'-0" USE: (2) 2 X 12" DFL #2 HEADER WITH A 2 X WALL THICKNESS BOTTOM HEADER PLATE.
 - (E) INTERIOR LOAD BEARING OR EXTERIOR 10' - 18'-0" USE: 3 1/8" X 13 1/2" GLU-LAM DF24-VF HEADER OR EQUIVALENT.
 - (F) ALL OVERHEAD GARAGE DOORS USE 3 1/8" X 13 1/2" GLU-LAM DF24-VF HEADER OR EQUIVALENT.
- POSTS UNDER BEAMS, GIRDERS SHALL BE (2) 2 X STUDS OR GREATER X (MATCHING WALL THICKNESS).
- ALL FLOOR & ROOF TRUSSES TO BE ENGINEERED BY TRUSS MANUFACTURER ACCORDING TO THE LOADING ON THE PLAN.
- UNLESS NOTED OTHERWISE ALL ROOF FRAMING SHALL BE PRE-MANUFACTURED ROOF TRUSSES PER THE ROOF TRUSS MANUFACTURER
- ALL FRAMING CONNECTORS ARE TO BE SIMPSON COMPANY OR EQUIVALENT.
- CEILING HEIGHTS:
 - (A) 8' CLG. = 8'-1 1/8" WALL HEIGHT
 - (B) 9' CLG. = 9'-1 1/8" WALL HEIGHT
 - (C) 10' CLG. = 10'-1 1/8" WALL HEIGHT
 - (D) 11' CLG. = 11'-1 1/8" WALL HEIGHT
 - (E) 12' CLG. = 12'-1 1/8" WALL HEIGHT

MISCELLANEOUS:

- PREFABRICATED FIREPLACES AND FLUES ARE TO BE U.L. APPROVED AND INSTALLED AS PER MANUFACTURERS SPECIFICATIONS.
- ALL MATERIALS, SUPPLIES AND EQUIPMENT TO BE INSTALLED AS PER MANUFACTURERS SPECIFICATIONS AND AS PER LOCAL CODES AND REQUIREMENTS.
- 1/2" WATER RESISTANT GYPSUM BOARD AROUND SHOWERS, TUBS AND WHIRLPOOLS & AT ALL "WET" LOCATIONS - (BATH ROOMS, LAUNDRY, KITCHEN, ETC.)
- 1/2" GYPSUM BOARD ON ALL INTERIOR WALLS AND 5/8" GYPSUM BOARD ON ALL CEILINGS.
- 5/8" FIRE RATED GYPSUM BOARD ON INTERIOR GARAGE WALLS TO EXTEND FROM FLOOR TO BOTTOM OF ROOF SHEATHING AND ON THE CEILING.
- 5/8" FIRE RATED GYPSUM BOARD ON UNDERSIDE OF STAIRS.
- VENT CLOTHES DRYER, RANGE HOOD FAN, ETC. & ALL EXHAUST FANS TO OUTSIDE AIR.
- PROVIDE 22" X 30" ATTIC ACCESS.
- OMISSIONS OR CONFLICTS BETWEEN VARIOUS ELEMENTS OF THE DRAWINGS, NOTES, AND DETAILS SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER AND BE RESOLVED BEFORE PROCEEDING WITH THE WORK.
- REMOVE ALL MATERIALS RESULTING FROM DEMOLITION WORK FROM THE SITE IN SUCH A MANNER AS TO AVOID CREATING A NUISANCE.
- THE CONTRACTOR OR SUBCONTRACTOR SHALL INSPECT THE PREMISES PRIOR TO COMMENCING WORK TO CHECK EXISTING WORKING CONDITIONS. SHOULD CONTRACTOR OR SUBCONTRACTOR FIND CONDITIONS WHICH THEY BELIEVE WOULD IMPEDE THEIR WORK, THEN SUCH CONDITIONS MUST BE REPORTED IMMEDIATELY TO THE OWNER. FAILURE TO SO ADVISE WILL CONSTITUTE NOTICE THAT THE CONTRACTOR IS FULLY SATISFIED AND THAT THEY INTEND TO PERFORM THEIR OBLIGATIONS WITH NO ALLOWANCE EITHER IN TIME OR MONEY FOR ANY IMPEDIMENTS TO WORK.
- CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN FIELD. IF DIMENSIONAL ERRORS OCCUR OR CONDITIONS NOT COVERED ON THE DRAWINGS IS ENCOUNTERED CONTRACTOR SHALL NOTIFY THE OWNER BEFORE COMMENCING THAT PORTION OF THE WORK.
- DETAILS, NOTES, AND FINISHES SHALL BE APPLICABLE TO ALL TYPICAL CONDITIONS, WHETHER OR NOT REFERENCED AT ALL PLACES. WHEN WORK NOT SPECIFICALLY CALLED OUT IS REQUIRED TO COMPLETE THE PROJECT, IT SHALL BE PROVIDED AND BE OF THE BEST MATERIALS AND WORKMANSHIP.
- THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONARY MEASURES TO PROTECT THE PUBLIC AND ADJACENT PROPERTIES FROM DAMAGES THROUGHOUT CONSTRUCTION THEY SHALL MEET THE LATEST REQUIREMENTS OF THE UNITED STATES DEPARTMENT OF LABOR OCCUPATIONAL SAFETY AND HEALTH STANDARDS AND COMPLY WITH THE MANUAL OF PREVENTIVE MAINTENANCE, ALL APPLICABLE SAFETY AND SANITARY LAWS, REGULATIONS AND ORDINANCES, AND ANY SAFETY RULES OR PROCEDURES ESTABLISHED BY THE OWNER FOR THE PROJECT.
- THE CONTRACTOR IS EXCLUSIVELY RESPONSIBLE FOR LOSS OR EXPENSE RESULTING FROM INJURY ON THE PROJECT SITE, THEY ASSUME ALL RISKS IN THE PERFORMANCE OF THE WORK AND IS RESPONSIBLE FOR SUPERVISION, MATERIALS, EQUIPMENT AND LABOR REQUIRED TO IMPLEMENT THE PLANS AND SPECIFICATIONS.
- THE CONTRACTOR IS SOLELY RESPONSIBLE FOR SUPERVISION, SAFETY, ADMINISTRATION AND ALL PHASES OF ITS CONTRACT. THEY ARE ALSO RESPONSIBLE FOR SCHEDULING, COORDINATING AND ADMINISTRATION OF SUBCONSULTANTS.
- THE CONTRACTOR SHALL VERIFY THE LOCATION OF EXISTING UTILITIES AND PROTECT THE SAME.
- ALL MANUFACTURED ARTICLES, MATERIALS AND EQUIPMENT SHALL BE APPLIED, INSTALLED, CONNECTED, ERECTED, USED, CLEANED AND CONDITIONED IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN SPECIFICATIONS OR INSTRUCTIONS UNLESS HEREINAFTER SPECIFIED TO THE CONTRARY.
- ALL WORK SHALL BE EXECUTED IN A NEAT AND WORKMANLIKE MANNER, ACCEPTABLE TO THE OWNER.
- CONTRACTOR SHALL GUARANTEE ALL WORKMANSHIP AND MATERIALS IN WRITING FOR A PERIOD OF _____ YEAR(S) FROM THE DATE OF CERTIFICATE OF OCCUPANCY.
- UNLESS OTHERWISE SPECIFICALLY NOTED, THE CONTRACTOR SHALL PROVIDE AND PAY FOR ALL LABOR, MATERIALS, EQUIPMENT, TOOLS, CONSTRUCTION EQUIPMENT AND MACHINERY, TRANSPORTATION, AND OTHER FACILITIES AND SERVICES NECESSARY FOR PROPER EXECUTION AND COMPLETION OF THE WORK.

ABBREVIATIONS

A.B.	ANCHOR BOLT	JAN.	JANITOR
A.B.C.	AGGREGATE	JT.	JOINT
A / C	BASE COURSE	KIT.	KITCHEN
ACOUS.	AIR CONDITIONING	LAM.	LAMINATE
ADJ.	ADJUSTABLE	LAV.	LAVATORY
A.F.F.	ABOVE FINISHED FLOOR	L.F.	LINEAT FOOT
AGG.	AGGREGATE	LT.	LIGHT
ALUM.	ALUMINUM	MAX.	MAXIMUM
ALT.	ALTERNATE	MECH.	MECHANICAL
APPROX.	APPROXIMATE	M.C.	MEDICINE CABINET
ARCH.	ARCHITECTURAL	MEMB.	MEMBRANE
ASPH.	ASPHALT	MET.	METAL
BD.	BOARD	MFR.	MANUFACTURER
BLDG.	BUILDING	MIR.	MIRROR
BLK.	BLOCK	MISC.	MISCELLANEOUS
BLKG.	BLOCKING	M.O.	MASONRY OPENING
BM.	BEAM	M.R.	MOISTURE RESISTANT
B.O.	BOTTOM OF	MTD.	MOUNTED
B.O.U.	BOTTOM BUILT-UP	MUL.	MULLION
CAB.	CABINET	N	NORTH
C.B.	CORNER BEAD	N.I.C.	NOT IN CONTRACT
C.T.	CERAMIC TILE	NO. OR	NUMBER
CHAN.	CHANNEL	N.T.S.	NOT TO SCALE
C.I.	CAST IRON	O.A.	OVERALL
C.I.P.	CAST IN PLACE	O.C.	ON CENTER
C.J.	CONSTRUCTION / CONTROL JOINT	O.D.	OUTSIDE DIAMETER
CLG.	CLEAR	O.F.C.I.	OWNER FINISHED/ CONTRACTOR INSTALLED
CLO.	CLOSET	OFF.	OFFICE
CLR.	CLEAR	OPNG.	OPENING
C.M.U.	CONCRETE	OPP.	OPPOSITE
CNTSRNK.	COUNTERSINK	PNLG.	PANELING
CNTR. TOP	COUNTER TOP	PAR.	PARAPET
C.O.	CLEAN OUT	PARTN	PARTITION
COL.	COLUMN	FL.	FLATE OR FRIEDRY LINE
CONC.	CONCRETE	F.LAM.	FLASTIC LAMINATE
CONN.	CONNECTION	PLAS.	PLASTER
CONSTR.	CONSTRUCTION	FR.	FAIR
CONT.	CONTINUOUS	P.V.C.	POLYVINYL CHLORIDE
CONTR.	CONTRACTOR	PLYWD.	PLYWOOD
CORR.	CORRIDOR	Q.T.	QUARRY TILE
CTR.	CENTER	R.	RISER
C.W.	COLD WATER	RAD.	RADIUS
DBL.	DOUBLE	R.A.	RETURN AIR
DEPT.	DEPARTMENT	R.D.	ROOF DRAIN
D.F.	DRAINAGE FLOW	REDWD.	REDWOOD
DIA.	DIAMETER	REF.	REFERENCE
DIM.	DIMENSION	REFRIG.	REFRIGERATOR
DISP.	DISPENSER	REINF.	REINFORCED
DN.	DOWN	REQ'D	REQUIRED
DN&PT.	DOWNSPOUT	RESIL.	RESILIENT
D.O.	DOOR OPENING	RM.	ROOM
DR.	DRAWING	R.O.	ROUGH OPENING
DTL.	DETAIL	ROOF'G	ROOFING
DWG.	DRAWING	S.	SOUTH
DWR.	DRAWER	S.A.	SUFFLY AIR
E.	EAST	S.C.	SOLID CORE
EA.	EACH	SCHED.	SCHEDULE
E.J.	EXPANSION JOINT	SECT.	SECTION
ELEC.	ELECTRICAL	SQ. FT.	SQUARE FEET
ELEC. PAN.	ELECTRICAL PANELBOARD	SH.	SHELF
ELEV.	ELEVATION	SHR.	SHOWER
ELEVATOR	ELEVATOR	SHT.	SHEET
EMER.	EMERGENCY	SIM.	SIMILAR
ENCL.	ENCLOSURE	SPEC.	SPECIFICATION
EQ.	EQUAL	SQ.	SQUARE
EQUIP.	EQUIPMENT	S.S.	STAINLESS STEEL
EXIST.	EXISTING	STD.	STANDARD
EXP.	EXPANSION	STL.	STEEL
EXT.	EXTERIOR	STOR.	STORAGE
F.D.	FLOOR DRAIN	STRUC.	STRUCTURAL
FOUND.	FOUNDATION	SUSP.	SUSPENDED
FIBERGL.	FIBERGLASS	SYM.	SYMMETRICAL
F.E.	FIRE	T.	TREAD
F.E.C.	FIRE EXT.	TEL.	TELEPHONE
F.E.C.	GUISHER CAB.	T & G	TONGUE AND GROOVE
FFE.	FINISH FLOOR	THK.	THICK
FIN.	FINISH	T.O.	TOP OF
FIN.	FINISH GRADE	T.O.C.	TOP OF CURB
FIN.	FINISH	T.O.W.	TOP OF WALL
FIXT.	FIXTURE	T.S.	TUBE STEEL
FLASH'G	FLASHING	T.T.B.	TELEPHONE TERMINAL BOARD
FLR.	FLOOR	TYP.	TYPICAL
FLUOR.	FLUORESCENT	U.N.O.	UNLESS NOTED OTHERWISE
FFRF.	FIREPROOF FRAMING	URINAL	URINAL
FRMG.	FRAMING	V.C.T.	VYTL COMPOSITION TILE
FT.	FOOT	VERT.	VERTICAL
FT.	FOOTING	VTR	VENT-THRU ROOF
FURN.	FURNITURE	W.	WEST
FURR.	FURRING	W/ & W/O	WITH AND WITHOUT
G.A.	GAUGE	W.C.	WATER CLOSET
GALV.	GALVANIZED	WD.	WOOD
GL.	GLASS	WDW	WINDOW
GL.BM.	GLU-LAM BEAM	WFR.	WEATHERPROOF
GRD.	GRADE	WR.	WATER RESISTANT
GRND.	GROUND	W.S.	WEEP SCREEN
GYP. BD.	GYPSUM BOARD.	WT.	WEIGHT
H.B.	HOSE BIBB		
H.C.	HOLLOW CORE		
HCP.	HANDICAP		
CDWD.	HARDWOOD		
HDWR.	HARDWARE		
H.M.	HOLLOW METAL		
HORIZ.	HORIZONTAL		
HT.	HEIGHT		
HW.	HOT WATER		
I.D.	INSIDE		
INSUL.	INSULATION		
INT.	INTERIOR		
INV.	INVERT		

PERSPECTIVE:



DESIGN CRITERIA

DESIGN CRITERIA:	
ROOF LOAD:	DL = 20 PSF / LL = 20 PSF (SNOW) + 40 PSF
FLOOR LOAD:	DL = 20 PSF / LL = 40 PSF + 60 PSF
DECK LOAD:	DL = 20 PSF / LL = 60 PSF + 80 PSF
WIND LOAD:	90 MPH / 20 PSF
SEISMIC ZONE:	C
SOIL BEARING:	1500 PSF MAX. UNLESS A HIGHER VALUE IS SUBSTANTIATED BY SOILS TESTING

- EFFECTIVE CODE:
- 2012 INTERNATIONAL RESIDENTIAL CODE (IRC)
 - 2012 INTERNATIONAL PLUMBING CODE (IPC)
 - 2012 INTERNATIONAL MECHANICAL CODE (IMC)
 - 2012 INTERNATIONAL FUEL GAS CODE (IFGC)
 - 2011 NATIONAL ELECTRIC CODE (NEC)
 - 2012 INTERNATIONAL ENERGY CONSERVATION CODE (IECC)

BUILDING INFORMATION

LEGAL DESCRIPTION:

OWNER INFORMATION:


BUILDING DATA:

EXISTING HOUSE:	3919 SQ. FT.
NEW COVERED PATIO:	675 SQ. FT.
SUB - TOTAL:	4653 SQ. FT.
BUILDING FOOTPRINT TOTAL:	4653 SQ. FT.
ZONING:	MPUD
OCCUPANCY:	M
CONSTRUCTION:	TYPE V - N
MAX. BLDG. HGT.:	35' / 2 STORIES
ACTUAL BLDG. HGT.:	11'-4" +/-
LOT SETBACKS:	
BACK:	5'
LEFT SIDE:	5'
RIGHT SIDE:	5'
LOT SIZE:	19553 SQ. FT. (0.45 ACRES)
MAX. LOT COVERAGE:	35%
LOT COVERAGE:	4653 SQ. FT. / 19553 SQ. FT. = 24% TOTAL LOT COVERAGE

SHEET INDEX

ARCHITECTURAL:	ELECTRICAL:
CS	COVER SHEET
A 1.0	SLAB PLAN
A 1.1	FOUNDATION PLAN
A 1.2	FLOOR PLAN
A 1.3	ROOF FRAMING PLAN
A 2.1	EXTERIOR ELEVATIONS
A 2.2	EXTERIOR DETAILS
A 2.3	EXTERIOR PERSPECTIVES
A 3.1	BUILDING SECTIONS
A 4.1	FOUNDATION DETAILS
A 5.1	FRAMING DETAILS
E 1.1	SCHEMATIC ELECTRICAL PLAN
P 1.1	SCHEMATIC PLUMBING PLAN

VICINITY MAP




BUILDING INFORMATION


LEGAL DESCRIPTION:

OWNER INFORMATION:

BUILDING DATA:


EXISTING HOUSE..... 3978 SQ. FT.
 NEW COVERED PATIO..... 675 SQ. FT.
 SUB - TOTAL..... 4653 SQ. FT.
 LOT SIZE: 19553 SQ. FT. (0.44 ACRES)
 LOT COVERAGE: 4653 SQ. FT. / 19553 SQ. FT. = 24% TOTAL LOT COVERAGE






FOUNDATION PLAN
 SCALE: 1/4" = 1'-0"

- GENERAL FOUNDATION NOTES:**
1. SPREAD AND OR CONTINUOUS FOOTING BEARING MATERIALS SHOULD EITHER BE ON UNDISTURBED SOILS OR 95% COMPACTED SOIL IN 12" LIFTS NOT TO EXCEED 4'-0". UNLESS APPROVED BY CERTIFIED INSPECTION OR BUILDING OFFICIAL.
 2. BOTTOM OF FOOTING SHALL BE NO LESS THAN 12" BELOW NATURAL GRADE OR CERTIFIED COMPACTED PAD AND ALWAYS BELOW FROST LINE.
 3. ALLOWABLE FOUNDATION BEARING PRESSURE SHALL BE 1500 P.S.I.
 4. FINISH GRADE SHALL SLOPE 5% MINIMUM FOR A DISTANCE OF 10'-0" AWAY FROM STRUCTURE TOWARD AND APPROVED WATER DISPOSAL AREA.
 5. FINISHED FLOOR SHALL BE A MINIMUM OF 8" ABOVE ADJACENT FINISHED GRADE.
 6. SLOPE OF LANDINGS AT DOORWAYS SHALL BE A MINIMUM OF 1" PER 10'-0".
 7. UNLESS APPROVED OTHERWISE, ALL CONCRETE SLABS ON GRADE SHALL BE BOUNDED BY CONTROL JOINTS (KEYED OR SAW CUT) SUCH THAT THE ENCLOSED AREA DOES NOT EXCEED 400 SQ. FT. -SAW CUT WITHIN 24 HOUR PERIOD AFTER POUR.
 8. ALL FOOTINGS SHALL BE 3000 P.S.I. (28 DAY COMPRESSIVE STRENGTH CONCRETE) WITH HORIZ. #4 REBAR CONTINUOUS (OVERLAP REBAR 30 BAR DIAMETERS) AT TOP & BOTTOM. FOOTING SIZE = 12" (WIDE) X 18" (DEEP), U.N.O.
 9. ALL SLABS ON GRADE SHALL BE 3000 P.S.I. (28 DAY COMPRESSIVE STRENGTH CONCRETE) UNLESS NOTED OTHERWISE.
 10. ALL SLABS ON GRADE SHALL BE 4" THICK (MIN.) AND BEAR ON 4" (MIN.) COMPACTED AGGREGATE BASE COURSE (COMPACTED TO 95%) UNLESS NOTED OTHERWISE.
 11. FOUNDATION WALLS ARE NOT TO BE BACKFILLED UNTIL FLOOR SYSTEM IS COMPLETELY IN PLACE.
 12. INSTALL 1/2" DIA. x 12" ANCHOR BOLTS TO 2x6 PRE-TREATED SILL PLATE OVER SILL SEALER AT 48" O.C. & NOT MORE THAN 12" FROM ANY CORNER OR END OF PLATE.
 13. IN THE EVENT THAT STEPPED FOOTINGS ARE REQUIRED -HORIZONTAL DIMENSION = 32" (MIN.) ; VERTICAL DIMENSION = 24" (MAX.)
 14. ALL REINFORCING STEEL FOR CONCRETE SHALL COMPLY WITH ASTM SPECIFICATION A-615 GRADE 60.
 15. CONTRACTOR TO PROVIDE 30' OF #4 COPPER U.F.F.R. WIRE 20' TO BE TIED TO FOOTING STEEL & 10' AVAILABLE AT PANEL LOCATION.
 16. WHERE HOLD DOWNS ARE PLACED, ALL REBARS, ANCHOR BOLTS & SETBOLTS MUST BE TIED IN PLACE BEFORE PLACING ANY CONCRETE. NO "WET STABBING" ALLOWED.



FLOOR PLAN
SCALE: 1/4" = 1'-0"

GENERAL FLOOR PLAN NOTES:


- THE DRAWINGS INDICATE THE GENERAL SCOPE OF THE PROJECT INTERMS OF ARCHITECTURAL DESIGN CONCEPT, THE DIMENSIONS OF THE BUILDING, THE MAJOR ARCHITECTURAL ELEMENTS, AND THE TYPE OF STRUCTURAL, MECHANICAL AND ELECTRICAL SYSTEMS. AS SCOPE OF DOCUMENTS, THE DRAWINGS DO NOT NECESSARILY INDICATE OR DESCRIBE ALL WORK REQUIRED FOR FULL PERFORMANCE AND COMPLETION OR THE REQUIREMENTS OF THE CONTRACT DOCUMENTS. ON THE BASIS OF THE GENERAL SCOPE INDICATED OR DESCRIBED, THE TRADE CONTRACTORS SHALL FURNISH ALL ITEMS REQUIRED FOR THE PROPER EXECUTION AND COMPLETION OF THE WORK. ALL ANGLES ARE 45 DEGREES UNLESS NOTED OTHERWISE.
- ALL DIMENSIONS ARE TO FACE OF STUD OR FACE OF CONCRETE OR FACE OF MASONRY STEM WALL UNLESS NOTED OTHERWISE. THESE DIMENSIONS TAKE PRECEDENCE AND SHALL BE VERIFIED BY THE CONTRACTOR ON THE JOB SITE. SHOULD DISCREPANCIES OCCUR, THE OWNER AND/OR DESIGNER SHALL BE NOTIFIED FOR ACCEPTABLE RESOLUTION BEFORE PROCEEDING WITH THE WORK.
- THE EXTERIOR SIDE OF ALL EXTERIOR WALLS AND INTERIOR WALLS WHERE REQUIRED SHALL BE BRACED AS REQUIRED PER 2012 IRC SECTION R602.10.4 BRACED WALL PANEL CONSTRUCTION METHOD C8-WSP (CONTINUOUSLY SHEATHED WOOD STRUCTURAL PANEL); CONTINUOUS 3/8" (MIN.) PLYWOOD / OSB WALL SHEATHING WITH 16-INCH STUD SPACING. WOOD STRUCTURAL PANELS SHALL BE INSTALLED W/ 8d NAILS AT 4" O.C. AT ALL PANEL EDGES & 12" O.C. ON ALL FRAMING MEMBERS NOT AT PANEL EDGES.
- ALL EXTERIOR RATED WALL SHEATHING SHALL BE INSTALLED WITH A 1/8" SEPARATION AT ENDS AND EDGES OF SHEATHING PANELS. DO NOT BUTT PANEL EDGES TIGHT.
- PROVIDE MIN. 2 X 4 BLOCKING / BACKING IN WALLS AS REQUIRED AT ALL AREAS TO RECEIVE BUILT-IN CABINETS, EQUIPMENT, HARDWARE AND ACCESSORIES (I.E. TOWEL BARS, GRAB BARS, DOOR BUMPERS, AND OTHER ITEMS THAT NEED SUBSTANTIAL PULL OUT RESISTANCE AND OR SUPPORT BACKING).
- ALL EXTERIOR WALLS COMMON TO HABITABLE AREAS SHALL HAVE A MINIMUM R-13. CEILINGS SHALL HAVE A MINIMUM R-38, AND CRAWL SPACES SHALL HAVE A MINIMUM R-13 INSULATION VALUE SPECIFICALLY FOR ZONE 4.
- INSULATION SHALL BE IN SUBSTANTIAL CONTACT WITH THE SURFACE BEING INSULATED TO AVOID AIR PATHS THAT BYPASS THE INSULATION AND SHALL NOT BE COMPRESSED AND SHALL FILL ALL CAVITIES. CUT INSULATION TO FIT BEHIND ELECTRICAL BOXES. SLICE TO FIT BEHIND AND IN FRONT OF WIRING, PLUMBING AND OTHER HORIZONTAL AND VERTICAL RUNS IN WALL CAVITY.
- MARKERS SHALL BE INSTALLED FOR BLOW-IN INSULATION AFFIXED TO THE TRUSSES OR JOISTS AND MARKED WITH A MINIMUM INITIAL INSTALLED THICKNESS BY ONE INCH HIGH NUMBERS. ONE MARKER FOR EVERY 300 SQ. FT. OF AREA AND NUMBERS FACING THE ATTIC ACCESS OPENING. LADDER MUST BE PROVIDED AT INSPECTION.
- ALL EXTERIOR WALL ASSEMBLIES OR BUILDING THERMAL ENVELOPE SHALL BE DURABLY SEALED TO LIMIT INFILTRATION (ALL SOURCES OF AIR LEAKAGE SHALL BE SEALED).
- BOTTOM AND TOP FLATE OF EXTERIOR WALLS SHALL BE SEALED WITH SILL GASKET OR CAULKING.
- ALL DUCT SUPPLY AND RETURN SHALL BE INSULATED MINIMUM R-6 EXCEPT DUCTS THAT ARE COMPLETELY INSIDE THE BUILDING THERMAL ENVELOPE.
- ALL MECHANICAL SYSTEM PIPING INSULATION SHALL BE MINIMUM R-2.
- ALL CIRCULATING HOT WATER SYSTEMS SHALL BE A MINIMUM R-2 (HOT WATER PIPING ONLY).
- HEATING AND COOLING UNITS TO BE SIZED IN ACCORDANCE WITH 2012 IRC M1401.3.
- ALL EXTERIOR WALLS: 2 X 6 STUDS AT 16" O.C. UNLESS NOTED OTHERWISE.
- INTERIOR BEARING WALL: 2 X 6 STUDS AT 16" O.C. WITH 2 X BLOCKING AT THIRD POINTS TYPICAL UNLESS NOTED OTHERWISE.
- INTERIOR NON-BEARING WALLS: 2 X 4 STUDS AT 16" O.C. UNLESS NOTED OTHERWISE.
- POSTS UNDER HEADERS, BEAMS, GIRDERS SHALL BE (2) 2 X STUDS OR GREATER (MATCHING WALL THICKNESS).
- MULTIPLE STUDS ARE TO BE SPIKED TOGETHER WITH 10d COMMON NAILS AT 8" O.C. ALONG LENGTH & STAGGERED 1 1/2" ABOUT CENTER LINE.
- DOUBLE TOP FLATE UNLESS NOTED OTHERWISE - SPLICE PLATES MIN. 24" OR USE SPLICE PLATE STRAPS.
- WALL SHEATHING TO BE 3/8" OSB / PLYWOOD. LEAVE 1/8" GAPS BETWEEN SHEATHING PANELS & 1/8" GAPS AROUND OPENINGS FOR WINDOWS & DOORS. FASTEN PANELS WITH 2 COMMON (6d) OR 1 3/4" DEFORMED SHANK NAILS AT 6" O.C. ALONG PANEL EDGES AND AT 12" O.C. ALONG THE INTERMEDIATE SUPPORTS. KEEP NAILS 3/8" AWAY FROM PANEL EDGES.
- ROOF SHEATHING TO BE 5/8" RATED OSB / PLYWOOD W/ 1" CLIPS FASTENED W/ 8d COMMON NAILS AT 6" O.C. ALONG PANEL EDGE AND 12" IN THE FIELD.
- PROVIDE BLOCKING AS REQUIRED AT ALL AREAS TO RECEIVE BUILT-IN CABINETS, EQUIPMENT, HARDWARE AND ACCESSORIES.
- ALL DUCTS, AIR HANDLERS, FILTER BOXES AND BUILDING CAVITIES (NOT FOR SUPPLY AIR) USED AS DUCTS SHALL BE SEALED. JOINTS OF DUCT SYSTEMS SHALL BE MADE SUBSTANTIALLY AIR TIGHT BY MEANS OF TAPES, MASTICS, GASKETING OR OTHER APPROVED CLOSURE SYSTEMS.
- ALL OUTDOOR AIR INTAKES & EXHAUSTS SHALL BE PROVIDED WITH DAMPERS (AUTOMATIC OR GRAVITY) TO EFFECTIVELY CLOSE WHEN VENTILATION SYSTEM IS NOT OPERATING.

PATIO STRUCTURE

FLOOR PLAN

DATE: 06 - 06 - 22
SCALE: AS NOTED
DRAWN: J. R.
JOB:
SHEET NO.:

A
1.2



ROOF FRAMING PLAN
SCALE: 1/4" = 1'-0"

GENERAL ROOF NOTES:

- ENGINEERED ROOF TRUSSES THROUGHOUT - SEALED CALCULATIONS TO BE DELIVERED WITH TRUSSES
- ROOF PITCH = 4:12 ∇ MATCH EXIST. U.N.O.
- TYPICAL OVERHANG = 1'-0"
- ALL MULTI-MEMBER ROOF TRUSSES MUST BE SUPPORTED W/ 2" x 6" TO MATCH NUMBER OF FLYS OF ROOF TRUSS - UPPER & LOWER LEVELS.

ROOF CONSTRUCTION:

- ASPHALT SHINGLES - MATCH EXIST. HOUSE
- "FALISADE" 35 YEAR SYNTHETIC ROOFING UNDERLAYMENT
- 1/2" (FOR SHINGLES) / 5/8" (FOR TILE) CDX PLYWOOD / O.S.B. ROOF SHEATHING W/ "H" CLIPS FASTENED W/ 8D COMMON NAILS AT 6" O.C. ALONG PANEL EDGE AND 12" IN THE FIELD
- FIRE-ENGINEERED ROOF TRUSSES PER TRUSS MANUFACTURER W/ SIMPSON H2.5A OR EQUAL CONNECTORS AT EACH TRUSS TYPICAL
- BLOWN OR BATT INSULATION (R-30)
- 1/2" NON-SAG GYPSUM BOARD CEILING (INTERIOR) / 3/8" ADX PLYWD. SOFFITS AT EAVES / 1/2" NON-SAG EXTERIOR GYPSUM BOARD CEILINGS AT COVERED ENTRY & PATIO LOCATIONS
- 1" x 8" LAMINATED FASCIA BOARD OVER
- 2" x 6" SUB-FASCIA 3/8" ADX PLYWOOD SOFFITS

NOTE:
TOP OF ALL WALLS ARE +9' - 1 1/8" - U.N.O.

NOTED CEILING HEIGHTS = WALL HEIGHT:

- A. 8' CLG. = 8'-1 1/8" WALL HEIGHT
- B. 9' CLG. = 9'-1 1/8" WALL HEIGHT
- C. 10' CLG. = 10'-1 1/8" WALL HEIGHT
- D. 11' CLG. = 11'-1 1/8" WALL HEIGHT
- E. 12' CLG. = 12'-1 1/8" WALL HEIGHT

ROOF TRUSS FRAMING TO BE INSTALLED PER ROOF TRUSS MANUFACTURERS LAYOUT

2018 IRC R802.10.3 BRACING
TRUSSES SHALL BE BRACED TO PREVENT ROTATION AND PROVIDE LATERAL STABILITY IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CONSTRUCTION DOCUMENTS FOR THE BUILDING AND ON THE INDIVIDUAL TRUSS DESIGN DRAWINGS. IN THE ABSENCE OF SPECIFIC BRACING REQUIREMENTS, TRUSSES SHALL BE BRACED IN ACCORDANCE WITH ACCEPTED INDUSTRY PRACTICE SUCH AS THE SBGA BUILDING COMPONENT SAFETY INFORMATION (BCSI) GUIDE TO GOOD PRACTICE FOR HANDLING, INSTALLING & BRACING OF METAL PLATE CONNECTED WOOD TRUSSES.




PATIO STRUCTURE


ROOF FRAMING PLAN

DATE: 06 - 06 - 22
SCALE: AS NOTED
DRAWN: J. R.
JOB:
SHEET NO.:


A
1.3




EAST ELEVATION 2
SCALE: 1/4" = 1'-0"




WEST ELEVATION 1
SCALE: 1/4" = 1'-0"



SOUTH ELEVATION 3
SCALE: 1/4" = 1'-0"



NORTH ELEVATION 3
SCALE: 1/4" = 1'-0"



- NOTES:
1. INSTALL WEEP SCREED TO TERMINATE MIN. 2" BELOW TOP OF FOUNDATION WALL & A MIN. 6" ABOVE FINISHED GRADE & 2" MIN. ABOVE AT FLAT WORK OR AS REQUIRED BY CODE.
 2. LAP MOISTURE BARRIER INTO WEEP SCREED TO DIRECT WATER TO THE EXTERIOR.
 3. PROVIDE WATER PROOFING AT THE FOUNDATION TO PROTECT THE SUPPORT STRUCTURE FROM RISING DAMP.

TYPICAL WEEP SCREED DETAIL 1
SCALE: 1/2" = 1'-0"

PATIO STRUCTURE
EXTERIOR DETAILS

DATE: 06 - 06 - 22
SCALE: AS NOTED
DRAWN: J. R.
JOB:
SHEET NO.:

A
2.2



PERSPECTIVE 2



PERSPECTIVE 1



PERSPECTIVE 4




PERSPECTIVE 3




FIREPLACE PERSPECTIVE 6



OUTSIDE KITCHEN 5




BUILDING SECTION "B"
SCALE: 1/4" = 1'-0"



BUILDING SECTION "A"
SCALE: 1/4" = 1'-0"

KEY NOTES:


- 24" X 12" THICKENED CONCRETE SLAB FOOTING REINF. W/ (2) #4 BARS PARALLEL TO WALL & #4 BARS PERPENDICULAR TO WALL AT 12" O.C.
- 4" CONC. SLAB REINF. W/ #3 BARS AT 24" O.C. EACH WAY
- 4" COMPACTED (95% MIN.) AGG. BASE COURSE
- 2" X (WALL THICKNESS) PLATE (SEE FLOOR PLAN) RED HEADED AT 48" O.C. AND FROM END OF PLATES
- 2" X (WALL THICKNESS) STUDS (SEE FLOOR PLAN) AT 16" O.C.
- UNDISTURBED SOIL OR ENGINEERED FILL



INTERIOR THICKENED SLAB CONDITION

KEY NOTES:

- 24" SQUARE X 12" CONCRETE PAD FOOTING REINF. W/ (3) #4 BARS EACH WAY
- 4" CONC. SLAB REINF. W/ #3 BARS AT 24" O.C. EACH WAY
- 4" COMPACTED (95% MIN.) AGG. BASE COURSE
- 2" X (WALL THICKNESS) PLATE (SEE FLOOR PLAN) RED HEADED AT 48" O.C. AND FROM END OF PLATES
- BUILT-UP STUDS OR SOLID WOOD POST / COL. WIDTH = BEAM WIDTH & / OR GIRDER TRUSS PLYS X MIN. DEPTH = WALL DEPTH - UNLESS NOTED OTHERWISE
- UNDISTURBED SOIL OR ENGINEERED FILL




INTERIOR THICKENED SLAB / PAD FOOTING

NOTE: ALL REBAR TO BE 3" CLEAR FROM SOIL

SCALE: 1" = 1'-0"

KEY NOTES:

- CONCRETE PAD FOOTING - SEE DETAIL 3 / A4.1
- C.M.U. / CONCRETE PIER - SEE FOUNDATION PLAN FOR SIZE & TYPE - REINF. W/ (2) HORIZ. #4 BARS AT TOP & BOTTOM & HORIZ. #4 BARS AT 32" O.C. & VERT. #4 BARS AT EACH CORNER
- SIMPSON CBSQ66-SD82.5 COLUMN BASE W/ 1" STANDOFF - SEE DETAIL 9 / A4.2
- 6" X 6" POST
- 4" COMPACTED (95% MIN.) AGG. BASE COURSE
- CONSTRUCTION JOINT W/ EXPANSION MATERIAL
- 4" CONCRETE SLAB REINF. W/ #3 REBAR AT 24" O.C. EACH WAY -SLOPE 1" PER 10'-0" AWAY -FROM BUILDING - W/ 8" X 8" TURNED DOWN SLAB EDGE
- NEW FINISHED GRADE TO SLOPE AWAY FROM BUILDING AT 5% (6" PER 10'-0")
- UNDISTURBED SOIL




TYPICAL C.M.U. / CONCRETE PIER DETAIL

NOTE: ALL REBAR TO BE 3" CLEAR FROM SOIL

SCALE: 1" = 1'-0"

KEY NOTES:

- SIMPSON CBSQ-SD82 POST BASE WITH 1" STANDOFF - CBSQ44-SD82 FOR A 4" X 4" POST, SIMPSON CBSQ66-SD82 FOR A 6" X 6" POST - SEE FLOOR PLAN FOR POST SIZE
- POST - SEE FLOOR PLAN FOR POST SIZE
- THICKENED CONCRETE SLAB, POURED CONCRETE PIER OR C.M.U. PIER BLOCK GROUTED SOLID - SEE FOUNDATION PLAN




TYP. CBSQ-SDS2 POST BASE DETAIL


NOTE: ALL REBAR TO BE 3" CLEAR FROM SOIL

KEY NOTES:


- 2" X 6" PRE-TREATED SILL PLATE OVER SILL SEALER W/ 1/2" DIA. X 12" ANCHOR BOLTS @ 48" O.C. MAX. 4 12" FROM CORNERS 4 END OF PLATES - INSTALL SO EXTERIOR WALL SHEATHING IS FLUSH WITH FOUNDATION WALL
- 2" X 6" STUDS AT 16" O.C.
- 3/8" (MIN.) CDX PLYWOOD OR O.S.B. WALL SHEATHING TO BE FLUSH W/ FACE OF FOUNDATION WALL - FASTEN W/ 8D NAILS AT 6" O.C. AT ALL PANEL EDGES 4 12" O.C. ON ALL FRAMING MEMBERS NOT AT PANEL EDGES
- "TYVEK" BUILDING WRAP
- EXTERIOR FINISH - SEE EXTERIOR ELEVATIONS
- 1/2" GYPSUM BOARD
- CORNER FRAMING - SEE INSIDE / OUTSIDE CORNER DETAIL 2 / 451
- DOUBLE 2" X 6" TOP PLATE - TOP PLATE TO OVERLAP AT ALL CORNERS



INSIDE CORNER



OUTSIDE CORNER



CORNER FRAMING AT TOP PLATE


CORNER FRAMING DETAILS

SCALE: 1" = 1'-0"

3

KEY NOTES:

- "FALISADE" 35 YEAR SYNTHETIC ROOFING UNDERLAYMENT OVER 1/2" (SHINGLES) / 5/8" (TILE) CDX FLYWOOD / O.S.B. ROOF SHEATHING W/ 1" CLIPS FASTENED W/ 8D COMMON NAILS AT 6" O.C. ALONG PANEL EDGE AND 12" IN THE FIELD
- APPLY FEEL 4 STICK RUBBERIZED ASPHALT MEMBRANE BY GRACE CONSTRUCTION PRODUCTS OR EQUAL TO VALLEY - LAP VALLEY 6" MIN. ON EACH SIDE
- 26 GA. GALVANIZED STEEL FLASHING - 24" WIDE W/ 1" V-CRIMP IN MIDDLE TO LIMIT FLOW ACROSS VALLEY - LAP FLASHING 6" MIN.
- APPLY FEEL 4 STICK RUBBERIZED ASPHALT MEMBRANE BY GRACE CONSTRUCTION PRODUCTS OR EQUAL TO LAP METAL VALLEY FLASHING 4" MIN.
- CONTINUOUS METAL DRIP EDGE
- APPLY FEEL 4 STICK RUBBERIZED ASPHALT MEMBRANE BY GRACE CONSTRUCTION PRODUCTS OR EQUAL TO LAP METAL DRIP EDGE 2" MIN.
- LIGHT WEIGHT CONC. FLAT "SLATE" STYLE ROOF TILE OVER 1" X 2" PRE-TREATED BATTENS 48" LONG W/ 1/2" GAP BETWEEN ENDS - SPACE BATTENS EVENLY AS REQUIRED TO ALLOW A 3" MIN. OVERLAP OF ROOF TILES - FASTEN W/ 8D NAILS AT 24" O.C. (BATTENS NOT SHOWN)
- FASCIA BOARD




VALLEY FLASHING DETAIL

SCALE: 1" = 1'-0"


2

KEY NOTES:

- POST - SEE FLOOR PLAN
- SIMPSON ECCQ-SD52.5 OR CCTQ-SD52.5 POST CAP - SEE FLOOR PLAN
- BEAM - SEE ROOF FRAMING PLAN



TYPICAL CORNER CONDITION (ECCQ)



TYPICAL CORNER CONDITION (CCTQ)


TYPICAL SIMPSON CCG / ECCQ / CCTQ POST CAP DETAILS

SCALE: 1" = 1'-0"

1

KEY NOTES:

- POST - SEE FLOOR PLAN
- SIMPSON CCG-SD52.5 POST CAP - SEE FLOOR PLAN
- BEAM - SEE ROOF FRAMING PLAN



TYPICAL CONDITION (CCQ)


TYPICAL SIMPSON CCG / ECCQ / CCTQ POST CAP DETAILS

SCALE: 1" = 1'-0"

1

KEY NOTES:


- 2" X 6" PRE-TREATED SILL PLATE OVER SILL SEALER W/ 1/2" DIA. X 10" ANCHOR BOLTS @ 48" O.C. MAX. 4 12" FROM CORNERS 4 END OF PLATES - INSTALL SO EXTERIOR WALL SHEATHING IS FLUSH WITH FOUNDATION WALL
- 2" X 6" PRE-CUT STUDS AT 16" O.C.
- 2" X 6" TRIMMER STUD - DOUBLE TRIMMER STUD FOR OPENINGS 9'-0" AND WIDER
- 2" X 6" KING STUD
- 2" X 6" SILL PLATE
- 2" X 6" CRIPPLE STUDS
- 2" X 6" HEADER PLATE
- HEADER (DOUBLE 2" X 10" MIN. - U.N.O.) - SEE ROOF FRAMING PLAN
- DOUBLE 2" X 6" TOP PLATE
- WALL HEIGHT
 - 8' CLG. = 8'-1 1/8"
 - 9' CLG. = 9'-1 1/8"
 - 10' CLG. = 10'-1 1/8"
 - 11' CLG. = 11'-1 1/8"
 - 12' CLG. = 12'-1 1/8"
- VARIABLES DEPENDING ON DOOR 4 WALL HEIGHT
- VARIABLES DEPENDING ON TOP OF WINDOW 4 WALL HEIGHT



TYPICAL EXTERIOR WALL FRAMING

SCALE: 1/2" = 1'-0"

5




- KEY NOTES:**
- DOUBLE 2" X 6" STUDS MIN.
 - SIMPSON HOLD-DOWN - SEE SCHEDULE
 - PRE-TREATED BOTTOM PLATE
 - SLAB / FOUNDATION WALL / FOOTING - SEE FOUNDATION PLAN
 - ANCHOR BOLTS - SEE SCHEDULE


TYPICAL HOLD DOWN DETAIL

SCALE: 3/4" = 1'-0"

4



PLAN NOTE:
VERIFY LOCATION OF EXISTING ELECTRICAL LINE. CONNECT NEW ELECTRICAL LINE INTO EXISTING AS REQUIRED



SCHEMATIC ELECTRICAL PLAN

SCALE: 1/4" = 1'-0"

ELECTRICAL PLAN NOTES:

- THE FOLLOWING APPLIANCES ARE REQUIRED TO HAVE A SEPARATE 20 AMP CIRCUIT: DISHWASHER, TRASH COMPACTOR, SWAMP COOLER, MICROWAVE, OVEN AND WASHER. THE WASHER CIRCUIT MAY SERVE ONE ADDITIONAL OUTLET IN THE LAUNDRY AREA.
- ELECTRICIAN TO PROVIDE COPPER WIRE AT ELECTRIC SERVICE ENTRANCE.
- ELECTRICIAN SHALL VERIFY LOCATION OF SERVICE ENTRANCE AND METER WITH UTILITY COMPANY PRIOR TO START OF CONSTRUCTION.
- ELECTRICIAN TO PROVIDE TEMPORARY POWER AS REQUIRED.
- IF INTERCOM AND/OR SECURITY SYSTEM IS INCLUDED, ELECTRICIAN SHALL VERIFY LOCATIONS WITH GENERAL CONTRACTOR.
- ELECTRICIAN SHALL HOOK UP ALL APPLIANCES SELECTED BY OWNER.
- ELECTRICIAN TO PRE-WIRE FOR TELEPHONE, TELEVISION, FUTURE CABLE AND INTERNET (INCLUDING TRIM-OUT)
- ALL CEILING BOXES TO BE RIGIDLY SECURED TO FRAMING.
- PROVIDE A FUSED DISCONNECT AS PER MANUFACTURER SPECIFICATIONS TO ALL A/C POWER LOCATIONS.
- ALL EXTERIOR OUTLETS, BATHROOM OUTLETS, GARAGE OUTLETS TO BE EQUIPPED WITH G.F.C.I.
- GARAGE AND EXTERIOR OUTLETS TO BE WATERPROOF.
- TWO OR MORE SEPARATE SMALL APPLIANCE CIRCUITS ARE REQUIRED IN THE KITCHEN, BREAKFAST ROOM, DINING ROOM OR OTHER SIMILAR AREA.
- PROVIDE OUTLETS AT KITCHEN SO THAT NO PORTION OF COUNTER IS MORE THAN 24" FROM AN OUTLET.
- ALL KITCHEN COUNTERTOP OUTLETS SHALL BE ON A DEDICATED 20 AMP G.F.C.I. BREAKER.
- ALL BATHROOM OUTLETS SHALL BE ON A DEDICATED 20 AMP G.F.C.I. BREAKER.
- ALL BRANCH CIRCUITS TO BEDROOMS SHALL BE ON A DEDICATED ARC-FAULT CIRCUIT INTERRUPTER BREAKER.
- PROVIDE ELECTRICAL SERVICE TO HVAC UNIT (VERIFY LOCATION)
- VERIFY WITH CONTRACTOR LOCATION OF PREFERRED LOCATIONS FOR TV AND PHONE OUTLETS. ANY CHANGES TO THE ELECTRICAL LAY-OUT, VERIFY FOR ANY ADDITIONAL CHANGES.
- ELECTRICAL PLAN IS STRICTLY DIAGRAMMATIC. CONTRACTOR IS TO OBTAIN ENGINEERING WHEN REQUESTED BY BUILDING OFFICIALS. ALL WORK MUST CONFORM TO 2011 NEC AND 2012 IRC CODES
- PROVIDE 120 VOLT SINGLE PHASE POWER TO UTILITY ROOF MOUNT A/C UNITS, ALSO PROVIDE COMPLETE WIRING, INCLUDING DISCONNECT SWITCHES, FUSES, CONTROL WIRING, ETC. FOR A/C EQUIPMENT PER MANUFACTURER'S SPECIFICATIONS IN COMPLIANCE WITH THE LATEST N.E.C. - SEE SHEET E-1.2 FOR LOCATIONS OF A/C UNITS.
- ELECTRICAL LOAD CALCULATIONS AND PANEL SCHEDULE ARE TO BE PROVIDED BY OTHERS

NOTES:

- A SEPARATE 20 AMP RATED BRANCH CIRCUIT FOR RECEPTACLES LOCATED IN BATHROOM AREAS.
- ALL BRANCHES THAT SUPPLY 125V, SINGLE PHASE, 15 AMP & 20 AMP RECEPTACLE OUTLETS INSTALLED IN BEDROOMS SHALL BE PROTECTED BY AN ARC FAULT CIRCUIT INTERRUPTERS.
- A SEPARATE 20 AMP RATED BRANCH CIRCUIT FOR RECEPTACLES LOCATED IN LAUNDRY AREAS.
- A MIN. OF (2) 20 AMP RATED BRANCH CIRCUITS FOR RECEPTACLES LOCATED IN THE KITCHEN, BREAKFAST & DINING AREAS

ELECTRICAL LEGEND

	CEILING MOUNT LIGHT
	HANGING PENDANT LIGHT
	RECESSED LED LIGHT
	WALL MOUNT LIGHT
	WALL MOUNT LIGHT FULLY SHIELDED
	48" LED FLUORESCENT GARAGE / SHOP LIGHT
	UNDER CABINET LED LIGHT
	EXHAUST FAN
	EXHAUST FAN & LIGHT COMBINATION
	CEILING FAN W/ LIGHT KIT
	CEILING FAN
	TRACK LIGHTING
	ROPE / ABOVE CABINET LED LIGHTING
	CABINET TOE KICK LED LIGHTING
	SMOKE DETECTOR
	CARBON MONOXIDE DETECTOR
	SINGLE POLE SWITCH
	DOUBLE POLE SWITCH
	THREE WAY SWITCH
	FOUR WAY SWITCH
	DIMMER SWITCH
	FAN SWITCH
	DOOR ACTIVATED SWITCH
	GARAGE DOOR OPENER
	CONDUIT
	DUPLEX - 110 VOLT OUTLET
	1/2 SWITCHED DUPLEX 110 VOLT OUTLET - VERIFY SWITCH LOCATION W/ OWNER
	DOUBLE DUPLEX 110 VOLT OUTLET
	220 VOLT
	RANGE 220 VOLT (36" A.F.F.)
	WEATHERPROOF (GFCI) DUPLEX 110 VOLT OUTLET
	GROUND FAULT CIRCUIT INTERRUPTER DUPLEX 110 VOLT OUTLET
	ARC FAULT CIRCUIT INTERRUPTER DUPLEX 110 VOLT OUTLET
	FLOOR - 110 VOLT OUTLET VERIFY LOCATION(S) W/ OWNER
	DRYER - 220V
	TELEPHONE
	CABLE T.V.
	DATA
	THERMOSTAT
	DOOR BELL
	DOOR BELL CHIME
	SPEAKER

NOTES:


- TOP OF ALL SWITCH BOXES TO BE AT 44"-48" ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE
- TOP OF ALL OUTLETS TO BE AT 12"-16" ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE
- MOUNT ALL GARAGE OUTLETS AT 42"-48" ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE
- MOUNT RECEPTACLES AT COUNTERTOP LOCATIONS 2" ABOVE BACKSPASH.
- DISHWASHER RECEPTACLE TO BE MOUNTED AT 6" ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE

NOTE:
DUE TO INDIVIDUAL PREFERENCES, MATERIALS AND METHODS OF INSTALLATION, THIS SHEET IS FOR THE BUILDER AND ELECTRICAL CONTRACTOR TO LAYOUT AND SIZE ALL REQUIRED WORK AND MATERIAL ACCORDINGLY. THE REQUIRED WORK, MATERIALS, INSTALLATION, AND OTHER DETAILS WILL VARY DEPENDING ON THE TYPE OF INDIVIDUAL PREFERENCES, MATERIALS AND METHODS OF INSTALLATION THAT ARE TO BE USED. THESE CORRESPONDING DETAILS AND SPECIFICATIONS ARE TO BE OBTAINED FROM YOUR BUILDER, OR ELECTRICAL CONTRACTOR.

PATIO STRUCTURE

SCHEMATIC ELECTRICAL PLAN

DATE: 06 - 06 - 22
SCALE: AS NOTED
DRAWN: J. R.
JOB:
SHEET NO.:



SCHEMATIC PLUMBING PLAN
SCALE: 1/4" = 1'-0"



NOTE:
DUE TO INDIVIDUAL PREFERENCES, MATERIALS AND METHODS OF INSTALLATION, THIS SHEET IS FOR THE BUILDER AND PLUMBING CONTRACTOR TO LAYOUT AND SIZE ALL REQUIRED WORK AND MATERIAL ACCORDINGLY. THE REQUIRED WORK, MATERIALS, INSTALLATION, AND OTHER DETAILS WILL VARY DEPENDING ON THE TYPE OF INDIVIDUAL PREFERENCES, MATERIALS AND METHODS OF INSTALLATION THAT ARE TO BE USED. THESE CORRESPONDING DETAILS AND SPECIFICATIONS ARE TO BE OBTAINED FROM YOUR BUILDER, OR PLUMBING CONTRACTOR.

- PLUMBING NOTES (2018 I.R.C.):**
1. VERIFY IN FIELD THE LOCATION OF THE CONNECTION TO THE WASTE TREATMENT SYSTEM LOCATION.
 2. PROVIDE DISHWASHER WITH AN APPROVED AIR GAP DEVICE.
 3. ALL FIXTURES WITH HOSE OUTLETS SHALL BE EQUIPPED WITH APPROVED BACK FLOW PREVENTERS (VACUUM BREAKERS).
 4. ISOLATE ALL PIPING FROM FRAMING WITH INSULATORS.
 5. INSULATE ALL HOT WATER PIPES AND COLD WATER PIPES EXPOSED TO POTENTIAL FREEZING CONDITIONS. USE FIBERGLASS PIPE INSULATION IN CRAWL SPACES AND IN EXPOSED LOCATIONS.
 6. THE PLUMBING CONTRACTOR SHALL BE RESPONSIBLE TO DETERMINE THE ACTUAL LAYOUT OF ALL GAS, WATER AND WASTE LINES.
 7. INSULATE ALL PLUMBING WALLS WITH SOUND DEADENING BATT.
 8. TANKLESS WATER HEATER (GAS) W/ EXPANSION TANK & RECIRCULATING PUMP - TANKLESS WATER HEATER IS A SEALED COMBUSTION DIRECT VENT HIGH EFFICIENCY (80% & ABOVE) UNIT - IT USES OUTSIDE AIR FOR COMBUSTION, NOT AIR INSIDE YOUR HOME. IT HAS (2) PVC PIPES PER MANUF. SPECS. THAT BRING IN COMBUSTION AIR FROM OUTDOORS AND THEN EXHAUSTS THE GASES BACK TO THE OUTDOORS.
 9. PROVIDE THERMAL EXPANSION TANK AT WATER SUPPLY.
 10. SEE FLOOR PLAN FOR LOCATION OF HOSE BIBBS (FROST FREE) WITH BACK FLOW PREVENTION.
 11. PROTECT WITH PLASTIC SLEEVES ALL COPPER LINES WHICH HAVE POTENTIAL OF COMING IN CONTACT WITH CONCRETE OR MASONRY.
 12. DIELECTRIC UNIONS SHALL BE REQUIRED ON WATER PIPING OF DISSIMILAR METAL MATERIALS.
 13. ISLAND SINKS SHALL BE LOOP VENTED.
 14. THE AUTO WASHER BOX FOR WASHING MACHINE SHALL HAVE A SINGLE LEVER TYPE HOSE TURN OFF FOR BOTH HOT AND COLD WATER - GLOBE VALVES ARE NOT ACCEPTED.
 15. SOLDER FOR COPPER PIPING SHALL HAVE A MAXIMUM LEAD CONTENT OF .002% (TWO TENTHS OF ONE PERCENT).
 16. VENTS SHALL BE A MINIMUM OF 10'-0" FROM ANY AIR INTAKE.
 17. SEE PLUMBING SPECIFICATIONS DIVISION 15 SECTION 15400.
 18. AT OPENINGS AROUND VENTS, PIPES, WASTE LINES, ETC. IN CEILING AND FLOOR PENETRATIONS, PROVIDE AN APPROVED FLAME AND HOT GAS SEALANT.
 19. PROVIDE CODE APPROVED SEDIMENT TRAPS AT GAS FIRED APPLIANCES, EXCLUDING ILLUMINATING FIXTURES, RANGES, CLOTHES DRYERS AND OUTDOOR GRILLS - SEE I.R.C. SECTION G2419.4.
 20. ALL PLUMBING WORK SHALL BE TESTED, THEN INSPECTED BY BUILDING OFFICIAL TO ENSURE COMPLIANCE WITH THE REQUIREMENTS OF THIS CODE.
 21. THE PLUMBER SHALL BE FAMILIAR WITH THE PLUMBING REQUIREMENTS OF THE 2018 I.R.C. WOOD FRAMED STRUCTURAL MEMBERS SHALL NOT BE DRILLED, NOTCHED OR ALTERED IN ANY MANNER EXCEPT ALLOWED BY CODE.

PLUMBING NOTES:
PLUMBING CONTRACTOR TO PLACE ALL PIPING AND FITTINGS IN FIELD PER CURRENT JURISDICTION CODE REQUIREMENTS - INSULATE HOT WATER LINES.

- WATER PIPING NOTES:**
1. WATER IS SUPPLIED BY A 1" WATER LINE FROM WATER METER.
 2. WATER HEATER SHALL BE SUPPLIED WITH A MINIMUM 3/4" COLD LINE.
 3. WATER HEATER SHALL HAVE A MINIMUM 3/4" LINE OUT SERVING THE FIXTURES LISTED.
 4. (1) 1/2" WATER LINE SHALL FEED NO MORE THAN (6) FIXTURE UNITS.
 5. ALL INDIVIDUAL FIXTURE SUPPLIES SHALL HAVE A 1/2" FEED LINE.
 6. ICE MAKER SHALL HAVE A MINIMUM 1/4" FEED LINE.
 7. LOOPED HOT WATER LINES FOR RECIRCULATION PUMP ARE REQUIRED.

- WASTE WATER PIPING NOTES:**
1. FOLLOW ALL MINIMUM PIPE SIZE NOTES.
 2. WATER HEATER SHALL BE SUPPLIED WITH A MINIMUM 3/4" COLD LINE.
 3. VENTS SHALL EXIT THE ROOF AND EXTEND A MINIMUM 12" ABOVE FINISH SURFACE.
 4. PIPES GOING THROUGH FOOTINGS OR UNDER FOOTINGS OR STEM WALLS SHALL BE SLEEVED.
 5. PIPE THROUGH FOOTINGS SHALL NOT AFFECT THE STRUCTURAL INTEGRITY OF THE FOOTING. A CONTINUOUS FOOTING SIZED PER THE FOUNDATION PLAN MUST BE ABOVE OR BELOW THE PIPE.
 6. VERIFY ALL FINISH FLOOR HEIGHTS IN REGARDS TO SEWER LATERAL TO ASSURE PROPER DRAINAGE FALL.
 7. SEWER LATERAL MAY FALL AT A MINIMUM OF 1/4" FOR 3" PIPE AND 1/8" FOR 4" PIPE.

FIRE SUPPRESSION SYSTEM IS TO DESIGN BY OTHERS