

# RHINEGEIST BREWERY WASTEWATER PRETREATMENT

SWOWEA Industrial Waste Seminar  
1/27/2022

---


**Janae Chaney**  
Sustainability Director  
Rhinegeist Brewery



# OVERVIEW

- 🔹 Brewery Wastewater pH
- 🔹 pH Control Project
- 🔹 Brewery Organic Solid Waste
- 🔹 High Strength Waste Project

# BREWERY WASTEWATER pH



# pH CONTROL PROJECT – BACKGROUND

## OPPORTUNITY

1. Wastewater effluent needs to remain between 5.0 – 12.5 per our Wastewater Discharge Permit

## GOALS

1. Minimize equipment footprint
2. Mitigate construction & operational costs
3. Install as quickly as possible
4. Post-project implementation effluent is between 5 and 12.5

## CONSTRAINTS

1. Equipment shall be installed in the basement
2. Equipment shall fit within the freight elevator (8' x 11.5' x 14')

# pH CONTROL PROJECT – DESIGN CONSIDERATIONS

## 1. Equalization Tanks

1. Wastewater hold-up volume
2. Material
3. Size
4. Quantity

## 2. Solids Settling

1. Recirculation via pumping or agitation via mixer

## 3. Chemical Dosing System

1. Gravity-fed from bulk storage tanks, one floor above
2. Pumped from individual chemical drums in basement

## 4. Control & Alarming

## 5. Data Collection & Reporting

# pH CONTROL PROJECT – SCOPE

## 1. Equalization Tanks

1. Two (2) 3,500-gallon tanks
  1. Double-walled fiberglass
  2. Agitator/motor/VFD to keep solids in circulation
  3. pH probe

## 2. Chemical Dosing System

1. Pumped via peristaltic pumps from individual drums in basement

## 3. PLC

1. HMI Screen
2. Trending
3. Remote monitoring (PC, no mobile access)

## 4. Motor Control Center


1. VFDs

# pH CONTROL PROJECT - OVERVIEW

BEFORE



AFTER



# pH CONTROL PROJECT – EQ TANKS




**EQUALIZATION TANKS  
DELIVERY**



**EQUALIZATION TANKS  
SET IN PLACE**



# pH CONTROL PROJECT – CHEMICAL DOSING



**CHEMICAL DOSING PUMP**  
• 4 TOTAL PUMPS




**ACID DRUMS**  
• 2 IN OPERATION  
• 0 SPARES

**CAUSTIC DRUMS**

- 2 IN OPERATION
- 2 SPARES

**SECONDARY CONTAINMENT**

# pH CONTROL PROJECT - CHEMICAL DOSING



# pH CONTROL PROJECT – PLC & MCC



**PROGRAMMABLE LOGIC CONTROLLER  
(PLC)**




**MOTOR CONTROL CENTER**

# pH CONTROL PROJECT MONITORING & SAMPLING LOCATION



## FLOW ANALYZER

- INSTANTANEOUS FLOW RATE
- HEAD
- TOTALIZED FLOW



## FLUME FAN

FLUME

## ULTRASONIC FLOW METER




## pH ANALYZER


- pH
- TEMPERATURE

## pH PROBE (inside flume)


# pH CONTROL PROJECT – IGNITION PROCESS SCREEN



# pH CONTROL PROJECT – IGNITION TRENDRING




# pH CONTROL PROJECT - TIMELINE



# pH CONTROL PROJECT – RESULTS

## Effluent pH Comparison





# pH CONTROL PROJECT – OPTIMIZATION

## 1. Noise Reduction

1. Installed RFI suppressors, due to pH probe flickering

## 2. pH Probe Cable

1. Ordered longer cable (20' to 30' foot) to allow calibration on floor level

## 3. Chemical Dosing Drum Inventory

1. Incorporated physical checks of drum levels over the weekend and during shifts outside of first shift


## 4. Flume Fan Installation

1. Installed fan on flume (upstream of ultrasonic flow meter) to blow CO<sub>2</sub> out of flume that was causing effluent pH to decrease during no flow timeframes over the weekend

## 5. Peristaltic Pump Preventive Maintenance

1. Increased frequency of PMs on peristaltic (dosing) pumps. Replace internal pump tubing once every 3-6 months

# BREWERY ORGANIC SOLID WASTE



# WASTEWATER SURCHARGES & DISCHARGE LIMITS






## SURCHARGE CONSTITUENTS

1. TSS – Total Suspended Solids
2. BOD – Biochemical Oxygen Demand
3. TKN – Total Kjeldahl Nitrogen

## SURCHARGE RATES & THRESHOLDS

WASTEWATER CONSTITUENT	SURCHARGE RATE	THRESHOLD
TOTAL SUSPENDED SOLIDS (TSS)	\$0.002756 per CCF for each mg/L above threshold	300 mg/L
BIOCHEMICAL OXYGEN DEMAND (BOD)	\$0.004707 per CCF for each mg/L above threshold	240 mg/L
TOTAL KJELDAHL NITROGEN (TKN)	\$0.004122 per CCF for each mg/L above threshold	25 mg/L

# BREWERY HSW STUDY



CONSTITUENT	THRESHOLD
TSS	300 mg/L
BOD	240 mg/L
TKN	25 mg/L

# HSW PROJECT – BACKGROUND

## OPPORTUNITIES

1. Surcharges begin in January 2021

## GOALS

1. Minimize wastewater surcharges
2. Minimize equipment footprint
3. Mitigate construction & operational costs
4. Install as quickly as possible

## CONSTRAINTS

1. Basement equipment shall be installed directly south of pH tanks
2. Basement equipment shall fit within the freight elevator (8' x 11.5' x 14')
3. No additional footprint required for storage in shipping/receiving area

# HSW PROJECT – DESIGN CONSIDERATIONS

## 1. Storage Tank(s)

1. Storage Volume
2. Material
3. Size(s)
4. Quantity

## 2. Solids Settling

1. Recirculation via pumping or agitation via mixer

## 3. Solids conveyance

1. Getting solids to storage tank
2. Pumping from storage tank to tanker

## 4. Control & Alarming

# HSW PROJECT – SCOPE

## 1. Storage Tanks

1. 3,500-gallon tank in basement
  1. Double-walled fiberglass
  2. Agitator/motor/VFD to keep solids in circulation
2. 7,200-gallon tank outside (between brewery & boiler building)

## 2. HSW Pumps

1. Base Mounted End Suction Centrifugal Pump
  1. Transfers HSW from Tank 1 (basement) to Tank 2 (outside)
2. Close Coupled In-Line Centrifugal Pump
  1. Transfers HSW from Tank 2 (outside) to HSW tanker

## 3. PLC


1. Tie into existing PLC (same one used for pH control system)

## 4. HSW Hauling


1. Trucked to a methane digester on a Poultry Farm in Fort Recovery, OH

# HSW PROJECT - OVERVIEW

BEFORE




AFTER





# HSW PROJECT - DECANTER



# HSW PROJECT – PUMPS & TRUCK LOADING



## PUMP 1 - BASEMENT

- FLOW: 200 GPM
- HEAD: 60 FT
- HP: 7.5
- RPM: 1200



## TRUCK LOADING PUSHBUTTON STATION



## PUMP 2 BOILER BUILDING


- FLOW: 300 GPM
- HEAD: 20 FT
- HP: 5
- RPM: 1800

# HSW PROJECT – STORAGE TANKS


## TANK 1 - BASEMENT




## TANK 2 - OUTSIDE




# HSW PROJECT – IGNITION PROCESS SCREEN



# HSW PROJECT – IGNITION TRENDDING



# HSW PROJECT - TIMELINE



# HSW PROJECT – RESULTS

## 1. SURCHARGE MITIGATION

### a) Pre-HSW Project

1. July 2020 sampling:
  1. Surcharge Rate: Serves as a baseline, pre-project implementation
  2. Estimated annual surcharge costs: over **\$1,000,000**

### b) Post-HSW Project

1. March 2021 sampling:
  1. Reduction in baseline surcharge rate: **56%**
  2. Estimated annual surcharge savings: over **\$600,000**
2. Dec 2021 sampling:
  1. Reduction in baseline surcharge rate: **61%**
  2. Reduction from March 2021 rate: **12%**
  3. Estimated annual surcharge savings: over **\$650,000**

## 2. SIDESTREAMED HSW (spent hops/yeast slurry)

- a) Over 850,000 gallons in 2021



# HSW PROJECT – OPTIMIZATION

## 1. Tank 1 (basement) level measurement

1. Issue with only knowing when tank was at high and low levels, nothing in between.
2. Replaced level sensor (floats) with radar level sensor

## 2. Tank 1 (basement) manual pump to Tank 2 (outside)

1. Issues with moving volume from Tank 1 to Tank 2 (highly manual process)
2. Added a button to the HMI that enables us to move liquid from Tank 1 to Tank 2, to ensure we get a full HSW truck every time.

## 3. HSW Pump 2 (in boiler building)

1. Issues with solids settling in the cone of the tank, causing longer truck pump outs or durations that the trucker is onsite
2. Swapped out the 3hp motor to a 5hp; increased the impeller size



# WASTEWATER SYSTEMS - BASEMENT



PRE-PROJECT INSTALLATIONS



POST-PROJECT INSTALLATIONS



**THANK YOU**