Peeling the "I/I Onion"

John W. Swartzbaugh, PE



BURGESS & NIPLE

Engineers ■ Architects ■ Planners

Develop a Plan

- How Many Communities Have I/I Issues?
- How Many Have Performed Rehabilitation?
- How Many Know What the Reduction in I/I sew.
- How Many Have a Plan in Place?







BURGESS & NIPLE


Data Gathering


- Gather Available Mapping
- Maintenance Records
- Complaint Records
- Historical Flow Metering and Rainfall Data
- Interview Staff



Public Outreach

- Letter and Questionnaire to Residents
- Inexpensive way to gain information






14. List the total number of roof downspouts on your property:

Thank you for your participation in this survey. Please return your completed questionnaire by 07/31/2012 in the enclosed return envelope.

Public Outreach

- Historically 30% 50% Return Rate
- Survey Monkey



Flow Meter & Rain Gauge Duration

- 3-4 Month Minimum Duration
- 1 Year is optimum for Data Collection
- Minimum of 1 Tipping Bucket Rain Gauge








Flow Meter and Rain Gauge Location Selection

- Select locations with 5,000 to 10,000 feet of Tributary Area
- Use Data Gathering Info to Guide Flow Meter Location Selection
- Install Meters for Baseline Comparison

Flow Meter Tributary Area Map



Detailed Flow Meter Locations Manhole Inspections

- Once Tributary Area Selected
- Verify Locations
- Observe Hydraulic Conditions and Debris Levels
- Confirm Pipe Diameters
- Inspect Flow Split Locations
- Fill out Inspection Sheets
- Take Pictures!

Flow Meter / Rain Gauge Installation



- No Flow Meter is
- Suited for Every Situation
- where they perform at their best. Each have their site conditions







Flow Meter / Rain Gauge Maintenance


- Weekly Downloads Check Batteries!
- At a Minimum Monthly Flow Confirmations
- Level Pressure Transducer Drift
- Debris partially covering velocity sensor
- Weekly Data Processing and QA/QC
- Hydrographs of Flow vs. Rainfall
- Scatter Graph of Velocity vs. Level

Flow Data QA/QC





Scatter Graph Chart - ADS




Flow and Rainfall Data Analysis

- Capacity Sheets or Hydraulic Model
- Pros and Cons to each
- Determine Sanitary Sewer Base Flow
- Water Consumption Records
- Determine Base GWI and Allowable GWI
- Determine the RDII

Further Data Analysis


- Correlate Peak Flows to Rain Fall Return Events
- Determine under Capacity Pipe Sections
- Review Tributary Area
- of I/I Determine Acceptable Level
- Prioritize Areas for Further Testing





Where is the Water Coming From?!?!

















Typical Separate Sewer Configuration




Smoke Testing





Smoke Testing Data Collection

	٥	Silloke Lesting Form		
Project Name:	NEW IBERIA			
Client Name:	NEW IBERIA	Date:	1/21	1/21/2011
Map Grid:	4-5	Technicians:	RC, SS	SS
General Information				
Address:	5085 Reed Road			
Upstream Node Name:	4-23	Downstream Node Name: 4-4	de Name: 4-4	
Line ID:	4-23:4-4			
Cover Information				
USMH Cover Holes?:		USMH Cover Slots?:	ts?:	
Number of Holes/Slots:		Size of Holes/Slots:	ts:	
Ponding?:		Print Correction?:	.,	
Pipe Information				
Pipe Length:	185	Pipe Size:	00	
Surface Cover:	ASPHALT	Smoke_Leak:	5	
Length Smoked:	185	UTSC Code:	N/A	
Comments:	NONE			
Smoke Defect Information	'n			
Line ID	_	Leak Address	Leak Number	Leak Type
4-23:4-4	50	5085 Reed Road	1	MAIN LINE



Dye Testing

- Key to Identifying I/I Pathways
- Select Locations Based on Flow Metering, **Smoke Testing and Flow Prioritization**
- Must be performed in conjunction with CCTV
- Storm Sewer Mapping is very important







Public Dye Testing


- Determine Storm Sewer Capacity
- Perform Rainfall Simulation to Known Storm Event
- Perform Testing on:
- Manholes
- Parallel Storm and Sanitary Lines
- Perpendicular Storm and Sanitary Lines in close vertical proximity

Identification of I/I Pathways




Public Dye Testing Results






Private Dye Testing

Use Questionnaire
 Results and Walk
 Abouts to determine
 unique characteristics
 to the testing area





Walk Abouts??

1492/1494	14.89	148/100	1483	1478/	1477	1472/474	1471	1468	1465	law	1821	1456	1451	1448	1445	1440	1439	1432	1429	1424	423/42	ALLEY	W. 7	Address	STREET	É
•				-		1				1	-										91		11/10	Business		
						×									×	×			×		×		A	Yard Ponding	NAME	
																							A	Street Flooding	W E	
77	TI	וד	π	TI	TI	TI	TI	71	TI	TI	TI	TI	TI	T	T	T	TI	TI	11	T	TI		3	Lateral in B-F-S	1	
																					-		-	Sag Over Lateral	3	
																	-	-	40.0					Gutter Missing	GOOM	밁
																								Gutter Clogged	100	유
																			Same					Surface Drains to	1	Ă_
000	8	100		8 0		1	-			000		00					00	0	0 0		0			Downspout Onto Ground	Ave	Ι Ξ Ξ.
																			17					Sump Onto Ground] "	\
0	0 0	0 9	0 0		00	0	0.	0	0.0		00		0	0 0	0 4	0 0	0	0 0			000			Downspout Into Ground		W = 1
		18		1	-				0.0		0.0				i,		-		o day		dix			Sump Into Ground		PROPERTY OBSERVATION
								\vdash				\vdash							į.	Г	,			Ranch on Slab	70	X = 3
			光																					Ranch w/ Basement	10	
			Ť									\vdash												BI-Level	7	Sg.
								\vdash							Г					Г				BI-Level w/ LL Garage		77
																					10			Split Level	SE	FORM
												\vdash												2-Story on Slab	SEWERSHED	Z
×ĕ	×	×g		×ec	×	Xook	×	× 8	×t	×	×S	× t	×	y. f	×	× f	×	×	×	×ŧ	×E			2-Story w/ Basement	T SE	
9		-		1	+	- 6		-	7	-	=			=		1	+	1		13				Garage Trench Drain	7 8	
								\vdash				0	1	-	•	1	5		>	1	•			LL Back Entrance Drain	10	
-					1						1													Yard Drain	10	
		w						نن				2		2	12	2				W				Good Prospect to Flood		
																								Date of Quick Response		







Public Interaction and Outreach

- Coordinate with inspection internal plumbing Homeowners time for
- Offer a copy of the lateral **Inspection CCTV**
- **Get your Property Access** Permission form Completed

TO THE PROPERTY OWNER OR TENANT

We stopped by to see you on ___/___ regarding

Sewer System Evaluation

The City of Columbus, Division of Sewerage and Drainage (DOSD) has retained Burgess & Niple, Inc. for the evaluation of the storm and sanitary sewer systems within the West televising your sewer laterals. downspouts, foundation drains, sump pumps and yard drains (if applicable); 3. Private Sewer system inspections/ basement and area flooding; 2. Testing of your laterals, requesting that you participate in the three upcoming perform field investigations in relation to the study. We are Fifth Avenue Area. Employees from Burgess and Niple, and subcontractors Brown and Caldwell, will be in the area to Owner/Resident interviews regarding

the interview and inspection. All workers will be wearing that field personnel may need to enter your home to conduct system which takes approximately 20 minutes. Please note schedule an interview and inspection of your private sewer at (614) 309-8646 or via email: Imcfarland@burnip.com to Please contact Mr. Louis McFarland of Burgess & Niple, Inc

Thank you for your cooperation. If you have any questions please contact Mr. Louis McFarland at (614) 309-8646 or via manager at (614) 645-4693 email: Imcfarland@burnip.com or Nick Domenick, Columbus Division of Sewerage and Drainage project



Columbus, Ohio 43206 Division of Sewerage and Drainage 1250 Fairwood Ave. Department of Public Utilities

Property Permission Access Form

BURGESS & NIPLE	
Phase 1 Dye Testing Form R	Recommended for Phase 2:Y/N
	S
Project Job #: 43222	Depart Time: 3:55 PM Testing Date: 6/11/2008
Testing Crew: FeeCorp B&N Field Rep: L.A. McFarland	Sanitary Main Size: 10 Inch Downstream MH: 0027S0104
1-1	Upstream MH: 0027S0092
Weather: Dry Rain	Lateral Location: 71 FROM MH0104 Rain in last 24hr
 Residential 	☐Commercial ☐Undeveloped
Used:	(\)
Dve Transfer:	
Time Water Started: 2:45 PM	
I I	
Time Dye Observed: NO DYE PRESENT IN SANITARY SEWER. 1,000 GAL	SEWER.
Downspouts Tested	RF LF CF CR RR LR
1	
Sump Pump:	DYE DISCHARGED ONTO GROUND
Leak Rating:	.5 or less 1 to 3gpm 3 to 5 gpm Greater 5 gpm
V:	Diluted
CCTV Equipment used:	
Additional Equipment Needed:	
Exhibit 1	Exhibit 2
	CONSTRUCTION CONTROL OF THE CONTROL OF T
Site Comments DYE LEAKING THROUGH N. BA	DYE LEAKING THROUGH N. BASEMENT WALL; FLOOR DRAIN CAPPED.

CITY OF | UPPER
ARLINGTON

ENGINEERING DIVISION
4100 Roberts Read • LOLUMBUS, UPTO 43228
FRAME 014 583 9365 FEX: NA 442 3270 • WMM.us-ohin.net

Upper Arlington Sanitary Sewer Evaluation and Survey Property Access Permission Form

Owner's/Resident's Information	
Name:	
Address:	
Phone: (H)(W)(C)	
Best Time to Contact:	
Property Being Investigated (if different from above address):	
have been informed and understand the tasks necessary to	5
perform the investigations for the Upper Arlington SSES Study. With my signature below, I grant permission to the City of Upper Arlington, Ohio and its agents, Burgess & Niple, Inc. and Flow Line.	ē
LLC. to enter my property at the above location for the purpose of performing one or more of the following investigation tasks at a verbally agreed upon time and date:	
iollowing investigation tasks at a verbally agreed upon time and date:	

The City's consultants are insured to perform this work and will restore your property to its preinspection condition including any plumbing fixtures that may be accessed. My signature also indicates that I am the rightful property owner and/or resident of the property location(s) where the investigation is to occur.

Clear water and/or dye testing inside and/or outside the house/structure as indicated below:

Rain water simulation tests on the exterior of the house/structure

Sewer lateral televising

Sewer lateral cleaning

Owner's or Resident's Signature

BURGESS & NIPLE


Date

Starting the Private I/I Testing


- **Based on County Auditors Mapping determine roof** area for homes that are being tested
- Calculate Runoff Rate from Home Roof and Impervious areas
- Divide Runoff Rate by Number of Downspouts
- Calibrate Gutter Hangars Flow

		1		1					A		
		2-Year	Storm	5-Year	Storm	10-Year	Storm	25-Year	Storm	NOTES:	1 The flow rate in dom assumes a roof with a 1 000 square foot surface area
ω	Rainfall (in)		_	/	1.24		1.43		1.72		ate in com a
30-Minute	Flow Rate (gpm)		21		26		30		36		ssimes a
	Volume (gal)		623		773	V	891		1,072		roof with a 1
1-Hour	Rainfall (in)		1.27		1.57		1.81		2.18		000 square
1-Hour	Flow Rate (gpm)		13		16		19		23		foot surface
	Volume (gal)		792	\	979		1,128		1,359		ne area
	Rainfall (in)		1.57	١	1.94		2.24		2.69		
2-Hour	Flow Rate (gpm)		8		10		12		14		
	Volume (gal)		979		1.209		1,396		1,677		

Private I/I Pathways without Sump Pump




Private I/I Pathways with Sump Pump



Private Lateral Cleaning Photos






Rain Fall Simulation Locations

- Downspouts
- House Foundations
- Yard / Driveway Drains
- Lateral Locations
- Low Spots or Sunken Sidewalks
- Lower Entry Steps and
 Driveways





Private Dye Testing



Innovative ways Homeowners Deal with I/I





Summarizing the Results

and Deposits Test Makestin	and the section of	1704 Wilsendotte Ave	1776 W Third Ave	1775 W. Third Ave	1771 W. Third Ave	1765 W. Third Ave	1646 W. Third Ave	1407 AARSTMOOD WAR	DAY DOOMSERA 1741	awa silah i ini	1011 Salla Ava	971 Sells Ave	957 Sells Ave	1778 Rhoda Ave.	BANK PORTING OF ALL	1718 Dhada Ava	1665 Rhoda Ave	1649 North Sta	1645 North Star	1563 North Star	1846 Kenny Rd	1820 Kenny Rd	1814 Kenny Rd	1778 Kenny Rd	1/bb Kenny Kd.	DIVID SERIO VOVI	1757 Hard Blod	1779 Hace Blud	1647 Hass Blud	1541 Haso Blod	ave watering 0791	1670 Grandway Ave	1608 Grandwaw Ave	1645 Glenn Ave	14bb Glenn Ave	1492 Hairnew Ave	1458 Fairnew Ave	1426 Fairnew Ave	1522 Elmwood Ave	1510 Elmwood Ave	1466/1468 Elmwood Ave	1456 Elmwood Ave	1445 Elmwood Ave	978 Chambers Rd	1610 Broadview Ave	1436 Broadview Ave		1461 Ashland Ave	1458 Ashland Ave	1446 Ashland Ave	1445 Ashland Ave	1424/1426 Ashland Ave	Address	
i		0					τ		Ť	i	0					0				TO		P	70	τ	2	i	7 2			0				7	,			T	70	-	r	۲	0	z		ъ	ד		ש				Phase 1	T
	0	ŀ	0	ъ	T	7		1	,	,	1	D	i		t	+		Ĭ		Ť	Р		۲	t	t	t	t	1	0	Ť	+	1	0	ı	τ	,	t	t	T	70	7	D		H							D		Complete	- Permission
į		t		Ì			T		t	,	0		О	τ	1	t						T	T	τ	,		t	t	1	0	1	0	t		T	τ	1	T		t	t		v				ס		ט		-	ī	Phase 2	d
r	ı	1			٠				ŀ			•	•				•		•		•						i,					1	1							T		Т		•				•	•		•		Single Family	Ī,
ŀ	į.		1			t	t	t	t	İ	1		i	r	t	Ť							t	t	t		t	Ť	+	1	Ť	+	+	T	t	t	t	t					Ť				•					•	Duplex	į
ı	İ	Ť	1		ĺ	f		Ť	t	Ť	İ	i	i		f	Ť		ĺ				Г	f	f	T	T	Ť	Ť	1	Ť	T	Ť	1	T	T		T	f		T	T	T	ı			Г					î		Apartment Complex	Died . Show
I	t	T	1					İ	T	T	İ	i			T	Ť	Ì						T				T	Ť	1	Ť	1	T					T			T			T							1			Commercial	i
Ī		T						Ī	T	T	Ī	Ī			İ	1							Ī		T	ı	T	Ť	T	ŀ					T					T													14 & 15	T
l	İ	ı						Ī	T	T					T	T							T	T	T	T	T	T		T	T	T			I	•				T					٠								21	b
ı			•	•	٠		•				Ī	Ī		Г	T	T					Г		Т		ı		T	T	T	ı	T	T	T				T					٠					•	•	•	•	•	•	22	Decivi No.
Γ	ŀ		T	П	Ī	Г	Г	Г	T	ı	Ī	1	ī	Г	T	Т		•	•	•		Г	Г	Г	ı	Ī	T	T	T	T	Т	Т	T		ı	П	Т	Г		Т	Г	Г			П			ī			1	ī	24	ı
	I	I			1	П	Г	Ι	Τ			٠	٠	•	ŀ	П	•				•	•	•	•			ı,		1		T	Т	T		Г		Т			Т	Г			•									34	T
Г	ı	I		•	٠		•	٠	ŀ					Г	Т	Т							Г	Г	Т	1	Т	Т	Т	ı	Т	Т	Т		Г		Т	П		Т		П	П	•					•		ä		Pre 1920	Т
•			•		ı				T	•	9	•	•	•			•		•	٠	•			•										1		1			•		•		•			•	•	•	100	•	•		1920 - 1950	1
					1/2	•		19	I						I	I		•		W		0				1						T				•		•	0								197		V27			•	Post 1950	ľ
4.0	0 0	0 3	48	20	27	3.0	1.5	10	1 4	0.0	0	5.0	1	5.0	7.0	200	2.0	3.2		1.0	2.1	6.7	2.3	2.0	3	2.0	3	9.0	30	3 2	0.0	200	3 0	1.0	3.0	4		2.0	0.5	6.9	1.5	5.0	30			3.0	4.8		4.0		2.6	5.0	Yes, (gal./min.)	1
Ī		T						I	T					Г	T	T		91					Г			0		9	T	T	T	T								Т		Г	Г				791	•	788	•	W		No	ľ
Г		T					٠		Т	T			Ų.	Г	I	ŀ	•				•	•	Г		Т	T	T	T	T	ı		Т	T		Т		Т			Т	•	•				•	ō					•	Sag /Clogged Gutter	Т
Γ	ı	T			Ī		Г	ı	T	I	I			٠	T	T							Г		Т		I	I	T	T	Т	T	T		Г	Г	Π	I		Т		Г		Г		•						•	Disconnected DS	9
Г		1	•		٠	•	٠	٠	•	•		•	•	٠			•			٠		•	٠				ŀ	4	1		Т	Т			٠					Т	Г	٠	٠	•	Г	•			•	•			Splash Block	9
•				•	•		٠		•			٠		Г	T	ŀ	•	•	•		•		Г		I		ŀ			ŀ		•	•	•		•		Т	•	٠	•						•	•		•	•		DS In Ground	
Г		I	1	•			٠	•	ŀ		I	Ī		Г	Т	Т			٠				Г	Г	Т	I	ŀ		T	ŀ	П	Т	T	•	Г		•	Г		•	L	Г					•						Curb Outlet (Good)	
	•	0							I	I	1				ſ	I							Г				T	T		ŀ		T											•					•					Curb Outlet (Plugged)	CHOCKING CONTROL
ľ	ŀ								Γ		1	•			Γ			•			•																					Г						•	Y		•		Daylight	
•		I			٠				Ι		1				Ι	1							Г	Γ			1		1		Ι	Ι					Ι			Π													Unknown	1
						•	•	1	I	١			•		I			•								100	I									•			1			٠				•	•		1.00		•		Grading to Bldg.	9
ſ		J	I						I	I	1				I	I											ŀ		•		I	I	I																	•			Low Yard Area	Ol Older
L	•				٠	17					1	٠	٠			-	•					•										ŀ		٠			1		1												•		Depressed Trench	ı
ŀ		1	-	•			•	•					٠	•			•			•							I	1				1	1			٠		•		•	•			•		•	•		•		•		Thru Basment Wall	ľ
		1	1						ľ	I	1					I					•						ŀ		I		I	ľ	I					•															Thru Basement Slab	
L							٠	L	I	•		٠		•						15												1									•	٠							100				Into Foundation Drain	
Ĺ		-	•		٠		•	•			•	٠	٠	٠			•				•		•			•			1			1	•							•			•				•		•		•		Into Lateral	۲
П									П	П	T				П	П							Г		T		П	T						1								1											Area Drain	П

14 of 16 (88%) Properties Tested Positive



4 - MAJOR PREFERENCE
3 - MEDIUM PREFERENCE
2 - MINOR PREFERENCE
1 - SLIGHT PREFERENCE
ONE POINT EACH (LETTER)

0

HOW IMPORTANT

Extrapolation of the Results – Weighted Criteria Matrix

1489 Ashland Ave.	1482 Ashland Ave.	1478/1480 Ashland Ave.	1477/1483 Ashland Ave.	1470 Ashland Ave.	1469/1475 Ashland Ave.	1464/1466 Ashland Ave.	1461 Ashland Ave.	1460/1462 Ashland Ave.	1457 Ashland Ave.	1454/1456 Ashland Ave.	1451 Ashland Ave.	1450/1452 Ashland Ave.	1446/1448 Ashland Ave.	1445 Ashland Ave.	1439 Ashland Ave.	1438/1440 Ashland Ave.	1434/1436 Ashland Ave.	1435 Ashland Ave.	1430/1432 Ashland Ave.	1429 Ashland Ave.	1424/1426 Ashland Ave.	1423 Ashland Ave.	1420/1422 Ashland Ave.	1414/1416 Ashland Ave.	1413 Ashland Ave.	1410/1412 Ashland Ave.	1405 Ashland Ave.	Address	I/I Contribution Probability: None = 0 Low = 1 Medium = 2 High = 3
0	0	%	%	0	,	%	0	0	0	0	0	0	0	%	0	0	0	0	0	%	27	0	0	0	3 27	0	0	9	Sagging/Clogged Gutters
27	%	6	00	00	00	00	0	0	1	%	%	0	0	%	%	0	0	0	0	%	0	%	0	0	3 27	0	27	9	Disconnected Downspouts (DS)
0	0	0	0	0	20	0	7	0	20	20	0	3	0	100	%	0	0	3	0	3		1	0	20	1-1	0	20	-	DS In Ground - Outlet Clear
0	6/2	0	6/0	6/10	0	ω\- ⁻	3	6/2	0	0	6/20	0	6/2	6/2	3	2 6	0	0	6/2	00	0	3 9	0	0	0	0	0	з	DS In Ground - Outlet Clogged
0	0	%	0	0	0	0	0	0	0	0	0	0	0	0	0	0	10	0	0	6	0	6	1	6	0	1	6	5	DS In Ground - Outlet Unknown
12	0	27	0	0	2 14	3 27	0	0	0	3 21	0	0	12	6	0	6	3 21	0	14	0	70	1-	3 21	3 27	12	2 14	1/2	7	DS On Ground - Slope to Bldg.
0	0	0	0	0	0	0	0	0	0	1	6	0	0	0	6	6	0	0	0	6	0	0	10	6	0	1	0	4	DS On Ground - Slope Away
12	12/2	12	2 12	16	2 12	3 18	6/-	18	12/2	3 18	2 12	12/2	2 12	18	2 12	6	1/2	6-	2 12	2 12	3 18	2 12	12	3 18	6	6	0	6	Grading Slopes to Bldg.
2 10	5	07	3 15	3 15	200	3 15	5	70	10/2	2 10	2 10	3 15	7	2 10	2 10	6	5	0	5	1 5	2 10	5	6	6	3 15	3 15	5	5	Depressed Trench/Low Area
0	0	0	0	4	0	2/4	4/0	0	0	0	0	0	3	4	0	0	0	0	0	0	3 6	0	0	~	0	0	6	2	Established Trees Present
0	0/4	0	0	0	0	0	0	0	0	0	0	00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	Sump Discharge Onto Ground
30	30	0	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	30	10	Basement Under Structure
0	0	0	0	0	0	0	0	0	24	0	3 24	0	0	3 24	0	0	0	0	%	0	0	\	0	0	2	0	0	8	Area Drain
93	57	38	63	61	89	91	49	64	78	81	82	60	73	92	61	36	78	39	67	50	106	63	63	71	128	65	78	Tota	
Г													_	_								\neg		SI	SAT	ANA			PRIVATE SOURCE PROP
							ΧI	H.	ΓĄ	M	SI	SA	. 11	7N	A										22 F	юта	SEC	- YC	W. FIFTH AVE. I/I STUD

CRITERIA SCORING MATRIX

E. Downspout Onto Ground - Sloped to Structure
F. Downspout Onto Ground - Sloped Away
G. Grading Slopes to Structure
H. Depressed Trench Low Lying Areas
I. Established Trees

M. Downspout In Ground - No Visible Outlet

Sump Discharge On Ground

A. Sagging and/or Clogged Gutters
B. Disconnected Downspouts
C. Downspout In-Ground - Outlet Clear
D. Downspout In Ground - Outlet Clogged

CRITERIA

RAW SCORE

WEIGHT

CRITERIA WEIGHTING PROCESS

PRIVATE SOURCE EVALUATION CRITERIA

W. FIFTH AVE. I/I STUDY

WEIGHTED CRITERIA


Develop Prioritization of Locations, Pilot Projects

Based on Public and Private Dye Testing **Prioritization of Locations for Pilot Projects** Results and Extrapolation – Develop

Follow Up Flow Metering

- Quantify Impact of Improvements
- Reduction of RDII flows 380 GPM remediated 76 homes
- Columbus Still Waiting on Results from Clintonville **Lateral Rehabilitation Pilot Project**

Questions??



Contact Information

John Swartzbaugh, PE

John.Swartzbaugh@burgessniple.com

Office- (614) 459-2050

Mobile – (614) 989-7759

