

# Eiger Express Pipeline Project Facts



Location:

**Pecos County, TX to  
Wharton County, TX**



Counties Crossed:

**19**



Construction timeline:

**2027 - 2028**



Mainline Test pressure:

**2,160 psi**



Operating pressure:

**900-1,440psi\***

\*pounds per square-inch



Mainline diameter:

**48"**



Product:

**Natural Gas**



Volume:

**Up to 3.7 bcf/d**

Designed to provide daily electricity  
for up to ~37.8M homes



Right of way:

**~98% Parallel  
Existing Utilities**



Annual state and local tax revenue:

**~\$28.5<sup>1</sup> Million\***

\*Once fully operational



Shut off valves:

**36**



Length:

**~450 miles**



Compressor stations:

**8**

[1] Words such as “anticipated,” “expected,” “targeted,” “projected,” “estimated,” and similar expressions are intended to identify forward-looking statements. These forward-looking statements rely on a number of assumptions concerning future events and are subject to a number of uncertainties, factors and risks, many of which are outside the control of the Company, which could cause results to differ materially from those expected by management of the Company.