



Adventures in FCC TV repacking!

ATC's Repack Status

Repack Q&A

Jim Stenberg
Principal Engineer, RF Broadcast
American Tower Corporation

Tower Location: Needham, MA
Asset Number: 5760

Repack is: TV's Gettysburg!

“It is rather for us, **the survivors of the incentive auction**, we here be dedicated to the great **repack** remaining before us — that, from these honored **auction winners** we take increased devotion to that cause for which they here, gave the last full measure of devotion — that we here highly resolve these **stations** shall not have died in vain ; that the **industry**, shall have a new birth of freedom, and that **television** of the people by the people for the people, shall not perish from the earth.”





Incentive Spectrum Auction Results

- **175** Full power and Class A reverse auction “winners” surrendered their 6 MHz spectrum
 - Options:
 - Go off-air
 - Channel share
 - Move to VHF
- **987** Full power and Class A stations require new “repack” channels
 - Channels 14 to 36 available
 - Exploit adjacent channel spacing



ATC Repack Impact



PROJECT TYPE:


- Type 1 - No tower or site modifications
- Type 2 - Moderate tower and or site modifications
- Type 3 - Complex towers, New BBAs, major tower mods

Approx. 20% of repacked stations are on ATC Assets



ATC Repack Impact

Sites and Stations by Phase and cut-over date




ATC Repack Project Status

Application Detail by Phase

- > **Phase 1:** All 15 applications received
- > **Phase 2:** All 44 applications received
- > **Phase 3:** 20 applications received, 2 remaining
- > **Phase 4:** 24 applications received, 6 remaining
- > **Phases 5-10:** 54 applications received, 61 remaining

Project Highlights

- > Of the 13 new BBA projects:
 - > 4 Complex BBA projects currently in construction to be completed in 2018
 - > 4 additional complex BBA projects starting in November 2018
- > 12 Phase 1 & 2 stations completed construction
- > 7 Major tower modifications completed in 2018



Have not received repack plans from 29% of stations



ATC Repack Project Summary


- › Phases 1-3 repack projects on ATC towers well underway
- › Processing all Phase 4-6 repack applications
- › 13 new BBA projects underway – supporting ~36 stations
- › 16 existing BBA channel reconfiguration designs completed
- › 7 major tower modifications completed through October 2018
- › Tower work for complex projects will challenge engineering, fabrication, and rigging resources in mid phases
- › Hiring qualified transmitter and RF equipment installers has become an issue
- › Safety remains our #1 priority



Existing ATC TV BBA fleet

BBA = Broadband Antenna = Multichannel system

- 29 UHF systems
- 1 VHF system
- 23 Impacted by Repack w/ 1 or more changes
- All except 1 are horizontally polarized only
- Limitations to consider
 - VSWR bandwidth
 - Pattern bandwidth
 - Power input capacity
 - Number of feedlines



Goals of our repack BBA program

- Optimize repack changes
 - Locate where an antenna has to be changed out
 - Include as many stations as possible in design
- Minimize on air disruptions
 - Provide side mount interim antennas
- Reduce overall tower loading
 - Remove unused lines/antennas
 - Re-use lines wherever practical
- Meet aggressive FCC timelines
- Minimize overall economic impact to all parties
- Provide future proof systems



New Repack BBA Locations and Quantities



ATC Repack BBA Market Solution - Boston

Boston Needham

Develop interim main site
which becomes off-site
auxiliary.

Reconfigure top of
candelabra tower for single
VHF/UHF stack




ATC Repack BBA Market Solution - Boston



Boston Needham


Dedicated common transmitter/combiner room. Five stations plus a dual chain combiner.



ATC Repack BBA Market Solution - Detroit

Detroit – Oak Park



Install side mount interim for three stations. Replace single frequency antennas on candelabra and provide auxiliary antenna long term



ATC Repack BBA Market Solution - Detroit

Detroit – Oak Park

Time domain and frequency domain measurements of 930 ft of 8" line and side mount antenna over 150 MHz







No individual response > 1.025

Input VSWR < 1.18



ATC Repack BBA Market Solution - Detroit



Three module, Four channel pre and post repack channel combiner

PRELIMINARY LAYOUT - ATC DETROIT COMBINER SYSTEM
LOOKING TOWARDS THE 22ND SECTION OF THE FENCE

REV	SHEET	ZONE	REVISION NOTE CAD MAINTAINED. CHANGES SHALL BE INCORPORATED BY THE DESIGN ACTIVITY.	EGG	DATE APPROVED
A			PRODUCTION RELEASE		

[illegible]

COMPANY CONFIDENTIAL INFORMATION CONTAINED HEREIN IS CONFIDENTIAL, IT IS THE PROPERTY OF DELTECH. IT IS TO BE USED SOLELY FOR THE PURPOSE PROVIDED, AND IT IS NOT TO BE DISCLOSED TO OTHERS WITHOUT THE PRIOR WRITTEN CONSENT OF DELTECH.

UNLESS OTHERWISE SPECIFIED

MANUFACTURING TOLERANCE AND PROCEDURES MUST BE ACCORDING TO THE ALL ALUMINA COPPER AND BRASS WELDING MUST COMPLY WITH BAKING SECT. BY THE OCEANOGRAPHIC AND PRODUCT DESIGN STRUCTURAL MATERIAL WELDING MUST COMPLY WITH NAD 14.1 CRYSTALLINE DESIGN.


ATC Repack BBA Market Solution – Houston

Missouri City RT

Develop side mount
interim main and top
mount variable
polarization dual chain
main system for three
repack stations.



ATC Repack BBA Market Solution - Houston



ATC Repack BBA Construction Underway

Atlanta Chester Avenue

Top mount interim main, permanent main, off-site auxiliary for four stations with single feedline variable polarization antenna fixed at top.

Completion 2/2019

Oklahoma City RT

Top mount interim main, permanent main, off-site auxiliary for three stations with single feedline variable polarization antenna fixed at top.

Completion 12/2018

Dallas Cedar Hill Milton

Top mount interim main, permanent main, off-site auxiliary for five stations with dual feedlines, adjustable polarization antenna part of two antenna stack, dual chain combiner. Extensive tower modification.

Completion 2/2019

Dielectric®



Questions?

Please feel free to contact me with any questions.

Jim Stenberg

Principal Engineer, RF Broadcast



james.stenberg@americantower.com



office: 207-632-8973



mobile: 207-632-8973



www.americantower.com

