

COPYRIGHT

[illegible]

PENNSYLVANIA ACT 187 REQUIREMENTS

UNDERGROUND UTILITIES SERIAL NO. 20243300770

CHESTER VILLAGE ENGINEERS, INC. DOES NOT GUARANTEE THE ACCURACY OF THE LOCATIONS FOR EXISTING SURFACE UTILITY STRUCTURES SHOWN ON THIS PLAN. THE CONTRACTOR SHALL VERIFY THE LOCATION AND ELEVATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES BEFORE THE START OF WORK.

EXCAVATIONS, TRENCHING, AND SHORING


ALL EXCAVATIONS, TRENCHING, AND SHORING OPERATIONS SHALL COMPLY WITH THE REQUIREMENTS OF THE OSHA 29 CFR 1926. SUBPART P, FEDERAL DEPARTMENT OF LABOR OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION PUBLICATIONS OR THE LATEST VERSIONS THEREOF.

SEE SHEET 02 FOR
FACILITY OWNER'S
DESIGNATED OFFICE
ADDRESS AND
TELEPHONE NUMBER

PENNSYLVANIA ONE CALL SYSTEM, INC.
CALL 3 WORKING DAYS BEFORE YOU DIG

POCS SERIAL NUMBER: 20243300770

MONTGOMERY COUNTY BLOCK 60-3 UNIT 12

<p align="center">CONSTRUCTION PLANS</p> <p align="center">FOR</p> <p align="center">UPPER POTTS GROVE MUNICIPAL COMPLEX</p> <p align="center">2290 GILBERTSVILLE ROAD</p> <p align="center">UPPER POTTS GROVE TOWNSHIP - MONTGOMERY COUNTY - PENNSYLVANIA</p>				
 <p>ChesterValley ENGINEERS, INC.</p> <p>112 Moores Road, Suite 200, Malvern, PA 19355 610-464-4623 www.chesterv.com</p>			<p>PROJECT NO.</p> <p>22096-200</p> <p>F.B.</p>	
SCALE	DATE	DRAWN BY	CHECKED BY	DRAWING
1"=40'	03/31/2025	HL	MJ	

SHEET 10 OF 23

The contractor shall contact the Company prior to beginning work to discuss the details of the transformer foundation such as position, orientation, working clearances, barrier protection, construction specifications, and inspection procedures. The contractor is responsible for purchasing as well as installing the necessary materials and equipment for the secondary rack and secondary rack enclosure (if needed). The contractor/developer shall coordinate site preparations with the desired delivery date. The contractor shall provide a clear and firm (e.g., concrete, asphalt, or grasetrete) approach to within ten (10) feet of the transformer. The contractor shall ensure that the approach is free of any materials that may block the use of delivery vehicles or Company vehicles (e.g., crane access to the transformer).

The developer/contractor is responsible for the excavation to install the transformer foundation and for backfilling afterward. The excavation shall be two (2) feet wider than the vault dimensions (shown Exhibit 25, page 2). The excavation depth shall be 45 inches deep for 42-inch high foundations and 54 inches deep for 42-inch high foundations. The excavation shall be 10 inches of AASHTO #57 crushed stone shall be leveled and compacted in the bottom of the excavation as a base. Pavement (concrete, asphalt, or grasetrete) shall be provided to within ten (10) feet of the installation for Company access. The contractor shall install a 4" x 4" x 8" lumber off to the side for temporarily unloading the foundation top at delivery time.

Conduits shall extend near the corners of the foundation (refer to Exhibit 25, page 1) through knockouts to provide for proper cable bending radius and pulling set-up and to facilitate cable routing (when needed). Conduits shall have end bells and shall be terminated flush with the inside surface of the transformer. The customer shall provide the conduit knockout areas around the conduit penetration into the foundation to transformer to prevent water migration.

The developer/contractor will furnish and install all service cables as required per Exhibit 1. The developer/contractor shall allow sufficient slack, approximately five (5) feet, in the service lateral cables after they are racked. The slack allows the service cables to be trained so that the weight of the cables will not pull the transformer out of position. The developer/contractor shall request the transformer building to provide the transformer building. The developer/contractor shall supply and install cable racks (e.g., 30-inch rack made by A.B. Chance (HUBBS), using the inserts, on the sides) of the foundation to support the service cables a minimum of 12 inches above the ground surface. Refer to Exhibit 13 for 30-inch galvanized cable rack and hooks, and ASTM A515 for zinc coating (hot dip) on iron and steel hardware.

The contractor shall seal around the service cables inside the conduits (with approved foam) to prevent migration of water or gases. All unused ducts shall also be capped.

Backfill on all sides up to finish grade with 6" minimum of AASHTO #57 crushed stone to form a reservoir to contain the transformer oil in case of a leak.

The contractor shall install a continuous loop of #2 bare, seven (7) strand, soft drawn copper ground wire underground with a minimum of 100 feet of continuous loop around the outside of the vault excavation in the undisturbed earth (refer to Exhibit 25, page 1). Both ends of the ground wire shall enter the foundation through a one (1) inch diameter hole to be drilled or chiseled in the upper right-hand corner of the foundation. Each ground wire tail shall extend fifteen (15) feet inside the vault beyond the knockout point.

The decision to open the pump drainage or leave it closed will be made by the Company based on field conditions. The contractor is responsible for taking corrective action (improve drainage, pump field, etc.) for a foundation that fills with water and water is leaking through service conduits into the foundation building. The area surrounding the foundation shall be graded so that ground water will not collect.


The contractor shall install protective barriers when the transformer is located in an area exposed to vehicular traffic (refer to Exhibit 30), consult the Company for details.

0 The deeper base for the 1500-2000 kVA transformer is used when secondary conduit configuration is not required. The 34.5 kV/1500-2000 kVA NESC common cover is used when secondary conduit configuration is required.


1 Foundation for 34.5 kV/1500-2000 kVA transformer includes 12" thick slab dividing vault from the high voltage and the low voltage compartments based 55-12" from the inside edge of the low voltage compartment side wall.




N.T.S.




N.T.S.



N.T.S.



N.T.S.



N.T.S.



HOLDING TANK DETAIL

N.T.S.

NO.	DATE	REVISION
-----	------	----------

UPPER POTTSGROVE MUNICIPAL COMPLEX

	PROJECT NO.
--	-------------








SCALE	DATE	DRAWN BY	CHECKED BY	DRAWING
-------	------	----------	------------	---------

SHEET 11 OF 11


MONTGOMERY COUNTY BLOCK 60-3 UNIT 12

SHEET 11 OF 23







STORMWATER PROFILE
FROM SW205 TO SW202
SCALE: 1"=40' HORIZ. 1"=4' VERT.




STORMWATER PROFILE
FROM OS#208 TO SW210
SCALE: 1"=40' HORIZ. 1"=4' VERT.




STORMWATER PROFILE
FROM SW207 TO SW206
SCALE: 1"=40' HORIZ. 1"=4' VERT.



STORMWATER PROFILE
FROM CO19A TO FES201
SCALE: 1"=40' HORIZ. 1"=4' VERT.



SANITARY SEWER PROFILE
FROM PUBLIC WORKS BUILDING
SCALE: 1"=40' HORIZ. 1"=4' VERT.



SANITARY SEWER PROFILE
FROM ADMIN. BUILDING
SCALE: 1"=40' HORIZ. 1"=4' VERT.

PROFILES

COPYRIGHT

CHESTER VALLEY ENGINEERS, INC., CIVIL ENGINEERS & SURVEYORS, EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND ALL OTHER PROPRIETARY RIGHTS IN THESE PLANS. ALL DRAWINGS, SPECIFICATIONS, AND COPIES THEREOF ARE AND SHALL REMAIN THE PROPERTY OF CHESTER VALLEY ENGINEERS, INC. THEY ARE TO BE USED ONLY IN RESPECT TO THE PROJECT AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF CHESTER VALLEY ENGINEERS, INC. ANY RE-USE WITHOUT WRITTEN PERMISSION OF CHESTER VALLEY ENGINEERS, INC. SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY OR LEGAL REMEDY TO CHESTER VALLEY ENGINEERS, INC. THE USER ASSUMES ANY RISK OF ANY AND ALL PROPERTY OF FINANCIAL LOSS OR DAMAGES OF ANY KIND RESULTING FROM THE USE OF THIS DOCUMENT WITHOUT FIRST OBTAINING FULL VERIFICATION AND VALIDATION OF THE INFORMATION CONTAINED IN THIS FILE.

NOTE TO USER OF THESE PLANS:

WARNING! THE INFORMATION CONTAINED ON THIS PLAN MAY NOT BE CONSISTENT WITH CONDITIONS IN THE FIELD. ANY PERSON OR ORGANIZATION USING OR RELYING ON THESE PLANS MUST CONTACT CHESTER VALLEY ENGINEERS, INC. FOR VERIFICATION OF ANY APPARENT DISCREPANCY BEFORE PROCEEDING OR RELYING UPON THESE PLANS FOR ANY PURPOSE, AND CONSTRUCTION OR INSTALLATION OF IMPROVEMENTS SHOULD OCCUR ONLY AFTER ALL DISCREPANCIES HAVE BEEN VERIFIED WITH CHESTER VALLEY ENGINEERS, INC. OR ANY OTHER PARTY. THE USER ASSUMES ANY RISK OF ANY AND ALL PROPERTY OF FINANCIAL LOSS OR DAMAGES OF ANY KIND RESULTING FROM THE USE OF THIS DOCUMENT WITHOUT FIRST OBTAINING FULL VERIFICATION AND VALIDATION OF THE INFORMATION CONTAINED IN THIS FILE.

PENNSYLVANIA ACT 187 REQUIREMENTS

CHESTER VALLEY ENGINEERS, INC. DOES NOT GUARANTEE THE ACCURACY OF THE LOCATIONS FOR EXISTING SUBSURFACE UTILITY STRUCTURES SHOWN ON THE PLANS, NOR DOES CHESTER VALLEY ENGINEERS, INC. GUARANTEE THAT ALL SUBSURFACE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL VERIFY THE LOCATION AND ELEVATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES BEFORE THE START OF WORK.



SEE SHEET 02 FOR
FACILITY OWNER'S
DESIGNATED OFFICE
ADDRESS AND
TELEPHONE NUMBER.

PENNSYLVANIA ONE-CALL SYSTEM, INC.
CALL 3 WORKING DAYS BEFORE YOU DIG
1-800-242-1776
POCS SERIAL NUMBER: 20243300770


MONTGOMERY COUNTY BLOCK 60-3 UNIT 12

NO.		DATE		REVISION	
CONSTRUCTION PLANS FOR UPPER POTTS GROVE MUNICIPAL COMPLEX 2290 GILBERTSVILLE ROAD UPPER POTTS GROVE TOWNSHIP - MONTGOMERY COUNTY - PENNSYLVANIA					
PROJECT NO. 22096-2000				F.B.	
SCALE 1"=40'				DATE 03/31/2025	
DRAWN BY PT				CHECKED BY MJ	


CVE ChesterValley
ENGINEERS, INC.

112 Moores Road, Suite 200, Malvern, PA 19355
610-644-4623
www.chestervalley.com

DRAWING



SURFACE WATER FROM THE SITE
ENTERS AN UNNAMED TRIBUTARY
OF MINISTER CREEK (TSF-MF)



INFILTRATION TESTING RESULTS							
TEST ID	EX. GROUND ELEVATION	TEST DEPTH (IN)	TEST ELEVATION	MEASURED INF. RATE	LIMITING ZONE	LIMITING ZONE ELEVATION	BMP NAME
TP1	440.22	23	438.30	0.05 IN/HR	ROCK	437.30	BMP #2
TP2	439.51	32	436.84	0.10 IN/HR	ROCK	435.84	BMP #2
TP3	442.18	40	438.85	0.44 IN/HR	ROCK	437.84	-
TP4	442.03	19	440.45	0.00 IN/HR	ROCK	439.44	-
				BMP BOTTOM ELEVATION			

POST-CONSTRUCTION
STORMWATER
MANAGEMENT PLAN

CONSTRUCTION PLANS
FOR
UPPER POTTS GROVE MUNICIPAL COMPLEX
2290 GILBERTSVILLE ROAD
UPPER POTTS GROVE TOWNSHIP - MONTGOMERY COUNTY - PENNSYLVANIA

ChesterValley
ENGINEERS, INC.

112 Moores Road, Suite 200, Malvern, PA 19355
610-644-4623
www.cve-engineers.com

PROJECT NO.
22096-2000

F.B.

SCALE
1"=40'

DATE
03/31/2025

DRAWN BY
HL

CHECKED BY
MJ

DRAWING

COPYRIGHT
CHESTER VALLEY ENGINEERS, INC., CIVIL ENGINEERS & SURVEYORS, EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND ALL OTHER PROPRIETARY RIGHTS IN THESE PLANS. ALL DRAWINGS, SPECIFICATIONS, AND COPIES THEREOF ARE AND SHALL REMAIN THE PROPERTY OF CHESTER VALLEY ENGINEERS, INC. THEY ARE TO BE USED ONLY IN RESPECT TO THE PROJECT AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF CHESTER VALLEY ENGINEERS, INC. ANY RE-USE WITHOUT WRITTEN PERMISSION OF CHESTER VALLEY ENGINEERS, INC. SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY OR LEGAL REMEDY TO CHESTER VALLEY ENGINEERS, INC. THE USER ASSUMES ANY RISK OF ANY AND ALL PROPERTY OF FINANCIAL LOSS OR DAMAGE OF ANY KIND RESULTING FROM THE USE OF THESE PLANS WITHOUT FIRST OBTAINING FULL VERIFICATION AND VALIDATION OF THE INFORMATION CONTAINED IN THIS FILE.


NOTE TO USER OF THESE PLANS:
WARNING! THE INFORMATION CONTAINED ON THIS PLAN MAY NOT BE CONSISTENT WITH CONDITIONS IN THE FIELD. ANY PERSON OR ORGANIZATION USING OR RELYING ON THESE PLANS MUST CONTACT CHESTER VALLEY ENGINEERS, INC. FOR VERIFICATION OF ANY APPARENT DISCREPANCY BEFORE PROCEEDING OR RELYING UPON THESE PLANS FOR ANY PURPOSE. NO CONSTRUCTION OR INSTALLATION OF IMPROVEMENTS SHOULD OCCUR UNTIL ALL DISCREPANCIES HAVE BEEN VERIFIED WITH CHESTER VALLEY ENGINEERS, INC. OR THEIR OFFICERS, EMPLOYEES AND REPRESENTATIVES SHALL NOT BE LIABLE FOR DAMAGES OF ANY KIND RESULTING FROM THE USER'S FAILURE TO OBTAIN CURRENT VERIFICATION AND VALIDATION OF THE INFORMATION CONTAINED ON THIS FILE TO THE USER OR ANY THIRD PARTY. THE USER ASSUMES ANY RISK OF ANY AND ALL PROPERTY OF FINANCIAL LOSS OR DAMAGE OF ANY KIND RESULTING FROM THE USE OF THESE PLANS WITHOUT FIRST OBTAINING FULL VERIFICATION AND VALIDATION OF THE INFORMATION CONTAINED IN THIS FILE.

PENNSYLVANIA ACT 187 REQUIREMENTS
UNDERGROUND UTILITIES SERIAL NO. 20243300770
CHESTER VALLEY ENGINEERS, INC. DOES NOT GUARANTEE THE ACCURACY OF THE LOCATIONS FOR EXISTING SUBSURFACE UTILITY STRUCTURES SHOWN ON THE PLANS, NOR DOES CHESTER VALLEY ENGINEERS, INC. GUARANTEE THAT ALL SUBSURFACE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL VERIFY THE LOCATION AND ELEVATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES BEFORE THE START OF WORK.
EXCAVATIONS, TRENCHING, AND SHORING
ALL EXCAVATIONS, TRENCHING, AND SHORING OPERATIONS SHALL COMPLY WITH THE REQUIREMENTS OF THE FOLLOWING UNITED STATES DEPARTMENT OF LABOR OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION PUBLICATIONS OR THE LATEST REVISIONS THEREOF:
(1) CONSTRUCTION INDUSTRY STANDARDS AND INTERPRETATIONS (OSHA 2201) SUBPART PP, PART 1926/1915 - "EXCAVATIONS, TRENCHING AND SHORING";
(2) "EXCAVATIONS AND TRENCHING OPERATIONS" (OSHA 2225) DATED 1989 (REVISED).

SEE SHEET 02 FOR
FACILITY OWNER'S
DESIGNATED OFFICE
ADDRESS AND
TELEPHONE NUMBER.

PENNSYLVANIA ONE CALL SYSTEM, INC.
CALL 3 WORKING DAYS BEFORE YOU DIG
1-800-242-1776
POCS SERIAL NUMBER: 20243300770

SOILS LIST		DEPTH TO SEASONALLY HIGH WATER TABLE		DEPTH TO BEDROCK		FREQUENCY OF FLOODING		HYDROLOGIC SOIL GROUP	HYDRIC SOIL RATING
SYMBOL	DESCRIPTION	6" - 36"	40" - 60"	6" - 36"	40" - 60"	NONE	NONE	C/D	NO
LHA	0% TO 3% SLOPES	6" - 36"	40" - 60"	NONE	NONE	C/D	NO		
LHB	3% TO 8% SLOPES	6" - 36"	40" - 60"	NONE	NONE	C/D	NO		



GENERAL NOTES:

- IT SHALL BE THE SOLE RESPONSIBILITY OF THE PROPERTY OWNER TO MAINTAIN THE POST CONSTRUCTION STORMWATER MANAGEMENT FACILITIES.
- STORMWATER MANAGEMENT DESIGN:
REFER TO "POST-CONSTRUCTION STORMWATER MANAGEMENT REPORT FOR PROPOSED MUNICIPAL COMPLEX," PREPARED BY CHESTER VALLEY ENGINEERS.
- EROSION AND SEDIMENTATION CONTROL:
REFER TO "EROSION AND SEDIMENTATION CONTROL PLAN", PREPARED BY CHESTER VALLEY ENGINEERS.
- MAINTENANCE NOTES:
 - THE BMPs LISTED BELOW WILL BE OWNED AND MAINTAINED BY THE PROPERTY OWNER.
 - BIORETENTION AREAS
 - STORM SEWER AND ASSOCIATED STRUCTURES
 - THE PARTY RESPONSIBLE FOR THE LONG TERM OPERATIONS AND MAINTENANCE OF STORMWATER MANAGEMENT FACILITIES SHALL MAKE RECORDS OF THE INSTALLATION AND ALL MAINTENANCE AND REPAIRS, AND SHALL RETAIN THE RECORDS FOR AT LEAST TEN (10) YEARS. THESE RECORDS SHALL BE SUBMITTED TO THE TOWNSHIP AS ESTABLISHED BY THE OPERATION AND MAINTENANCE PLAN OR IF OTHERWISE REQUIRED BY THE TOWNSHIP
- THE POST CONSTRUCTION STORMWATER MANAGEMENT PLAN HAS BEEN DESIGNED TO MEET THE FOLLOWING GOALS AND GUIDELINES:
 - PRESERVE THE INTEGRITY OF STREAM CHANNELS AND MAINTAIN AND PROTECT THE PHYSICAL, BIOLOGICAL AND CHEMICAL QUALITIES OF RECEIVING STREAMS THROUGH THE IMPLEMENTATION OF WATER QUALITY BMPs TO TREAT THE RUNOFF PRODUCED BY THE PROPOSED DEVELOPMENT BEFORE DISCHARGING FROM THE SITE.
 - PREVENT AN INCREASE IN THE RATE OF STORMWATER RUNOFF AT THE DISCHARGE POINTS.
 - MINIMIZE ANY INCREASE IN STORMWATER RUNOFF VOLUME.
 - MINIMIZE IMPERVIOUS AREAS TO ONLY THOSE WHICH ARE NECESSARY FOR THE SITE TO FUNCTION AS INTENDED.
 - MAXIMIZE THE PROTECTION OF EXISTING DRAINAGE FEATURES AND EXISTING VEGETATION.
 - MINIMIZE LAND CLEARING AND GRADING.
 - MINIMIZE SOIL COMPACTION.
 - UTILIZE OTHER STRUCTURAL OR NONSTRUCTURAL BMPs TO PREVENT OR MINIMIZE CHANGES IN STORMWATER RUNOFF RESULTING FROM THE CHANGE IN IMPERVIOUS AREA.
- THE RECEIVING WATERCOURSE FOR THIS PROJECT IS AN UNNAMED TRIBUTARY OF MINISTER CREEK (TSF-MF).
- THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1 ET SEQ., AND 287.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP, OR DISCHARGE ANY BUILDING MATERIAL OR WASTES AT THE SITE. CONSTRUCTION WASTES MUST BE RECYCLED TO THE EXTENT PRACTICABLE, AND DISPOSAL METHODS MUST COMPLY WITH FEDERAL, STATE, AND LOCAL REQUIREMENTS.
- THE PERMITTEE SHALL PROVIDE ENGINEERING CONSTRUCTION OVERSIGHT FOR THE PROPOSED STORMWATER BMPs. A LICENSED PROFESSIONAL ENGINEER KNOWLEDGEABLE IN THE DESIGN AND CONSTRUCTION OF STORMWATER BMPs, PREFERABLY THE DESIGN ENGINEER, SHALL CONDUCT THE OVERSIGHT.
- AS-BUILT PLANS OF THE STORMWATER BMPs SHALL BE PROVIDED WITHIN SIX MONTHS FOLLOWING THE COMPLETION OF EACH PHASE. THE AS-BUILT PLANS SHALL BE SIGNED AND SEALED BY A PA REGISTERED PROFESSIONAL ENGINEER.
- A NOTICE OF TERMINATION (NOT) WILL BE REQUIRED TO BE SUBMITTED FOLLOWING APPROVAL OF THE FINAL AS-BUILT PLANS. PRIOR TO ACCEPTING THE NOT, THE DEPARTMENT AND/OR CONSERVATION DISTRICT STAFF WILL PERFORM A FINAL INSPECTION TO ENSURE SITE STABILIZATION AND VERIFY ADEQUATE INSTALLATION AND FUNCTION OF STORMWATER BMPs.
- PCSM REPORTING AND RECORDKEEPING. THE PCSM PLAN, INSPECTION REPORTS AND MONITORING RECORDS SHALL BE AVAILABLE FOR REVIEW AND INSPECTION BY THE DEPARTMENT OR THE CONSERVATION DISTRICT.
- FINAL CERTIFICATION. THE PERMITTEE SHALL INCLUDE WITH THE NOTICE OF TERMINATION "RECORD DRAWINGS" WITH A FINAL CERTIFICATION STATEMENT FROM A LICENSED PROFESSIONAL, WHICH READS AS FOLLOWS:

"I (NAME) DO HEREBY CERTIFY PURSUANT TO THE PENALTIES OF 18 PA.C.S.A. § 4904 TO THE BEST OF MY KNOWLEDGE, INFORMATION AND RELIEF, THAT THE ACCOMPANYING RECORD DRAWINGS ACCURATELY REFLECT THE AS-BUILT CONDITIONS, ARE TRUE AND CORRECT, AND ARE IN CONFORMANCE WITH CHAPTER 102 OF THE RULES AND REGULATIONS OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION AND THAT THE PROJECT SITE WAS CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PCSM PLAN, ALL APPROVED PLAN CHANGES AND ACCEPTED CONSTRUCTION PRACTICES."

- THE PERMITTEE SHALL RETAIN A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED PCSM PLAN.
- THE PERMITTEE SHALL PROVIDE A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED PCSM PLAN TO THE PERSON IDENTIFIED IN THIS SECTION AS BEING RESPONSIBLE FOR THE LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPs.

- UPON PERMANENT STABILIZATION OF THE EARTH DISTURBANCE ACTIVITY UNDER § 102.22(A)(2) (RELATING TO PERMANENT STABILIZATION), AND INSTALLATION OF BMPs IN ACCORDANCE WITH AN APPROVED PLAN PREPARED AND IMPLEMENTED IN ACCORDANCE WITH §§ 102.4 AND 102.8 (RELATING TO EROSION AND SEDIMENT CONTROL REQUIREMENTS, AND PCSM REQUIREMENTS), THE PERMITTEE OR CO-PERMITTEE SHALL SUBMIT A NOTICE OF TERMINATION TO THE DEPARTMENT OR CONSERVATION DISTRICT.

- THE NOTICE OF TERMINATION MUST INCLUDE:
- THE FACILITY NAME, ADDRESS AND LOCATION.
 - THE OPERATOR NAME AND ADDRESS.
 - THE PERMIT NUMBER.
 - THE REASON FOR PERMIT TERMINATION.
 - IDENTIFICATION OF THE PERSONS WHO HAVE AGREED TO AND WILL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPs IN ACCORDANCE WITH §102.8(M) AND PROOF OF COMPLIANCE WITH § 102.8(M)(2).

PRIOR TO ACCEPTING THE NOT, THE DEPARTMENT AND/OR CONSERVATION DISTRICT STAFF WILL PERFORM A FINAL INSPECTION AND APPROVE OR DENY THE NOTICE OF TERMINATION.

GENERAL CONSERVATION NOTES AND SPECIFICATIONS

INTENT OF CONSERVATION PROGRAM: THE INTENT OF THIS PROGRAM IS TO PREVENT ACCELERATED EROSION OF THE EXPOSED SITE SOILS DURING THE CONSTRUCTION AND PERMANENT LIFE PERIODS OF THE DEVELOPMENT. THE PROGRAM REQUIRES RETENTION OF ALL SEDIMENTS ON THE CONSTRUCTION SITE TO MINIMIZE THE IMPACT OF DEVELOPMENT ON EXISTING STREAMS AND ADJACENT PROPERTY OWNERS. THESE OBJECTIVES WILL BE ACHIEVED BY MINIMIZING THE EXPOSURE TIME OF POTENTIALLY ERODIBLE SOILS TO RUNOFF AND INSTALLATION OF THE TEMPORARY CONSTRUCTION. THE INTENT OF THIS PROGRAM SHOULD BE UNDERSTOOD AND IMPLEMENTED THROUGHOUT THE ENTIRE DEVELOPMENT. THE VARIOUS CONSTRUCTION TRADES SHOULD BE APPRAISED OF THIS PROGRAM AND DIRECTED TO PREVENT UNDUE DISTURBANCE OF PREPARED AND PROTECTED SURFACES.

SURFACE STABILIZATION CRITERIA: ALL DISTURBED SOIL SURFACES, INCLUDING SOIL STOCKPILES, ARE SUBJECT TO EROSION AND SHALL BE STABILIZED EITHER TEMPORARILY OR PERMANENTLY. IMMEDIATELY DURING NON-GERMINATION PERIODS, MULCH MUST BE APPLIED AT THE RECOMMENDED RATES. CRUSHED STONE ON PAVEMENT SUBGRADES IS CONSIDERED ADEQUATE PROTECTION. ALL DISTURBED ZONES AND VEGETATED REGIONS SHALL BE STABILIZED. PREFERABLY WITH A PERMANENT TREATMENT.

DISPOSAL AND RECYCLING

THE OWNER IS RESPONSIBLE FOR THE PROPER DISPOSAL OF ALL WASTES ONSITE. GARBAGE SHALL BE COLLECTED ON-SITE UNTIL RETRIEVED BY AN APPROVED DISPOSAL OR RECYCLING COMPANY, CONTRACTOR SHALL NOT INCINERATE EXCESS MATERIALS.

SILT REMOVED FROM POST CONSTRUCTION STORMWATER MANAGEMENT FACILITIES SHALL BE DISPOSED OF ON-SITE IN LANDSCAPED AREAS LOCATED OUTSIDE OF VEGETATED RAIN GARDEN AREAS. AREAS OF SEDIMENT DISPOSAL SHALL BE CONSIDERED CRITICAL VEGETATION AREAS (CVA).

LIKELY WASTE TO BE GENERATED DURING MAINTENANCE OF THE POST-CONSTRUCTION BMPs ARE:

- ACCUMULATED SEDIMENT IN THE BIORETENTION AREAS AND STORM SYSTEM.
- ACCUMULATED GARBAGE AND DEBRIS IN THE BIORETENTION AREAS AND STORM SEWER.

CRITICAL STAGES OF CONSTRUCTION

THE PROFESSIONAL DESIGN ENGINEER, GEOTECHNICAL ENGINEER, OR SOILS PROFESSIONAL MUST BE PRESENT ON-SITE FOR THE ENTIRE INSTALLATION AND INSPECTION OF THE STORMWATER BMPs. THE SPECIFIC CRITICAL STAGES OF CONSTRUCTION FOR EACH BMP ARE:

- FOR BIORETENTION AREAS: EXCAVATION OF BIORETENTION AREA, PREPARATION OF THE SUBGRADE, PLACEMENT OF THE GEOTEXTILE FABRIC, INSTALLATION OF THE UNDERDRAIN, INSTALLATION OF AMENDED SOILS, CONSTRUCTION OF THE BIORETENTION BERM, AND INSTALLATION OF THE OUTLET STRUCTURE.
- FOR ALL WATER QUALITY INLETS: VERIFY INSTALLATION PER MANUFACTURER'S RECOMMENDATIONS.

CRITICAL VEGETATION AREAS (CVA)

CRITICAL VEGETATION AREAS ARE TO BE GRADED, HYDROSEEDDED, AND MULCHED WITHIN 10 DAYS OF THE BEGINNING OF EXCAVATION. IN GENERAL, CRITICAL VEGETATION AREAS ARE DEFINED AS CUT SLOPES STEEPER THAN 3:1, ALL FILL SLOPES STEEPER THAN 4:1, IN ALL DRAINAGE SWALES, BASIN AND RAIN GARDEN AREAS.

POST CONSTRUCTION STORMWATER MANAGEMENT REPORTING AND RECORD KEEPING

A WRITTEN REPORT DOCUMENTING EACH INSPECTION AND ALL BMP REPAIRS AND MAINTENANCE ACTIVITIES MUST BE PROVIDED AS PART OF THE LONG-TERM OPERATION AND MAINTENANCE PROGRAM.

THE POST CONSTRUCTION STORMWATER MANAGEMENT PLAN, INSPECTION REPORTS, AND MONITORING RECORDS SHALL BE AVAILABLE FOR REVIEW AND INSPECTION BY THE DEPARTMENT OR THE CONSERVATION DISTRICT.

MONTGOMERY COUNTY BLOCK 60-3 UNIT 12

BIORETENTION AREAS

- BMP #1 & BMP #2, AS INDICATED ON PCSM PLAN

PLANTING NOTES AND SPECIFICATIONS:

- DEVELOP A PLANTING MEDIUM IN ACCORDANCE WITH THE APPROVED DETAIL SHOWN ON POST-CONSTRUCTION STORMWATER MANAGEMENT DETAIL SHEET.

INSPECTION REQUIREMENTS

- ALL STORMWATER MANAGEMENT SYSTEMS SHALL BE INSPECTED ANNUALLY FOR THE FIRST FIVE (5) YEARS AND ONCE EVERY THREE (3) YEARS THEREAFTER, FOR ACCUMULATION OF SEDIMENT, TRASH AND DEBRIS, DAMAGE TO OUTLET STRUCTURES, EROSION, SIGNS OF CONTAMINATION OR SPILLS AND BERM STABILITY.

MAINTENANCE/REPAIR INSTRUCTIONS

- THE SUGGESTED ITEMS IN THIS SECTION INCLUDE, BUT ARE NOT LIMITED TO THE THOSE LISTED BELOW:
 - ACCUMULATED SEDIMENT SHALL BE RESPREAD ON-SITE AS DESCRIBED IN THE DISPOSAL AND RECYCLING SECTION OF THIS PLAN SHEET.
 - ANY DISCOVERED TRASH OR DEBRIS SHALL BE REMOVED IMMEDIATELY.
 - REPAIR OR REPLACE OUTLET STRUCTURE AS NEEDED.
 - STABILIZE ERODED AREAS IN ACCORDANCE WITH APPROVED E&S SEEDING AND MULCHING NOTES.
 - IN THE EVENT OF CONTAMINATION OR SPILL, IMMEDIATELY CONTACT AN ENVIRONMENTAL PROFESSIONAL QUALIFIED TO IDENTIFY AND EXECUTE THE REQUIRED CLEANUP METHODS THAT ADHERE TO LOCAL, STATE AND FEDERAL REGULATIONS.
 - IMMEDIATELY AFTER DISCOVERY OF BERM INSTABILITY, CONTACT A GEOTECHNICAL ENGINEER AND SITE CONTRACTOR TO DETERMINE AND EXECUTE METHODS TO REMEDY THE UNSTABLE BERM.

GENERAL MAINTENANCE NOTES:

- INSPECT BMP FOR SEDIMENT BUILDUP, EROSION, VEGETATIVE CONDITIONS, ETC.
- WHILE VEGETATION IS BEING ESTABLISHED, PRUNING AND WEEDING MY BE REQUIRED.
- RE-SPREAD MULCH WHEN EROSION IS EVIDENT AND REPLENISH AS NEEDED. REPLENISH MULCH ONCE EVERY 2 TO 3 YEARS.
- INSPECT AND CORRECT EROSION PROBLEMS, DAMAGE TO VEGETATION, AND SEDIMENT AND DEBRIS ACCUMULATION (ADDRESS WHEN > 3 INCHES AT ANY SPOT OR COVERING VEGETATION).
- WATER AS NEEDED DURING PERIODS OF EXTENDED DROUGHT.
- INSPECT VEGETATION ON SIDE SLOPES FOR EROSION AND FORMATION OF RILLS OR GULLIES, CORRECT AS NEEDED.
- INSPECT FOR POOLS OF STANDING WATER; DEWATER AND DISCHARGE TO AN APPROVED LOCATION AND RESTORE TO DESIGN GRADE.
- TRIM VEGETATION TO ENSURE SAFETY, AESTHETICS, PROPER SWALE OPERATION, OR TO SUPPRESS WEEDS AND INVASIVE VEGETATION; DISPOSE OF CUTTINGS IN A LOCAL COMPOSTING FACILITY, MOW ONLY WHEN SWALE IS DRY TO AVOID RUTTING.
- INSPECT FOR LITTER; REMOVE PRIOR TO TRIMMING.
- INSPECT FOR UNIFORMITY IN CROSS-SECTION, CORRECT AS NEEDED.
- INSPECT INFLOW POINTS (CURB CUTS, INLETS, PIPES, ETC.) AND OUTLET FOR SIGNS OF EROSION OR BLOCKAGE, CORRECT AS NEEDED.
- CONTACT DESIGN ENGINEER IMMEDIATELY AFTER DISCOVERY OF SINKHOLE OCCURRENCE, SINKHOLE SHOULD BE PROMPTLY AND PROPERLY REPAIRED.
- THE VEGETATION (FOR BMP CONTRIBUTING DRAINAGE AREA) SHOULD BE MAINTAINED IN GOOD CONDITION, AND ANY BARE SPOTS REVEGETATED.
- CARE SHOULD BE TAKEN TO AVOID EXCESSIVE COMPACTION BY MOWERS. MOW ONLY AS APPROPRIATE FOR VEGETATIVE SPECIES.
- INSPECT BMP #2 AT LEAST TWO TIMES PER YEAR AFTER RUNOFF EVENTS GREATER THAN 0.8 INCH AND MAKE SURE THAT RUNOFF DRAINS DOWN WITHIN THE DESIGN PARAMETERS (THE LICENSED PROFESSIONAL ENGINEER SHOULD CLEARLY IDENTIFY WHAT THESE PARAMETERS ARE).
- ALL CATCH BASINS AND INLETS SHOULD BE INSPECTED AND CLEANED AT LEAST TWO (2) TIMES PER YEAR.
- AS NEEDED, REMOVE ACCUMULATED SEDIMENT AS REQUIRED TO MAINTAIN INFILTRATION THROUGH THE MRC STONE MEDIA AND TO MAINTAIN WATER QUALITY FUNCTIONALITY. RESTORE ORIGINAL CROSS SECTION. PROPERLY DISPOSE OF SEDIMENT.
- ALL MRC BMP COMPONENTS SHOULD BE MAINTAINED AS INDICATED IN THE STORMWATER BMP MANUAL.
- AT LEAST TWO TIMES PER YEAR, OR MORE IF HISTORICAL MAINTENANCE INDICATE IT IS NECESSARY, INSPECT FOR ACCUMULATION OF SEDIMENT, DAMAGE TO OUTLET CONTROL STRUCTURES, EROSION, SIGNS OF WATER CONTAMINATIONS/SPILLS, AND INSTABILITY.
- LEAF LITTER NEEDS TO BE REMOVED ANNUALLY.

WINTER MAINTENANCE NOTES:

- BMP SHOULD BE INSPECTED IMMEDIATELY AFTER THE SPRING MELT, REMOVE RESIDUALS AND REPLACE DAMAGED VEGETATION.

- IF ROADSIDE OR PARKING LOT RUNOFF IS DIRECTED TO THE BMP, MULCHING AND/OR SOIL AERATION/MANIPULATION MAY BE REQUIRED IN THE SPRING TO RESTORE SOIL STRUCTURE AND MOISTURE CAPACITY AND TO REDUCE THE IMPACTS OF DEICING AGENTS.

- USE NONTOTOXIC, ORGANIC DEICING AGENTS, APPLIED EITHER AS BLENDED, MAGNESIUM CHLORIDE-BASED LIQUID PRODUCTS OR AS PRETREATED SALT.

- USE SALT-TOLERANT VEGETATION.

- CLOSE MOW OR TRIM PERENNIAL MATERIAL TO ALLOW PROPER GERMINATION AND TO CONTROL INVASIVE SPECIES (TO BE DONE ONCE IN LATE FALL, WINTER OR EARLY SPRING).

- REPLENISH MULCH IN AREAS WHERE EROSION IS EVIDENT. REPLENISH MULCH IN ENTIRE INFILTRATION AREA AT LEAST EVERY 2 TO 3 YEARS.

CONSTRUCTION SEQUENCING

- INSTALL FILTER SOCK AND/OR OTHER APPROPRIATE TEMPORARY EROSION CONTROL DEVICES TO PREVENT SEDIMENT FROM LEAVING OR ENTERING THE PRACTICE DURING CONSTRUCTION.
- PRIOR TO CONSTRUCTION, BIORETENTION AREA/BIO-FILTRATION AREAS SHALL BE MARKED OFF IN THE FIELD. THE AREAS SHALL BE DELINEATED WITH CONSTRUCTION FENCING OR TAPE IN SUCH A MANNER AS TO PREVENT THE PARKING OR REPEATED MOVEMENT OF CONSTRUCTION TRAFFIC.
- ALL DOWN-GRADIENT PERIMETER SEDIMENT CONTROL BMPs MUST BE IN PLACE BEFORE ANY UP GRADIENT LAND DISTURBING ACTIVITY BEGINS.
- PERFORM CONTINUOUS INSPECTIONS OF EROSION CONTROL PRACTICES.
- INSTALL UTILITIES (WATER, SANITARY SEWER, ELECTRIC, PHONE, FIBER OPTIC, ETC) PRIOR TO SETTING FINAL GRADE OF BIORETENTION DEVICE.
- ROUGH GRADE THE SITE. IF BIORETENTION AREAS ARE BEING USED AS TEMPORARY SEDIMENT BASINS LEAVE A MINIMUM OF 1 FOOT OF COVER OVER THE PRACTICE TO PROTECT THE UNDERLYING SOILS FROM CLOGGING.
- PERFORM ALL OTHER SITE IMPROVEMENTS.
- TRIM AND MULCH ALL AREAS AFTER DISTURBANCE.
- CONSTRUCT BIORETENTION DEVICE UPON STABILIZATION OF CONTRIBUTING DRAINAGE AREA.
- CONSTRUCT CURB CUTS OR OTHER INFLOW BUT PROVIDE PROTECTION TO PROHIBIT SEDIMENT LADEN WATER FROM ENTERING THE BMP.
- CRITICAL STAGE OF CONSTRUCTION: CONTACT ENGINEER TO VERIFY INSTALLATION OF BIORETENTION AREA.
- IMPLEMENT TEMPORARY AND PERMANENT EROSION CONTROL PRACTICES.
- PLANT AND MULCH BIORETENTION DEVICE.
- REMOVE TEMPORARY EROSION CONTROL DEVICES AFTER THE CONTRIBUTING DRAINAGE AREA IS ADEQUATELY VEGETATED.

BMP FAILURE NOTES (PER PROTOCOL 2 OF THE BMP MANUAL)

THE TERM "FAILURE" FOR THE PROPOSED BIORETENTION AREAS SHALL BE DEFINED AS:

- THE LOSS OF FUNCTIONALITY OF THE PROPOSED OUTLET STRUCTURE, DISCHARGE PIPE, UNDERDRAIN SYSTEM OR ANY OTHER DRAINAGE STRUCTURE/PIPE WITHIN THE BMP.
- THE LOSS OF STRUCTURAL INTEGRITY OF THE PROPOSED BERM
- THE INABILITY OF THE BIORETENTION AREA TO SUPPORT SURFACE VEGETATION DUE TO TOO MUCH OR TOO LITTLE WATER
- EXCESSIVE EROSION OR ACCUMULATION OF SEDIMENT OR DEBRIS
- STANDING WATER IS OBSERVED IN THE BIORETENTION AREA AFTER 72-HOURS.

THE PERMITTEE SHALL MAKE THE NECESSARY REPAIRS TO THE OUTLET STRUCTURE, DISCHARGE PIPING, UNDERDRAIN SYSTEM, OTHER DRAINAGE STRUCTURES/PIPES WITHIN THE BMP, SURFACE VEGETATION, AND BERM AS NEEDED. REMOVE SEDIMENT OR DEBRIS THAT HAS ACCUMULATED IN THE BMP BOTTOM AND STABILIZE EROSION USING PERMANENT STABILIZATION TECHNIQUES INDICATED ON THE EROSION AND SEDIMENT POLLUTION CONTROL PLAN. DEWATER BIORETENTION AREAS.

THE TERM "FAILURE" FOR THE PROPOSED WATER QUALITY INLETS (FILTER INSERTS) SHALL BE DEFINED AS:

- DISCOVER EVIDENCE OF DAMAGED FILTER MEDIA
- DISCOVER EVIDENCE OF THE FILTER MEDIA'S INABILITY TO SUPPORT ACCUMULATED SEDIMENT OR DEBRIS.

THE PERMITTEE SHALL REPAIR BMP FAILURE BY REPLACING THE FILTER MEDIA IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS.

THERMAL IMPACT

THERE ARE SEVERAL PROPOSED/IN PLACE MEASURES INTENDED TO TREAT RUNOFF FOR THERMAL IMPACTS. FIRSTLY, THE PROPOSED LANDSCAPING TREES WITHIN AND BORDERING THE NEW BUILDING AND SIDEWALK AREAS WILL SHADE THE ADJACENT IMPERVIOUS SURFACES WHICH WILL KEEP THE AREAS COOL. SECONDLY, THE STORMWATER RUNOFF COLLECTED BY THE STORM SEWER SYSTEM WILL BE COOLED BY THE LOWER UNDERGROUND TEMPERATURE AS THE RUNOFF FLOWS THROUGH THE SYSTEM. THIRDLY, THE WATER DETAINED IN THE BIORETENTION AMENDED SOILS WILL BE COOLED AS IT IS SLOWLY RELEASED AS A RESULT OF THE LOWER UNDERGROUND TEMPERATURE. AS THE POST DEVELOPMENT FLOWS ARE LOWER THAN THE PRE-DEVELOPMENT FLOWS THE REDUCED RATE MEANS THE RUNOFF WILL HAVE MORE TIME TO COOL IN THE PROPOSED BMPs. THE COOLING INFLUENCES OF THE ONSITE BMPs WILL NEUTRALIZE/REMOVE THE HEAT ENERGY ABSORBED BY THE PROJECT SITE RUNOFF PRIOR TO DISCHARGE INTO THE RECEIVING WATERCOURSE.

STORM SEWER

INSPECTION REQUIREMENTS:

- ALL DRAINAGE COLLECTION STRUCTURES SHALL BE INSPECTED ANNUALLY FOR THE FIRST FIVE (5) YEARS AND ONCE EVERY THREE (3) YEARS THEREAFTER, FOR TRASH, DEBRIS OR EVIDENCE OF PIPE LEAKAGE OR SAGGING; REMOVE TRASH OR DEBRIS IMMEDIATELY, IMMEDIATELY REPAIR OR REPLACE LEAKING/SAGGING DRAINAGE FEATURES.


GENERAL MAINTENANCE NOTES:

- ACCESS CAN BE GAINED TO EACH COLLECTION STRUCTURE THROUGH THE REMOVABLE INLET GRATE OR MANHOLE LID. STEEL OR OTHER APPROVED RINGS HAVE BEEN INSTALLED ON THE INSIDE OF EACH STRUCTURE OVER FOUR FEET DEEP FOR ANY NECESSARY ENTRY. GRATES AND LIDS SHALL BE REPLACED SECURELY IMMEDIATELY AFTER MAINTENANCE.
- CONTACT DESIGN ENGINEER IMMEDIATELY AFTER DISCOVERY OF SINKHOLE OCCURRENCE, SINKHOLE SHOULD BE PROMPTLY AND PROPERLY REPAIRED.
- IF SEDIMENT/TRASH/DEBRIS IS FOUND IN THE CONVEYANCE SYSTEM, THE SYSTEM SHALL BE JETTED AND VACUUMED TO REMOVE ALL SEDIMENT/TRASH/DEBRIS AND DISPOSED OF APPROPRIATELY.
- REFER TO WATER QUALITY INLET MAINTENANCE GUIDELINES FOR ADDITIONAL DETAIL IN CLEANING OF THOSE STRUCTURES WITH WATER QUALITY APPARATUS INSTALLED.


SITE RESTORATION O&M REQUIREMENTS

ESTABLISH AND MAINTAIN VEGETATIVE COVER IN ACCORDANCE WITH PERMANENT SEEDING SPECIFICATIONS.

PERFORM ROUTINE INSPECTIONS AND CORRECT EROSION PROBLEMS, IF ENCOUNTERED.




BMP #1 BIORETENTION AREA
CROSS-SECTION
N.T.S.




BMP #2 M.R. BIORETENTION AREA
CROSS-SECTION
N.T.S.

TYPICAL BIORETENTION AREA NOTES:


- CONTRACTOR SHALL TREAT COMPACTED SUBGRADE SOILS AS SPECIFIED IN THE SOIL AMENDMENT SPECIFICATION PRIOR TO PLACEMENT OF THE UNDERDRAIN AND SOIL AMENDMENT SHOWN ON SHEET 9F.
- IN THE EVENT THAT SEDIMENT IS INTRODUCED INTO THE BMP DURING OR IMMEDIATELY FOLLOWING EXCAVATION, THIS MATERIAL SHALL BE REMOVED FROM THE PRACTICE PRIOR TO CONTINO CONSTRUCTION.
- GRADING OF AREAS SHALL BE ACCOMPLISHED USING LOW-COMPACTION EARTH-MOVING EQUIPMENT TO PREVENT COMPACTION OF UNDERLYING SOILS.
- ALL SUB MATERIALS BELOW THE SPECIFIED BIORETENTION DEPTH (ELEVATION) SHALL BE UNDISTURBED, UNLESS OTHERWISE NOTED.
- CONTRACTOR SHOULD PROVIDE A ONE-YEAR 100% CARE AND REPLACEMENT WARRANTY FOR ALL PLANTING BEGINNING AFTER INSTALLATION AND INSPECTION OF ALL PLANTS.
- REFER TO OPERATIONS AND MAINTENANCE PLAN FOR POST-DEVELOPMENT CONSTRUCTION SEQUENCING AND MAINTENANCE SPECIFICATIONS.
- ALL CONNECTIONS TO INLET/OUTLET STRUCTURES AND CLEANOUT PIPES SHALL HAVE WATERTIGHT SEALS.



OS#208 -- DETAIL
PLAN VIEW: N.T.S.











OS#208 -- DETAIL
SECTION A-A: N.T.S.



OS#208 -- DETAIL
SECTION B-B: N.T.S.

POST-CONSTRUCTION STORMWATER MANAGEMENT NOTES/DETAILS




NO.	DATE	REVISION			
CONSTRUCTION PLANS					
FOR					
UPPER POTTS GROVE MUNICIPAL COMPLEX					
UPPER POTTS GROVE TOWNSHIP - MONTGOMERY COUNTY - PENNSYLVANIA					
 112 Moores Road, Suite 200, Malvern, PA 19355 610-644-4623 www.chestervalleyn.com				PROJECT NO.	
				22096-2000	
				F.B.	
SCALE	DATE	DRAWN BY	CHECKED BY	DRAWING	
As Noted	03/31/2025	HL	MJ		



CHANNEL NO.	BOTTOM WIDTH B (FT)	SLOPE (%)	DEPTH D (FT)	TOP WIDTH W (FT)	Z1 (FT)	Z2 (FT)
1	6	2.0	1.5	15.00	3	3

NOTES:




1. CHANNEL DIMENSIONS SHALL BE CONSTANTLY MAINTAINED. CHANNEL SHALL BE CLEANED WHENEVER TOTAL CHANNEL DEPTH IS REDUCED BY 25% AT ANY LOCATION. SEDIMENT DEPOSITS SHALL BE REMOVED WITHIN 24 HOURS OF DISCOVERY OR AS SOON AS SOIL CONDITIONS PERMIT ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE. DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF DISCOVERY.
2. NO MORE THAN ONE THIRD OF THE SHOOT (GRASS LEAF) SHALL BE REMOVED IN ANY MOWING. GRASS HEIGHT SHALL BE MAINTAINED BETWEEN 2 AND 3 INCHES UNLESS OTHERWISE SPECIFIED. EXCESS VEGETATION SHALL BE REMOVED FROM PERMANENT CHANNELS TO ENSURE SUFFICIENT CHANNEL CAPACITY.



PIPE DIAMETER	PART NO.	A, ±1 (25)	B MAX	H, ±1 (25)	L, ±1/2 (13)	W, ±2 (50)
10 (250)	1015 NP	3.5 (95)	10 (254)	6.5 (168)	28 (711)	34.5 (876)
12, 15 (300, 375)	1215 NP	6.5 (165)	10 (254)	6.5 (165)	25 (635)	29 (736)

FLARED END SECTION DETAIL

N.T.S.



SUITABLE MATERIAL

SUITABLE MATERIAL - CLEAN SOIL CONTAINING NOT MORE THAN 30% SILT/CLAY PARTICLES FINER THAN THE NO. 200 SIEVE (BY WEIGHT), AS DETERMINED BY SOIL LABORATORY TESTING AND METHOD OF ASTM D-2487, WHICH IS CAPABLE OF BEING COMPACTED TO THE REQUIRED DENSITY AT THE PROPER MOISTURE CONTENT, AND WHICH IS FREE OF TOPSOIL, ROOTS, TRASH, DEBRIS, FROZEN MATTER, EXCESS MOISTURE (WATER CONTENT AT COMPACTION MUST BE WITHIN 2% OF OPTIMUM) AND OTHER DELETERIOUS INCLUSIONS. THE LIMITS OF ROCK AS SUITABLE MATERIAL SHALL NOT EXCEED 4 INCHES (4") IN SIZE. THE REMAINDER OF ROCK SHALL BE CLASSED AS UNSUITABLE. THE PERCENTAGE OF ROCK IN SUITABLE MATERIAL SHALL BE LIMITED TO THAT WHICH WILL PERMIT COMPACTION OF FILL TO THE REQUIRED DENSITY. SUITABLE FILL SHALL BE APPROVED BY THE ON-SITE GEOTECHNICAL ENGINEER AND TOWNSHIP PRIOR TO PLACEMENT AND COMPACTION.

SUITABLE FILL

1. PLACEMENT OF BACKFILL MATERIAL IN 8 INCH LAYERS (LIFTS) SHALL BE PERMITTED WHEN USING VIBRATORY COMPACTION EQUIPMENT.

PIPE TYPE	BEDDING	INITIAL BACKFILL	BACKFILL TO SUBGRADE	
			BENEATH BITUMINOUS PAVEMENT (EXISTING TO REMAIN OR PROPOSED), CONCRETE SIDEWALK OR PAVERS	BENEATH OTHER AREA
ANY PIPE WITHIN PUBLIC ROW	AASHTO #57 COARSE AGGREGATE	PA DOT NO. 2A COARSE AGGR.	PA DOT NO. 2A COARSE AGGREGATE	PA DOT NO. 2A COARSE AGGR.
STORM (METAL)	AASHTO #57 COARSE AGGREGATE	PA DOT NO. 2A COARSE AGGR.	PA DOT NO. 2A COARSE AGGREGATE	SUITABLE MATERIAL
STORM (RCP)	AASHTO #57 COARSE AGGREGATE	PA DOT NO. 2A COARSE AGGR.	PA DOT NO. 2A COARSE AGGREGATE	PA DOT NO. 2A COARSE AGGR.
STORM (OTHER)	AASHTO #57 COARSE AGGR.	PA DOT NO. 2A COARSE AGGR.	PA DOT NO. 2A COARSE AGGREGATE	SUITABLE MATERIAL
SANITARY	AASHTO #57 COARSE AGGREGATE	PA DOT NO. 2A COARSE AGGR.	SUITABLE MATERIAL	SUITABLE MATERIAL
WATER (PIPE)	NONE REQUIRED	PA DOT NO. 2A COARSE AGGR.	SUITABLE MATERIAL	SUITABLE MATERIAL
WATER (TUBING)	CEMENT CONCRETE SAND, TYPE A, PA DOT, PUB. 408, § 703.1	CEMENT CONCRETE SAND, TYPE A, PA DOT, PUB. 408, § 703.1	SUITABLE MATERIAL	SUITABLE MATERIAL
OTHER PIPE, CONDUIT	AASHTO #57 COARSE AGGREGATE	PA DOT NO. 2A COARSE AGGR.	SUITABLE MATERIAL	SUITABLE MATERIAL

POST-CONSTRUCTION STORMWATER MANAGEMENT DETAILS

NO.	DATE	REVISION

CONSTRUCTION PLANS FOR UPPER POTTS GROVE MUNICIPAL COMPLEX



UPPER POTTS GROVE TOWNSHIP - MONTGOMERY COUNTY - PENNSYLVANIA

ChesterValley ENGINEERS, INC.

112 Moores Road, Suite 200, Malvern, PA 19355
610-644-4623
www.chestervalley.com


PROJECT NO. **22096-2000**

SCALE: As Noted DATE: 03/31/2025 DRAWN BY: HL CHECKED BY: MJ





GENERAL PHOTOMETRIC SCHEDULE	
AVERAGE FOOT-CANDLES	0.30
MAXIMUM FOOT-CANDLES	8.93
MINIMUM FOOT-CANDLES	0.00
MINIMUM TO MAXIMUM FC RATIO	0.00
MAXIMUM TO MINIMUM FC RATIO	8.93 / 0.00
AVERAGE TO MINIMUM FC RATIO	0.30 / 0.00



GENERAL LIGHTING NOTES
THIS LIGHTING PLAN DEPICTS PROPOSED SUSTAINED ILLUMINATION LEVELS CALCULATED USING DATA PROVIDED BY THE NOTED MANUFACTURERS.

- INSTALLATION NOTES:
- 1.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL EXISTING UNDERGROUND STRUCTURES AND UTILITIES, SUCH AS WATER MAINS, SANITARY AND STORM SEWERS, TELEPHONE AND ELECTRIC CONDUITS, AND GAS LINES, ETC. AND ABOVE GROUND UTILITIES WHICH MAY BE ENCOUNTERED DURING CONSTRUCTION OPERATIONS.
 - 2.) DIMENSIONS ARE APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY ALL ELEVATIONS, INVERTS, AND DIMENSIONS IN THE FIELD PRIOR TO THE COMMENCEMENT OF WORK.
 - 3.) THE PENNSYLVANIA ONE CALL NUMBER IS 1-800-242-1776. THE CONTRACTOR IS REQUIRED TO SUBMIT VERIFICATION TO THE MUNICIPALITY THAT A ONE "ONE-CALL" HAS BEEN PLACED PRIOR TO THE START OF DEMOLITION WORK.
 - 4.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS FROM THE MUNICIPALITY RELATIVE TO THE PROPOSED PROJECT.
 - 5.) THE CONTRACTOR SHALL REPAIR ALL UTILITY TRENCHING WORK LOCATED WITHIN EXISTING PAVED STREETS.
 - 6.) THE CONTRACTOR SHALL COMPLY WITH ALL CITY, STATE, AND FEDERAL REGULATIONS IN EFFECT AT THE TIME OF CONSTRUCTION.
 - 7.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRAFFIC CONTROL.
 - 8.) ALL AREAS DISTURBED AS A RESULT OF THE INSTALLATION OF LIGHTING IMPROVEMENTS SHALL BE RESTORED TO THEIR ORIGINAL CONDITION.
 - 9.) THE LIGHT LEVELS DEPICTED ON THIS PLAN WERE CALCULATED BASED ON THE LLF SHOWN IN THE LUMINAIRE SCHEDULE.
 - 10.) THE LIGHTING VALUES AND CALCULATION POINTS DEPICTED ON THIS PLAN ARE ANALYZED ON A HORIZONTAL GEOMETRIC PLANE AT GROUND LEVEL UNLESS OTHERWISE NOTED.
 - 11.) ILLUMINATION LEVELS ARE SHOWN IN FOOT-CANDLES (FC).
 - 12.) THE ELECTRICAL CONTRACTOR IS RESPONSIBLE TO ENSURE THAT SHIELDING AND OR ROTATED OPTICS ARE INSTALLED AS INDICATED ON THE PLAN IN ORDER TO ACHIEVE THE LIGHTING LEVELS THE REVIEWING AGENCY APPROVED.

LIGHTING CONTROLS AND SURGE PROTECTION: ALL NEW FIXTURES ARE TO BE EQUIPPED WITH DIMONOFF RME-XBP PHOTOCELLS AND ABLE POWER PRODUCTS RWL-S SURGE DEVICE. FIXTURES MUST BE EQUIPPED WITH ALL-MODE PROTECTION (L-N, L-G, N-G). SURGE PROTECTION INTEGRAL TO THE PHOTOCONTROL SHOULD HAVE 3 MODES OF PROTECTION: LINE-TO-NEUTRAL, LINE-TO-GROUND AND NEUTRAL-TO-GROUND. THE MINIMUM SURGE PROTECTION SPECIFICATIONS SHOULD BE 10KA IN, 25KA IMAX AND 20KV UOC.

PARKING FACILITY AND VEHICULAR AND PEDESTRIAN WAY LIGHTING (EXCEPT FOR SAFETY AND SECURITY APPLICATIONS AND ALL-NIGHT BUSINESS OPERATIONS), FOR COMMERCIAL, INDUSTRIAL AND INSTITUTIONAL USES SHALL BE AUTOMATICALLY EXTINGUISHED NO LATER THAN ONE HOUR AFTER THE CLOSE OF BUSINESS OR FACILITY OPERATION. WHEN SAFETY OR SECURITY LIGHTING IS PROPOSED FOR AFTER-HOURS ILLUMINATION, IT SHALL NOT BE IN EXCESS OF 33% OF THE NUMBER OF FIXTURES REQUIRED OR PERMITTED FOR ILLUMINATION DURING REGULAR BUSINESS HOURS, OR IN AN AMOUNT JUDGED NECESSARY BY THE TOWNSHIP ENGINEER.

SET ONE SMART PHOTOCCELL TO CONTROL ALL OTHER SITE LIGHTING FIXTURES (DIMONOFF #RME-XBP).
PLEASE CONTACT INDEPENDENCE LIGHTING FOR PRICING:
KENT LAZOR
DIRECT: 610-363-5271

LUMINAIRE SCHEDULE							
TYPE	SYMBOL	MOUNTING	MODEL	VOLTS	QUANTITY	LLD	LLF
SITE		POLE	Isotek Electronics USA LLC, ART3-C02-W-W-30K-13-BK-120	120V 1P 2W	12	0.9	0.9
ORNAMENTAL		POLE	Spryng City Electrical Manufacturing Co, CLW-LE100-2F2-30-OR3-YPLF	120V 1P 2W	4	0.9	0.9
BOLLARD		SURFACE	LIGMAN, MC-10013-W-W30	120V 1P 2W	13	0.9	0.9
FLOOD (FLAG POLE)		SURFACE	LIGMAN, OD-50161-W-W-8040	120V 1P 2W	3	0.9	0.9

LIGHTING PLAN/ NOTES

CONSTRUCTION PLANS
FOR
UPPER POTTS GROVE MUNICIPAL COMPLEX
2290 GILBERTSVILLE ROAD
UPPER POTTS GROVE TOWNSHIP - MONTGOMERY COUNTY - PENNSYLVANIA

ChesterValley
ENGINEERS, INC.

112 Moores Road, Suite 200, Malvern, PA 19355
610-644-4623
www.chestervalley.com

PROJECT NO:
22096-2000

F.B.
DRAWING

SCALE 1"=40'	DATE 03/31/2025	DRAWN BY ND	CHECKED BY AG
-----------------	--------------------	----------------	------------------


COPYRIGHT
CHESTER VALLEY ENGINEERS, INC., CIVIL ENGINEERS & SURVEYORS, EXPRESSLY RESERVES ITS OWN AND ALL OTHER PROPRIETARY RIGHTS IN THESE PLANS. ALL DRAWINGS, SPECIFICATIONS, AND COPIES THEREOF ARE AND SHALL REMAIN THE PROPERTY OF CHESTER VALLEY ENGINEERS, INC. THEY ARE TO BE USED ONLY IN RESPECT TO THE PROJECT AND ARE NOT TO BE USED ON ANY OTHER PROJECT, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE WRITTEN PERMISSION AND CONSENT OF CHESTER VALLEY ENGINEERS, INC. ANY RE-USE WITHOUT WRITTEN PERMISSION, REPRODUCTION, OR ADAPTATION BY CHESTER VALLEY ENGINEERS, INC. FOR THE SPECIFIC PURPOSE INTENDED WILL BE AT THE THIRD PARTY'S SOLE RISK AND WITHOUT LIABILITY OR LEGAL EXPOSURE TO CHESTER VALLEY ENGINEERS, INC. THE THIRD PARTY SHALL FURTHER INDEMNIFY AND HOLD HARMLESS CHESTER VALLEY ENGINEERS, INC. FROM ALL CLAIMS, DAMAGES, LOSSES, AND EXPENSES ARISING THEREFROM OR RESULTING THEREFROM.

NOTE TO USER OF THESE PLANS:
WARNING! THE INFORMATION CONTAINED ON THIS PLAN MAY NOT BE CONSISTENT WITH CONDITIONS IN THE FIELD. ANY PERSON OR ORGANIZATION USING OR RELYING ON THESE PLANS MUST CONTACT CHESTER VALLEY ENGINEERS, INC. FOR VERIFICATION OF ANY APPARENT DISCREPANCY BEFORE PROCEEDING OR RELYING UPON THESE PLANS FOR ANY PURPOSE, AND CONSTRUCTION OR INSTALLATION OF IMPROVEMENTS SHOULD OCCUR UNTIL ALL DISCREPANCIES HAVE BEEN VERIFIED WITH CHESTER VALLEY ENGINEERS. CHESTER VALLEY ENGINEERS, THEIR OFFICERS, EMPLOYEES AND REPRESENTATIVES SHALL NOT BE LIABLE FOR DAMAGES OF ANY KIND RESULTING FROM THE USER'S FAILURE TO OBTAIN CURRENT VERIFICATION AND VALIDATION OF THE INFORMATION CONTAINED ON THIS FILE TO THE USER OR ANY THIRD PARTY. THE USER ASSUMES ANY RISK OF ANY AND ALL PROPERTY OF FINANCIAL LOSS OR DAMAGES OF ANY KIND RESULTING FROM THE USE OF THIS DOCUMENT WITHOUT FIRST OBTAINING FULL VERIFICATION AND VALIDATION OF THE INFORMATION CONTAINED IN THIS FILE.


PENNSYLVANIA ACT 187 REQUIREMENTS
UNDERGROUND UTILITIES SERIAL NO. 20243300770
CHESTER VALLEY ENGINEERS, INC. DOES NOT GUARANTEE THE ACCURACY OF THE LOCATIONS FOR EXISTING SUBSURFACE UTILITY STRUCTURES SHOWN ON THE PLANS, NOR DOES CHESTER VALLEY ENGINEERS, INC. GUARANTEE THAT ALL SUBSURFACE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF ALL UNDERGROUND UTILITIES AND STRUCTURES BEFORE THE START OF WORK.
EXCAVATIONS, TRENCHING, AND SHORING
ALL EXCAVATIONS, TRENCHING, AND SHORING OPERATIONS SHALL COMPLY WITH THE REQUIREMENTS OF THE FOLLOWING UNITED STATES DEPARTMENT OF LABOR OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION PUBLICATIONS OR THE LATEST REVISIONS THEREOF:
(1) CONSTRUCTION INDUSTRY STANDARDS AND INTERPRETATIONS (OSHA 2201) SUBPART PP, PART 1025/1015 - EXCAVATIONS, TRENCHING AND SHORING;
(2) EXCAVATIONS AND TRENCHING OPERATIONS" (OSHA 2225) DATED 1989 (REVISED).

SEE SHEET 02 FOR FACILITY OWNER'S DESIGNATED OFFICE ADDRESS AND TELEPHONE NUMBER.


PENNSYLVANIA ONE CALL SYSTEM, INC.
CALL 3 WORKING DAYS BEFORE YOU DIG
1-800-242-1776
POCS SERIAL NUMBER: 20243300770




ORNAMENTAL LIGHT POLE
FOOTING DETAIL
N.T.S.




PARKING LIGHT POLE FOOTING DETAIL
N.T.S.




PARKING LIGHT POLE DETAILS
N.T.S.




ORNAMENTAL LIGHT FIXTURE DETAIL
N.T.S.




ORNAMENTAL LIGHT POLE DETAIL
N.T.S.



PARKING LIGHT FIXTURE DETAIL
N.T.S.



BOLLARD LIGHT DETAIL
N.T.S.



FLOOD LIGHT
(FLAG POLE)
DETAIL
N.T.S.

PARKING LOT LUMINAIRE SPECIFICATIONS

- LEOTEK ARIETA LUMINAIRE
- MODEL: (SEE LUMINAIRE SCHEDULE)
 - IES FULL CUTOFF
 - DISTRIBUTION TYPE (SEE LUMINAIRE SCHEDULE)
 - COLOR: BRONZE
 - QTY: 12
 - OPTIONS: DIMONOFF PHOTOCELL & RWL-S SURGE DEVICE

BOLLARD LIGHT SPECIFICATIONS

- LIGMAN - MACARON 5 BOLLARD LIGHT
- MODEL: (SEE LUMINAIRE SCHEDULE)
 - IES FULL CUTOFF
 - DISTRIBUTION TYPE (SEE LUMINAIRE SCHEDULE)
 - COLOR: BRONZE
 - QTY: 13
 - OPTIONS: DIMONOFF PHOTOCELL & RWL-S SURGE DEVICE

FLOOD LIGHT (FLAG POLE) SPECIFICATIONS


- LIGMAN - ODESSA 14 OUTDOOR FLOODLIGHT
- MODEL: (SEE LUMINAIRE SCHEDULE)
 - HIGH EFFICIENCY PMMA LENS
 - DISTRIBUTION TYPE: VN
 - COLOR: BRONZE
 - QTY: 3
 - OPTIONS: ANTI GLARE VISOR (A54431)

LIGHTING DETAILS


CONSTRUCTION PLANS FOR UPPER POTTS GROVE MUNICIPAL COMPLEX			
UPPER POTTS GROVE TOWNSHIP - MONTGOMERY COUNTY - PENNSYLVANIA			
PROJECT NO.		22096-2000	
F.B.		F.B.	
SCALE		DATE	
As Noted		03/31/2025	
DRAWN BY		CHECKED BY	
ND		AG	
DRAWING		DRAWING	






TRASH/GENERATOR ENCLOSURE WALL DETAIL (POLICE/ADMIN BUILDING)
N.T.S.



ORNAMENTAL VERTICAL PIVOT GATE DETAIL
N.T.S.




CHAINLINK VERTICAL PIVOT GATE DETAIL
N.T.S.




ACCESS CONTROL OPTIONS

CONSTRUCTION DETAILS

<h1 style="text-align: center;">CONSTRUCTION PLANS</h1> <h2 style="text-align: center;">FOR</h2> <h1 style="text-align: center;">UPPER POTTS GROVE MUNICIPAL COMPLEX</h1>				
UPPER POTTS GROVE TOWNSHIP - MONTGOMERY COUNTY - PENNSYLVANIA				
 <div style="display: inline-block; vertical-align: middle;"> <h2 style="margin: 0;">ChesterValley</h2> <p style="margin: 0;">ENGINEERS, INC.</p> <p style="margin: 0;">112 Moores Road, Suite 200, Malvern, PA 19355</p> <p style="margin: 0;">610-464-4623</p> <p style="margin: 0;">www.chesterv.com</p> </div>			PROJECT NO. <h1 style="margin: 0;">22096-200</h1>	
SCALE As Noted			DATE 03/31/2025	
DRAWN BY HL			CHECKED BY AG	
DRAWING			F.B.	



C:17 - TYPICAL OUTSIDE CURVE GEOGRID PLAN



- Drainage zone and bacfill material should be placed and compacted up to the geogrid elevation prior to geogrid being installed at the geogrid elevation. The geogrid should be placed and compacted in the correct direction.
- Measure, cut and orient the geogrid, as per the engineer's design, in the correct stretch direction.
- Place the geogrid over the Keystone units within 1-inch of the front block face, then place next course units over grid to hold grid in place. Next, tension the geogrid by pulling it back away from the wall. Place a stake through the geogrid at the back to tension the geogrid.
- Proceed with placement of additional Keystone units, then drainage zone and bacfill material. Starting at the wall and moving away from the wall, place the drainage zone and bacfill materials over the geogrid to hold the geogrid in place under tension.
- Compact the bacfill material in 8-inch lifts up to the next reinforcement elevation.
- Measure the length of the geogrid beyond current wall face + 1 inch. The geogrid length must match design length.
- Where geogrid detail overlaps naturally, place 3-inches of rock or soil between the overlapping layers.

Keystone units can be easily integrated with multiple curves within the same wall. However, convex curves require attention to details during construction. Every wall system has a minimum radius that can be built before the tails of the units come into contact with each other. This minimum radius is unique to the shape of each individual block system. In convex curves, the tightest radius will always be the top course of the wall. This means that the radius at the base course of a convex curve wall will be larger than the desired radius at the top of the wall. Care should be taken when laying out a wall horizontal location in the field given these wall batter and radius relationships.

The minimum radius of an outside curve should not be less than 5-feet. When constructing an outside curve, we recommend performing the following steps to maintain running bond configuration. It is recommended to construct the wall into the curve, maintaining a running bond pattern in the straight sections of the wall on either side of the curve. (See Figure C-15, below) Due to the unit setback, the radius change in a curved wall will cause the units to migrate off from running bond. When this occurs, it will be necessary to cut a block to maintain running bond; cut unit width shall be no smaller than 6-inches. Use exterior grade concrete adhesive to secure the partial unit. When coming out of the radius, do not stack cut units. Cutting of another block may be required to maintain a more precise running bond on the straight wall extending away from the curve.

The diagram illustrates a curved arch bridge structure. It shows a series of interlocking concrete units forming the arch. Labels with leader lines identify the components: 'Keystone Full' units are shown at the base of the arch, and 'Keystone Compac III (Both Sides of Center Units)' are shown along the upper curve of the arch.

- Full uncut units to be used for the base course and as indicated in the details.
- Verify actual cut widths for each course as wall is constructed.
- Cut units shall not be less than 6-inches in width.
- Do not stack cut units.

The diagram illustrates the construction of a 24' Unit Drainage Fill Zone. The left side shows a cross-section of a curved wall with a height of $H/2$ and a width of $H/2$. The wall is composed of 24' Unit Drainage Fill, with Unit Drainage Fill Limits (Every Course) and Additional Drainage Fill Limits (Every Course) indicated. The wall is topped with a Keystone Compac III Unit. The right side shows a perspective view of the wall, highlighting the Unit Drainage Fill (Every Course), the Keystone Compac III Unit, and the Leveling pad. A note specifies: "NOTE: Place additional drainage fill at outside wall curves to extend back from wall face each way a distance of the wall height $\frac{1}{2}$, ($H/2$)".

- Place additional drainage fill at outside wall curves to extend back from wall face each way a distance of the wall height / 2, (H/2).

Inside curves for moderately tall Keystone walls are more difficult to construct than a straight wall due to the complex geometry resulting from a battered wall face in a curve. Inside curves allow good access for compaction and the wall face units tend to support each other like an arch when the soil strain associated with the active earth pressure condition develops. As the wall gets taller, inside curves will result in the top of the wall becoming longer than the base. For wall systems to maintain the desired running bond configuration, gaps between units tend to form.

The following is an outline to a process of constructing inside curves in taller walls. See the illustrations below.


1. Units can be moved laterally to remove gapping. Eventually, cutting partial units will be necessary to get the coursing back on the running bond pattern.
2. The minimum inside radius at the base of the wall course should not be less than 6 feet.

NOTES:

- To maintain a running bond pattern, cut units as necessary to maintain and adjust bond pattern.
- Cut units are designated with shading on top of units.
- Cut units shall not be less than 6-inches in width.
- Vary cut unit location. Do not stack cut units.

Keystone Full Compac III Unit

C:13 - INSIDE CURVE GEOGRID INSTALLATION (PRIMARY ELEVATION)



Keystone Compact III Unit

Grid Strength


Additional Grid
Next Block
the Primary
Center Addi
Place Perpet

Proceed with placement of additional Keynote units and unit drainage fill. Start backfilling nearest the Keynote units and then move away from the wall placing backfill materials over the geogrid.

Compact the backfill materials in 8-inch lifts up to the next reinforcement elevation.


If the radius of the wall creates a gap between adjacent primary elevation geogrid layers (see Figure C-13, above) of greater than 20 inches, place a secondary elevation geogrid layer in the center of the gap. The secondary elevation geogrid layer should be placed on the same slope as the primary elevation geogrid, with the middle of the secondary elevation geogrid centered on the mark made in the center of the gapped geogrid below.

The use of 12-foot wide rolls may not be possible in walls with anything tighter than a gradual inside radius curve. Very tight inside radius curves may even require cutting the width of the roll to maintain the geogrid being as perpendicular as possible to the wall units.




NOTE:
THIS DETAIL SHALL BE USED WHEN INSTALLING
RAILING BEYOND WALL AREAS.

RAILING FOOTING DETAIL
N.T.S.




ADA ALUMINUM BARRIER AND HANDRAIL DETAIL
N.T.S.




NOTES:
1. ALL RAMPS, LANDINGS AND RAILINGS SHALL COMPLY WITH THE APPROPRIATE BUILDING CODE.


TYPICAL HC RAMP & RAILING DETAIL
N.T.S.



TYPICAL HANDRAIL POST DETAIL
N.T.S.




TYPICAL STEPS STRUCTURAL DETAIL
N.T.S.



NOTE:
CONTRACTOR SHALL SUBMIT DETAILED DRAWINGS (SIGNED & SEALED BY REGISTERED ENGINEER) FOR REVIEW APPROVAL PRIOR TO INSTALLING PROPOSED WALLS. DETAILS SHALL INCLUDE THE PROPOSED SLEEVE AT ANCHORING SYSTEM

KEYSTONE RETAINING WALL COMPACT III UNIT DETAIL
N.T.S.



NOTES:

1. FENCING SYSTEMS APPROVED FOR USE WITH SLEEVE-IT ARE LIMITED TO THE FOLLOWING HEIGHTS: CHAIN LINK - UP TO 8-FT, PRIVACY - UP TO 6-FT (WOODEN, PVC, METAL). POST SIZE 4"x4" MAX.
2. THIS DETAIL SHALL BE USED FOR FENCE/RAILING INSTALLED BEHIND RETAINING WALL.

FENCE SLEEVE-IT DETAIL
N.T.S.

CONSTRUCTION DETAILS

[illegible]