

CUMRU FIRE DEPARTMENT

1775 WELSH ROAD MOHNTON, PA 19540

CONFORMED SET

05/02/2024



SYMBOLS & TAGS LEGEND

TAG	DESCRIPTION
101A	DOOR TAG
101A	CASEWORK TAG
101A	SPECIALTY EQUIPMENT TAG
101A	COLUMN LINE DESIGNATION TAG
101A	LEVEL ELEVATION TAG
101A	NORTH ARROW TAG
101A	ROOM NAME & NUMBER TAG
101A	SECTION TAG
101A	CALLOUT / DETAIL
101A	SPOT ELEVATION TAG
101A	DETAIL / DRAWING TITLE TAG
101A	CEILING TAG
101A	PARTITION TAG
101A	MATERIAL TAG
101A	WINDOW TAG
101A	ROOF SLOPE ANNOTATION
101A	ELEVATION TAG
101A	SPECIFIC NOTE

COMMON ABBREVIATIONS

SYMBOLS	AND	FIN	FINISH	PSF	POUNDS PER SQUARE FOOT
AB	ANCHOR BOLT	FIN FL	FINISHED FLOOR	PSI	POUNDS PER SQUARE INCH
ABV	ABOVE	FL	FLOOR	PTD	PAINTED
AC	ACOUSTICAL	FLOR	FLOOR	PVC	POLYVINYL CHLORIDE
ACT	ACOUSTIC TILE	FND	FOUNDATION	PWT	PAVEMENT
ACU	A/C UNIT	FPM	FEET PER MINUTE	PWT	PREFABRICATED WOOD TRUSS
AFF	ABOVE FINISH FLOOR	FRT	FIRE RETARDANT TREATED	R	RADIUS
AHJ	AUTHORITY HAVING JURISDICTION	FSK	FOLI SCRIM KRAFT	RCP	REFLECTED CEILING PLAN
ALUM	ALUMINUM	FT	FLOOR TRANSITION	REIN	REINFORCING, REINFORCED
AP	ACCESS PANEL	FTG	FOOTING	RES	RESINOUS
APPROX	APPROXIMATELY	GA	GAGE, GAUGE	REQD	REQUIRED
ARCH	ARCHITECTURAL	GA	GAGE, GAUGE	REV	REVISION
B	BOTTOM CHORD	GLV	GALVANIZED	RIGD	RIGID
B.C.	BOTTOM	GRD	GROUND	RM	ROOM
BLK	BLOCK	GRTG	GRATING	RO	ROUGH OPENING
BLKG	BLOCKING	GSB	GYPSUM WALL BOARD	RST	REINFORCING STEEL
BLKHD	BULKHEAD	H	HEIGHT	S	SMART BOARD
BM	BEAM	HI	HIGH	SCD	SEE CIVIL DRAWINGS
B.O.	BOTTOM OF	HC	HANDICAPPED	SCHED	SCHEDULE
BOD	BASIS OF DESIGN	HD	HANDICAPPED	SD	STORM DRAIN
BOT	BOTTOM	HM	HOLLOW METAL	SED	SEE ELECTRICAL DRAWINGS
B.R.	BULLET RESISTANT	HORIZ	HORIZONTAL	SECT	SECTION
BRNG	BEARING	HOUR	HOUR	SF	SQUARE FOOT
C	CENTER LINE	HT	HEIGHT	SQ	SQUARE INCH
CFCI	CONTRACTOR FURNISHED, CONTRACTOR INSTALLED, OWNER INSTALLED	ID	INSIDE DIAMETER	SLP	SLOPE
CFPI	CONTRACTOR FURNISHED, CONTRACTOR INSTALLED, OWNER INSTALLED	IN	INCH	SM	SIMILAR
CFPI	CONTRACTOR FURNISHED, CONTRACTOR INSTALLED, OWNER INSTALLED	INSUL	INSULATION	SN	SEE MECHANICAL DRAWINGS
CFL	COUNTER FLASHING	IN	INCH	SPCL	SPECIAL
CJ	CONTROL JOINT	IN	INCH	SPEC	SPECIFICATIONS
CJ	CLOSET	IN	INCH	SPLY	SUPPLY
CLG	CEILING	INSUL	INSULATION	SQ	SQUARE
CMU	CONCRETE MASONRY UNIT	J	JUNCTION BOX	SS	STAINLESS STEEL
CONC	CONCRETE	JM	JAMB	SSD	SEE STRUCTURAL DRAWINGS
CONSTR	CONSTRUCTION	JT	JOINT	ST	STREET
CONT	CONTINUOUS	JT	JOINT	STD	STANDARD
CT, CT	CERAMIC TILE	KL	KLEIN	STL	STEEL
CT	CARPET / CARPET TILE	LG	LONG	STOR	STORAGE
CTK	COUNTERSUNK	LL	LIVE LOAD	STRUCT	STRUCTURAL
CUB	CUBIC	LL	LIVE LOAD	SURF	SURFACE
CUB FT	CUBIC FOOT	LG	LONG	SUSP	SUSPENDED
CUB YD	CUBIC YARD	LL	LIVE LOAD	SW	SWITCH
CG	CORNER GUARD	LFC	LIFE SAFETY CODE	SYS	SYSTEM
D	DEEP / DEPTH	LTG	LIGHTING	T	TYPICAL
DEG	DEGREES	M	MACHINE	T & B	TOP AND BOTTOM
DIA	DIAMETER	MACH	MACHINE	T.S.	TACK BOARD
DIM	DIMENSION	MATL	MATERIAL	T.D.	TO BE DETERMINED
DL	DEAD LOAD	MAX	MAXIMUM	TD	TRENCH DRAIN
DMPR	DAMPER	MBT	MARBLE THRESHOLD	TEMP	TEMPERATURE
DN	DOWN	MECH	MECH	THK	THICK
DR	DOWN	MEP	MECHANICAL / ELECTRICAL / PLUMBING	THRES	THRESHOLD
DS	DOWNSPOUT	MFR	MANUFACTURER	TAG	TONGUE & GROOVE
DTL	DETAIL	MH	MANHOLE	TOB	TOP OF BEARING POINT
DWG	DRAWING	MIN	MINIMUM	TOC	TOP OF CONCRETE
E	EACH	MO	MASONRY OPENING	TOF	TOP OF FOOTING
EA	ELECTRIC HEATER	MNSRY	MASONRY	TOM	TOP OF MASONRY
EIPS	EXTERIOR INSULATION AND FINISHING SYSTEM	MT	METAL THRESHOLD	TOP	TOP OF PAVEMENT, PARAPET
ELEC	ELECTRICAL	MTL	METAL	TOS	TOP OF STEEL
EL	ELEVATION	MTP	MOUNTED	TRTD	TREATED
ELEV	ELEVATION	MTR	MOUNTED	TS	TRANSITION STRIP
ELMA	ELEVATOR MACHINE ROOM	NA	NOT APPLICABLE	TYP	TYPICAL
EJ	EXPANSION JOINT	NO	NOT IN CONTRACT	U	UNDERGROUND
ENT	ENTRANCE, ENTRY	NTS	NOT TO SCALE	UN	UNDERWRITERS LAB
EQ	EQUAL	O	ON CENTER	UNO	UNLESS NOTED OTHERWISE
EST	ESTIMATE	OFIC	OUTSIDE DIAMETER	UON	UNLESS OTHERWISE NOTED
EXT	EXTERIOR	OPNG	OPENING	V	VAPOR BARRIER
EXT	EXPOSED	OPP	OPPOSITE	VCT	VINYL COMPOSITION TILE
EXT	EXTERIOR	OPP HND	OPPOSITE HAND	VIF	VERIFY IN FIELD
EXP	EXPANSION JOINT	OV	OVER	VOL	VOLUME
EXP JT	EXPANSION JOINT	OVHD	OVERHEAD	W	WIDE / WIDTH
F	FAHRENHEIT	P	PANEL	W	WITH
FD	FLOOR DRAIN	PLAM	PLASTIC LAMINATE	W/O	WITHOUT
F.E.	FIRE EXTINGUISHER	PLYWD	PLYWOOD	W.B.	WHITEBOARD
F.E.C.	FIRE EXTINGUISHER CABINET	PLBD	PANELBOARD	WD	WOOD
FF	FINISHED FLOOR	PNT	PAINT	WR	WATER RESISTANT
FF EL	FINISHED FLOOR ELEVATION	POLYSO	POLYISOCYANURATE	WRPR	WATERPROOF
FG	FIRE GRADE	PRESS	PRESSURE	WWF	WELDED WIRE FABRIC
FHY	FIRE HYDRANT	PROJ	PROJECT	WWM	WELDED WIRE MESH
FDC	FIRE DEPARTMENT CONNECTION	PROP	PROPERTY		

THIS LIST OF ABBREVIATIONS IS A GUIDE TO ABBREVIATIONS WHICH MAY BE USED IN THESE DOCUMENTS. ABBREVIATIONS NOT LISTED MAY ALSO BE USED.

KEY TO MATERIALS

CUT-THRU PATTERN	DESCRIPTION
[Pattern]	BRICK
[Pattern]	CIVIL MASONRY
[Pattern]	CONCRETE
[Pattern]	POROUS FILL
[Pattern]	EARTH
[Pattern]	PLYWOOD
[Pattern]	GYPSUM BOARD
[Pattern]	RIGID INSULATION
[Pattern]	BATT INSULATION
[Pattern]	END GRAIN LUMBER
[Pattern]	WOOD BLOCK OR SHIM
[Pattern]	FINISH WOOD

CORRELATION AND INTENT OF THE CONTRACT DOCUMENTS

THE INTENT OF THE CONSTRUCTION DRAWINGS AND THE CONSTRUCTION SPECIFICATIONS/PROJECT MANUAL IS TO INCLUDE ALL ITEMS NECESSARY FOR THE PROPER EXECUTION AND COMPLETION OF THE WORK BY THE CONTRACTOR. THE CONSTRUCTION DRAWINGS AND THE CONSTRUCTION SPECIFICATIONS/PROJECT MANUAL ARE COMPLEMENTARY, AND WHAT IS REQUIRED BY ONE SHALL BE AS BINDING AS IF REQUIRED BY ALL. PERFORMANCE BY THE CONTRACTOR SHALL BE REQUIRED ONLY TO THE EXTENT CONSISTENT WITH THE CONSTRUCTION DRAWINGS AND THE CONSTRUCTION SPECIFICATIONS/PROJECT MANUAL AND REASONABLY INFERRABLE FROM THEM AS BEING NECESSARY TO PRODUCE THE INDICATED/INTENDED RESULTS. IN THE CASE OF INCONSISTENCIES BETWEEN THE CONSTRUCTION DRAWINGS AND THE CONSTRUCTION SPECIFICATIONS/PROJECT MANUAL, OR WITHIN EITHER DOCUMENT NOT CLARIFIED BY ADDENDUM, THE BETTER QUALITY OR GREATER QUANTITY OF WORK SHALL BE PROVIDED IN ACCORDANCE WITH THE ARCHITECT'S INTERPRETATION.

PROJECT TEAM

ARCHITECT MANN'S WOODWARD STUDIOS 10839-D PHILADELPHIA ROAD WHITE MARSH, MARYLAND 21162 PHONE: 410-344-1460 FAX: 443-403-2460	MEP ENGINEER BKM MEP ENGINEERING 1416 CLARKVIEW ROAD BALTIMORE, MARYLAND 21209 PHONE: 410-323-0600 FAX: 410-377-2543	CIVIL ENGINEER ONE ATLAS 920 GERMANTOWN PIKE PLYMOUTH MEETING, PENNSYLVANIA 19462 PHONE: 610-313-3100
---	--	--

DRAWING INDEX


SHEET NUMBER	SHEET NAME
GENERAL / CODE	COVER SHEET
G000	CODE ANALYSIS
G002	CODE PLANS & DIAGRAMS
G003	TYPICAL ACCESSIBILITY GUIDELINES
CIVIL - NEW WORK	TITLE SHEET
100	EXISTING FEATURES PLAN
147	CONSTRUCTION TYPES
148	CONSTRUCTION TYPES
148.1	SITE DETAILS & PROFILE
148.2	GRADING PLAN
148.3	GRADING DETAILS AND PROFILES
148.4	WALL DETAILS
148.5	DRAINAGE & UTILITIES PLAN
148.6	LANDSCAPING PLAN & DETAILS
166	EROSION & SEDIMENTATION CONTROL PLAN
166.1	EROSION & SEDIMENTATION CONTROL NOTES
166.2	EROSION & SEDIMENTATION CONTROL NOTES
166.3	EROSION & SEDIMENTATION CONTROL DETAILS
166.4	EROSION & SEDIMENTATION CONTROL DETAILS
183	POSTCONSTRUCTION STORMWATER MANAGEMENT GRADING PLAN
183.1	POSTCONSTRUCTION STORMWATER MANAGEMENT UTILITY PLAN
183.2	POSTCONSTRUCTION STORMWATER MANAGEMENT NOTES
183.3	POSTCONSTRUCTION STORMWATER MANAGEMENT DETAILS
183.4	POSTCONSTRUCTION STORMWATER MANAGEMENT BASIN #5 DETAILS
183.5	POSTCONSTRUCTION STORMWATER MANAGEMENT BASIN #6 DETAILS
183.6	POSTCONSTRUCTION STORMWATER MANAGEMENT BASIN #6 DETAILS
183.7	POSTCONSTRUCTION STORMWATER MANAGEMENT PROFILES
183.8	POSTCONSTRUCTION STORMWATER MANAGEMENT PROFILES
184	PRE-DEVELOPMENT PHASE #2 DRAINAGES
184.1	POST-DEVELOPMENT PHASE #2 DRAINAGES
U	UNDERGROUND
UN	UNDERWRITERS LAB
UNO	UNLESS NOTED OTHERWISE
UON	UNLESS OTHERWISE NOTED
V	VAPOR BARRIER
VCT	VINYL COMPOSITION TILE
VIF	VERIFY IN FIELD
VOL	VOLUME
W	WIDE / WIDTH
W/O	WITHOUT
W.B.	WHITEBOARD
WD	WOOD
WR	WATER RESISTANT
WRPR	WATERPROOF
WWF	WELDED WIRE FABRIC
WWM	WELDED WIRE MESH

DRAWING INDEX

SHEET NUMBER	SHEET NAME
ARCHITECTURAL - NEW WORK	ARCHITECTURAL SITE DIAGRAM
A100	EXTERIOR SITE SLAB DIAGRAM
A101	REFERENCE PLAN
A102	DIMENSION PLAN
M201	CONSTRUCTION TYPES
M202	SLAB/MASONRY DIAGRAM
A105	FINISH PLAN
A106	FINISH SCHEDULE & DETAILS
A107	FINISH DETAILS
A108	EQUIPMENT & BLOCKING PLAN
A109	CLEARESTORY PLAN
A110	PLAN DETAILS
A111	ENTRY PLAN, ELEVATIONS & DETAILS
A112	EXTERIOR STAIR DETAILS
A113	SITE DETAILS
A114	SIORAGE DETAILS
A200	BUILDING ELEVATIONS
A300	TRANSVERSE BUILDING SECTIONS
A301	LONGITUDINAL BUILDING SECTIONS
A400	FOUNDATION PLAN - PLUMBING
A401	FIRST FLOOR PLAN - PLUMBING
A402	PART FLOOR PLANS - PLUMBING
A403	PLUMBING DETAILS
A404	PLUMBING DETAILS
A405	PLUMBING DETAILS
A406	PLUMBING RISER DIAGRAMS
A407	PLUMBING RISER DIAGRAMS
A500	ROOF PLAN
A501	ROOF DETAILS
A502	ROOF DETAILS
A503	ROOF DETAILS
A504	ROOF PENETRATION & LIGHTNING PROTECTION DETAILS
A600	DOOR/WINDOW SCHEDULE & TYPES
A601	EXTERIOR & INTERIOR DOOR DETAILS
A602	EXTERIOR & INTERIOR WINDOW DETAILS
A603	EXTERIOR STOREFRONT ELEVATIONS & DETAILS
A604	EXT. & INT. STOREFRONT ELEVATIONS & DETAILS
A700	TYPICAL EQUIPMENT & CASEWORK DETAILS
A701	ENLARGED PLANS & INT. ELEVATIONS
A702	ENLARGED PLANS & INT. ELEVATIONS
A703	ENLARGED PLANS & INT. ELEVATIONS
A704	ENLARGED PLANS & INT. ELEVATIONS
A705	ENLARGED PLANS & INT. ELEVATIONS
A706	ENLARGED PLANS & INT. ELEVATIONS
A707	ENLARGED PLANS & INT. ELEVATIONS
A708	ENLARGED PLANS & INT. ELEVATIONS
A709	ENLARGED PLANS & INT. ELEVATIONS
A710	ENLARGED PLANS & INT. ELEVATIONS
A800	REFLECTED CEILING PLAN
A801	ENLARGED CEILING PLANS & DETAILS
A802	MISC DETAILS
STRUCTURAL - NEW WORK	FOUNDATION / FIRST FLOOR PLAN
S101	MEZZANINE FRAMING PLAN
S102	MEZZANINE FRAMING PLAN
S103	ROOF FRAMING PLAN
S104	HIGH ROOF
S201	GENERAL NOTES & SCHEDULES
S301	TYPICAL DETAILS
S302	TYPICAL DETAILS
S303	TYPICAL DETAILS
S401	SECTIONS
S402	SECTIONS
S403	SECTIONS
S404	SECTIONS
S405	SECTIONS

DRAWING INDEX

SHEET NUMBER	SHEET NAME
MECHANICAL - GENERAL	MECHANICAL LEGEND, ABBREVIATIONS, AND GENERAL NOTES
M001	MECHANICAL LEGEND, ABBREVIATIONS, AND GENERAL NOTES
MECHANICAL - NEW WORK	FIRST FLOOR PLAN DUCTWORK
M101	FIRST FLOOR PLAN - HVAC PIPING
M201	PART FLOOR PLANS - HVAC
M401	MECHANICAL SECTIONS
M402	MECHANICAL SECTIONS
M501	MECHANICAL DETAILS
M502	MECHANICAL DETAILS
M601	MECHANICAL CONTROLS
M701	MECHANICAL SCHEDULES
M702	MECHANICAL SCHEDULES
PLUMBING - GENERAL	PLUMBING LEGEND, ABBREVIATIONS, SCHEDULES & GENERAL NOTES
P001	PLUMBING LEGEND, ABBREVIATIONS, SCHEDULES & GENERAL NOTES
P002	SITE PLAN PLUMBING NEW WORK
PLUMBING - NEW WORK	FOUNDATION PLAN - PLUMBING
P100	FOUNDATION PLAN - PLUMBING
P101	FIRST FLOOR PLAN - PLUMBING
P201	PART FLOOR PLANS - PLUMBING
P301	PLUMBING DETAILS
P302	PLUMBING DETAILS
P303	PLUMBING DETAILS
P401	PLUMBING RISER DIAGRAMS
P402	PLUMBING RISER DIAGRAMS
P403	PLUMBING RISER DIAGRAMS
ELECTRICAL - GENERAL	ELECTRICAL LEGEND, ABBREVIATIONS, AND GENERAL NOTES
E001	ELECTRICAL LEGEND, ABBREVIATIONS, AND GENERAL NOTES
E002	SITE PLAN ELECTRICAL NEW WORK
E003	SITE PLAN LIGHTNING PROTECTION NEW WORK
ELECTRICAL - NEW WORK	FIRST FLOOR PLAN POWER
E101	FIRST FLOOR PLAN MECHANICAL POWER
E102	FIRST FLOOR PLAN - FIRE ALARM
E201	FIRST FLOOR PLAN LIGHTING
E301	PART FLOOR PLANS - ELECTRICAL
E401	ELECTRICAL DETAILS
E402	ELECTRICAL DETAILS
E501	ELECTRICAL ONE LINE DIAGRAM
E601	LIGHTING FIXTURE SCHEDULE
E602	PANEL SCHEDULE
E603	PANEL SCHEDULE
ELECTRICAL - CAD ALERTING SYSTEM	COVER SHEET
AL-100	GENERAL REQUIREMENTS
AL-101	ALERTING DIAGRAM
AL-102	ALERTING WIRING DIAGRAM
AL-103	ALERTING WIRING DIAGRAM
AL-104	ALERTING WIRING DIAGRAM
AL-105	TYPICAL DETAILS & DISPLAY DIAGRAM



VICINITY MAP
NOT TO SCALE

MANN'S WOODWARD STUDIOS
ARCHITECTURE + MASTER PLANNING
10839-D PHILADELPHIA RD
WHITE MARSH, MD 21162
(P) 410-344-1460
(F) 443-403-2460
(E) INFO@MWSARCH.COM
WWW.MWSARCH.COM

SEAL:
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ARCHITECT UNDER THE LAWS OF THE STATE OF PENNSYLVANIA. LICENSE NUMBER: #0405311 EXPIRATION DATE: 6/30/2023

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS, BOTH THE DRAWINGS AND THE PROJECT MANUAL AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ACCORDANCE WITH THE CONTRACT. THIS SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID SPECIFICATIONS, ALL ADDENDA, AND THE OWNER'S ACCEPTED BID ALTERNATES AND CONTINGENCES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

CUMRU FIRE DEPARTMENT
1775 WELSH ROAD
MOHNTON, PA 19540

NO.	DESCRIPTION	DATE

PROJECT NUMBER:
18-036
PROJECT SET:
BID SET
DATE ISSUED:
11/30/2023

DRAWING TITLE:
COVER SHEET

SHEET NUMBER:
G000

CODE ANALYSIS - SUMMARY

PROJECT	APPLICABLE CODES	BUILDING SIZE
CUMRU TOWNSHIP FIRE DEPARTMENT STATION 42	PENNSLVANIA UNIFORM CONSTRUCTION CODE 2015 INTERNATIONAL BUILDING CODE 2015 INTERNATIONAL MECHANICAL CODE 2015 NATIONAL ELECTRIC CODE 2014 INTERNATIONAL PLUMBING CODE 2015 INTERNATIONAL ENERGY CODE 2015	TOTAL BUILDING: 22,908 GSF SINGLE STORY

PROJECT DESCRIPTION

THE PROJECT PROPOSES A NEW 22,908 GSF, SINGLE STORY FIRE STATION FOR THE CUMRU FIRE DEPARTMENT. THE NEW FIRE STATION WILL HOUSE A NON-SEPERATED MIXED-USE OF A-3, B, R2, AND S-2, INCLUDED BUT NOT LIMITED TO, ADMINISTRATIVE OFFICE AREA, KITCHEN AND LIVING AREA, A MEETING ROOM, APPARATUS SUPPORT AND STORAGE AREAS, ALONG WITH FIVE DOUBLE DEEP APPARATUS BAYS. THE APPARATUS BAYS ARE FLANKED ON EITHER END WITH TWO MEZZANINE STORAGE PLATFORMS WHOSE PRIMARY FUNCTION IS TO HOLD MECHANICAL HVAC EQUIPMENT. THE BUILDING IS SINGLE STORY, TYPE IIB CONSTRUCTION AND WILL BE COMPLETELY SPRINKLERED.

OCCUPANT LOAD TABLE

OCCUPANT LOAD FACTORS - TABLE 1004.1.2

ROOM NAME	AREA SF	FACTOR (SF/OCCUPANCY)	OCCUPANT LOAD	TOTAL OCCUPANTS	
STORAGE USE					
WATCH OFFICE 109	262	50	6	10	
VESTIBULE 147	116	---			
SHOWER 136	73	---			
SHOWER 137	73	---			
CLEAN ROOM 135	140	---			
TURNOUT GEAR 138	640	---			
DECON 139	313	---			
APPARATUS BAY 140	8,560	---			
UTILITY 146	181	---			
ELEC. 141	174	---			
SCBA 145	97	---			
TOILET 144	63	---			
ENGINEER 143	80	50	2		
WORKSHOP 142	120	100	2		
STORAGE 141.1	120	---			
MEZZANINE 201	1,108	---			
MEZZANINE 202	931	---			
ASSEMBLY USE					
VESTIBULE 100	151	---		313	
LOBBY 101	663	7 NET	95		
WOMEN 102	187	---			
JAN 102.1	13	---			
MEN 103	166	---			
JAN 103.1	13	---			
MEETING 104	1,492	7 NET	214		
STOR 104.1	119	500	1		
OFFICE 104.2	134	50	3		
BUSINESS USE					
		100 GSF (U.M.O)			58
OFFICE 105	128				
OFFICE 106	128				
OFFICE 107	128				
OFFICE 108	213		11		
OFFICE 109.1	120				
CHIEF'S OFFICE 110	220				
CONFERENCE 111	194	15 NET	13		
COPY 113	95		3		
OFFICE 114	122				
SHOWER 115	88	---			
MECH 115.1	30	500	1		
SHOWER 116	108	---			
LAUNDRY 117	103	500	1		
ELEC. 118	54	---			
FITNESS 119	526	50 GROSS	11		
SHOWER 120	81	---			
SHOWER 121	81	---			
MECH 122	20	500	3		
ST. 129.1	63	---			
IT 129	98	---			
CORRIDOR 130	748	---			
CORRIDOR 131	1,742	---			
KITCHEN 133	483	100	5		
DAYROOM 134	453	50	10		
RESIDENTIAL USE					
	1,464	50 GROSS		15	
BUNK 123,124,125,126,127,128	716				
CORRIDOR 130	748	---			
BUILDING TOTAL				396	

INTERNATIONAL BUILDING CODE 2015

USE CLASSIFICATIONS - CHAPTER 3

A-3 - ASSEMBLY - MEETING ROOM
B - BUSINESS - FIRE DEPARTMENT ADMINISTRATION
R2 - RESIDENTIAL - DORMITORY
S2 - STORAGE - APPARATUS BAY/ANCILLARY SPACES

CONSTRUCTION TYPE - CH.6

CONSTRUCTION TYPE: IIB FULLY-SPRINKLERED

BUILDING HEIGHT & AREA - CH.5

NON-SEPERATED MIXED OCCUPANCIES (IBC SECTION 508.3)

HEIGHT TABULAR - STORIES TABULAR - AREA TABULAR

A-3 - 75' A-3 - 3 A3 - 38,000
B - 75' B - 4 B - 76,000
R2 - 75' R2 - 5 R2 - 64,000
S-2 - 75' S-2 - 4 S-2 - 104,000

HEIGHT ALLOWED - STORIES ALLOWED - AREA ALLOWED

75' 3 45,125 SF
(MOST RESTRICTIVE OCCUPANCY, A-3)

HEIGHT ACTUAL - STORIES ACTUAL - AREA ACTUAL

31' 1 22,908

FIRE-RES. REQUIREMENTS FOR BLDG. ELEMENTS - TABLE 601

PER TABLE 602 NO FIRE RATING IS REQUIRED FOR ANY BUILDING ELEMENT UNLESS NOTED OTHERWISE.

OPENINGS IN FIRE RATED WALLS

WALL DOOR

CORRIDOR PARTITIONS 1/2 HR 20 MIN.

SECTION 505 - MEZZANINES & EQUIPMENT PLATFORMS

505.2.1. EXCEPTION #2. THE AGGREGATE AREA OF MEZZANINES IN BUILDINGS OF TYPE II CONSTRUCTION SHALL NOT BE GREATER THAN ONE-HALF OF THE FLOOR AREA OF THE ROOM IN BUILDINGS EQUIPPED THROUGHOUT WITH AN APPROVED AUTOMATIC SPRINKLER SYSTEM.

MEZZANINE 201 - 1,130 SF
MEZZANINE 202 - 931 SF

AGGREGATE MEZZANINE AREA: 2,061 SF

APPARATUS BAY - 8,563 SF / 2 = 4,281 SF > 2,601 SF

505.2.3 OPENNESS, EXCEPTIONS #1 - MEZZANINES OR PORTIONS THEREOF ARE NOT REQUIRED TO BE OPEN TO THE ROOM IN WHICH THE MEZZANINES ARE LOCATED, PROVIDED THAT THE OCCUPANT LOAD OF THE AGGREGATE AREA OF THE ENCLOSED SPACE IS NOT GREATER THAN 10.

SECTION 508 - MIXED USE & OCCUPANCY

508.1 - EACH PORTION OF A BUILDING SHALL BE INDIVIDUALLY CLASSIFIED IN ACCORDANCE WITH SECTION 502.1, WHERE A BUILDING CONTAINS MORE THAN ONE OCCUPANCY GROUP, THE BUILDING OR PORTION THEREOF SHALL COMPLY WITH THE APPLICABLE PROVISIONS OF SECTION 508.2, 508.3, OR 508.4.

508.3 NONSEPERATED OCCUPANCIES - BUILDINGS OR PORTIONS OF BUILDINGS THAT COMPLY WITH THE PROVISIONS OF THIS SECTION SHALL BE CONSIDERED AS NONSEPERATED OCCUPANCIES.

508.3.3 - SEPARATION. NO SEPARATION IS REQUIRED BETWEEN NONSEPERATED OCCUPANCIES.

EXCEPTION 2, GROUP R-2 SHALL BE SEPARATED FROM OTHER DWELLING OR SLEEPING UNITS FROM OTHER OCCUPANCIES CONTIGUOUS TO THEM IN ACCORDANCE WITH REQUIREMENTS OF SECTION 420.

420.2 SEPARATION WALLS - WALLS SEPARATING DWELLING OR SLEEPING UNITS SHALL BE CONSTRUCTED AS FIRE PARTITIONS IN ACCORDANCE WITH SECTION 708.

SECTION 1004 - OCCUPANT LOAD

ACCESSORY STORAGE AREAS, MECHANICAL EQUIPMENT ROOMS

-300 GROSS

ASSEMBLY, UNCONSECRATED (TABLES & CHAIRS)

-15 NET

BUSINESS AREAS

-100 GROSS

DORMITORIES

-50 GROSS

EXERCISE ROOMS

-50 GROSS

PARKING GARAGES

-200 GROSS

RESIDENTIAL

-200 GROSS

SECTION 1005.3.2, MEANS OF EGRESS CAPACITY

THE CAPACITY IN INCHES OF MEANS OF EGRESS COMPONENTS OTHER THAN STAIRWAYS SHALL BE CALCULATED BY MULTIPLYING THE OCCUPANT LOAD SERVED BY SUCH COMPONENT BY A MEANS OF EGRESS CAPACITY FACTOR OR .2 INCHES.

SECTION 1007.1.1, EXIT SEPARATION DISTANCE
EXCEPTION 2: WHERE A BUILDING IS EQUIPPED THROUGHOUT WITH AN AUTOMATIC SPRINKLER SYSTEM, THE SEPARATION DISTANCE SHALL NOT BE LESS THAN ONE-THIRD OF THE LENGTH OF THE MAXIMUM OVERALL DIAGONAL OF THE AREA SERVED.

SECTION 1020, CORRIDORS
PER TABLE 1020.1 FIRE RATING IS ONLY REQUIRED FOR ANY CORRIDORS SERVING "R" OCCUPANCY. FIRE RATING SHALL BE 1/2 HOUR. CORRIDORS WITHIN GROUPS B AND S-2 ARE NOT REQUIRED TO BE FIRE RATED.

THE REQUIRED CAPACITY OF CORRIDORS SHALL BE DETERMINED AS SPECIFIED IN SECTION 1005.1 BUT THE MINIMUM WIDTH SHALL NOT BE LESS THAN 44 INCHES.

1020.4 DEADEND CORRIDORS
EXCEPTION #3 - A DEAD-END CORRIDOR SHALL NOT BE LIMITED IN LENGTH WHERE THE LENGTH OF THE DEAD-END CORRIDOR IS LESS THAN 2.5 TIMES THE LEAST WIDTH OF THE DEAD-END CORRIDOR.

EGRESS THROUGH INTERVENING SPACES
EXCEPTION: MEANS OF EGRESS ARE NOT PROHIBITED THROUGH ADJOINING OR INTERVENING ROOMS OR SPACES IN GROUP S OCCUPANCY WHERE ADJOINING OR INTERVENING ROOMS OR SPACES ARE THE SAME OR A LESSER HAZARD OCCUPANCY GROUP.

OCCUPANCY	COMMON PATH	TRAVEL DISTANCE	DEAD-END CORRIDORS
A-3: ASSEMBLY	20' ALLOW./(N/A) ACTUAL	250' ALLOW./49' ACTUAL	20' ALLOW./(N/A) ACTUAL
B: BUSINESS	100' ALLOW./(N/A) ACTUAL	300' ALLOW./133' ACTUAL	50' ALLOW./14' 3" ACTUAL
R2: RESIDENTIAL	50' ALLOW./(N/A) ACTUAL	300' ALLOW./ 67' 8" ACTUAL	50' ALLOW./14' 3" ACTUAL
S-2: STORAGE	100' ALLOW./(N/A) ACTUAL	400' ALLOW./ 88' 4"	100' ALLOW./13' 10" ACTUAL
UNOCCUPIED MEZ.	100' ALLOW./98' 6" ACTUAL	400' ALLOW./ 148'	100' ALLOW./(N/A) ACTUAL

SEAL:

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ARCHITECT UNDER THE LAWS OF THE STATE OF PENNSYLVANIA.
LICENSE NUMBER: #6405311
EXPIRATION DATE: 6/30/2023

THIS CONFIRMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS, BOTH THE DRAWINGS AND THE PROJECT MANUAL AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDUM 1A. THIS CONFIRMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS, DRAWINGS, A SPECIFICATIONS, ALL ADDENDA, AND THE OWNER'S ACCEPTED BID ALTERNATES AND CONTINGENCES. THIS CONFIRMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

CUMRU FIRE DEPARTMENT
1775 WELSH ROAD
MOHNTON, PA 19540

NO.	DESCRIPTION	DATE


PROJECT NUMBER:
18-036
PROJECT SET:
BID SET
DATE ISSUED:
11/30/2023

DRAWING TITLE:
CODE ANALYSIS

SHEET NUMBER:
G001

SEAL:
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ARCHITECT UNDER THE LAWS OF THE STATE OF PENNSYLVANIA. LICENSE NUMBER: #0405311 EXPIRATION DATE: 6/30/2023



THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS, BOTH THE DRAWINGS AND THE PROJECT MANUAL AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDUM 1A. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS, DRAWINGS & SPECIFICATIONS, ALL ADDENDA, AND THE OWNER'S ACCEPTED BID ALTERNATES AND CONTINGENCES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.



1 CODE PLAN
1/8" = 1'-0"

	A = REQUIRED WIDTH
	B = ACTUAL WIDTH
	C = OCCUPANT COUNT
	ILLUMINATED "EXIT" SIGN
	ILLUMINATED "EXIT" SIGN W/ DIRECTION INDICATOR
	RATED WALL TAG
	RECESSED FIRE EXTINGUISHER & CABINET
	FIRE EXTINGUISHER MOUNTED TO WALL
	1 HOUR RATED PARTITION
	1/2 HOUR RATED PARTITION
	0 HOUR SMOKE PARTITION
	SEPARATION DISTANCE
	DOOR CARD READER

LEGEND - CODE PLAN LEGEND



MEZZANINE 201 (UNOCCUPIED):
COMMON PATH: 38' 6"
TRAVEL DISTANCE: 148' 0"
MEZZANINE 202 (UNOCCUPIED):
COMMON PATH: 83' 6"
TRAVEL DISTANCE: 95' 6"

2 CODE DIAGRAM
1/16" = 1'-0"

3 MEZZANINE CODE DIAGRAM
1/16" = 1'-0"

GENERAL CODE PLAN NOTES	
#	NOTES
1	FIRE WALLS, FIRE BARRIERS, FIRE PARTITIONS, SMOKE BARRIERS AND SMOKE PARTITIONS OR ANY OTHER WALL REQUIRED TO HAVE PROTECTED OPENINGS OR PENETRATIONS SHALL BE EFFECTIVELY AND PERMANENTLY IDENTIFIED AS REQUIRED BY IBC 703.7

CUMRU FIRE DEPARTMENT
1775 WELSH ROAD
MOHNTON, PA 19540

NO.	DESCRIPTION	DATE

PROJECT NUMBER:
18-036
PROJECT SET:
BID SET
DATE ISSUED:
11/30/2023
DRAWING TITLE:
CODE PLANS & DIAGRAMS
SHEET NUMBER:
G002

SEAL:
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ARCHITECT UNDER THE LAWS OF THE STATE OF PENNSYLVANIA. LICENSE NUMBER: #04405311 EXPIRATION DATE: 6/30/2023

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS, BOTH THE DRAWINGS AND THE PROJECT MANUAL AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDUM 1A. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS, DRAWINGS, AND SPECIFICATIONS. ALL ADDENDA, AND THE OWNER ACCEPTED BID ALTERNATES AND CONTINGENCES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

CUMRU FIRE DEPARTMENT
1775 WELSH ROAD
MOHNTON, PA 19540

NO. DESCRIPTION DATE

PROJECT NUMBER:
18-036
PROJECT SET:
BID SET
DATE ISSUED:
11/30/2023

DRAWING TITLE:
TYPICAL ACCESSIBILITY
GUIDELINES

SHEET NUMBER:
G003

11/29/2023 11:44:37 AM




Front Approaches - Swinging Doors




Hinge Side Approaches - Swinging Doors




Latch Side Approaches - Swinging Doors



Doorways without Doors




Recessed Doors and Gates




Two Hinged Doors in Series

DOOR CLEARANCES (TYPICAL)
NOT TO SCALE







- PROVIDE SIGNAGE AT ALL OF THE FOLLOWING LOCATIONS:
- ADA COMPLIANT IDENTIFICATION ROOM SIGNAGE WITH REMOVABLE INSERT AT ALL ROOMS OTHER THAN MECHANICAL ROOMS AND TOILET ROOMS. SIGNS SHALL INDICATE ROOM NUMBER AND PROVIDE REMOVABLE INSERT FOR ROOM NAMES.
 - ADA COMPLIANT IDENTIFICATION ROOM SIGNAGE AT MECHANICAL ROOMS AND TOILET ROOMS. SINGLE OCCUPANT TOILET ROOMS SHALL BE IDENTIFIED AS UNI-SEX. SINGLE OCCUPANT TOILET ROOMS WITH CHANGING STATIONS SHALL BE IDENTIFIED AS FAMILY RESTROOMS.
 - ADA COMPLIANT IDENTIFICATION EXIT SIGNAGE AT ALL DOORS LEADING TO RATED EXITS.
 - ADA COMPLIANT IDENTIFICATION FLOOR LEVEL SIGNAGE AT ALL FLOOR LANDINGS OF STAIRS AND RAMPS.
 - ADA COMPLIANT INFORMATIONAL SIGNAGE AT ALL AED STATIONS AND FIRE EXTINGUISHERS.
 - ADA COMPLIANT INFORMATIONAL SIGNAGE INDICATING THE MAXIMUM OCCUPANCY OF ALL ASSEMBLY SPACES.
 - ADA COMPLIANT INFORMATIONAL SIGNAGE SHALL BE PROVIDED AT ALL ELEVATORS.



ADA SIGNAGE MOUNTING LOCATIONS
1/4" = 1'-0"




STAIR & RAMP CLEARANCES (TYPICAL)
NOT TO SCALE




TOILET ROOM CLEARANCES (TYPICAL)
NOT TO SCALE




TYPICAL RESTROOM SIGN
TYPICAL SIGNAGE DETAILS
3" = 1'-0"



HIGH FORWARD REACH LIMIT (FRONT APPROACH)




MAXIMUM FORWARD REACH OVER AN OBSTRUCTION
NOTE: WHEN X IS >20 INCHES MAX, Y SHALL BE 48 INCHES MAX
WHEN X IS 20-25 INCHES MAX, Y SHALL BE 44 INCHES MAX




HIGH & LOW SIDE REACH LIMITS
SIDE REACH




REACH RANGES & APPROACHES (TYPICAL)
NOT TO SCALE





DRINKING FOUNTAINS (TYPICAL)
NOT TO SCALE




TYPICAL TOILET & SHOWER STALL ACCESSORY MOUNTING HEIGHTS & LOCATIONS
NOT TO SCALE




SHOWERS (TYPICAL)
NOT TO SCALE




NOTE: SHOWER HEAD AND CONTROL AREA MAY BE ON BACK (LONG) WALL (AS SHOWN) OR ON EITHER SIDE WALL.




SHOWER CLEARANCES (TYPICAL)
NOT TO SCALE



DRINKING FOUNTAINS (TYPICAL)
NOT TO SCALE



FLOOR CLEARANCES (TYPICAL)
NOT TO SCALE



SCHEDULE - TOILET ROOM ACCESSORIES

MARK	DESCRIPTION	BID MANUFACTURER	BID MODEL	COMMENTS
CR1	HEAVY DUTY SHOWER CURTAIN ROD	AMERICAN SPECIALTIES	1214/1200-SHU	
CS1	RECESSED DIAPER CHANGING STATION	AMERICAN SPECIALTIES	9013	<varies>
DT51	DOUBLE TOWEL RACK W/ TOP SHELF	AMERICAN SPECIALTIES	7311-24	
E7	BLACKOUT ROLLER SHADE	MECHO	SEE SPECIFICATIONS	BY 1a GENERAL PRIME CONTRACTOR
FS51	ADA FOLDING SHOWER SEAT	AMERICAN SPECIALTIES	8203	
GB1	18" LONG GRAB BAR	AMERICAN SPECIALTIES	3800	
GB2	24" LONG GRAB BAR	AMERICAN SPECIALTIES	3800	
GB4	36" LONG GRAB BAR	AMERICAN SPECIALTIES	3800	
GB5	42" LONG GRAB BAR	AMERICAN SPECIALTIES	3800	
GB6	48" LONG GRAB BAR	AMERICAN SPECIALTIES	3800	
GD1	SOAP DISPENSER	N/A	N/A	OWNER PROVIDED CONTRACTOR INSTALLED
LD2	LAVATORY LIQUID SOAP DISPENSER	N/A	N/A	OWNER PROVIDED CONTRACTOR INSTALLED
MH1	MOP & BROOM HOLDER	BOBRICK	B-238X34	
MR1	CHANNEL FRAME MIRROR - 24" WIDE x 42" TALL	AMERICAN SPECIALTIES	0620-2442	
MR2	CUSTOM CHANNEL FRAME MIRROR - 48" TALL	LANCASTER PAINT & GLASS		VERIFY MAX WIDTH IN FIELD PRIOR TO FABRICATION
PT1	WALL MOUNTED PAPER TOWEL DISPENSER	N/A	N/A	<varies>
RH1	DOUBLE ROBE HOOK	AMERICAN SPECIALTIES	7345	
SD51	SOAP DISH SHELF	AMERICAN SPECIALTIES	7380-518	
SN1	SANITARY WASTE RECEPTACLE	N/A	N/A	OWNER PROVIDED CONTRACTOR INSTALLED
TP1	TOILET PAPER DISPENSER	N/A	N/A	OWNER PROVIDED CONTRACTOR INSTALLED

SCHEDULE - TOILET ROOM ACCESSORIES

MARK	DESCRIPTION	BID MANUFACTURER	BID MODEL	COMMENTS
CR1	HEAVY DUTY SHOWER CURTAIN ROD	AMERICAN SPECIALTIES	1214/1200-SHU	
CS1	RECESSED DIAPER CHANGING STATION	AMERICAN SPECIALTIES	9013	<varies>
DT51	DOUBLE TOWEL RACK W/ TOP SHELF	AMERICAN SPECIALTIES	7311-24	
E7	BLACKOUT ROLLER SHADE	MECHO	SEE SPECIFICATIONS	BY 1a GENERAL PRIME CONTRACTOR
FS51	ADA FOLDING SHOWER SEAT	AMERICAN SPECIALTIES	8203	
GB1	18" LONG GRAB BAR	AMERICAN SPECIALTIES	3800	
GB2	24" LONG GRAB BAR	AMERICAN SPECIALTIES	3800	
GB4	36" LONG GRAB BAR	AMERICAN SPECIALTIES	3800	
GB5	42" LONG GRAB BAR	AMERICAN SPECIALTIES	3800	
GB6	48" LONG GRAB BAR	AMERICAN SPECIALTIES	3800	
GD1	SOAP DISPENSER	N/A	N/A	OWNER PROVIDED CONTRACTOR INSTALLED
LD2	LAVATORY LIQUID SOAP DISPENSER	N/A	N/A	OWNER PROVIDED CONTRACTOR INSTALLED
MH1	MOP & BROOM HOLDER	BOBRICK	B-238X34	
MR1	CHANNEL FRAME MIRROR - 24" WIDE x 42" TALL	AMERICAN SPECIALTIES	0620-2442	
MR2	CUSTOM CHANNEL FRAME MIRROR - 48" TALL	LANCASTER PAINT & GLASS		VERIFY MAX WIDTH IN FIELD PRIOR TO FABRICATION
PT1	WALL MOUNTED PAPER TOWEL DISPENSER	N/A	N/A	<varies>
RH1	DOUBLE ROBE HOOK	AMERICAN SPECIALTIES	7345	
SD51	SOAP DISH SHELF	AMERICAN SPECIALTIES	7380-518	
SN1	SANITARY WASTE RECEPTACLE	N/A	N/A	OWNER PROVIDED CONTRACTOR INSTALLED
TP1	TOILET PAPER DISPENSER	N/A	N/A	OWNER PROVIDED CONTRACTOR INSTALLED

CUMRU FIRE DEPARTMENT


CUMRU TOWNSHIP, BERKS COUNTY, PENNSYLVANIA CONTRACT #1A, #15A, #15B & #16A



920 Germantown Pike, Suite 200
Plymouth Meeting, PA. 19462

DRAWING INDEX

1 OF 25	100	TITLE SHEET
2 OF 25	147	EXISTING FEATURES PLAN
3 OF 25	148	CONSTRUCTION PLAN
4 OF 25	148.1	SITE DETAILS & PROFILE
5 OF 25	148.2	GRADING PLAN
6 OF 25	148.3	GRADING DETAIL
7 OF 25	148.4	WALL DETAILS
8 OF 25	148.6	DRAINAGE & UTILITIES PLAN
9 OF 25	148.7	LANDSCAPING PLAN & DETAILS
10 OF 25	166	EROSION & SEDIMENT CONTROL PLAN
11 OF 25	166.1	EROSION & SEDIMENT CONTROL NOTES
12 OF 25	166.2	EROSION & SEDIMENT CONTROL NOTES
13 OF 25	166.3	EROSION & SEDIMENT CONTROL DETAILS
14 OF 25	166.4	EROSION & SEDIMENT CONTROL DETAILS
15 OF 25	183	POST CONSTRUCTION STORMWATER MANAGEMENT GRADING PLAN
16 OF 25	183.1	POST CONSTRUCTION STORMWATER MANAGEMENT UTILITY PLAN
17 OF 25	183.2	POST CONSTRUCTION STORMWATER MANAGEMENT NOTES
18 OF 25	183.3	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS
19 OF 25	183.4	POST CONSTRUCTION STORMWATER MANAGEMENT BASIN #5 DETAILS
20 OF 25	183.5	POST CONSTRUCTION STORMWATER MANAGEMENT BASIN #6 DETAILS
21 OF 25	183.6	POST CONSTRUCTION STORMWATER MANAGEMENT BASIN #6 DETAILS
22 OF 25	183.7	POST CONSTRUCTION STORMWATER MANAGEMENT PROFILES
23 OF 25	183.8	POST CONSTRUCTION STORMWATER MANAGEMENT PROFILES
24 OF 25	191	PRE-DEVELOPMENT DRAINAGE AREA MAP
25 OF 25	192	POST-DEVELOPMENT DRAINAGE AREA MAP



PROJECT REQUIREMENTS AND NOTES

GENERAL

- All referenced plans, specifications, codes or other information are to be included as part of the design documents. All contractors, including subcontractors, shall be fully aware of these documents prior to bidding and construction.
- Any discrepancies found in the design documents shall be brought in writing to the attention of the responsible engineer immediately.
- No substitutions and/or changes shall be allowed unless requested and approved in writing by the responsible engineer.
- All work shall be performed in strict accordance with OSHA, Federal, State and local codes and requirements.

CONSTRUCTION

- All components of construction not specifically called for or detailed on the drawings, but are required, necessary and considered good practice for construction shall be included in the design.
- All construction shall comply with PennDOT Publication 408, Latest Edition unless specified in the construction document.
- All construction details shall comply with PennDOT Publication 72, "Standards for Roadway Construction", Series RC 0 to 100, Latest Edition unless detailed in the project plans.
- All curb, sidewalk and sidewalk ramp construction, if any, must meet the respective accessibility regulations and provisions as established in the American with Disabilities Act U.S.C. (ADAAG)
- The Berks County Conservation District (BCCD) must be notified prior to any earth disturbance. All required erosion and sediment control measures must be installed and operating prior to any earth disturbance, and maintained per BCCD requirements for the duration of the project. Refer to the Soil Erosion and Sediment Control Notes for additional requirements.
- Maintenance and protection of traffic during construction shall be in accordance with PennDOT Publication 203, "Work Zone Traffic Control" where applicable.
- Public access to all roadways, driveways, and sidewalks must be available at all times during construction as is possible.
- During construction, all obstructions (including, but not limited to, equipment and construction materials) shall be removed by the contractor at the end of each working day to allow a safe sight distance for drivers, cyclists, and pedestrians accessing the roadways, driveways and sidewalks. Trained flagmen or other approved means shall be used to assist drivers, cyclists, and pedestrians safely around any temporary sight obstructions.
- Fire hydrants and other public safety devices must remain visible, operational and accessible at all times during construction.
- Slopes shall be graded to a maximum of 3 horizontal to 1 vertical or as safely allowed by the soil conditions.
- All unsuitable materials and other construction materials shall become the property of the contractor, unless specifically requested by the owner, and to be to be properly disposed off-site as required per the soil erosion and sediment control notes.
- All excavation to be unclassified.
- The contractor is fully responsible for adherence to the Preparedness, Prevention and Contingency (PPC) plan as listed in the project plans and specifications.
- Blasting allowed where necessary due to rock conditions if approved by owner per specifications. Contractor must video inspect all adjacent structures prior to confirm existing conditions prior to blasting. Contractor will be responsible for all collateral damages arising from blasting.
- Construction materials, equipment, and supplies may not be stored in floodplains and/or wetlands.
- Excavated material not to be used as trench backfill in R-O-W or under pavement.
- The removal of debris and accumulated sediment to ensure hydraulic capacity of the stream culverts shall be limited to 50 feet upstream and downstream from the culvert and shall be conducted in accordance with PADEP requirements.
- Required Bag Turtle avoidance measures for all stream crossings: Avoid in-stream impacts by spanning the waterway or going under it (e.g., via horizontal boring or directional drilling). If in-stream impacts cannot be avoided, carry out in stream work -- including installation of permanent structures (e.g., pipelines, livestock crossings, riprap), or installation, use, and removal of temporary structures (e.g., temporary road crossings) -- between October 1 and March 31.

UTILITIES

- The contractor is solely responsible for verifying the actual locations by contacting the PA One Call System and the individual utility companies at least three (3) working days prior to any excavation. Additional excavation of test pits may be required for determining the precise location of a buried utility.
- All existing utility (water, sewer, gas, electric, drainage, etc.) locations and elevations must be verified by the contractor prior to fabrication and construction of replacement of connected utilities.
- The contractor is solely responsible for the protection of all utilities crossing or adjacent to the construction area per the requirements of the utility owner. Any damaged utilities must be inspected by the utility owner and repaired as necessary per the utility owner's requirements and at the expense of the contractor.
- Any utilities requiring relocation, either permanent or temporary, shall be completed by the contractor per the requirements and inspection of the utility owner.
- All required connections from the constructed or replaced utility systems to the existing systems and laterals shall be completed per the requirements of the utility owner. Each connection location, depth, and condition to be verified by contractor and confirmed by the utility owner per PA One Call requirements and exploratory excavation as required.
- Excavated clean and suitable material, where to be used as backfill, may be temporarily stored adjacent to the trench and must be used by the end of each work day.

SURVEY

- Horizontal Survey Control Datum is State Plane Coordinates, NAD83, Pennsylvania South Zone.
- Vertical Survey Control Datum is NAVD88.
- Local benchmarks are as noted on the plans.
- Floodplains shown are based on the latest National Flood Insurance Program (NFIP) Flood Insurance Rate Map as published by FEMA.
- Soil types mapped are as shown on USDA NRCS Web Soil Survey.
- The plan depicts the survey conditions as existed on or around 1/1/23.
- All Right-Of-Ways, Easements and Property Lines shown are for information only, based on existing available records. The plans were prepared without benefit of a title report and are not to be used for establishment of ownership boundaries in the field.
- Owner will provide building exterior, grading and site work construction stakeout. Contractor is responsible for building interior layout.

PERMITS

- The owner is obtaining or has obtained the following permits for the project:
 - PHMC #2020-1958-011-A, 07/24/20
 - Individual National Pollutant Discharge Elimination System (NPDES) Permit for Stormwater Discharges Associated with Construction Activities approved by the Pennsylvania Department of Environmental Protection #PAD060047.
- The contractor shall be responsible for obtaining any and all other required permits and approvals needed for the project.
- It shall be the contractor's responsibility to be aware of and conform to the requirements of these and any other required permits and approvals.
- The contractor shall be liable for all penalties for failure to comply with permit requirements, including any sanitary sewer overflows due to construction conditions.
- The contractor shall be responsible for obtaining all permit extensions as needed for the project duration.
- The contractor shall be responsible for obtaining approval from the permitting agencies for amending or modifying any permits.
- All applicable permits must be transferred into the contractor's name prior to any earth disturbance.

CORRELATION AND INTENT OF THE CONTRACT DOCUMENTS

The intent of the construction drawings and the construction specifications/project manual is to include all items necessary for the proper execution and completion of the work by the contractor. The construction drawings and the construction specifications/project manual are complementary, and what is required by one shall be as binding as if required by all; performance by the contractor shall be required only to the extent consistent with the construction drawings and the construction specifications/project manual and reasonably inferable from them as being necessary to produce the indicated/intended results. In the case of inconsistencies between the construction drawings and the construction specifications/project manual or within either document not clarified by addendum, the better quality or greater quantity of work shall be provided in accordance with the Civil Engineer interpretation.

Engineer's Certification

I Jeffrey E. Skinner do hereby certify pursuant to the penalties of 18 Pa. C.S.A. Sec. 4904 to the best of my knowledge, information and belief, that the information contained in the accompanying plans, specifications, and reports has been prepared in accordance with accepted engineering practice, is true and correct, and is in conformance with Chapter 105 of the rules and regulations of the Department of Environmental Protection.

SITE LEGEND	
---	PROPERTY LINE
---	EXISTING BUILDING
---	EXISTING CONTOUR
---	EXISTING STORMWATER PIPE
---	EXISTING STORMWATER INLET
---	EXISTING EDGE OF PAVING
---	EXISTING CURB
---	EXISTING SIGN
---	EXISTING SANITARY SEWER
---	EXISTING GAS MAIN
---	EXISTING WATER MAIN
---	EXISTING SANITARY MANHOLE
---	GAS CURB STOP
---	WATER CURB STOP
---	SANITARY CLEAN OUT
---	FIRE HYDRANT
---	VALVE
---	TEST PIT LOCATION
---	P.S.B. PROJECT SITE BOUNDARY
---	LOD LIMIT OF DISTURBANCE
---	542 PROPOSED BUILDING
---	542 PROPOSED CONTOUR
---	PROPOSED STORMWATER PIPE
---	PROPOSED STORMWATER INLET
---	PROPOSED EDGE OF PAVING
---	PROPOSED CURB
---	PROPOSED SIGN
---	PROPOSED SANITARY SEWER
---	PROPOSED GAS MAIN
---	PROPOSED WATER MAIN
---	TO BE VERIFIED (BY CONTRACTOR)
---	TO BE REMOVED

Pennsylvania One Call System, Inc.




Call Before You Dig
in Pennsylvania
1-800-242-1776

State Law Requires
Construction Phase: Three working Days Notice
Design Phase: Ten working Days Notice
Facility Owners: Member of One Call System

- SERIAL NO. #20210272169,
- SERIAL NO. #20210272189,
- SERIAL NO. #20210272250,
- SERIAL NO. #20210272251,
- SERIAL NO. #20210272292,
- SERIAL NO. #20210272341

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION
Date	Draft	Chkd	
TITLE SHEET			
CUMRU FIRE DEPARTMENT NEW BUILDING			
Prepared For: TOWNSHIP OF CUMRU			
Situate In: CUMRU TOWNSHIP, BERKS CO., PA.			
			PROJECT #: Z057000538 DRAWING #: 100 SHEET #: 1 OF 25
920 GERMANTOWN PIKE, SUITE 200, PLYMOUTH MEETING, PA 19462			



SOILS TYPE ON SITE		
LEGEND	NAME	DESCRIPTION
NaB	NESHAMINY SILT LOAM	3 TO 8 PERCENT SLOPES
NaC	NESHAMINY SILT LOAM	8 TO 15 PERCENT SLOPES
NhD	NESHAMINY GRAVELLY SILT LOAM	8 TO 25 PERCENT SLOPES, EXTREMELY BOULDERY

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS DRAWINGS & SPECIFICATIONS, ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FOR COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

Date	Draft	Chkd	ISSUED FOR BIDS
11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION

EXISTING FEATURES PLAN
CUMRU FIRE DEPARTMENT NEW BUILDING
 Prepared For:
TOWNSHIP OF CUMRU
 Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.

Jeffrey E. Skinner
 PE-042652-E
 SU-052889-E


ATLAS
 920 GERMANTOWN PIKE, SUITE 200,
 PLYMOUTH MEETING, PA 19462

PROJECT #:
Z057000538
 DRAWING #:
147
 SHEET #:
2 OF 25








Pennsylvania One Call System, Inc.
 Call Before You Dig
 in Pennsylvania
 1-800-242-1776

State Law Requires
 Construction Phase: Three working Days Notice
 Design Phase: Ten working Days Notice
 Facility Owners: Member of One Call System

SERIAL NO. #20210272169, SERIAL NO. #20210272189
 SERIAL NO. #20210272250, SERIAL NO. #20210272251
 SERIAL NO. #20210272292, SERIAL NO. #20210272341



S:\FILES\SERVER\Projects\Cumru\2057000538 - Resurf Fire Station\DWG\FIRE STATION\DWG_11/29/2023 2:48:49 PM_AutoCAD PLOT (General Documentation).pc3



CONCRETE CURB 1 (IF REQUIRED) N.T.S. 148.1

DEPRESSED CURB DETAIL 2 (IF REQUIRED) N.T.S. 148.1

SECTION A-A (IF REQUIRED) N.T.S. 148.1



CURB TAPER DETAIL 3 N.T.S. 148.1

BOLLARD DETAIL 5 N.T.S. 148.1

CUMRU TOWNSHIP TYPICAL STANDPIPE SINGLE SERVICE CONNECTION 22 S022


PROPOSED 4\"/>

- NOTES**
1. PROVIDE MATERIALS AND CONSTRUCTION MEETING THE REQUIREMENTS OF PENN DOT PUBLICATION 408/2000, SECTIONS 420, 421, 422, 630 AND 676.
 2. PROVIDE EXPANSION JOINT MATERIAL 1/2" THICK WHERE CURB RAMP ADJOINS ANY RIGID PAVEMENT, SIDEWALK OR STRUCTURE WITH THE TOP OF JOINT FILLER FLUSH WITH ADJACENT CONCRETE SURFACE.
 3. SEAL JOINTS WITH AN APPROVED SEALING MATERIAL.
 4. PROVIDE SLIP RESISTANT TEXTURE ON CURB RAMP BY COARSE BROOMING TRANSVERSE TO THE SLOPE OF THE RAMP. EXTEND TEXTURE THE FULL WIDTH AND LENGTH OF THE CURB RAMP INCLUDING FLARED SIDE RAMP.
 5. MODIFY CONSTRUCTION DETAILS TO ADAPT DIMENSIONS WHERE THE CURB IS LESS THAN THE STANDARD 7" HEIGHT.
 6. CURB RAMP AND SIDE FLARE LENGTHS ARE VARIABLE AND BASED ON CURB HEIGHT AND THE SIDEWALK PITCH.
 7. WHENEVER POSSIBLE, CONSTRUCT THE TRANSITION SLOPE FROM THE CURB RAMP AND FLARE SIDES TO ADJOINING SURFACES WITH A GRADUAL CURVE RATHER THAN AN ABRUPT ANGLE.




HANDICAP RAMP, TYPE 1

TRANSITION CURB DETAIL 4 N.T.S. 148.1




CONCRETE SIDEWALK DETAIL 9 N.T.S. 148.1



PARKING STALL NOTES:

1. PROVIDE 2 COATS OF PAINT ON ALL SITE STRIPING.
2. SEE SITE PLAN FOR ACTUAL STALL LOCATION AND DIMENSIONS.




STANDARD ACCESSIBLE DIMENSIONING 11 148.1

A U.S. DEPARTMENT OF TRANSPORTATION R7-8 (RESERVED PARKING) AND SUPPLEMENTAL SIGNS AS NOTED ABOVE MUST BE MOUNTED ON A PERMANENT POST NO LOWER THAN FOUR FEET FROM THE PAVEMENT. THE POST MUST BE MOUNTED IN THE CENTER OF THE 9 FOOT WIDE ACCESSIBLE PARKING SPACE, 30 INCHES FROM THE FRONT OF THE PARKING SPACE (PLACE SIGN OUTSIDE OF WALKWAYS). SEE ILLUSTRATION ABOVE.

THE ACCESS AISLE SHALL BE DESIGNATED WITH HIGH QUALITY BLUE DIAGONAL SURFACE PAINT STRIPING.


RAMP MUST NOT EXTEND OUT FROM THE CURB INTO THE ACCESS AISLE OF ANY ACCESS PARKING SPACE.




HANDICAPPED PARKING GRAPHICS DETAIL 11 148.1

HANDICAP PARKING SPACE DETAIL 11 N.T.S. 148.1

ONE-WAY BARRIER GORE MARKING 12 N.T.S. 148.1



ASPHALT PARKING LOT/DRIVEWAY PAVEMENT 15 N.T.S. 148.1




FIRE TRUCK CONCRETE DRIVEWAY 16 N.T.S. 148.1

DRIVEWAY & PARKING LOT RECONSTRUCTION NOTES:

1. 9.5 MM MIX SUPERPAVE ASPHALT MIXTURE DESIGN (WMA), WEARING COURSE, PG. 645-22, 3 TO 30 MILLION ESALS, DESIGN LEVEL 75 GYRATIONS.
2. 25.0 MM MIX SUPERPAVE ASPHALT MIXTURE DESIGN (WMA), BASE COURSE, PG. 645-22, 3 TO 30 MILLION ESALS, DESIGN LEVEL 75 GYRATIONS.
3. 2A MODIFIED AGGREGATE SUBBASE, COMPACTED TO 100% OF THE MAXIMUM DRY-WEIGHT DENSITY.
4. SUBGRADE TOPSOIL, LARGE ROCKS, AND OTHER TYPES OF LOW QUALITY, UNSUITABLE SOIL SHALL BE REMOVED AND REPLACED. THE EXPOSED SURFACE SHALL BE COMPACTED WITH SUITABLE EQUIPMENT (MINIMUM 10-TON ROLLER). SUBGRADE COMPACTION SHOULD BE TO A DRY DENSITY OF AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY (ASTM D698).
5. 2 RC TO BE INSTALLED BETWEEN TOP OF BASIN #6 STONE AND SUBBASE.
6. EXCAVATE AND REMOVE EXISTING PAVEMENT AND MATERIAL TO REQUIRED ELEVATION. RECOMPACT EXPOSED SUBGRADE. TACK COAT ALL EXPOSED VERTICAL PAVEMENT EDGES.
7. HOT SEAL ALL EDGE JOINTS WITH 12" WIDE PG 645-22 TO EXISTING PAVEMENTS, CURBS, DRAINAGE AND UTILITY STRUCTURES.


FIRE TRUCK CONCRETE PAD NOTES:

1. 5000 PSI CONCRETE.
2. #4 EPOXY COATED BARS 6" O.C. BOTH DIRECTIONS.
3. FINISHED, PROVIDE A 1/2" THICK EXPANSION JOINTS W/ 1/2" DEEP SEALANT APPROXIMATELY 50' O.C. AND SCORE JOINTS APPROXIMATELY 5' O.C.
4. REGRADE AND COMPACT AS NEEDED TO MEET SUBBASE GRADE AND STABILIZATION REQUIREMENTS OF 100% OF THE MAXIMUM DRY-WEIGHT DENSITY. PROVIDE ADDITIONAL MATERIAL AS NEEDED TO MEET REQUIRED GRADES.




- ADA PARKING SIGN NOTES:**
1. SIGNS: R7-8A, R7-8, & R7-8P
 2. SIGNS: R7-8 & R7-8P


ADA PARKING SIGN 17 N.T.S. 148.1




RESERVED PARKING SIGN (R7-8) 18 N.T.S. 148.1




VAN ACCESSIBLE SIGN (R7-8P) 20 N.T.S. 148.1




VIOLATORS SUBJECT TO FINE AND TOWING 19 N.T.S. 148.1



STOP SIGN (R1-1) 21 N.T.S. 148.1



STOP LINE 13 N.T.S. 148.1



POLE LIGHT STANDARD AND FIXTURE DETAIL 24 N.T.S. 148.1

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION
Date	Draft	Chkd	

SITE DETAILS & PROFILE

CUMRU FIRE DEPARTMENT NEW BUILDING

Prepared For:
TOWNSHIP OF CUMRU

Site In:
CUMRU TOWNSHIP, BERKS CO., PA.


PROJECT #:
Z057000538

DRAWING #:
148.1

SHEET #:
4 OF 25







Jeffrey E. Skinner
PE-042652-E
SU-052889-E

ATLAS
920 GERMANTOWN PIKE, SUITE 200,
PLYMOUTH MEETING, PA 19462



WALL LEGEND

TW = TOP ELEVATION OF WALL
 CW = CHANGE OF WALL ELEVATION
 BW = BOTTOM ELEVATION OF WALL
 GR = PROPOSED GROUND ELEVATION



THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.





Date	Draft	Chkd	ISSUED FOR BIDS
11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION

GRADING DETAILS AND PROFILES
CUMRU FIRE DEPARTMENT NEW BUILDING
 Prepared For:
TOWNSHIP OF CUMRU
 Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.

Jeffrey E. Skinner
 PE-042652-E
 SU-052889-E

ATLAS
 920 GERMANTOWN PIKE, SUITE 200,
 PLYMOUTH MEETING, PA 19462

PROJECT #: Z057000538
 DRAWING #: 148.3
 SHEET #: 6 OF 25






2 SECTION - NEW RETAINING WALL #1
148.4 SCALE: 1/2" = 1'-0"


3 SECTION - NEW RETAINING WALL #2
148.4 SCALE: 1/2" = 1'-0"

7 DETAIL - CONTROL JOINTS
148.4 SCALE: 1/2" = 1'-0"

- WALL LEGEND**
- TW = TOP OF WALL ELEVATION
 - CW = CHANGE IN HEIGHT AT TOP WALL ELEVATION
 - SW = WALL ELEVATION @ SIDEWALK, DRIVEWAY OR AT INLET
 - GR = PROPOSED GROUND ELEVATION
 - FT1 = BOTTOM FOOTER ELEVATION
 - FT2 = CHANGE IN HEIGHT AT BOTTOM OF FOOTER ELEVATION



6 SECTION - NEW RETAINING WALL #3
148.4 SCALE: 1/2" = 1'-0"



8 SECTION - WALL ELEVATION LEGEND
148.4 SCALE: 1/2" = 1'-0"

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION
Date	Draft	Chkd	


WALL DETAILS
CUMRU FIRE DEPARTMENT NEW BUILDING
Prepared For:
TOWNSHIP OF CUMRU
Site In:
CUMRU TOWNSHIP, BERKS CO., PA.

Jeffrey E. Skinner
PE-042652-E
SU-052889-E


ATLAS
920 GERMANTOWN PIKE, SUITE 200,
PLYMOUTH MEETING, PA 19462

PROJECT #:
Z057000538
DRAWING #:
148.4
SHEET #:
7 OF 25

S:\FILES\SERVER\Projects\Cumru\2057000415 - Resurf Fire Station\DWG\FIRE-STATION.dwg, 11/29/2023 2:49:15 PM, AutoCAD PLOT (General Documentation).pc3




- NOTES:**
- 18" MINIMUM DISTANCE BETWEEN SANITARY SEWER LATERALS AND ROOF DRAIN.
 - PROPOSED SANITARY SEWER LAYOUT & PIPE SIZES, SEE PLUMBING DWGS.
 - 18" MINIMUM DISTANCE BETWEEN WATER LATERAL AND GAS LATERAL.
 - PROPOSED GAS LATERAL CONNECTION, SEE PLUMBING DWGS.
 - PROPOSED FIRE DEPARTMENT CONNECTION, SEE PLUMBING DWGS.
 - PROPOSED CONCRETE TRANSFORMER PAD AND CONDUITS, SEE ELECTRICAL DWGS.
 - PROPOSED GENERATOR & SYSTEMS, SEE ELECTRICAL DWGS.
 - THE LENGTH OF THE BASIN EDGE IS NOT SQUARE BETWEEN BASIN #6 AND SWALES #3 & #4. THIS ELEVATION ON BASIN EDGE IS 536.75.
 - PROPOSED LIGHTING AND ELECTRICAL WIRING (TYP.), SEE ARCHITECTURAL DWGS.
 - EXISTING GAS LATERAL CAP, REMOVE THE CAP & TIE INTO GAS LATERAL.
 - EXISTING 6" WATER LATERAL CAP, REMOVE THE CAP & TIE INTO PROP. 6" WATER LATERAL.



- NOTES:**
- 6" DIP SUPPLY CONNECTED TO MAIN.
 - 6" DIP FIRE & 3" DIP DOMESTIC STUBS ON BUILDING SIDE CAPPED.
 - SHOULD THE PRECAST'S STANDARD SIZE METER PIT NOT MATCH THE MINIMUM SIZE SPECIFIED, THE PRECAST'S STANDARD SIZE PIT CAN BE SUBMITTED FOR REVIEW.

UTILITIES	
CABLE TV	COMCAST CABLE 4601 SMITH STREET, HARRISBURG, PA 17109 EMAIL: DAVE.MOLUCKIE@COMCAST.COM
ELECTRIC	METROPOLITAN EDISON CO/FIRSTENERGY CORP., 76 S. MAIN STREET, AKRON, OH 44308
SANITARY SEWER	CUMRU TOWNSHIP WASTEWATER DEPT. ROBERT MCHICHOLS JR. 1775 WELSH ROAD, MOHNTON, PA 19540 610-777-1343
CABLE	SERVICE ELECTRIC CABLEVISION INC. (SVC) 6400 PERKOWEN AVENUE PO BOX 8, BIRDSBORO, PA 19508
WATER	SHILLINGTON BOROUGH 2 E. LANCASTER AVENUE PO BOX 247 SHILLINGTON, PA 19607 MICHAEL MOUNTZ E-MAIL:MM@SHILLINGTONBORO.NET
GAS	UGI UTILITIES, INC. PO BOX 13009 READING, PA 19612-3009 PHONE NO.: 800-276-2722



Pipe	Pipe Encasement			Warning Tape	Trench Backfill Material	
	Bedding	Sides	Top		Pavement	Grass
Water						
DIP (6" Dia. or Greater)	6"	8"	12"	PennDOT #2A	No	PennDOT #2A Suitable Material
Copper (2" Dia. or Less)	4"	4"	4"	PennDOT #1B	No	PennDOT #2A Suitable Material
Sanitary Sewer						
PVC	6"	8"	12"	PennDOT #2B	No	PennDOT #2A Suitable Material
Gas						
HDPE (2" Of less)	6"	6"	6"	AASHTO #10	Yes	PennDOT #2A Suitable Material
Stormwater (Refer to Stormwater Pipe Installation Procedures)						
SLCPP (12" or Greater)	6"	12"	12"	PennDOT #2A	No	PennDOT #2A Suitable Material
PVC	6"	6"	6"	PennDOT #2B	No	PennDOT #2A Suitable Material
Electric						
PVC (2" or Less)	2"	2"	2"	Sand	Yes	PennDOT #2A Suitable Material

Notes:

- Pipe encasement material to be 3,000 psi concrete where noted on plan.
- DIP to be wrapped in plastic prior to concrete encasement.
- Warning tape to be magnetic and appropriately labeled for utility installed directly below.
- Warning tape to be installed approximately 12" below final grade.

LEGEND


PROPOSED LIGHT LOCATION, SEE ARCHITECTURAL DWGS. FOR DETAILS.

24 148.1

Pennsylvania One Call System, Inc.
Call Before You Dig in Pennsylvania
1-800-242-1776

State Law Requires
Construction Phase: Three working Days Notice
Design Phase: Ten working Days Notice
Facility Owners: Member of One Call System

SERIAL NO. #2010272169, SERIAL NO. #2010272189
SERIAL NO. #2010272250, SERIAL NO. #2010272251
SERIAL NO. #2010272292, SERIAL NO. #2010272341



DRAINAGE & UTILITY PLAN
CUMRU FIRE DEPARTMENT NEW BUILDING

Prepared For:
TOWNSHIP OF CUMRU

Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.





PROJECT #:
Z057000538

DRAWING #:
148.5

SHEET #:
8 OF 25

Jeffrey E. Skinner
PE-042652-E
SU-052889-E

8/11/2023 RC JES REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
07/21/2023 RC JES ADDED WATER METER PIT DETAIL
04/20/2023 RC JES NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION



LANDSCAPE NOTES

- THE TREES AND SHRUBS SHALL BE NURSERY GROWN IN A CLIMATE SIMILAR TO THAT OF THE LOCALITY OF THE PROJECT.
- THE CALIPER OF THE TRUNK, MEASURED AT A HEIGHT OF SIX (6) INCHES ABOVE FINISHED GRADE, SHALL BE A MINIMUM OF TWO (2) INCHES.
- ALL PLANTING SHALL BE PERFORMED IN CONFORMANCE WITH GOOD NURSERY AND LANDSCAPE PRACTICE INCLUDING PROPER GUYING AND STAKING.
- REQUIREMENTS FOR THE MEASUREMENTS, BRANCHING, GRADING, QUALITY, BALLING, AND BURLAPPING OF TREES SHALL FOLLOW THE CODE OF STANDARDS RECOMMENDED BY THE AMERICAN ASSOCIATION OF NURSERMEN, INC. IN THE AMERICAN STANDARD FOR NURSERY STOCK, ANSI Z60, 1-1973, AS AMENDED.
- LANDSCAPING PLAN SHALL INCLUDE FURNISHING AND INSTALLING MULCHED BEDS AND PLANTS MATERIALS SHOWN ON LANDSCAPING SCHEDULE AND COMPLYING WITH THE LANDSCAPING NOTES AND PLANTING DETAILS.
- PLANT MATERIAL SHALL COMPLY WITH ANSI Z60.1-1990. PLANT SIZES AND CONTAINER SIZES SHOWN ARE MINIMUM.
- CONTRACTOR SHALL LABEL AT LEAST ONE (1) PLANT OF EACH VARIETY WITH A SECURED, ATTACHED TAG BEARING THE LEGIBLE DESIGNATION OF BOTANICAL AND COMMON NAME TO HELP CONFIRM PLANT TYPE.
- SUBSTITUTIONS, ADDITIONS, AND DELETIONS ARE PERMISSIBLE UPON APPROVAL FROM THE LANDSCAPE ARCHITECT AND MUNICIPALITY.
- LANDSCAPING CONTRACTOR TO WARRANT LANDSCAPE PLANTS FOR A TWENTY-FOUR (24) MONTH PERIOD COMMENCING FIVE (5) DAYS FROM THE DATE OF INSPECTION OF THE PLANT MATERIALS INSTALLATION. CONTRACTOR TO WARRANT ALL PLANTS AGAINST DEFECTS INCLUDING DEATH AND UNSATISFACTORY GROWTH. ALL PLANTS SHALL BE IN WIGOROUS AND THRIVING CONDITION AT THE END OF THE TWENTY-FOUR (24) MONTH PERIOD. FINAL INSPECTION OF THE SITE FOLLOWING THE TWENTY-FOUR (24) MONTH PERIOD WILL BE MADE AS DETERMINED BY THE TOWNSHIP ENGINEER OR HIS DESIGNEE. PLANTS FOUND TO BE IN POOR HEALTH OR LACKING NORMAL GROWTH HABIT DURING THE TWENTY-FOUR (24) MONTH GUARANTEE PERIOD SHALL BE REPLACED WITH NURSERY-GROWN PLANTS, IN ACCORDANCE WITH THE APPROVED LANDSCAPE PLAN. WITHIN THIRTY (30) DAYS OF BEING NOTIFIED BY THE TOWNSHIP, IF NOTIFICATION IS MADE OUT OF SEASON, REPLACEMENTS SHALL BE MADE DURING THE NEXT PLANTING SEASON. IF THE ORIGINAL PLANTS DECLINE, SUBSTITUTE SPECIES ACCEPTABLE TO THE TOWNSHIP ENGINEER AND SUITABLE FOR THE SITE'S ENVIRONMENTAL CONDITIONS OR PLANTING SCHEME MAY BE USED AND REVISED LANDSCAPE PLAN SHALL BE FILED WITH THE TOWNSHIP ENGINEER AFTER INSTALLATION. ALL REPLACEMENT PLANTS SHALL BE SUBJECT TO A NEW TWENTY-FOUR (24) MONTH GUARANTEE PERIOD AND INSPECTIONS BY THE TOWNSHIP AS PRESCRIBED IN SUBSECTIONS 1 & 2 ABOVE.
- MULCH IS TO BE SHREDDED BARK. MULCH BED THICKNESS SHALL BE (TWO) 2 INCHES MINIMUM AFTER LIGHT TAMPING, EXCEPT THAT MULCH DEPTH AT ANNUAL FLOWERS SHALL BE 1-1/2". PLACE BED OVER WEED BARRIER MAT OR EQUAL, UNLESS NOTED OTHERWISE.
- ALL LANDSCAPE PLANTING SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH ACCEPTED PRACTICES AS RECOGNIZED BY THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION. PLANTING AND MAINTENANCE OF VEGETATION SHALL INCLUDE, BUT NOT NECESSARILY BE LIMITED TO, PROVISIONS FOR PRUNING, MULCHING, WEEDING, AND WATERING.
- THE APPLICANT GUARANTEES THAT ALL REQUIRED LANDSCAPE IMPROVEMENTS SHALL BE MAINTAINED IN A HEALTHY AND SOUND CONDITION, TO OTHERWISE BE REPLACED BY EQUIVALENT IMPROVEMENTS, FOR A PERIOD OF TWENTY-FOUR (24) MONTHS FOLLOWING TOWNSHIP INSPECTION / APPROVAL.
- GROUND COVER SHRUBS, HERBACEOUS PERENNIALS, BULBS AND ANNUALS SHALL BE SPACED SO THAT 100 PERCENT OF THE BEDS ARE COVERED AFTER 2 YEARS GROWTH.
- SHRUBS SHALL BE PLANTED BETWEEN SEPTEMBER 1 AND NOVEMBER 15, OR MARCH 1 AND MAY 31.
- PLACE "DEWITT 15 YEAR WEED BARRIER" WOVEN POLYPROPYLENE OR APPROVED EQUAL IN ALL PLANT BEDS AND AT EACH TREE RING.
- APPLY "SNAP SHOT 2.5 10" OF APPROVED EQUAL TO ALL PLANT BEDS AND TREE RINGS PER MANUFACTURER'S RECOMMENDATIONS PRIOR TO PLACEMENT OF FINAL PLANT BED/ TREE RING COVER.
- PLACE PLANT CENTER NO CLOSER THAN 3 FEET FROM EDGE OF RIGHT-OF-WAY.
- TREES SHALL NOT BE PLANTED WITHIN 10' OF GAS MAINS

KEY	QTY.	BOTANICAL NAME	COMMON NAME	SIZE/CAL.	ROOT
EVERGREEN SHRUBS					
B.M.	11	BUXUS MICROPHYLLA VAR. JAPONICA	WINTER GEM BOXWOOD	18" HEIGHT MINIMUM	NO. 2 CONTAINER
I.C.	10	ILEX CORNUTA 'CARISSA'	CARISSA HOLLY	18" HEIGHT MINIMUM	NO. 2 CONTAINER
I.M.	5	ILEX X MERSERVAE 'BLUE PRINCESS'	BLUE PRINCESS HOLLY	24" HEIGHT MINIMUM	NO. 2 CONTAINER
P.G.	12	PICEA GLAUCA 'NORTH STAR'	NORTH STAR DWARF WHITE SPRUCE	3" HEIGHT MINIMUM	B & B
DECIDUOUS SHRUBS					
HERBACEOUS PERENNIALS					
R.G.	10	RUBIACEAE GRADENIA JASMINOIDES RADICANS	CREeping DWARF GARDENIA	12" HEIGHT MINIMUM	NO. 2 CONTAINER
S.B.	14	SPIRAEA X BUMALDA 'RED DART'	RED DART SPIREA	18" HEIGHT MINIMUM	NO. 2 CONTAINER
S.N.	21	SPIRAEA NIPPONICA 'SNOWMOUNDS'	SNOWMOUNDS SPIREA	18" HEIGHT MINIMUM	NO. 2 CONTAINER

Pennsylvania One Call System, Inc.
Call Before You Dig in Pennsylvania
1-800-242-1776

State Law Requires Construction Phase: Three working Days Notice Design Phase: Ten working Days Notice Facility Owners: Member of One Call System

SERIAL NO. #20210272169, SERIAL NO. #20210272189
SERIAL NO. #20210272250, SERIAL NO. #20210272251
SERIAL NO. #20210272292, SERIAL NO. #20210272341

11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION
Date	Draft	Chkd	

LANDSCAPING PLAN & DETAILS
CUMRU FIRE DEPARTMENT NEW BUILDING
Prepared For:
TOWNSHIP OF CUMRU
Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.


Jeffrey E. Skinner
PE-042652-E
SU-052889-E


PROJECT #:
2057000538
DRAWING #:
148.6
SHEET #:
9 OF 25

ATLAS
920 GERMANTOWN PIKE, SUITE 200,
PLYMOUTH MEETING, PA 19462


THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

NOTE:
THE LANDSCAPING FOR BASIN #5, STEEP SLOPES, AND SWALES, SEE DRAWING POST-CONSTRUCTION STORMWATER MANAGEMENT GRADING PLAN, PAGE 183.






SOILS TYPE ON SITE		
LEGEND	NAME	DESCRIPTION
NaB	NESHAMING SILT LOAM	3 TO 8 PERCENT SLOPES
NaC	NESHAMING SILT LOAM	8 TO 15 PERCENT SLOPES
NhD	NESHAMING GRAVELLY SILT LOAM	8 TO 25 PERCENT SLOPES, EXTREMELY BOULDERY



EROSION & SEDIMENT CONTROL (E&S) LEGEND	
PH #2	PHASE #2 WORK BOUNDARY
1	CONSTRUCTION ENTRANCE
SB	SOIL BOUNDARY
NaC	SOIL TYPE
CSF	FILTER SOCK
IP	INLET PROTECTION
6	RIPRAP
4	EROSION CONTROL MATTING
7	TOP SOIL STOCK PIPE
7	STOCK PILE
1	TEMPORARY SEEDING STABILIZATION
1	FINAL SEEDING STABILIZATION
1	GRASS IN SPECIAL AREAS - SWALE, BASIN BOTTOM



THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDUM 4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

Date	Draft	Chkd	Issued For
11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION

EROSION & SEDIMENTATION CONTROL PLAN

CUMRU FIRE DEPARTMENT NEW BUILDING
 Prepared For: TOWNSHIP OF CUMRU
 Site: CUMRU TOWNSHIP, BERKS CO., PA.



Pennsylvania One Call System, Inc.
 Call Before You Dig in Pennsylvania 1-800-242-1776
 State Law Requires Construction Phase: Three working Days Notice Design Phase: Ten working Days Notice Facility Owners: Member of One Call System

SERIAL NO. #20210272169, SERIAL NO. #20210272189
 SERIAL NO. #20210272250, SERIAL NO. #20210272251
 SERIAL NO. #20210272292, SERIAL NO. #20210272341

Jeffrey E. Skinner
 PE-042652-E
 SU-052889-E



920 GERMANTOWN PIKE, SUITE 200, PLYMOUTH MEETING, PA 19462

PROJECT #: Z057000538
 DRAWING #: 166
 SHEET #: 10 Of 25

I. GENERAL

A. The contractor shall assure that the approved erosion and sediment control plan is properly and completely implemented. Before initiating any revisions to the approved erosion and sediment control plan or revisions to the plan which may affect the effectiveness of the approved E&S Control Plan, the operator must receive approval of the revisions from the Berks County Conservation District, 1238 County Welfare Road, Suite 200, Leesport, PA 19533-9710, Telephone number: (610) 372-4657 prior to beginning land disturbance. The contractor shall assure that an erosion and sediment control plan has been prepared, approved by the appropriate conservation district, and is being implemented and maintained for all soil and/or rock spoil and borrow areas, regardless of their locations. It shall be the responsibility of the contractor to implement this plan in the field and meet all state and local regulations pertaining to it. The contractor shall assign this responsibility to a person experienced in sediment and erosion control procedures. Modifications or deviations from this plan will be allowed only if the contractor first obtains written permission from the agencies having jurisdiction. A copy of this plan shall be kept at the project site.

1. All earth disturbances, including clearing and grubbing as well as cuts and fills shall be done in accordance with the approved E&S plan. A copy of the approved drawings must be available at the project site at all times. The reviewing agency shall be notified of any changes to the approved plan prior to implementation of those changes. The reviewing agency may require a written submittal of those changes for review and approval at its discretion.

2. At least 7 days prior to starting any earth disturbance activities, including clearing and grubbing, the owner and/or operator shall invite all contractors, the landowner, appropriate municipal officials, the E&S plan preparer, the PCSM plan preparer, the licensed professional responsible for oversight of critical stages of implementation of the PCSM plan, and a representative from the local conservation district to an on-site preconstruction meeting.

3. At least 3 days prior to starting any earth disturbance activities, or expanding into an area previously unmarked, the Pennsylvania One Call System Inc. shall be notified at 1-800-242-1776 for the location of existing underground utilities.

4. All earth disturbance activities shall proceed in accordance with the sequence provided on the plan drawings. Deviation from that sequence must be approved in writing from the local conservation district or by the Department prior to implementation.

5. Areas to be filled are to be cleared, grubbed, and stripped of topsoil to remove trees, vegetation, roots and other objectionable material.

6. Clearing, grubbing, and topsoil stripping shall be limited to those areas described in each stage of the construction sequence. General site clearing, grubbing and topsoil stripping may not commence in any stage or phase of the project until the E&S BMPs specified by the BMP sequence for that stage or phase have been installed and are functioning as described in this E&S plan.

7. At no time shall construction vehicles be allowed to enter areas outside the limit of disturbance boundaries shown on the plan maps. These areas must be clearly marked and fenced off before clearing and grubbing operations begin.

8. Topsoil required for the establishment of vegetation shall be stockpiled at the location(s) shown on the plan maps(s) in the amount necessary to complete the final grading of all exposed areas that are to be stabilized by vegetation. Each stockpile shall be protected in the manner shown on the plan drawings. Stockpile heights shall not exceed 35 feet. Stockpile slopes shall be 2H:1V or flatter.

9. Immediately upon discovering unforeseen circumstances posing the potential for accelerated erosion and/or sediment pollution, the operator shall implement appropriate best management minimize the potential for erosion and sediment pollution and notify the local conservation district and/or the regional office of the Department.

10. All building materials and wastes shall be removed from the site and recycled or disposed of in accordance with the Department's Solid Waste Management Regulations at 25 Pa. Code 260.1, et seq., 271.1, and 287.1, et seq. No building materials or wastes or unused building materials shall be burned, buried, dumped, or discharged at the site.

11. All off-site waste and borrow areas must have an E&S plan approved by the local conservation district or the Department fully implemented prior to being activated.

12. The contractor is responsible for ensuring that any material brought on site is clean fill. Form FP-001 must be retained by the property owner for any fill material affected by a spill or release of a regulated substance but qualifying as clean fill due to analytical testing.

13. All pumping of water from any work area shall be done according to the procedure described in this plan, over undisturbed vegetated areas.

14. Vehicles and equipment must enter directly and exit directly through the construction entrance.

15. Until the site is stabilized, all erosion and sediment BMPs shall be maintained properly. Maintenance shall include inspections of all erosion and sediment BMPs after each runoff event and on a weekly basis. All preventative and remedial maintenance work, including clean out, replacement, regrading, reseeding, mulching and renetting must be performed immediately. If the E&S BMPs fail to perform as expected, replacement BMPs, or modifications of those installed will be required.

16. The maintenance instruction should specify that inspection be logged on DEP form 3800-BM-FM02074. This log showing dates that E&S BMPs were inspected as well as any deficiencies found and the date they were corrected shall be maintained on the site and be made available to regulatory agency officials at the time of inspection.

17. Sediment trapped onto any public roadway or sidewalk shall be returned to the construction site by the end of each work day and disposed in the manner described in this plan. In no case shall the sediment be washed, shoveled, or swept into any roadside ditch, storm sewer, or surface water.

18. All sediment removed from BMPs shall be disposed of in the manner described on the plan drawings.

19. Areas which are to be topsoiled shall be scarified to a minimum depth of 3 to 5 inches - 6 to 12 inches on compacted soils - prior to placement of topsoil. Areas to be vegetated shall have a minimum 4 inches of topsoil in place prior to seeding and mulching. Fill out slopes shall have a minimum of 2 inches of topsoil.

20. All fills shall be compacted as required to reduce erosion, slippage, settlement, subsidence or other related problems. Fill intended to support buildings, structures and conduits, etc. shall be compacted in accordance with local requirements or codes.

21. All earthen fills shall be placed in compacted layers not to exceed 9 inches in thickness.

22. Fill materials shall be free of frozen particles, brush, roots, sod, or other foreign or objectionable materials that would interfere with or prevent construction of satisfactory fills.

23. Frozen materials or soft, mucky, or highly compressible materials shall not be incorporated into fills.

24. Fill shall not be placed on saturated or frozen surfaces.

25. Seeps or springs encountered during construction shall be handled in accordance with the standard and specification for subsurface drain or other approved method.

26. All graded areas shall be permanently stabilized immediately upon reaching finished grade. Cut slopes in competent bedrock and rock fills need not be vegetated.

27. At stream crossing, a 50-foot buffer shall be maintained, on buffers, clearings, sod disturbances and excavations, equipment traffic should be minimized. Activity such as stacking logs, burning cleared brush, discharging rainwater from trenches, welding pipe sections, refueling and maintaining equipment should be avoided within buffer zones.

28. Immediately after earth disturbance activities cease in any area or subarea of the project, the operator shall stabilize all disturbed areas. During non-germinating months, mulch or protective blanketing shall be applied as described in the plan. Areas not at finished grade, which will be reactivated within 1 year, may be stabilized in accordance with the temporary stabilization specifications. Those areas which will not be reactivated within 1 year shall be stabilized in accordance with the permanent stabilization specifications.

29. Permanent stabilization is defined as a minimum uniform, perennial 70% vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated erosion. Cut and fill slopes shall be capable of resisting failure due to slumping, sliding, or other movements.

30. E&S BMPs shall remain functional as such until all areas tributary to them are permanently stabilized or until they are replaced by another BMP approved by the local conservation district or the Department.

31. Upon completion of all earth disturbance activities and permanent stabilization of all disturbed areas, the owner and/or operator shall contact the local conservation district for an inspection prior to removal/conversion of the E&S BMPs.

32. After final site stabilization has been achieved, temporary erosion and sediment BMPs must be removed or converted to permanent post construction stormwater management BMPs. Areas disturbed during removal or conversion of the BMPs shall be stabilized immediately. In order to ensure rapid revegetation of disturbed areas, such removal/conversions are to be done only during the germinating season.

33. Upon completion of all earth disturbance activities and permanent stabilization of all disturbed areas, the owner and/or operator shall contact the local conservation district to schedule a final inspection.

34. Failure to correctly install E&S BMPs, failure to prevent sediment-laden runoff from leaving the construction site, or failure to take immediate corrective action to resolve failure of E&S BMPs may result in administrative, civil, and/or criminal penalties being instituted by the Department as defined in Section 602 of the Pennsylvania Clean Streams Law. The Clean Streams Law provides for up to \$10,000 per day in civil penalties, up to \$10,000 in summary criminal penalties, and up to \$25,000 in misdemeanor criminal penalties for each violation.

B. Stockpile

1. All striped topsoil and excavated earthen material from the project site shall be properly stockpiled in accordance with the "stockpile control" detail. Material found to be unsuitable for subsequent use or in excess of the quantity required shall be disposed of. The location, method of disposal, and means of transport shall be in accordance with state and local laws.

2. All soil that is to be stockpiled for a period of greater than 10 calendar days shall be temporarily stabilized as described in item iii. "Temporary Stabilization."

3. Stockpile heights must not exceed 35 feet, stockpile slopes must be 2:1 or flatter.

4. Silt fence shall be provided at the base of all stockpiles for additional protection. See "Stockpile Control" detail.

II. EROSION AND SEDIMENT CONTROL MEASURES

A. Rock Construction Entrance

1. A rock construction entrance shall be provided as needed to prevent the tracking or flow of sediment onto areas other than the immediate project site. See "Stabilized Construction Entrance" detail.

2. Rock construction entrance thickness will be constantly maintained to the specified dimensions by adding rock. A stockpile of rock material will be maintained on the site for this purpose. At the end of each construction day, all sediment deposited on public roadways will be removed and returned to the construction site.

B. PRESERVATION OF EXISTING VEGETATION

1. GOOD STANDARDS OF EXISTING VEGETATION ADEQUATE TO CONTROL EROSION SHOULD BE PRESERVED WHEREVER POSSIBLE. REGENERATION OF WOOD PLANTS SHOULD BE ENCOURAGED WHERE ACCEPTABLE. NEW VEGETATION, SOIL TREATMENTS, ETC. SHALL BE DONE AS SPECIFIED ON THE DRAWINGS AND IN THE APPLICABLE SECTIONS OF THE SPECIFICATIONS.

C. COMPOST FILTER SOCK

1. SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1 OF THE PA DEP EROSION CONTROL MANUAL. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2 OF THE PA DEP EROSION CONTROL MANUAL.

2. COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY BARRIER SHALL NOT EXCEED THAT SPECIFIED FOR THE SIZE OF THE SOCK AND THE SLOPE OF ITS TRIBUTARY AREA.

3. TRAFFIC SHALL NOT BE PERMITTED TO CROSS COMPOST FILTER SOCKS.

4. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE BARRIER AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.

5. COMPOST FILTER SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER AND/OR REPLACED WITHIN 24 HOURS OF INSPECTION.

6. BIODEGRADABLE COMPOST FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER.

7. UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

D. INLET FILTER BAG

1. INLET FILTER BAGS SHOULD BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. FILTER BAGS SHOULD BE CLEANED AND/OR REPLACED WHEN THE BAG IS HALF FULL OR WHEN FLOW CAPACITY HAS BEEN REDUCED SO AS TO CAUSE FLOODING OR BYPASSING OF THE INLET.

2. ACCUMULATED SEDIMENT SHOULD BE DISPOSED IN THE APPROVED MANNER. BAGS THAT WILL BE REUSED SHOULD BE RINSED AT A LOCATION WHERE THE RINSE WATER WILL ENTER A SEDIMENT TRAP OR SEDIMENT BASIN.

3. NEEDED REPAIRS SHOULD BE INITIATED IMMEDIATELY AFTER THE INSPECTION.

4. DAMAGED FILTER BAGS SHOULD BE REPLACED. A SUPPLY SHALL BE MAINTAINED ON SITE FOR REPLACEMENT OF BAGS.

5. AT A MINIMUM, THE FABRIC SHALL HAVE A MINIMUM GRAB TENSILE STRENGTH OF 120 LBS, A MINIMUM BURST STRENGTH OF 200 PSI, AND A MINIMUM TRAPEZOIDAL TEAR STRENGTH OF 50 LBS. FILTER BAGS SHALL BE CAPABLE OF TRAPPING ALL PARTICLES NOT PASSING A NO. 40 SIEVE.

E. PUMPED WATER

1. SEDIMENTS FILTER BAG SHALL BE INSTALLED AT PUMP DISCHARGE TO FILTER PUMPED WATER IN ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS. BAG SHALL FILTER PARTICLES LARGER THAN 150 MICRONS AND BE MANUFACTURED FROM NON-WOVEN GEOTEXTILE MATERIAL.

2. A MINIMUM OF ONE CUBIC FOOT OF STORAGE CAPACITY FOR EACH GALLON PER MINUTE OF THE DEWATERING PUMPING RATE SHALL BE PROVIDED TO INSURE STRUCTURE FAILURE WILL NOT OCCUR.

F. PUMPED WATER FILTER BAG

1. LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

Table with 3 columns: PROPERTY, TEST METHOD, MINIMUM STANDARD. Rows include AVG. WIDE WIDTH STRENGTH, GRAB TENSILE, PUNCTURE, MULLEN BURST, UV RESISTANCE, and AOS % RETAINED.

2. A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.

3. BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5% FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS.

4. NO DOWN SLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HO OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.

5. THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE.

6. THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.

7. FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

G. COMPOST SOCK WASHOUT

1. Concrete washout activities must be conducted in a manner that does not contribute pollutants to surface waters or stormwater runoff.

2. Wherever compost sock washouts are used, a suitable impervious geomembrane should be placed at the location of the washout. Compost socks should be staked in the manner recommended by the manufacturer around perimeter of the geomembrane so as to form a ring with the ends of the sock located at the up slope corner (Figure 3.18). Care should be taken to ensure continuous contact of the sock with the geomembrane at all locations. Where necessary, socks may be stacked and staked so as to form a triangular cross-section.

3. Washout facilities should not be placed within 50 feet of storm drains, open ditches or surface waters. They should be in a convenient location for the trucks, preferably near the place where the concrete is being poured, but far enough from other vehicular traffic to minimize the potential for accidental damage or spills. Wherever possible, they should be located on slopes not exceeding a 2% grade.

4. Part of inspecting and maintaining washout areas is ensuring that adequate signage is provided and in good repair and that the washout area is being used, as opposed to washout in non-designated areas of the site.

5. Remove concrete waste in the washout area, as needed to maintain BMP function (typically when filled to about two-thirds of its capacity). Collect concrete waste and deliver offsite to a designated disposal location.

6. Upon termination of use of the washout site, accumulated solid waste, including concrete waste and any contaminated soils, must be removed from the site to prevent on-site disposal of solid waste. If the wash water is allowed to evaporate and the concrete hardens, it may be recycled.

III. TEMPORARY STABILIZATION

A. All areas disturbed by on-site work that will not be constructed immediately shall be temporarily stabilized:

1. Vegetative cover Temporary vegetative cover shall be provided in areas requiring temporary stabilization during construction, as follows:

A. Fertilizer: apply 10-20-20 fertilizer or equivalent at the rate of 150 lbs per acre.

B. Limestone: shall be an agricultural grade lime stone equivalent to 50% Calcium plus Magnesium oxides, and applied at the rate of 1 ton per acre.

C. Seed type shall be as indicated below:

1. Optimum seeding dates are February 15 through May 1 or August 15 through October 15 for the following species:

Table with 3 columns: Species, Pounds Per acre, Optimum seed depth (double for sandy soil). Rows include Annual Ryegrass, Perennial Ryegrass, Oats, Barley, Pearl Millet, Sudan Grass, Millet (German or Hungarian), Weeping Lovegrass.

2. Optimum seeding dates are May 1 through August 15 for the following species:

Table with 3 columns: Species, Pounds Per acre, Optimum seed depth (double for sandy soil). Rows include Pearl Millet, Sudan Grass, Millet (German or Hungarian), Weeping Lovegrass.

2. Mulching

A. Mulching shall be provided as required in areas difficult to vegetate, and during Off-season operations. Mulching methods and materials shall conform to the following:

(1) Mulch materials shall be unrattled salt hay, hay or small grain straw applied at the rate of 3 tons per acre. Mulch blowers shall not grind or chop the material.

(2) Mulch shall be spread uniformly by hand or mechanically so that approximately 75% to 95% of the soil surface will be covered.

(3) Mulch anchoring shall be accomplished immediately after placement to minimize loss by wind or water. This may be done by one of the following methods, depending upon the size of slopes and costs.

(a) Peg and twine - drive 8 to 10 inch pegs to within 2 to 3 inches of the soil surface every 4 feet in all directions. Stakes may be driven before or after applying mulch. Secure mulch to soil surface by stretching twine between pegs in a criss-cross and a square pattern, secure twine around each peg with two or more round turns.

(b) Mulch netting - staple paper, jute, cotton or plastic netting to the soil surface. Use a degradable netting in areas to be mowed.

(c) Liquid mulch binders - may be used to anchor salt hay, hay or straw mulches.

(d) Applications should be heavier at edges where wind catches the mulch, in valleys and at crests of banks. Remainder of area should be uniform in appearance.

(e) Wood-fiber or paper-fiber mulch at the rate of 1,500 pounds per acre may be applied by a hydroseeder. Use is limited to flatter slopes and during optimum seeding periods in spring and fall.

3. Other

A. Where excessive soil erosion, tracking, or flowing of sediment is evident or anticipated, a minimum of 4 inches of crushed stone shall be placed within the affected area and maintained until permanent stabilization is provided. Additional stone shall be placed as required until stabilization is achieved. Crushed stone shall conform to AASHTO Designation M43, size No. 2 (2-1/2" to 1-1/2").

B. Upon completion of an earth disturbance activity or any stage or phase of an activity, the operator shall stabilize immediately the disturbed areas to protect from accelerated erosion. During non-germinating periods, mulch must be applied at the specified rates. Disturbed areas which are not at finished grade, and which will be reactivated within 1 year, may be stabilized in accordance with Temporary Seeding Specifications. Disturbed areas, which are either at finished grade or will not be reactivated within 1 year, must be stabilized in accordance with Permanent Seeding Specifications.

C. Diversion channels, sedimentation basins, sediment traps, and stockpiles must be stabilized immediately.

D. Mulch with mulch control netting or erosion blankets must be installed on all slopes greater than 3:1.

IV. FINAL SEEDING

A. GENERAL

1. NO MORE THAN 15,000 SQUARE FEET OF DISTURBED AREA SHALL ACHIEVE FINAL GRADE BEFORE STABILIZATION BY VEGETATIVE COVER WITH SEEDING AND MULCHING.

2. AFTER THE CONSTRUCTION PHASE IS COMPLETE, PERMANENT VEGETATION ON THE AREAS THAT HAVE BEEN DISTURBED SHALL BE REESTABLISHED AS RAPIDLY AS POSSIBLE. IF THE COMPLETION OF THE CONSTRUCTION ACTIVITIES DOES NOT COINCIDE WITH A SEASON IN WHICH PERMANENT VEGETATION CAN BE STARTED, AN INTERIM OR TEMPORARY PROGRAM IS REQUIRED. THIS SHALL INCLUDE SOIL STABILIZATION, MULCHING OR THE ESTABLISHMENT OF FILTER STRIPS. IN ANY CASE, SEDIMENT AND EROSION CONTROLS SHALL BE INSTALLED PROMPTLY AND THEIR MAINTENANCE ASSURED.

4. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM OF 70% UNIFORM PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING OR OTHER MOVEMENTS.

5. AT A MINIMUM, PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED BY PROVIDING THE FOLLOWING:

a. FERTILIZER: 500 LBS PER ACRE OF 10-20-20, OR EQUIVALENT.

b. LIMESTONE: SHALL BE AN AGRICULTURAL GRADE LIME STONE EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDES, AND APPLIED AT THE RATE OF 4 TONS PER ACRE.

c. PERMANENT SEEDING (MINIMUM REQUIREMENTS) SHALL BE AS FOLLOWS:

V. MAINTENANCE

A. Inspection shall be made at frequent intervals and after each storm event to detect any impairment in the ability of the erosion control facilities, installed as part of this plan, to continue to function effectively.

Table with 5 columns: Species, % BY WEIGHT, MINIMUM % PURITY, MINIMUM % GERMINATION, MAXIMUM % WEED SEED. Rows include Kentucky bluegrass, Pennine Perennial Rye Grass, Pennlawn and Fescue, Kentucky 31 Tall Fescue, Pennine Perennial Rye Grass.

B. The approved erosion and sediment control plan and any standard conditions relating to soil erosion and sediment control, issued as part of any permits, shall be available at the immediate site of construction activity at all times.

C. Until the site is stabilized, all erosion and sedimentation controls must be maintained properly. Maintenance must include inspection of all erosion and sedimentation controls after each storm event and on a weekly basis. All preventative and remedial maintenance work, including clean out, repair, replacement, regrading, reseeding, mulching and renetting must be performed immediately.

VI. EXCAVATED TRENCH OPEN

*The total length of excavated trench open at any one time should not be greater than the total length of the utility line that can be placed in the trench and back-filled in one working day. No more than 50 lineal feet of open trench should exist when utility line installation ceases at the end of the workday. Soil supplements, seed and much must be applied according to 25 Pa. Code §102.22. (Page 283 of E&S Manual).

VII. SEQUENCE OF EARTH MOVING RELATED ACTIVITY

2 166.1

- 1. Pre-Construction Stage: a. Field-marks limits of disturbance and environmentally sensitive areas. b. At least 7 days prior to starting any earth disturbance activities (including clear and grubbing), the Owner and/or Operator shall invite all Contractors, the Landowner, appropriate Municipal Officials, the E&S plan preparer, the PCSM plan preparer, and a representative from the Bucks County Conservation District to an on-site reconstruction meeting. c. Upon installation or stabilization of all perimeter sediment control BMP's and at least 3 days prior to proceeding with the bulk earth disturbance activities, the permittee of co-permittee shall provide notification to the department or authorized conservation district. d. At least 3 days prior to starting any earth disturbance activities, or expanding into an area previously unmarked, the Pennsylvania One Call System Inc. shall be notified at 1-800-242-1776 for the location of existing underground utilities. e. All earth disturbance activities shall proceed in accordance with the sequence provided on the plans. Deviation from the sequence must be approved by the Bucks County Conservation District or by the department prior to implementation. Each step of sequence shall be completed before proceeding to the next step, except where noted.

2. Construction Activity: a. Convert the existing 150-foot Rock Construction Access #1 to Rock Construction Access with Wash Rock, where as depicted on the plan. b. Install Rock Construction Access #2 with Wash Rock and Concrete Washouts, see drawing. c. Access to site's E&S BMPs, see drawings for work areas. i. Install Compost Filter Sock as depicted on the plan. ii. Install Inlet Protection per plan. iii. Install Orange Construction Fence around the basins per plan.

d. Site Operation for earthwork: i. Bring the proposed Building pad grades to the proper elevation. Construction new Building. ii. All building materials and wastes must be removed from the site and recycled or disposed of in accordance with the Pennsylvania Department of Environmental Protection's Solid Waste Management Regulations at 25pa. Code §260.1 et seq., §271.1 et seq., and §287.1 et seq. No building material or wastes or unused building materials shall be burned, buried, dumped, or discharged at the site. iii. Install all existing utilities, see "note **" below.

iv. Critical Stage: Remove sediment traps by digging the areas to the proposed grade. Sediment trap #3A becomes swale #3A/B and part of basin #6 and sediment trap #4A becomes swale #4A/B and part of basin #6. See dwg. #183 notes on converting sediment traps into basin 5. v. Critical Stage: Construct basin #5 and basin #6. Stabilize basin #5 steep slope with E&S blankets. Additional notes detailing Basin #5 & Basin #6 construction shown on dwgs. 183.4 & 183.6. vi. Install stormwater inlets and pipes. Install Inlet Protection on all new inlets and stabilize areas. See "note **" below. vii. Construct all swales and stabilize with temporary seeding. viii. Construction proposed parking lot wall.

iii. Final Seeding with Temporary Seeding: Construction new sidewalk and proposed walls. Install subbase stone course on parking lot and all driveways. Then install parking lot and driveways with binder course. e. Permanent stabilization stage: i. Replacement of top soil (4-6 inches) and install all permanent vegetation requirements. ii. Permanent seeding and mulch all areas. An area shall be considered to have achieved final stabilization when it has a minimum of 70% uniform perennial vegetative cover or other permanent non-vegetative cover with density sufficient to resist accelerated surface erosion and off-subsurface characteristics sufficient to resist sliding or other movements. Topsoil shall be replaced to predevelopment depths or to a minimum depth of 6 inches, whichever is greater. It is also recommended that soil tests be performed in order to determine actual lime and fertilizer needs instead of providing a generic application rate. iii. Clean binder course of parking lot and all driveway surfaces and install wearing course on all surfaces.

- 3. Removal/Conversion of temporary sediment pollution controls stage: a. Prior to removal of the E&S bmp's, the Berks County Conservation District should be contacted. The district may require a site inspection prior to the conversion or removal of BMP's. b. Remove all E&S BMPs when the work area is at a minimum of 70% uniform perennial vegetative cover or trench backfill paving is complete. c. Remove all filter sock and other temporary soil erosion and sediment control facilities after all areas have been permanently stabilized. Areas disturbed during removal of the controls must be stabilized immediately. An area shall be considered to have achieved final stabilization when it has a minimum of 70% uniform perennial vegetative cover or other permanent non-vegetative cover with density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding or other movements. Topsoil shall be replaced to predevelopment depths or to a minimum depth of 6 inches, whichever is greater. It is also recommended that soil tests be performed in order to determine actual lime and fertilizer needs instead of providing a generic application rate. d. Within 30 days after the completion of earth disturbance activities authorized by this permit, including the permanent stabilization of the site and proper installation of PCSM BMPs in accordance with the approved PCSM Plans, or upon submission if NOT sooner, the permittee shall file with the department or authorized conservation district a statement signed by a licensed professional and by the permittee certifying that work has been performed in accordance with the terms and conditions of the permit and the work approved erosion and sedimentation and post construction stormwater management plans. Completion certificated are needed to ensure that all is performed in accordance with the terms and conditions of the permit and the approved E&S and PCSM Plans.

Note: Critical Stage, the design engineer shall be on site.

Note *: "The total length of excavated trench open at any one time should not be greater than the total length of the utility line that can be placed in the trench and back-filled in one working day. No more than 50 lineal feet of open trench should exist when utility line installation ceases at the end of the workday. Soil supplements, seed and much must be applied according to 25 Pa. Code §102.22. (Page 283 of E&S Manual)."

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS BOTH THE DRAWINGS AND THE PROJECT MANUAL AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

Table with 4 columns: Date, Draft, Chkd, Issued For Bids. Rows include 08/11/2023, 04/20/2023, and 08/11/2023.

EROSION & SEDIMENTATION CONTROL NOTES
CUMRU FIRE DEPARTMENT NEW BUILDING
Prepared For: TOWNSHIP OF CUMRU
Situate In: CUMRU TOWNSHIP, BERKS CO., PA.
PROJECT #: Z057000538
DRAWING #: 166.1
SHEET #: 11 Of 25
Jeffrey E. Skinner
PE-042652-E
SU-052889-E
920 GERMANTOWN PIKE, SUITE 200, PLYMOUTH MEETING, PA 19462

PREPAREDNESS, PREVENTION AND CONTINGENCY PLAN NOTES

This plan is part of the NPDES permit application for the discharge of stormwater associated with construction activities and the related Erosion and Sediment Control Plan. It is required to comply with Chapter 101.3(b) of the Rules and Regulations of the Pennsylvania Department of Environmental Protection, and conditions under the NPDES permit.

- 1. Name of Permittee: Cumru Township
Name of Co-permittee (contractor): TBD
2. Name of Project: Reed Street Utility Extension
3. Project Location: Mohnton, Berks County, PA
4. List name(s) and telephone number(s) of responsible Cumru Township officials to be contacted in case of emergency (to be confirmed at pre-construction meeting):
5. List name and telephone number of the following: Bucks County emergency management; Nearest fire department station; Nearest hospital;
6. Notification to the following agencies must be made immediately in the event of a spill of any polluting substances.
7. List name and telephone number of any downstream water users, including drinking water supplies, industrial intakes and agricultural uses.

- 8. General Description of Construction Activity.
Re-grading and realignment of Welsh Road. Replace sanitary and storm sewers along Welsh Road and sanitary from border of Mohnton Borough along Reed Street. Extension of gas on water main from intersection of Main Street and Fairview Ave. to Welsh Road.
See NPDES permit drawings

- 9. Material and Waste Inventory
A. Pesticides and herbicides*
B. Fertilizer*
C. Other chemicals, such as paints, detergents, acids for cleaning, solvents, soil additives, concrete curing compounds;
D. Petroleum based products
Note: It is not anticipated that gasoline, diesel fuel, lubricating oils, etc. will be stored onsite.

- 10. List the types and quantities of absorbent materials used for spill mitigation that are stored on premises. The quantities of absorbent booms, pads and other materials and equipment needed to contain spills and begin cleanup must be kept at the site.

A selection of absorbent socks, mat pads, barrel top pads, etc., of various sizes will be kept onsite by the contractor.

- 11. During concrete work, steps shall be taken to assure that no pollution enters waterways. Concrete mixer truck washings shall be deposited onsite into a container specially designed for the purpose.

- 12. Particular attention shall be given to equipment refueling operations. Refueling shall only occur as far upslope on the site as practicable.

- 13. The site shall be inspected daily for evidence of existing or potential spills or leaks, vandalism, and the condition and quantity of cleanup materials.

- 14. Material Management Practices
The following material management practices shall be used to reduce the risk of spills or other accidental discharge of materials and substances to storm water runoff:

- A. Good Housekeeping:
The following good housekeeping practices shall be followed onsite during construction:
- All efforts shall be made to store only enough products onsite as are required to do the job.
- Materials stored onsite shall be stored in a neat, orderly manner in appropriate containers and, if possible, under a roof or other enclosure.
- Products shall be kept in their original containers with the original manufacturer's label.
- Substances shall not be mixed with one another unless recommended by the manufacturer.
- Whenever possible, all of a product shall be used up before disposing of the container.
- Manufacturer's recommendations for proper use and disposal shall be strictly followed.
- The contractor's site superintendent shall perform daily inspections to ensure proper use and disposal of materials onsite.
- At least once per month, the contractor's safety consultant shall inspect the premises to confirm conformance to all OSHA regulations.

- B. Hazardous Products:
The practices described below shall be used to reduce the risks associated with hazardous materials:
- Products shall be kept in their original containers unless they are not resealable.
- Original labels and material safety data sheets (MSDS's) shall be retained at the jobsite.
- If surplus materials must be disposed of, manufacturer's or local and State recommended methods for proper offsite disposal shall be followed.

- 15. Product-Specific Practices
The following product-specific practices shall be followed onsite:

- A. Petroleum Products:
All onsite vehicles and equipment shall be monitored daily for leaks and shall receive regular preventive maintenance to reduce the chance of leakage. Petroleum products shall be stored in tightly-sealed containers which are clearly labeled. Any asphaltic material used onsite shall only be applied according to the manufacturer's recommendations.

- B. Fertilizers:
Fertilizers used shall be applied only in the minimum amount recommended by the manufacturer. Once applied, fertilizer shall be worked into the soil to limit exposure to stormwater. Storage shall be in a covered shed. The contents of any partially-used bags of fertilizer shall be immediately transferred to a sealable plastic bin to avoid spills.

- C. Chemical/Paints:
All containers shall be tightly sealed and stored when not in use. Excess paint shall not be disposed of in the storm sewer system, it shall be properly disposed of according to the manufacturer's instructions or per State and local requirements.

- D. Concrete Truck Washout Materials:
Concrete truck washout materials shall be deposited onsite into a container specifically designed for the purpose. The container shall be located in a specific area as far upslope on the site as practicable to best prevent migration of materials into streams, drainage ways or storm sewers. Once cured and hardened, the concrete shall be removed from the site and properly disposed of.

- 16. Spill Prevention Practices
In addition to the good housekeeping and material management practices described above, the following practices shall be followed for spill prevention and cleanup:
- The manufacturer's recommended methods for spill cleanup shall be clearly posted, and site personnel shall be trained in the proper procedures and the location of the information and cleanup supplies.
- Materials and the equipment necessary for spill cleanup shall be kept onsite. Equipment and materials shall include, but not limited to: Brooms, dust pans, mops, rags, gloves, goggles, absorbent granular material, sand, sawdust, and plastic and metal trash containers specifically for this purpose.
- All spills shall be cleaned up immediately after discovery.
- The spill area shall be kept well ventilated and personnel shall wear appropriate protective clothing to prevent contact with a hazardous substance.
- All spills of toxic or hazardous material, regardless of the size of the spill, shall be reported immediately via text, email or in writing to the Engineer, the Owner, and the appropriate local and State government agencies.
- The spill prevention plan shall be revised to include measures to prevent any type of spill from recurring, and to confirm how to clean up a spill if there is another one. A description of the spill, what caused it, and the cleanup measures used shall also be included in the written spill report.
- The contractor's site superintendent responsible for the day-to-day site operations shall be the project's spill prevention and cleanup coordinator. The superintendent shall designate at least three (3) other site personnel, who shall receive spill prevention and cleanup training. The names and cell phone numbers of these responsible spill personnel shall be posted prominently onsite. These individuals shall each be made responsible for a particular phase of spill prevention and cleanup.

- 17. Site Security
All materials requiring security shall be kept locked within secure containers stored in a designated secure area.

- 18. All construction and site activities shall be performed in accordance with the specifications and plans approved by the appropriate governmental authorities. Activities may also be monitored and inspected by the municipal engineer, related agency inspectors, and the municipal water/sewer authorities.

EROSION & SEDIMENT CONTROL (E&S) PLAN NARRATIVE

E&S Plan Planning & Design 102.4(b)(4)
The E&S Plans are separate from the PSCM Plans and are labeled "E&S Plan" and are the final plans to be used during construction.

Documentation that the E&S Plans was prepared by a person trained and experienced in E&S design methods and techniques applicable to the size and scope of the project is provided in ATTACHMENT C.
The temporary erosion control measures provided during construction and restoration activities are designed to minimize soil loss, prevent pollution of Siliwater Run near the municipal campus and the unnamed tributary at the Ashley Run Clean Soils Site, both tributaries to Angelica Creek, in addition to the tributaries to Wyomissing Creek along Reed Street. These controls will also protect adjacent properties, and maximize protection of existing drainage features and vegetation.

The following measures and Best Management Practices (BMP's) shown on the E&S Plans must be incorporated throughout the project's construction by the contractor:

- Limiting areas of disturbance, and preservation of existing vegetation wherever possible
- Temporary seeding and mulching applied immediately to all disturbed areas
- Proper silt fence and/or filter sock sediment barrier installation and maintenance
- Stabilized construction entrance installation and maintenance
- Restricting construction traffic to the site disturbed areas and stone driveways
- Pumped water filter bag installation and maintenance
- Erosion control matting along stream banks and steep slopes as needed
- Filter bag/stone & block inlet protection installation and maintenance

- The above measures, shown throughout the E&S Plans will:
a Minimize the extent and duration of earth disturbance;
a Maximize protection of existing site drainage features and vegetation;
a Minimize soil compaction; and
a Control/minimize the generation of increased stormwater runoff.

Existing topographic features of the project site and the immediate surrounding area §102.4(b)(5)(i)
The topography of the project site is shown on the drawings, by use of contours at one-foot intervals. A USGS quadrangle location map is provided in ATTACHMENT D and on the plan cover sheet.

The project drawings incorporate both construction and E&S information on the E&S plan to aid the contractor in compliance with E&S requirements during construction.

Soil Types, depth, slope, locations and limitations §102.4(b)(5)(ii)
The maps of soil types and limits related to the project were identified using the NRCS Web Soil Survey website. The soil survey map pertaining to the project is provided in ATTACHMENT E1 and E2 and soil boundaries are shown on the drawings.

Per the PADEP E&S Chapter 102 Manual, Appendix E, there are no limitations listed for Urban land, Joanna complex (UpD). Other soils at the site can be used to determine the properties of this urban land. Soil at the project site include Neshaminy Silt Loam (NaB and NaC), Neshaminy gravelly silt loam (NhD) and the site is bordered by Brecknock channery silt loam (BpD). The table below describes the expected limitations for these soils.

Table with 3 columns: Map Unit Symbol, Map Unity Name, Limitations. Rows include BpB, BpC, NaB, NaC, NaD, NhD, UpB, UpD.

These limitations can be addressed with proper shoring of bulk excavations and use of trench boxes for linear excavations, the coating of exposed concrete and steel proposed for underground service, and standard pumping of water from excavations.

Preliminary sampling and testing of representative soils is being performed concurrently with the submittal of this application. Once construction starts, further sampling and testing will be performed on the underlying soils. Test results will be presented upon receipt and will be used in determining the proper disposal method for exported fill materials.

Since there are only a few construction-related notes on the plans, it is requested that it be deemed acceptable that the Construction Plans are included in the E&S and PSCM (Restoration) Plan set. This provides better coordination to the contractor than having two separate plan sets in the field. Every effort has been made to ensure that the plan information shown is complete and legible.

Past, present and proposed land uses and proposed alteration to project site §102.4(b)(5)(iii)

From review of available online historical mapping, the past use(s) for the project sites for the prior fifty years indicate that the uses have been farming, vacant, residential homes, and roadways.

The present land use for the past five years has not changed. The proposed work during Phase 1 includes along E Fairview Street, Cedar Street, Reed Street, and Church Road will include with restoration of the existing residential (paved street) to existing conditions. Proposed work along Welsh Road includes raising the elevation of the road at the conclusion of utility line installation and replacement. Land to the west of Welsh Road will be regraded and a fire station built upon it.

The proposed work during Phase 2 includes the construction of a new fire station with driveways and parking as well as stormwater management features to address the increase in runoff due to the new impervious surfaces connected to features installed in Phase 1.

Volume and rate of runoff from the project site and its upstream watershed area §102.4(b)(5)(iv)

During Phase 1, a decrease in volume and peak rate of runoff from the site can be expected due to work completed during this phase of the project. The work includes removal of several impervious areas (garage, driveway, and pavilion), regrading of fields in front of the township building, and reconstruction of the stormwater management basin. Changes to the existing stormwater management basin will increase retention time in the basin. Regrading to the east of the township building includes installation of a new basin to manage other stormwater flows being directed further south along Welsh Road via road gutter lines that are to be improved.

During Phase 2, an increase in volume and peak rate of runoff can be expected due to work completed. These increases are addressed by PSCM features including an infiltration basin and a dry extended detention basin beneath the parking lot. Summary of calculations results is in the ATT JS, each labeled for relevant locations.

Location of all surface waters and their classification under Chapter 93 §102.4(b)(5)(v)

During Phase 1, the receiving surface waters, tributaries to Wyomissing Creek and tributaries to Angelica Creek. These waterways are shown and labeled on the drawings. During Phase 2, runoff will only flow to the tributaries to Angelica Creek.

Per PADEP Chapter 93 classification, the designated use of the receiving stream basin, the Wyomissing Creek, is HQ-CWF (High Quality Cold Water Fishes) and MF (Migratory Fishes); it is a HQ designated watershed.

Angelica Creek has a designated use listed as CWF (Cold Water Fishes) and MF (Migratory Fishes); it is not a HQ or EV designated watershed. There is no existing use listed in Chapter 93.

Narrative description of the location and type of perimeter and onsite BMPs §102.4(b)(5)(vi)

The temporary erosion control measures to be provided during construction and restoration activities are designed to minimize soil loss, prevent water pollution of adjacent streams and rivers, protect adjacent properties, and maximize protection of existing drainage features and vegetation. The following E&S Best Management Practices (BMP's) are incorporated in the design and details of the project:

- Limiting areas of disturbance and preservation of existing vegetation wherever possible.
- Temporary seeding and mulching to be applied immediately to all disturbed areas.
- Silt fence/filter sock sediment barrier
- Benching of slopes
- (Stabilized) Rock construction entrances
- Pumped water filter bags
- Erosion control matting along stream banks and steep slopes
- Filter bag inlet protection

Sequence of BMP installation and removal §102.4(b)(5)(vii)

A general construction sequence for the installation of piping and appurtenances, including installation and removal of temporary E&S BMPs, is shown on the drawings.

Supporting calculations and measurements §102.4(b)(5)(viii)

Supporting calculations for E&S measures is included in ATT G. These include worksheets for compost sock, flare end sections and end walls, swale and channel design, and anti-seep collars. Attachments are labeled for phases to which they correspond.

Supporting calculations for the existing land cover and basins are included in ATT K of the Appendices to the PSCM Narrative. Existing land cover for Phase 2 is the proposed land cover at the conclusion of Phase 1.

Supporting calculations for the proposed new basins are included in ATT L of the PSCM Appendices. Phase 1 includes calculations for permanent basin 1 and 2 as well as temporary sediment basins 3 and 4. Phase 2 includes calculations for removal of temporary sediment traps 3 and 4 and permanent basins 5 and 6.

Plan drawings §102.4(b)(5)(ix)

Drawings describing the proposed earthmoving are included in the application. The limit of disturbance is shown on the drawings. The existing grading will generally be restored at the conclusion of Phase 1. Grading will be adjusted as shown of the plans for Phase 2. E&S BMP details are included on the drawings.

Maintenance program §102.4(b)(5)(x)

Erosion and sediment control measures included in this plan shall be maintained after construction so that they individually and collectively perform the function for which they were designed.

During the work, the contractor will assign worker(s) experienced in erosion control measures to make inspections and preparing reports weekly and after rainfall events, to determine any maintenance or repair that may be required. Temporary features such as silt fence, inlet protection, and erosion control matting will be inspected and any needed maintenance or repair will be noted. After inspection, the preventative and remedial work needed will be determined and corrected immediately.

Sediment will not be permitted to accumulate to a depth sufficient to limit the effectiveness of the proposed E&S BMP(s). After final site stabilization has been achieved, only then will the temporary erosion and sediment BMP's be removed. Any areas disturbed during removal of the BMP's will be stabilized immediately.

The maintenance of the proposed BMP's is addressed in the notes on the drawings.

An inspection schedule for the proposed BMP's is addressed in the notes on the drawings.

A written report documenting inspections and repairs is specified in the notes on the drawings.

Recycling or disposal of materials §102.4(b)(5)(xi)

Practical construction wastes from a project of this type include: sediment collected in the trench water filtration system, disturbed sediments that may run overland, concrete truck washout materials, wood dunnage from equipment delivery pallets and concrete framework, excess excavated materials, and typical construction debris. All of these wastes will be recycled or disposed of offsite as described in the standard general sediment control notes #A.10 & 11 on the permit plans (Drawing 162); i.e., per the PADEP Solid Waste Management Regulations (document 258-2182-773); no disposal will occur onsite.

Instructions for the proper recycling/offsite disposal of other materials are provided in the notes on the drawings and on the Preparedness, Prevention and Contingency (PPC) Plan which is included on the drawings and in ATT H.

Geologic formations/soil conditions that may have the potential to cause pollution §102.4(b)(5)(xii)

There are no known naturally-occurring geologic or other soil conditions that are anticipated to have the potential to cause pollution; measures to avoid, minimize or mitigate them are not applicable.

Potential thermal impacts to surface waters §102.4(b)(5)(xiii)

During the project, the thermal impacts of stormwater will be avoided, minimized, and mitigated by pumping water from the trenches through a filter bag and into a grassy area allowing time for water to cool before any may possibly run off into surface waters.

The post-construction thermal impacts of stormwater runoff from the project site will be avoided, minimized, and mitigated by restoring most disturbed areas to the cover conditions (or better) that existed prior to construction. For areas that were changed and not restored, the revegetated storm swales along the sites of Welsh Road will slow the first flush and allow for some to be retained and infiltrated or runoff to cool before entering waters of the Commonwealth.

E&S Plan designed and implemented to be consistent with PSCM Plan §102.4(b)(5)(xiv)

The proposed PSCM structural BMP stormwater management basins are shown on the E&S Plan Maps. These areas are protected during construction as suggested in their implementation guidelines to prevent sediment from entering the system before they have been fully stabilized and to avoid compaction by construction equipment. Drainage area and ground cover calculations show that there is no expected increase in runoff peak rate. A summary of the results of the calculations are included to support this in the PSCM Spreadsheets.

There are no existing or proposed riparian buffers within the project site. Therefore the requirement that riparian buffers are shown outside limits of disturbance is not applicable. A wetland delineation was performed. Wetlands are located outside the project site and are labeled on the drawings.

Existing/proposed riparian forest buffers §102.4(b)(5)(xv)

The project site does not discharges to a High Quality or Exceptional Value watershed. The site and disturbance area is within 150 feet of a perennial or intermittent river, stream, or creek, lake, pond or reservoir, however, the project consists primarily of road maintenance activities during Phase 1. Therefore, the project meets the requirements for granting of a waiver listed in the following section(s) of Chapter 102.14:

- 102.14(d)(1)(v) Road maintenance activities so long as any existing riparian buffer is undisturbed to the extent practicable.
During Phase 2 the following waiver applies:
- 102.14(d)(1)(i) A project site located greater than 150 feet (45.7 meters) from a river, stream, creek, lake, pond or reservoir.

There are wetlands present to the east of the site, per review of the NMI mapping online, and these wetlands are shown on the project plans. These areas are not forested and are outside the disturbance.


Antidegradation Analysis

The project site drains to an MS4. This MS4 drains to a wetland as shown on the plans. Wetlands are designated as EV if they meet the definition listed in 105.17(1)(i)-(v). Given the wide definition in the PA Code and the lack of knowledge of other wetlands in the area which may affect the classification of wetlands adjacent to the site and cost prohibitive nature to classify them, it is unclear if these wetlands meet the criteria for definition as EV, therefore the Antidegradation Analysis Module 3 is included. ABACT BMPs are proposed for use.


THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

Table with columns: Date, Draft, Chkd, and Issued For Bids. Rows include 11/30/2023, 08/11/2023, and 04/20/2023.


EROSION & SEDIMENTATION CONTROL NOTES
CUMRU FIRE DEPARTMENT NEW BUILDING
Prepared For: TOWNSHIP OF CUMRU
Situate In: CUMRU TOWNSHIP, BERKS CO., PA.
Project #: 2057000538
Drawing #: 166.2
Sheet #: 12 Of 25
Jeffrey E. Skinner
PE-042652-E
SU-052889-E



STANDARD CONSTRUCTION DETAIL #3-2
ROCK CONSTRUCTION ACCESS WITH WASH RACK 166.3
NOT TO SCALE



STANDARD CONSTRUCTION DETAIL #6
ROCK CONSTRUCTION ENTRANCE 166.3
N.T.S.



* SEE MANUFACTURER'S LINING INSTALLATION DETAIL FOR STAPLE PATTERNS, VEGETATIVE STABILIZATION FOR SOIL AMENDMENTS, SEED MIXTURES AND MULCHING INFORMATION

CHANNEL NO.	STATIONS	BOTTOM WIDTH B (FT)	DEPTH D (FT)	TOP WIDTH W (FT)	Z1 (FT)	Z2 (FT)	LINING *
SWALE 1A	6 LF	1	1	7	3	3	R-5
SWALE 1B	40 LF	1	1	7	3	3	GRASS-LEGUME
SWALE 2	94 LF	1	1	7	3	3	GRASS-LEGUME
SWALE 3A	91 LF	1	1	7	3	3	GRASS-LEGUME
SWALE 3B	58 LF	1	1	7	3	3	GRASS-LEGUME
SWALE 4A	52 LF	1	1	7	3	3	GRASS-LEGUME
SWALE 4B	50 LF	1	1	7	3	3	GRASS-LEGUME
SWALE 5A	49 LF	2.5	1.26	10.04	3	3	GRASS-LEGUME
SWALE 5B	56 LF	2.5	1	8.5	3	3	GRASS-LEGUME

NOTES:


ANCHOR TRENCHES SHALL BE INSTALLED AT BEGINNING AND END OF CHANNEL IN THE SAME MANNER AS LONGITUDINAL ANCHOR TRENCHES.

CHANNEL DIMENSIONS SHALL BE CONSTANTLY MAINTAINED. CHANNEL SHALL BE CLEANED WHENEVER TOTAL CHANNEL DEPTH IS REDUCED BY 25% AT ANY LOCATION.

SEDIMENT DEPOSITS SHALL BE REMOVED WITHIN 24 HOURS OF DISCOVERY OR AS SOON AS SOIL CONDITIONS PERMIT ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE. DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF DISCOVERY.

NO MORE THAN ONE THIRD OF THE SHOOT (GRASS LEAF) SHALL BE REMOVED IN ANY MOWING. GRASS HEIGHT SHALL BE MAINTAINED BETWEEN 2 AND 3 INCHES UNLESS OTHERWISE SPECIFIED. EXCESS VEGETATION SHALL BE REMOVED FROM PERMANENT CHANNELS TO ENSURE SUFFICIENT CHANNEL CAPACITY.

STANDARD CONSTRUCTION DETAIL #6-1
VEGETATED CHANNEL 166.3
NOT TO SCALE



INLET PROTECTION SHALL NOT BE REQUIRED FOR INLET TRIBUTARY TO SEDIMENT BASIN OR TRAP. BERMS SHALL BE REQUIRED FOR ALL INSTALLATIONS.


ROLLED EARTHEN BERM IN ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS STONED. ROAD SUBBASE BERM ON ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS PAVED. EARTHEN BERM IN CHANNEL SHALL BE MAINTAINED UNTIL PERMANENT STABILIZATION IS COMPLETED OR REMAIN PERMANENTLY.

AT A MINIMUM, THE FABRIC SHALL HAVE A MINIMUM GRAB TENSILE STRENGTH OF 120 LBS., A MINIMUM BURST STRENGTH OF 200 PSI AND A MINIMUM TRAPEZOIDAL TEAR STRENGTH OF 50 LBS. FILTER BAGS SHALL BE CAPABLE OF TRAPPING ALL PARTICLES NOT PASSING A NO. 40 SIEVE.

INLET FILTER BAGS SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. BAGS SHALL BE EMPTIED AND RINSED OR REPLACED WHEN HALF FULL OR WHEN FLOW CAPACITY HAS BEEN REDUCED SO AS TO CAUSE FLOODING OR BYPASSING OF THE INLET. DAMAGED OR CLOGGED BAGS SHALL BE REPLACED. A SUPPLY SHALL BE MAINTAINED ON SITE FOR REPLACEMENT OF BAGS. ALL NEEDED REPAIRS SHALL BE INITIATED IMMEDIATELY AFTER THE INSPECTION. DISPOSE ACCUMULATED SEDIMENT AS WELL AS ALL USED BAGS ACCORDING TO THE PLAN NOTES.


DO NOT USE ON MAJOR PAVED ROADWAYS WHERE PONDING MAY CAUSE TRAFFIC HAZARDS.

FILTER BAG INLET PROTECTION 3
N.T.S. 166.3



- PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED(TM) MUST BE INSTALLED WITH PAPER SIDE DOWN.
- BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" (15cm) DEEP X 6" (15cm) WIDE TRENCH WITH APPROXIMATELY 12" (30cm) OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30cm) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30cm) PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30cm) APART ACROSS THE WIDTH OF THE BLANKET.
- ROLL THE BLANKETS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING OPTIONAL DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
- THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2"-5" (5cm-12.5cm) OVERLAP DEPENDING ON BLANKET TYPE. TO ENSURE PROPER SEAM ALIGNMENT, PLACE THE EDGE OF THE OVERLAPPING BLANKET (BLANKET BEING INSTALLED ON TOP) EVEN WITH THE COLORED SEAM STITCH ON THE PREVIOUSLY INSTALLED BLANKET.
- CONSECUTIVE BLANKETS SPICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" (7.5cm) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30cm) APART ACROSS ENTIRE BLANKET WIDTH. NOTE: *IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15cm) MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.

EROSION CONTROL MATTING 4
N.T.S. 166.3



LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4832	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AGS % RETAINED	ASTM D-4751	80 SIEVE

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.

BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS.


NO DOWN SLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HO OR EY WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.

THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE.


THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.

FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

STANDARD CONSTRUCTION DETAIL #5
PUMPED WATER FILTER BAG 166.3
N.T.S.



STANDARD CONSTRUCTION DETAIL #7
TOPSOIL & CLEAN SPOILS STOCKPILE CONTROL 166.3
N.T.S.



STANDARD CONSTRUCTION DETAIL #10
TYPICAL COMPOST SOCK WASHOUT INSTALLATION 166.3
N.T.S.

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

Date	Draft	Chkd	RC	JES	ISSUED FOR BIDS
11/30/2023			RC	JES	ISSUED FOR BIDS
08/11/2023			RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023			RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION

EROSION & SEDIMENTATION CONTROL DETAILS

CUMRU FIRE DEPARTMENT NEW BUILDING

Prepared For:
TOWNSHIP OF CUMRU


Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.

PROJECT #: 2057000538
DRAWING #: 166.3
SHEET #: 13 OF 25


ATLAS
920 GERMANTOWN PIKE, SUITE 200, PLYMOUTH MEETING, PA 19462

Jeffrey E. Skinner
PE-042652-E
SU-052288-E

S:\FILESERVER\Projects\Cumru\2057000538 - Resurf Fire Station\DWG\FIRE STATION_166.3.dwg, 11/29/2023, 2:49:45 PM, AutoCAD PDF (General Documentation) p2



EMBANKMENT ALONG PRINCIPAL SPILLWAY




CROSS SECTION AT OUTLET BARREL

NOTES:
A CONCRETE CRADLE MAY BE USED IN CONJUNCTION WITH ANTI-SEEP COLLARS AND/OR FILTER DIAPHRAGM. ANTI-SEEP COLLAR NUMBER, SIZE AND SPACING SHALL BE AS SHOWN ELSEWHERE IN PLAN.

STANDARD CONSTRUCTION DETAIL #7-17
CONCRETE CRADLE FOR BASIN OR TRAP OUTLET BARREL
NOT TO SCALE

1
166.4




CHANNEL CROSS-SECTION

CHANNEL NO.	STATIONS	BOTTOM WIDTH B (FT)	DEPTH D (FT)	Z1 (FT)	Z2 (FT)	RIPRAP GRADATION N (R-)	RIPRAP DEPTH t (IN)	UNDERLAYMENT	UNDER-LAYMENT THICKNESS
SWALE 1A	6.0 LF	1	1	3	3	R-5	24	NA	NA
FES 44	3.0'	4.5	1	3	3	R-4	18	NA	NA
FES 45	3.0'	3	0.5	3	3	R-4	18	NA	NA

NOTES:
FILTER STONE UNDERLAYMENT FOR BED SLOPES ≥ 0.10 FT/FT (10 %) SHALL BE USED.
CHANNEL DIMENSIONS ARE FOR THE COMPLETED CHANNEL AFTER ROCK PLACEMENT. CHANNEL MUST BE OVER-EXCAVATED A SUFFICIENT AMOUNT TO ALLOW FOR THE VOLUME OF ROCK PLACED WITHIN THE CHANNEL WHILE PROVIDING THE SPECIFIED FINISHED DIMENSIONS.
CHANNEL DIMENSIONS SHALL BE CONSTANTLY MAINTAINED. CHANNEL SHALL BE CLEANED WHENEVER TOTAL CHANNEL DEPTH IS REDUCED BY 25% AT ANY LOCATION. SEDIMENT DEPOSITS SHALL BE REMOVED WITHIN 24 HOURS OF DISCOVERY OR AS SOON AS SOIL CONDITIONS PERMIT ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE.
DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF DISCOVERY.
THE MINIMUM ROCK THICKNESS (t) SHALL BE 1.5 TIMES THE MAX ROCK SIZE.

RIPRAP CHANNEL
(SCD 6-3)
N.T.S.

2
166.4




BASIN OR TRAP NO.	PIPE SIZE (IN)	S (IN)	NO. OF COLLARS	RISER TO FIRST COLLAR (FT)	COLLAR SPACING (FT)
#6	24	48	2	5	10

NOTES:
ALL COLLARS SHALL BE INSTALLED SO AS TO BE WATERTIGHT.
COLLAR SIZE AND SPACING SHALL BE AS INDICATED WITHIN TABLE.

CONCRETE ANTI-SEEP COLLAR FOR PERM. BASINS OR TRAPS (SCD 7-16)
N.T.S.

3
166.4



LOCATE SUMP AT LOW POINT IN WORK AREA AND OUTSIDE OF CONSTRUCTION ACTIVITY. WHEREVER RUNOFF FROM A WORK AREA FLOWS DIRECTLY TO THE SUMP AREA, A FILTER BAG SHALL BE ATTACHED AT THE DISCHARGE POINT UNLESS PUMPING TO A SEDIMENT BASIN OR SEDIMENT TRAP.

MINIMUM DIAMETER OF PIT BOTTOM SHALL BE 24" LARGER THAN PIPE DIAMETER. MINIMUM DEPTH OF PIT SHALL BE 24" BELOW WATER LEVEL IN WORK AREA (INCLUDING THE AASHTO #57 STONE). 12" TO 24" PERFORATED CMP OR PVC PIPE SHALL BE SET ON 12" OF CLEAN AASHTO #57 STONE.


VOID SPACE AROUND PIPE SHALL BE FILLED WITH AASHTO #57 STONE. PIPE TO EXTEND 12" MIN. ABOVE TOP OF STONE AND/OR WATER BEING PUMPED FROM WORK AREA.

SET PUMP INTAKE INSIDE STANDPIPE.
DISCHARGE FROM PUMP SHALL BE TO A STABLE AREA BELOW DISTURBANCES FROM THE WORK ZONE.

SUMP MAY BE USED IN CONJUNCTION WITH FILTER BAG WHERE ADDITIONAL FILTERING IS NEEDED.

STANDARD WATER DETAIL
SUMP PIT
N.T.S.

4
166.4




OUTLET CROSS-SECTION

UP-SLOPE FACE

NOTES:
A ROCK FILTER OUTLET SHALL BE INSTALLED WHERE FAILURE OF A SILT FENCE OR STRAW BALE BARRIER HAS OCCURRED DUE TO CONCENTRATED FLOW. ANCHORED COMPOST LAYER SHALL BE USED ON UPSLOPE FACE IN HQ AND EV WATERSHEDS.
SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLET.

STANDARD CONSTRUCTION DETAIL #4-6
ROCK FILTER OUTLET
NOT TO SCALE

5
166.4




OUTLET NO.	PIPE DIA Pd (IN)	RIPRAP		APRON		
		SIZE R-	THICK. (IN)	INITIAL WIDTH Atw (FT)	TERMINAL WIDTH Atw (FT)	
44	18	R-4	18	7	4.5	8
45	12	R-4	18	9	3	9

NOTES:
ALL APRONS SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN. TERMINAL WIDTHS SHALL BE ADJUSTED AS NECESSARY TO MATCH RECEIVING CHANNELS.
ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT. DISPLACED RIPRAP WITHIN THE APRON SHALL BE REPLACED IMMEDIATELY.

RIPRAP APRON AT PIPE OUTLET W/ FLARED
(SCD 9-1)
N.T.S.

6
166.4




3
166.4

1
166.4

3
183.5

CONCRETE ANTI-SEEP COLLAR & CONCRETE CRADLE
SCALE: 1" = 5'

7
166.4



THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

Date	Draft	Chkd	Issued For
11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION

EROSION & SEDIMENTATION CONTROL DETAILS

CUMRU FIRE DEPARTMENT NEW BUILDING

Prepared For:
TOWNSHIP OF CUMRU

Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.


PROJECT #:
Z057000538

DRAWING #:
166.4

SHEET #:
14 Of 25

Jeffrey E. Skinner
PE-042652-E
SU-052889-E

920 GERMANTOWN PIKE, SUITE 200,
PLYMOUTH MEETING, PA 19462



PROPOSED FIRE STATION
24,647 SF.
F.F.E. 541.00

WATERSHED TO STILLWATER RUN
(ANGELICA CREEK)

LONG-TERM OPERATION AND MAINTENANCE NOTES:

- ALL BASIN STRUCTURES EXPECTED TO RECEIVE AND/OR TRAP DEBRIS AND SEDIMENT SHALL BE INSPECTED FOR CLOGGING AND EXCESSIVE DEBRIS AND SEDIMENT ACCUMULATION AT LEAST FOUR TIMES PER YEAR (QUARTERLY) AS WELL AS AFTER EVERY STORM GREATER THAN 1 INCH. REMOVE SEDIMENT FROM SUMP PITS IN INLETS AT LEAST ONCE PER YEAR.
- STRUCTURES INCLUDE BASIN BOTTOMS, TRASH RACKS, OUTLET STRUCTURES, RIPRAP OR GABION STRUCTURES, SNOUTS, AND INLETS.
- BASIN 5 SHALL ADDITIONALLY BE CHECKED FOR SCOURING AS ABOVE
 - IF SCOURING IS APPARENT AT INLETS TO BASIN, CHECK RIPRAP. REPLACE AS NECESSARY OR EXPAND TO SLOW INFLOW. REPAIR UNDERCUT AND ERODED AREAS AT OUTLET STRUCTURES.
 - FOR SCOURING ALONG SIDES OF BASIN, PLANT ADDITIONAL NATIVE VEGETATION WITH EROSION CONTROL MATTING UNTIL RESTABILIZED. INSTALL GEOCELL/HONEYCOMB EROSION CONTROL MATTING IN AREAS THAT CONTINUE TO SCOUR POST VEGETATION.
 - INSPECT OUTLET STRUCTURES FOR CONCRETE FAILURE AND PATCH CRACKS.
- RECORD AND MAINTAIN INSPECTION LOGS USING PA DEP FORM #3800-FM-BCW0531A
- SEDIMENT REMOVAL SHALL BE CONDUCTED WHEN BASIN 5 IS COMPLETELY DRY. SEDIMENT SHALL BE DISPOSED OF PROPERLY AND ONCE SEDIMENT IS REMOVED, DISTURBED AREAS MUST BE IMMEDIATELY STABILIZED AND REVEGETATED TO MAINTAIN THIS COVER SECTION.

NOTE: IF SEDIMENT IS FOUND IN BASIN 6, SEE NOTE 4.B. BELOW FOR REMEDIAL STEPS.
- MOWING AND/OR TRIMMING OF VEGETATION SHALL BE PERFORMED AS NECESSARY TO SUSTAIN THE SYSTEM WITH ALL DEBRIS REMOVED FROM THE BASIN 5, SWALE 3, AND SWALE 4.
- VEGETATED AREAS SHALL BE INSPECTED ANNUALLY FOR EROSION, AND UNWANTED GROWTH OF EXOTIC/INVASIVE SPECIES SHALL BE REMOVED.
- VEGETATIVE COVER SHALL BE MAINTAINED AT A MINIMUM OF 95%. COVER VEGETATION SHALL BE REESTABLISHED AS NECESSARY TO MAINTAIN THIS COVER REQUIREMENT.
- AVOID EXCESSIVE COMPACTION OF BASIN 5. VEHICLES SHALL NOT BE PARKED OR DRIVEN IN THE BASIN.
- STORMWATER MANAGEMENT FEATURES SHALL DEWATER 72 HOURS. IF FEATURES FAIL TO DEWATER NOTIFY ENGINEER AND PERFORM THE FOLLOWING.
 - IF BASIN 5 FAILS TO DEWATER, ASSESS COMPACTION AND SEDIMENTATION. SCARIFY SOILS TO PROMOTE INFILTRATION OR REPLACE AMENDED SOILS IN BOTTOM OF BASIN. TEST INFILTRATION RATES.
 - IF BASIN 6 FAILS TO DEWATER (WATER ELEVATION BELOW BOTTOM OF CHAMBERS), ASSESS STONE MEDIA AND STORM CHAMBERS.
 - VERIFY OUTFLOW IS FREE OF SEDIMENT. CLEAN OUT UNDERDRAIN PERFORATED PIPING AND INSPECT CHAMBERS VIA CLEANOUTS. IF SEDIMENT EXISTS, CHECK GEOTEXTILE WRAP FOR TEARS (DURING CONSTRUCTION) AND/OR INLETS FOR PROPER PRETREATMENT FUNCTION.
 - CHECK ROOF DRAIN FILTER SCREENS FOR DEBRIS AND CLEAN/REPLACE AS NECESSARY.
 - DRAIN VIA PUMPING DURING DRY WEATHER. IF SLOW DRAINAGE PERSISTS, CONSIDER REPLACEMENT.

SOILS TYPE ON SITE		
LEGEND	NAME	DESCRIPTION
NaB	NESHAMINY SILT LOAM	3 TO 8 PERCENT SLOPES
NaC	NESHAMINY SILT LOAM	8 TO 15 PERCENT SLOPES
NhD	NESHAMINY GRAVELLY SILT LOAM	8 TO 25 PERCENT SLOPES, EXTREMELY BOULDERY

POST-CONSTRUCTION STORMWATER MANAGEMENT (PCSM) LEGEND


PH #2 LIMIT OF DISTURBANCE

SB SOIL BOUNDARY

NaC SOIL TYPE

PA CHAPTER 93

ANGELICA CREEK
STREAM USE DESCRIPTION: CWF (COLD WATER FISH), MF (MIGRATORY FISH), IT IS NOT A HQ OR EV DESIGNATED WATERSHED.



THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

Pennsylvania One Call System, Inc.

Call Before You Dig in Pennsylvania 1-800-242-1776

State Law Requires Construction Phase: Three working Days Notice Design Phase: Ten working Days Notice Facility Owners: Member of One Call System

SERIAL NO. #20210272169, SERIAL NO. #20210272189
SERIAL NO. #20210272250, SERIAL NO. #20210272251
SERIAL NO. #20210272292, SERIAL NO. #20210272341

Date	Draft	Chkd	RC	JES	ISSUED FOR BIDS
11/30/2023			RC	JES	ISSUED FOR BIDS
08/11/2023			RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023			RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION

POST CONSTRUCTION STORMWATER MANAGEMENT UTILITY PLAN

CUMRU FIRE DEPARTMENT NEW BUILDING

Prepared For:
TOWNSHIP OF CUMRU

Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.

PROJECT #: 2057000538
DRAWING #: 183.1
SHEET #: 16 OF 25

Jeffrey E. Skinner
PE-042652-E
SU-052889-E

920 GERMANTOWN PIKE, SUITE 200,
PLYMOUTH MEETING, PA 19462

PREPAREDNESS, PREVENTION AND CONTINGENCY PLAN NOTES

This plan is part of the NPDES permit application for the discharge of stormwater associated with construction activities and the related Erosion and Sediment Control Plan. It is required to comply with Chapter 101.3(b) of the Rules and Regulations of the Pennsylvania Department of Environmental Protection, and conditions under the NPDES permit.

- 1. Name of Permittee: Cumru Township
Name of Co-permittee (contractor): TBD
2. Name of Project: Reed Street Utility Extension

- 3. Project Location: Mohnton, Berks County, PA
4. List name(s) and telephone number(s) of responsible Cumru Township officials to be contacted in case of emergency (to be confirmed at pre-construction meeting):

Table with 3 columns: Name, Day Phone #, Night Phone #. Entry for Bob McNichols with phone numbers (610) 777-1343.

- 5. List name and telephone number of the following:
(Berks) Brian Gotschall - (610) 374-4800 x8202
Cumru Fire Chief (610) 777-1343
Nearest fire department station:
Nearest hospital: Reading Hospital (484) 628-8000

6. Notification to the following agencies must be made immediately in the event of a spill of any polluting substances.
PADEP Regional Office: Southcentral Regional Office (Harrisburg) - (717) 705-4700
PA Fish and Boat Commission: Harrisburg, PA (717) 705-7800

- 7. List name and telephone number of any downstream water users, including drinking water supplies, industrial intakes and agricultural uses. It is the permittee's/co-permittees responsibility to immediately contact water users if polluting material is released from the site.

8. General Description of Construction Activity.
Re-grading and realignment of Welsh Road. Replace sanitary and storm sewers along Welsh Road and sanitary from border of Mohnton Borough along Reed Street. Extension of gas on water main from intersection of Main Street and Fairview Ave. to Welsh Road.

- 9. Material and Waste Inventory
A. Pesticides and herbicides*
B. Fertilizer*
C. Other chemicals, such as paints, detergents, acids for cleaning, solvents, soil additives, concrete curing compounds*
D. Petroleum based products

Note: It is not anticipated that gasoline, diesel fuel, lubricating oils, etc. will be stored onsite. Heavy equipment will typically be serviced periodically by fuel trucks on an as-needed basis.

- 10. List the types and quantities of absorbent materials used for spill mitigation that are stored on premises. The quantities of absorbent booms, pads and other materials and equipment needed to contain spills and begin cleanup must be kept at the site.

11. During concrete work, steps shall be taken to assure that no pollution enters waterways. Concrete mixer truck washings shall be deposited onsite into a container specially-designed for the purpose.

12. Particular attention shall be given to equipment refueling operations. Refueling shall only occur as far upslope on the site as practicable. The location shall be protected by a containment dike and secured from vandalism.

13. The site shall be inspected daily for evidence of existing or potential spills or leaks, vandalism, and the condition and quantity of cleanup materials.

14. Material Management Practices.
The following material management practices shall be used to reduce the risk of spills or other accidental discharge of materials and substances to storm water runoff:

- A. Good Housekeeping:
- All efforts shall be made to store only enough products onsite as are required to do the job.
- Materials stored onsite shall be stored in a neat, orderly manner in appropriate containers and, if possible, under a roof or other enclosure.

- B. Hazardous Products:
- The practices described below shall be used to reduce the risks associated with hazardous materials:
- Products shall be kept in their original containers unless they are not resalable.

15. Product-Specific Practices
The following product-specific practices shall be followed onsite:

- A. Petroleum Products:
- All onsite vehicles and equipment shall be monitored daily for leaks and shall receive regular preventive maintenance to reduce the chance of leakage.
B. Fertilizers:
- Fertilizers used shall be applied only in the minimum amount recommended by the manufacturer.

16. Spill Prevention Practices
The following product-specific practices shall be followed onsite:

In addition to the good housekeeping and material management practices described above, the following practices shall be followed for spill prevention and cleanup:

- The manufacturer's recommended methods for spill cleanup shall be clearly posted, and site personnel shall be trained in the proper information on cleanup supplies and procedures.
- Materials and the equipment necessary for spill cleanup shall be kept onsite.
- All spills shall be cleaned up immediately after discovery.

17. Site Security
All materials requiring security shall be kept locked within secure containers stored in a designated secure area.

18. All construction and site activities shall be performed in accordance with the specifications and plans approved by the appropriate governmental authorities.

POST-CONSTRUCTION STORMWATER MANAGEMENT (PCSM) PLAN NARRATIVE

General PCSM planning and design §102.8(f)(8)
The Post Construction Stormwater Management Plans for the project are labeled as 'Post Construction Stormwater Management Plans' and are the final site construction plans.

This construction and restoration project proposes no change of use, no land subdivision and no land development, as the utilities will be underground within the existing road right-of-way. There are no new buildings as part of Phase 1, although construction is a consideration in a later phase.

Phase 1 of the project includes plans to realize storm swales along Welsh Road, enlarge and rehabilitate stormwater management basins on the Township Campus, and regrade parts of the township campus in preparation for the new fire station to be constructed in a later phase.

New impervious areas are proposed with Phase 2 of the project. New stormwater sources providing an increase in stormwater runoff volume include the aforementioned fire station building, the fire station driveways, and the fire station parking lot.

Existing vegetation is protected by maintaining the smallest possible limit of disturbance. Existing drainage features are to be utilized and revitalized as part of the project, specifically the drainage swale along Welsh Road between the township building driveway and the location of the future fire station driveway.

No wooded areas need to be cleared, as the areas are already open fields. Areas to be regraded include along Welsh Road to raise the low point and to realign a section where a building is to be removed, and within the township campus to prepare the new foundation for the proposed fire station.

Existing topographic features of the project site and the immediate surrounding area §102.8(f)(1)
The topography of the project site is shown on the site drawings, by use of contours at one foot intervals.

Types, depth, slope, locations and limitations of the soils and geologic formations §102.8(f)(2)
The maps of soil types and limits related to the project were identified using the NRCS Web Soil Survey website.

Characteristics of the project site, including the past, present and proposed land uses and the proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(i) - The project addresses periodic sanitary sewer overflows into the Anglica Creek from a manhole in Woodcrest Ave on Point of Connection Interceptor 8 to the Reading Treatment Plant.

102.14(a)(1)(v) Work along Welsh Road includes road maintenance activities, plans are in place to maintain existing riparian buffer as undisturbed to the extent practicable.

102.14(a)(2)(v) Redevelopment projects which may include brownfields or use of other vacant land and property within a developed area for further construction or development.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

installation of the BMPs are shown on the drawings is applicable. Critical stages when a licensed professional oversee the modification of the existing permanent PCSM BMPs are shown on the plans.

Supporting calculations §102.8(f)(8)
Worksheets were not used to design a PCSM BMP. They are therefore not applicable or included.

Calculations for all drainage areas and Points of Interest (POI) are contained in ATTACHMENTS (d-L) in the appropriate Phase appendices to the PCSM Narrative.

Plan drawings §102.8(f)(9)
A map of tributary areas in Phase 1 is shown on the Drainage Area Map (ATTACHMENT O) and a Drainage Area Map in the plan set for Phase 2. Drainage areas for Phase 1 are broken down by land use category in TR-20 Analysis Input Parameter Summary (ATTACHMENT I).

The existing stormwater discharge points will be retained and are shown on the drawings. Points of interest correspond to stormwater discharge points.

The PCSM Plan is consistent with the E&S Plan in relation to proposed contours, improvements, soils, wetlands, floodways, streams, and discharge locations.

Long-term operation and maintenance schedule §102.8(f)(10)
Long-term operation and maintenance schedule including inspection, repair, and replacement for the proposed PCSM BMPs are shown on the drawings.

Stormwater management basin Long-term operation, maintenance, and inspection:
- Inspect inlet and outlet structure seasonally and after every major storm event
- Repair/replace any damaged or non-functioning snout

- Remove and dispose of any debris and accumulated sediment in inlets or on basin bottoms
- In case of standing water, verify soil compaction and replace substrate or clean underdrain via cleanout.

- After every runoff event, check for scouring.
- If scouring is apparent at inlets to basin, check riprap and replace or expand to slow inflow. Repair undercut and eroded areas at outlet structures.

- For scouring along around sides of basin, plant additional native vegetation with erosion control matting until re-stabilized. Install geocell/honeycomb erosion control matting in areas that continue to scour after adding vegetation.
- Inspect outlet structure for concrete failure after every runoff event. Patch cracks.

Recycling or disposal of materials §102.8(f)(11)
Anticipated construction wastes will be soil rock, earth materials, concrete, asphalt pavement and other materials normally associated with heavy utility construction.

Geologic formations or soil conditions §102.8(f)(12)
There are no known geologic or other soil conditions that have the potential to cause pollution during construction.

Potential thermal impacts §102.8(f)(13)
There are no new potential thermal impacts post construction during Phase 1.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

102.14(a)(1)(v) Final stabilization of the site and proposed alteration to the project site §102.8(f)(3)
The limit of disturbance is shown on the drawings. The limit of disturbance is the NPDES permit boundary.

102.14(a)(2)(v) Riparian forest buffer management plan §102.8(f)(14)
A riparian forest buffer management plan is not required as this project meets criterion for exceptions in accordance with 102.14(d); a riparian buffer is not shown on the drawings.

LONG-TERM OPERATION AND MAINTENANCE NOTES: SEE DWG. 183.1

1. Pre-Construction Stage:
a. Field-marks limits of disturbance and environmentally sensitive areas.

b. At least 7 days prior to starting any earth disturbance activities (including clear and grubbing), the Owner and/or Operator shall invite all Contractors, the Landowner, appropriate Municipal Officials, the E&S plan preparer, the PCSM plan preparer, and a representative from the Bucks County Conservation District to an on-site reconstruction meeting.

c. Upon installation or stabilization of all perimeter sediment control BMP's and at least 3 days prior to proceeding with the bulk earth disturbance activities, the permittee or co-permittee shall provide notification to the department or authorized conservation district.

d. At least 3 days prior to starting any earth disturbance activities, or expanding into an area previously unmarked, the Pennsylvania One Call System Inc. shall be notified at 1-800-242-1776 for the location of existing underground utilities.

e. All earth disturbance activities shall proceed in accordance with the sequence provided on the plans. Deviation from the sequence must be approved by the Bucks County Conservation District or the department prior to implementation.

2. Construction Activity:
a. Convert the existing 150 foot Rock Construction Access #1 to Rock Construction Access with Wash Rock.

b. Install Rock Construction Access #2 with Wash Rock and Concrete Washouts, see drawing.
c. Access to site's E&S BMPs, see drawings for work areas.

d. Site Operation for earthwork:
i. Bring the proposed Building pad grades to the proper elevation. Construction new Building.

ii. All building materials and wastes must be removed from the site and recycled or disposed of in accordance with the Pennsylvania Department of Environmental Protection's Solid Waste Management Regulations at 25pa. Code §271.1 et seq., §271.1 et seq., and §287.1 et seq. No building material or wastes or unused building materials shall be burned, buried, dumped, or discharged at the site.

iii. Install all building utilities, see note ** below.
iv. Critical Stage: remove sediment traps by grading the areas to the proposed grade.

v. Critical Stage: Construct basin #5 and basin #6. Stabilize basin #5 steep slope with E&S blankets. Additional notes detailing Basin #5 & Basin #6 construction shown on dwgs. 183.4 & 183.6.

vi. Install stormwater inlets and pipes. Install Inlet Protection on all new inlets and stabilize areas. See note ** below.
vii. Construct all swales and stabilize with temporary seeding.

viii. Construction proposed parking lot wall.
ix. Final grade site and stabilize with temporary seeding, construction new sidewalk and proposed driveway binder course on parking lot and all driveways. Then install parking lot and driveways with binder course.

e. Permanent stabilization stage:
i. Replacement of top soil (4-6 inches) and install all permanent vegetation requirements.

ii. Permanent seeding and mulch all areas. An area shall be considered to have achieved final stabilization when it has a minimum of 70% uniform perennial vegetative cover or the permanent non-vegetative cover with density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding or other movements.

iii. Clean binder course of parking lot and all driveway surfaces and install wearing course on all surfaces.

3. Removal/Conversion of temporary sediment pollution controls stage:
a. Prior to removal of the E&S bmp's, the Berks County Conservation District should be contacted. The district may require a site inspection prior to the conversion or removal of BMP's.

b. Remove all E&S BMPs when the work area is at a minimum of 70% uniform perennial vegetative cover or trench backfill paving is complete.

c. Remove all filter sock and other temporary soil erosion and sediment control facilities after all areas have been permanently stabilized. Areas disturbed during removal of the controls must be stabilized immediately. An area shall be considered to have achieved final stabilization when it has a minimum of 70% uniform perennial vegetative cover or other permanent non-vegetative cover with density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding or other movements.

d. Within 30 days after the completion of earth disturbance activities authorized by this permit, including the permanent stabilization of the site and proper installation of PCSM BMPs in accordance with the approved PCSM Plans, or upon submission if NOT sooner, the permittee shall file with the department or authorized conservation district a statement signed by a licensed professional and by the permittee certifying that work has been performed in accordance with the terms and conditions of the permit and the work approved erosion and sedimentation and post construction stormwater management plans.

Note: Critical Stage, the design engineer shall be on site.
Note *: *The total length of excavated trench open at any one time should not be greater than the total length of the utility line that can be placed in the trench and back-filled in one working day. No more than 50 lineal feet of open trench should exist when utility line installation ceases at the end of the workday. Soil supplements, seed and mulch must be applied according to 25 Pa. Code §102.22. (Page 283 of E&S Manual)."

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS THEREOF. THE DRAWINGS TO THE CONTRACT DOCUMENTS SHALL BE SHOWN AS SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

Table with 4 columns: Date, RC, JES, Chkd. Rows for 11/30/2023, 08/11/2023, 04/20/2023.

POST CONSTRUCTION STORMWATER MANAGEMENT NOTES

CUMRU FIRE DEPARTMENT NEW BUILDING
Prepared For:
TOWNSHIP OF CUMRU
Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.

Jeffrey E. Skinner
PE-042652-E
SU-052889-E
820 GERMANTOWN PIKE, SUITE 200,
PLYMOUTH MEETING, PA 19462


CONSTRUCTION DETAILS BELOW COVER THE FOLLOWING CONDITIONS:

- (A) PIPE LYING ON TOP OF THE NATURAL GROUND, ROCK OR COMPACTED (97% SPD) FILL.
- (B) THE EXISTING GROUND IS BETWEEN THE TOP AND THE BOTTOM OF THE PROPOSED PIPE AND THE PIPE IS TO BE COVERED WITH EARTH FILL.
- (C) THE TOP OF PIPE IS BELOW THE LEVEL OF THE NATURAL GROUND OR COMPACTED FILL (TO MINIMUM 97% SPD) AND TO BE COVERED WITH EARTH FILL TO HEIGHTS ABOVE THE NATURAL GROUND.

STEP 1: REMOVE TOPSOIL (COMPRESSIBLE LAYER, FOR EXAMPLE, ORGANIC MATERIAL) TO A WIDTH EQUAL TO 5 OUTSIDE DIAMETERS OF THE PIPE IN ALL FILL CONDITIONS ABOVE (A),(B)&(C). ALSO IF SPECIFIED ON THE CONTRACT DRAWING, UNDERCUT FOR THE DEPTH BELOW THE BEDDING AS SHOWN BY DESIGN (MAKE MIN WIDTH 3 DIAMETERS OF PIPE).


STEP 2: CONSTRUCT THE EMBANKMENT TO 4'-0" ABOVE THE TOP OF PIPE OR TO THE SUBGRADE ELEVATION, WHICHEVER IS LESS. FOR PIPES 72" OR GREATER SEE NOTE 1.

STEP 3: EXCAVATE THE TRENCH TO THE WIDTH OF THE OUTSIDE DIAMETER OF THE PIPE PLUS 2'-0" AND CREATE AN APPROPRIATE BEDDING 6" DEEP.



THOROUGH ROCK, OR HARD SHALE, OR IN AREAS OF UNDERCUT, PROVIDE 6"x6" INCH/FT OF, Do+4'-0", BELOW THE INTENDED BOTTOM ELEVATION OF THE PIPE, 12" MAX.

NOTE: IF UNSUITABLE MATERIAL IS FOUND, UNDERCUT AS DIRECTED AND BACKFILL WITH SUITABLE MATERIAL TO BOTTOM OF BEDDING ELEVATION. (UNLESS OTHERWISE SPECIFIED.)




FOR THERMOPLASTIC PIPE, SEE STEP 6B.


STEP 6: FOR CONCRETE PIPE, SEE STEP 6A.

CONCRETE PIPE

STEP 6A: PLACE 2A COARSE AGGREGATE MATERIAL IN LIFTS 4" THICK, ADJACENT TO THE LOWER HAUNCHES TO A HEIGHT OF 0.6 Do. COMPACT TO 95% SPD. TEST THE SIDE BACKFILL MATERIAL AND CONTINUE EMBANKMENT IN ACCORDANCE WITH SECTION 601.




DEEP FILLS OVER 4'-0"



SHALLOW FILLS 4'-0" AND LESS


STEP 6B: THERMOPLASTIC PIPE (PVC, HDPE, SLCPP)

PLACE 2A COARSE AGGREGATE MATERIAL IN LIFTS 4" THICK, ADJACENT TO THE LOWER HAUNCHES TO A HEIGHT OF 12" ABOVE TOP OF PIPE. COMPACT TO 95% SPD. TEST THE BACKFILL MATERIAL AND CONTINUE EMBANKMENT IN ACCORDANCE WITH SECTION 601.




THERMOPLASTIC PIPE

LEGEND




Do = OUTSIDE DIAMETER OF PIPE
SPD = STANDARD PROCTOR DENSITY
ID = INSIDE DIAMETER


STORMWATER PIPE INSTALLATION PROCEDURES




TEMPORARY TRENCH RESTORATION - PAVED AREAS



TRENCH RESTORATION - UNPAVED AREAS



SEMI-PERMANENT TRENCH RESTORATION




PERMANENT TRENCH RESTORATION


DRIVEWAY & PARKING LOT RECONSTRUCTION NOTES:

- 9.5 MM MIX SUPERPAVE ASPHALT MIXTURE DESIGN (WMA), WEARING COURSE, PG. 64-22, 3 TO 30 MILLION ESALS, DESIGN LEVEL 75 CYRATIONS.
- 19.0 MM MIX SUPERPAVE ASPHALT MIXTURE DESIGN (WMA), BINDER COURSE, PG. 64-22, 3 TO 30 MILLION ESALS, DESIGN LEVEL 75 CYRATIONS.
- 25.0 MM MIX SUPERPAVE ASPHALT MIXTURE DESIGN (WMA), BASE COURSE, PG. 64-22, 3 TO 30 MILLION ESALS, DESIGN LEVEL 75 CYRATIONS.
- 2A MODIFIED AGGREGATE SUBBASE, COMPACTED TO 100% OF THE MAXIMUM DRY-WEIGHT DENSITY.
- SUBGRADE TOPSOIL, LARGE ROCKS, AND OTHER TYPES OF LOW QUALITY, UNSUITABLE SOIL SHALL BE REMOVED AND REPLACED. THE EXPOSED SURFACE SHALL BE COMPACTED WITH SUITABLE

- EQUIPMENT (MINIMUM 10-TON ROLLER). SUBGRADE COMPACTION SHOULD BE TO A DRY DENSITY OF AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY (ASTM D698).
- MINIMUM 1" PAVEMENT CUTBACK. EXCAVATE EXISTING AND TEMPORARY PAVEMENT AND MATERIAL TO REQUIRED ELEVATION. RECOMPACT EXPOSED SUBGRADE. TACK COAT ALL VERTICAL PAVEMENT EDGES.
- EXCAVATE AND REMOVE EXISTING PAVEMENT AND MATERIAL TO REQUIRED ELEVATION. RECOMPACT EXPOSED SUBGRADE. TACK COAT ALL EXPOSED VERTICAL EDGES.
- INSTALL ONLY BASE COURSE AND BINDER COURSE IN ONE DAY.
- SEAL ALL EDGE JOINTS WITH EXISTING PAVEMENTS, CURBS, DRAINAGE AND UTILITY STRUCTURES.
- REPLACE AND REINSTALL ALL PAVEMENT MARKINGS.
- 1 1/2" MILLING AND OVERLAY.
- PROVIDE TEMPORARY PAVING TRANSITION FOR VEHICLE TRAFFIC BETWEEN EXISTING PAVEMENT ELEVATION AND PAVEMENT NOT AT FINAL ELEVATION.



STORMWATER BASIN #5 OUTLET DETAIL



STORMWATER BASIN #5 WEIR DETAIL

Construction Sequence For Basin #5 and All Swales

- Begin vegetated basin construction only when the upgradient temporary erosion and sediment control measures are in place. Vegetated basin should be constructed and stabilized early in the construction schedule, preferably before mass earthwork and paving increase the rate and volume of runoff.
- Remove the top soil and storage as it is show on the plan.
- Rough grade the vegetated basin. Equipment shall avoid excessive compaction and/or land disturbance. Excavating equipment should operate from the side of the basin and never on the bottom of the basin. No compacted soil is needed.
- Install outlet structure and pipe as it show on the plan.
- Fine grade the vegetated basin. Accurate grading is crucial for basin. Even the smallest nonconformities may compromise flow conditions.
- Seed, vegetate and install protective lining as per approved plans and according to final planting list. Plant the basin at a time of the year when successful establishment without irrigation is most likely. However, temporary irrigation may be needed in periods of little rain or drought. Vegetation should be established as soon as possible to prevent erosion and scour.
- Once all tributary areas are sufficiently stabilized, remove temporary erosion and sediment controls. It is very important that the basin be stabilized before receiving upland stormwater flow.
- Follow maintenance guidelines, as discussed below.

Note: If a vegetated basin is used for runoff conveyance during construction, it should be regraded and reseeded immediately after construction and stabilization has occurred. Any damaged areas should be fully restored to ensure future functionality of the basin.

Maintenance Issues

- Compared to other stormwater management measures, the required upkeep of vegetated basin is relatively low. In general, maintenance strategies for basin focus on sustaining the hydraulic and pollutant removal efficiency of the basin, as well as maintaining a dense vegetative cover. Experience has proven that proper maintenance activities ensure the functionality of vegetated basin for many years. The following schedule of inspection and maintenance activities is recommended:
- Maintenance activities to be done annually and within 48 hours after every major storm event (> 1 inch rainfall depth):
 - Inspect and correct erosion problems, damage to vegetation, and sediment and debris accumulation (address when > 3 inches at any spot or covering vegetation)
 - Inspect vegetation on side slopes for erosion and formation of rills or gullies, correct as needed
 - Inspect for pools of standing water; dewater and discharge to an approved location and restore to design grade
 - Mow and trim vegetation to ensure safety, aesthetics, proper basin operation, or to suppress weeds and invasive vegetation; dispose of cuttings in a local composting facility; mow only when basin is dry to avoid rutting
 - Inspect for litter; remove prior to mowing
 - Inspect for uniformity in cross-section and longitudinal slope, correct as needed

- Inspect basin's inlet (curb cuts, pipes, etc.) and outlet for signs of erosion or blockage, correct as needed

Maintenance activities to be done as needed:

- Plant alternative grass species in the event of unsuccessful establishment
- Reseed bare areas; install appropriate erosion control measures when native soil is exposed or erosion are forming
- Rototill and replant basin if draw down time is more than 72 hours
- Inspect and correct of altered water flow (channelization, obstructions, erosion, etc.) are identified
- Water during dry periods, fertilize, and apply pesticide only when absolutely necessary
- Most of the above maintenance activities are reasonably within the ability of individual owner. More intensive basin (i.e. more substantial vegetation, etc.) may warrant more intensive maintenance duties and should be vested with a responsible agency. A legally binding and enforceable maintenance agreement between the facility owner and the local review authority might be warranted to ensure sustained maintenance execution. Winter conditions also necessitate additional maintenance concerns, which include the following:
 - Inspect basin immediately after the spring melt, remove residuals (e.g. sand) and replace damaged vegetation without disturbing remaining vegetation.
 - If roadside or parking lot runoff is directed to the basin, mulching and/or soil aeration/manipulation may be required in the spring to restore soil structure and moisture capacity and to reduce the impacts of deicing agents.
 - Use nontoxic, organic deicing agents, applied either as blended, magnesium chloride-based liquid products or as pretreated salt.
 - Use salt-tolerant vegetation in basin.

BASIN'S TRASH RACK CAGE AND CONCRETE BASE						
LOCATION	TRASH CAGE (TC)			CONCRETE BASE DIMENSIONS		
	LENGTH (FT.)	HEIGHT (FT.)	WIDTH (FT.)	LENGTH (FT.)	WIDTH (FT.)	HEIGHT (FT.)
BASIN #5 (#50)	3.77	1.50	1.00	4.77	1.50	0.50


TRASH CAGE NOT TO SCALE

Amendment Soil Construction Sequence

All construction should be completed and stabilized before beginning soil restoration.


COMPOST SOIL AMENDMENT INSTALLATION

- Amended soil to meet PADEP requirement of 20-30% organic content, clay content <10%, and Ph between 5.5 and 6.5.
- Spread 2-3 inches of approved compost on existing soil. Till added soil into existing soil with a rotary tiller that is set to a depth of 6 inches. Add an additional 4 inches of approved compost to bring the area up to grade.
- After permanent planting/seeding, 2-3 inches of compost blanket will be applied to a areas not protected by grass or other plants



BASIN #5 EMERGENCY SPILLWAY & INLET EMERGENCY FLOW

NOT TO SCALE



PROPOSED EMERGENCY BASIN #5 SPILLWAY PROFILE

SCALE: V. 1" = 2' H. 1" = 20'

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

Date	Draft	Chkd	ISSUED FOR BIDS
11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION

POST CONSTRUCTION STORMWATER MANAGEMENT BASIN #5 DETAILS

Prepared For:
TOWNSHIP OF CUMRU

Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.


PROJECT #:
2057000538

DRAWING #:
183.4



SHEET #:
19 Of 25

Jeffrey E. Skinner
PE-042652-E
SU-052889-E


920 GERMANTOWN PIKE, SUITE 200,
PLYMOUTH MEETING, PA 19462




BASIN #6 PLAN
SCALE: 1" = 10'
183.5



BASIN #6 OUTLET STRUCTURAL (OS #47) DETAIL
N.T.S.
2
183.5



BASIN #6 U-DRAIN & OUTLET STRUCTURAL (OS #47) DETAIL
N.T.S.
4
183.5



BASIN #6 PROFILE
SCALE: V. 1" = 2'
H. 1" = 20'
3
183.5

- BASIN #6 NOTES:**
1. STORAGE SWM BASIN #6 TRENCH [(241.00'(l1)) x (59.59'(w1)) x (3.50' (h)) (8 ROWS) + (90.50' (l2)) x (18.00' (w2)) x (3.5' (h)) (4 ROWS) SEE PLAN]
 2. 292 CHAMBERS - SC 740 CHAMBER (SEE BASIN #6 PLAN)
 3. 4" PERFORATION PVC PIPES
 4. SC 740 CHAMBER END CAPS W/ 15" SLCPP WELDED STUB
 5. SC 740 CHAMBER END CAPS W/ 24" SLCPP WELDED STUB
 6. 15" CROSS TEES W/ 6" RISER
 7. 15" TEES W/ 6" RISER
 8. 15" 90° BENDS W/ 6" RISER
 9. 15" SLCPP (CUT LENGTH DETERMINED BY CONTRACTOR)
 10. 15"x24" REDUCER
 11. 24" TEES W/ 6" RISER
 12. 24" 90° BENDS W/ 6" RISER
 13. 24" SLCPP (CUT LENGTH DETERMINED BY CONTRACTOR)
 14. 15" SOIL-TIGHT COUPLER
 15. 24" SOIL-TIGHT COUPLER
 16. 5/8" ALUM. WEIR PLATE W/ ORIFICE CUT IN
 17. 4 - ALUM. L4"x4"x3/8", EACH SIDE (TYP.)
 18. (3) 3/8" S.S. ADHESIVE ANCHORS (TYP.) @ 12" MAX. C/C, 3 1/2" EMBED.
 19. 2 - HAND LIFT: 1/2" @ ALUM., SMOOTH BAR (WELDED TO PLATE)

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION
Date	Draft	Chkd	

POST CONSTRUCTION STORMWATER MANAGEMENT BASIN #6 DETAIL

CUMRU FIRE DEPARTMENT NEW BUILDING

Prepared For:
TOWNSHIP OF CUMRU

Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.

PROJECT #: 2057000538
DRAWING #: 183.5
SHEET #: 20 Of 25

Jeffrey E. Skinner
PE-042652-E
SU-052889-E

ATLAS
920 GERMANTOWN PIKE, SUITE 200,
PLYMOUTH MEETING, PA 19462

SC-740 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH SC-740.
- CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE COPOLYMERS.
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE AND NO INTERNAL SUPPORTS THAT WOULD IMPIDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE ASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE ASHTO DESIGN TRUCK WITH CONSIDERATION FOR INLET AND MULTIPLE VEHICLE PRESENCES.
- CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION DESIGN TRUCK".
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, THE ARCH STIFFNESS CONSTANT SHALL BE CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:
 - THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
 - THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE ASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
 - THE TEST DETERMINED CREEP MODULUS AS SPECIFIED IN ASTM F2418 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-TH PERCENTILE MODULUS USED FOR DESIGN.
- CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

183.6


IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF THE SC-740 SYSTEM

- STORMTECH SC-740 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLER.
- STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
 - ONESHOOTER LOCATED OFF THE CHAMBER BED.
 - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
 - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
- MAINTAIN MINIMUM 6" (150 mm) SPACING BETWEEN THE CHAMBER ROWS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE 3/4"-2" (20-50 mm).
- THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN ENGINEER.
- ADS RECOMMENDS THE USE OF "TLESDORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.

NOTES FOR CONSTRUCTION EQUIPMENT

- STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- THE USE OF CONSTRUCTION EQUIPMENT OVER SC-740 CHAMBERS IS LIMITED:
 - NO EQUIPMENT IS ALLOWED ON BASE CHAMBERS.
 - NO RUBBER Tired LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNLESS PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
 - WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING. USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO THE CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.

CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.



NOMINAL CHAMBER SPECIFICATIONS

SIZE (W X H X INSTALLED LENGTH)	51.0" X 30.0" X 85.4" (1295 mm X 762 mm X 2169 mm)
CHAMBER STORAGE	45.9 CUBIC FEET (1.30 m ³)
MINIMUM INSTALLED STORAGE*	74.9 CUBIC FEET (2.12 m ³)
WEIGHT	75.0 lbs. (33.6 kg)

*ASSUMES 6" (152 mm) STONE ABOVE, BELOW, AND BETWEEN CHAMBERS

PRE-FAB STUB AT BOTTOM OF END CAP WITH FLAMP END WITH "BR"

PRE-FAB STUBS AT BOTTOM OF END CAP FOR PART NUMBERS ENDING WITH "B"

PRE-FAB STUBS AT TOP OF END CAP FOR PART NUMBERS ENDING WITH "T"

PRE-CORED END CAPS END WITH "PC"

PART #	STUB	A	B	C
SC740EPEDT / SC740EPEBTPC	6" (150 mm)	10.9" (277 mm)	18.5" (470 mm)	---
SC740EPEDB / SC740EPEDBPC	---	---	---	0.5" (13 mm)
SC740EPEBT / SC740EPEBTPC	8" (200 mm)	12.2" (310 mm)	16.5" (419 mm)	---
SC740EPEDB / SC740EPEDBPC	---	---	---	0.6" (15 mm)
SC740EPE10T / SC740EPE10TPC	10" (250 mm)	13.4" (340 mm)	14.8" (376 mm)	---
SC740EPE10B / SC740EPE10BPC	---	---	---	0.7" (18 mm)
SC740EPE12T / SC740EPE12TPC	12" (300 mm)	14.7" (373 mm)	12.5" (318 mm)	---
SC740EPE12B / SC740EPE12BPC	---	---	---	---
SC740EPE15T / SC740EPE15TPC	15" (375 mm)	18.4" (467 mm)	9.0" (229 mm)	1.2" (30 mm)
SC740EPE15B / SC740EPE15BPC	---	---	---	1.3" (33 mm)
SC740EPE18T / SC740EPE18TPC	18" (450 mm)	19.7" (500 mm)	5.0" (127 mm)	---
SC740EPE18B / SC740EPE18BPC	---	---	---	1.6" (41 mm)
SC740EPE24B*	24" (600 mm)	18.5" (470 mm)	---	0.1" (3 mm)
SC740EPE24BR*	24" (600 mm)	18.5" (470 mm)	---	0.1" (3 mm)

ALL STUBS, EXCEPT FOR THE SC740EPE24B/SC740EPE24BR ARE PLACED AT BOTTOM OF END CAP SUCH THAT THE OUTSIDE DIAMETER OF THE STUB IS FLUSH WITH THE BOTTOM OF THE END CAP. FOR ADDITIONAL INFORMATION CONTACT STORMTECH AT 1-888-892-2694.

* FOR THE SC740EPE24B/SC740EPE24BR THE 24" (600 mm) STUB LIES BELOW THE BOTTOM OF THE END CAP APPROXIMATELY 1.75" (44 mm). BACKFILL MATERIAL SHOULD BE REMOVED FROM BELOW THAT THE FITTING SITS LEVEL.

NOTE: ALL DIMENSIONS ARE NOMINAL

SC-740 TECHNICAL SPECIFICATIONS

183.6

CONSTRUCTION SEQUENCE FOR BASIN #6 NOTES:

- CHAMBER SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S LATEST INSTALLATION GUIDELINES.
- FOUNDATIONS: TRENCH BOTTOMS WITH UNSTABLE OR UNYIELDING MATERIAL SHALL BE EXCAVATED TO A DEPTH DIRECTED BY THE ENGINEER AND REPLACED WITH SUITABLE MATERIAL FOR UNSTABLE MATERIALS. GEOTEXTILE MAY BE USED TO STABILIZE THE TRENCH BOTTOM, IF DIRECTED BY THE ENGINEER. THE DESIGN ENGINEER IS RESPONSIBLE FOR VERIFYING FOUNDATION SUITABILITY.
- GEOTEXTILE: A 6oz. NON-WOVEN GEOTEXTILE FILTER FABRIC (AASHTO M288 CLASS 2) SHOULD BE USED TO PREVENT SOIL FROM MIGRATING INTO THE INITIAL BACKFILL MATERIAL. THE NON-WOVEN GEOTEXTILE FILTER FABRIC TO BE INSTALLED ALL AROUND THE BASIN #6. ALL SEAMS SHOULD HAVE 2 FOOT OVERLAPPING OF GEOTEXTILE MATERIAL.
- BEDDING: SUITABLE MATERIAL SHALL BE A 3/4" - 2" INCH, CLEAN, CRUST ANGULAR STONE, OR AASHTO M43 SIZES (3, 357, 4, 467, 5, 56,57) WITH CLEAN, CRUSHED, ANGULAR STONE ADDED TO THE GRADATION, e.g., CLEAN, CRUSHED, ANGULAR #3 (AASHTO M43) STONE. MINIMUM BEDDING THICKNESS SHALL BE 6 INCHES. COMPACTION SHOULD BE DONE IN LIFTS OF NO MORE THEN 9 INCHES TO A DENSITY OF 95% STANDARD PROCTOR DENSITY.
- EMBEDMENT BACKFILL: SUITABLE MATERIAL SHALL BE 3/4" - 2" INCH, CLEAN, CRUSHED ANGULAR STONE, OR AASHTO M43 SIZES (3, 357, 4, 467, 5, 56,57) WITH CLEAN, CRUSHED, ANGULAR STONE ADDED TO THE GRADATION, e.g., CLEAN, CRUSHED, ANGULAR #3 (AASHTO M43) STONE. EMBEDMENT BACKFILL SHALL EXTEND FROM TOP OF BEDDING TO NOT LESS THAN 6 INCHES ABOVE THE TOP OF THE CHAMBER. NO COMPACTION IS REQUIRED BUT AN EFFORT SHOULD BE MADE TO HAND KNIFE STONE INTO ALL CORRUGATIONS.

INSPECTION & MAINTENANCE

- INSPECT ISOLATOR ROW PLUS FOR SEDIMENT
 - INSPECTION PORTS (IF PRESENT)
 - REMOVE/OPEN LID ON INLET/OUTLET INLINE DRAIN
 - REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
 - USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG
 - LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL)
 - IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
 - ALL ISOLATOR PLUS ROWS
 - REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS
 - USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW PLUS THROUGH OUTLET PIPE
 - MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY
 - FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE
 - IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.

- CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS
 - A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45° (1.1 m) OR MORE IS PREFERRED
 - APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN
 - VACUUM STRUCTURE SUMP AS REQUIRED
- REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.
- INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

NOTES


- INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER LEVELS.
- CONDUCT JETTING AND VECTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.

ACCEPTABLE FILL MATERIALS: STORMTECH SC-740 CHAMBER SYSTEMS

MATERIAL LOCATION	DESCRIPTION	CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
C	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 18" (450 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	AASHTO M145 A-1, A-2, A-3 OR AASHTO M43 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 12" (300 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 6" (150 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS. ROLLER GROSS VEHICLE WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAMIC FORCE NOT TO EXCEED 20,000 lbs (89 kN).
B	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	AASHTO M43 3, 357, 4, 467, 5, 56, 57	NO COMPACTION REQUIRED.
A	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	AASHTO M43 3, 357, 4, 467, 5, 56, 57	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. 2,3

PLEASE NOTE:

- THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
- STORMTECH COMPACTION REQUIREMENTS ARE MET FOR "A" LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6" (150 mm) MAX LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR.
- WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAVING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.
- ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOLS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.




NOTES:

- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- SC-740 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 500 LBS/(7.75) AND 6) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- BEGIN COMPACTIONS AFTER 12" (300 mm) OF MATERIAL. COMPACT ADDITIONAL LAYERS IN 6" (150 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS. ROLLER GROSS VEHICLE WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAMIC FORCE NOT TO EXCEED 20,000 lbs (89 kN).

SC-740 CROSS SECTION DETAIL

183.6



NOTES:


- PART NUMBERS WILL VARY BASED ON INLET PIPE MATERIALS. CONTACT STORMTECH FOR MORE INFORMATION.
- CONTACT ADS ENGINEERING SERVICES IF INSERTA TEE INLET MUST BE RAISED AS NOT ALL INVERTS ARE POSSIBLE.

CHAMBER	MAX DIAMETER OF INSERT A TEE	HEIGHT FROM BASE OF CHAMBER (X)
SC-310	6" (150 mm)	4" (100 mm)
SC-740	10" (250 mm)	4" (100 mm)
DC-780	10" (250 mm)	4" (100 mm)
MC-3500	12" (300 mm)	6" (150 mm)
MC-4500	12" (300 mm)	8" (200 mm)
MC-7200	12" (300 mm)	8" (200 mm)

INSERT A TEE FITTINGS AVAILABLE FOR SDR 26, SDR 35, SDR 40 IPS ORKATED & SOLVENT WELD, H=12, HP STORM, C=900 OR DUCTILE IRON


INSERT A-TTEE SIDE INLET DETAIL

183.6




SC-740 CROSS SECTION OF BASIN #6

183.6



CONCRETE ANTI-SEEP COLLAR & CONCRETE CRADLE

SCALE: 1" = 5"



BASIN OR TRAP NO.	PIPE SIZE (IN)	S (IN)	NO. OF COLLARS	RISER TO FIRST COLLAR (FT)	COLLAR SPACING (FT)
#6	24	48	2	5	10

NOTES:
ALL COLLARS SHALL BE INSTALLED SO AS TO BE WATERTIGHT.
COLLAR SIZE AND SPACING SHALL BE AS INDICATED WITHIN TABLE.

CONCRETE ANTI-SEEP COLLAR FOR PERM. BASINS OR TRAPS (SCD 7-16)

183.6

NOTES:
A CONCRETE CRADLE MAY BE USED IN CONJUNCTION WITH ANTI-SEEP COLLARS AND/OR FILTER DIAPHRAGM.
ANTI-SEEP COLLAR NUMBER, SIZE AND SPACING SHALL BE AS SHOWN ELSEWHERE IN PLAN.
STANDARD CONSTRUCTION DETAIL #7-17
CONCRETE CRADLE FOR BASIN OR TRAP
OUTLET BARREL

183.6

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS, DRAWINGS & SPECIFICATIONS, ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

Date	Draft	Chkd	ISSUED FOR BIDS
11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION

POST CONSTRUCTION STORMWATER MANAGEMENT BASIN #6 DETAILS

CUMRU FIRE DEPARTMENT NEW BUILDING

Prepared For:
TOWNSHIP OF CUMRU

Site/Use In:
CUMRU TOWNSHIP, BERKS CO., PA.


PROJECT #:
2057000538

DRAWING #:
183.6


SHEET #:
21 OF 25

Jeffrey E. Skinner
PE-042652-E
SU-052889-E


ATLAS
920 GERMANTOWN PIKE, SUITE 200,
PLYMOUTH MEETING, PA 19462




PROPOSED BASIN #5 TO CROSS SECTION PROFILE
SCALE: V. 1" = 2'
H. 1" = 20'




PROPOSED SWALE #4A TO SWALE #4B PROFILE
SCALE: V. 1" = 2'
H. 1" = 20'



PROPOSED TRENCH DRAIN TO INLET #52 PROFILE
SCALE: V. 1" = 2'
H. 1" = 20'



PROPOSED YARD DRAIN #40 TO BASIN #5 PROFILE
SCALE: V. 1" = 2'
H. 1" = 20'



PROPOSED OS #47 TO EXIST. ENDWALL #30A PROFILE
SCALE: V. 1" = 2'
H. 1" = 20'

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION


Date	Draft	Chkd	
------	-------	------	--

POST CONSTRUCTION STORMWATER MANAGEMENT PROFILES
CUMRU FIRE DEPARTMENT NEW BUILDING
Prepared For:
TOWNSHIP OF CUMRU
Site: In:
CUMRU TOWNSHIP, BERKS CO., PA.


Jeffrey E. Skinner
PE-042652-E
SU-052889-E

ATLAS
920 GERMANTOWN PIKE, SUITE 200,
PLYMOUTH MEETING, PA 19462



PROJECT #:
Z057000538
DRAWING #:
183.7
SHEET #:
22 OF 25




EXISTING INLET #12 TO EXISTING ENDWALL #15 (PHASE #1) PROFILE
 SCALE: V. 1" = 2'
 H. 1" = 20'




PROPOSED INLET #54 TO BASIN #6 PROFILE
 SCALE: V. 1" = 2'
 H. 1" = 20'



PROPOSED O.S. #50 TO EXIST. INLET #12 PROFILE
 SCALE: V. 1" = 2'
 H. 1" = 20'



PROPOSED REAR OF BUILDING DRIVEWAY TO BASIN #5 PROFILE
 SCALE: V. 1" = 2'
 H. 1" = 20'



PROPOSED INLET #52 TO BASIN #6 PROFILE
 SCALE: V. 1" = 2'
 H. 1" = 20'

THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS & SPECIFICATIONS, ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FROM COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

11/30/2023	RC	JES	ISSUED FOR BIDS
08/11/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION

Date Draft Chkd

POST CONSTRUCTION STORMWATER MANAGEMENT PROFILES

CUMRU FIRE DEPARTMENT NEW BUILDING

Prepared For:
TOWNSHIP OF CUMRU

Site/ute In:
CUMRU TOWNSHIP, BERKS CO., PA.

PROJECT #:
 Z057000538


DRAWING #:
 183.8

SHEET #:
 23 OF 25

Jeffrey E. Skinner
 PE-042652-E
 SU-052889-E

ATLAS
 920 GERMANTOWN PIKE, SUITE 200,
 PLYMOUTH MEETING, PA 19462

S:\FILES\SERVER\Projects\Cumru\2057000538 - Resurf Fire Station\DWG\FIRE STATION\PCS14.dwg, 11/29/2023 2:51:07 PM, AutoCAD PDF (General Documentation).pc3



THIS CONFORMED SET IS COMPRISED OF THE ORIGINAL BID DOCUMENTS (BOTH THE DRAWINGS AND THE PROJECT MANUAL) AND REVISIONS REFLECTING THE CHANGES TO THE CONTRACT DOCUMENTS MADE IN ADDENDA 1-4. THIS CONFORMED SET SHALL BE CONSIDERED SECONDARY AND SUPPLEMENTAL TO THE CONTRACT DOCUMENTS, WHICH CONSIST OF THE BID DOCUMENTS (DRAWINGS & SPECIFICATIONS), ALL ADDENDA, AND THE OWNERS ACCEPTED BID ALTERNATES AND CONTINGENCIES. THIS CONFORMED SET IS PROVIDED AS A CONVENIENCE FOR COMPLIANCE WITH THE FULL REQUIREMENTS OF THE CONTRACT DOCUMENTS.

07/30/2023	RC	JES	ISSUED FOR BIDS
07/28/2023	RC	JES	REVISED DRAWINGS PER BCCD REVIEW E-MAIL, DATED 07/31/2023.
04/20/2023	RC	JES	NPDES PERMIT #PAD060047, PHASE #2 SUBMISSION

Date	Draft	Chkd
------	-------	------

PRE-DEVELOPMENT PHASE #2 DRAINAGES
CUMRU FIRE DEPARTMENT NEW BUILDING
 Prepared For:
TOWNSHIP OF CUMRU
 Situate In:
CUMRU TOWNSHIP, BERKS CO., PA.



Jeffrey E. Skinner
 PE-042652-E
 SU-052889-E



PROJECT #:
 Z057000538
 DRAWING #:
 184
 SHEET #:
 24 OF 25

S:\FILES\SERVER\Projects\Cumru\Z057000538 - Resurf Fire Station\DWG\FIRE STATION PRE-DRAIN AREAS.dwg, 11/29/2023 3:51:23 PM, AutoCAD PDF (General Documentation).pc3

