

ADMINISTRATION SQUARE FOOTAGE = 5,568
 APPARATUS BAYS SQUARE FOOTAGE = 5,760
 TOTAL SQUARE FOOTAGE = 11,328




1 FIRST FLOOR PLAN
 A-1.0
 1/8" = 1'-0"

WALL LEGEND

- TYPICAL EXTERIOR WALLS: 2X6 STUDS @ 16" O/C W/ 1/2" STRUCT. SHEATHING, 15# FELT, CEMENT BEVELED SIDING, R-19 BATT INSULATION W/ VAPOR BARRIER & 5/8" TYPE 'X' GYP. BD.
 - TYPICAL INTERIOR SOUND WALLS: 2X4 STUDS @ 8" O/C STAGGERED INSIDE @ PERIMETER OF ALL OFFICES, W.C.'S, CONFERENCE ROOM, TRAINING, INSULATION & 5/8" TYPE 'X' GYP. BD. @ EACH SIDE, TYPICAL U.I.O. PROVIDE 2X8 STUDS WHERE REQ'D FOR PLUMBING VERIFY W/ PLUMBING PRIOR TO FRMG. (SEE NOTES @ A-1.0 REGARDING FIRE RATED WALLS)
 - TYPICAL INTERIOR WALLS (N.O.S.): 2X4 STUDS @ 16" O/C W/ R-11 SOUND INSULATION & 5/8" TYPE 'X' GYP. BD. @ EA. SIDE.
- NOTE: ALL TACKBOARDS SHALL BE PLACED W/ TOP EVEN W/ TOPS OF DOOR HEADS TYP. PROVIDE FLAT BLK'G AS REQ.
- ALONG A WALL INDICATES WALL SHALL BE A 1-HOUR FIRE SEPARATED WALL FROM TOP OF CONCRETE TO BOTTOM OF ROOF SHT'G. SEE NOTES ON A-0.0 REGARDING FIRE RATING & CONTRACTOR OPTIONS @ SLEEPING ROOM WALLS.
- ALL PERIMETER WALLS OF SLEEPING ROOMS SHALL HAVE A 1/2 HR FIRE RATING & EXTEND FROM TOP OF CONC. TO BOTTOM OF ROOF SHT'G.

- LEGEND**
- DOOR # (SEE A-1.2)
 - WINDOW TYPE (SEE A-3.0)
 - INTERIOR ELEVATION REFERENCE
 - RELITE TYPE (SEE A-1.2)



615 SE ANDERSON STREET
 ROSELAND, OR 97270
 503.272.0273 OFFICE
 503.272.0273 FAX
 503.272.0273 CELL
 PAUL@PAULBENTLEYARCHITECT.COM

PAUL L BENTLEY Architect A.I.A. P.C.

ADDENDUM #3 BLDG DEPT. CHANGES 12-9-13
 ADDENDUM NO. 1 11-15-13

A NEW MAIN FIRE STATION FOR:
GLIDE RURAL FIRE PROTECTION DISTRICT
 18910 N. UMPQUA HWY. GLIDE, OR



DRAWN BY: CMHII
 CHECKED BY: PLB
 DATE: 10-28-19
 TITLE: FLOOR PLAN
 SCALE: 1/8" = 1'-0"

SHEET NO:
A-1.0
 OF 13