SAURYAJYOTI RENEWABLES PVT LIMITED

(RENEWABLE DIVISION OF M/S GANAPATI PRODUCTS)




PV INSTALLATION & QUALITY ASSURANCE BEST PRACTICES

PV INSTALLATION & QUALITY ASSURANCE BEST PRACTICES

Effective and simple designs are best

Equipment selection

- Installation work day & efficiency concepts
- Site prep and install processes
 (ground prep with clips and roof layout marking essentials)



SYSTEM COMPONENTS



PV Modules



Module Mounting Structures (MMS)



DC Cables



Strings Junction Box (SJB)




Inverters









Lightning Arrestors



AC Distribution Box (ACDB)



EFFECTIVE AND SIMPLE DESIGNS ARE BEST

- Goals = increase productivity and profitability
- Less complicated designs result in faster installations
- Typically more reliable performance

How?

• Avoid mini array "islands" (an array with only one or two modules)

Why?

- Lots of penetrations per module
- Lots of cabling and conduit runs
- More design challenges depending on inverters used
- More complications in predicting system performance

EFFECTIVE AND SIMPLE DESIGNS ARE BEST

How?

• Avoid overly challenging sites

Why?

- A skipped opportunity is a lot cheaper than a site that costs you money
- Liability on challenging roof types from leaks or damaged materials or excessive engineering and equipment costs
- Time spent to close the sale, design and build this one system could have been used on three other conventional sites. aka "opportunity cost"
- Reduced safety issues and mistakes.

EQUIPMENT SELECTION

Goals?

- Cost, be sure to include labor with your calcs
- Installation speed / productivity
- Reliability & performance
- Reduced callbacks
- Referrals
- Safety
- Modules
- Inverters
- Solar Structure / Racking
- BOS

EQUIPMENT SELECTION: MODULES

Modules

- Reliability
- Warranty
- Price
- Efficiency?
- kWh per KW or per square foot
- Crystalline Silicon poly vs mono / thin film

EQUIPMENT SELECTION: INVERTERS

Inverters

- Reliability
- Warranty
- Price
- Efficiency?
- String / Central inverter vs Micro inverter?
- Hybrid inverter string with optimizers
- Which is best?

EQUIPMENT SELECTION: RACKING

Solar Structure / Racking

- ✓ Reliability
- ✓ Warranty
- ✓ Price
- ✓ Efficiency?
- ✓ Physically
- ✓ Tested at manufacturer system approach
- ✓ Briefly it includes–Mechanical–Bonding/Grounding
- ✓ CABLE MANAGEMENT (& CONDUIT management)
- ✓ Include cable management and essential accessories
- \checkmark Install quickly with few tools
- $\checkmark\,$ Effective total solution that manages overall costs
- $\checkmark\,$ Roof attachments and flashing typically used

EQUIPMENT SELECTION: BOS

BOS balance of systems (everything else)

- ✓ Junction boxes
- ✓ Flashings (stay away from rubber boot based)
- ✓ Wire splices
- ✓ Sub panels
- ✓ Meter mounts
- ✓ Switch gear
- ✓ DC disconnects needed? Odd site or PV location?
- ✓ Conduit supports? Conduit bonding clamp

INSTALLATION WORK DAY: EFFICIENCY

Industry standard, a PV install in one day is typical

How?

- ✓ Good design
- ✓ Right equipment helps, especially if its mostly pre assembled
- ✓ Man hours per kw is still important
- ✓ eg: nine person crew installing 5kw in one day is likely more expensive than three person crew taking two days...

INSTALLATION WORK DAY: PLAN AND COMMUNICATE

Planning ahead of time and communicating with homeowner is essential.

Before work starts communicate a plan with your team. -Even drawing out pv stringing on a scrap can be a timesaver.

Set clear goals

- -"By 10 am break all racking footings should be in"
- -"before lunch all racking should be installed and leveled"
- -"we should be laying glass after lunch and testing the system by 3pm..."

Complete as much work as possible at your warehouse or on the ground -module wire management with wire clips

-prefabricate sub panels

INSTALLATION WORK DAY: PLAN AND COMMUNICATE

Misc

Work like a machine (or an assembly line)

- One person drills and applies sealant to holes, another follows with L feet/standoffs and flashings
- ✓ If there is a bottleneck redirect or rotate to other items then resume assembly line

Try to stay out of the house (garage) if you can

✓ Gear can usually be installed quicker and more readily serviced

Installation Quality

Why does quality matter?

- ✓ Performance
- ✓ Safety
- ✓ Liability
- ✓ Pride & morale
- ✓ Reliability
- ✓ Service costs / call backs
- ✓ Referrals

Installation Quality

Check quality while you work and when system is completed...

- It's best to maintain quality as you work rather than returning to correct something
- If documentation is needed, it may be best to collect while installation is underway
- Sometimes a 2nd opinion can provide a better solution
- It's best to promote high quality not just pick on mistakes
 - ✓ Friendly competition and positive reinforcement can promote productivity and morale. Take pride in your work.

Common Tools & Equipment's Used

Wire Cutter

Honni.





Srew Drivers



Hammer

Battery Maintenance Kit



Compass

Measuring Tape

Megohm meter Crimping Tool Set

Nut Drivers

Angle Finder



Flashlight

Cutting Piler Wire Stripper

Cleaning Brush Battery water filler





Clamp Meter

Pyranometer



Hydrometer

Multimeter



Some observations from Site – DUST Effect

a) Dust observed on PV Modules?



Cleaned Modules



Cleaning Required Shortly (No significant financial impact)



Cleaning required (Significant financial impact)

The table alongside shows the impact of dust in month of 'December' on a 10 kW system

*Rs. 5.14 is the Tariff Rate (per unit price) considered for calculation for a domestic consumer.

For a commercial consumer, the rate is doubled (Rs. 10/-)

b) Effect of Dust on PV Modules

PV Module Actua	Actual Monthly Energy Generation	
Uncleaned Modules	1,143 kWh	
Cleaned Modules	1,443 kWh	
Table 1: Effect of dust on PV Modules		
Line Company of the second sec	43 Units 1,443 Units cleaned) (Cleaned)	
Units Gained - (1,443 - 1,143)	300 Units	
Monthly Savings - (300 × 5.14*)	Rs.1,620	
Daily Saving - (Rs 1,620 ÷ 30)	Rs.54 / day	
Annual Saving - (54 × 365)	Rs.19,500 /year	

Financial analysis of dust on PV Modules

Some observations from Site – MODULE SHADING

a) Shading observed on PV Module?



Modules being used to dry chilies



Shading on PV modules due to surrounding objects



Power loss due to shading on modules

Daily Generation	4.2 Units (Shaded)	7.5 Units (Unshaded)	
Units Gained = (7.5 - 4.2)	3.3 Units		
Daily Savings = (3.3 × 5.14*)	Rs.17 /day		
Monthly Saving = (Rs 17 × 30)	Rs.510 / month		
Annual Saving = (510 × 12)	~ Rs.6,100 /year		
Financial analysis of shading on PV Modules			
*Assumption: Rs. 5.14/kWh is the power tariff rate of an			

"Assumption: Rs. 5.14/KWh is the power tariff rate of an average residential customer

Some observations from Site – PHYSICAL INTEGRITY OF PV MODULES

a) Physical Integrity observed?



Moisture Condensation



Tiny Hairline Cracks



Corrosion



Delamination





Damaged Module



Never climb on modules



Never sit or stand on PV modules

Some observations from Site – PHYSICAL INTEGRITY OF INVERTERS




Check the inverter's display screen, which is the primary indicator of a possible problem with the inverter. The inverter can detect and display inverter warnings and faults.

LED Green - Indicating correct operation of inverter



LED Red - Indicating incorrect operation of inverter



• Check inverter display and record all input and output voltages readings.



Figure 81: Inverter damage - Burn out



Disconnected wire from inverter base



Dust accumulation on Inverter

• Visually check or inspect the inverter for external damage.

Check for loose or disconnected
 wires

- Check for noise levels of inverter through an audio check. If you notice that inverter is producing a large humming sound, then contact your service provider. Refer (Unit 3 Advanced Section).
- Inspect, clean or replace the filters (By trained personnel only).

Inverter display screen

Some observations from Site – PHYSICAL INTEGRITY OF BOS



Cables are tied using cable tie



Blown fuse



Incorrect cables connection looped tightly



Incorrect cables connection looped loosely



Correct cabling connection



Properly insulated



Improper insulation



Incorrect - Conduits are damaged



Correct - Conduits are in proper condition



Incorrect - Cable conduit are not closed



Correct- Cable conduit are closed

Some observations from Site – STRUCTURE & EARTHING



Cables are labelled properly



Cables are not labelled properly




Rusting of Mounting structure



Poor Lightning Protection



Good Lightning Protection



No Equipment Grounding

Proper Equipment Grounding



Loosed clamps






Good Installation

Bad Installation

Some observations from Site – INVERTER READINGS



Inverter display screen showing units generated by PV system



Net metering display screen showing units consumed by consumer

Some observations from Site – SAFETY NORMS



Incorrect practice - Without safety helmet



Correct practice - With safety helmet



Incorrect practice - Normal glasses



Incorrect practice - Without face shield



Correct practice - With face shield





PVC Gloves



Incorrect practice - Without safety gloves



Correct practice - With safety gloves

Cotton Gloves



Incorrect practice - Without safety shoes



Correct practice - With safety shoes

