



## HOW TO PREPARE FOR YOUR WALLPAPER INSTALLATION

### **General Workspace Requirements:**

- A 9'x 9' minimum clear area to set up a worktable and pasting machine
- Jobsite must have working HVAC and be between 68-70 degrees during the install
- Access to clean, hot and cold water
- All furniture must be moved at least 4ft off any wall that will be wallpapered
- All TVs, hardware, lighting, outside mounted window treatments, artwork, mirrors and wall décor must be off the wall and placed in a secure location. If you are placing the item in the same location after the wallpaper is installed, the hanging hardware may remain, otherwise the hanging hardware should also be removed, and any large holes filled with spackle and sanded once dry.

### **Specific Requirements**

#### *1. Powder Rooms*

- Anything on the wall as described in General Workspace Requirements above should be removed
- Light fixtures should be off so that wallpaper can be hung to the junction box.
- All toiletries, garbage bins, plungers, toilet bowl brushes etc. should be removed.
- If new construction, the paper should be hung **BEFORE** the toilet and/or pedestal sink are installed. If not new construction, the pedestal needs to be uninstalled as well as the tank of the toilet if it closer than 3" to the wall.
- All surfaces are to be cleaned and disinfected.

#### *2. Full Bathrooms*

- Anything on the wall as described in General Workspace Requirements above should be removed. **This also includes any shower rods and hardware.**
- Light fixtures should be off so that paper can be hung to the junction box.
- All toiletries, garbage bins, scales, etc. should be removed
- All surfaces are to be cleaned and disinfected.
- If part of the general space and not in a separate water closet
  - Plungers, toilet bowl brushes etc. should be removed
  - The tank of the toilet needs to be uninstalled if it closer than 3" to the wall



## HOW TO PREPARE FOR YOUR WALLPAPER INSTALLATION

### 3. *Water closets*

- Anything on the wall as described in General Workspace Requirements above should be removed.
- All toiletries, garbage bins, scales, plungers, toilet bowl brushes etc. should be removed
- The tank of the toilet needs to be uninstalled if it closer than 3" to the wall
- All surfaces are to be cleaned and disinfected

### 4. *Ceilings*

- Everything must be removed from directly under where the wallpaper is to be installed as to avoid any primer or paste from contacting personal belongings. Please make the necessary arrangements to have this completed by the day of installation as we do not move personal items or furniture.
- All lighting fixtures should be removed.

### 5. *Laundry Rooms*

- Anything on the wall as described in General Workspace Requirements above should be removed.
- Washer and Dryer must be completely unhooked and moved to center of space if wallpaper is being installed behind or beside them.