

AMJ Plumbing
4708 Brenda St NE
Albuquerque, NM 87109 USA
+15053154523
jones.markw@gmail.com

Estimate

ADDRESS
Pat & Paul Willems Pat & Paul Willems 4709 Brenda St. NE Albuquerque, New Mexico 87109

SHIP TO
Pat & Paul Willems Pat & Paul Willems 4709 Brenda St. NE Albuquerque, New Mexico 87109

ESTIMATE #	DATE	EXPIRATION DATE
4709 Brenda	08/19/2025	09/19/2025

DATE	SERVICE	DESCRIPTION	QTY	RATE	AMOUNT
	01 Plans and Permits	Plans and Permits	1	260.00	260.00T
	22 Specialty	Specialties; Crane & operator	2	635.00	1,270.00T
	15 HVAC	Heating & Cooling	11	135.00	1,485.00T
	Materials	Misc., Materials: 1/4" copper tubing, duct sealant, curb, etc.	1	368.34	368.34T

4709 Brenda St NE,
Evaporative cooler removal:
Disconnect and remove the existing evaporative cooler from the roof, using a crane if necessary due to its size and weight.
Ensure all electrical and water connections are properly disconnected and capped off to prevent hazards during the roof replacement.
Lower the evaporative cooler to the ground, taking precautions to avoid damage to the unit or the roof.
Address the roof penetration left by the evaporative cooler removal:
Supply and install a suitable roof curb or stop for the evaporative cooler penetration, if needed. This ensures proper flashing and weatherproofing to prevent leaks after the cooler is reinstalled.
Once the new roof is complete and the curb/stop is in place, re-install the evaporative cooler onto the roof.
Connect the unit to a new water line, ensuring proper seals and connections.
Install a new leg kit if required for stable mounting on the new roof structure.

SUBTOTAL	3,383.34
TAX	257.98
TOTAL	\$3,641.32

Accepted By

Pat & Paul Willems

Accepted Date

08/19/2025