

**Project Name:** PS 154 (1625 11TH AVE, BROOKYN, NY)  
**Ref. DWG #'s:** S-201  
**Location:** S-201 "A" SOUTH ELEVATION

PC#	Material	lb's per	Length Ft.	lb's	Ind. PC		Notes
					lb	Hr's	
3	L6X4X3/8	12.30	92.50	3413	1138	20	"A5"/S401
6	L6X4X3/8	12.30	26.17	1931	322	18	
6	L6X4X5/16	10.30	26.17	1617	270	18	
81	PL5/16"x11"	11.70	1.50	1422	18	12	"A1"/S402
3	L8X4X1/2	19.60	26.00	1529	510	12	
3	L2X2X3/8	4.70	26.00	367	122	6	
20	PL5/16"x11"	11.70	1.50	351	18	6	
2	L2X2X3/8	4.70	10.66	100	50	4	
2	L8X4X1/2	19.60	10.66	418	209	4	
4	C12X20.7	8.00	8.25	264	66	5	"B3"/S402
4	L4X4X5/16	8.00	8.25	264	66	4	
12	HSS12X4X3/8"	37.69	15.63	7067	589	47	"B1"/S-401
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
				0	#DIV/0!	0	
<b>146</b>		<b>128</b>		<b>18743</b>		<b>156</b>	

avg pc #

Detail Material	pc # / LF	lb's	Hr's
			0
			0
			0
			0
			0
			0
			0
			0
			0
			0
			0
(48) rebar Couplers			0
(24) 1/2" RODS X 3"LONG W/ NUT			0
			0
			0
			0
			0
	<b>0</b>		<b>0</b>

	Qty.	Units	Rate
Material	20,617	lb	\$0.77
Galvanizing	9,436	lb	\$0.34
Deck	47	Sq. Ft.	\$3.00
Shop Fab.	156	Hr.	\$65
Red Oxide Painting	41	Hr.	\$40
Detailing	32	Hr.	\$65
Trucking	8	Unit	\$300
PM	24	Hr.	\$70
Foreman	7	Day	\$890
Ironworkers	14	Day	\$890
Inspection		Unit	\$600
Equipment Rentals		Day	\$50
Crane/ Crane Permit		Day	\$5,000
Expansion Bolts		Unit	\$4.00
Shear Studs		Unit	\$4.00
Epoxy Anchors	96	Unit	\$12.00
Anchor Bolts		Unit	\$3.00
Couplers and rods	72	Unit	\$7.14
Mics		Unit	
Other		Unit	
<b>Total</b>			

\_\_\_\_\_

**Detail**


<b>Cost</b>
\$15,845
\$3,208
\$141
\$10,172
\$1,649
\$2,080
\$2,400
\$1,680
\$6,230
\$12,460
\$0
\$0
\$0
\$0
\$0
\$0
\$1,152
\$0
\$514
\$0
\$0
<b>\$57,532</b>