

EXHIBIT G – FINISH SCHEDULE (FLOORING-RELATED)

Project: Warrior Hall Interior Renovation – St. Martin's Episcopal School

Location: 3110 Ashford Dunwoody Road, Atlanta, Georgia 30319

Issue: Schematic Design – 02.03.2026

Scope Limited To: Division 09 Flooring-Related Finishes

Documents Reviewed: Finish Schedule A-701; Finish Plans A-711, A-712, A-713

Created By: Compass Global | Powered by SQUARES AI Platform

FLOOR FINISHES

Finish ID	Manufacturer	Product / Series	Color / Pattern	Notes
LVT-1	Shaw Contract	Union 4349V	Concrete Spindle 49140	Classrooms – See Finish Plans A-711
LVT-2	Shaw Contract	Inlet 0926V	Spindle 26140	Hallways – See Finish Plans A-711
LVT-3	Shaw Contract	Commingle 4350V	Concrete 50105	Lab / X-Ray / Breakroom – Per A-712
LVT-4	Shaw Contract	Solo 5.0mm 4536V	Spindle 49140	Location Per Plans A-711 / A-712 / A-713
CPT-1	Shaw Contract	Atlas 5A267	Empathy 67100	Classrooms – 8' x 10' – Refer to A-711
CPT-2	Mohawk	exploreD BT609	973 Bearpaw	Alumni Room – Per A-712
CPT-3	Mohawk	exploreD BT609	975 Raven	Media Center – Per A-713
EP-1	Stonhard	Stonshield HRI Broadcast	Color TBD by Architect	Restrooms – Integral 4" Base – See Finish Schedule A-701

BASE FINISHES

Finish ID	Manufacturer	Product	Color	Height / Notes
RB-1	Flexco	Rubber Base	030 Meridian Bone	4" – Throughout U.N.O. – Per Finish Schedule A-701