

ST MARTINS EPISCOPAL SCHOOL
3110 ASHFORD DUNWOODY ROAD
ATLANTA GA

Style: Color	Extra waste	Gross Qty
CI **UNKNOWN FINISH**	0.00%	79.45 SF
CPT1 Shaw Contract, Atlas 5A267, Empathy 67100 [8'x10']	0.00%	17.78 SY
CPT2 Mohawk, Explored, BT609, 973 Bearpaw [24"x24"]	3.00%	206.92 SY
CPT3 Mohawk, Explored, BT609, 975 Raven [24"x24"]	3.00%	417.49 SY
EPI Stonhard, Stonsheid, HRI Broadcast, Medium Texture, Color TBS	0.00%	56.85 SF
LVT1 Shaw Contract, Union 4349V, Concrete Spindle 49140 [9"x48"]	3.00%	11,531.88 SF
LVT2 Shaw Contract, Inlet 0926V, Spindle 26140 [9"x48"]	3.00%	7,233.69 SF
LVT3 Shaw Contract, Commingle 4350V, Concrete 50105 [9"x48"]	3.00%	1,906.53 SF
RBI Flexco, 030 Meredian Bone, Rubber Base [4"]	3.00%	3,944.05 LF
STAIR LANDINGS- FINISH IS NOT KNOWN	0.00%	671.91 SF
TS01 Transition- Carpet to Resilient	3.00%	68.27 LF
TS02 Transition- Resilient to Epoxy	3.00%	3.23 LF
WDF Nosing to Match [assumed]	3.00%	78.42 LF
WDF- Unspecified Finish- Stage	15.00%	248.40 SF

ESTIMATED BY: CCCE

ESTIMATE# 2026-014

DATE PRINTED: 02-12-26

NUMBER OF PAGES: --