



2018-19 Corium Installation & Production Values

	Avg. Crew Size	Avg. Rate \$/Hr	Production (SF) Per-Crew-Day	Production (SF) Per-Man-Hour	Production Brick-Per-Day	Installation Cost-Per-SF
<u>Vert. Rail (16" Centers)</u>						
Efficient Wall Area	3	\$ 80.00	1200	50		\$ 1.60
Moderate Wall Area	3	\$ 80.00	800	33.33		\$ 2.40
Complex Wall Area	3	\$ 80.00	600	25.00		\$ 3.20
Avg.				36.11		\$ 2.40
<u>Trays (8' Lengths)</u>						
Efficient Wall Area	3	\$ 80.00	1500	62.50		\$ 1.28
Moderate Wall Area	3	\$ 80.00	1100	45.83		\$ 1.75
Complex Wall Area	3	\$ 80.00	800	33.33		\$ 2.40
Small Qty/Mockup	3	\$ 80.00	800	33.33		\$ 2.40
Avg.				43.75		\$ 1.96
<u>Brick (US or UK Modular)</u>						
Efficient Wall Area	3	\$ 80.00	900	37.50	6300	\$ 2.13
Moderate Wall Area	3	\$ 80.00	600	25.00	4200	\$ 3.20
Complex Wall Area	3	\$ 80.00	400	16.67	2800	\$ 4.80
Avg.		\$ 80.00		26.39		\$ 3.38
<u>Mortar/Strike</u>						
Mechanical Ground Pump	3	\$ 80.00	750	31.25		\$ 2.56
Mortar Bags	3	\$ 80.00	500	20.83		\$ 3.84
Mortar Hand Gun	3	\$ 80.00	400	16.67		\$ 4.80
Drill Pump	3	\$ 80.00	1000	41.67		\$ 1.92
Avg.				27.60		\$ 3.28
<u>Strike & Brush Mortar</u>						
Hand Tools	2	\$ 80.00	1000	62.50		\$ 1.28
<u>Washdown - Optional</u>						
Detergent & Brush	2	\$ 70.00	1200	75.00		\$ 0.93

Total Installation Cost		
Efficient	\$ 9.79	/SF
Moderate	\$ 13.40	/SF
Complex	\$ 17.41	/SF
Avg	\$ 13.23	/SF

3 Man Crew Production - Avg.	
Z-Rail/Substructure	866.67 SF/Crew Day
Trays	1050.00 SF/Crew Day
Brick	633.33 SF/Crew Day
Mortar/Strike	662.50 SF/Crew Day
Washdown	1800.00 SF/Crew Day