

Workbook 6

Question 3

Explain what should be confirmed, if issuing a permit to release a hold point or load/bring in to use. **List** the missing words in the following clause.

1. The temporary works have been (1)_____ in accordance with a (2)_____ design.
2. Any modifications to the temporary works have been approved by the (3)_____.
3. (4)_____, (5)_____ and environmental conditions are envisaged by the (6)_____.

Hint: Page 121 or [BS 5975-1:2024](#) clause 13.2.1.3

- | | |
|----|----|
| 1. | 4. |
| 2. | 5. |
| 3. | 6. |

Question 4

Explain the procedure for dismantling temporary works. **List** the missing words in the following clause.

1. When the structure being supported by the temporary works has become (1)_____, or the excavation has been (2)_____ or other condition, the temporary works should be dismantled (removed) in accordance with any restrictions imposed by the (3)_____ as set out in the (4)_____.
2. As at the loading stage, a permit to (5)_____ the temporary works might be appropriate, particularly where this takes place in (6)_____.
3. Care should be taken to keep the temporary works (7)_____ during all stages of the dismantling process.

Hint: Page 133 or [BS 5975-1:2024](#) clause 13.3

- | | |
|----|----|
| 1. | 5. |
| 2. | 6. |
| 3. | 7. |
| 4. | |