



[Redacted] Inc
 CSLB No. [Redacted]
 [Redacted]
 Roseville, CA. 95661
 [Redacted].com/
 [Redacted]ns.com
 +1415 [Redacted]

Quote

QT00157

Pacific Villas Apartments	Site	Pacific Villa Apartments	Date	20 June 2023
	Site Address	4550 Shelley Court Stockton California United States 95207	Expiry Date	20 July 2023
	Reference	Metal Trash enclosure rebuild x 3, and repair/mitigate t111 siding damage due to fire and smoke.	Tax Number	[Redacted]

Description	Quantity	Unit Price	Amount
Provide labor and materials.	1	108,750.00	108,750.00
		Subtotal	108,750.00
Total USD			108,750.00

Provide labor and materials remove, demolish, and properly dispose of the existing emanated and fire burnt trash enclosure(s).

Provide labor and materials to construct and build (3) new 10' x 12' trash enclosures with 4x4 x 1/4 thick square tubing posts at 8' on center max. 2 gates per trash enclosure (5' each 10' total opening span) with heavy gauge corrugated walls and roof structure. 4x6 x 1/4 horizontal bumper rails on three sides of interior (2 different rails at approximately 8" off the ground and 42" off the ground respectively) as required to serve as interior bumper rails to protect trash enclosure walls for actual trash cans. There will be a side man door approximately 42" for trash dumping . Footings will be approximately 18" square by 2)" deep on posts spaced 8' on center. Corrugated pan decking thickness will be 20 gauge. Scope includes paint to match existing building facade. Gate hardware will be (2) 3/4 inch bolts one in each gage and heavy duty latching system.

Repair and replace building facade t11 siding as needed where smoke and fire damage occurred proximal to fire unit that burned causing smoke and fire damage to building facade. Paint match existing colors with owner provided paint.

Exclusions: Plans, Permits, Inspections, engineering, drawings, special inspections, and anything not listed within this scope of work. Please note that this scope of work does not include planning approvals, paint match, and anything else not

specifically listed within this scope of work. Concrete and concrete pad. New trash enclosures will have a footing for the posts, but not a concrete pad. Ada accessible site improvements and path of travel. Drainage and or 2% slope of Asphalt. Structural members, insulation, interior wall smoke damage. Scope of work includes and assumes building facade smoke/fire damage only and presupposed siding replacement of t111 existing in like for like manner only. Paint match excluded.