



(254) 836-0413 info@fullhouseinspect.com https://fullhouseinspect.com



RESIDENTIAL HOME INSPECTION

1234 Main Street Waco TX 76708

> Buyer Name 10/10/2023 9:00AM



Inspector
Jordan Peitsmeyer
TREC Lic #21056
(254) 836-0413
info@fullhouseinspect.com



Agent Name 555-555-5555 agent@spectora.com



PROPERTY INSPECTION REPORT FORM

Buyer Name Name of Client 1234 Waco TX 76708	10/10/2023 9:00AM Date of Inspection
Address of Inspected Property	
Jordan Peitsmeyer	TREC Lic #21056
Name of Inspector	TREC License #
Name of Sponsor (if applicable)	TREC License #

PURPOSE OF INSPECTION

A real estate inspection is a visual survey of a structure and a basic performance evaluation of the systems and components of a building. It provides information regarding the general condition of a residence at the time the inspection was conducted. *It is important* that you carefully read ALL of this information. Ask the inspector to clarify any items or comments that are unclear.

RESPONSIBILITY OF THE INSPECTOR

This inspection is governed by the Texas Real Estate Commission (TREC) Standards of Practice (SOPs), which dictates the minimum requirements for a real estate inspection.

The inspector IS required to:

- use this Property Inspection Report form for the inspection;
- inspect only those components and conditions that are present, visible, and accessible at the time of the inspection;
- indicate whether each item was inspected, not inspected, or not present;
- indicate an item as Deficient (D) if a condition exists that adversely and materially affects the performance of a system or component **OR** constitutes a hazard to life, limb or property as specified by the SOPs; and
- explain the inspector's findings in the corresponding section in the body of the report form.

The inspector IS NOT required to:

- identify all potential hazards;
- turn on decommissioned equipment, systems, utilities, or apply an open flame or light a pilot to operate any appliance;
- climb over obstacles, move furnishings or stored items;
- prioritize or emphasize the importance of one deficiency over another;
- provide follow-up services to verify that proper repairs have been made; or
- inspect system or component listed under the optional section of the SOPs (22 TAC 535.233).

RESPONSIBILTY OF THE CLIENT

While items identified as Deficient (D) in an inspection report DO NOT obligate any party to make repairs or take other actions, in the event that any further evaluations are needed, it is the responsibility of the client to obtain further evaluations and/or cost estimates from qualified service professionals regarding any items reported as Deficient (D). It is recommended that any further evaluations and/or cost estimates take place prior to the expiration of any contractual time limitations, such as option periods.

Please Note: Evaluations performed by service professionals in response to items reported as Deficient (D) on the report may lead to the discovery of additional deficiencies that were not present, visible, or accessible at the time of the inspection. Any repairs made after the date of the inspection may render information contained in this report obsolete or invalid.

REPORT LIMITATIONS

This report is provided for the benefit of the named client and is based on observations made by the named inspector on the date the inspection was performed (indicated above).

ONLY those items specifically noted as being inspected on the report were inspected.

This inspection IS NOT:

- a technically exhaustive inspection of the structure, its systems, or its components and may not reveal all deficiencies;
- an inspection to verify compliance with any building codes;
- an inspection to verify compliance with manufacturer's installation instructions for any system or component and DOES NOT imply insurability or warrantability of the structure or its components.

NOTICE CONCERNING HAZARDOUS CONDITIONS, DEFICIENCIES, AND CONTRACTUAL AGREEMENTS

Conditions may be present in your home that did not violate building codes or common practices in effect when the home was constructed but are considered hazardous by today's standards. Such conditions that were part of the home prior to the adoption of any current codes prohibiting them may not be required to be updated to meet current code requirements. However, if it can be reasonably determined that they are present at the time of the inspection, the potential for injury or property loss from these conditions is significant enough to require inspectors to report them as Deficient (D). Examples of such hazardous conditions include:

- malfunctioning, improperly installed, or missing ground fault circuit protection (GFCI) devices and arc-fault (AFCI) devices;
- ordinary glass in locations where modern construction techniques call for safety glass;
- malfunctioning or lack of fire safety features such as smoke alarms, fire-rated doors in certain locations, and functional emergency escape and rescue openings in bedrooms;
- malfunctioning carbon monoxide alarms;
- excessive spacing between balusters on stairways and porches;
- improperly installed appliances;
- improperly installed or defective safety devices;
- lack of electrical bonding and grounding; and
- lack of bonding on gas piping, including corrugated stainless steel tubing (CSST).

Please Note: items identified as Deficient (D) in an inspection report DO NOT obligate any party to make repairs or take other actions. The decision to correct a hazard or any deficiency identified in an inspection report is left up to the parties to the contract for the sale or purchase of the home.

This property inspection report may include an inspection agreement (contract), addenda, and other information related to property conditions.

INFORMATION INCLUDED UNDER "ADDITIONAL INFORMATION PROVIDED BY INSPECTOR", OR PROVIDED AS AN ATTACHMENT WITH THE STANDARD FORM, IS NOT REQUIRED BY THE COMMISSION AND MAY CONTAIN CONTRACTUAL TERMS BETWEEN THE INSPECTOR AND YOU, AS THE CLIENT. THE COMMISSION DOES NOT REGULATE CONTRACTUAL TERMS BETWEEN PARTIES. IF YOU DO NOT UNDERSTAND THE EFFECT OF ANY CONTRACTUAL TERM CONTAINED IN THIS SECTION OR ANY ATTACHMENTS, CONSULT AN ATTORNEY.

ADDITIONAL INFORMATION PROVIDED BY INSPECTOR

Notice:

- Photos on the report may not show all of the deficiencies in any given area. Photos are not taken of every deficiency.
- Items marked "Note:" or "Informational Item" are informational and not necessarily deficient as far as the Texas Standards of Practice is concerned.
- Mold/Mildew investigations are NOT included with this report; it is beyond the scope of this inspection at the present time. Any reference of water intrusion is recommended that a professional investigation be obtained.

In Attendance: Buyer Agent, Buyer, Inspector

Occupancy: Occupied

Temperature (Approximate) Degrees Fahrenheit: 70's, 80's

House/Property Facing Direction: East

Weather Conditions: Clear -

	7	. •
	n	tice:
ιν.	v	ucc.

THIS REPORT IS PAID FOR BY AND PREPARED FOR THE CLIENT NAMED ABOVE.
THIS REPORT IS NOT VALID WITHOUT THE SIGNED SERVICE AGREEMENT AND IS NOT TRANSFERABLE.

Inaccessible or Obstructed Areas: Walls/Ceilings Covered or Freshly Painted, Behind/Under Furniture and/or Stored Items, Attic Space is Limited - Viewed from Accessible Areas, Plumbing Areas - Only Visible Plumbing Areas Inspected

I=Inspected NI=Not Inspected

NI NP D NP=Not Present **D=Deficient**

I. STRUCTURAL SYSTEMS

X A. Foundations

Type of Foundation(s): Slab on Grade

Comments:

Note: Weather conditions, drainage, leakage, and other adverse factors are able to affect structures, and differential movements are likely to occur. The inspector's opinion is based on visual observations of accessible and unobstructed areas of the structure at the time of the inspection. Future performance of the structure cannot be predicted or warranted.

Foundation Performance Opinion: (An opinion on performance is mandatory): The foundation may be in need of repair based on evidence of substantial structural movement observed at the inspection. A structural engineer or foundation professional should be contacted for further evaluation of the structure and to provide suggestions as to any corrective actions that may be needed. -

Signs of Previous Structural Movement or Settling: Cracks in interior walls and or ceilings, Separations at brick frieze corners, Floors not level, Cracks in exterior wall cladding, Drifting doors, Cracks in exposed footers and or skirting materials, Door and/or window frames out of square -

How was the Foundation Inspected?: A visual inspection of readily accessible foundation and structural components was performed. The inspector does not use specialized measuring devices to determine elevation or levelness of the structure. Any specialized testing should be performed by a qualified structural professional. -

SUGGESTED FOUNDATION MAINTENANCE AND CARE:

Proper drainage and moisture maintenance to all types of foundations is necessary due to the expansive nature of the area load bearing soils. Drainage must be directed away from all sides of the foundation with grade slopes. In most cases, floor coverings and/or stored articles prevent recognition of signs of settlement cracking in all but the most severe cases. It is important to note, this was not a structural engineering survey nor was any specialized testing performed of any sub-slab plumbing systems during this limited visual inspection, as these are specialized processes requiring excavation. In the event that structural movement is noted, the client is advised to consult with a Structural Engineer who can isolate and identify causes and determine what corrective steps, if any, should be considered to either correct and/or stop structural movement.

NI=Not Inspected

NP=Not Present

D=Deficient

NI NP D

1: Cracked Corners

✓ Informational Item

Note: Cracks or "corner pops" observed at the exterior foundation corners are typical and do not usually represent a structural concern.



2: Hairline Foundation Cracks

Informational Item

Typical hairline cracks were observed in the foundation walls of the house. This implies that some structural movement of the building has occurred.



3: Significant Foundation Movement

Deficiency

Evidence of significant structural movement was observed. It is recommended that a qualified structural professional be consulted for further evaluation of the structure and to provide suggestions as to what, if any, corrective actions should be taken.

I=Inspected NI=Not Inspected

NP=Not Present

D=Deficient

NI NP D

☑ □ □ ☑ B. Grading and Drainage

Comments:

1: Low Soils

Deficiency

Improper grading was observed. The grading should be improved to promote the flow of storm water away from the house. This can usually be accomplished by the addition or removal of topsoil. (Standing or ponding water at the foundation can affect the performance of the foundation) The ground should slope away from the house at a rate of 6 inches for the first ten feet.



2: Sidewalks High

Deficiency

Sidewalks or flatwork surrounding or connected to parts of the foundation are higher than the adjacent grade at the foundation. This can lead to standing water at the foundation which can contribute to foundation movement or moisture issues.



☑ □ □ ☑ C. Roof Covering Materials

•

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

Types of Roof Covering: Composition Shingles (Architectural)

Viewed From: Viewed from Rooftop

Comments:

1: Flashings Missing

Deficiency

No flashings installed where shingles meet the vertical walls in one or more locations. This is conducive to moisture infiltration.



Front Exterior

2: Rubber Rain Collar Missing

Deficiency

Rubber rain collar was missing. Repairs should be performed to prevent storm water from entering the structure.



☑ □ □ ☑ D. Roof Structures and Attics

Viewed From: Entered the Attic (Limited Visibility and Access)

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

Approximate Average Depth of Insulation: 5 Inches

Comments:

Limited Access and Visibility:

Note: Not all portions of the roof structure and attic were visible or accessible for inspection.

1: Missing Insulation

Deficiency

Missing insulation observed in the attic. This results in reduced insulating efficiency and typically higher utility bills.



2: Insulation Improvements Recommended

Deficiency

Insulation improvements recommended. Insulation improvements may be cost effective, depending on the anticipated term of ownership.

I=Inspected NI=Not Inspected

NI NP D **NP=Not Present**

D=Deficient

3: Vermin in Attic

Informational Item

Evidence of previous vermin activity observed in attic. Further evaluation is recommended.



4: Sagging Soffit

Deficiency

Sagging or loose soffit observed.



 \mathbf{X} \mathbf{X} E. Walls (Interior and Exterior) Comments:

NI=Not Inspected NP=Not Present **D=Deficient**


NI NP D

I=Inspected

1: Interior Wall Cracks

Deficiency

Interior wall cracks and or movement at tape joints observed. This appears to be the result of previous structural movement.



2: Damaged and/or deteriorated Fascia Deficiency

Damage and/or deterioration observed at exterior fascia and trim.



Report Identification. 1234 Main Street Waco 174 70700 - 07/30/202

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

3: Loose siding and/or trim

Deficiency

Loose siding and/or trim observed.



South Exterior

4: Brick Frieze Separations

Deficiency

Separation at the brick frieze observed. This is an indicator of previous foundation movement.



report fundamentalis. 123 : Main Street Water 111 / 6/66 65/2621

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

5: Exterior Wall Cracks

Deficiency

Exterior wall cracks observed (Evidence of structural movement). Further evaluation is recommended.



NI=Not Inspected

I=Inspected

NP=Not Present

D=Deficient

NI NP D

6: Grout or Caulking Needed

Deficiency

Grout or caulking improvements needed in the shower enclosure to prevent moisture from entering behind the wall.



Master Bathroom

\mathbf{X} \mathbf{X} F. Ceilings and Floors

Comments:

1: Interior Ceiling Cracks

Deficiency

Interior ceiling cracks and or movement at tape joints observed. This could be related to structural movement.



I=Inspected

NI=Not Inspected

NP=Not Present

D=Deficient

NI NP D

2: Floor Slopes

Deficiency

Floor slopes and or deflections were apparent. This condition could indicate greater than normal movement within the structure and potential structural problems. Further evaluation recommended.

3: Cracked Floor Tile

Deficiency

Cracked floor tile observed. This may be related to structural movement.



Main/Guest Bathroom

4: Loose Floor Tiles

Deficiency

Master Bathroom

Loose floor tiles observed.

X X **G. Doors (Interior and Exterior)**

Comments:

1: Drifting Doors

Deficiency

Drifting doors observed. This is usually the result of foundation settling but may indicate a poor installation.

2: Door Latch Misaligned

Deficiency

Hallway Closet

Door latch was misaligned which prevented it from latching closed properly. Adjustments or repairs needed.

3: Hardware Adjustments

Deficiency

Hallway Closet

Hardware repairs and or adjustments were needed at doors.

I=Inspected

NI=Not Inspected

NP=Not Present **D=Deficient**

NI NP D

4: Door Hardware was Missing

Deficiency

Door hardware was missing.





Bedroom Two Closet

Bedroom Two Closet

5: Damaged trim Deficiency

Damaged trim observed.



Front Exterior

I=Inspected

NI=Not Inspected

NP=Not Present

D=Deficient

NI NP D

6: Loose Seal

Deficiency

Seal is loose at the shower door.



Main/Guest Bathroom

🛛 🗆 🔻 H. Windows

Comments:

Inaccessible Windows:

Note: Only visible and accessible windows were tested. Due to furniture or personal belongings, some windows or portions of windows were obstructed and not visible or accessible for inspection/testing.

1: Screens Missing

Deficiency

Rear Exterior

Window screen missing and or not installed.

I=Inspected NI=Not Inspected

NI NP NP=Not Present

D=Deficient

D

2: Screen Mesh Damaged

Deficiency

Damaged screen mesh observed at window exteriors.



Rear Exterior

NI=Not Inspected

NI NP D

I=Inspected

NP=Not Present

D=Deficient

3: Cracked Window Glass

Deficiency

Cracked or broken window glass observed.







Master Bathroom

Master Bedroom

Living Room



Bedroom One

I=Inspected

NI=Not Inspected **NP=Not Present**

NI NP D

4: Glazing Beads Damaged

Deficiency

Loose and or damaged glazing beads observed on various windows.

D=Deficient



Various Locations

5: Screen Spline Loose

Deficiency

Window screen spline was loose. This is responsible for holding the screen mesh in place.



Rear Exterior

I=Inspected

NI=Not Inspected

NP=Not Present

D=Deficient

NI NP D

6: Caulk Windows

Deficiency

Windows were not caulked at exteriors where window frames meet exterior cladding.



7: Seal Failure

Deficiency

Various Locations

Evidence of seal failure observed on thermal pane windows in one or more locations. This can result in condensation between the panes and reduced efficiency.



Kitchen Dining Room

□ □ ■ I. Stairways (Interior and Exterior)

Comments:

Notice: No Stairways were present.

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

I NI NP D


☑ □ □ J. Fireplaces and Chimneys

Comments:

1: Refractory Cracks

Informational Item

Note: Typical cracks were observed at the rear refractory brick within the hearth.




🛛 🗆 🗆 K. Porches, Balconies, Decks, and Carports

Comments:

1: Typical Flatwork Cracks

Note: Typical settlement cracks were observed in exterior flatwork in various locations.



II. ELECTRICAL SYSTEMS

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

☑ □ □ ■ A. Service Entrance and Panels

Comments:

Main Electrical Panel: Closet

1: Labeling Incomplete

Deficiency

Sub Panel in Laundry Room

Service panel breaker labeling was incomplete.



2: Vermin/Insect Activity

Deficiency

Main Panel, South Exterior

Evidence of vermin or insect activity was observed within the electrical panel. The panel should be cleaned and all potential vermin entry points to the panel should be sealed.



Disconnect Panel for Outdoor Cooling Unit

report identification. 123 i fram Street video 17t 70700 07/30/202

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

3: Knockouts Missing

Deficiency

Any unused openings (knockouts) in the electrical panel should be properly covered to prevent dust, moisture, insects, rodents, or other foreign objects from entering the panel.



Disconnect Panel for Outdoor Cooling

4: Neutrals not Separated

Deficiency

The electrical panel had one or more instances of neutral wires that were sharing the same terminal screw on the neutral bus bar. While this is common, it is not a proper wiring practice under current standards and could result in loose connections or possible arcing. The proper way to wire the neutral bus bar is to have one terminal screw for each neutral wire.



Main Panel

I=Inspected NI=Not Inspected

NP=Not Present

D=Deficient

NI NP D

5: Neutrals and Grounds not Isolated

Deficiency

The electrical distribution sub panel had an improper wiring condition. The neutral wires and the ground wires were connected together on the same bus bar, which is not allowed for sub panels. This can create a potential shock hazard and interfere with the proper operation of the circuits. The neutral wires and the ground wires should be separated on different bus bars, and the neutral bus bar should be isolated from the panel enclosure.





Septic Sub Panel

Sub Panel in Laundry Room

6: Panel Bonding

Deficiency

No visible bonding of the electrical panel box to the grounding system was observed. The presence of proper bonding could not be verified. Further evaluation is recommended.



Septic Sub Panel

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

7: Insufficient Working Clearance

Deficiency

Main Panel

Insufficient working clearance observed in front of the electrical distribution panel.

8: Panel in Closet

Deficiency

An electrical distribution panel was located in a clothes closet. This is considered a hazardous location by current standards.



Main Panel

9: Dead Front Cover Missing

Deficiency

Sub Panel for Septic, Disconnect Panel for Outdoor Cooling Unit

A dead front cover was missing from the electrical panel. A dead front cover is needed for improved safety.

Troport Identification 125 : Intern Street (1400 111 / 0 / 00 0 0 / 20/20/20/

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

10: Double Lugged Wiring

Deficiency

Double lugged wiring observed in panel. This is an improper wiring practice. Further evaluation by a qualified electrician is recommended.



Disconnect Panel for Outdoor Cooling Unit

☑ □ □ ☑ B. Branch Circuits, Connected Devices, and Fixtures

Type of Wiring: Copper

Comments:

Inaccessible Electrical Receptacles:

Note: Only visible and accessible electrical receptacles were tested. Due to furniture or personal belongings, some receptacles were obstructed and not visible or accessible for inspection.

1: GFCI Needed

Deficiency

Kitchen, Laundry Room

Ground fault circuit protection (GFCI) was not found for one or more receptacles at the required locations.

2: Arc Fault Breakers

Deficiency

Arc fault circuit interrupting devices were not found in the electrical panel for all required locations. Arc fault circuit protection is recommended for living rooms, family rooms, dining rooms, parlors, libraries, dens, sunrooms, recreation rooms, closets, hallways, bedrooms, and similar rooms and areas. Arc fault protection is required in new home construction.

3: Tamper Resistant

Deficiency

Electrical receptacles located less than 5 and a half feet above the floor are required to be reported as deficient by TREC standards of practice when they lack tamper resistance. Receptacles were not tamper resistant in where required.

NI=Not Inspected

NI NP

I=Inspected

NP=Not Present

D=Deficient

D

4: Lights Inoperative

Deficiency

Laundry Room

Lights inoperative. Bulbs may be in need of replacement.

5: Exposed Wiring

Deficiency

Exposed wiring that was not protected within conduit was observed.



6: Open Grounds

Deficiency

South Exterior

Three-prong electrical receptacles observed to have open grounds.

I=Inspected

NI=Not Inspected **NP=Not Present D=Deficient**

NI NP D

7: Wiring Within 6 Feet of Attic Access

Deficiency

The attic access was located within six feet of exposed wiring, which could pose a risk of electric shock or injury to anyone entering or exiting the attic. The wiring should be enclosed in a protective conduit or moved away from the access area to prevent accidental contact and ensure safety.



8: Abandoned Wiring

Deficiency

Abandoned wiring was observed. This should be replaced or appropriately terminated to prevent causing a safety hazard.



South Exterior

---r

NI=Not Inspected

NI NP D

I=Inspected

NP=Not Present

D=Deficient

9: Incandescent Lights

Deficiency

Incandescent light fixtures in closets need bulbs completely enclosed within a globe.



Master Bathroom

10: Smoke Detectors Needed

Deficiency

All Bedrooms

Smoke detectors needed in one or more locations. Smoke detectors should be installed in all bedrooms, adjacent hallways and near the top and bottom of all stairways.

11: Photo Sensors

Informational Item

Note: The inspector did not test the fixtures with photo-sensing devices for their functionality. Photo-sensing devices are sensors that detect the amount of light in the environment and turn the fixtures on or off accordingly. The inspector could not test these devices because they require specific lighting conditions to operate, such as darkness or daylight.

NI NP D

12: Junction Box Cover Missing

Deficiency

Junction box covers and or gang box covers missing. All junction boxes should be fitted with cover plates in order to protect the wire connections.



13: Light Bulbs Missing

Deficiency

Rear Exterior

Light bulbs were missing from fixtures.

14: Damp Location Covers Missing

Deficiency

Damp location covers not installed on exterior electrical receptacles where needed.



Rear Exterior

report identification. 123 i Main Street Water 171 /0/00 05/30/20

NI=Not Inspected NP=Not Present D=Deficient

NI NP D

I=Inspected

15: Reverse Polarity

Deficiency

An electrical receptacle was found to have reversed polarity, which means that the hot and neutral wires were connected to the wrong terminals. This is a potential safety hazard that can cause electric shock or damage to sensitive devices. Reversed polarity can be easily corrected by a qualified electrician.





Garage Conversion

Laundry Room

16: Wet Location Covers Needed

Deficiency

The installation of wet location covers is recommended over receptacles with exposure to rain fall, irrigation systems or splashing water from any other source. This will give added protection if something is plugged into these receptacles.



South Exterior

report recitification. 123 i main succe made 171 /0/00 09/30/2021

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

17: Light Above Tub

Deficiency

Light fixture located above tub is considered hazardous due to proximity to the tub.



Master Bathroom

18: Conduit Separated

Deficiency

Conduit beneath the septic control panel has separated from the panel. Wiring is exposed as a result. Repair recommended.



South Exterior

NI=Not Inspected

NI NP D

I=Inspected

NP=Not Present

D=Deficient

19: Open Neutral



Kitchen Dining Room

A receptacle appeared to have an open neutral when tested. Further evaluation is recommended.



□ ■ □ C. Other

Comments:

Not Inspected:

Low voltage lighting, yard lighting, and electrical components in outbuildings or other structures on the property, when present, are not included as part of the standard TREC inspection and are not inspected unless said structure or outbuildings are specifically included in the inspection.

III. HEATING, VENTILATION AND AIR CONDITIONING SYSTEMS

☒ ☐ **☒** A. Heating Equipment

Type of Systems: Central - Forced Air

Energy Sources: Electric

Comments:

Number of Heating Units: 1

I=Inspected NI=Not Inspected

NI NP D **NP=Not Present**

D=Deficient

1: Cable Clamp Missing

Deficiency

A cable clamp or bushing was missing where the electrical wiring passes into the furnace housing.



B. Cooling Equipment

Type of Systems: Central Air Conditioner

Note: A measurement was taken for the temperature differential of the AC unit, which is the difference between the supply air temperature and the return air temperature. The ideal temperature differential for an AC unit is within 15 to 22 degrees Fahrenheit.

Temperature Differential for Cooling Unit: 22 - Acceptable

I=Inspected

NI=Not Inspected

NP=Not Present

D=Deficient

NI NP D

1: Evaporator Coil Dirty

Deficiency

The evaporator coil was excessively dirty. Servicing is needed.



2: Raise to 3 Inches

Deficiency

Exterior unit pad was not the proper height off grade. Bottom of AC unit should sit three inches above grade. This will reduce conditions conducive to corrosion and or physical damage.



X		C. Duct Systems, Chases, and Ven
		Comments:

□ **⊠** □ □ **D. Other**Comments:

I=Inspected NI=Not Inspected

NP=Not Present

D=Deficient

NI NP D

Not Inspected:

Humidifiers, dehumidifiers, air purifiers, motorized dampers, electronic air filters, multistage controllers, sequencers, heat reclaimers, wood burning stoves boilers, oil-fired units, supplemental heating appliances, deicing provisions, reversing valves, and unvented gas heaters, when present, are not included as part of the standard TREC inspection and are not inspected.

IV. PLUMBING SYSTEMS

X A. Plumbing Supply, Distribution Systems, and Fixtures

Location of Water Meter: Front of Property Near Street

Location of Main Water Supply Valve: In the Water Meter Box

Static Water Pressure Reading: 60 PSI Type of Supply Piping Material: PEX

Comments:

Supply Plumbing Materials:

Note: The type of supply plumbing reported was only the visible and accessible plumbing observed at the time of the inspection. Supply plumbing that was concealed within the structure, below grade, or other areas, may differ than what was visible to the inspector.

Washing Machine Plumbing:

Note: The water supply faucets for the washing machine were not tested.

1: Anti-Siphon Devices Missing

Deficiency

Anti-siphon devices were missing at the exterior hose bibs.

2: Toilet Loose at Floor

Deficiency

Master Bathroom

Toilet was not secured tightly to the floor.

I=Inspected

NI=Not Inspected

NP=Not Present

D=Deficient

NI NP D

3: Supply Lines not Insulated

Deficiency

Water supply lines were not insulated. This increases the potential for damaging water lines during periods of freezing weather.



Attic

4: Flush Adjustment

Deficiency

Master Bathroom, Main/Guest Bathroom

The toilet flush mechanism requires adjustment for improved performance.

5: Sink Stop Stuck

Deficiency

Master Bathroom - right sink

The bathroom sink drain stop became stuck while testing. Repairs or adjustments needed.

■ □ □ ■ B. Drains, Wastes, and Vents

Type of Drain Piping Material: PVC

Comments:

Drain Not Tested:

Note: The washing machine drain was not tested.

I=Inspected

NI=Not Inspected **NP=Not Present**

NI NP D

1: Flexible Drain

Deficiency

Flexible drain pipe observed installed under the sink. This type of drain line should not be installed in this location and tends to build up debris at the interior.

D=Deficient







Kitchen

Master Bathroom - both sinks

Main/Guest Bathroom

2: Standing Water in Drain

Deficiency

Standing water observed in the drain pipe leading to the septic. This could be a result of an improperly sloped drain. Further evaluation is recommended.



C. Water Heating Equipment

Energy Sources: Gas

Capacity: See Comments Below for Number of Water Heaters and Capacity of Each

Comments:

Number of Water Heaters Present: 1

I=Inspected NI=Not Inspected

NP=Not Present

D=Deficient


NI NP D

Capacity of Unit: Tankless

1: TPRV Drain Line Missing



The discharge piping serving the temperature and pressure relief valve for the water heater was missing.



■ □ ■ D. Hydro-Massage Therapy Equipment Comments:

1: Hydro Massage Tub Motor Inoperative

Deficiency

The hydro massage tub motor was inoperative when the switch was pushed. Further evaluation is recommended.

☑ □ □ ☑ E. Gas Distribution Systems and Gas Appliances

Location of Gas Meter: Not Present

Type of Gas Distribution Piping Material: Black Steel

Comments:

Limitation:

Note: The type of gas supply plumbing reported was only the visible and accessible plumbing observed at the time of the inspection. Gas supply plumbing that was concealed within the structure, below grade, or other areas, may differ than what was visible to the inspector.

I=Inspected NI=Not Inspected **NP=Not Present D=Deficient**

NI NP D

1: No Sediment Traps

Deficiency

There were no visible sediment traps installed on the gas lines adjacent and leading to the gas appliances.



2: Propane Tank Too Close Deficiency

The propane tank was too close to the house.



Front Exterior

V. APPLIANCES

 \mathbf{X} A. Dishwashers

Comments:

Notice: No Dishwashers were present.

Report Identification: 1234 Main Street Waco TX 76708 - 09/30/2021 I=Inspected NI=Not Inspected NP=Not Present **D=Deficient** NI NP D \mathbf{X} **B. Food Waste Disposers** Comments: *Notice:* No Food Waste Disposers were present. \mathbf{X} C. Range Hood and Exhaust Systems Comments: Notice: No Range Hood or Exhaust Systems were present. 1: Exhaust System Missing FInformational Item Note: No exhaust system present to prevent moisture and grease in kitchen area. Recommend qualified contractor install range hood or exhaust system. X D. Ranges, Cooktops, and Ovens Comments: 1: Range Missing Anti-tip Device Deficiency Range was not fastened to the floor. This poses a safety hazard to children. Recommend a qualified contractor secure range with an anti-tip bracket so it can't tip. X E. Microwave Ovens Comments: Notice: No Built-in Microwave Ovens were present. Free Standing Units: Note: This section pertains to built-in microwave units. Free standing appliances are not included in the inspection. X F. Mechanical Exhaust Vents and Bathroom Heaters Comments: 1: Bathroom Exhaust Vents Terminate in Attic Deficiency The mechanical exhaust vents in the bathrooms appeared to vent into the attic, rather than the exterior of the house as required by current standards. X G. Garage Door Operators Comments: *Notice:* No Garage Door Operators were present. H. Dryer Exhaust Systems Comments:

I=Inspected NI=Not Inspected

NI NP D NP=Not Present

D=Deficient

1: Cleaning or Adjustments needed

✓ Informational Item

Front Exterior

Cleaning or adjustments needed at the dryer vent exterior termination for the damper to close when not in use.



VI. OPTIONAL SYSTEMS

		Ш	Outbuilding not inspected: Note: This outbuilding was not part of the inspection.
×		×	E. Private Sewage Disposal Systems Type of System: Aerobic with Effluent Pump/Spray Heads Location of Drain Field: East of Tank Comments:

General Information:

- Homes that have been vacant for a period of weeks or longer may have septic systems that perform differently once the home is put into use again. This can affect the outcome of the load testing.
- The use of a garbage disposer is not recommended for homes utilizing private waste water treatment systems.

Septic Inspection Checklist: Located the tank and opened one or more access covers, Inspected the visible and accessible portions of the tank or tanks, Flushed toilets once and ran all fixtures to verify if they flow into the treatment tank, Tested the effluent pump, Tested the alarm system, Tested the spray heads, Inspected the aerator, Inspected the control panel

Was the inspector aware of proximities of the system to any known water wells, underground cisterns, water supply lines, bodies of water, sharp slopes or breaks, easement lines, property lines, soil absorption systems, swimming pools, or sprinkler systems?: No

•

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

Gray Water Location and Type: Washing Machine Drain Termination, Laundry Sink Drain Termination Flexible Hose at Front Yard



Did all waste drains terminate to the treatment tank?: No

Was the inlet visible?: Yes Was the outlet visible?: Yes

Depth of Tank Access Below Grade: Tank access was visible above grade

Measured the water, scum, and sludge levels of the primary tank:

- When scum/sludge = 25% or more of normal water level, a tank pump out is recommended.
- Tank pump outs are not included as a part or our inspection process.



Water level depth: 54 Inches

Scum level thickness In Primary Chamber: 2 Inches

Sludge level thickness: 10 Inches -

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

Is pump out recommended?: Yes. The tank(s) should be pumped out -

System Chlorinator: Was it a liquid or tablet chlorinator?: Liquid

..

Summary:

The following were functioning as intended: Treatment Tank(s), Spray Heads, Aerator, Alarm System, Effluent Pump

Company Disclaimer:

Based on what we were able to observe and our experience with onsite wastewater technology, we submit this Onsite Wastewater Treatment System Inspection Report based on the present condition of the onsite wastewater treatment system. Full House Inspections has not been retained to warrant, guarantee, or certify the proper functioning of the system for any period of time in the future. Because of the numerous factors (usage, soil characteristics, previous failures, etc.) which may effect the proper operation of a wastewater treatment system, this report shall not be construed as a warranty by our company that the system will function properly for any particular buyer. Full House Inspections DISCLAIMS ANY WARRANTY, expressed or implied, arising from the inspection of the wastewater treatment system or this report. We are also not ascertaining the impact the system is having on the environment.

1: Scum Level Excessive

Informational Item

The level of scum on top of the water in one of the tank chambers was excessive (12 inches) The tank should be pumped out, as excessive scum can interfere with proper functioning of the system.



2: Pump Out Needed Informational Item

It is recommended that the system be pumped out due to the contents of the tank having reached a certain level.

I=Inspected NI=Not Inspected NP=Not Present D=Deficient

NI NP D

3: Lid Missing Screws

Deficiency

The lid for the aeration chamber was missing screws and had screws stripped out. The lid was not well secured.