
Annual Groundwater Monitoring Report [40 CFR 257.90(e)] Calendar Year 2023

Prepared for:
Rosebud Power Plant
Colstrip, MT

Prepared by:



Bison Engineering, Inc.
3143 E. Lyndale Avenue
Helena, MT 59601

&



Allied Engineering Services, Inc.
32 Discovery Drive
Bozeman, MT 59718

January 30, 2024

TABLE OF CONTENTS

| | | |
|-------|--|----|
| 1.0 | INTRODUCTION..... | 3 |
| 2.0 | REGULATORY REQUIREMENTS..... | 4 |
| 3.0 | AREA DESCRIPTION AND GEOLOGY..... | 5 |
| 4.0 | GROUNDWATER MONITORING SYSTEM DESCRIPTION | 7 |
| 4.1 | GROUNDWATER CHARACTERISTICS DISCUSSION | 10 |
| 5.0 | GROUNDWATER MONITORING: DATA ANALYSIS | 12 |
| 5.1 | DATA REPORTING..... | 12 |
| 5.2 | DATA SUMMARY STATISTICS | 17 |
| 5.3 | DATA ANALYSIS - GRAPHICAL..... | 19 |
| 5.4 | DATA ANALYSIS – STATISTICS..... | 21 |
| 5.4.1 | NORMALITY TESTING | 21 |
| 5.4.2 | ANALYSIS OF VARIANCE (ANOVA) TESTING | 22 |
| 5.5 | STATISTICAL RESULTS SUMMARY | 26 |
| 6.0 | GROUNDWATER MONITORING: HYDROGEOLOGY EVALUATION..... | 28 |
| 7.0 | CONCLUSION | 30 |

LIST OF TABLES

| | | |
|-----------|---|----|
| Table 1: | Well Description and Status | 8 |
| Table 2: | Appendix III Constituents Analyzed: 2023 Reporting Period..... | 12 |
| Table 3: | Data Summary OMW-1 Appendix III Constituents Plus Sodium..... | 13 |
| Table 4: | Data Summary OMW-5 Appendix III Constituents Plus Sodium..... | 14 |
| Table 5: | Data Summary OMW-7 Appendix III Constituents Plus Sodium..... | 15 |
| Table 6: | Data Summary OMW-8 Appendix III Constituents Plus Sodium..... | 16 |
| Table 7: | CCR Well Summary Statistics..... | 17 |
| Table 8: | Normality Test Results | 22 |
| Table 9: | ANOVA (between wells) Summary Results | 23 |
| Table 10: | t-Test Summary Results | 24 |
| Table 11: | Kruskal-Wallis Multiple Comparison Test Summary..... | 25 |
| Table 12: | Results Kruskal-Wallis One-Way ANOVA Test Summary Results | 26 |
| Table 13: | Statistics Results..... | 26 |

1.0 INTRODUCTION

Colstrip Energy Limited Partnership (CELP) owns an electric utility steam-generating unit (EGU) and an “existing Coal Combustion Residuals (CCR) landfill” as defined by 40 CFR 257.53. The generation facility is fired with waste coal and a portion of the CCR is stored at their nearby existing CCR landfill.¹

EPA requirements for CCR landfills are primarily contained in 40 CFR 257.50 through 107 which became effective on April 17, 2015 (80 FR 21468). This collection of requirements is commonly referred to as the CCR rule.

Among the requirements of the CCR rule is “Groundwater Monitoring and Corrective Action” this requires an “annual groundwater monitoring and corrective action report” be submitted annually beginning 1/31/2018. This document fulfills the annual reporting requirement. The remainder of this document provides a background discussion, summary of the sampling network, results of the sampling and the conclusions of the sample results as they relate to the requirements of the CCR rule.

The ash deposited in the landfill is hydrated with water to allow the calcium sulfate and the unreacted calcium oxide in the ash to form a solid bed similar to concrete. There are no water containment ponds or sites. No water leaches from or through the solid hydrated bed into the ground water. The groundwater monitoring is nevertheless undertaken to substantiate the lack of any impacts from the ash storage facility.

¹ In addition to the current active “existing” landfill there is also a closed landfill on the property. The closed landfill does not meet the definition of an “existing” or “new” landfill within the meaning of 40 CFR 257.53 and is not the subject of this report.

2.0 REGULATORY REQUIREMENTS

The CCR rule contains the following requirements/discussion as it relates to the annual groundwater monitoring plan [40 CFR 257.90(e)]:

“(e) *Annual groundwater monitoring and corrective action report.* For existing CCR landfills ... the owner or operator must prepare an annual groundwater monitoring and corrective action report. ... For the preceding calendar year, the annual report must document the status of the groundwater monitoring and corrective action program for the CCR unit, summarize key actions completed, describe any problems encountered, discuss actions to resolve the problems, and project key activities for the upcoming year. ... At a minimum, the annual groundwater monitoring and corrective action report must contain the following information, to the extent available:

- (1) A map, aerial image, or diagram showing the CCR unit and all background (or upgradient) and downgradient monitoring wells, to include the well identification numbers, that are part of the groundwater monitoring program for the CCR unit;
- (2) Identification of any monitoring wells that were installed or decommissioned during the preceding year, along with a narrative description of why those actions were taken;
- (3) In addition to all the monitoring data obtained under §§257.90 through 257.98, a summary including the number of groundwater samples that were collected for analysis for each background and downgradient well, the dates the samples were collected, and whether the sample was required by the detection monitoring or assessment monitoring programs;
- (4) A narrative discussion of any transition between monitoring programs ...; and
- (5) Other information required to be included in the annual report as specified in §§257.90 through 257.98.”

In accordance with the provisions of §257.90(b)(i), 91 and elsewhere, CELP has installed and is operating a “groundwater monitoring system.” The system was installed and operational by December 2016. The system has been monitoring and collecting data since that time.

This report provides a summary of the results of the sampling and analysis to date which roughly covers December 2016 through December 2023. The report will be entered into the facility’s operating record and posted on the CELP CCR website² as required by §§257.105(h)(1).

² www.celpccr.com

3.0 AREA DESCRIPTION AND GEOLOGY

The regulated site is located approximately seven miles north of the town of Colstrip, Montana, in the southwest quarter of Section 29 and the northwest quarter of Section 32, Township 3 North, Range 41 East [Latitude 45.978859°, Longitude -106.663772° (WGS 84)]. The landfill serves an on-site power generation plant owned by Colstrip Energy Limited Partnership. The power plant and the landfill are operated by Rosebud Operating Services, Inc.

Conventional environmental monitoring and analyses of landfills include sampling and testing of upgradient and downgradient water from the “uppermost aquifer” under the site. Water quality of the upgradient and downgradient samples is then compared to evaluate the possibility of the contaminant transport from the landfill via groundwater. For this landfill, such comparisons and definitions of upgradient, downgradient and uppermost aquifer are not feasible. In some wells, groundwater, although relatively shallow (less than 10-feet below ground surface), has been encountered. In other cases, no groundwater has been found except in extremely rare circumstances.³ Even in cases where groundwater is present, the definition of the aquifer is not self-evident. As a result, the typical boundaries of upgradient and downgradient aquifers are ill-defined. Clearly caution is needed in evaluating the water quality data since the typical comparison between up- and downgradient wells is not necessarily applicable. This has made it difficult to install monitoring wells meeting the CCR intent.

In addition, the uppermost aquifer(s) in the local hydrogeologic regime are accumulated from localized surface infiltration of direct precipitation, snowmelt, and ephemeral streams, as is the case with a surface impoundment on a neighboring property that creates a significant shallow groundwater mound and influences a downgradient monitoring well. Based on the data, and experience in similar conditions, infiltrated surface waters naturally accumulate soluble components of the local geologic materials which include shale, coal, and other marine and continental sedimentary rock and their derivatives including residual clays and alluvium/colluvium. These soluble components, including sulfate, calcium, sodium and other analytes generally considered unfavorable for water quality often increase with time in contact with the various geologic materials. These conditions result in a somewhat random distribution of groundwater quality under the site that does not appear related to the presence of the CCR landfill. It is necessary to be mindful that differences in constituent concentrations may not be due to the landfill itself, but due to the variations of native groundwater quality irrespective of the landfill.

The landfill itself is made up of a series of layers of solidified boiler ash (CCR) that is in many ways similar to concrete. Excess lime (CaO or quicklime) from the combustion desulfurization process in the boiler, coupled with the resultant calcium sulfate and calcium sulfite that is also produced, renders the ash (CCR) into a cement-like substance. This substance is hydrated during placement in the CCR landfill. Once hydrated and hardened,

³ Well OMW-9 has produced a water sample only three times in nine years while OMW-10 has never produced any water.

very little surface water penetrates through it and what little does is chemically used up hydrating the un-hydrated CCR; thus, no leachate should be produced.

The site and the general Colstrip region are located within a large area of outcropping Fort Union Formation⁴. The Fort Union Formation is Tertiary aged sediments, roughly horizontal in this area and is composed of coal, shale, and sandstone. In general, the topography is cut into the bedrock with a mantle of residual and colluvial soils on the slopes and deposits of windblown and alluvial soils in the drainages. According to the geology map (Figure GE-1) the Lebo Member of the Fort Union Formation outcrops beneath the site, near the boundary of the overlying Tongue River Member of the Fort Union Formation.

Exposure of site geology in the landfill base excavation revealed discontinuous layers of weathered shale, siltstone, and coal dipping gently to the northeast, roughly coincident with the surface topography (i.e., dipping generally eastward roughly five degrees) with a discontinuous mantling of sandy and clayey colluvial and alluvial deposits.

⁴ Montana Bureau of Mines and Geology in Open-File Reports MBMG-428 [Geologic map of the Lame Deer 30' x 60' quadrangle, eastern Montana, revised 2007 by Vuke, S.M., Heffern, E.L., Bergantino, R.N., and Colton, R.B. (2007)]

4.0 GROUNDWATER MONITORING SYSTEM DESCRIPTION

The surface hydrology at the site is characterized as mostly ephemeral drainage basins draining to the east into East Fork Armells Creek, a perennial stream that flows generally north to join the West Fork of Armells and then north to the Yellowstone River. The local topography influences the locations of significant infiltration in that well-drained ridges and steep slopes generally infiltrate less than flatter drainage bottoms and ephemeral streams that accumulate surface flow. Surface materials also influence infiltration in exposures of more permeable materials infiltrating more than exposures of low permeability materials. In any case, once infiltrated, groundwater moves vertically and horizontally in saturated and unsaturated flow conditions in response to the relative permeability and geologic dip of the local rock, which is generally about five degrees to the east. However, at the site, which is located on an east flowing ephemeral unnamed tributary of East Fork Armells Creek, the local uppermost aquifer is often perched above the regional aquifer, is discontinuous and, in some locations, is ephemeral. Similar but disconnected perched uppermost aquifers form in many named and unnamed tributaries to East Fork Armells, including Corral Creek to the south.


Groundwater at the site is presently monitored using nine groundwater monitoring wells located throughout the power generation site. This includes wells used for purposes other than the CCR rule itself. The location of these wells is shown in Figure 1.

Table 1 below provides a description and the status of each well. The well purpose may be either “Detection” or Assessment” per 40 CFR 257.94 or 95, respectively. The analysis in the table below indicates that only four of the ten historical wells may serve a purpose under CCR. Wells 9 and 10 could be useful in analyzing the information if they were to produce water.

Table 1: Well Description and Status

| Well | Description | Well Status | Purpose |
|---------------|---|--------------------|----------------|
| OMW-1 | Down/cross-gradient in uppermost aquifer. | Downgradient CCR | Detection |
| OMW-2 | Down/cross-gradient in a lower aquifer. This well is not in the uppermost aquifer and thus does not meet the requirement of CCR. | Non-CCR | n/a |
| OMW-3 | Cross-gradient; however, the well was abandoned in 1990. | Non-CCR | n/a |
| OMW-4 | Cross-gradient uppermost aquifer and not likely representative of the active landfill. | Non-CCR | n/a |
| OMW-5 | Upgradient/cross-gradient in the uppermost aquifer of the closed non-CCR landfill. This well represents the upgradient well due to the lack of another representative producing well directly upgradient of the active landfill. | Upgradient CCR | Detection |
| OMW-6 | Upgradient/cross-gradient of the active landfill. However, this well is immediately downstream of a stock-watering pond that is hydraulically connected to the elevated groundwater observed in OMW-6. Based on its elevation, proximity to stock pond and groundwater quality data, OMW-6 is not representative of the typical condition of the uppermost aquifer. | Upgradient Non-CCR | n/a |
| OMW-7 | Downgradient in the uppermost aquifer and is considered representative for the purposes of a downgradient well as required in the CCR Rule. | Downgradient CCR | Detection |
| OMW-8 | Downgradient in the uppermost aquifer and is considered a reasonable representation of downgradient well as required in the CCR Rule. | Downgradient CCR | Detection |
| OMW-9 | Upgradient in the uppermost aquifer. However, the on-going monitoring of this well data is problematic because the well has been dry save for samples in 2011 and 2012 (an unusually wet period prior to the sampling event) and an additional single sample in the spring of 2018. Data might be suitable for analysis should water collection prove successful in the future. | Upgradient CCR | n/a |
| OMW-10 | Upgradient in the uppermost aquifer. However, like OMW-9 it has not produced reliable water. | Upgradient CCR | n/a |

Figure 1: Monitoring Well Locations



4.1 GROUNDWATER CHARACTERISTICS DISCUSSION

There are only four wells that meet the CCR criteria. It is instructive to review and analyze characteristics of the wells and hydrogeology in general. The depths to groundwater among the on-site wells vary, with some wells having water at 8 feet and others with water at 80 to 100 feet deep. Many of the wells are completed in bedrock and are pressurized indicating confined aquifer characteristics. The hydrologic head varies among wells that exhibit confining conditions adding to the discontinuous nature of the underlying aquifers. The shallow groundwater observed in the on-site monitoring wells can be characterized as perched or confined water tables flowing intermittently and/or ephemerally in alluvial deposits or shallow coal seams bound by low permeability bedrock or weathered bedrock (clay). The regional drinking water table ranges from about 295 to 430 feet below natural ground. Regional groundwater flow direction appears to be northeasterly.

The uppermost aquifers appear to generally flow to the northeast following the geologic dip and the topography of surface drainage basins. The upper-most aquifer appears more continuous and perennially lower in the drainage basin in the vicinity of OMW-7 and OMW-8. The uppermost aquifer higher in the drainage basin near OMW-9 and OMW-10 is generally discontinuous and produces little, if any, water in the wells in most years.

Appendix A contains sample well elevations. In addition, Appendix A also provides information regarding groundwater flow and direction.

As noted, the uppermost aquifer is discontinuous in nature and is influenced by precipitation and site hydrology. Estimates of groundwater characteristics are derived from lithological and monitoring well data along with laboratory data for hydraulic conductivity. The saturated and unsaturated lithology in the uppermost aquifer typically varies between sandy/gravelly clay to clay. The confining layers are typically clay. A summary of groundwater characteristics is as follows:

- Saturated and unsaturated geologic units overlying the uppermost aquifer generally include alluvium/colluvium comprised of mixtures of clay, sand, and gravel. Fill material includes clayey soils as the bottom liner for the active CCR landfill.
- Groundwater gradients in the discontinuous and ephemeral uppermost aquifers are variable in slope and direction. Assuming observed water in the four CCR area wells that had water represent a connected aquifer, interpretations of those surfaces on 5/16/23 and 9/6/23 are provided in Appendix A (Sheets GW-1 and GW-2). While the groundwater surfaces depicted in GW-1 and GW-2 may appear unusual, the following conditions are depicted by the calculated surface:
 - OMW-5 is located approximately 1600 feet south within the adjacent Corral Creek ephemeral drainage. The uppermost aquifer encountered at this location is about 20 feet lower than the aquifer downstream of the CCR landfill and is likely disconnected from the unnamed tributary in which the CCR landfill is situated.

- Flow between OM-7 and OM-8 may not be directly down gradient so actual gradients may be higher. Sheet GW-2 of Appendix A indicates that the gradient is about 4.8% to the NE. These discontinuous perched aquifers in hilly terrain like this commonly have steep and variable gradients.
- The uppermost aquifer thickness varies between wells and ranges between 1.03 feet and 47.81 feet. This aquifer is seasonally thicker in the spring of each year.
- Hydraulic conductivities of soils underlying the active landfill are estimated to vary between 2.5 and 3.8 feet/year.
- Porosity is estimated between 30%-45% for clayey substrate indicative of site soils.
- Based on the estimated hydraulic conductivity, gradient, and effective porosity of the uppermost aquifer at the active landfill, the average 2023 linear groundwater velocities are estimated between 0.15 and 0.37 feet/day.

5.0 GROUNDWATER MONITORING: DATA ANALYSIS

This section of the report provides a summary of the results of the monitoring data collected during the subject period (primarily calendar year 2023). This information is provided in fulfillment of 40 CFR 257.90(e)(3).

5.1 DATA REPORTING

Table 1 contains a list of the monitoring wells, ID designation, and the sampling purpose (assessment or detection monitoring). Table 2 contains the constituents analyzed during each reporting period as required in Appendix III of 40 CFR 257.

The reader will note that, for this reporting period, all sampling and analyses were conducted for “detection” monitoring. “Assessment” monitoring is required whenever a statistically significant increase over background levels has been detected during detection monitoring which can be associated with an indication of contamination by the landfill in question. Assessment monitoring was not required for this reporting period.

Tables 3 through 6 list the results of groundwater monitoring of the constituents listed in Table 3 for wells OMW-1, OMW-5, OMW-7, and OMW-8, respectively, from 2016 through 2023.

Table 2: Appendix III Constituents Analyzed: 2023 Reporting Period

| Constituent | Program * |
|--|------------------|
| Boron (B) | Detection |
| Calcium (Ca) | Detection |
| Chloride (Cl⁻) | Detection |
| Fluoride (F⁻) | Detection |
| pH | Detection |
| Sulfate (SO₄⁻²) | Detection |
| Total Dissolved Solids (TDS) | Detection |

* 40 CFR 257.94

Table 3: Data Summary OMW-1 Appendix III Constituents Plus Sodium

| Date | pH | TDS (mg/l) | Calcium (mg/l) | Sodium (mg/l) | Sulfate (mg/l) | Fluoride (mg/l) | Chloride (mg/l) | Boron (mg/l) |
|------------|-----|------------|----------------|----------------|----------------|---------------------|-----------------|----------------------|
| 12/06/2016 | 7.4 | 1,530 | 140 | 263 | 625 | 0.5 | 67 | 0.09 |
| 01/05/2017 | 7.5 | 1,520 | 130 | 247 | 629 | 0.4 | 62 | 0.08 |
| 02/10/2017 | 7.4 | 1,610 | 126 | 241 | 658 | 0.6 | 67 | 0.07 |
| 03/15/2017 | 7.5 | 1,200 | 95 | 170 | 448 | 0.5 | 43 | 0.06 |
| 04/12/2017 | 7.5 | 710 | 80 | 112 | 213 | 0.4 | 19 | 0.08 |
| 05/11/2017 | 7.5 | 1,160 | 102 | 190 | 423 | 0.4 | 39 | 0.06 |
| 06/07/2017 | 7.6 | 1,420 | 112 | 217 | 534 | 0.4 | 52 | 0.06 |
| 07/12/2017 | 7.5 | 1,480 | 119 | 246 | 558 | 0.4 | 60 | 0.06 |
| 08/09/2017 | 7.4 | 1,410 | 125 | 231 | 597 | 0.5 | 60 | 0.025 ⁽²⁾ |
| 09/13/2017 | 7.4 | 1,460 | 112 | 215 | 612 | 0.6 | 63 | 0.025 ⁽²⁾ |
| 10/05/2017 | 7.5 | 1,460 | 118 | 230 | 586 | 0.5 | 60 | 0.025 ⁽²⁾ |
| 11/09/2017 | 7.4 | 1,430 | 115 | 215 | 623 | 0.4 | 64 | 0.09 |
| 06/06/2018 | 7.7 | 750 | 66 | 125 | 220 | 0.5 | 19 | 0.10 |
| 10/26/2018 | 7.5 | 1,210 | 107 | 214 | 415 | 0.4 | 44 | 0.10 |
| 04/26/2019 | 7.7 | 683 | 67 | 132 | 168 | 0.4 | 15 | 0.09 |
| 10/09/2019 | 7.4 | 1,230 | 109 | 178 | 450 | 0.8 | 50 | 0.10 |
| 05/06/2020 | 7.5 | 652 | 69 | ⁽¹⁾ | 105 | 0.3 | 13 | 0.10 |
| 11/04/2020 | 7.4 | 1,440 | 127 | ⁽¹⁾ | 528 | 0.5 | 67 | 0.10 |
| 05/05/2021 | 7.5 | 1,460 | 128 | 220 | 594 | 0.4 | 69 | 0.08 |
| 10/06/2021 | 7.4 | 1,470 | 128 | 246 | 577 | 0.4 | 69 | 0.10 |
| 5/10/2022 | 7.5 | 1,470 | 128 | 213 | 573 | 0.4 | 69 | 0.09 |
| 11/1/2022 | 7.4 | 1,250 | 106 | 191 | 433 | 0.05 ⁽²⁾ | 52 | 0.10 |
| 5/16/2023 | 7.6 | 730 | 64 | 121 | 148 | 0.5 | 17 | 0.10 |
| 10/5/2023 | 7.5 | 1,060 | 96 | 169 | 338 | 0.4 | 40 | 0.11 |

⁽¹⁾ Sodium was included and used in the combined cation analysis discussed later in this report. Sodium was not analyzed in 2020.

⁽²⁾ Data analysis conducted as ½ of the laboratory Reporting Level.

Table 4: Data Summary OMW-5 Appendix III Constituents Plus Sodium

| Date | pH | TDS (mg/l) | Calcium (mg/l) | Sodium (mg/l) | Sulfate (mg/l) | Fluoride (mg/l) | Chloride (mg/l) | Boron (mg/l) |
|------------|-----|---------------|-------------------|------------------|-------------------|--------------------|--------------------|-----------------|
| 12/06/2016 | 7.6 | 4,300 | 43 | 1,570 | 1,810 | 0.7 | 103 | 0.95 |
| 01/05/2017 | 7.6 | 4,200 | 42 | 1,500 | 1,880 | 0.6 | 109 | 0.95 |
| 02/10/2017 | 7.6 | 4,370 | 40 | 1,430 | 2,030 | 0.6 | 115 | 0.93 |
| 03/15/2017 | 7.6 | 4,310 | 36 | 1,330 | 2,020 | 0.6 | 105 | 0.93 |
| 04/12/2017 | 7.6 | 3,980 | 42 | 1,410 | 1,960 | 0.6 | 105 | 0.91 |
| 05/11/2017 | 7.6 | 4,280 | 44 | 1,440 | 1,970 | 0.7 | 106 | 0.83 |
| 06/07/2017 | 7.6 | 4,400 | 41 | 1,490 | 1,960 | 0.5 | 105 | 0.96 |
| 07/12/2017 | 7.6 | 4,300 | 41 | 1,500 | 2,060 | 0.6 | 116 | 0.98 |
| 08/09/2017 | 7.6 | 4,130 | 36 | 1,390 | 1,930 | 0.6 | 107 | 0.80 |
| 09/13/2017 | 7.6 | 4,200 | 39 | 1,480 | 1,940 | 0.6 | 102 | 0.96 |
| 10/05/2017 | 7.6 | 4,000 | 40 | 1,470 | 1,960 | 0.6 | 100 | 0.92 |
| 11/09/2017 | 7.6 | 4,130 | 44 | 1,450 | 1,970 | 0.5 | 107 | 0.94 |
| 06/06/2018 | 7.6 | 3,970 | 41 | 1,410 | 1,860 | 0.6 | 105 | 0.90 |
| 10/26/2018 | 7.8 | 4,090 | 39 | 1,410 | 1,670 | 0.6 | 99 | 0.90 |
| 04/26/2019 | 7.8 | 3,960 | 37 | 1,480 | 1,910 | 0.6 | 105 | 0.90 |
| 09/18/2019 | 7.8 | 4,290 | 41 | 1,410 | 1,950 | 0.6 | 116 | 0.90 |
| 05/06/2020 | 7.6 | 4,240 | 41 | (1) | 2,100 | 0.4 | 109 | 1.00 |
| 11/04/2020 | 7.6 | 4,330 | 40 | (1) | 1,940 | 0.6 | 111 | 1.01 |
| 05/05/2021 | 8.1 | 4,330 | 39 | 1,420 | 1,960 | 0.6 | 109 | 0.95 |
| 09/08/2021 | 7.6 | 4,160 | 38 | 1,400 | 1,910 | 0.6 | 109 | 0.99 |
| 5/10/2022 | 7.7 | 4,250 | 39 | 1,460 | 1,980 | 0.6 | 107 | 0.95 |
| 11/1/2022 | 7.6 | 4,320 | 40 | 1,460 | 1,950 | 0.6 | 114 | 0.84 |
| 5/16/2023 | 7.7 | 4,210 | 40 | 1,570 | 1,980 | 0.7 | 114 | 1.00 |
| 11/7/2023 | 7.7 | 4,230 | 39 | 1,570 | 2,020 | 0.6 | 119 | 0.90 |

(0) Sodium was included and used in the combined cation analysis discussed later in this report. Sodium was not analyzed in 2020.

Table 5: Data Summary OMW-7 Appendix III Constituents Plus Sodium

| Date | pH | TDS (mg/l) | Calcium (mg/l) | Sodium (mg/l) | Sulfate (mg/l) | Fluoride (mg/l) | Chloride (mg/l) | Boron (mg/l) |
|------------|-----|------------|----------------|---------------|----------------|-----------------|-----------------|-----------------|
| 12/06/2016 | 7.2 | 2,620 | 230 | 492 | 1,340 | 0.4 | 85 | 0.13 |
| 01/05/2017 | 7.3 | 2,660 | 214 | 457 | 1,290 | 0.4 | 80 | 0.14 |
| 02/10/2017 | 7.3 | 2,780 | 215 | 464 | 1,380 | 0.4 | 88 | 0.12 |
| 03/15/2017 | 7.3 | 2,670 | 182 | 396 | 1,380 | 0.4 | 87 | 0.09 |
| 04/12/2017 | 7.3 | 2,230 | 185 | 364 | 1,160 | 0.4 | 71 | 0.12 |
| 05/11/2017 | 7.3 | 2,250 | 181 | 391 | 1,190 | 0.4 | 66 | 0.18 |
| 06/07/2017 | 7.4 | 2,370 | 181 | 412 | 1,190 | 0.4 | 68 | 0.08 |
| 07/12/2017 | 7.4 | 2,400 | 185 | 423 | 1,160 | 0.4 | 72 | 0.09 |
| 08/09/2017 | 7.3 | 2,360 | 177 | 400 | 1,280 | 0.4 | 74 | 0.06 |
| 09/13/2017 | 7.4 | 2,440 | 173 | 391 | 1,300 | 0.4 | 77 | 0.10 |
| 10/05/2017 | 7.3 | 2,390 | 183 | 414 | 1,220 | 0.5 | 72 | 0.08 |
| 11/09/2017 | 7.3 | 2,370 | 204 | 453 | 1,290 | 0.4 | 77 | 0.15 |
| 06/06/2018 | 7.5 | 1,800 | 144 | 325 | 939 | 0.4 | 51 | 0.11 |
| 10/26/2018 | 7.5 | 1,900 | 153 | 364 | 900 | 0.4 | 51 | 0.13 |
| 04/06/2019 | 7.5 | 2,200 | 179 | 409 | 1,070 | 0.4 | 65 | 0.03 |
| 09/18/2019 | 7.6 | 1,850 | 142 | 331 | 875 | 0.4 | 44 | 0.13 |
| 05/06/2020 | 7.2 | 2,030 | 151 | (1) | 991 | 0.3 | 51 | 0.14 |
| 11/04/2020 | 7.3 | 1,940 | 152 | (1) | 943 | 0.4 | 49 | 0.16 |
| 05/05/2021 | 7.3 | 2,120 | 160 | 387 | 1,160 | 0.3 | 60 | 0.11 |
| 10/06/2021 | 7.2 | 2,010 | 155 | 383 | 993 | 0.4 | 51 | 0.14 |
| 5/10/2022 | 7.4 | 1,840 | 142 | 338 | 841 | 0.4 | 43 | 0.12 |
| 11/1/2022 | 7.3 | 2,040 | 154 | 372 | 987 | 0.4 | 52 | 0.13 |
| 5/16/2023 | 7.3 | 2,030 | 151 | 391 | 996 | 0.4 | 47 | 0.13 |
| 10/5/2023 | 7.3 | 1,640 | 122 | 325 | 714 | 0.4 | 25 | ND ² |

(1) Sodium was included and used in the combined cation analysis discussed later in this report. Sodium was not analyzed in 2020.

(2) Boron was Not Detected in the sample.

Table 6: Data Summary OMW-8 Appendix III Constituents Plus Sodium

| Date | pH | TDS (mg/l) | Calcium (mg/l) | Sodium (mg/l) | Sulfate (mg/l) | Fluoride (mg/l) | Chloride (mg/l) | Boron (mg/l) |
|------------|-----|------------|----------------|---------------|----------------|-----------------|-----------------|--------------|
| 12/06/2016 | 7.4 | 3,090 | 223 | 619 | 1,680 | 0.4 | 87 | 0.22 |
| 01/05/2017 | 7.4 | 3,050 | 206 | 610 | 1,690 | 0.4 | 84 | 0.22 |
| 02/10/2017 | 7.4 | 3,180 | 199 | 614 | 1,700 | 0.4 | 89 | 0.22 |
| 03/15/2017 | 7.4 | 3,070 | 171 | 560 | 1,720 | 0.5 | 86 | 0.19 |
| 04/12/2017 | 7.4 | 2,840 | 202 | 533 | 1,640 | 0.5 | 85 | 0.23 |
| 05/11/2017 | 7.4 | 3,040 | 201 | 588 | 1,720 | 0.4 | 87 | 0.19 |
| 06/07/2017 | 7.5 | 3,060 | 189 | 606 | 1,710 | 0.4 | 88 | 0.18 |
| 07/12/2017 | 7.5 | 2,860 | 170 | 569 | 1,580 | 0.4 | 91 | 0.18 |
| 08/09/2017 | 7.4 | 2,970 | 175 | 570 | 1,780 | 0.5 | 98 | 0.16 |
| 09/13/2017 | 7.4 | 3,020 | 180 | 565 | 1,750 | 0.5 | 100 | 0.20 |
| 10/05/2017 | 7.4 | 2,790 | 195 | 585 | 1,660 | 0.5 | 95 | 0.16 |
| 11/09/2017 | 7.4 | 2,890 | 200 | 625 | 1,730 | 0.4 | 98 | 0.25 |
| 06/06/2018 | 7.5 | 3,110 | 215 | 621 | 1,710 | 0.4 | 86 | 0.18 |
| 10/26/2018 | 7.5 | 2,520 | 158 | 537 | 1,380 | 0.4 | 76 | 0.18 |
| 04/26/2019 | 7.6 | 2,950 | 201 | 553 | 1,950 | 0.4 | 90 | 0.18 |
| 09/18/2019 | 7.6 | 3,000 | 212 | 536 | 1,650 | 0.4 | 95 | 0.18 |
| 05/06/2020 | 7.4 | 3,240 | 213 | (1) | 1,870 | 0.3 | 104 | 0.20 |
| 11/04/2020 | 7.3 | 3,240 | 216 | (1) | 1,750 | 0.4 | 111 | 0.21 |
| 05/05/2021 | 7.4 | 3,430 | 211 | 630 | 2,030 | 0.4 | 124 | 0.21 |
| 10/06/2021 | 7.4 | 3,370 | 201 | 662 | 1,840 | 0.4 | 117 | 0.25 |
| 5/10/2022 | 7.5 | 3,240 | 181 | 666 | 1,670 | 0.4 | 119 | 0.24 |
| 11/1/2022 | 7.4 | 3,070 | 178 | 621 | 1,640 | 0.5 | 106 | 0.21 |
| 5/16/2023 | 7.4 | 3,220 | 181 | 682 | 1,890 | 0.5 | 118 | 0.20 |
| 10/5/2023 | 7.5 | 2,830 | 158 | 614 | 1,500 | 0.4 | 93 | 0.20 |

(0) Sodium was included and used in the combined cation analysis discussed later in this report. Sodium was not analyzed in 2020.

5.2 DATA SUMMARY STATISTICS

The tables below provide a statistical summary of the Appendix III (Detection) constituents. For Appendix IV data, no analysis is required. A summary and general conclusion regarding Appendix IV data were presented in the report titled “Groundwater Monitoring and Action Plan” (10/17/17) and can be found on the website.

Table 7: CCR Well Summary Statistics

| | Parameter | pH | TDS | Ca | Sulfate | Fluoride | Chloride | Boron | Cation (Ca + Na) |
|-------|------------------------|------|---------|--------|---------|----------|----------|-------|---------------------|
| OMW-1 | Count (n) ⁵ | 26 | 26 | 26 | 26 | 26 | 26 | 26 | 23 |
| | Mean ⁶ | 7.48 | 1217.08 | 105.38 | 444.69 | 0.44 | 47.85 | 0.08 | 300.96 |
| | Std. Dev. ⁷ | 0.09 | 332.96 | 23.80 | 184.60 | 0.13 | 20.45 | 0.03 | 72.85 |
| | Skewness ⁸ | 0.98 | -0.53 | -0.68 | -0.54 | 4.90 | -0.79 | 0.36 | -0.06 |
| | Kurtosis | 1.08 | -0.94 | -0.72 | -0.85 | -0.15 | -0.80 | -1.04 | -0.92 |
| | CV | 0.01 | 0.25 | 0.21 | 0.38 | 0.30 | 0.39 | 0.33 | 0.21 |
| OMW-5 | Count (n) | 32 | 32 | 32 | 32 | 32 | 32 | 32 | 20 |
| | Mean | 7.66 | 4208.75 | 39.94 | 1955.94 | 0.61 | 109.53 | 0.93 | 1505.23 |
| | Std. Dev. | 0.11 | 152.63 | 2.03 | 81.04 | 0.06 | 5.24 | 0.05 | 71.15 |
| | Skewness | 8.35 | -0.09 | -0.13 | 4.06 | 3.35 | -0.80 | 0.18 | 0.69 |
| | Kurtosis | 2.58 | -0.88 | 0.14 | -1.42 | -0.95 | -0.12 | -0.55 | 0.66 |
| | CV | 0.02 | 0.03 | 0.05 | 0.04 | 0.10 | 0.05 | 0.06 | 0.04 |
| OMW-7 | Count (n) | 26 | 26 | 26 | 26 | 26 | 26 | 25 | 23 |
| | Mean | 7.34 | 2183.46 | 169.85 | 1095.50 | 0.40 | 61.31 | 0.11 | 563.63 |
| | Std. Dev. | 0.10 | 307.35 | 26.25 | 184.72 | 0.03 | 16.46 | 0.03 | 69.77 |
| | Skewness | 0.92 | -0.81 | -0.11 | -1.00 | 7.02 | -0.75 | 1.97 | -0.02 |
| | Kurtosis | 1.03 | 0.24 | 0.54 | -0.10 | -0.70 | -0.10 | -1.23 | 0.48 |
| | CV | 0.01 | 0.14 | 0.16 | 0.17 | 0.09 | 0.26 | 0.28 | 0.13 |
| OMW-8 | Count (n) | 26 | 26 | 26 | 26 | 26 | 26 | 26 | 23 |
| | Mean | 7.44 | 3040.00 | 191.96 | 1698.85 | 0.43 | 97.42 | 0.20 | 791.92 |
| | Std. Dev. | 0.07 | 211.36 | 18.43 | 125.61 | 0.05 | 12.66 | 0.03 | 47.07 |
| | Skewness | 0.62 | 0.26 | -0.98 | 2.11 | -0.28 | -0.52 | -0.35 | -0.96 |
| | Kurtosis | 0.83 | -0.41 | -0.21 | 0.17 | 0.21 | 0.62 | 0.24 | -0.23 |
| | CV | 0.01 | 0.07 | 0.10 | 0.08 | 0.13 | 0.13 | 0.13 | 0.06 |

The “Skewness” is presented because it is one indicator to determine if the dataset has or nears a “normal” distribution. The term “normal” refers to a Gaussian distribution. In general, a “Skewness” coefficient greater than unity (absolute value) is an indication, in small sample populations such as the case here, that treating the data as a near-normal distribution

⁵ The count indicates the number of data values.

⁶ The mean is the arithmetic mean of the data values.

⁷ The standard deviation is a measure of the amount of variation in the data set.

⁸ Skewness indicates if the normal (bell-shaped) distribution has a degree of asymmetry.

might not yield fruitful results. A review of Table 7 indicates that 24 of the 32 skewness values are less than 1 (absolute). Therefore, that indicator leans toward a near-normal assumption for much of the data.

Another general 'normal' indicator is Kurtosis. It is like Skewness except Kurtosis indicates large deviation (or outliers) in the data. The term is commonly discussed as a measure of how peaked (or flat) a probability distribution curve may be. However, it is more accurate to refer to it as a measure of the tails of the curve. A value of 3 is a perfectly normal distribution curve. There seems to be no consensus in the literature as to an acceptable range of Kurtosis that is a good indicator of normality. However, values between 2 and 4 seem to be the most common. All but one of our data points (1 of 32) is below this accepted window of normality. Indicating a tendency toward a non-normal aspect of our data set.

The coefficient of variation (CV) also provides an indication as to normality of the data. It is simply the ratio of the standard deviation to the mean. A highly variable (non-normal) dataset will have a high CV. This is an indication, but not necessarily definitive, that the normal (bell-shaped) curve is too flat. An extremely low CV might indicate the opposite, i.e., the curve is too spiked. EPA guidance documents⁹ do not provide definitive guideline values for the CV. Nonetheless, the document indicates a value less than 0.5 is a positive indication of normality. A review of the data in Table 7 indicates that all analyses yielded a CV less than or equal to 0.5. This statistic tends to indicate near-normal distributions.

⁹ "Statistical Analysis of Groundwater Monitoring Data at RCRA Facilities" EPA 530-R-09-007, March 2009.


5.3 DATA ANALYSIS - GRAPHICAL

To decide if there is evidence, statistical or otherwise, of contamination, several analyses seem appropriate. One of the best ways to gain insight into the data is to review the information in a graphical manner. CCR data from 2017 through 2023 is presented in the following eight graphics. Each figure plots a constituent by well in a time series manner.

There are a few observations worth noting in the data.

- 1) Ranking the wells from highest constituent concentration to lowest (with the exception of calcium) reveals the following general order: OMW-5, OMW-8, OMW-7 and then OMW-1. The results of calcium alone are, for the most part, opposite to that described above. The calcium data for OMW-5 is lower than the other three wells.
- 2) Based on the observation in 1), it was decided to combine the two most common cations (Ca and Na) to observe a pattern or difference. A 'total cation' graph was created and included in the list of plots below. The detailed reasoning for combining the two cations is discussed later in this report.

Figure 2: Constituents by Well



Note: Units = mg/l (except pH)

5.4 DATA ANALYSIS – STATISTICS

A statistical analysis of the groundwater monitoring constituents (pH, TDS, Ca, SO₄²⁻, F⁻, Cl⁻ and B) was completed. The statistical methods used for this analysis are discussed in Appendix B and in the document “Groundwater Monitoring and Action Plan” (10/17/17) which can be found on the website.

5.4.1 NORMALITY TESTING

A substantial amount of analysis was conducted to determine the possibility of a normal distribution. Appendix B of this document contains the details of tests used to evaluate the assumption of normality for each of the well-constituent data sets. Data that are near normal were analyzed using parametric tests while non-normal data was analyzed using nonparametric methods described above.

There are a number of statistical tests that may be used to ascertain (near) normal status. For purposes of this study, the following were employed:

- Coefficient of Variation (CV)
- D’Agostino-Pearson Test
- Shapiro-Wilk Test

The reason for choosing the coefficient of variation as a statistic is briefly discussed in Section 5.2 above. Additionally, the CV is a measure discussed in the statistics guideline. The D’Agostino-Pearson test analyzes both the Kurtosis and Skewness of the data. It uses a combination of this data to provide a better predictor of normal distributions than either Skewness or Kurtosis alone. The Shapiro-Wilk test is one of the more common, semi-robust analyses to test for normality.

No single statistic or test was considered definitive. Rather the decision as to normality was based on the weight of evidence of the three methods.

The test for normality was conducted on the raw (non-transformed) data.¹⁰ The results of the normality tests are summarized below. The results of the individual tests are found in Appendix B.

¹⁰ The first annual report made various attempts to subject the data to various linear transformations to determine if perhaps a better normal distribution might emerge. Those efforts did not improve a normal vs. non-normal outcome and that analysis was not repeated here.

Table 8: Normality Test Results

| Well | pH | TDS | Calcium | Sulfate | Fluoride | Chloride | Boron |
|-------|----------|----------|----------|----------|----------|----------|----------|
| OMW 1 | No | Probable | Probable | Probable | No | Probable | Probable |
| OMW 5 | No | Probable | Yes | No | No | Yes | Probable |
| OMW 7 | No | Yes | Yes | Yes | No | Yes | No |
| OMW 8 | Probable | Yes | Yes | Yes | Probable | Yes | Yes |

“Yes” = All three statistical tests indicate a (near) normal distribution.
“Probable” = Two of the three tests indicate (near) normal distribution.
“No” = Either one or zero tests indicate (near) normal distribution.

To cover all eventualities, it was decided to conduct all analyses using both parametric and non-parametric statistical analysis in the appendix. However, in this report we focus on the method deemed appropriate from our normality test results. The conclusions reached for these constituents were the same regardless of the underlying parametric or non-parametric treatment.

5.4.2 ANALYSIS OF VARIANCE (ANOVA) TESTING

To conduct an analysis of variance a combination of the ANOVA, t-test, (paired and unpaired), Kruskal-Wallis (one-way) or Kruskal-Wallis (well by well: Q-Test) was employed. Details are provided below.

ANOVA - Parametric¹¹

The parametric ANOVA test was conducted followed by various t-tests. The ANOVA test employed is a “one-way” test. This testing effectively tests the hypothesis: “*Are the means of a given constituent (e.g., pH, TDS, etc.) across all wells the same?*” If there is enough statistical evidence (at the 5% level) to reject this null hypothesis, then one can conclude that the means of the constituent analyzed across groups (wells) are statistically different. This is accomplished by analyzing the variance within each group (well-constituent) and among each group. If there is no statistical difference in the well-constituents, then the variance among and within the group is consistent. The analysis calculates an “F” statistic based on an “F-distribution.” The calculated F is compared against the “critical” F [a value based on the desired Type I error (5%) and sample size].

For this analysis, the detailed results of the calculations are shown in Appendix C. The appendix data is summarized below.

¹¹ The traditional ANOVA (and “t”) test is a parametric test and best suited for normally distributed data. Nonetheless, this statistical testing was conducted on all the data in the interest of completeness since most of the well/constituent data had at least some indication of a near normal distribution. There were a few exceptions, and these are addressed later in this section.

Table 9: ANOVA (between wells) Summary Results

| Constituent | Calculated F Statistic | Critical F-Statistic | Statistical Difference? |
|-------------|------------------------|----------------------|-------------------------|
| pH | 45.2 | 2.7 | Yes |
| TDS | 613.3 | 2.7 | Yes |
| Calcium | 289.4 | 2.7 | Yes |
| Sulfate | 474.9 | 2.7 | Yes |
| Fluoride | 32.3 | 2.7 | Yes |
| Chloride | 89.0 | 2.7 | Yes |
| Boron | 2,753.5 | 2.7 | Yes |

A “Yes” does not indicate a statistically significant increase; it only indicates that the means among the wells (for the same constituent) are not the same (or do not appear to come from the same population of data). The results of the ANOVA show that each constituent among all four wells is not equal (within a 95% probability window). For example, the mean fluoride concentration is not the same for all four wells. This now leads to the question of whether there is a difference (significant increase) in concentrations between upgradient (background) well OMW-5 and the other three downgradient wells. The comparison needs to be made on a constituent-by-constituent basis. That analysis immediately follows.

t-Test (Parametric)

The (parametric) ANOVA tests indicate differences in individual constituent concentrations among the wells. The ANOVA analysis, however, is not able to distinguish exactly which wells are ‘different’ from each other for a given constituent. Furthermore, where differences are noted, ANOVA does not yield whether the differences indicate an increase or a decrease, just a statistical difference. The t-test is able to directly compare two sets of data and ascertain the probability that they have the same mean (or come from the same population) and whether the difference is an increase or decrease.

The “unpaired with equal variances” and “unpaired with unequal variance” were used as the purposes of this analysis was to compare means of the constituents in the downgradient wells to the means of the constituents in the upgradient well. To be thorough, the t-test was applied to every possible pair of wells and constituents. The complete results of those tests are found in Appendix C along with the ANOVA results. The data is summarized in the table below.

Table 10: t-Test Summary Results

| Constituent | Parameter | OMW-1 vs OMW-5 | | OMW-7 vs OMW-5 | | OMW-8 vs OMW-5 | |
|-------------|----------------------------|----------------|----------|----------------|----------|----------------|----------|
| pH | Mean | 7.5 | 7.7 | 7.3 | 7.7 | 7.4 | 7.7 |
| | Variance | 0.008 | 0.014 | 0.011 | 0.014 | 0.005 | 0.014 |
| | Calculated "t" | -5.65* | | -9.97* | | -7.87 | |
| | Critical "t" ¹² | 1.7* | | 1.7* | | 1.7 | |
| | Difference? ¹³ | Yes | | Yes | | Yes | |
| TDS | Mean | 1,241.5 | 4,208.3 | 2,205.8 | 4,208.3 | 3,045.0 | 4,208.3 |
| | Variance | 96,693.1 | 16,918.8 | 9,4529.7 | 16,918.8 | 40,391.3 | 16,918.8 |
| | Calculated "t" | -43.1 | | -29.4 | | -23.8 | |
| | Critical "t" | 1.7 | | 1.7 | | 1.7 | |
| | Difference? | Yes | | Yes | | Yes | |
| Calcium | Mean | 107.0 | 40.0 | 171.5 | 40.0 | 193.2 | 40.0 |
| | Variance | 521.9 | 4.7 | 707.6 | 4.7 | 348.4 | 4.7 |
| | Calculated "t" | 14.3 | | 24.1 | | 39.9 | |
| | Critical "t" | 1.7 | | 1.7 | | 1.7 | |
| | Difference? | Yes | | Yes | | Yes | |
| Sulfate | Mean | 460.6 | 1,945.0 | 1,107.9 | 1,945.0 | 1,703.3 | 1,945.0 |
| | Variance | 29,996.1 | 7,130.4 | 34,956.5 | 7,130.4 | 16,875.4 | 7,130.4 |
| | Calculated "t" | -37.7 | | -20.0 | | -7.6 | |
| | Critical "t" | 1.7 | | 1.7 | | 1.7 | |
| | Difference? | Yes | | Yes | | Yes | |
| Fluoride | Mean | 0.4 | 0.6 | 0.4 | 0.6 | 0.4 | 0.6 |
| | Variance | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | Calculated "t" | -5.3 | | -13.6 | | -10.2 | |
| | Critical "t" | 1.7 | | 1.7 | | 1.7 | |
| | Difference? | Yes | | Yes | | Yes | |
| Chloride | Mean | 49.2 | 108.0 | 62.8 | 108.0 | 97.0 | 108.0 |
| | Variance | 376.6 | 24.7 | 265.8 | 24.7 | 167.0 | 24.7 |
| | Calculated "t" | -14.4 | | -13.0 | | -3.9 | |
| | Critical "t" | 1.7 | | 1.7 | | 1.7 | |
| | Difference? | Yes | | Yes | | Yes | |
| Boron | Mean | 0.1 | 0.9 | 0.1 | 0.9 | 0.2 | 0.9 |
| | Variance | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | Calculated "t" | -69.3 | | -60.4 | | -59.6 | |
| | Critical "t" | 1.7 | | 1.7 | | 1.7 | |
| | Difference? | Yes | | Yes | | Yes | |

A review of Table 10 shows that there is enough statistical evidence to reject the hypothesis that the two means (between two wells) are not likely from the same underlying population. The sign (\pm) that describes the t-statistic, however, is important. As the analysis was conducted, only a positive value "t" is an indication that there is a "statistically significant increase" (SSI) in concentration in the downgradient well compared to OMW-5 (the

¹² Critical "t" is based on 5% Type I error and sample size and is the one-tail value.

¹³ "Yes" does not indicate a statistically significant increase; it only indicates that the means among the two wells being tested (for the given constituent) are not equal (or come from the same underlying population).

* Data in table Using t-test: Two-Sample assuming equal variance (all others assume unequal variance) used F-test p value < 0.05 to determine an unequal variance.

Table 12: Results Kruskal-Wallis One-Way ANOVA Test Summary Results

| Constituent | H Statistic | r ² /n | Pvalue | Statistical Difference? |
|-------------|-------------|-------------------|--------|-------------------------|
| pH | 58.2 | 270,948.9 | 0.00 | Yes |
| Fluoride | 53.6 | 260,906.8 | 0.00 | Yes |
| Boron | 82.9 | 290120.0 | 0.00 | Yes |

5.5 STATISTICAL RESULTS SUMMARY

The results of the parametric and nonparametric ANOVA and t-tests are quite clear from an exclusively statistical point of view. On a constituent-by-constituent basis these tests indicate that all wells in the analyses fail to show a statistically significant increase (SSI) for pH, TDS, sulfate, fluoride, chloride, and boron.¹⁴ This observation was true for both parametric and nonparametric testing. The lone exception in the analysis is calcium. For reasons and rationale discussed later in this document, calcium concentrations, as a lone cation, in the upgradient/background well were less than those in all three downgradient wells.

There is one additional statistical observation to be made prior to making a conclusion. There are a total of 60 statistical tests spread over 8 constituents (7 of which EPA has chosen for analysis and believe to be an indicator of contamination). If contamination were to occur, it would seem highly likely that several (or all) of the 7 constituents would yield an SSI. While there is no way to estimate how many of the 7 constituents would yield an SSI, one could conservatively give each constituent a 50:50 (independent) probability as it is statistically reasonable that the probability is higher for an SSI if contamination is occurring. That being the case, the probability that only 1 constituent yields an SSI is less than 2%, and by adding cation analysis would further drop the probability to 1%. This observation suggests that the results of the CCR statistical exercise should be treated with caution.

Table 13: Statistics Results

| Well | Constituent | Statistical Increase Above OMW-5 | |
|-------|-------------|----------------------------------|----------------|
| | | Parametric | Non-Parametric |
| OMW-1 | pH | No | No |
| | TDS | No | -- |
| | Calcium | Yes | -- |
| | Sulfate | No | -- |
| | Fluoride | No | No |
| | Chloride | No | -- |
| | Boron | No | No |

¹⁴ The statistics show a near universal significant difference, but not a statistically significant increase.

| Well | Constituent | Statistical Increase Above OMW-5 | |
|-------|-------------|----------------------------------|----------------|
| | | Parametric | Non-Parametric |
| OMW-7 | pH | No | No |
| | TDS | No | -- |
| | Calcium | Yes | -- |
| | Sulfate | No | -- |
| | Fluoride | No | No |
| | Chloride | No | -- |
| | Boron | No | No |
| OMW-8 | pH | No | No |
| | TDS | No | -- |
| | Calcium | Yes | -- |
| | Sulfate | No | -- |
| | Fluoride | No | No |
| | Chloride | No | -- |
| | Boron | No | No |

6.0 GROUNDWATER MONITORING: HYDROGEOLOGY EVALUATION

This review provides a brief discussion of data observations along with an understanding of the physical realities of the project location. The statistical data, by itself, suggests that all three downgradient wells observe calcium levels above background or upgradient well (OMW-5) levels. While the mathematics indicate a difference, there are several confounding variables which are discussed below:

Varying geology

It is noteworthy that in this area the uppermost aquifers in the local hydrogeologic regime are accumulated from localized surface infiltration of direct precipitation, snowmelt, and ephemeral streams. Based on the data and experience in similar conditions, these waters naturally accumulate soluble components of the local geologic materials. These soluble components (including calcium and sodium) often increase with time in contact with the various geologic materials, which result in a somewhat random array of groundwater quality that does not necessarily appear related to the presence of the CCR landfill.

OMW-5 as Background Well

The Rosebud facility has gone to extraordinary lengths to locate an ideal upgradient well. Despite those efforts, it was necessary to use OMW-5 as a background well which was far from ideal. The well is located near the landfill and generally upgradient; but not in the location that was preferred.¹⁵

Total Cations

Calcium and sodium are, in many cases, among the two most common cations in water. These two cations are very similar and tend to be interchangeable when associated with many anions (sulfate, chloride, fluoride, etc.). The low calcium in OMW-5 was unexpected because it had more sulfate and TDS than the other wells. This begs the question as to which cation is in this water if not calcium.

The laboratory was able to obtain sodium data from all years except 2020. The sodium concentration in OMW-5 was much higher than the other three downgradient wells. This is the exact opposite of calcium. These two observations help to explain why the sulfate (and to some extent TDS) concentrations in all wells were similar, but the single ion concentrations (Ca or Na) were opposite of each other. It seemed appropriate that, to consider the unique nature of OMW-5 as a stand-in for an upgradient or background well, the best statistical analysis would be to analyze the combination (sum) of calcium and sodium. This is the reason that the summary and statistic tables included an analysis of the sum of the two cations. The results are consistent with the other six constituent analyses. The data shows there isn't SSI for the cations as a whole.

¹⁵ OMW – 9 and 10 are the 'ideal' locations for upgradient CCR wells. However, both wells have failed to yield any water with three exceptions.

Discontinuous aquifers

The entire CCR premise is that an establishment of one (or more) wells will be upgradient of the landfill itself and the other three (or more) wells are downgradient. The assumption that there are 'definitive' up- and downgradient wells is not appropriate. The data for this area shows that the uppermost aquifer is not continuous and is, to some degree, ephemeral. Additionally, the only true 'upgradient' well is OMW9 which has been dry except for a single sample in 2018. The data quality from that single sample showed much higher concentrations of constituents than all downgradient wells. This is apparently due to the nature of the surrounding geological materials and not due to the landfill.

Ground Disturbances

Some site disturbing actions, independent of CCR requirements, were completed during calendar years 2017, 2018, 2019, and 2020. Due to the lag time for transport of constituents, the results of a corrective erosion repair upslope of OMW-7 and 8 may take additional time before a reduction of calcium levels in OMW-7 and OMW-8 is observed (if slight erosion of the cap upslope of the wells contributed to the measured elevated calcium).

7.0 CONCLUSION

This annual report has been prepared in accordance with the requirements of the CCR rule. More specifically, the report fulfills the requirements of 40 CFR 257.90(e) to complete an “annual groundwater monitoring and corrective action” report. The general purpose of the report is to provide a description and summary of the groundwater monitoring program put in place as a result of the CCR rule. Prior sections provided a summary of the monitoring well program, location of wells, data collected from those wells and other salient information. Overall, the data and results of these analyses are consistent with data and conclusions from previous years annual reports.

The data from the monitoring program has undergone various statistical analyses as generally outlined in §257.93(f), (g) and (h). The results of these mathematical analyses indicate that for all Appendix III pollutants, save calcium, there is no statistically significant increase (SSI) of constituents in the downgradient wells (OMW-1, 7 and 8) compared to the upgradient well (OMW-5).

The only possible exception to this observation is calcium. However, that statistical observation cannot be accepted as sole evidence of contamination for the reasons and discussion below:

- A significant portion of the ash itself is a combination of CaSO_4 , CaSO_3 , etc. If, in fact, OMW-7 and 8 are affected by the ash and OMW-5 is not, then there must be more sulfate and calcium in OMW-7 and 8, which is not true. The sulfate content in OMW-5 is higher than OMW-7 and 8 and the calcium concentration is less than OMW-7 and 8. The sodium concentration (a very similar ion to calcium) is much higher in OMW-5 than the other wells. These observations conflict with the underlying assumption (sulfates = calcium if contaminated) and thus do not support a hypothesis that the landfill may be causing contamination. Rather the calcium concentration variability between the wells is more likely due to the natural background presence of sodium sulfate in the ground water (OMW5), not from any leachate from the ash.
- Analysis for calcium is an analysis of a cation which is associated with several possible anions. Chemically, sodium is another similar cation which is commonly found in groundwater. These two cations effectively serve the same chemical purpose as an association with anions. The sum of the two cations were analyzed as a better indicator of a difference between OMW-5 and the other three wells. The results indicate relative values and statistical conclusions consistent with all other constituent analysis.
- Since there is no traditional upgradient well in the upper-most aquifer in the active landfill drainage basin, a traditional “statistically significant increase” conclusion is not appropriate for elevated calcium observed in downgradient wells due to the general discontinuous nature of the aquifers and hydrogeology. As a result, elevated calcium in downgradient wells appears to be due to natural variation of the discontinuous uppermost aquifer (and geology).

Overall, the data and results of these analyses are consistent with data and conclusions from previous annual reports. The results of these mathematical analyses indicate that for all Appendix III pollutants, save calcium, there is no statistically significant increase (SSI) of constituents in the downgradient wells (OMW-1, 7 and 8) compared to the upgradient well (OMW-5).


Based on the results of the analyses conducted in this document and considering the variables and caveats above, we make the following conclusions:


- (1) There is no statistically significant increase in the Appendix III constituents in the three downgradient wells OMW-1, 7 and 8 compared to the upgradient/background well OMW-5 for the monitoring period.
- (2) Although there was a mathematical increase in calcium, further investigation yielded its cause was due to the unique nature of the groundwater characteristics of the general area surrounding the project along with an inability to establish a traditional upgradient well. This was confirmed by an analysis of additional cations (Na). Combining the cations (Ca and Na) yields no statistically significant increase between the upgradient/background well and the other three CCR wells.

Appendix A

Groundwater Well: Elevation, Flow and Direction

Calendar Year 2023





| NO. | REVISIONS | DRAWN BY | DATE |
|-----|-----------|----------|------|
| | | | |
| | | | |
| | | | |

0 100 200 300
SCALE (FEET)

PROJECT ENGINEER: DSC DRAWN BY: ACF
DESIGNED BY: RECHECKED BY: BDA

ANNUAL GROUNDWATER REPORT
GROUNDWATER MONITORING EVENT: 09-06-2023
ROSEBUD COUNTY, MT

32 BRIGGS DRIVE
ROSEBUD, MT 59718
PHONE (406) 524-2221
FAX (406) 524-0773
www.civilengineering.com

Civil Engineering
Geotechnical Engineering
Land Surveying

PROJECT # 15-125 SHEET
DATE: 01/29/2024 GW-2

Appendix B

Groundwater Well Data: Statistical Tests for Normality

Calendar Years: 2016 - 2023

A set of ‘goodness of fit’ analyses was run to determine if each constituent (on a well-by-well basis) could be treated as a normal distribution. All constituents that met this test were then analyzed by analysis of variance using the traditional ANOVA and t-tests. Those not meeting the normality test were analyzed using both parametric (i.e., ANOVA and t-test) and nonparametric testing.

Since there is no single definitive test for data normality, multiple tests were employed. These include D’Agostino-Pearson statistic, coefficient of variation and the Shapiro-Wilk statistic. It was decided that if any variable (constituent by well) passed at least two of the three test statistics, the variable would then be subject to only parametric methods.

The selection criteria for each test (normal vs non-normal) are as follows:

| Test | Criteria | Source / Comment |
|---------------------------------|--|---|
| Shapiro - Wilk | If the probability statistic > 0.05 then normality is assumed. | This statistic is a common measure for normality. A Type I error of 0.05 was used. This value and the statistic itself are discussed and recommended in “Statistical Analysis of Groundwater Monitoring Data at RCRA Facilities,” EPA 530-R-09-007; March 2009. |
| Coefficient of Variation | If value of the Coefficient of Variation < 0.5; then normality is assumed. | The coefficient of variation (CV) is not considered a robust test of normality; however, the CV provides a ‘quick and easy’ screening test for normality according to “Statistical Analysis of Groundwater Monitoring Data at RCRA Facilities,” EPA 530-R-09-007, March 2009. |
| D’Agostino-Pearson | If the probability statistic > 0.05 normality is assumed. | This test employs both the Kurtosis and Skewness statistic. These two statistics are, in and of themselves, a measure of normality, making this a reasonable choice for a normality test. |

The analysis for the Coefficient of Variation was calculated using Excel. In order to calculate the Shapiro-Wilk and the D’Agostino-Pearson statistic, the Add-In Software “Real Statistics Resource Pack” was employed since these functions are not available in Excel or in the Excel “Data Analysis” add-in. More information regarding the statistical package may be found at: <http://www.real-statistics.com/free-download/real-statistics-resource-pack/>

Normality Tests

Smaller probabilities indicate non-normality.

2017 ↔ 2023

OMW 1

| | Valid Cases | Missing | Mean | Standard Deviation | Shapiro-Wilk Test | Probability | d'Agostino-Pearson Test | Probability | Coefficient of Variation | # Accepted Normality Tests |
|--|-------------|---------|---------|--------------------|-------------------|-------------|-------------------------|-------------|--------------------------|----------------------------|
| pH | 24 | 0 | 7.49 | 0.09 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 1 |
| TDS | 24 | 0 | 1195.75 | 310.96 | 0.00 | 0.00 | 0.00 | 0.00 | 0.26 | 1 |
| Calcium (Ca) | 24 | 0 | 104.35 | 22.84 | 0.00 | 0.00 | 0.00 | 0.00 | 0.22 | 1 |
| Sulfate (SO ₄) ²⁻ | 24 | 0 | 414.86 | 173.19 | 0.00 | 0.00 | 0.00 | 0.00 | 0.42 | 1 |
| Flouride (F) | 24 | 0 | 0.41 | 0.13 | 0.00 | 0.00 | 0.00 | 0.00 | 0.32 | 1 |
| Chloride (Cl) | 24 | 0 | 43.85 | 19.41 | 0.00 | 0.00 | 0.00 | 0.00 | 0.44 | 1 |
| Boron (B) | 24 | 0 | 0.07 | 0.03 | 0.00 | 0.00 | 0.00 | 0.00 | 0.35 | 1 |

OMW 5

| | Valid Cases | Missing | Mean | Standard Deviation | Shapiro-Wilk Test | Probability | d'Agostino-Pearson Test | Probability | Coefficient of Variation | # Accepted Normality Tests |
|--|-------------|---------|----------|--------------------|-------------------|-------------|-------------------------|-------------|--------------------------|----------------------------|
| pH | 24 | 0 | 7.66 | 0.12 | 0.00 | 0.00 | 0.00 | 0.00 | 0.02 | 1 |
| TDS | 24 | 0 | 4,207.19 | 130.75 | 0.00 | 0.00 | 0.00 | 0.00 | 0.03 | 1 |
| Calcium (Ca) | 24 | 0 | 39.99 | 2.16 | 0.00 | 0.00 | 0.00 | 0.00 | 0.05 | 1 |
| Sulfate (SO ₄) ²⁻ | 24 | 0 | 1,943.17 | 84.44 | 0.00 | 0.00 | 0.00 | 0.00 | 0.04 | 1 |
| Flouride (F) | 24 | 0 | 0.59 | 0.06 | 0.00 | 0.00 | 0.00 | 0.00 | 0.11 | 1 |
| Chloride (Cl) | 24 | 0 | 107.93 | 4.97 | 0.00 | 0.00 | 0.00 | 0.00 | 0.05 | 1 |
| Boron (B) | 24 | 0 | 0.93 | 0.05 | 0.00 | 0.00 | 0.00 | 0.00 | 0.06 | 1 |

OMW 7

| | Valid Cases | Missing | Mean | Standard Deviation | Shapiro-Wilk Test | Probability | d'Agostino-Pearson Test | Probability | Coefficient of Variation | # Accepted Normality Tests |
|--|-------------|---------|----------|--------------------|-------------------|-------------|-------------------------|-------------|--------------------------|----------------------------|
| pH | 24 | 0 | 7.34 | 0.10 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 1 |
| TDS | 24 | 0 | 2,185.22 | 307.46 | 0.00 | 0.00 | 0.00 | 0.00 | 0.14 | 1 |
| Calcium (Ca) | 24 | 0 | 169.52 | 26.60 | 0.00 | 0.00 | 0.00 | 0.00 | 0.16 | 1 |
| Sulfate (SO ₄) ²⁻ | 24 | 0 | 1,091.96 | 186.97 | 0.00 | 0.00 | 0.00 | 0.00 | 0.17 | 1 |
| Flouride (F) | 24 | 0 | 0.39 | 0.04 | 0.00 | 0.00 | 0.00 | 0.00 | 0.09 | 1 |
| Chloride (Cl) | 24 | 0 | 60.44 | 16.30 | 0.00 | 0.00 | 0.00 | 0.00 | 0.27 | 1 |
| Boron (B) | 24 | 0 | 0.11 | 0.03 | 0.00 | 0.00 | 0.00 | 0.00 | 0.29 | 1 |

OMW 8

| | Valid Cases | Missing | Mean | Standard Deviation | Shapiro-Wilk Test | Probability | d'Agostino-Pearson Test | Probability | Coefficient of Variation | # Accepted Normality Tests |
|--|-------------|---------|----------|--------------------|-------------------|-------------|-------------------------|-------------|--------------------------|----------------------------|
| pH | 24 | 0 | 7.44 | 0.07 | 0.00 | 0.00 | 0.00 | 0.00 | 0.01 | 1 |
| TDS | 24 | 0 | 3,038.50 | 200.98 | 0.00 | 0.00 | 0.00 | 0.00 | 0.07 | 1 |
| Calcium (Ca) | 24 | 0 | 192.28 | 18.67 | 0.00 | 0.00 | 0.00 | 0.00 | 0.10 | 1 |
| Sulfate (SO ₄) ²⁻ | 24 | 0 | 1,698.55 | 129.91 | 0.00 | 0.00 | 0.00 | 0.00 | 0.08 | 1 |
| Flouride (F) | 24 | 0 | 0.42 | 0.05 | 0.00 | 0.00 | 0.00 | 0.00 | 0.13 | 1 |
| Chloride (Cl) | 24 | 0 | 96.17 | 12.92 | 0.00 | 0.00 | 0.00 | 0.00 | 0.13 | 1 |
| Boron (B) | 24 | 0 | 0.20 | 0.03 | 0.00 | 0.00 | 0.00 | 0.00 | 0.13 | 1 |

Appendix C

Analysis of Variance for Groundwater Data:

ANOVA & t-Test Results

Calendar Years 2017 through 2023

The ‘analysis of variance’ was discussed in greater detail in previous years reports. It was decided, based in part that the normality tests were largely successful, to conduct this testing using the two methods below:

- ANOVA and
- t-test (unpaired)

The ANOVA test was conducted first followed by various t-tests. The ANOVA test employed is a “one-way” test to determine, on the whole, whether the means from all four wells (OMW1, 5, 7 and 8) are statistically the same. Should that test “fail” (i.e., there is enough statistical evidence to reject the null hypothesis that all means are the same), then paired comparisons were made between the upgradient well (OMW5) and all other wells individually and by constituent.

An F-test was used to compare the variances of the upgradient well constituent data to each of the downgradient wells’ constituent data to determine which unpaired t-test should be used. If the F-test result shows a probability of less than 5% that the variances are equal, then the t-test: two-sample assuming unequal variances was used. If the F-test shows that the variance of the upgradient well constituent data and the downgradient well constituent data are the same (i.e., the null hypothesis cannot be rejected), then the t-test: two-sample assuming equal variances was used.

The following pages provide the raw output from the statistical analyses themselves for every combination described above. Each page contains the constituent-specific ANOVA for all wells, and the t-test and F-test results for each upgradient-downgradient combination.

Boron: ANOVA & t-Tests

Anova: Single Factor

SUMMARY

| Groups | Count | Sum | Average | Variance |
|--------|-------|-------|----------|-------------|
| OMW-1 | 24 | 1.905 | 0.079375 | 0.000618071 |
| OMW-5 | 24 | 22.4 | 0.933333 | 0.003023188 |
| OMW-7 | 24 | 2.595 | 0.108125 | 0.001458288 |
| OMW-8 | 24 | 4.74 | 0.1975 | 0.000636957 |

ANOVA

| Source of Variation | SS | df | MS | F | P-value | F crit |
|---------------------|-------------|----|----------|-------------|-------------|----------|
| Between Groups | 11.84659375 | 3 | 3.948865 | 2753.499234 | 6.54158E-90 | 2.703594 |
| Within Groups | 0.131939583 | 92 | 0.001434 | | | |
| Total | 11.97853333 | 95 | | | | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-1 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 0.079375 | 0.933333 |
| Variance | 0.000618071 | 0.003023 |
| Observations | 24 | 24 |
| Pooled Variance | 0.00182063 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -69.32925172 | |
| P(T<=t) one-tail | 1.71903E-48 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 3.43805E-48 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-1 | OMW-5 |
|------------------------------|--------------|-------|
| Mean | 0.1 | 0.9 |
| Variance | 0.0 | 0.0 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 32 | |
| t Stat | -69.32925172 | |
| P(T<=t) one-tail | 9.40289E-37 | |
| t Critical one-tail | 1.693888748 | |
| P(T<=t) two-tail | 1.88058E-36 | |
| t Critical two-tail | 2.036933343 | |

F-Test Two-Sample for Variances

| | OMW-1 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 0.079375 | 0.933333 |
| Variance | 0.000618071 | 0.003023 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 0.204443313 | |
| P(F<=f) one-tail | 0.000163074 | |
| F Critical one-tail | 0.496419613 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-7 | OMW-5 |
|------------------------------|-------------|----------|
| Mean | 0.108125 | 0.933333 |
| Variance | 0.001458288 | 0.003023 |
| Observations | 24 | 24 |
| Pooled Variance | 0.002240738 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -60.3891152 | |
| P(T<=t) one-tail | 9.20245E-46 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 1.84049E-45 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-7 | OMW-5 |
|------------------------------|-------------|-------|
| Mean | 0.1 | 0.9 |
| Variance | 0.0 | 0.0 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 41 | |
| t Stat | -60.3891152 | |
| P(T<=t) one-tail | 5.46278E-42 | |
| t Critical one-tail | 1.682878002 | |
| P(T<=t) two-tail | 1.09256E-41 | |
| t Critical two-tail | 2.01954097 | |

F-Test Two-Sample for Variances

| | OMW-7 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 0.108125 | 0.933333 |
| Variance | 0.001458288 | 0.003023 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 0.48236757 | |
| P(F<=f) one-tail | 0.043548545 | |
| F Critical one-tail | 0.496419613 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-8 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 0.1975 | 0.933333 |
| Variance | 0.000636957 | 0.003023 |
| Observations | 24 | 24 |
| Pooled Variance | 0.001830072 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -59.58486193 | |
| P(T<=t) one-tail | 1.69215E-45 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 3.3843E-45 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-8 | OMW-5 |
|------------------------------|--------------|-------|
| Mean | 0.2 | 0.9 |
| Variance | 0.0 | 0.0 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 32 | |
| t Stat | -59.58486193 | |
| P(T<=t) one-tail | 1.15472E-34 | |
| t Critical one-tail | 1.693888748 | |
| P(T<=t) two-tail | 2.30944E-34 | |
| t Critical two-tail | 2.036933343 | |

F-Test Two-Sample for Variances

| | OMW-8 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 0.1975 | 0.933333 |
| Variance | 0.000636957 | 0.003023 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 0.210690316 | |
| P(F<=f) one-tail | 0.00020694 | |
| F Critical one-tail | 0.496419613 | |

Calcium: ANOVA & t-Tests

Anova: Single Factor

Anova: Single Factor

SUMMARY

| Groups | Count | Sum | Average | Variance |
|--------|-------|------|----------|-------------|
| OMW-1 | 24 | 2569 | 107.0417 | 521.8677536 |
| OMW-5 | 24 | 961 | 40.04167 | 4.650362319 |
| OMW-7 | 24 | 4115 | 171.4583 | 707.5634058 |
| OMW-8 | 24 | 4636 | 193.1667 | 348.4057971 |

ANOVA

| Source of Variation | SS | df | MS | F | P-value | F crit |
|---------------------|-------------|----|----------|-------------|-------------|----------|
| Between Groups | 343469.2813 | 3 | 114489.8 | 289.3919188 | 1.02819E-46 | 2.703594 |
| Within Groups | 36397.20833 | 92 | 395.6218 | | | |
| Total | 379866.4896 | 95 | | | | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-1 | OMW-5 |
|------------------------------|-------------|----------|
| Mean | 107.0416667 | 40.04167 |
| Variance | 521.8677536 | 4.650362 |
| Observations | 24 | 24 |
| Pooled Variance | 263.259058 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | 14.30453565 | |
| P(T<=t) one-tail | 7.50364E-19 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 1.50073E-18 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-1 | OMW-5 |
|------------------------------|-------------|-------|
| Mean | 107.0 | 40.0 |
| Variance | 521.9 | 4.7 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 23 | |
| t Stat | 14.30453565 | |
| P(T<=t) one-tail | 3.07951E-13 | |
| t Critical one-tail | 1.713871528 | |
| P(T<=t) two-tail | 6.15901E-13 | |
| t Critical two-tail | 2.06865761 | |

F-Test Two-Sample for Variances

| | OMW-1 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 107.0416667 | 40.04167 |
| Variance | 521.8677536 | 4.650362 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 112.2208804 | |
| P(F<=f) one-tail | 1.51938E-18 | |
| F Critical one-tail | 2.014424842 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-7 | OMW-5 |
|------------------------------|-------------|----------|
| Mean | 171.4583333 | 40.04167 |
| Variance | 707.5634058 | 4.650362 |
| Observations | 24 | 24 |
| Pooled Variance | 356.1068841 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | 24.12408698 | |
| P(T<=t) one-tail | 4.71833E-18 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 9.43666E-28 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-7 | OMW-5 |
|------------------------------|-------------|-------|
| Mean | 171.5 | 40.0 |
| Variance | 707.6 | 4.7 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 23 | |
| t Stat | 24.12408698 | |
| P(T<=t) one-tail | 3.91722E-18 | |
| t Critical one-tail | 1.713871528 | |
| P(T<=t) two-tail | 7.83443E-18 | |
| t Critical two-tail | 2.06865761 | |

F-Test Two-Sample for Variances

| | OMW-7 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 171.4583333 | 40.04167 |
| Variance | 707.5634058 | 4.650362 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 152.1523179 | |
| P(F<=f) one-tail | 4.81532E-20 | |
| F Critical one-tail | 2.014424842 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-8 | OMW-5 |
|------------------------------|-------------|----------|
| Mean | 193.1666667 | 40.04167 |
| Variance | 348.4057971 | 4.650362 |
| Observations | 24 | 24 |
| Pooled Variance | 176.5280797 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | 39.923612 | |
| P(T<=t) one-tail | 1.19056E-37 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 2.38112E-37 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-8 | OMW-5 |
|------------------------------|-------------|-------|
| Mean | 193.2 | 40.0 |
| Variance | 348.4 | 4.7 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 24 | |
| t Stat | 39.923612 | |
| P(T<=t) one-tail | 9.21314E-24 | |
| t Critical one-tail | 1.71088208 | |
| P(T<=t) two-tail | 1.84263E-23 | |
| t Critical two-tail | 2.06398562 | |

F-Test Two-Sample for Variances

| | OMW-8 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 193.1666667 | 40.04167 |
| Variance | 348.4057971 | 4.650362 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 74.92014024 | |
| P(F<=f) one-tail | 1.44323E-16 | |
| F Critical one-tail | 2.014424842 | |

Catious: ANOVA & t-Tests

Anova: Single Factor

SUMMARY

| Groups | Count | Sum | Average | Variance |
|--------|-------|-------|-------------|-------------|
| OMW-1 | 22 | 6779 | 308.1363636 | 4340.504329 |
| OMW-5 | 22 | 32830 | 1492.272727 | 3268.207792 |
| OMW-7 | 22 | 12494 | 567.9090909 | 5057.134199 |
| OMW-8 | 22 | 17373 | 789.6818182 | 2358.512987 |

ANOVA

| Source of Variation | SS | df | MS | F | P-value | F crit |
|---------------------|-------------|----|-------------|-------------|------------|----------|
| Between Groups | 17043466.45 | 3 | 5681155.485 | 1512.518536 | 5.7898E-73 | 2.713227 |
| Within Groups | 315511.5455 | 84 | 3756.089827 | | | |
| Total | 17358978 | 87 | | | | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-1 | OMW-5 |
|------------------------------|-------------|----------|
| Mean | 308.1363636 | 1492.273 |
| Variance | 4340.504329 | 3268.208 |
| Observations | 22 | 22 |
| Pooled Variance | 3804.356061 | |
| Hypothesized Mean Difference | 0 | |
| df | 42 | |
| t Stat | -63.6733181 | |
| P(T<=t) one-tail | 1.03959E-43 | |
| t Critical one-tail | 1.681952357 | |
| P(T<=t) two-tail | 2.07919E-43 | |
| t Critical two-tail | 2.018081703 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-7 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 567.9090909 | 1492.273 |
| Variance | 5057.134199 | 3268.208 |
| Observations | 22 | 22 |
| Pooled Variance | 4162.670996 | |
| Hypothesized Mean Difference | 0 | |
| df | 42 | |
| t Stat | -47.51745274 | |
| P(T<=t) one-tail | 1.91793E-38 | |
| t Critical one-tail | 1.681952357 | |
| P(T<=t) two-tail | 3.83587E-38 | |
| t Critical two-tail | 2.018081703 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-8 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 789.6818182 | 1492.273 |
| Variance | 2358.512987 | 3268.208 |
| Observations | 22 | 22 |
| Pooled Variance | 2813.36039 | |
| Hypothesized Mean Difference | 0 | |
| df | 42 | |
| t Stat | -43.93252698 | |
| P(T<=t) one-tail | 4.85334E-37 | |
| t Critical one-tail | 1.681952357 | |
| P(T<=t) two-tail | 9.70669E-37 | |
| t Critical two-tail | 2.018081703 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-1 | OMW-5 |
|------------------------------|-------------|----------|
| Mean | 308.1363636 | 1492.273 |
| Variance | 4340.504329 | 3268.208 |
| Observations | 22 | 22 |
| Hypothesized Mean Difference | 0 | |
| df | 41 | |
| t Stat | -63.6733181 | |
| P(T<=t) one-tail | 6.37065E-43 | |
| t Critical one-tail | 1.682878002 | |
| P(T<=t) two-tail | 1.27413E-42 | |
| t Critical two-tail | 2.01954097 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-7 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 567.9090909 | 1492.273 |
| Variance | 5057.134199 | 3268.208 |
| Observations | 22 | 22 |
| Hypothesized Mean Difference | 0 | |
| df | 40 | |
| t Stat | -47.51745274 | |
| P(T<=t) one-tail | 4.12422E-37 | |
| t Critical one-tail | 1.683851013 | |
| P(T<=t) two-tail | 8.24845E-37 | |
| t Critical two-tail | 2.02107539 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-8 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 789.6818182 | 1492.273 |
| Variance | 2358.512987 | 3268.208 |
| Observations | 22 | 22 |
| Hypothesized Mean Difference | 0 | |
| df | 41 | |
| t Stat | -43.93252698 | |
| P(T<=t) one-tail | 2.07449E-36 | |
| t Critical one-tail | 1.682878002 | |
| P(T<=t) two-tail | 4.14898E-36 | |
| t Critical two-tail | 2.01954097 | |

F-Test Two-Sample for Variances

| | OMW-1 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 308.1363636 | 1492.273 |
| Variance | 4340.504329 | 3268.208 |
| Observations | 22 | 22 |
| df | 21 | 21 |
| F | 1.328099253 | |
| P(F<=f) one-tail | 0.26063164 | |
| F Critical one-tail | 2.084188623 | |

F-Test Two-Sample for Variances

| | OMW-7 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 570.2083333 | 1492.273 |
| Variance | 6069.563406 | 3268.208 |
| Observations | 24 | 22 |
| df | 23 | 21 |
| F | 1.857153459 | |
| P(F<=f) one-tail | 0.079290289 | |
| F Critical one-tail | 2.063280363 | |

F-Test Two-Sample for Variances

| | OMW-8 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 789.6818182 | 1492.273 |
| Variance | 2358.512987 | 3268.208 |
| Observations | 22 | 22 |
| df | 21 | 21 |
| F | 0.721653315 | |
| P(F<=f) one-tail | 0.230563593 | |
| F Critical one-tail | 0.479803022 | |

Chloride: ANOVA & t-Tests

Anova: Single Factor

SUMMARY

| Groups | Count | Sum | Average | Variance |
|--------|-------|------|----------|-------------|
| OMW-1 | 24 | 1180 | 49.16667 | 376.5797101 |
| OMW-5 | 24 | 2593 | 108.0417 | 24.73731884 |
| OMW-7 | 24 | 1506 | 62.75 | 265.7608696 |
| OMW-8 | 24 | 2327 | 96.95833 | 166.9981884 |

ANOVA

| Source of Variation | SS | df | MS | F | P-value | F crit |
|---------------------|-------------|----|---------|-------------|-------------|----------|
| Between Groups | 55675.20833 | 3 | 18558.4 | 89.00100635 | 4.21084E-27 | 2.703594 |
| Within Groups | 19183.75 | 92 | 208.519 | | | |
| Total | 74858.95833 | 95 | | | | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-1 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 49.16666667 | 108.0417 |
| Variance | 376.5797101 | 24.73732 |
| Observations | 24 | 24 |
| Pooled Variance | 200.6585145 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -14.39768762 | |
| P(T<=t) one-tail | 5.87198E-19 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 1.1744E-18 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-7 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 62.75 | 108.0417 |
| Variance | 265.7608696 | 24.73732 |
| Observations | 24 | 24 |
| Pooled Variance | 145.2490942 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -13.01823806 | |
| P(T<=t) one-tail | 2.46727E-17 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 4.93454E-17 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-8 | OMW-5 |
|------------------------------|-----------|----------|
| Mean | 96.95833 | 108.0417 |
| Variance | 166.9982 | 24.73732 |
| Observations | 24 | 24 |
| Pooled Variance | 95.86775 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -3.921252 | |
| P(T<=t) one-tail | 0.000146 | |
| t Critical one-tail | 1.67866 | |
| P(T<=t) two-tail | 0.000291 | |
| t Critical two-tail | 2.012896 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-1 | OMW-5 |
|------------------------------|--------------|-------|
| Mean | 49.2 | 108.0 |
| Variance | 376.6 | 24.7 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 26 | |
| t Stat | -14.39768762 | |
| P(T<=t) one-tail | 3.3489E-14 | |
| t Critical one-tail | 1.70561792 | |
| P(T<=t) two-tail | 6.69781E-14 | |
| t Critical two-tail | 2.055529439 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-7 | OMW-5 |
|------------------------------|--------------|-------|
| Mean | 62.8 | 108.0 |
| Variance | 265.8 | 24.7 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 27 | |
| t Stat | -13.01823806 | |
| P(T<=t) one-tail | 1.88247E-13 | |
| t Critical one-tail | 1.703288446 | |
| P(T<=t) two-tail | 3.76495E-13 | |
| t Critical two-tail | 2.051830516 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-8 | OMW-5 |
|------------------------------|-----------|-------|
| Mean | 97.0 | 108.0 |
| Variance | 167.0 | 24.7 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 30 | |
| t Stat | -3.921252 | |
| P(T<=t) one-tail | 0.000237 | |
| t Critical one-tail | 1.697261 | |
| P(T<=t) two-tail | 0.000474 | |
| t Critical two-tail | 2.042272 | |

F-Test Two-Sample for Variances

| | OMW-1 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 49.16666667 | 108.0417 |
| Variance | 376.5797101 | 24.73732 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 15.22314171 | |
| P(F<=f) one-tail | 4.5369E-09 | |
| F Critical one-tail | 2.014424842 | |

F-Test Two-Sample for Variances

| | OMW-7 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 62.75 | 108.0417 |
| Variance | 265.7608696 | 24.73732 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 10.74331747 | |
| P(F<=f) one-tail | 1.46367E-07 | |
| F Critical one-tail | 2.014424842 | |

F-Test Two-Sample for Variances

| | OMW-8 | OMW-5 |
|---------------------|----------|----------|
| Mean | 96.95833 | 108.0417 |
| Variance | 166.9982 | 24.73732 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 6.75086 | |
| P(F<=f) one-tail | 1.09E-05 | |
| F Critical one-tail | 2.014425 | |

Fluoride: ANOVA & t-Tests

Anova: Single Factor

SUMMARY

| Groups | Count | Sum | Average | Variance |
|--------|-------|------|----------|-------------|
| OMW-1 | 24 | 10.7 | 0.445833 | 0.015634058 |
| OMW-5 | 24 | 14.3 | 0.595833 | 0.003894928 |
| OMW-7 | 24 | 9.5 | 0.395833 | 0.001286232 |
| OMW-8 | 24 | 10.2 | 0.425 | 0.002826087 |

ANOVA

| Source of Variation | SS | df | MS | F | P-value | F crit |
|---------------------|-----------|----|----------|-------------|-------------|----------|
| Between Groups | 0.5728125 | 3 | 0.190938 | 32.30574713 | 2.35767E-14 | 2.703594 |
| Within Groups | 0.54375 | 92 | 0.00591 | | | |
| Total | 1.1165625 | 95 | | | | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-1 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 0.445833333 | 0.595833 |
| Variance | 0.015634058 | 0.003895 |
| Observations | 24 | 24 |
| Pooled Variance | 0.009764493 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -5.258441398 | |
| P(T<=t) one-tail | 1.8375E-06 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 3.67499E-06 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-1 | OMW-5 |
|------------------------------|--------------|-------|
| Mean | 0.4 | 0.6 |
| Variance | 0.0 | 0.0 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 34 | |
| t Stat | -5.258441398 | |
| P(T<=t) one-tail | 3.96671E-06 | |
| t Critical one-tail | 1.690924255 | |
| P(T<=t) two-tail | 7.93343E-06 | |
| t Critical two-tail | 2.032244509 | |

F-Test Two-Sample for Variances

| | OMW-1 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 0.445833333 | 0.595833 |
| Variance | 0.015634058 | 0.003895 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 4.013953488 | |
| P(F<=f) one-tail | 0.000741609 | |
| F Critical one-tail | 2.014424842 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-7 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 0.395833333 | 0.595833 |
| Variance | 0.001286232 | 0.003895 |
| Observations | 24 | 24 |
| Pooled Variance | 0.00259058 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -13.61200622 | |
| P(T<=t) one-tail | 4.7981E-18 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 9.5962E-18 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-7 | OMW-5 |
|------------------------------|--------------|-------|
| Mean | 0.4 | 0.6 |
| Variance | 0.0 | 0.0 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 37 | |
| t Stat | -13.61200622 | |
| P(T<=t) one-tail | 2.78641E-16 | |
| t Critical one-tail | 1.68709362 | |
| P(T<=t) two-tail | 5.57281E-16 | |
| t Critical two-tail | 2.026192463 | |

F-Test Two-Sample for Variances

| | OMW-7 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 0.395833333 | 0.595833 |
| Variance | 0.001286232 | 0.003895 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 0.330232558 | |
| P(F<=f) one-tail | 0.005146325 | |
| F Critical one-tail | 0.496419613 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-8 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 0.425 | 0.595833 |
| Variance | 0.002826087 | 0.003895 |
| Observations | 24 | 24 |
| Pooled Variance | 0.003360507 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -10.20847383 | |
| P(T<=t) one-tail | 1.05151E-13 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 2.10303E-13 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-8 | OMW-5 |
|------------------------------|--------------|-------|
| Mean | 0.4 | 0.6 |
| Variance | 0.0 | 0.0 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 45 | |
| t Stat | -10.20847383 | |
| P(T<=t) one-tail | 1.35695E-13 | |
| t Critical one-tail | 1.679427393 | |
| P(T<=t) two-tail | 2.7139E-13 | |
| t Critical two-tail | 2.014103389 | |

F-Test Two-Sample for Variances

| | OMW-8 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 0.425 | 0.595833 |
| Variance | 0.002826087 | 0.003895 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 0.725581395 | |
| P(F<=f) one-tail | 0.223839144 | |
| F Critical one-tail | 0.496419613 | |

pH: ANOVA & t-Tests

Anova: Single Factor

SUMMARY

| Groups | Count | Sum | Average | Variance |
|--------|-------|-------|----------|-------------|
| OMW-1 | 24 | 179.7 | 7.4875 | 0.008097826 |
| OMW-5 | 24 | 183.8 | 7.658333 | 0.01384058 |
| OMW-7 | 24 | 176.2 | 7.341667 | 0.010362319 |
| OMW-8 | 24 | 178.5 | 7.4375 | 0.005054348 |

ANOVA

| Source of Variation | SS | df | MS | F | P-value | F crit |
|---------------------|-------------|----|----------|------------|-------------|----------|
| Between Groups | 1.267083333 | 3 | 0.422361 | 45.2266408 | 4.73529E-18 | 2.703594 |
| Within Groups | 0.859166667 | 92 | 0.009339 | | | |
| Total | 2.12625 | 95 | | | | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-1 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 7.4875 | 7.658333 |
| Variance | 0.008097826 | 0.013841 |
| Observations | 24 | 24 |
| Pooled Variance | 0.010969203 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -5.650354592 | |
| P(T<=t) one-tail | 4.82388E-07 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 9.64776E-07 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-1 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 7.4875 | 7.658333 |
| Variance | 0.008097826 | 0.013841 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 43 | |
| t Stat | -5.650354592 | |
| P(T<=t) one-tail | 5.88331E-07 | |
| t Critical one-tail | 1.681070703 | |
| P(T<=t) two-tail | 1.17666E-06 | |
| t Critical two-tail | 2.016692199 | |

F-Test Two-Sample for Variances

| | OMW-1 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 7.4875 | 7.658333 |
| Variance | 0.008097826 | 0.013841 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 0.585078534 | |
| P(F<=f) one-tail | 0.103113642 | |
| F Critical one-tail | 0.496419613 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-7 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 7.341666667 | 7.658333 |
| Variance | 0.010362319 | 0.013841 |
| Observations | 24 | 24 |
| Pooled Variance | 0.012101449 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -9.971816572 | |
| P(T<=t) one-tail | 2.22607E-13 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 4.45215E-13 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-7 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 7.341666667 | 7.658333 |
| Variance | 0.010362319 | 0.013841 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 45 | |
| t Stat | -9.971816572 | |
| P(T<=t) one-tail | 2.84037E-13 | |
| t Critical one-tail | 1.679427393 | |
| P(T<=t) two-tail | 5.68073E-13 | |
| t Critical two-tail | 2.014103389 | |

F-Test Two-Sample for Variances

| | OMW-7 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 7.341666667 | 7.658333 |
| Variance | 0.010362319 | 0.013841 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 0.748691099 | |
| P(F<=f) one-tail | 0.246562794 | |
| F Critical one-tail | 0.496419613 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-8 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 7.4375 | 7.658333 |
| Variance | 0.005054348 | 0.013841 |
| Observations | 24 | 24 |
| Pooled Variance | 0.009447464 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -7.870415009 | |
| P(T<=t) one-tail | 2.29721E-10 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 4.59442E-10 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-8 | OMW-5 |
|------------------------------|--------------|----------|
| Mean | 7.4375 | 7.658333 |
| Variance | 0.005054348 | 0.013841 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 38 | |
| t Stat | -7.870415009 | |
| P(T<=t) one-tail | 8.43652E-10 | |
| t Critical one-tail | 1.68595446 | |
| P(T<=t) two-tail | 1.6873E-09 | |
| t Critical two-tail | 2.024394164 | |

F-Test Two-Sample for Variances

| | OMW-8 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 7.4375 | 7.658333 |
| Variance | 0.005054348 | 0.013841 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 0.365183246 | |
| P(F<=f) one-tail | 0.009586334 | |
| F Critical one-tail | 0.496419613 | |

Sulfate: ANOVA & t-Tests

Anova: Single Factor

SUMMARY

| Groups | Count | Sum | Average | Variance |
|--------|-------|-------|----------|-------------|
| OMW-1 | 24 | 11055 | 460.625 | 29996.07065 |
| OMW-5 | 24 | 46680 | 1945 | 7130.434783 |
| OMW-7 | 24 | 26589 | 1107.875 | 34956.46196 |
| OMW-8 | 24 | 40880 | 1703.333 | 16875.36232 |

ANOVA

| Source of Variation | SS | df | MS | F | P-value | F crit |
|---------------------|-------------|----|----------|-------------|-------------|----------|
| Between Groups | 31682264.25 | 3 | 10560755 | 474.8629964 | 7.73347E-56 | 2.703594 |
| Within Groups | 2046041.583 | 92 | 22239.58 | | | |
| Total | 33728305.83 | 95 | | | | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-1 | OMW-5 |
|------------------------------|-------------|-----------|
| Mean | 460.625 | 1945 |
| Variance | 29996.07065 | 7130.4348 |
| Observations | 24 | 24 |
| Pooled Variance | 18563.25272 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -37.7404623 | |
| P(T<=t) one-tail | 1.46753E-36 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 2.93505E-36 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-1 | OMW-5 |
|------------------------------|-------------|---------|
| Mean | 460.6 | 1,945.0 |
| Variance | 29,996.1 | 7,130.4 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 33 | |
| t Stat | -37.7404623 | |
| P(T<=t) one-tail | 5.00914E-29 | |
| t Critical one-tail | 1.692360309 | |
| P(T<=t) two-tail | 1.00183E-28 | |
| t Critical two-tail | 2.034515297 | |

F-Test Two-Sample for Variances

| | OMW-1 | OMW-5 |
|---------------------|-------------|-----------|
| Mean | 460.625 | 1945 |
| Variance | 29996.07065 | 7130.4348 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 4.206766006 | |
| P(F<=f) one-tail | 0.000523374 | |
| F Critical one-tail | 2.014424842 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-7 | OMW-5 |
|------------------------------|--------------|-----------|
| Mean | 1107.875 | 1945 |
| Variance | 34956.46196 | 7130.4348 |
| Observations | 24 | 24 |
| Pooled Variance | 21043.44837 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -19.99044586 | |
| P(T<=t) one-tail | 1.27963E-24 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 2.55925E-24 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-7 | OMW-5 |
|------------------------------|--------------|---------|
| Mean | 1,107.9 | 1,945.0 |
| Variance | 34,956.5 | 7,130.4 |
| Observations | 24 | 24 |
| Hypothesized Mean Difference | 0 | |
| df | 32 | |
| t Stat | -19.99044586 | |
| P(T<=t) one-tail | 6.0459E-20 | |
| t Critical one-tail | 1.693888748 | |
| P(T<=t) two-tail | 1.20918E-19 | |
| t Critical two-tail | 2.036933343 | |

F-Test Two-Sample for Variances

| | OMW-7 | OMW-5 |
|---------------------|-------------|-----------|
| Mean | 1107.875 | 1945 |
| Variance | 34956.46196 | 7130.4348 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 4.90243064 | |
| P(F<=f) one-tail | 0.000160158 | |
| F Critical one-tail | 2.014424842 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-8 | OMW-5 |
|------------------------------|--------------|-----------|
| Mean | 1703.333333 | 1945 |
| Variance | 16875.36232 | 7130.4348 |
| Observations | 24 | 24 |
| Pooled Variance | 12002.89855 | |
| Hypothesized Mean Difference | 0 | |
| df | 46 | |
| t Stat | -7.641248212 | |
| P(T<=t) one-tail | 5.02189E-10 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 1.00438E-09 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-8 | OMW-5 |
|------------------------------|--------------|---------|
| Mean | 1,703.3 | 1,945.0 |
| Variance | 16,875.4 | 7,130.4 |
| Observations | 24.0 | 24.0 |
| Hypothesized Mean Difference | 0 | |
| df | 39 | |
| t Stat | -7.641248212 | |
| P(T<=t) one-tail | 1.43452E-09 | |
| t Critical one-tail | 1.684875122 | |
| P(T<=t) two-tail | 2.86905E-09 | |
| t Critical two-tail | 2.02269092 | |

F-Test Two-Sample for Variances

| | OMW-8 | OMW-5 |
|---------------------|-------------|-----------|
| Mean | 1703.333333 | 1945 |
| Variance | 16875.36232 | 7130.4348 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 2.366666667 | |
| P(F<=f) one-tail | 0.022034581 | |
| F Critical one-tail | 2.014424842 | |

TDS: ANOVA & t-Tests

Anova: Single Factor

SUMMARY

| Groups | Count | Sum | Average | Variance |
|--------|-------|--------|-----------|-------------|
| OMW-1 | 24 | 29795 | 1241.4583 | 96693.12862 |
| OMW-5 | 24 | 101000 | 4208.3333 | 16918.84058 |
| OMW-7 | 24 | 52940 | 2205.8333 | 94529.71014 |
| OMW-8 | 24 | 73080 | 3045 | 40391.30435 |

ANOVA

| Source of Variation | SS | df | MS | F | P-value | F crit |
|---------------------|-------------|----|-----------|-------------|------------|------------|
| Between Groups | 114316082 | 3 | 38105361 | 613.2845647 | 1.1387E-60 | 2.70359404 |
| Within Groups | 5716258.625 | 92 | 62133.246 | | | |
| Total | 120032340.7 | 95 | | | | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-1 | OMW-5 |
|------------------------|-------------|----------|
| Mean | 1241.458333 | 4208.333 |
| Variance | 96693.12862 | 16918.84 |
| Observations | 24 | 24 |
| Pooled Variance | 56805.9846 | |
| Hypothesized Mean Diff | 0 | |
| df | 46 | |
| t Stat | -43.1213974 | |
| P(T<=t) one-tail | 3.76456E-39 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 7.52913E-39 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-1 | OMW-5 |
|------------------------|-------------|----------|
| Mean | 1241.458333 | 4208.333 |
| Variance | 96693.12862 | 16918.84 |
| Observations | 24 | 24 |
| Hypothesized Mean Diff | 0 | |
| df | 31 | |
| t Stat | -43.1213974 | |
| P(T<=t) one-tail | 1.52907E-29 | |
| t Critical one-tail | 1.695518783 | |
| P(T<=t) two-tail | 3.05814E-29 | |
| t Critical two-tail | 2.039513446 | |

F-Test Two-Sample for Variances

| | OMW-1 | OMW-5 |
|---------------------|-------------|----------|
| Mean | 1241.458333 | 4208.333 |
| Variance | 96693.12862 | 16918.84 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 5.715115535 | |
| P(F<=f) one-tail | 4.56784E-05 | |
| F Critical one-tail | 2.014424842 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-7 | OMW-5 |
|------------------------|--------------|---------|
| Mean | 2205.8 | 4208.3 |
| Variance | 94529.7 | 16918.8 |
| Observations | 24 | 24 |
| Pooled Variance | 55724.27536 | |
| Hypothesized Mean Diff | 0 | |
| df | 46 | |
| t Stat | -29.38603104 | |
| P(T<=t) one-tail | 9.3004E-32 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 1.86008E-31 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-7 | OMW-5 |
|------------------------|--------------|------------|
| Mean | 2205.833333 | 4208.33333 |
| Variance | 94529.71014 | 16918.8406 |
| Observations | 24 | 24 |
| Hypothesized Mean Diff | 0 | |
| df | 31 | |
| t Stat | -29.38603104 | |
| P(T<=t) one-tail | 1.67971E-24 | |
| t Critical one-tail | 1.695518783 | |
| P(T<=t) two-tail | 3.35941E-24 | |
| t Critical two-tail | 2.039513446 | |

F-Test Two-Sample for Variances

| | OMW-7 | OMW-5 |
|---------------------|-------------|------------|
| Mean | 2205.833333 | 4208.33333 |
| Variance | 94529.71014 | 16918.8406 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 5.58724516 | |
| P(F<=f) one-tail | 5.51864E-05 | |
| F Critical one-tail | 2.014424842 | |

t-Test: Two-Sample Assuming Equal Variances

| | OMW-8 | OMW-5 |
|------------------------|--------------|---------|
| Mean | 3045.0 | 4208.3 |
| Variance | 40391.3 | 16918.8 |
| Observations | 24 | 24 |
| Pooled Variance | 28655.07246 | |
| Hypothesized Mean Diff | 0 | |
| df | 46 | |
| t Stat | -23.80641717 | |
| P(T<=t) one-tail | 8.30563E-28 | |
| t Critical one-tail | 1.678660414 | |
| P(T<=t) two-tail | 1.66113E-27 | |
| t Critical two-tail | 2.012895599 | |

t-Test: Two-Sample Assuming Unequal Variances

| | OMW-8 | OMW-5 |
|------------------------|--------------|------------|
| Mean | 3045 | 4208.33333 |
| Variance | 40391.30435 | 16918.8406 |
| Observations | 24 | 24 |
| Hypothesized Mean Diff | 0 | |
| df | 39 | |
| t Stat | -23.80641717 | |
| P(T<=t) one-tail | 3.86741E-25 | |
| t Critical one-tail | 1.684875122 | |
| P(T<=t) two-tail | 7.73482E-25 | |
| t Critical two-tail | 2.02269092 | |

F-Test Two-Sample for Variances

| | OMW-8 | OMW-5 |
|---------------------|-------------|------------|
| Mean | 3045 | 4208.33333 |
| Variance | 40391.30435 | 16918.8406 |
| Observations | 24 | 24 |
| df | 23 | 23 |
| F | 2.387356519 | |
| P(F<=f) one-tail | 0.021016932 | |
| F Critical one-tail | 2.014424842 | |

Appendix D

Analysis of Variance for Groundwater Data:

Kruskal-Wallis (Nonparametric) ANOVA & Q-Test Results

Calendar Years 2017 through 2023

The Kruskal-Wallis test is effectively a non-parametric alternative to the one-way F-test (ANOVA) for comparing multiple groups (wells) simultaneously. ANOVA testing's null hypothesis is that the data all come from the same underlying population (i.e., the means are the same among all the tested wells). In this case, this method looks for a difference in the average population ranks equivalent to the medians. Perhaps more importantly, the Kruskal-Wallis test does not require the underlying population to be normally distributed.

A review of the pH and fluoride data indicates the underlying population may not be normal. That is not to say that the typical parametric ANOVA and t-test might not yield a usable result. In fact, such testing was conducted and reported in this document in order that the investigation be thorough. Nonetheless, it was deemed cautionary to expand the analysis for these constituents by conducting a non-parametric analysis using the Kruskal-Wallis test.

The following pages provide the raw output from the statistical analyses themselves for each and every combination of wells for pH and fluoride.

Boron: Kruskal-Wallis ANOVA & Q-Test

Kruskal-Wallis Test

| | OMW-1 | OMW-5 | OMW-7 | OMW-8 | |
|----------|-------------|--------|----------|-------|-------------|
| median | 0.09 | 0.95 | 0.12 | | 0.20 |
| rank sum | 424 | 2028 | 754.5 | | 1449.5 |
| count | 24 | 24 | 24 | | 96 |
| r^2/n | 7490.666667 | 171366 | 23719.59 | | 87543.76042 |
| H-stat | | | | | 290120.0208 |
| H-ties | | | | | 82.86600623 |
| df | | | | | 83.04624768 |
| p-value | | | | | 3 |
| alpha | | | | | 6.81514E-18 |
| sig | | | | | 0.05 |
| | | | | | yes |

| TUKEY HSD/KRAMER | | alpha | | 0.05 | |
|------------------|----------|-------|----------|------|-------------|
| group | mean | n | ss | df | q-crit |
| OMW-1 | 0.08 | 24 | 0.014216 | | |
| OMW-5 | 0.93 | 24 | 0.069533 | | |
| OMW-7 | 0.108125 | 24 | 0.033541 | | |
| OMW-8 | 0.1975 | 24 | 0.01465 | | |
| | | 96 | 0.13194 | 92 | 3.700826087 |

| Q TEST | | | | | | | | | | |
|---------|---------|----------|---------|-------------|-------------|----------|----------|-------------|-------------|--|
| group 1 | group 2 | mean | std err | q-stat | lower | upper | p-value | mean-crit | Cohen d | |
| OMW-1 | OMW-5 | 0.853958 | 0.00773 | 110.4710956 | 0.825350386 | 0.882566 | 3.49E-13 | 0.028607947 | 22.54981797 | |
| OMW-1 | OMW-7 | 0.02875 | 0.00773 | 3.719202537 | 0.000142053 | 0.057358 | 0.048363 | 0.028607947 | 0.759179039 | |
| OMW-1 | OMW-8 | 0.118125 | 0.00773 | 15.28107129 | 0.089517053 | 0.146733 | 3.49E-13 | 0.028607947 | 3.119235616 | |
| OMW-5 | OMW-7 | 0.825208 | 0.00773 | 106.7518931 | 0.796600386 | 0.853816 | 3.49E-13 | 0.028607947 | 21.79063893 | |
| OMW-5 | OMW-8 | 0.735833 | 0.00773 | 95.19002436 | 0.707225386 | 0.764441 | 3.49E-13 | 0.028607947 | 19.43058236 | |
| OMW-7 | OMW-8 | 0.089375 | 0.00773 | 11.56186876 | 0.060767053 | 0.117983 | 9.65E-12 | 0.028607947 | 2.360056577 | |

Fluoride: Kruskal-Wallis ANOVA & Q-Test

Kruskal-Wallis Test

| | | | | | |
|----------|-------------|----------|----------|-------------|-------------|
| | OMW-1 | OMW-5 | OMW-7 | OMW-8 | |
| median | 0.4 | 0.6 | 0.4 | 0.4 | |
| rank sum | 1079.5 | 1925.5 | 711.5 | 939.5 | |
| count | 24 | 24 | 24 | 24 | 96 |
| r^2/n | 48555.01042 | 154481.3 | 21093.01 | 36777.51042 | 260906.7917 |
| H-stat | | | | | 45.22009235 |
| H-ties | | | | | 53.5715754 |
| df | | | | | 3 |
| p-value | | | | | 1.38477E-11 |
| alpha | | | | | 0.05 |
| sig | | | | | yes |

TUKEY HSD/KRAMER alpha 0.05

| group | mean | n | ss | df | q-crit |
|-------|-------------|----|----------|----|-------------|
| OMW-1 | 0.445833333 | 24 | 0.359583 | | |
| OMW-5 | 0.595833333 | 24 | 0.089583 | | |
| OMW-7 | 0.395833333 | 24 | 0.029583 | | |
| OMW-8 | 0.425 | 24 | 0.065 | | |
| | | 96 | 0.54375 | 92 | 3.700826087 |

Q TEST

| group 1 | group 2 | mean | std err | q-stat | lower | upper | p-value | mean-crit | Cohen d |
|---------|---------|----------|----------|-------------|--------------|----------|----------|-------------|-------------|
| OMW-1 | OMW-5 | 0.15 | 0.015693 | 9.558531124 | 0.091923722 | 0.208076 | 7.45E-09 | 0.058076278 | 1.951126995 |
| OMW-1 | OMW-7 | 0.05 | 0.015693 | 3.186177041 | -0.008076278 | 0.108076 | 0.11691 | 0.058076278 | 0.650375665 |
| OMW-1 | OMW-8 | 0.020833 | 0.015693 | 1.327573767 | -0.037242945 | 0.07891 | 0.7841 | 0.058076278 | 0.27098986 |
| OMW-5 | OMW-7 | 0.2 | 0.015693 | 12.74470816 | 0.141923722 | 0.258076 | 5.13E-13 | 0.058076278 | 2.60150266 |
| OMW-5 | OMW-8 | 0.170833 | 0.015693 | 10.88610489 | 0.112757055 | 0.22891 | 9.17E-11 | 0.058076278 | 2.22116856 |
| OMW-7 | OMW-8 | 0.029167 | 0.015693 | 1.858603274 | -0.028909612 | 0.087243 | 0.556308 | 0.058076278 | 0.379385805 |

pH: Kruskal-Wallis ANOVA & Q-Test

Kruskal-Wallis Test

| | | | | | |
|-------------------|-----------|----------|----------|-----------|-------------|
| | OMW-1 | OMW-5 | OMW-7 | OMW-8 | |
| median | 7.5 | 7.6 | 7.3 | 7.4 | |
| rank sum | 1227 | 1948.5 | 511.5 | 969 | |
| count | 24 | 24 | 24 | 24 | 96 |
| r ² /n | 62730.375 | 158193.8 | 10901.34 | 39123.375 | 270948.9375 |
| H-stat | | | | | 58.16100193 |
| H-ties | | | | | 61.16359342 |
| df | | | | | 3 |
| p-value | | | | | 3.316E-13 |
| alpha | | | | | 0.05 |
| sig | | | | | yes |

TUKEY HSD/KRAMER

| | | | | | alpha | 0.05 |
|-------|-------------|----|----------|----|-------------|------|
| group | mean | n | ss | df | q-crit | |
| OMW-1 | 7.4875 | 24 | 0.18625 | | | |
| OMW-5 | 7.658333333 | 24 | 0.318333 | | | |
| OMW-7 | 7.341666667 | 24 | 0.238333 | | | |
| OMW-8 | 7.4 | 24 | 0.11625 | | | |
| | | 96 | 0.859167 | 92 | 3.700826087 | |

Q TEST

| group 1 | group 2 | mean | std err | q-stat | lower | upper | p-value | mean-crit | Cohen d |
|---------|---------|----------|----------|-------------|-------------|----------|----------|------------|-------------|
| OMW-1 | OMW-5 | 0.170833 | 0.019726 | 8.660310037 | 0.097830813 | 0.243836 | 1.33E-07 | 0.07300252 | 1.767778384 |
| OMW-1 | OMW-7 | 0.145833 | 0.019726 | 7.392947592 | 0.072830813 | 0.218836 | 6.32E-06 | 0.07300252 | 1.509079108 |
| OMW-1 | OMW-8 | 0.05 | 0.019726 | 2.534724889 | -0.02300252 | 0.123003 | 0.283608 | 0.07300252 | 0.517398551 |
| OMW-5 | OMW-7 | 0.316667 | 0.019726 | 16.05325763 | 0.243664147 | 0.389669 | 3.49E-13 | 0.07300252 | 3.276857492 |
| OMW-5 | OMW-8 | 0.220833 | 0.019726 | 11.19503493 | 0.147830813 | 0.293836 | 3.26E-11 | 0.07300252 | 2.285176935 |
| OMW-7 | OMW-8 | 0.095833 | 0.019726 | 4.858222704 | 0.022830813 | 0.168836 | 0.004852 | 0.07300252 | 0.991680557 |