

ADDENDUM NO. 6

Project: Transit Facility Renovation – Floors 1 & 2

This Addendum forms a part of the Contract Documents and modifies the original Bid Documents as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Proposal. All other terms and conditions of the Contract Documents remain unchanged.

Bidder Question No. 94

Question:

Plan A0.2 lists a Material Schedule; however, Material Part Numbers/Model Numbers were not provided. Please revise the Material Schedule with the required Material Information (Part Numbers/Model Numbers) completely for fair bidding purposes among the bidders.

Response:

See **Attachment A – Material Schedule**.

Bidder Question No. 96

Question:

Plan A0.2 lists the Specialty Equipment Schedule as Contractor Furnished Contractor Installed (CFCI); however, Material Part Numbers/Model Numbers were not provided for SP-1 through SP-6 with the notes indicating "Specification by Owner." Please provide the product specifications (Brand Name and Model Number) completely for fair bidding purposes among the bidders.

Response:

See **Attachment B – Specialty Equipment Schedule**.

Attachments

- **Attachment A – Material Schedule**
- **Attachment B – Specialty Equipment Schedule**

See attached Material Schedule

MATERIAL SCHEDULE				
MARK	MATERIAL	MANUFACTURER	MODEL	COMMENTS
CONC	CONCRETE AND STAIN	PER SPEC	DARK GRAY - ARCHITECT TO APPROVE	AT FLOORS. PROVIDE SAMPLE FOR APPROVAL BEFORE APPLICATION. IN WET AREAS PROVIDE ANTISLIP FINISH WHERE APPLICABLE
CT-1	CARPET TILES - FIELD	SHAW CARPET	MODEL PER CLIENT	COLOR PER CLIENT. PROVIDE ALL REQUIRED UNDERLAYMENT AND TRIMS FOR COMPLETE INSTALLATION
GL-1	GLAZING	-	SEE SPEC	STOREFRONTS AND WINDOWS
ML-1	MULLIONS	PER SPEC	SEE SPEC	STOREFRONTS AND WINDOWS
PL-1	LAMINATE	WILSONART - HPL TEXTURE MATTE FINISH	WALNUT WOOD LOOK - ARCHITECT TO SELECT	CASEWORK AND VANITIES
PL-2	LAMINATE	WILSONART - HPL MATTE FINISH	DARK GREY COLOR - ARCHITECT TO SELECT	HALLWAY STORAGE CABINETS
PT-1	PAINT - INTERIOR	SHERWIN WILLIAMS	TO MATCH EXISTING - ARCHITECT TO SELECT	SATIN FINISH UON. SEMIGLOSS FINISH AT RESTROOMS, KITCHEN FLAT FINISH AT WAREHOUSE CEILING, AND BREAKROOM CEILINGS. COLOR PER CLIENT - CONTRACTOR TO COORDINATE PRIOR TO SUBMITTAL
PT-1A	PAINT - INTERIOR ACCENT	SHERWIN WILLIAMS	SUBMIT FOR APPROVAL	SATIN FINISH UON. SEMIGLOSS FINISH AT RESTROOMS, KITCHEN FLAT FINISH AT WAREHOUSE CEILING, AND BREAKROOM CEILINGS. COLOR PER CLIENT - CONTRACTOR TO COORDINATE PRIOR TO SUBMITTAL
PT-2	PAINT - EXTERIOR	SHERWIN WILLIAMS	TO MATCH EXISTING - SUBMIT FOR APPROVAL	EXTERIOR GRADE WEATHER PROOF AND MARINE GRADE COLOR PER CLIENT - CONTRACTOR TO COORDINATE PRIOR TO SUBMITTAL
PT-2A	PAINT - EXTERIOR ACCENT	SHERWIN WILLIAMS	SUBMIT FOR APPROVAL	EXTERIOR GRADE WEATHER PROOF AND MARINE GRADE COLOR PER CLIENT - CONTRACTOR TO COORDINATE PRIOR TO SUBMITTAL
PT-5	PAINT - DOOR FRAME	SHERWIN WILLIAMS	TO MATCH EXISTING - SUBMIT	SATIN FINISH
PT-6	PAINT - INTERIOR DOOR	SHERWIN WILLIAMS	TO MATCH EXISTING - ARCHITECT TO SELECT	SATIN FINISH AT INTERIOR DOORS - HOLLOW METAL
SGL-1	SPANDREL GLASS PANEL	SEE SPEC	SEE SPEC	AT NEW EXTERIOR STOREFRONT SYSTEM TO MAINTAIN FIRE VALVE
SS-1	SOLID SURFACE	WILSONART - CORIAN	MORNING ICE OR EQUAL - ARCHITECT TO SELECT	CONTERTOPS AT RESTROOM AND KITCHENETTE
TL-1	PORCELAIN FLOOR TILE	DALTILE - 12X24	NEOSPECK OR EQUAL ARCHITECT TO SELECT	AT INTERIOR RESTROOMS. GROUT JOINT TO BE 1/8"MIN GROUT: TBD
TL-2	PORCELAIN WALL TILE	DALTILE - 12X24	ARTICULO OR EQUAL ARCHITECT TO SELECT	AT INTERIOR RESTROOMS GROUT JOINT TO BE 1/8"MIN GROUT: TBD
TL-3	PORCELAIN WALL TILE	DALTILE - 3D WAVE MULTITUDE	OR EQUAL ARCHITECT TO SELECT COLOR	AT KITCHENETTE. GROUT JOINT TO BE 1/8"MIN GROUT: TBD
WB-1	WALL BASE	ALLSTATE RUBBER	4" TALL	TO MATCH CONCRETE
WB-2	WALL BASE	ALLSTATE RUBBER	4" TALL	TO MATCH CARPET
WC-1	(E) WALL CLADDING	SHERWIN WILLIAMS	SUBMIT FOR APPROVAL	EXTERIOR GRADE WEATHER PROOF AND MARINE GRADE COLOR PER CLIENT - CONTRACTOR TO COORDINATE PRIOR TO SUBMITTAL. FIRST FLOOR EXTERIOR ELEVATOR FACADE TO BE PAINTED (PT-1A). SECOND FLOOR ELEVATOR FACADE TO BE PAINTED(PT-2A)
WC-2	(N) WALL CALDDING	TO MATCH EXISTING	SEE SPEC	2"MIN ALUMINUM HORIZONTAL WALL CLADDING. PROVIDE ALL REQUIRED BRACING AND TRIMS FOR COMPLETE INSTALLATION. TO MATCH EXISTING SUBMIT FOR APPROVAL COORDINATE WITH CLIENT

See Below Specialty Equipment Schedule

SPECIALTY EQUIPMENT SCHEDULE

Mark	EQUIPMENT	SPECIFICATION	PURCHASED/INSTALLED BY	Comments
SP-1	70" LARGE TV DISPLAY	BY OWNER	CONTRACTOR	CONTRACTOR TO SUPPLY RECESSED WALL BOX FOR POWER AND DATA. CONTRACTOR TO SUPPLY POWER AND DATA. FIRST FLOOR DISPATCH BREAKROOM
SP-2A	30" REFRIGERATOR	BY OWNER	CONTRACTOR	TO INCLUDE WATER LINE FOR ICE MAKER OUTSIDE. PROVIDE PROPER POWER. FIRST FLOOR DISPATCH KITCHENETTE
SP-2B	30" REFRIGERATOR	BY OWNER	CONTRACTOR	TO INCLUDE WATER LINE FOR ICE MAKER. PROVIDE PROPER POWER. SECOND FLOOR KITCHEN
SP-3	GARBAGE DISPOSAL	CONTRACTOR	CONTRACTOR	CONTRACTOR TO SUPPLY POWER. GARBAGE DISPOSAL TO MEET ADA APPROACH CLEARANCES. INSINKERATOR ADGER SERIES BADGER 5XP OR EQUAL FIRST FLOOR KITCHENETTE AND SECOND FLOOR KITCHEN
SP-4	18X12 MICROWAVE	BY OWNER	CONTRACTOR	CONTRACTOR TO SUPPLY POWER. FIRST FLOOR KITCHENETTE AND SECOND FLOOR KITCHEN
SP-5	50" SMALL TV DISPLAY	BY OWNER	CONTRACTOR	CONTRACTOR TO SUPPLY RECESSED WALL BOX FOR POWER AND DATA. CONTRACTOR TO SUPPLY POWER AND DATA. SECOND FLOOR ELEVATOR LANDING
SP-6	LOCKERS	CONTRACTOR	CONTRACTOR	5% OF LOCKERS TO COMPLY WITH ACCESSIBILITY CODE.
SP-7	MAILBOXES	RETAINED	CONTRACTOR	CONTRACTOR TO REINSTALL MAILBOXES IN NEW LOCATION