



MRF Contracting



MRF Plant Hire



Temporary Access for drilling rig

Mrf Contracting were instructed to provide access for a drilling to complete the drilling of a new water main.

Restrictions;

- ~The works were being undertaken in October
- ~The ground was already saturated and not load bearing
- ~Vegetation blocked certain areas of access
- ~HGV tankers were required for vacuum tanking
- ~Reptiles were known to be present on site
- ~Livestock was to be left grazing fields

MRF Solution;

- ~Mobilise in-house vegetation clearance teams to remove shrubs / trees
- ~Mobilise in house fencing teams to install reptile drift fencing
- ~ Mobilise in-house fencing teams to install stock fencing (2,000m)
- ~ Mobilise in house plant operators to strip and lay 550M of temporary boards (provided by MRF Plant hire)
- ~ Mobilise in house teams to lay terras and create compounds for contractors plant.

2 weeks to install site
 2 weeks to demob site
 - reseed and return to
 land owner

MRF Contracting

Office: 01843 843447

Emergency: 0788 5914294

Email:

office@mrfcontracting.com