



**LOS VAQUEROS RESERVOIR JOINT POWERS AUTHORITY  
OPERATIONS AND ENGINEERING COMMITTEE**

**AGENDA**

Regular Meeting

June 15, 2023 – 10:00 a.m.

Directors participating telephonically:

Jose Gutierrez - 3130 North Fresno Street, Fresno, California 93703

Steve Ritchie - 525 Golden Gate Avenue, San Francisco, CA 94102

Jonathan Wunderlich - 43885 S. Grimmer Blvd., Fremont, California 94538

---

---

This meeting will be conducted remotely and any member of the public who desires to participate in the open session items of this meeting may do so by accessing the Zoom link below without otherwise complying with the Brown Act's teleconference requirements.

**Please click the link below to join the Meeting/Webinar:**

**<https://lagerlof.zoom.us/j/83227564437?pwd=SnBST0lHQXdkbm8rNEp0ODB0NjN0dz09>**

**Webinar ID: 832 2756 4437**

**Passcode: 567930**

**Or One tap mobile:**

**US: +16699006833,,83227564437#,,,\*567930#**

**or Telephone: +1-669-900-6833**

Any member of the public wishing to make any comments to the Committee may do so by accessing the above-referenced link where they may select the option to join via webcam or teleconference. Members of the public may also submit written comments to the Clerk by 4:00 p.m. on the day prior to the meeting for the Clerk to read into the record (subject to three-minute limitation). The meeting Chair will acknowledge such individual(s) at the appropriate time in the meeting prior to making their comment. Members of the public will be disconnected from the meeting prior to any Closed Session, if applicable.

NOTE: *To comply with the Americans with Disabilities Act, if you need special assistance to participate in this Committee meeting, please contact the Authority's Interim Clerk at [rperea@lagerlof.com](mailto:rperea@lagerlof.com) by 4:00 p.m. on June 14, 2023 to inform the Authority of your needs and to determine if accommodation is feasible. Each item on the Agenda shall be deemed to include any appropriate motion, resolution, or ordinance, to take action on any item. Materials related to items on this Agenda are available for public review at: [www.losvaquerosjpa.com/board-meetings](http://www.losvaquerosjpa.com/board-meetings).*

## **CALL TO ORDER**

## **PLEDGE OF ALLEGIANCE**

## **ROLL CALL OF COMMITTEE MEMBERS**

Jose Gutierrez – Chair, San Luis & Delta-Mendota Water Authority

Jonathan Wunderlich – Alameda County Water District

Antonio Martinez – Contra Costa Water District

Steve Ritchie – San Francisco Public Utilities Commission

## **PUBLIC COMMENT ON NON-AGENDA ITEMS**

*Any member of the public wishing to address the Operations and Engineering Committee regarding items not on the Agenda should do so at this time. The Committee welcomes your comments and requests that speakers present their remarks within established time limits and on issues that directly affect the Authority or are within the jurisdiction of the Authority.*

## **DISCUSSION ITEMS**

- 1.1 March 16, 2023 Operations and Engineering Committee Meeting Summary**
- 1.2 Update on Pumping Plant No. 1 Replacement Design**
- 1.3 Update on Transfer-Bethany Pipeline**

## **FUTURE AGENDA ITEMS**

## **ADJOURNMENT**

**ITEM 1.1: MARCH 16, 2023 OPERATIONS AND ENGINEERING COMMITTEE MEETING SUMMARY**

**RESPONSIBLE/LEAD STAFF MEMBER:**

James Ciampa, General Counsel

**DISCUSSION:**

Attached for the Committee's information is the summary prepared for the March 16, 2023 Operations and Engineering Committee meeting.

**ALTERNATIVES:**

Any suggested revisions to the attached summary will be considered.

**FISCAL ANALYSIS:**

Not applicable.

**ENVIRONMENTAL REQUIREMENTS:**

Not applicable.

**EXHIBITS/ATTACHMENTS:**

Summary from March 16, 2023 Operations and Engineering Committee meeting



## **SUMMARY OF REGULAR MEETING OF OPERATIONS AND ENGINEERING COMMITTEE**

March 16, 2023 – 10:00 a.m.

---

---

Chair Jose Gutierrez and Committee Members Jonathan Wunderlich, Antonio Martinez and Steve Ritchie participated telephonically. Staff and nine others also participated. The meeting was called to order at 10:00 a.m.

### **1.1 February 16, 2023 Operations and Engineering Committee Meeting Summary.**

The summary from the February 16, 2023 Operations and Engineering Committee meeting was presented. The draft summary was accepted with no revisions and will be included in the next Board meeting packet.

### **1.2 Review of Transfer Pipeline Inspection Results.**

Taryn Ravazzini, Executive Director, introduced Bryan Perkins, CCWD Senior Engineer, who reviewed the results from the recent inspection of the Transfer Pipeline (TPL). The existing TPL is used to fill and draw water from the Los Vaqueros Reservoir (Reservoir). The TPL will continue to be relied upon following construction of the expanded Reservoir, and it will be operated under higher pressure with the increased Reservoir water level. CCWD conducted an inspection of the TPL to determine whether the TPL has sufficient pressure capacity to reliably operate under the future higher-pressure condition and to verify its current condition. Mr. Perkins reported the inspection report concluded the TPL is in good condition, with no major deficiencies or signs of corrosion and no major repairs needed.

Committee Member Steve Ritchie asked whether the high pressure expected from the Reservoir expansion was considered when the pipeline was first designed and constructed. Chris Hentz, CCWD Engineering Manager for the Los Vaqueros Reservoir Expansion Project, advised the TPL was not specifically designed for that increased pressure, but was designed very conservatively with excess strength to meet and exceed all American Water Works Association (AWWA) standards. He further stated the TPL's steel has been confirmed through testing to meet those AWWA requirements for safety and surge protection.

Committee member Antonio Martinez asked how future construction of the Project would affect the life of the TPL. Mr. Hentz advised that increased cathodic protection has been recommended to extend the TPL's useful life. Chair Jose Gutierrez inquired as to any costs that were assumed for rehabilitation of the TPL that were included in the budget that could now be removed. Mr. Hentz stated that such rehabilitation costs were not included in the budget for the

inspection report project, but that any additional costs for minor improvements are well within the contingency budget for the inspection project.

Executive Director Ravazzini thanked CCWD staff for the presentation and their continuing work on the Project. She also thanked members of the committee for their questions. She asked CCWD staff to elaborate on the coordination with East Bay MUD regarding supplying water to CCWD while the TPL was out of service. Mr. Hentz advised that coordination occurred under the existing CCWD-EBMUD intertie agreement and all went very well. Marguerite Patil added the inspection report project came in on schedule and under budget.

**FUTURE AGENDA ITEMS:**

None.

Executive Director Ravazzini advised she will work with the Committee to determine whether there are any matters that are time sensitive which would require an April meeting.

The meeting was adjourned at 10:34 a.m.

*James D. Ciampa*

---

James D. Ciampa  
General Counsel

**ITEM 1.2: UPDATE ON PUMPING PLANT NO. 1 REPLACEMENT DESIGN**

**RESPONSIBLE/LEAD STAFF MEMBER:**

Taryn Ravazzini, Executive Director

**DISCUSSION:**

Pumping Plant No. 1 has a current capacity of 100 cubic feet per second (cfs). The capacity of that pumping plant must be increased to 350 cfs in order to deliver contemplated supplies to the Authority members through the Neroly High Lift Pump Station, as well as to meet reliability needs when the Los Vaqueros Reservoir is taken out of service.

Stan Ali of Contra Costa Water District staff and Bryan Perkins, Senior Engineer on CCWD's Los Vaqueros Project team, will review the current status of the design of the replacement facility for Pumping Plant No. 1, including reviewing the results of the geotechnical investigation completed in July 2022 and the results from the physical model of the Pumping Plant No. 1 replacement. They will also review the anticipated construction schedule and the related design coordination agreements that are needed.

**ALTERNATIVES:**

For information only

**FISCAL ANALYSIS:**

Not applicable

**ENVIRONMENTAL REQUIREMENTS:**

Not applicable

**EXHIBITS/ATTACHMENTS:**

Slide deck regarding Pumping Plant No. 1 Replacement Design



**LOS  
VAQUEROS  
RESERVOIR  
EXPANSION  
PROJECT**

**Operations & Engineering  
Committee Meeting**

**Update on Pumping Plant No. 1 Replacement Project**

**June 15, 2023**

# Objective and Messages

## Objective


- Provide an update on the PP1 Replacement Project

## Messages:


- CCWD completed a geotechnical investigation and is addressing findings in the design
- Procurement of some equipment impacted by supply chain delays, will likely extend the construction schedule
- Timing of bidding reflects the latest plan for CWC Full Funding Award



# LVE Facilities



# PP1 Location



# Background

- The RS Intake, built in 1936, is one of four intakes used by the District to divert Delta supplies
- Originally designed and permitted for 350 cubic feet per second (cfs), PP1 capacity is currently 100 (cfs)
  - Reduced by Canal Replacement Project (CRP)
  - CRP identified modifications in 2009 to increase capacity when needed and financially justified
  - Explored feasibility to replace pumps to incrementally increase capacity if needed
  - If not for LVE, PP1 modifications would not be funded in CCWD's 10-year CIP

# Background

- The scope and timing of PP1 Replacement is defined by LVE Project needs
- Replacing PP1 to achieve capacity of 350 cfs is needed to:
  - Deliver up to 300 cfs to partners through the Neroly High Lift Pump Station
  - Meet reliability needs during the Dam outage, avoiding a single point of failure for District operations

# Geotechnical Investigation Findings

- Geotechnical investigation completed in July 2022
- Supports structural design, informs construction techniques, dewatering requirements, and cost estimates
- Significant potential for liquefaction from sandy soil layers and high groundwater
- District is evaluating options to avoid damage from settlement during a major earthquake

# PP1 Physical Model

- Physical models are recommended by the Hydraulic Institute for high-flow pump stations
  - Reliable method to identify flow instabilities
  - Identify modifications and confirm adjustments at model scale
  - Reduce the risk of high-cost issues if found late in design or after construction
- A physical model of the PP1 Replacement was constructed in August 2022 and completed in November 2022
- Results peer reviewed by Stantec

# Physical Model

- Verified intake hydraulics
- Tested under a wide variety of scenarios to validate performance



# Physical Modeling Results

- Confirmed suction side hydraulics of the project
- Minor recommended design enhancements
  - Install floor-sidewall fillet and floor cone
  - Install vanes within the pump suction can that are equally spaced
  - Relocate overflow return pipe downstream
- Pipe sizing and revised pump layout meets ANSI/HI-9.8 pump intake design standard for the full range of expected operations



# PP1 Vegetation Screening

- Existing PP1 vegetation screen and rakes protect the pump from aquatic vegetation
- Vegetation will continue to present risks to pumps from the remaining 2-acre open water near RSFS
- Existing screens will be replaced with an upstream screen facility to protect the pumps
- District is conducting a design review to confirm the screen is the most cost-effective approach

# 60% Design Value Engineering (VE)

- District conducts design reviews and VE to identify potential cost-saving concepts for further evaluation
- Alternative concepts are identified for further evaluation to:
  - Confirm design intent is maintained
  - Cost savings are realized after additional analysis and estimating
- Reclamation required a formal VE Study of the 30% design
  - VE Study identified 5 concepts for consideration
- District requested GEI to review the 60% Design
  - GEI identified 9 concepts for consideration

# VE Concept Evaluation

- District analyzed but did not adopt 4 of Reclamation's VE; they didn't meet the design objectives and offer savings:
  - Use of Archimedes' screw pumps; re-use 1930's era building for new motor control center; relocate PP1 upstream; modify manifold configuration
- District adopted Reclamation's recommendation for security ~\$10,000
- GEI's review resulted in the following changes and savings:
  - Modify pump foundation concrete mix design ~\$250k
  - Reduce pump foundation concrete volume ~\$200k
  - Modify electrical building walls ~\$35k
- CCWD will continue to conduct design reviews and present designs to the JPA Design Review Team at each design milestone

# PP1 Construction Schedule

- District updated the construction schedule to reflect the 60% design
- Long lead electrical equipment has been identified as a critical path activity
  - Supply chain challenges continue to delay deliveries
  - Transformers have a lead time of 120 weeks
  - Value of equipment is estimated at \$2.5 million
- PP1 has extended to a 3-year construction schedule
- Options to accelerate schedule constrained until construction funds are available

# Design Coordination Agreements

- CCWD is progressing utility coordination and service agreements needed for construction


Agreement	Purpose	Status
Western Area Power Authority (WAPA)	<ul style="list-style-type: none"><li>• Substation design approval</li><li>• Pole relocation</li></ul>	<ul style="list-style-type: none"><li>• Ongoing design review under design agreement</li><li>• Construction agreement needed by September 2024</li></ul>
Diablo Water District	<ul style="list-style-type: none"><li>• Utility Water</li></ul>	<ul style="list-style-type: none"><li>• Construction agreement needed by September 2024</li></ul>
Iron House Sanitation District (ISD)	<ul style="list-style-type: none"><li>• Disposal of construction groundwater on ISD-owned lands</li></ul>	<ul style="list-style-type: none"><li>• Agreement needed by September 2024</li><li>• Permits needed by September 2024</li></ul>

- Agreements are on track to be in place prior to bidding

# Schedule

Item	Date
90% PP1 Design	Aug 2023
30% Veg Screen Design	November 2023
100% PP1 and Veg Screen Design	June 2024
Advertise PP1 for Bidding	Fall 2024
PP1 Construction Start	Jan 2025

# QUESTIONS?



**ITEM 1.3: UPDATE ON TRANSFER-BETHANY PIPELINE**

**RESPONSIBLE/LEAD STAFF MEMBER:**

Taryn Ravazzini, Executive Director

**DISCUSSION:**

Bryan Perkins, Senior Engineer on CCWD's Los Vaqueros Project team, will provide an update on the status of the Transfer-Bethany Pipeline (TBPL), which will deliver water from the expanded Transfer Pump Station to the California Aqueduct. Mr. Perkins will review the selected TBPL alignment and hydraulic profile of the TBPL.

Mr. Perkins will also give the Committee an overview of the Turn-In Agreement that is under negotiation with the Department of Water Resources and provide an update on the Turn-In design. Mr. Perkins will provide the results of the geotechnical and environmental site investigations conducted to date, discuss right-of-way acquisition and review the TBPL schedule.

**ALTERNATIVES:**

For information only

**FISCAL ANALYSIS:**

Not applicable

**ENVIRONMENTAL REQUIREMENTS:**

Not applicable

**EXHIBITS/ATTACHMENTS:**

Slide deck regarding Transfer-Bethany Pipeline Update



The logo for the Los Vaqueros Reservoir Expansion Project. It features the text "LOS VAQUEROS" in blue, "RESERVOIR EXPANSION" in green, and "PROJECT" in green. To the right of the text is a stylized graphic of a reservoir dam or structure, composed of several horizontal bars of varying heights, colored in shades of blue and green.

**LOS  
VAQUEROS  
RESERVOIR  
EXPANSION  
PROJECT**

A large white text overlay on a background image of a reservoir and rolling green hills. The text reads "Operations and Engineering Committee Meeting". In the background, a large blue reservoir is visible, surrounded by green hills. Several wind turbines are scattered across the hills in the distance. A road or pipeline runs along the edge of the reservoir in the foreground.


**Operations and Engineering  
Committee Meeting**

**Transfer-Bethany Pipeline Update**

**June 15, 2023**




# Background

- Transfer-Bethany Pipeline (TBPL) will deliver water from expanded Transfer Pump Station (TPS) to the California Aqueduct
- TBPL will be a 90-inch, 7.5-mile pipeline with a max capacity of 300 cubic feet per second (cfs)
- The expected average annual delivery of TBPL is 80,000 Acre-feet per year
- Progressing design to support a Turn-In agreement with DWR, required ahead of CWC hearing




# Pipeline Alignment

- Evaluated multiple alternatives
- Coordinated selection with CDFW and planned transportation improvements
- Selected Alignment:
  - Reduces impacts to lands encumbered with conservation protections
  - Overall lowest cost and lowest impact option




# Hydraulic Profile



# California Aqueduct Turn-In

- A Turn-In Agreement with the Department of Water Resources is needed prior to the CWC Final Award Hearing
- DWR will own and maintain facilities on DWR property
- Updating design based on DWR's comments on the 90-percent design

# Turn-In Design Updates



Coordinating Fiber Optic route

New Perpendicular Connection to Reduce Costs

Control Building and Valve Vault

Flow Meter Vault






DWR reviewing plan and profile

# FY 24 Pipeline Design Activities

- 30% design drawings of pipeline alignment (in progress)
- CEQA update to address alignment changes (in progress)
- Conduct site investigations on select parcels in Fall 2023 and remaining parcels in 2024
- Progress utility coordination and design of the Vasco Road trenchless crossing
- Prepare Preliminary Design Report

# Site Investigation

- Geotechnical and environmental site investigations
- Limit initial investigations to EIS/EIR alignment
- 13 borings, 19 CPTs, and 5 test pits
- Remaining investigations will be completed following CEQA update






# Right-of-Way (ROW) Acquisition

- Requesting access from property owners for initial phase of site investigations in Fall 2023
- Permanent ROW acquisition will be initiated after CWC full funding award
- Acquiring ROW within lands under conservation easements requires approvals from resource agencies, EBRPD and ECCCHC

# Schedule



CEQA Update	Summer 2023
Initial Site investigations	Fall 2023
Additional Site Investigations	Summer 2024
Begin Land Acquisition	Late 2024
Final Design and Bidding	Late 2025
Construction Complete	2028