

Langdon Quad Diamond Complex
Quad Diamonds - Informal Quotation

Contractor Name:

This quantities is based on the conceptual / schematic layout plan provided on August 7, 2018

ITEM	DESCRIPTION	UNIT	UNIT PRICE	QTY	AMOUNT
Section 1 - Site Preparation					
1.01	Mobilization, Demobilization	LS		1.0	
1.02	Mud Mat (10m x 6m)	LS		1.0	
1.03	Construction Sediment Control	lin.m		933.0	
1.04	Construction Fencing	lin.m		933.0	
	Subtotal:				
Section 2 - Bulk Excavation & Backfill					
2.01	Rough grading of site to depths indicated on details and drawing. Rough grading of profile by Laser Grading/automated unit.	m2		61,500.0	
	Subtotal:				
Section 3 - Irrigation					
3.01	Baseball Fields Labour and Materials - To be supplied by Contractor - All appurtenances not listed to be supplied contractor	L.S.		1.0	
3.02	Irrigation Allowance for water service connection and booster pump connections if required	Allowance		1.0	
	Subtotal:				
Section 4 - Drainage					
4.01	Field Collector Pipe - 300mm Dia. SDR 35	lin.m		210.0	
4.02	300mm Dia. Perforated Lateral Pipe c/w 16mm clear rock, wrapped with non-woven geotextile)	lin.m		1,751.0	
4.03	Field Lateral Cleanouts	each		28.0	
4.04	Storm Connection to Existing Stormwater Sewer / Into SWM Pond	each		1.0	
	Subtotal:				
Section 6 - Paving, Pathways & Retaining Walls					
6.01	Asphalt Surfacing (walkways) - LD	sq.m		5,230.0	
6.01B	Asphalt Surfacing (walkways) - HD	sq.m		1,080.0	
6.02	Concrete Paving	sq.m		978.0	
6.03	Screening (Gravel) Pathway	sq.m		-	
6.04	Retaining Wall	lin.m		178.0	
	Subtotal:				
Section 7 - Soft Landscaping					
7.01	Turf on 300mm topsoil - outside the baseball diamonds	sq.m		21,541.0	
	Subtotal:				
Section 8 - Fencing					
8.01	Chain Link Fence 1.5m tall with protection capping	lin.m		421.0	
8.02	Chain Link Fence 3.0m tall	lin.m		121.0	
8.03	Chain Link Fence 9.0m tall (BACKSTOP)	lin.m		278.0	
8.04	Chain Link Fence 3.0m tall (Outfield) with protection capping	lin.m		1,197.0	
8.05	Foul Poles	each		8.0	
8.06	1.5m wide Gate	each		36.0	
8.07	3.6m wide Maintenance Gate	each		8.0	
8.08	Player's Shelters with Benches	each		8.0	
	Subtotal:				
Section 9 - Softball Diamonds					
9.01	Sport Field Sod	sq.m		24,125.0	
9.02	Topsoil (Existing Topsoil Stockpile onsite - Screen and Blended) - 300mm Depth	sq.m		24,125.0	
9.03	Topsoil Amendments (Sand)	cu. M		2,756.4	
9.04	Warning track (Shale)				
	Option #1	sq.m		1,692.0	
	Option #2	sq.m		1,692.0	
	Option #3	sq.m		1,692.0	
9.05	Skinned area Surfacing				
	Option #1	sq.m		8,471.0	
	Option #2	sq.m		8,471.0	
	Option #3	sq.m		8,471.0	
9.06	Batter's Box Area				
	Option #1	sq.m		60.0	
	Option #2	sq.m		60.0	
	Option #3	sq.m		60.0	
	Subtotal:				
Section 11 - Site Servicing					
11.01	Water Servicing	lin.m		222.0	
11.02	Stormwater Servicing	lin.m		652.0	
11.03	SWM MH	each		14.0	
11.04	SWM CB	each		1.0	
11.05	Sanitary Servicing	lin.m		203.0	
11.06	SAN MH	each		2.0	
11.07	Misc. Items	allowance		1.0	
	Subtotal:				
Subtotal Construction Costs:					
Total Estimated Construction Cost:					