

# SPECIFICATIONS

- ➔ Bows on 5' centers, 4 corner braces, and peak braces
- ➔ We recommend adding 2 extra feet in height for future garage
- ➔ 2 1/2" & 2 1/4 " 14 Gauge Galvanized Steel
- ➔ 29 Gauge STEEL roof panels
- ➔ Buildings 22' or 24' wide, or 8' legs or taller, we recommend extra bracing
- ➔ Arkansas Carports is not responsible for impenetrable stony ground
- ➔ If you are needing special drawings or wet stamped drawing for your building, there will be an additional charge
- ➔ Certification includes extra bracing + the best anchors for your installation surface. Certified for 140mph winds + 35lbs snow load psf

ADDITIONAL LABOR	20'L	25'L	30'L	35'L	40'L	45'L	50'L
<b>BUILD OVER FEE</b>	\$135	\$157	\$180	\$225	\$247	\$292	\$315
<b>CUT LEGS ON SITE</b>	\$90	\$112	\$135	\$157	\$189	\$202	\$225

## ACCESSORIES

<p><b>Extra Panels</b></p> <p>21' Long \$184 each                  26' Long \$229 each                  31' Long \$274 each                  36' Long \$319 each</p>	<p><b>Roll-Up Commercial Doors With Chain</b></p> <p>12' x 12' <b>\$1,615</b>                  14' x 14' <b>\$2,641</b> <i>(Requires Lift)</i></p> <p style="font-size: small;">Fee to install Roll-Up Commercial Doors on side of buildings 12' to 30' wide is \$250</p>	<p style="text-align: center;"><b>End Frame Outs</b> <i>(Must close ends first)</i></p> <p>Window Frame Outs Up to 30" x 30" <span style="float: right;"><b>\$162 (Per Opening)</b></span></p> <p>Walk-In Door Frame Outs Up to 36" x 80" <span style="float: right;"><b>\$225 (Per Opening)</b></span></p> <p>Garage Door Frame Outs on Ends up to 12' x 12' <span style="float: right;"><b>\$315 (Per Opening)</b></span></p>
<p><b>Extra Braces</b></p> <p>2 ft Brace \$26 per leg                  4 ft Brace \$54 per leg</p>	<p><b>Garage Doors (Roll-Up)</b></p> <p>6 x 6 <b>\$500.00</b>                  6 x 7 <b>\$517.00</b>                  8 x 8 <b>\$697.00</b>                  9 x 8 <b>\$720.00</b>                  10 x 8 <b>\$765.00</b>                  10 x 10 <b>\$877.00</b></p> <p style="font-size: small;">Fee to install Roll-Up doors on side of buildings 12' to 30' wide is \$250</p>	<p style="text-align: center;"><b>Connect Fee</b></p> <p>End to End: 12' to 30' Wide <b>\$288.00</b>                  Side to Side: 21' Long <b>\$238.00</b>                  26' Long <b>\$261.00</b>                  31' Long <b>\$283.00</b>                  36' Long <b>\$310.00</b>                  41' Long <b>\$333.00</b>                  46' Long <b>\$355.00</b>                  51' Long <b>\$378.00</b></p>
<p><b>Windows</b></p> <p>30" x 30"..... \$247.00 each</p>	<p style="text-align: center;"><b>Insulation</b></p> <p><b>\$1.00 per square foot - Bubble</b>  <b>\$3.00 per square foot - Spray foam</b></p>	<p style="text-align: center;"><b>Asphalt Anchors 30"</b>  <b>\$67.00 Each</b>  <b>\$45.00 Not installed</b></p>
<p><b>Walk-In Door</b></p> <p>36" x 80"..... \$382.00 each</p>	<p style="text-align: center;"><b>Concrete Anchors Bolts</b>  <b>\$36.00 Each</b></p>	<p style="text-align: center;"><b>Mobile Home Anchors 30"</b>  <b>\$67.00 Each</b>  <b>\$45.00 Not installed</b></p>
<p><b>45° Arch Cut</b></p> <p>\$112.00 per Opening</p> 		