New Eating Shelters for:

Camp Ben Lomond Eating Shelters

2635 East 5100 North Liberty, Utah

Code Information

IBC Code Requirement Actual Building Design Occupancy Classification Chapter 3 Business, Group A-3 Construction Type Type II-B **Roof Construction Class** Table 1505.1 Class A Fire Sprinklers 480 sf Shelter Area 32 occupants per eating shelter for total Occupant Load 1 Occupant per net 15 sf

Building Codes

2021 International Residential Code
2021 International Building Code per R301.1 1. 3 (Structural)
2009 ANSI A117.1 Standard For Accessible And Usable Buildings And Facilities

Drawing Index

G101 Cover Sheet
C101 Overall Map
C201 Weber County Erosion Control Details
C411 Site Plan & Section
C811 Eating Shelter Plans, Notes and Details
C812 Eating Shelter Plans, Notes and Details

C813 Eating Shelter Plans, Notes and Details

Deferred Submittals

Submittal documents for deferred items shall be submitted to the architect or engineer of record who shall review them and forward to the building official with a notation indicating that the deferred documents have been reviewed and that they have been found to be in general conformance with the design of the building. The deferred items shall not be installed until their design & submittal documents have been approved by the building official.

Items to have deferred submittal include

General Notes

1. All existing roads, buildings, camp facilities, concrete flatwork, culinary water services, ampitheather, utilities, etc are to remain; protect during construction; any damage to existing items are to be repaired or replaced with no additional cost to

2. Contractor shall field verify all existing conditions.

Owner-Provided / Contractor Installed

1. Eating shelter kit; including but not limited to steel columns, base plates, beams and roofing. The contractor is responsible for unloading.

2. Picnic tables; the contractor shall include in their bid the cost to assemble (4) picnic tables for each eating shelter.

(1) table at each shelter to provide a space for a wheel chair.

Site Preparation

1. The contractor shall coordinate the exact location of each pavilion with the Owner and Architect prior to starting any work. Actual conditions vary at each location.

2. The contractor shall remove all existing vegetation, trees, roots, etc from a 28'-0" x 28'-0" area at each pavilion.

3. The contractor shall remove 12" of topsoil and other deleterious material from the building pad area.4. The contractor shall prepare and compact a flat area 28'-0" x 28'-0" to a relative compaction of 95%.

5. The contractor shall include in their bid the cost to import, place and compact structural fill for each pavilion location. A total of 28 cy of material shall be provided for each location. All structural fill shall be compacted to a relative compaction

Eating Shelter Access

The contractor shall include in their bid the cost to provide a drive access and parking pad for each eating shelter.
 The contractor shall remove all existing vegetation, trees, roots, etc from a 12'-0" x 75'-0" area at each pavilion. The exact location will be coordinated between the Owner and Architect prior to starting any work.

3. The contractor shall remove 8" of topsoil and other deleterious material from the access and parking areas.4. The contractor shall include in their bid the cost to import, place and compact 8" deep road base along the access and parking areas. The road base shall be compacted to a relative compaction of 95%.

5. A 12'-0" wide x 24'-0" long parking pad adjacent to the eating shelter shall have a slope (each direction) of 1.5%.

Final Grading

1. The contractor shall provide 4" of topsoil around the perimeter of each eating shelter to a width of 3'-0".

Provide a native sead mix over all new topsoil areas.

Weber County General Notes

HOURS OF CONSTRUCTION – Work is limited to 7:00am to 9:00pm Monday through Saturday.
 ADJOINING PROPERTIES – All work shall be contained within the limits of disturbance identified on the site plan.
 PROJECT FENCING – All limits of disturbance shall be staked on the ground prior to any construction activity and

4. NATURAL ENVIRONMENT – The project construction shall minimize impacts to all aspects of the natural environment. Any necessary construction measure shall be installed prior to any construction activity and maintained for

5. NOXIOUS WEED CONTROL – Project will take all necessary measures to control the growth & spread of noxious weeds in accordance with the Summit County Noxious Weeds Act, Utah Code Annotated 4-14-101 (as amended).
6. CONSTRUCTION PARKING MANAGEMENT – On-site parking locations (no street parking), unless otherwise identified on the site plan, shall be designated and made continually available for all project personnel. The contractor shall maintain continuous emergency vehicle access, on and around the project site, including, but not limited to, police, fire, ambulance, and snowplow services.

7. STAGING AREAS – All staging must occur within the approved development envelope, unless identified on the site

8. WASHOUT FACILITIES – Washout Facilities shall be available, clearly marked, and maintained.

9. TRAFFIC CONTROL – There shall be no impact to vehicular or pedestrian traffic. If a public lane/road closure becomes necessary, the contractor shall apply for & receive a permit through E360 prior to the closure.

10. SEDIMENT AND EROSION CONTROL – A stormwater pollution prevention plan & erosion control plan (if necessary) shall be implemented prior to any construction activity and maintained for the duration of the project.

11. SANITARY FACILITES – Portable toilets shall be provided during construction. Toilets will be located outside adiacent road rights-of-way and secured to prevent tipping.

12. FUGITIVE DUST CONTROL – If the project degrades air quality or creates a nuisance for adjacent properties and roadways as a result of blowing dust, the project representative will take immediate action to eliminate the nuisance.

13. NOISE CONTROL – All construction equipment and activities shall be adequately muffled and maintained to minimize project noise.

14. SNOW STORAGE – All snow accumulated within the project will be stored within property boundaries, unless otherwise identified on the site plan.
15. ROUGH GRADE ENGINEERING INSPECTION – All construction mitigation elements must be in place before

16. PRESURFACE INSPECTION – This inspection must be scheduled and completed before the final driveway surface (e.g. asphalt, concrete, gravel) is placed.

17. BUILDING INSPECTIONS – Inspection requests shall be made online at least a minimum of 24 hours in advance of

the actual inspection.

18. FAILED INSPECTIONS - Failure to correct all deficiencies noted on previous inspections will result in a failed inspection and the assessment of a re-inspection fee. Re-inspection fees are a minimum of \$100.00.

19. PREREQUISITE INSPECTIONS – Footings and Final Engineering inspections have prerequisites that must be

completed before the subsequent inspection can be scheduled. Please plan accordingly to avoid any delays.


Project Team

<u>Chitect</u>
EA Architecture
11576 South State Street, #103B
Draper, Utah

Chad Spencer (801) 450-5113 chad@studio-ea.com

Vicinity Map

Project Site





THE CHURCH OF


JESUS CHRIST

OF LATTER-DAY SAINTS

New Eating Shelters for:

Camp Ben Lomond

> 2635 East 5100 North Liberty, Utah



25-36
Plan Series:


Property Number: 533-4012-24020101


September 2, 2025


Cover Sheet


G101


r











Inspection	Description/Requirements	Contact		
mspection	Required prior to scheduling a footing inspection. Rough cut of	Contact		
Rough Grade	driveway, stabilized construction entrance, sediment control	Engineering		
Engineering	BMPs, & concrete washout all must be installed per site plan.	Engineering		
Footings	Schedule after steel is in place and before concrete is poured	Duilding		
Footings		Building Building		
Foundation	Schedule after steel is in place in forms and before concrete is poured			
Under Slab	Schedule before concrete is poured or plumbing has been	Building		
Plumbing/Heating	backfilled			
	Performed by a licensed surveyor. Required before scheduling a	Planning		
and/ or Survey	Floor Framing Inspection			
Floor Framing/				
Foundation Drain	Required prior to placing floor sheeting	Building		
Shear Wall	After the building is "up to square," all shear walls have been			
Siledi VVdii	nailed, and all tie downs and shear wall connections installed			
Fire Sprinkler	Required prior to Four-Way Inspection, when required by Local	Building		
The Sprinkler	Fire District	Ballallig		
	All rough electrical, plumbing, and mechanical has been installed. All			
Four-Way	framing is complete, shear walls have been previously inspected, and	Building		
	truss specifications are on site for review. Plumbing must have either an air or water pressure test on them when the inspector arrives.			
Weather Barrier/	Weather barrier must be inspected prior to applying veneer.			
Stucco Lath	Approved stucco I.C.C. research reports on site	Building		
Gas Line/Meter Set	Required before gas meter clearance is given to Dominion	Building		
	Steel in masonry and before concrete/grout is poured	Building		
Insulation	Pre-drywall insulation certificate required	Building		
Drywall Nailing	Required before drywall is taped	Building		
Power to Panel	Building must be up with permanent roof installed	Building		
Pre-Surface	Before driveway is paved/stabilized. Erosion control installed on			
	graded slopes greater than 3:1. Driveway graded to final slope.	Engineering		
Engineering	graded slopes greater than 3.1. Driveway graded to final slope.			
	Required prior to Certificate of Occupancy and/or bond release.			
	Driveway paved/ stabilized w/ non-tracking, permanent			
Final Engineering	material. Final grading must be less than 2:1 slopes, with erosion			
	control measures installed on unretained slopes greater than 3:1			
	Described for Cortificate of Ossumanar, All work is done building			
Final Building	Required for Certificate of Occupancy. All work is done, building	Building		
	is complete. Final clearances from wastewater district, Health			
	Department for septic, and Fire District for sprinkler system must			
	be on site for this inspection.			
Certificate of	No person may occupy the structure until CofO is issued. Final			
	clearances must be obtained and presented to the Building	B - 11 11		
Occupancy	Dept: Final from Building, Final from Engineering, Final from	Building		
	Fire District (where required), Final from Water District or Health			
011/02/505 5	Dept (where required).			
SWP3/ECP Bond	Site must be 100% stabilized (revegetated or covered) to at least	Engineering		

70% density.

Show location for dumpster, portable toilets, materials storage, parking

Roadside parking is not allowed from November 1st to April 1st

Construction parking/traffic may not block the street without a permit (available from the

The construction site must be maintained in a neat manner. Trash and other debris may

Mud tracked out onto the street must be cleaned prior to the end of the work day

Construction Mitigation Plan Notes

Engineering Division)


not accumulate outside the dumpster.


Release


- Engineering Perform washout of concrete trucks offsite or in designated concrete washout areas only.
- Do not wash out concrete trucks onto the ground, or into storm drains, open ditches, streets, or streams.
- Do not allow excess concrete to be dumped onsite, except in designated concrete washout areas.


Concrete washout areas may be prefabricated concrete washout containers, or self-installed structures (above-grade or below-grade).

- o Prefabricated containers are most resistant to damage and protect against spills and leaks. Companies may offer delivery service and provide regular maintenance and disposal of solid and liquid waste.
- o If self-installed concrete washout areas are used, below-grade structures are preferred over above-grade structures because they are less prone to spills and leaks.
- Self-installed above-grade structures should only be used if excavation is not practical.










Project for:

THE CHURCH OF JESUS CHRIST OF LATTER-DAY SAINTS

> New Eating Shelters for: Camp Ben

Lomond

2635 East 5100 North Liberty, Utah




25-36 Plan Series:


Property Number 533-4012-24020101


September 2, 2025

Weber County Erosion Control Details

C201







Project for:

THE CHURCH OF


JESUS CHRIST

OF LATTER-DAY SAINTS

New Eating Shelters for:

Camp Ben Lomond

> 2635 East 5100 North Liberty, Utah




Project Number: 25-36
Plan Series:


Property Number: 533-4012-24020101

September 2, 2025

Site Plan & Section

C411





DESIGN CRITERIA:

- 1. 2021 INTERNATIONAL BUILDING CODE WITH STATEWIDE AMENDMENTS
- TYPE OF CONSTRUCTION: TYPE II-B BUILDING USE: ASSEMBLY A-3
- 4. BUILDING OCCUPANCY CATEGORY: II 5. BUILDING HEIGHT: PER PLANS
- 6. NO. OF OCCUPANTS: 120 7. ROOF DEAD LOAD - 6 PSF PLUS FRAMING WEIGHT
- a. METAL DECK: 1.5 PSF SNOW LOAD b. Pg: 80 PSF (GROUND SNOW LOAD)
- c. Pf = 0.7 * Pg * Ce * Ct * Is = 78 PSF (ROOF SNOW LOAD)1) Ce: 1.2 Ct: 1.2 ls: 1.0
- d. Ps = Pf CsCs: 0.96 FOR A 4:12 PITCH
- Ps: 78 PSF
- 10. WIND LOAD a. V3s: 115 MPH
- b. EXPOSURE: C c. W: 1.00 11. SEISMIC LOAD
- a. le: 1.00 d. Sds: 0.87

e. Sd1: 0.83

- f. SITE CLASS: D SEISMIC DESIGN CATEGORY: D R: 1.25 (CANTILEVERED STEEL COLUMNS) EQUIVALENT LATERAL FORCE PROCEDURE
- Cs = 0.69612. ALLOWABLE SOIL BEARING PRESSURE = 1,500 POUNDS PER SQUARE FOOT. 13. ALLOWABLE FOUNDATION AND LATERAL PRESSURE = 100 PSF/FT BELOW NATURAL GRADE (TABLE 1806.2 OF 2021 IBC).

PAVILION CONSTRUCTION SEQUENCE NOTES:

- 1. VERIFY PERMIT REQUIREMENTS BEFORE SIGNING CONTRACTS.
- BUILDING PERMIT PLANNING OR CONDITIONAL USE PERMIT
- OBTAIN REQUIRED USE PERMIT 2. REMOVE ALL VEGETATION, ROCKS, OUTCROPPINGS, AND TREES FROM LOCATION OF PAVILION SLAB. STRIP 6" OF TOP SOIL.
- 3. LEVEL PAVILION BUILDING AREA. AVOID GRADING THAT ALLOWS WATER TO DRAIN TOWARD PAVILION. 4. DIG COLUMN CAISSONS. 5. PLACE COLUMN CAISSON FORMS AND SET REINFORCING STEEL.
- 6. SET COLUMN ANCHOR BOLTS USING PLYWOOD TEMPLATE OF APPROXIMATELY THE SAME SIZE AS COLUMN BASE PLATE TO INSURE BOLT LOCATION ACCURACY.
- 7. PLACE CONCRETE IN CAISSON FORMS FROM BOTTOM OF PIER UP TO A LEVEL 1-1/2" BELOW BOTTOM OF COLUMN BASE PLATE. LET CONCRETE CURE 7 DAYS.
- 8. SET GALVANIZED STEEL TUBE COLUMNS OVER PRE-SET ANCHOR BOLTS ALLOWING COLUMNS TO REST ON LEVELING NUTS AND 1/4"x 3" PLATE WASHERS. LEVELING NUTS ARE TO BE USED TO SET COLUMNS PLUMB AND TRUE AND AT CORRECT BEARING HEIGHT TO RECEIVE STEEL BEAMS.
- 9. AFTER COLUMNS ARE SET PLUMB AND TRUE, VERIFY ACCURACY OF DIMENSIONS BETWEEN COLUMNS AND SECURE COLUMNS IN PLACE USING 1/4"x 3" PLATE WASHERS UNDER NUTS. TIGHTEN NUTS WITH ADDITIONAL 1/4 TURN PAST SNUG.
- 10. LIFT BEAMS AND SET EACH END IN THE COLUMN SADDLE PLATES. 11. ANCHOR BEAMS TO COLUMN CAP PLATES WITH (4) 1/2" DIAMETER BOLTS, WASHERS, AND NUTS.

12. INSTALL PRE-FINISHED METAL DRIP EDGING ON ALL PERIMETER EDGES OF ROOF.

- 13. INSTALL METAL ROOF PANELS. FOLLOW MANUFACTURER'S INSTRUCTIONS. 14. PLACE NON-SHRINK GROUT UNDER COLUMN BASE PLATES. FINISH NON-SHRINK GROUT EDGES TO
- 15. PLACE REMAINDER OF CONCRETE SLAB ANY TIME AFTER BEAMS, ROOF DECKING ARE SECURELY IN
- 16. FINISH TOP SURFACE OF CONCRETE WITH A LIGHT BROOM FINISH. 17. AS SOON AS CONCRETE HAS CURED ENOUGH TO SUPPORT AN EARLY ENTRY SAW (4-6 HOURS AFTER PLACEMENT), CUT CONTROL JOINTS IN SLAB TOP SURFACE. DEPTH OF CONTROL JOINTS IS
- TO BE 1" DEEP. 18. INSTALL MEMBRANE CURING ON CONCRETE SLAB.
 19. ALLOW CONCRETE SLAB TO CURE A MINIMUM OF 7 DAYS BEFORE PROCEEDING WITH REMAINDER OF
- 20. ALL STEEL COLUMNS, SADDLES, BOLTS, AND BASE PLATES TO BE POWDER COATED. TOUCH-UP FINISH PAINTING BY OTHERS.

- SCOPE- ONE EACH 22 FOOT BY 22 FOOT PAVILION WITH MINIMUM 4 INCH THICK CONCRETE SLAB. PROVIDE SHINGLES, ROOFING FELTS, FASCIA, SHEATHING, ROOF FRAMING, BEAMS, SOFFIT, CONNECTION HARDWARE, COLUMNS, CONCRETE SLAB, CONCRETE CAISSONS AND FINISHES TO CONSTRUCT COMPLETE
- PAVILION HAS BEEN DESIGNED AS A FREE STANDING, OPEN STRUCTURE. RE-ENGINEER PAVILION IF WALLS ARE ADDED (SEE SHEET C813), IF STRUCTURE IS TO ADJOIN ANOTHER STRUCTURE, OR IF OTHER SUCH MODIFICATIONS ARE MADE. PROPERLY BRACE STEEL BEAMS AND MEMBERS UNTIL COMPLETE STRUCTURAL SYSTEM HAS BEEN CONSTRUCTED.

SITE PREPARATION:

- 1. PLACE FOOTINGS/CAISSONS IN FIRM UNDISTURBED NATURAL SUBGRADE (UNLESS NOTED OTHERWISE BY
- GEOTECHNICAL REPORT). 2. COMPACT SUBGRADE AND FILL UNDER CONCRETE FLOOR SLAB TO 90 PERCENT OF ASTM D-1557 (UNLESS
- NOTED OTHERWISE BY GEOTECHNICAL REPORT) 3. INSTALL AND COMPACT 4 INCH GRANULAR BASE BENEATH CONCRETE FLOOR SLAB TO 95 PERCENT OF ASTM

<u>UTILITIES:</u>

INSTALL PLUMBING LINE FOR COLD WATER AS NEEDED. 2. INSTALL ELECTRICAL LIGHTS, BOXES, CONDUITS, AND SWITCHES AS NEEDED.

CONCRETE:

- 1. REMOVE ALL ORGANIC MATERIAL AND TOPSOIL FROM PAVILION AREA. VERIFY SUITABILITY OF SUBGRADE. FOUNDATIONS ARE TO BE ON UNDISTURBED, NATURAL SOIL OR ENGINEERED FILL EXTENDING TO SUITABLE
- UNDISTURBED NATURAL SOILS. 2. PROVIDE 4" MINIMUM OF COMPACTED SAND, GRAVEL OR CRUSHED ROCK BENEATH THE CONCRETE SLAB ON
- 3. CONCRETE SLAB ON GRADE IS TO BE REINFORCED AS SPECIFIED AND BE 4" MINIMUM THICK. INSTALL WITH
- CRACK CONTROL JOINTS AS SHOWN. SURFACE IS TO HAVE A BULL FLOAT FINISH AND BE LIGHTLY BROOMED. 4. EDGE OF SLAB IS TO BE THICKENED TO 8" WIDE AND BE REINFORCED WITH (2) #4 CONTINUOUS BARS. LAP
- SPLICES 24". USE EPOXY COATED REINFORCING BARS IN AREAS OF FREEZE THAW CONDITIONS. PROVIDE DEFORMED REINFORCING STEEL BARS CONFORMING TO ASTM A615 WITH A MINIMUM YIELD STRENGTH OF 60,000 PSI. SECURELY ANCHOR REINFORCING STEEL, AND PROVIDE CLEARANCES, IN ACCORDANCE WITH
- 6. MINIMUM COMPRESSIVE STRENGTH OF CONCRETE IS TO BE 4,500 PSI AT 28 DAYS, WITH 6 PERCENT AIR ENTRAINMENT (PLUS OR MINUS 1-1/2 PERCENT) IS TO BE USED IN AREAS SUBJECT TO FREEZE THAW CYCLES. USE CEMENT TYPE I/II OR II. LIMIT SLUMP TO 4" PLUS OR MINUS 1". VERIFY STRENGTH REQUIREMENTS AND CEMENT TYPE REQUIREMENTS WITH THE GEOTECHNICAL EVALUATION REPORT. ALL CONCRETE WORK TO BE IN ACCORDANCE WITH THE LATEST EDITION OF ACI 318.

STRUCTURAL STEEL:

ALL STEEL PLATES TO BE ASTM A36

THE LATEST EDITION OF ACI 318.

- STEEL TUBES TO BE ASTM A500, GRADE C, Fy = 50,000 PSI ALL WELDING IS TO BE DONE IN ACCORDANCE WITH LATEST AWS STANDARDS. IF WELDS ARE NOT
- SPECIFIED, ALL WELDS ARE TO DEVELOP THE FULL STRENGTH OF ALL COMPONENT PARTS.


4. ALL BOLTS ARE TO BE ASTM A325 EXCEPT THAT ANCHOR BOLTS ARE TO BE ASTM F 1554 GRADE 105.

5. ALL HOLES IN STEEL TO BE 13/16" DIAMETER UNLESS NOTED OTHERWISE. 6. STEEL COLUMNS ARE SANDBLASTED (SSPC5/NACE "white finish"), PRIMED (SMALL MOLECULE ZINC RICH EPOXY PRIMER) AND POWDER COATED (SUPER DURABLE TGIC POLYESTER TOP COAT). ALL OTHER FABRICATED STEEL TO BE POWDER COATED.

METAL ROOF SYSTEM:

- MEGA-RIB PAINTED ROOF PANELS BY MCELROY METAL.
- PROFILE DEPTH: 1-1/2" PANEL WIDTH: 36"
- MIN THICKNESS: 24ga.
- COLOR AS PER OWNER FROM MANUFACTURERS STANDARD COLOR SELECTION. INSTALL AS PER MANUFACTURERS INSTRUCTIONS.
- PROVIDE EDGE AND TERMINATION DETAIL COMPONENTS AS REQUIRED TO OBTAIN MANUFACTURER WARRANTY.

- 1. PROVIDE ONE DEDICATED 30 A CIRCUITS FOR THE PAVILION. RUN THE CIRCUITS IN 3/4-INCH CONDUIT UNDERGROUND WITH NO. 12 THWN COPPER CONDUCTORS PLUS GROUND AND NEUTRAL FROM THE NEAREST 110 VOLT SOURCE WITH AVAILABLE CAPACITY. TIE THE LIGHT FIXTURES TO ONE OF THE DEDICATED CIRCUITS. PROVIDE FOUR CONVENIENCE DUPLEX RECEPTACLES. TIE TWO DUPLEX RECEPTACLES PER CIRCUIT. FOR UNDERGROUND CONDUIT RUNS, USE PVC-40 PIPE WITH BURIAL DEPTH PER CODE REQUIREMENTS. USE
- INTERMEDIATE METAL CONDUIT OR RIGID STEEL CONDUIT FOR EXPOSED RISER UP TO SWITCH. INSTALL TIME SWITCH (4-HOUR CYCLE, NO-HOLD, AUTOMATIC SHUT-OFF, INTERMATIC #FF34H OR EQUAL BY PARAGON OR TORK) WITH WEATHERPROOF COVER ON COLUMN AT 48 INCHES ABOVE CONCRETE SLAB TO
- 3. CONNECT LIGHTING FIXTURES WITH SURFACE MOUNTED 1/2-INCH EMT AND STEEL FITTINGS AND NO. 12 THWN OR XHHW COPPER CONDUCTORS.
- 4. LIGHTING FIXTURES SHALL BE IMPACT RESISTANT, ENCLOSED, SURFACE MOUNTED FLUORESCENT WITH FOUR FO32 T8 LAMPS, LOW TEMPERATURE ELECTRONIC BALLASTS, AND DAMP LOCATION LABEL. LITHONIA TDMW232-AR-120 OR EQUAL BY COLUMBIA, DAY-BRITE, OR METALUX.
- 5. PROVIDE WATERPROOF WHILE IN USE ALUMINUM OUTLET WITH PADLOCK LOOPS.



2 Roof Framing Plan 3/8"=1'-0"

DOUGLAS M.

FARLEY

No.318831

05/23/2025

 _	 	 _	
			Description
			Date (DD-MM-YY)
			ž

Project Number:

Plan Series: Property Number:

Sheet Title: 3D VIEW PLAN VIEWS

C811

