



ADDENDUM

Date Issued:	May 29, 2019
Project:	Intermountain Medical Center Gamma Knife Scan Room Remodel 5121 Cottonwood Street Murray, Utah 84107
Addendum Number:	1

The Contractors submitting proposals on the above-captioned project shall be governed by the following addendum, changes and explanations to the drawings and specifications and shall submit their bids in accordance therewith.

Item Number	General Items Description
1	Intermountain Healthcare shall hire the Rigging Company directly and pay for their services. General Contractor shall coordinate construction activities with the rigging company during the rigging process.
2	Due to the limited scope of work, there is no project manual for this project.

Sheet Number	Drawings
Architectural Drawings	
A-111	<p>Revise Keyed Note #09.07 as follows:</p> <p>REMOVE EXISTING SHEET VINYL FLOOR COVERING IN THE ENTIRE ROOM AND REPLACE WITH NEW SHEET VINYL FLOOR COVERING. ACCENT PATTERN SHALL MATCH EXISTING. FLOOR COVERING SHALL BE SELF COVERED TO ACT AS WALL BASE. FIELD FLOOR COVERING SHALL BE: BIOSPEC SR, COLOR - "FLAX 67361", MANUFACTURED BY MANNINGTON. ACCENT COLOR SHALL BE: BIOSPEC SR, COLOR - "BEDROCK 15369", MANUFACTURED BY MANNINGTON.</p> <p>AS TIME IS LIMITED FOR THE CONCRETE TO CURE AND THEN INSTALL THE FLOOR COVERING, CONTRACTOR SHALL APPLY "ARDEX MCT™ RAPID MOISTURE CONTROL SYSTEM". THIS IS A ONE-COAT, 100% SOLIDS EPOXY MOISTURE MANAGEMENT SYSTEM FORMULATED TO SUPPRESS EXCESSIVE MOISTURE VAPOR EMISSIONS IN NEW AND/OR EXISTING CONCRETE PRIOR TO INSTALLING AN ARDEX UNDERLAYMENT WITH FLOORING OR AN ARDEX TOPPING WITH SEALER.</p>

Attachments:

None.