

project Intermountain IMED MRI project no 19480.00

date 2019-07-22 no. pages

**owner** Intermountain Healthcare

contractor

**bid date** 2019-07-29 **bid time** 2:00 pm

This Addendum shall be considered part of the Contract Documents and Project Manual for the above mentioned project as though it had been issued at the same time and shall be incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original Contract Documents and Project Manual, the Addendum shall govern and take precedence.

#### general

### 1.1 **APPROVALS:**

1. REFER to attached Mechanical Narrative from VBFA providing a list of products, trade names and manufactures allowed to bid on this project.

## drawings

item sheet# description
1.1 AD110 LEVELS LL-1 & LL-2 - DEMOLITION PLAN - OVERALL

- ADD note to 'Demolition of Metal Cover Structure Over the Mechanical Piping.' Existing metal cover structure to be removed in its entirety.
- 2. Photo of existing metal cover structure has been included for reference.
- 1.2 A110.0 LEVEL LL-1 SLAB PLAN ENLARGED
  - 1. REVISE concrete slab infill to include 5" REINFORCED CONCRETE SLAB OVER EXTRUDED POLYSTYRENE GEOFOAM.
  - 2. This new condition occurs in MRI SUITE 102 & MRI EQUIPMENT 103.
- 1.3 A120.1 LEVEL LL-2 ANNOTATED AND DIMENSION PLAN ENLARGED
  - 1. REVISE location of concrete chiller pad.
  - 2. REMOVE keyed note 2-501
  - 3. PROVIDE a new metal cover roof structure, starting at the new chiller connection to the point where the new chiller pipes enter the building.
  - 4. Photo of existing metal cover structure has been relocated to sheet AD110.

5. "FIELD VERIFY" note added to detail A6.

### 1.4 **MECHANICAL DRAWINGS**:

1. See attached Mechanical Drawings and Narrative from VBFA.

## 1.5 **ELECTRICAL DRAWINGS**:

1. See attached Electrical Drawings and Narrative from Spectrum Engineers.

# specifications

item	section#	description
1.1	230900	INSTRUMENTATION AND CONTROL FOR HVAC
		- Section has been added to the project.
1.2	232116	HYDRONIC PIPING SPECIALTIES
		- Section has been added to the project.
1.3	232123	HYDRONIC PUMPS
		- Section has been added to the project.
1.4	232513	WATER TREATMENT FOR CLOSED-LOOP HYDRONIC SYSTEMS
		- Section has been added to the project.
1.5	232516	WATER TREATMENT FOR OPEN-LOOP HYDRONIC SYSTEMS
		- Section has been added to the project.
1.6	233713	DIFFUSERS, REGISTERS AND GRILLES
		- Section has been added to the project.
1.7	235700	HEAT EXCHANGERS
		- Section has been added to the project.
1.8	312300	EXPANDED POLYSTYRENE GEOFOAM
		- Section has been added to the project.

### approvals

In addition to the manufacturers called out in the contract documents, the following manufacturers, trade names and products are acceptable with the provisions that they shall completely satisfy every requirement of the drawings, specifications, and all addenda, and shall conform to the design, quality and standards specified, established and required for the complete and satisfactory installation and performance of the building and all its respective parts. Any costs incurred due to the use of the following manufacturers shall be paid by the contractor.

section material manufacturer action