

project SDP Sumitomo Dainippon Pharma TI project no 21560

date 2021-09-02 no. pages

owner SDP Sumitomo Dainippon Pharma Oncology

contractor

**bid date** 2021-09-16 **bid time** 2:00 pm

This Addendum shall be considered part of the Contract Documents and Project Manual for the above mentioned project as though it had been issued at the same time and shall be incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original Contract Documents and Project Manual, the Addendum shall govern and take precedence.

## drawings

item	sheet#	description	
4.1	A111.0C	Location of relocated light sensor & ceiling til	
4.2	A111.3	Relocate light & sensor ceiling tile	
4.3	ED101B	Relocate light sensor & ceiling tile	
4.4	EL101	Location of relocated light sensor & ceiling tile	

## **End of Addendum 004**

1. IT IS THE INTENTION OF SDP TO REMAIN OPEN & OPERATIONAL DURING BUSINESS HOURS. ALL CONSTRUCTION WORK REQUIRED IN THE MAIN LAB ROOM 002, LAB 2 ROOM 004 AND IHC/NANOSTRING BAY 005 NEED TO BE DONE IN THE OFF-HOURS OR ON WEEKENDS. THE TEAM IDENTIFIED THESE ITEMS TO BE DONE IN OFF-HOUR OR WEEKEND TIMES:

> \* EPOXY FLOOR AND PAINT \* FIRE PROOFING SPRAY \* RE-ROUTING CONDENSATE PIPING TO THE FLOOR SINK \* REMOVAL OF DOORS INTO LABS IDENTIFIED ABOVE

THIS LIST IS NOT INCLUSIVE AND ADDITIONAL ITEMS CAN BE ADDED BY CONTRACTOR AFTER DISCUSSION WITH THE DESIGN TEAM.

2. PROTECT ALL EXISTING EQUIPMENT TO REMAIN, KEEP FREE OF DUST.

3. SEE ANNOTATED PLAN FOR MODIFICATIONS MADE TO EXISTING WALLS & CEILINGS TO BECOME 1-HR FIRE BARRIERS.

4. PROTECT ALL LIGHT FIXTURES & CEILINGS TO REMAIN.

**KEYED NOTES** 

- 201.0 REMOVE EXISTING GYP BD CEILING & FIRE PROOFING TO ENABLE WALLS TO EXTEND TO UNDERSIDE OF DECK
- 233.0 EXISTING CEILING TO REMAIN, PROTECT DURING CONSTRUCTION
- REMOVE AND DISCARD CEILING, SALVAGE LIGHT FIXTURES AND DIFFUSERS SEE REFLECTED Y~CEILUNG/PLAN~ Y~ Y~ Y~ Y~ Y~ Y~
- 237.0 REMOVE CEILING TILE WITH LIGHT SENSOR, INSTALL IN NEW LOCATION PER ELEC DWGS. REPLACE WITH OTHER CEILING TILE IT IS REPLACING






REV DATE DESCRIPTION 2 09.02.21

VCBO NUMBER: **CLIENT NUMBER:** DATE:

JULY 27, 2021

**DEMO RCP** A111.0C



DEMO REFLECTED CEILING PLAN

SCALE: 1/8" = 1'-0"





524 SOUTH 600 EAST

SALT LAKE CITY, UT 84102



 REV
 DATE
 DESCRIPTION

 2
 09.02.21
 ADD 04


VCBO NUMBER: 2156
CLIENT NUMBER:

JULY 27, 2021

DATE:

## DAINIPPON PHARMA

SYNO I KAVEKSE MOUNIAIN BL SI DEDMIT & DID CET



3	4	5	
GENERAL SHEET NOTES	GENERAL SHEET NOTES	○SHEET KEYNOTES	
1 EVERY EFFORT HAS BEEN MADE TO SHOW EXISTING DEVICES THAT NEED TO BE DEMOLISHED ON WALLS AND CEILINGS, BUT EXACT SCOPE MUST BE CONFIRMED ON-SITE.	8 ALL ITEMS INDICATED TO REMAIN SHALL BE PROTECTED DURING ALL PHASES OF CONSTRUCTION.	1 RELOCATE SWITCH AND CONTROLS PER NEW LIGHTING PLANS.  2 RELOCATE LIGHTING SENSOR, COORDINATE EXACT LOCATION WITH OWNER.	<b>}</b> ∕₃∖
2 UNLESS NOTED OTHERWISE REMOVE ALL LIGHTING FIXTURES DEVICES AND EQUIPMENT SHOWN DASHED. REMOVE CONDUIT AND WIRING BACK TO PANELBOARD OF ORIGIN OR TO FIRST ACTIVE DEVICE THAT REMAINS.	9 DEVICES MARKED "(RR)" ARE TO BE REMOVED AND RELOCATED PER NEW PLANS. EXTEND CIRCUITING AS REQUIRED FOR RELOCATION.		
3 SALVAGE ALL LIGHT FIXTURES, TWIST-LOCK RECEPTACLES AND WALLPLATES, CEILING SPEAKERS AND SECURITY AND FIRE ALARM DEVICES TO OWNER. PROTECT SALVAGED EQUIPMENT FROM DAMAGE.			
4 PRIOR TO REMOVAL OF ANY ELECTRICAL EQUIPMENT OR WIRING, FIELD VERIFY THAT THE EQUIPMENT OR WIRING IS INACTIVE OR NO LONGER IN USE.			D
REMOVE ALL FIRE ALARM DEVICES WHERE EXISTING WALLS AND CEILINGS ARE BEING REMOVED, WITH ASSOCIATED CONDUIT AND WIRING. EXISTING FIRE ALARM DEVICES AND SYSTEM NOT INDICATED FOR REMOVAL SHALL REMAIN ACTIVE THROUGHOUT DEMOLITION AND CONSTRUCTION UNTIL THE NEW SYSTEM IS TESTED AND OPERATIONAL. MAINTAIN ALL CLASS A FIRE ALARM INITIATING AND INDICATING LOOPS WHERE EXISTING DEVICES ARE REMOVED.			
6 CONTRACTOR TO TRACE AND LABEL ALL EXISTING LOADS TO REMAIN, THAT ARE CURRENTLY FED FROM PANELS THAT ARE BEING DEMOLISHED IN THIS PHASE. THESE LOADS TO BE RE-FED FROM NEW PANELS IN NEXT PHASE.			
7 REFER TO ARCHITECTURAL DRAWINGS FOR REMOVAL OF MOTORS, CONDUIT, CONDUCTOR AND CONTROL WIRING ASSOCIATED WITH EXISTING PARTITIONS AND LIGHTING.			






REV DATE DESCRIPTION 1 08/05/2021 ADDENDUM #01 2 09/02/2021 ADDENDUM #04


VCBO NUMBER: **CLIENT NUMBER:** DATE:

SPECTRUM ENGINEERS 324 S. State St., Suite 400 Salt Lake City, UT 84111 800-678-7077 801-328-5151

fax: 801-328-5155 www.spectrum-engineers.com

SUMITOMO LEVEL 1 CEILING DEMOLITION PLAN ED101B









 REV
 DATE
 DESCRIPTION

 1
 08/05/2021
 ADDENDUM #01

 2
 09/02/2021
 ADDENDUM #04

 VCBO NUMBER:
 21560

 CLIENT NUMBER:
 07/27/2021

SPECTRUM
ENGINEERS
324 S. State St., Suite 400
Salt Lake City, UT 84111
800-678-7077
801-328-5151
fax: 801-328-5155

Salt Lake City, UT 84111 800-678-7077 801-328-5151 fax: 801-328-5155 www.spectrum-engineers.com

## DAINIPPON PHARMA T

ORGE COMPANIES 00 TRAVERSE MOUNTAIN BLVD, SUITE 100

