

Scope of work

Remodel of restrooms on two floors . 4 total

Remove vinyl floor and float floor to have positive slope to drain

Remove counter and sinks

Remove toilet partitions and all accessories

Remove wall coverings

Remove doors (reuse hardware)

1.Install new ceramic tile floor and tile wainscoat 4'

Floor tile 8"x8" Empress white A215 crossville

Wall field 1"x2" Sauge SE 66 am. Olean

Trim 3" tall Base 6" tall accent

Float floors to drain

2. Paint walls and ceilings (epoxy paint)

Stain and finish doors and paint frames

3.New stone/ marble/cultured counter tops

4.New toilet partitions and accessories (grab bars, mirrors, etc.)

5. New lights above vanities. Replace 2x4 lights in ceilings withLED

6. New sinks at vanities (price to replace toilets and urinals separately)

Any other questions please contact Craig saunders 801-668=0446