



JRCA Architects  
Galloway & Company, Inc.

Salt Lake Office:  
577 South 200 East  
Salt Lake City, Utah 84111  
(801) 533-2100 Phone

Corporate Office:  
6162 S. Willow Drive, Suite 320

## ADDENDUM NUMBER ONE

<b>DATE OF ISSUANCE:</b>	9 <sup>th</sup> December, 2021	<b>PROJECT NUMBER:</b>	21031
<b>PROJECT:</b>	Riverton Hospital Fluoro Room Remodel 3741 W 12600 S Riverton, UT 84065	<b>ARCHITECT:</b>	JRCA Architects a Galloway Company 577 South 200 East Salt Lake City, Utah 84111
<b>OWNER:</b>	Facility Design & Construction Intermountain Healthcare 36 South State Street Salt Lake City, UT 84111		

Incorporate the following revisions to the Specifications, Drawings, and other Contract Documents of the project named above. General Items are not referenced. Revisions to the Specifications are referenced by section, page number, and paragraph number. Revisions to the Drawings are referenced by the drawing sheet number. This Addendum forms part of the Construction Documents.

The end of this Addendum is indicated by the note "END OF ADDENDUM." Attachments are located at the end of the Addendum and are referenced in the Amendment.

### General Items:

<u>Item No.</u>	<u>Section or Sheet No.</u>	<u>Description</u>
GI-01	Bid Questions	The only demolition in the project is limited specifically to the new equipment and lighting.
GI-02	Bid Questions	All electrical outlets the control room and staff areas are considered existing.
GI-02	Bid Questions	All electrical outlets the control room and staff areas are considered ``
GI-03	Bid Questions	There will be no communications in the scope of this project.
GI-04	Bid Questions	There is no specification for the wall duct. The information for the wall duct is below.
		The contractor will supply and install the item. Page 13 of the drawings: 2 10" x 3 1/2" [250mm x 100mm] Flush wall duct with minimum 2 dividers 3 10" x 3 1/2" [250mm x 100mm] Surface wall duct with minimum 2 dividers 4 10" x 3 1/2" [250mm x 100mm] Surface wall duct to bottom of PDU with minimum 2 dividers
		Wiremold or Walker duct are approved brands

### Specification Items:

<u>Item No.</u>	<u>Section or Sheet No.</u>	<u>Description</u>
-----------------	-----------------------------	--------------------

### Drawing Items:

<u>Item No.</u>	<u>Section or Sheet No.</u>	<u>Description</u>
AR-01	G1101	Title of Code Analysis was updated to read Riverton Hospital. Projects Square Footage was added to code analysis

### Civil Items:

<u>Item No.</u>	<u>Section or Sheet No.</u>	<u>Description</u>
-----------------	-----------------------------	--------------------

**Landscaping Items:**

<u>Item No.</u>	<u>Section or Sheet No.</u>	<u>Description</u>
-----------------	-----------------------------	--------------------

**Structural Items:**

<u>Item No.</u>	<u>Section or Sheet No.</u>	<u>Description</u>
ST-01	S101	Adjustments made to Unistrut framing detail 2.
ST-02	S501	Updated Unistrut details details 1&2.

**Mechanical & Plumbing Items:**

<u>Item No.</u>	<u>Section or Sheet No.</u>	<u>Description</u>
-----------------	-----------------------------	--------------------

**Electrical Items:**

<u>Item No.</u>	<u>Section or Sheet No.</u>	<u>Description</u>
-----------------	-----------------------------	--------------------

**END OF ADDENDUM ONE**