

specifications

September 2019

Southridge Park Restroom
Replacement - Taylorsville

5051 South 4015 West
Taylorsville, UTAH 84118

project manual

Owner



prepared by;

ajc architects

703 east 1700 south, salt lake city, utah 84105

project no. 1859.01



THIS PAGE INTENTIONALLY LEFT BLANK

**PROJECT MANUAL
TABLE OF CONTENTS**

Southridge Park Restroom Replacement - Taylorsville
5051 South 4015 West, Taylorsville, Utah 84118

Section	Title	Pages
000107	SEALS PAGE	1 – 2
000110	PROJECT MANUAL TABLE OF CONTENTS	1 – 6
DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS		
002600	PROCUREMENT SUBSTITUTION PROCEEDURES	1 – 2
002605	CSI FORM 1.5C SUBSTITUTION REQUEST	1 – 2
DIVISION 01 - GENERAL REQUIREMENTS		
010000	GENERAL REQUIREMENTS	1 – 4
011000	SUMMARY	1 – 4
012500	SUBSTITUTION PROCEDURES	1 – 4
	SUBSTITUTION REQUEST FORM	1 – 2
012600	CONTRACT MODIFICATION PROCEDURES	1 – 2
012900	PAYMENT PROCEDURES	1 – 4
013100	PROJECT MANAGEMENT AND COORDINATION	1 – 10
013200	CONSTRUCTION PROGRESS DOCUMENTATION	1 – 8
013233	PHOTOGRAPHIC DOCUMENTATION	1 – 4
013300	SUBMITTAL PROCEDURES	1 – 8
	SUBMITTAL TRANSMITTAL	1 – 2
	AJC ELECTRONIC RELEASE FORM	1 – 2
014000	QUALITY REQUIREMENTS	1 – 8
015000	TEMPORARY FACILITIES AND CONTROLS	1 – 6
015639	TREE PROTECTION	1 – 3
016000	PRODUCT REQUIREMENTS	1 – 6
017300	EXECUTION	1 – 8
017419	CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL	1 – 4
017700	CLOSEOUT PROCEDURES	1 – 6
017823	OPERATION AND MAINTENANCE DATA	1 – 4
017839	PROJECT RECORD DOCUMENTS	1 – 4
017900	DEMONSTRATION AND TRAINING	1 – 4
DIVISION 02 - EXISTING CONDITIONS		
024119	SELECTIVE DEMOLITION AND REPAIR	1 - 3
DIVISION 03 - CONCRETE		
033000	CAST-IN-PLACE CONCRETE	1 - 20
DIVISION 04 - MASONRY		
042200	CONCRETE UNIT MASONRY	1 – 10
DIVISION 05 - METALS		
055000	METAL FABRICATIONS	1 – 10

DIVISION 06 - WOOD AND PLASTICS

061053	MISCELLANEOUS ROUGH CARPENTRY	1 - 6
061600	SHEATHING	1 - 4
064000	PLASTIC PANELING	1 - 4

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

071113	BITUMINOUS DAMPPROOFING	1 - 4
072100	THERMAL INSULATION	1 - 4
074113.16	STANDING-SEAM METAL ROOF PANELS	1 - 8
076200	SHEET METAL FLASHING AND TRIM	1 - 10
079200	JOINT SEALANTS	1 - 8

DIVISION 08 - DOORS AND WINDOWS

081113	HOLLOW METAL DOORS AND FRAMES	1 - 6
083323	OVERHEAD COILING DOORS	1 - 6
084523	FIBERGLASS SANDWICH PANEL ASSEMBLIES	1 - 6

DIVISION 09 - FINISHES

099600	HIGH-PERFORMANCE COATINGS	1 - 6
--------	---------------------------	-------

DIVISION 10 - SPECIALTIES

102800	TOILET, BATH, AND LAUNDRY ACCESSORIES	1 - 4
--------	---------------------------------------	-------

DIVISION 11 – EQUIPMENT

(NOT USED)

DIVISION 12 – FURNISHINGS

(NOT USED)

DIVISION 13 - SPECIAL CONSTRUCTION

(NOT USED)

DIVISION 14 - CONVEYING SYSTEMS

(NOT USED)

DIVISION 21- FIRE SUPPRESSION

(NOT USED)

DIVISION 22 – PLUMBING

22 01 00	GENERAL REQUIREMENTS	1 - 14
22 05 00	COMMON WORK RESULTS FOR PLUMBING	1 - 8
22 05 19	METERS AND GAUGES FOR PLUMBING PIPING	1 - 6
22 05 23	GENERAL-DUTY VALVES FOR PLUMBING PIPING	1 - 8
22 05 29	HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT	1 - 12
22 05 48	VIBRATION AND SEISMIC CONTROLS FOR PLUMBING PIPING AND EQUIPMENT	1 - 8
22 05 53	PLUMBING IDENTIFICATION	1 - 4
22 07 00	PLUMBING INSULATION	1 - 14
22 11 16	DOMESTIC WATER PIPING	1 - 12
22 11 19	DOMESTIC WATER PIPING SPECIALTIES	1 - 8
22 13 16	SANITARY WASTE AND VENT PIPING	1 - 6
22 13 19	SANITARY WASTE PIPING SPECIALTIES	1 - 8
22 33 00	ELECTRIC WATER HEATERS	1 - 6
22 46 00	SECURITY PLUMBING FIXTURES	1 - 6

DIVISION 23 - HEATING, VENTILATIONING, AND AIR CONDITIONING

23 01 00	GENERAL REQUIREMENTS	1 - 2
23 05 00	COMMON WORK RESULTS FOR HVAC	1 - 2
23 05 13	COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT	1 - 2
23 05 29	HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT	1 - 2
23 05 48	VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT	1 - 2
23 05 53	MECHANICAL IDENTIFICATION	1 - 2
23 05 93	TESTING, ADJUSTING, AND BALANCING FOR HVAC	1 - 10
23 07 00	HVAC INSULATION	1 - 2
23 31 13	METAL DUCTS	1 - 14
23 33 00	DUCT ACCESSORIES	1 - 8
23 34 23	EXHAUST FANS	1 - 6
23 37 13	DIFFUSERS, REGISTERS, AND GRILLES	1 - 4
23 37 14	LOUVERS AND VENTS	1 - 6

DIVISION 25 - INTERGRATED AUTOMATION

(NOT USED)

DIVISION 26 – ELECTRICAL

260500	ELECTRICAL GENERAL PROVISIONS	1 – 10
260501	MECHANICAL AND ELECTRICAL COORDINATION	1 – 4
260502	ELECTRICAL SUBMITTALS, O & M MANUALS AND SPARE PARTS	1 - 10
260507	ELECTRICAL CONNECTIONS FOR EQUIPMENT	1 - 2
260519	CONDUCTORS AND CABLES	1 - 4
260526	GROUNDING	1 - 4
260529	SUPPORTING DEVICES	1 - 2
260532	CONDUIT RACEWAY	1 - 6
260533	ELECTRICAL BOXES AND FITTINGS	1 - 4
260553	ELECTRICAL IDENTIFICATION	1 - 6
260923	OCCUPANCY SENSORS	1 - 8
260943	LIGHTING CONTROL EQUIPMENT	1 – 6
262200	TRANSFORMERS	1 - 5
262413	SWITCHGEAR AND SWITCHBOARDS	1 - 4
262416	PANELBOARDS	1 - 2
262726	WIRING DEVICES	1 - 4
262815	OVERCURRENT PROTECTIVE DEVICES	1 - 4
262816	MOTOR AND CIRCUIT DISCONNECTS	1 - 2
262913	MOTOR STARTERS	1 – 4
264313	SURGE PROTECTIVE DEVICES (SPD)	1 - 6
265100	INTERIOR AND EXTERIOR BUILDING LIGHTING	1 - 4

DIVISION 27 – COMMUNICATIONS

(NOT USED)

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

283111	FIRE ALARM AND DETECTION SYSTEM	1 - 8
--------	---------------------------------	-------

DIVISION 31 - EARTHWORK

311010	PAVEMENT REMOVAL	1 – 3
312326	COMPACTION	1 – 2

DIVISION 32 - EXTERIOR IMPROVEMENTS

321123	CRUSHED AGGREGATE BASE	1 – 5
321313	CONCRETE PAVING	1 – 5
328400	UNDERGROUND IRRIGATION SYSTEMS	1 – 19
329113	SOIL PREPARATION	1 – 6
329119	LANDSCAPE GRADING	1 – 3
329200	TURF AND GRASSES	1 – 10

DIVISION 33 - UTILITIES

330502	BACKFILLING TRENCHES	1 – 5
321100	WATER DISTRIBUTION AND TRANSMISSION	1 – 6
333100	SANITARY SEWERAGE SYSTEMS	1 – 4

DOCUMENT 00 26 00

PROCUREMENT SUBSTITUTION PROCEDURES

1.1 DEFINITIONS

- A. Procurement Substitution Requests: Requests for changes in products, materials, equipment, and methods of construction from those indicated in the Procurement and Contracting Documents, submitted prior to receipt of bids.
- B. Substitution Requests: Requests for changes in products, materials, equipment, and methods of construction from those indicated in the Contract Documents, submitted following Contract award. See Section 012500 "Substitution Procedures" for conditions under which Substitution requests will be considered following Contract award.

1.2 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

1.3 PROCUREMENT SUBSTITUTIONS

- A. Procurement Substitutions, General: By submitting a bid, the Bidder represents that its bid is based on materials and equipment described in the Procurement and Contracting Documents, including Addenda. Bidders are encouraged to request approval of qualifying substitute materials and equipment when the Specifications Sections list materials and equipment by product or manufacturer name.
- B. Procurement Substitution Requests will be received and considered by Owner when the following conditions are satisfied, as determined by Architect; otherwise requests will be returned without action:
 - 1. Extensive revisions to the Contract Documents are not required.
 - 2. Proposed changes are in keeping with the general intent of the Contract Documents, including the level of quality of the Work represented by the requirements therein.
 - 3. The request is fully documented and properly submitted.

1.4 SUBMITTALS

- A. Procurement Substitution Request: Submit to Architect. Procurement Substitution Request must be made in writing in compliance with the following requirements:
 - 1. Requests for substitution of materials and equipment will be considered if received no later than 10 days prior to date of bid opening.
 - 2. Submittal Format: Submit three copies of each written Procurement Substitution Request, using or CSI Substitution Request Form 1.5C, or one electronic submittal.
 - a. Identify the product or the fabrication or installation method to be replaced in each request. Include related Specifications Sections and drawing numbers.
 - b. Provide complete documentation on both the product specified and the proposed substitute, including the following information as appropriate:
 - 1) Point-by-point comparison of specified and proposed substitute product data, fabrication drawings, and installation procedures.
 - 2) Copies of current, independent third-party test data of salient product or system characteristics.
 - 3) Samples where applicable or when requested by Architect.

- 4) Detailed comparison of significant qualities of the proposed substitute with those of the Work specified. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
 - 5) Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - 6) Research reports, where applicable, evidencing compliance with building code in effect for Project, from ICC-ES.
 - 7) Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors, which will become necessary to accommodate the proposed substitute.
- c. Provide certification by manufacturer that the substitute proposed is equal to or superior to that required by the Procurement and Contracting Documents, and that its in-place performance will be equal to or superior to the product or equipment specified in the application indicated.
 - d. Bidder, in submitting the Procurement Substitution Request, waives the right to additional payment or an extension of Contract Time because of the failure of the substitute to perform as represented in the Procurement Substitution Request.
- B. Architect's Action:
1. Architect may request additional information or documentation necessary for evaluation of the Procurement Substitution Request. Architect will notify all bidders of acceptance of the proposed substitute by means of an Addendum to the Procurement and Contracting Documents.
- C. Architect's approval of a substitute during bidding does not relieve Contractor of the responsibility to submit required shop drawings and to comply with all other requirements of the Contract Documents.

END OF DOCUMENT

CSI Form 1.5C

**SUBSTITUTION
REQUEST**
(During the Bid Period)

Project: _____ Substitution Request Number: _____

From: _____

To: _____ Date: _____

A/E Project Number: _____

Re: _____ Contract For: _____

Specification Title: _____ Description: _____

Section: _____ Page: _____ Article/Paragraph: _____

Proposed Substitution: _____

Manufacturer: _____ Address: _____ Phone: _____

Trade Name: _____ Model No.: _____

Attached data includes product description, specifications, drawings, photographs, and performance and test data adequate for evaluation of the request; applicable portions of the data are clearly identified.

Attached data also includes a description of changes to the Contract Documents that the proposed substitution will require for its proper installation.

The Undersigned certifies:

- Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product.
- Same warranty will be furnished for proposed substitution as for specified product.
- Same maintenance service and source of replacement parts, as applicable, is available.
- Proposed substitution will have no adverse effect on other trades and will not affect or delay progress schedule.
- Proposed substitution does not affect dimensions and functional clearances.
- Payment will be made for changes to building design, including A/E design, detailing, and construction costs caused by the substitution.

Submitted by: _____

Signed by: _____

Firm: _____

Address: _____

Telephone: _____

A/E's REVIEW AND ACTION

- Substitution approved - Make submittals in accordance with Specification Section 01 25 00 Substitution Procedures.
- Substitution approved as noted - Make submittals in accordance with Specification Section 01 25 00 Substitution Procedures.
- Substitution rejected - Use specified materials.
- Substitution Request received too late - Use specified materials.

Signed by: _____

Date: _____

Supporting Data Attached: Drawings Product Data Samples Tests Reports _____

THIS PAGE IS INTENTIONALLY LEFT BLANK

SECTION 01 00 00
GENERAL REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes general requirements that are to apply to all Work throughout the Project. Requirements included in this Section are to apply to all other specification Sections.
- B. Refer to Construction Agreement for other requirements by the General Contractor, Subcontractors, suppliers, etc.

1.3 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Center of...": Indicates a specific single point at the exact center of the tile, panel, or other surface indicated.
- D. "Contractor": The General Contractor unless otherwise stated.
- E. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "approved," "required," and "permitted" have the same meaning as "directed."
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- H. "Install": Operations at Project site including unloading, temporarily storing, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
- I. "Project Manager": The Contractor's project manager.
- J. "Project Representative": The Owner's project representative(s).
- K. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.
- L. "Provide": Furnish and install, complete and ready for the intended use.
- M. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- N. "Related Sections": Related Sections articles are included herein as a courtesy to assist in the locating of items in the specifications that the reader might expect to find in the Section but that are specified elsewhere. The list of sections may or may not be complete. 'Related Sections' articles do not relieve the Contractor of the contractual

obligation to perform to all the Contract Documents or to coordinate who does what amongst the team of subcontractors.

1.4 SITE INSPECTION

- A. Examine the premises and site and compare them with the drawings and specifications.
- B. Become familiar with existing conditions such as obstructive areas, excavating or filling, and any problems related to construction. No allowances will subsequently be made by reason of failure to examine the site.

1.5 SCOPE OF THE WORK

- A. See Division 01 Section 01100 "Summary" for an overall general summary of the Work.
- B. Unless otherwise provided, all materials, labor, equipment, tools, transportation, and utilities necessary for the successful completion of the Project shall be provided at the expense of the Contractor.
- C. Requirements of the Work are contained in the Contract Documents, and include cross-references herein to published information, which is not necessarily bound therewith.
- D. Provide, as part of the Bid and without additional charge, all incidental items required for completion of the Work, even if not specifically indicated.
 - 1. Install all Work so that its several component parts function together as a complete and workable system, and with all equipment properly adjusted and in working order.
- E. Conform to highest quality standards for materials and workmanship to execute Work that is indicated or specified and that is necessary to fully satisfy the Contract Document requirements for a complete, finished, acceptable installation regardless of whether indicated or specified or not.
- F. Responsibilities of the Contractor includes the responsibility to verify all field measurements of actual building conditions so that all Work fits properly in the locations indicated and specified. Protect existing structures, improvements, trees, and other items from physical damage, unless identified to be removed.
- G. Any existing surfaces, furniture or equipment that are damaged by the Contractor are to be restored to their original condition, or better, to the satisfaction of the Owner.
- H. Contractor is to restore any roads, utilities, walks, curbs, gutters or other existing conditions that are used for construction and are damaged, to the same condition as they existed prior to commencement of construction. Where existing conditions are damaged, they shall be replaced by new Work to match existing adjacent Work, or repaired, if acceptable to Project Representative, at no cost to Owner.

1.6 WORKERS

- A. The Contractor is to enforce strict discipline and good order among his/her employees at all times and shall not employ on the Project any unfit person or anyone not skilled in the Work assigned to him/her.
- B. Consumption of alcohol, smoking or any other controlled, non-medically prescribed substance will not be allowed on the Project.
- C. Contractor shall rectify behavior unacceptable to the Owner or Owner's Project Representative by strict enforcement of discipline. Owner reserves the right to request dismissal of individual workers for failure to comply with standards of behavior communicated to the Contractor.

1.7 MANUFACTURER'S DIRECTIONS

- A. Manufactured articles, materials, or equipment shall be applied, installed, connected, erected, used, cleaned, and conditioned in accordance with the Manufacturer's printed directions unless otherwise indicated in the Contract Documents.

1.8 FASTENERS

- A. Unless noted otherwise, the trade requiring the fastening of its Work to any substrate or support is responsible for provision and installation of requisite fasteners.

1.9 PENETRATIONS

- A. The sealing of all penetrations in fire-rated, acoustically-rated or structural partitions and separations is the responsibility of the trade making or requiring the penetration.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 10 00

SUMMARY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes:
1. Project information.
 2. Work covered by Contract Documents.
 3. Access to site.
 4. Coordination with occupants.
 5. Specification and drawing conventions.

1.3 PROJECT INFORMATION

- A. Project Identification: Southridge Park Restroom Replacement - Taylorsville
B. Project Location: 5051 South 4015 West, Taylorsville, Utah 84118
C. Owner: Salt Lake County Parks and Recreation
2001 State St S4-700
Salt Lake City, UT 84190
1.385.468.1800
- D. Architect: ajc architects;
703 East 1700 South
Salt Lake City, Utah 84105
Ph#: 801.466.8818
Contact: Jill Jones
- E. Architect's Consultants: The Architect has retained the following design professionals who have prepared designated portions of the Contract Documents:
1. Structural **MJ Structural Engineers**
5673 South Redwood Road
Salt Lake City, Ut 84123
1.801.905.1097
Contact: Matt Jackson
 2. Mechanical/Plumbing: **WHW Engineering Inc**
8619 Sandy Parkway
Sandy, Utah 84070
1.801.466.4021
Contact: Win Packer.
 3. Electrical: **BNA Consulting**
635 South State Street
Salt Lake City, Utah 84111
1.801.532.2196
Contact: Gopichand Pulivarthi
 4. Landscape: **Arcsitio Design, Inc.**
1058 West 2100 South
Salt Lake City, Utah 84106
1.801.487.4923

1.4 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work of the Project is defined by the Contract Documents and consists of the following:

Project Description:

The project consists of two (2) new restroom buildings located within the park. The construction of the buildings are concrete masonry units with wood framed roof and will have facilities for Men and Women and shall be fully ADA accessible.

1.5 ACCESS TO SITE

- A. General: Contractor shall have full use of Project site for construction operations during construction period. Contractor's use of Project site is limited only by Owner's right to perform work or to retain other contractors on portions of Project.
- B. Use of Site: Limit use of Project site to work only in areas shown on the contract documents. Do not disturb portions of the site beyond areas in which the Work is indicated unless approved in writing prior to work.
1. Driveways, Walkways and Entrances: Keep driveways, parking, loading areas, and entrances serving premises clean and clear in the event of an emergency.
 - a. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- C. Condition of Existing Building: Maintain existing building, affected by construction operations, in a weathertight condition throughout construction period. Repair damage caused by construction operations.

1.6 COORDINATION WITH OCCUPANTS

- A. Partial Occupancy: The Park will be open to the public during entire construction period, with the exception of areas under construction. Cooperate with City and Park users during construction operations to minimize conflicts and facilitate Park usage. Perform the Work so as not to interfere with Park operations.
1. Maintain access to existing walkways, and other adjacent occupied or used facilities. Do not close or obstruct walkways, or other occupied or used facilities without written permission from Owner and authorities having jurisdiction.
 2. Provide not less than 72 hours' notice to Owner of activities that will affect Park operations.
 3. Architect will prepare a Certificate of Substantial Completion for each specific portion of the Work to be occupied prior to Owner acceptance of the completed Work.
 4. Obtain a Certificate of Occupancy from authorities having jurisdiction before limited Owner occupancy.
 5. Before limited Owner occupancy, mechanical and electrical systems shall be fully operational, and required tests and inspections shall be successfully completed. On occupancy, Owner will operate and maintain mechanical and electrical systems serving occupied portions of Work.
 6. On occupancy, Owner will assume responsibility for maintenance and custodial service for occupied portions of Work.

1.7 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:

1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
 2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.
- B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.
- C. Drawing Coordination: Requirements for materials and products identified on the Drawings are described in detail in the Specifications. One or more of the following are used on the Drawings to identify materials and products:
1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
 2. Keynoting: Materials and products are identified by reference keynotes referencing Specification Section numbers found in this Project Manual.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 25 00

SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Sections:
 - 1. Section 00 26 00 "Procurement Substitution Procedures."
 - 2. Section 01 60 00 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.
 - 3. Divisions 02 through 49 Sections for specific requirements and limitations for substitutions.

1.3 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.
 - 1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
 - 2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required in order to meet other Project requirements but may offer advantage to Owner.

1.4 SUBMITTALS

- A. Substitution Requests: Submit electronic submittal of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution Request Form: Use attached standard Substitution Request form, acceptable to Owner.
 - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified product or fabrication, or installation cannot be provided, if applicable.
 - b. Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors, that will be necessary to accommodate proposed substitution.
 - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable specification section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.

- d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - e. Samples, where applicable or requested.
 - f. Certificates and qualification data, where applicable or requested.
 - g. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.
 - h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
 - j. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
 - k. Cost information, including a proposal of change, if any, in the Contract Sum.
 - l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
 - m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
- a. Forms of Acceptance: Owner's Change Order form, Owner's Construction Change Directive form, or Architect's Supplemental Instructions for minor changes in the Work.
 - b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.5 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage qualified testing agency to perform compatibility tests recommended by manufacturers.

1.6 PROCEDURES

- A. Coordination: Modify or adjust affected work as necessary to integrate work of the approved substitutions.

PART 2 - PRODUCTS

2.1 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately upon discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
 - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied,

Architect will return requests without action, except to record noncompliance with these requirements:

- a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - b. Substitution request is fully documented and properly submitted.
 - c. Requested substitution will not adversely affect Contractor's construction schedule.
 - d. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - e. Requested substitution is compatible with other portions of the Work.
 - f. Requested substitution has been coordinated with other portions of the Work.
 - g. Requested substitution provides specified warranty.
 - h. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- B. Substitutions for Convenience: Architect will consider requests for substitution if received prior to the issuance of the last addenda during the bidding period. Requests received after that time may be considered or rejected at discretion of Architect.
1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
 - a. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
 - b. Requested substitution does not require extensive revisions to the Contract Documents.
 - c. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - d. Substitution request is fully documented and properly submitted.
 - e. Requested substitution will not adversely affect Contractor's construction schedule.
 - f. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - g. Requested substitution is compatible with other portions of the Work.
 - h. Requested substitution has been coordinated with other portions of the Work.
 - i. Requested substitution provides specified warranty.
 - j. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

PART 3 - EXECUTION (Not Used)

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK



SUBSTITUTION REQUEST (After the Bidding Phase)

Project: _____ Substitution Request Number: _____

 From: _____
 To: _____ Date: _____

 A/E Project Number: _____
 Re: _____ Contract For: _____

Specification Title: _____ Description: _____
 Section: _____ Page: _____ Article/Paragraph: _____

Proposed Substitution: _____
 Manufacturer: _____ Address: _____ Phone: _____
 Trade Name: _____ Model No.: _____
 Installer: _____ Address: _____ Phone: _____

History: New product 2-5 years old 5-10 yrs old More than 10 years old

Differences between proposed substitution and specified product: _____

Point-by-point comparative data attached - REQUIRED BY A/E

Reason for not providing specified item: _____

Similar Installation:
 Project: _____ Architect: _____
 Address: _____ Owner: _____
 _____ Date Installed: _____

Proposed substitution affects other parts of Work: No Yes; explain _____

Savings to Owner for accepting substitution: _____ (\$ _____).

Proposed substitution changes Contract Time: No Yes [Add] [Deduct] _____ days.

Supporting Data Attached: Drawings Product Data Samples Tests Reports _____

SUBSTITUTION REQUEST (Continued)

The Undersigned certifies:

- Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product.
- Same warranty will be furnished for proposed substitution as for specified product.
- Same maintenance service and source of replacement parts, as applicable, is available.
- Proposed substitution will have no adverse effect on other trades and will not affect or delay progress schedule.
- Cost data as stated above is complete. Claims for additional costs related to accepted substitution which may subsequently become apparent are to be waived.
- Proposed substitution does not affect dimensions and functional clearances.
- Payment will be made for changes to building design, including A/E design, detailing, and construction costs caused by the substitution.
- Coordination, installation, and changes in the Work as necessary for accepted substitution will be complete in all respects.

Submitted by: _____

Signed by: _____

Firm: _____

Address: _____

Telephone: _____

Attachments: _____

A/E's REVIEW AND ACTION

- Substitution approved - Make submittals in accordance with Specification Section 01330.
- Substitution approved as noted - Make submittals in accordance with Specification Section 01330.
- Substitution rejected - Use specified materials.
- Substitution Request received too late - Use specified materials.

Signed by:

Date:

Additional Comments: Contractor Subcontractor Supplier Manufacturer A/E _____

SECTION 01 26 00
CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for handling and processing Contract modifications.
- B. Related Requirements:
 - 1. Section 012500 "Substitution Procedures" for administrative procedures for handling requests for substitutions made after the Contract award.
 - 2. Section 016000 "Product Requirements" for administrative procedures for handling requests for substitutions made after contract award.

1.3 CHANGES IN THE WORK

- A. Any changes in the work of this contract due to discovered conditions or project scope modifications are subject to the following requirements:
 - 1. A "Request for Proposal" shall be issued to the Contractor by the Architect clearly stating the exact conditions of the proposed change in the work or a "Request for Change" shall be issued to the Architect by the Contractor for review and acceptance.
 - 2. The Contractor shall provide a written "Proposal" identifying the specific material and labor required to complete the change in the work. The Proposal shall completely itemize all material quantities, unit costs, labor estimates, hourly rates, and mark-up factors calculated in the overall cost. Material costs shall not exceed those listed at established market levels and labor costs shall not exceed those listed at Journeyman schedules as established for this region by current year R.S.Means.
 - a. Direct subcontractor and/or contractor mark-up for profit, overhead and administrative costs shall not exceed a combined total of 15% of the itemized costs for material supplied and labor directly performed by that individual firm. Additional contractor mark-up on subcontractor work is limited to 5% of the work of those other subcontractor amount. A maximum additional performance bond mark-up of 1%, or the actual bond cost rate as verified by the bonding company, will also be allowed as valid mark-up as part of the Contractor's submittals.
 - b. No other mark-ups are allowed. (i.e. project management, supervision)
 - 3. The Architect shall review and certify all Contractor's proposals and shall issue to the County a justification statement for all proposed changes. Execution of formal change orders is a time consuming process which could delay action on critical work. Any work performed prior to the issuance of the official change order is at the contractor's risk. However, the County Project Manager will endeavor to minimize that risk through the expeditious processing of all change order items. Full, complete and detailed information on each item by the contractor will aid in that process.

4. Change Authorizations: A construction change authorization form will be issued by the County under special circumstances, to authorize immediate completion of changes in the work. The form will be prepared and completed by the Architect when time limits are such that the formal change order will cause unreasonable delays or additional costs to the project. The form will include a fixed or estimated cost to be included as part of a change order at the earliest possible date. All forms should be numbered consecutively, beginning with number one of each project. Electronic format shall be used. The Architect shall maintain a log for construction change authorizations throughout the entire construction phase.ct's supplemental Instruction (ASI).

1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
 2. Within time specified in Proposal Request or 20 days, when not otherwise specified, after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and supervision directly attributable to the change.
 - d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 - e. Quotation Form: Use forms acceptable to Architect.
- B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect, on a proposal request form acceptable to Architect.
 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 4. Include costs of labor and supervision directly attributable to the change.
 5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
 7. Proposal Request Form: Use form acceptable to Architect.

1.5 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Work Change Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor.

1.6 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Architect may issue a Construction Change Directive. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 - 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
 - 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 29 00

PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Requirements:
 - 1. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
 - 2. Section 013200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.3 DEFINITIONS

- A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule. Cost-loaded Critical Path Method Schedule may serve to satisfy requirements for the schedule of values.
 - 1. Coordinate line items in the schedule of values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with continuation sheets.
 - b. Submittal schedule.
 - c. Items required to be indicated as separate activities in Contractor's construction schedule.
 - 2. Submit the schedule of values to Architect at earliest possible date, but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one-line item for each Specification Section.
 - 1. Identification: Include the following Project identification on the schedule of values:
 - a. Project name and location.
 - b. Name of Architect.
 - c. Architect's Project number.
 - d. Contractor's name and address.
 - e. Date of submittal.

2. Arrange the schedule of values in tabular form, with separate columns to indicate the following for each item listed:
 - a. Related Specification Section or Division.
 - b. Description of the Work.
 - c. Name of subcontractor.
 - d. Name of manufacturer or fabricator.
 - e. Name of supplier.
 - f. Change Orders (numbers) that affect value.
 - g. Dollar value of the following, as a percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent. Round dollar amounts to whole dollars, with total equal to Contract Sum.
 - 1) Labor.
 - 2) Materials.
 - 3) Equipment.
3. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
4. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - a. Differentiate between items stored on-site and items stored off-site.
5. Purchase Contracts: Provide a separate line item in the schedule of values for each purchase contract. Show line-item value of purchase contract. Indicate Owner payments or deposits, if any, and balance to be paid by Contractor.
6. Overhead Costs: Include total cost and proportionate share of general overhead and profit for each line item.
7. Closeout Costs. Include separate line items under Contractor and principal subcontracts for Project closeout requirements in an amount totaling five percent of the Contract Sum and subcontract amount.
8. Schedule of Values Revisions: Update and resubmit before the schedule of values before the next Application for Payment, when Change Orders or Construction Change Directives result in a change in the Contract Sum. Include at least one separate line item for each Change Order and Construction Change Directive.

1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
- C. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
 2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.

3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
 4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.
- E. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored on-site and items stored off-site.
1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment for stored materials.
 2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
 3. Provide summary documentation for stored materials indicating the following:
 - a. Value of materials previously stored and remaining stored as of date of previous Applications for Payment.
 - b. Value of previously stored materials put in place after date of previous Application for Payment and on or before date of current Application for Payment.
 - c. Value of materials stored since date of previous Application for Payment and remaining stored as of date of current Application for Payment.
- F. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from subcontractors, sub-subcontractors, and suppliers for construction period covered by the previous application.
1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
 2. When an application shows completion of an item, submit conditional final or full waivers.
 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
 4. Submit final Application for Payment with or preceded by conditional final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
 5. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.
- H. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
1. List of subcontractors.
 2. Schedule of values.
 3. Contractor's construction schedule (preliminary if not final).
 4. Combined Contractor's construction schedule (preliminary if not final) incorporating Work of multiple contracts, with indication of acceptance of schedule by each Contractor.
 5. Products list (preliminary if not final).
 6. Submittal schedule (preliminary if not final).
 7. List of Contractor's staff assignments.
 8. List of Contractor's principal consultants.
 9. Copies of building permits.
 10. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 11. Initial progress report.
 12. Report of preconstruction conference.
 13. Certificates of insurance and insurance policies.

14. Performance and payment bonds.
15. Data needed to acquire Owner's insurance.
- I. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
 1. Evidence of completion of Project closeout requirements.
 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 3. Updated final statement, accounting for final changes to the Contract Sum.
 4. AIA Document G706, "Contractor's Affidavit of Payment".
 5. AIA Document G706A, "Contractor's Affidavit of Release of Leans".
 6. AIA Document G707, "Consent of Surety to Final Payment".
 7. Evidence that claims have been settled.
 8. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 01 31 00
PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
 - 1. General coordination procedures.
 - 2. Coordination drawings.
 - 3. RFIs.
 - 4. Digital project management procedures.
 - 5. Project meetings.
- B. Each contractor shall participate in coordination requirements. Certain areas of responsibility are assigned to a specific contractor.
- C. Related Requirements:
 - 1. Section 013200 "Construction Progress Documentation" for preparing and submitting Contractor's construction schedule.
 - 2. Section 017300 "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
 - 3. Section 017700 "Closeout Procedures" for coordinating closeout of the Contract.

1.3 DEFINITIONS

- A. BIM: Building Information Modeling.
- B. RFI: Request for Information. Request from Owner, Architect, or Contractor seeking information required by or clarifications of the Contract Documents.

1.4 INFORMATIONAL SUBMITTALS

- A. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
 - 1. Name, address, telephone number, and email address of entity performing subcontract or supplying products.
 - 2. Number and title of related Specification Section(s) covered by subcontract.
 - 3. Drawing number and detail references, as appropriate, covered by subcontract.
- B. Key Personnel Names: Within 15 days of starting construction operations, submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and cellular telephone numbers and e-mail addresses. Provide names, addresses, and telephone numbers of individuals assigned as alternates in the absence of individuals assigned to Project.
 - 1. Post copies of list in project meeting room, in temporary field office, in web-based Project software directory (if one is set-up), and in prominent location in built facility. Keep list current at all times.

1.5 GENERAL COORDINATION PROCEDURES

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations included in different Sections that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
 - 3. Make adequate provisions to accommodate items scheduled for later installation.
- B. Coordination: Each contractor shall coordinate its construction operations with those of other contractors and entities to ensure efficient and orderly installation of each part of the Work. Each contractor shall coordinate its own operations with operations included in different Sections that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components with other contractors to ensure maximum performance and accessibility for required maintenance, service, and repair.
 - 3. Make adequate provisions to accommodate items scheduled for later installation.
- C. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
 - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.
- D. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
 - 1. Preparation of Contractor's construction schedule.
 - 2. Preparation of the schedule of values.
 - 3. Installation and removal of temporary facilities and controls.
 - 4. Delivery and processing of submittals.
 - 5. Progress meetings.
 - 6. Preinstallation conferences.
 - 7. Project closeout activities.
 - 8. Startup and adjustment of systems.
 - 9. Project close-out activities.
- E. Conservation: Coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials. Coordinate use of temporary utilities to minimize waste.
 - 1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work. Refer to other Sections for disposition of salvaged materials that are designated as Owner's property.

1.6 COORDINATION DRAWINGS

- A. Coordination Drawings, General: Prepare coordination drawings according to requirements in individual Sections, and additionally where installation is not completely indicated on Shop Drawings, where limited space availability necessitates coordination, or if coordination is required to facilitate integration of products and materials fabricated or installed by more than one entity.

1. Content: Project-specific information, drawn accurately to a scale large enough to indicate and resolve conflicts. Do not base coordination drawings on standard printed data. Include the following information, as applicable:
 - a. Use applicable Drawings as a basis for preparation of coordination drawings. Prepare sections, elevations, and details as needed to describe relationship of various systems and components.
 - b. Coordinate the addition of trade-specific information to coordination drawings by multiple contractors in a sequence that best provides for coordination of the information and resolution of conflicts between installed components before submitting for review.
 - c. Indicate functional and spatial relationships of components of architectural, structural, civil, mechanical, and electrical systems.
 - d. Indicate space requirements for routine maintenance and for anticipated replacement of components during the life of the installation.
 - e. Show location and size of access doors required for access to concealed dampers, valves, and other controls.
 - f. Indicate required installation sequences.
 - g. Indicate dimensions shown on Drawings. Specifically note dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternative sketches to Architect indicating proposed resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.
- B. Coordination Drawing Organization: Organize coordination drawings as follows:
 1. Floor Plans and Reflected Ceiling Plans: Show architectural and structural elements, and mechanical, plumbing, fire-protection, fire-alarm, and electrical Work. Show locations of visible ceiling-mounted devices relative to acoustical ceiling grid. Supplement plan drawings with section drawings where required to adequately represent the Work.
 2. Plenum Space: Indicate sub-framing for support of ceiling and wall systems, mechanical and electrical equipment, and related Work. Locate components within plenums to accommodate layout of light fixtures and other components indicated on Drawings. Indicate areas of conflict between light fixtures and other components.
 3. Mechanical Rooms: Provide coordination drawings for mechanical rooms showing plans and elevations of mechanical, plumbing, fire-protection, fire-alarm, and electrical equipment.
 4. Structural Penetrations: Indicate penetrations and openings required for all disciplines.
 5. Slab Edge and Embedded Items: Indicate slab edge locations and sizes and locations of embedded items for metal fabrications, sleeves, anchor bolts, bearing plates, angles, door floor closers, slab depressions for floor finishes, curbs and housekeeping pads, and similar items.
 6. Mechanical and Plumbing Work: Show the following:
 - a. Sizes and bottom elevations of ductwork, piping, and conduit runs, including insulation, bracing, flanges, and support systems.
 - b. Dimensions of major components, such as dampers, valves, diffusers, access doors, cleanouts and electrical distribution equipment.
 - c. Fire-rated enclosures around ductwork.
 7. Electrical Work: Show the following:
 - a. Runs of vertical and horizontal conduit 1-1/4 inches in diameter and larger.
 - b. Light fixture, exit light, emergency battery pack, smoke detector, and other fire-alarm locations.
 - c. Panel board, switch board, switchgear, transformer, busway, generator, and motor-control center locations.

- d. Location of pull boxes and junction boxes, dimensioned from column center lines.
 - 8. Fire-Protection System: Show the following:
 - a. Locations of standpipes, mains piping, branch lines, pipe drops, and sprinkler heads.
 - 9. Review: Architect will review coordination drawings to confirm that in general the Work is being coordinated, but not for the details of the coordination, which are Contractor's responsibility. If Architect determines that coordination drawings are not being prepared in sufficient scope or detail, or are otherwise deficient, Architect will so inform Contractor, who shall make suitable modifications and resubmit.
 - 10. Coordination Drawing Prints: Prepare coordination drawing prints according to requirements in Section 013300 "Submittal Procedures."
- C. Coordination Digital Data Files: Prepare coordination digital data files according to the following requirements:
 - 1. File Preparation Format: Same digital data software program, version, and operating system as original Drawings.
 - 2. File Preparation Format: DWG, Version 18, operating in Microsoft Windows operating system.
 - 3. File Submittal Format: Submit or post coordination drawing files using PDF format.
 - 4. BIM File Incorporation: Develop and incorporate coordination drawing files into BIM established for Project. When included in construction contract.
 - a. Perform three-dimensional component conflict analysis as part of preparation of coordination drawings. Resolve component conflicts prior to submittal. Indicate where conflict resolution requires modification of design requirements by Architect.
 - 5. Architect will furnish Contractor one set of digital data files of Drawings for use in preparing coordination digital data files.
 - a. Architect makes no representations as to the accuracy or completeness of digital data files as they relate to Drawings.
 - b. Digital Data Software Program: Drawings are available in Revit – 2017 Format.
 - c. Contractor shall execute a data licensing agreement in the form of Agreement form acceptable to Owner and Architect.

1.7 REQUEST FOR INFORMATION (RFI)

- A. General: Immediately on discovery of the need for additional information, clarification, or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.
 - 1. Architect will return without response those RFIs submitted to Architect by other entities controlled by Contractor.
 - 2. Coordinate and submit RFIs in a prompt manner as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:
 - 1. Project name.
 - 2. Project number.
 - 3. Date.
 - 4. Name of Contractor.
 - 5. Name of Architect.
 - 6. RFI number, numbered sequentially.
 - 7. RFI subject (description).
 - 8. Specification Section number and title and related paragraphs, as appropriate.
 - 9. Drawing number and detail references, as appropriate.

10. Field dimensions and conditions, as appropriate.
 11. Contractor's suggested resolution. If Contractor's suggested resolution impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
 12. Contractor's signature.
 13. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
 - a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.
- C. RFI Forms: AIA Document G716 or Software-generated form with substantially the same content as indicated above, acceptable to Architect.
1. Attachments shall be electronic files in PDF format.
- D. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow seven working days for Architect's response for each RFI. RFIs received by Architect after 1:00 p.m. will be considered as received the following working day.
1. The following Contractor-generated RFIs will be returned without action:
 - a. Requests for approval of submittals.
 - b. Requests for approval of substitutions.
 - c. Requests for approval of Contractor's means and methods.
 - d. Requests for coordination information already indicated in the Contract Documents.
 - e. Requests for adjustments in the Contract Time or the Contract Sum.
 - f. Requests for interpretation of Architect's actions on submittals.
 - g. Incomplete RFIs or inaccurately prepared RFIs.
 2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt by Architect of additional information.
 3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."
 - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.
- E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly. Include the following:
1. Project name.
 2. Name and address of Contractor.
 3. Name and address of Architect.
 4. RFI number including RFIs that were returned without action or withdrawn.
 5. RFI description.
 6. Date the RFI was submitted.
 7. Date Architect's response was received.
 8. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
 9. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.
- F. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within seven days if Contractor disagrees with response.

1.8 DIGITAL PROJECT MANAGEMENT PROCEDURES

- A. Use of Architect's Digital Data Files: Digital data files of Architect's will be provided by Architect, if requested by the Contractor's, for use during construction. The Contractor

will have to complete and sign an ajc electronic files release form prior to any digital documents released.

1. Digital data files may be used by Contractor in preparing coordination drawings, Shop Drawings, and Project record Drawings.
 2. Architect makes no representations as to the accuracy or completeness of digital data files as they relate to Contract Drawings.
 3. Digital Drawing Software Program: Contract Drawings are available in Revit 2017.
 - a. Subcontractors, and other parties working with the Contractor on this project may request Architect's digital data files, but must also complete and sign an ajc electronic files release form, prior to any digital documents released. No one is given the right to release ajc Architects digital files except ajc Architects.
 4. Upon request, The following digital data files will be furnished for each appropriate discipline:
 - a. Floor plans.
 - b. Reflected ceiling plans.
- B. PDF Document Preparation: Where PDFs are required to be submitted to Architect, prepare as follows:
1. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
 2. Name file with submittal number or other unique identifier, including revision identifier.
 3. Certifications: Where digitally submitted certificates and certifications are required, provide a digital signature with digital certificate on where indicated.

1.9 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site unless otherwise indicated.
1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times a minimum of 10 working days prior to meeting.
 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
 3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within three days after the meeting.
- B. Preconstruction Conference: Schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement.
1. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 2. Agenda: Discuss items of significance that could affect progress, including the following:
 - a. Responsibilities and personnel assignments.
 - b. Tentative construction schedule.
 - c. Phasing.
 - d. Critical work sequencing and long lead items.
 - e. Designation of key personnel and their duties.

- f. Lines of communications.
 - g. Procedures for processing field decisions and Change Orders.
 - h. Procedures for RFIs.
 - i. Procedures for testing and inspecting.
 - j. Procedures for processing Applications for Payment.
 - k. Distribution of the Contract Documents.
 - l. Submittal procedures.
 - m. Preparation of Record Documents.
 - n. Use of the premises.
 - o. Work restrictions.
 - p. Working hours.
 - q. Owner's occupancy requirements.
 - r. Responsibility for temporary facilities and controls.
 - s. Procedures for moisture and mold control.
 - t. Procedures for disruptions and shutdowns.
 - u. Construction waste management and recycling.
 - v. Parking availability.
 - w. Office, work, and storage areas.
 - x. Equipment deliveries and priorities.
 - y. First aid.
 - z. Security.
 - aa. Progress cleaning.
3. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity when required by other sections and when required for coordination with other construction.
- 1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
 - 2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
 - a. Contract Documents.
 - b. Options.
 - c. Related RFIs.
 - d. Related Change Orders.
 - e. Purchases.
 - f. Deliveries.
 - g. Submittals.
 - h. Review of mockups.
 - i. Possible conflicts.
 - j. Compatibility requirements.
 - k. Time schedules.
 - l. Weather limitations.
 - m. Manufacturer's written instructions.
 - n. Warranty requirements.
 - o. Compatibility of materials.
 - p. Acceptability of substrates.
 - q. Temporary facilities and controls.
 - r. Space and access limitations.
 - s. Regulations of authorities having jurisdiction.
 - t. Testing and inspecting requirements.
 - u. Installation procedures.
 - v. Coordination with other work.
 - w. Required performance results.

- x. Protection of adjacent work.
- y. Protection of construction and personnel.
- 3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
- 4. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
- 5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Project Closeout Conference: Schedule and conduct a project closeout conference, at a time convenient to Owner and Architect, but no later than 45 days prior to the scheduled date of Substantial Completion.
 - 1. Conduct the conference to review requirements and responsibilities related to Project closeout.
 - 2. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the meeting. Participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 3. Agenda: Discuss items of significance that could affect or delay Project closeout, including the following:
 - a. Preparation of Record Documents.
 - b. Procedures required prior to inspection for Substantial Completion and for final inspection for acceptance.
 - c. Procedures for completing and archiving web-based Project software site data files.
 - d. Submittal of written warranties.
 - e. Requirements for preparing operations and maintenance data.
 - f. Requirements for delivery of material samples, attic stock, and spare parts.
 - g. Requirements for demonstration and training.
 - h. Preparation of Contractor's punch list.
 - i. Procedures for processing Applications for Payment at Substantial Completion and for final payment.
 - j. Submittal procedures.
 - k. Owner's partial occupancy requirements.
 - l. Installation of Owner's furniture, fixtures, and equipment.
 - m. Responsibility for removing temporary facilities and controls.
 - 4. Minutes: Entity conducting meeting will record and distribute meeting minutes.
- E. Progress Meetings: Conduct progress meetings at weekly intervals.
 - 1. Coordinate dates of meetings with preparation of payment requests.
 - 2. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 3. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - 1) Review schedule for next period.

- b. Review present and future needs of each entity present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Deliveries.
 - 5) Off-site fabrication.
 - 6) Access.
 - 7) Site use.
 - 8) Temporary facilities and controls.
 - 9) Progress cleaning.
 - 10) Quality and work standards.
 - 11) Status of correction of deficient items.
 - 12) Field observations.
 - 13) Status of RFIs.
 - 14) Status of Proposal Requests.
 - 15) Pending changes.
 - 16) Status of Change Orders.
 - 17) Pending claims and disputes.
 - 18) Documentation of information for payment requests.
4. Minutes: Entity responsible for conducting the meeting will record and distribute the meeting minutes to each party present and to parties requiring information.
 - a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.
5. Reporting: Record meeting results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from each meeting.
- F. Coordination Meetings: Conduct Project coordination meetings at weekly intervals. Project coordination meetings are in addition to specific meetings held for other purposes, such as progress meetings and preinstallation conferences.
- 1. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meetings shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 2. Agenda: Review and correct or approve minutes of the previous coordination meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Combined Contractor's Construction Schedule: Review progress since the last coordination meeting. Determine whether each contract is on time, ahead of schedule, or behind schedule, in relation to combined Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - b. Schedule Updating: Revise combined Contractor's construction schedule after each coordination meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with report of each meeting.
 - c. Review present and future needs of each contractor present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.

- 3) Resolution of BIM component conflicts.
 - 4) Status of submittals.
 - 5) Deliveries.
 - 6) Off-site fabrication.
 - 7) Access.
 - 8) Site use.
 - 9) Temporary facilities and controls.
 - 10) Work hours.
 - 11) Hazards and risks.
 - 12) Progress cleaning.
 - 13) Quality and work standards.
 - 14) Status of RFIs.
 - 15) Proposal Requests.
 - 16) Change Orders.
 - 17) Pending changes.
3. Reporting: Record meeting results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 01 32 00
CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
 - 1. Startup construction schedule.
 - 2. Contractor's Construction Schedule.
 - 3. Construction schedule updating reports.
 - 4. Daily construction reports.
 - 5. Material location reports.
 - 6. Site condition reports.
 - 7. Unusual event reports.
- B. Related Requirements:
 - 1. Section 013300 "Submittal Procedures" for submitting schedules and reports.
 - 2. Section 014000 "Quality Requirements" for submitting a schedule of tests and inspections.

1.3 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction Project. Activities included in a construction schedule consume time and resources.
 - 1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
 - 2. Predecessor Activity: An activity that precedes another activity in the network.
 - 3. Successor Activity: An activity that follows another activity in the network.
- B. Cost Loading: The allocation of the schedule of values for completing an activity as scheduled. The sum of costs for all activities must equal the total Contract Sum.
- C. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.
- D. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.
- E. Event: The starting or ending point of an activity.
- F. Float: The measure of leeway in starting and completing an activity.
 - 1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.
 - 2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
 - 3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.

- G. Resource Loading: The allocation of manpower and equipment necessary for completing an activity as scheduled.

1.4 INFORMATIONAL SUBMITTALS

- A. Format for Submittals: Submit required submittals in the following format:
 - 1. Working electronic copy of schedule file, where indicated.
 - 2. PDF file.
 - 3. Approval of cost-loaded start-up construction schedule will not constitute approval of schedule of values for cost-loaded activities.
- B. Startup construction schedule.
 - 1. Submittal of cost-loaded, startup construction schedule will not constitute approval of schedule of values for cost-loaded activities.
- C. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.
- D. CPM Reports: Concurrent with CPM schedule, submit each of the following reports. Format for each activity in reports shall contain activity number, activity description, cost and resource loading, original duration, remaining duration, early start date, early finish date, late start date, late finish date, and total float in calendar days.
 - 1. Activity Report: List of activities sorted by activity number and then early start date, or actual start date if known.
 - 2. Logic Report: List of preceding and succeeding activities for each activity, sorted in ascending order by activity number and then by early start date, or actual start date if known.
 - 3. Total Float Report: List of activities sorted in ascending order of total float.
- E. Construction Schedule Updating Reports: Submit with Applications for Payment.
- F. Daily Construction Reports: Submit at monthly intervals Applications for Payment.
- G. Material Location Reports: Submit at monthly intervals.
- H. Site Condition Reports: Submit at time of discovery of differing conditions.
- I. Unusual Event Reports: Submit at time of unusual event.

1.5 QUALITY ASSURANCE

- A. Prescheduling Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." Review methods and procedures related to the preliminary construction schedule and Contractor's Construction Schedule, including, but not limited to, the following:
 - 1. Review software limitations and content and format for reports.
 - 2. Verify availability of qualified personnel needed to develop and update schedule.
 - 3. Discuss constraints, including work stages, area separations, interim milestones and partial Owner occupancy.
 - 4. Review delivery dates for Owner-furnished products.
 - 5. Review schedule for work of Owner's separate contracts.
 - 6. Review submittal requirements and procedures.
 - 7. Review time required for review of submittals and resubmittals.
 - 8. Review requirements for tests and inspections by independent testing and inspecting agencies.
 - 9. Review time required for Project closeout and Owner startup procedures, including Commissioning Activities.
 - 10. Review and finalize list of construction activities to be included in schedule.
 - 11. Review procedures for updating schedule.

1.6 COORDINATION

- A. Coordinate Contractor's Construction Schedule with the schedule of values, list of subcontracts, submittal schedule, progress reports, payment requests, and other required schedules and reports.
 - 1. Secure time commitments for performing critical elements of the Work from entities involved.
 - 2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

1.7 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Computer Scheduling Software: Prepare schedules using current version of a program that has been developed specifically to manage construction schedules.
- B. Time Frame: Extend schedule from date established for the Notice to Proceed to date of Substantial Completion.
 - 1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- C. Activities: Treat each floor or separate area as a separate numbered activity for each main element of the Work. Comply with the following:
 - 1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
 - 2. Procurement Activities: Include procurement process activities for the following long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
 - 3. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with submittal schedule.
 - 4. Startup and Testing Time: Include no fewer than 15 days for startup and testing.
 - 5. Commissioning Time: Include no fewer than 15 days for commissioning.
 - 6. Substantial Completion: Indicate completion in advance of date established for Substantial Completion and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
 - 7. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and final completion.
- D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule and show how the sequence of the Work is affected.
 - 1. Phasing: Arrange list of activities on schedule by phase.
 - 2. Products Ordered in Advance: Include a separate activity for each product. Include delivery date indicated in Section 011000 "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
 - 3. Work Restrictions: Show the effect of the following items on the schedule:
 - a. Coordination with existing construction.
 - b. Limitations of continued occupancies.
 - c. Uninterruptible services.
 - d. Partial occupancy before Substantial Completion.
 - e. Use-of-premises restrictions.
 - f. Seasonal variations.
 - g. Environmental control.
 - 4. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:
 - a. Subcontract awards.
 - b. Submittals.
 - c. Purchases.

- d. Mockups.
 - e. Fabrication.
 - f. Sample testing.
 - g. Deliveries.
 - h. Installation.
 - i. Tests and inspections.
 - j. Adjusting.
 - k. Curing.
 - l. Startup and placement into final use and operation.
 - m. Commissioning.
5. Construction Areas: Identify each major area of construction for each major portion of the Work. Indicate where each construction activity within a major area must be sequenced or integrated with other construction activities to provide for the following:
- a. Structural completion.
 - b. Temporary enclosure and space conditioning.
 - c. Completion of mechanical installation.
 - d. Completion of electrical installation.
 - e. Substantial Completion.
- E. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and final completion and the following interim milestones:
- 1. Temporary enclosure and space conditioning.
- F. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:
- 1. Unresolved issues.
 - 2. Unanswered Requests for Information.
 - 3. Rejected or unreturned submittals.
 - 4. Notations on returned submittals.
 - 5. Pending modifications affecting the Work and the Contract Time.
- G. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule at each regularly scheduled progress meeting.
- 1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
 - 2. As the Work progresses, indicate final completion percentage for each activity.
- H. Recovery Schedule: When periodic update indicates the Work is 14 or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule. Indicate changes to working hours, working days, crew sizes, equipment required to achieve compliance, and date by which recovery will be accomplished.
- I. Distribution: Distribute copies of approved schedule to Architect, Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
- 1. Post copies in Project meeting rooms and temporary field offices.
 - 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

1.8 STARTUP CONSTRUCTION SCHEDULE

- A. Gantt-Chart Schedule: Submit startup, horizontal, Gantt-chart-type construction schedule within seven days of date established for the Notice to Proceed.

- B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line. Outline significant construction activities for first 90 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.

1.9 CPM SCHEDULE REQUIREMENTS

- A. CPM Schedule Preparation: Prepare a list of all activities required to complete the Work. Using the startup network diagram, prepare a skeleton network to identify probable critical paths.
 - 1. Activities: Indicate the estimated time duration, sequence requirements, and relationship of each activity in relation to other activities. Include estimated time frames for the following activities:
 - a. Preparation and processing of submittals.
 - b. Mobilization and demobilization.
 - c. Purchase of materials.
 - d. Delivery.
 - e. Fabrication.
 - f. Utility interruptions.
 - g. Installation.
 - h. Work by Owner that may affect or be affected by Contractor's activities.
 - i. Testing and inspection.
 - j. Commissioning.
 - k. Punch list and final completion.
 - l. Activities occurring following final completion.
 - 2. Critical Path Activities: Identify critical path activities, including those for interim completion dates. Scheduled start and completion dates shall be consistent with Contract milestone dates.
 - 3. Processing: Process data to produce output data on a computer-drawn, time-scaled network. Revise data, reorganize activity sequences, and reproduce as often as necessary to produce the CPM schedule within the limitations of the Contract Time.
 - 4. Format: Mark the critical path. Locate the critical path near center of network; locate paths with most float near the edges.
 - a. Subnetworks on separate sheets are permissible for activities clearly off the critical path.
- B. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis using a network fragment to demonstrate the effect of the proposed change on the overall Project schedule.
- C. Initial Issue of Schedule: Prepare initial network diagram from a sorted activity list indicating straight "early start-total float." Identify critical activities. Prepare tabulated reports showing the following:
 - 1. Contractor or subcontractor and the Work or activity.
 - 2. Description of activity.
 - 3. Main events of activity.
 - 4. Immediately preceding and succeeding activities.
 - 5. Early and late start dates.
 - 6. Early and late finish dates.
 - 7. Activity duration in workdays.
 - 8. Total float or slack time.
 - 9. Average size of workforce.
 - 10. Dollar value of activity (coordinated with the schedule of values).
- D. Schedule Updating: Concurrent with making revisions to schedule, prepare tabulated reports showing the following:
 - 1. Identification of activities that have changed.
 - 2. Changes in early and late start dates.

3. Changes in early and late finish dates.
4. Changes in activity durations in workdays.
5. Changes in the critical path.
6. Changes in total float or slack time.
7. Changes in the Contract Time.

1.10 REPORTS

- A. Daily Construction Reports: Prepare a daily construction report recording the following information concerning events at Project site:
 1. List of subcontractors at Project site.
 2. List of separate contractors at Project site.
 3. Approximate count of personnel at Project site.
 4. Equipment at Project site.
 5. Material deliveries.
 6. Testing and inspection.
 7. Accidents.
 8. Meetings and significant decisions.
 9. Unusual events.
 10. Stoppages, delays, shortages, and losses.
 11. Delays due to weather.
 12. Meter readings and similar recordings.
 13. Emergency procedures.
 14. Orders and requests of authorities having jurisdiction.
 15. Change Orders received and implemented.
 16. Construction Change Directives received and implemented.
 17. Services connected and disconnected.
 18. Equipment or system tests and startups.
 19. Partial completions and occupancies.
 20. Substantial Completions authorized.
- B. Material Location Reports: At monthly intervals, prepare and submit a comprehensive list of materials delivered to and stored at Project site. List shall be cumulative, showing materials previously reported plus items recently delivered. Include with list a statement of progress on and delivery dates for materials or items of equipment fabricated or stored away from Project site. Indicate the following categories for stored materials:
 1. Material stored prior to previous report and remaining in storage.
 2. Material stored prior to previous report and since removed from storage and installed.
 3. Material stored following previous report and remaining in storage.
- C. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.
- D. Unusual Event Reports: When an event of an unusual and significant nature occurs at Project site, whether or not related directly to the Work, prepare and submit a special report. List chain of events, persons participating, responses by Contractor's personnel, evaluation of results or effects, and similar pertinent information. Advise Owner in advance when these events are known or predictable.
 1. Submit unusual event reports directly to Owner within one day(s) of an occurrence. Distribute copies of report to parties affected by the occurrence.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 32 33
PHOTOGRAPHIC DOCUMENTATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for the following:
 - 1. Preconstruction photographs.
 - 2. Periodic construction photographs.
 - 3. Final completion construction photographs.
 - 4. Construction video recordings (Optional).
 - 5. Web-based construction photographic documentation (Optional).
- B. Related Requirements:
 - 1. Section 013300 "Submittal Procedures" for submitting photographic documentation.
 - 2. Section 017700 "Closeout Procedures" for submitting photographic documentation as project record documents at Project closeout.
 - 3. Section 017900 "Demonstration and Training" for submitting video recordings of demonstration of equipment and training of Owner's personnel.

1.3 INFORMATIONAL SUBMITTALS

- A. Digital Photographs: Submit image files within three days of taking photographs.
 - 1. Digital Camera: Minimum sensor resolution of 8 megapixels.
 - 2. Format: Minimum 3200 by 2400 pixels, in unaltered original files, with same aspect ratio as the sensor, uncropped, date and time stamped, in folder named by date of photograph, accompanied by key plan file.
 - 3. Identification: Provide the following information with each image description in file metadata tag:
 - a. Name of Project.
 - b. Name and contact information for photographer.
 - c. Name of Architect.
 - d. Name of General Contractor (GC).
 - e. Date photograph was taken.
 - f. Description of vantage point, indicating location, direction (by compass point), and elevation or story of construction.
 - g. Unique sequential identifier keyed to accompanying key plan.
- B. Construction Photographs: Submit one print of each photographic view within seven days of taking photographs.
 - 1. Format: 8-by-10-inch smooth-surface matte prints on single-weight, commercial-grade photographic paper; enclosed in clear plastic sleeves that are punched for standard three-ring binder.
 - 2. Identification: On back of each print, provide an applied label or rubber-stamped impression with the following information:
 - a. Name of Project.
 - b. Name and contact information for photographer.
 - c. Name of Architect.

- d. Name of GC
 - e. Date photograph was taken if not date stamped by camera.
 - f. Description of vantage point, indicating location, direction (by compass point), and elevation or story of construction.
 - g. Unique sequential identifier keyed to accompanying key plan.
- C. Video Recordings, at contractor's option: Submit video recordings within seven days of recording.
- 1. Submit video recordings in digital video disc format acceptable to Architect by posting to Project Web site.
 - 2. Identification: With each submittal, provide the following information:
 - a. Name of Project.
 - b. Name and address of photographer.
 - c. Name of Architect.
 - d. Name of GC
 - e. Date video recording was recorded.
 - f. Description of vantage point, indicating location, direction (by compass point), and elevation or story of construction.
 - g. Weather conditions at time of recording.
 - 3. Transcript: Prepared on 8-1/2-by-11-inch paper, punched and bound in heavy-duty, three-ring, vinyl-covered binders. Mark appropriate identification on front and spine of each binder. Include a cover sheet with same label information as corresponding video recording. Include name of Project and date of video recording on each page.
- D. Web-Based Photographic Documentation, at contractor's option: Provide link for real time web cam video recordings.

1.4 QUALITY ASSURANCE

- A. Photographer Qualifications: An individual who has been regularly engaged as a professional photographer of construction projects for not less than three years.
- B. Web-Based Photographic Documentation Service Provider: A firm specializing in providing photographic equipment, Web-based software, and related services for construction projects, with record of providing satisfactory services similar to those required for Project.

1.5 USAGE RIGHTS

- A. Obtain and transfer copyright usage rights from photographer to Owner for unlimited reproduction of photographic documentation.

PART 2 - PRODUCTS

2.1 PHOTOGRAPHIC MEDIA

- A. Digital Images: Provide images in JPG format, produced by a digital camera with minimum sensor size of 8 megapixels, and at an image resolution of not less than 3200 by 2400 pixels.
- B. Digital Video Recordings: Provide optional high-resolution, digital video disc in format acceptable to Architect.

2.2 WEB-BASED PHOTOGRAPHIC DOCUMENTATION (Optional)

- A. Project Camera: Provide fixed exterior camera installation, mounted to provide unobstructed view of construction site from location approved by Architect.
 - 1. Provide one or two fixed-location camera(s), with the following characteristics:

- a. Static view.
 - b. Capable of producing minimum 3.0-megapixel pictures.
 - c. Provide power supply, active high-speed data connection to service provider's network, and static public IP address for each camera.
- B. Web-Based Image Access: Password-protected access for Project team administered by Contractor, providing current image access and archival image access by date and time, with images downloadable to viewer's device.
 - 1. Provide public viewer open access to most recent project camera image.

PART 3 - EXECUTION

3.1 CONSTRUCTION PHOTOGRAPHS

- A. Photographer: Provide a qualified photographer to take construction photographs.
- B. General: Take photographs using the maximum range of depth of field, and that are in focus, to clearly show the Work. Photographs with blurry or out-of-focus areas will not be accepted.
 - 1. Maintain key plan with each set of construction photographs that identifies each photographic location.
- C. Digital Images: Submit digital images exactly as originally recorded in the digital camera, without alteration, manipulation, editing, or modifications using image-editing software.
 - 1. Date and Time: Include date and time in file name for each image.
 - 2. Field Office Images: Maintain one set of images accessible in the field office at Project site, available at all times for reference. Identify images in the same manner as those submitted to Architect.
- D. Preconstruction Photographs: Before commencement of excavation, take photographs of Project site and surrounding properties, including existing items to remain during construction, from different vantage points, as directed by Architect.
 - 1. Flag excavation areas and construction limits before taking construction photographs.
 - 2. Take 20 photographs to show existing conditions adjacent to property before starting the Work.
 - 3. Take 20 photographs of existing buildings either on or adjoining property to accurately record physical conditions at start of construction.
 - 4. Take additional photographs as required to record settlement or cracking of adjacent structures, pavements, and improvements.
- E. Periodic Construction Photographs: Take 20 photographs weekly, with timing each month adjusted to coincide with the cutoff date associated with each Application for Payment. Select vantage points to show status of construction and progress since last photographs were taken.
- F. Architect-Directed Construction Photographs: From time to time, Architect will instruct photographer about number and frequency of photographs and general directions on vantage points. Select actual vantage points and take photographs to show the status of construction and progress since last photographs were taken.
- G. Final Completion Construction Photographs: Take 20 color photographs after date of Substantial Completion for submission as project record documents. Architect will inform photographer of desired vantage points.
 - 1. Do not include date stamp.
- H. Additional Photographs: Architect or Owner may request photographs in addition to periodic photographs specified. Additional photographs will be paid for by Change Order and are not included in the Contract Sum.
 - 1. Three days' notice will be given, where feasible.
 - 2. In emergency situations, take additional photographs within 24 hours of request.
 - 3. Circumstances that could require additional photographs include, but are not limited to, the following:

- a. Special events planned at Project site.
- b. Immediate follow-up when on-site events result in construction damage or losses.
- c. Photographs to be taken at fabrication locations away from Project site. These photographs are not subject to unit prices or unit-cost allowances.
- d. Substantial Completion of a major phase or component of the Work.
- e. Extra record photographs at time of final acceptance.
- f. Owner's request for special publicity photographs.

3.2 CONSTRUCTION VIDEO RECORDINGS (Optional)

- A. Video Recording Photographer: Engage a qualified videographer to record construction video recordings.
- B. Recording: Mount camera on tripod before starting recording unless otherwise necessary to show area of construction. Display continuous running time and date. At start of each video recording, record weather conditions from local newspaper or television and the actual temperature reading at Project site.
- C. Preconstruction Video Recording: Before starting excavation, record video recording of Project site and surrounding properties from different vantage points, as directed by Architect.
 - 1. Flag excavation areas and construction limits before recording construction video recordings.
 - 2. Show existing conditions adjacent to Project site before starting the Work.
 - 3. Show existing buildings either on or adjoining Project site to accurately record physical conditions at the start of excavation. Show protection efforts by Contractor.
- D. Periodic Construction Video Recordings: Record optional video recording weekly, with timing each month adjusted to coincide with the cutoff date associated with each Application for Payment. Select vantage points to show status of construction and progress since last video recordings were recorded. Minimum recording time shall be 30 minutes(s).

3.3 WEB-BASED CONSTRUCTION PHOTOGRAPHIC DOCUMENTATION (Optional)

- A. Live Streaming Construction Site Images: Provide Web-accessible image of current site image from fixed location camera(s), updated at 15-minute intervals during daytime operation.
- B. Time-Lapse Sequence Construction Site Recordings: Provide video recording from a fixed-location camera to show status of construction and progress.
 - 1. Frequency: Record one frame of video recording every 15 minutes, from same vantage point each time, to create a time-lapse sequence of construction activities.
 - 2. Timer: Provide timer to automatically start and stop video recorder so recording occurs only during daylight construction work hours.
- C. Maintain cameras and Web-based access in good working order according to Web-based construction photographic documentation service provider's written instructions until final completion. Provide for service of cameras and related networking devices and software.

END OF SECTION

SECTION 01 33 00

SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Submittal schedule requirements.
 - 2. Administrative and procedural requirements for submittals.
- B. Related Requirements:
 - 1. Section 012900 "Payment Procedures" for submitting Applications for Payment and the schedule of values.
 - 2. Section 013100 "Project Management and Coordination" for submitting coordination drawings and subcontract list and for requirements for web-based Project software.
 - 3. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
 - 4. Section 014000 "Quality Requirements" for submitting test and inspection reports, and schedule of tests and inspections.
 - 5. Section 017700 "Closeout Procedures" for submitting closeout submittals and maintenance material submittals.
 - 6. Section 017823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
 - 7. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
 - 8. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 9. Section 019113 "General Commissioning Requirements".

1.3 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."

1.4 SUBMITTAL SCHEDULE

- A. Submittal Schedule: Submit, as an action submittal, a list of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.

1. Coordinate submittal schedule with list of subcontracts, the schedule of values, and Contractor's construction schedule.
2. Initial Submittal: Submit concurrently with startup construction schedule. Include submittals required during the first 60 days of construction. List those submittals required to maintain orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
3. Final Submittal: Submit concurrently with the first complete submittal of Contractor's construction schedule.
 - a. Submit revised submittal schedule to reflect changes in current status and timing for submittals.
4. Format: Arrange the following information in a tabular format:
 - a. Scheduled date for first submittal.
 - b. Specification Section number and title.
 - c. Submittal Category: Action; informational.
 - d. Name of subcontractor.
 - e. Description of the Work covered.
 - f. Scheduled date for Architect's final release or approval.
 - g. Scheduled dates for purchasing.
 - h. Scheduled dates for installation.
 - i. Activity or event number.

1.5 SUBMITTAL FORMATS

- A. Submittal Information: Include the following information in each submittal:
 1. Project name.
 2. Date.
 3. Name of Architect.
 4. Name of Contractor.
 5. Name of firm or entity that prepared submittal.
 6. Names of subcontractor, manufacturer, and supplier.
 7. Unique submittal number, including revision identifier. Include Specification Section number with sequential alphanumeric identifier; and alphanumeric suffix for resubmittals.
 8. Category and type of submittal.
 9. Submittal purpose and description.
 10. Number and title of Specification Section, with paragraph number and generic name for each of multiple items.
 11. Drawing number and detail references, as appropriate.
 12. Indication of full submittal.
 13. Location(s) where product is to be installed, as appropriate.
 14. Other necessary identification.
 15. Remarks.
 16. Signature of transmitter.
- B. Options: Identify options requiring selection by Architect.
- C. Deviations and Additional Information: On each submittal, clearly indicate deviations from requirements in the Contract Documents, including minor variations and limitations; include relevant additional information and revisions, other than those requested by Architect on previous submittals. Indicate by highlighting on each submittal or noting on attached separate sheet.
- D. PDF Submittals: Prepare submittals as PDF package, incorporating complete information into each PDF file. Name PDF file with submittal number.

1.6 SUBMITTAL PROCEDURES

- A. Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.

1. Email: Prepare submittals as PDF package and transmit to Architect by sending via email. Include PDF transmittal form. Include information in email subject line as requested by Architect.
 - a. Architect will return annotated file. Annotate and retain one copy of file as a digital Project Record Document file.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.
 3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.
 4. Coordinate transmittal of submittals for related parts of the Work specified in different Sections so processing will not be delayed because of need to review submittals concurrently for coordination.
 - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 3. Resubmittal Review: Allow 15 days for review of each resubmittal.
 4. Sequential Review: Where sequential review of submittals by Architect's consultants, Owner, or other parties is indicated, allow 21 days for initial review of each submittal.
 5. Concurrent Consultant Review: Where the Contract Documents indicate that submittals may be transmitted simultaneously to Architect and to Architect's consultants, allow 15 days for review of each submittal. Submittal will be returned to Architect before being returned to Contractor.
- D. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
 1. Note date and content of previous submittal.
 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
 3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.
- E. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- F. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.

1.7 SUBMITTAL REQUIREMENTS

- A. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
 1. If information must be specially prepared for submittal because standard published data are unsuitable for use, submit as Shop Drawings, not as Product Data.

2. Mark each copy of each submittal to show which products and options are applicable.
 3. Include the following information, as applicable:
 - a. Manufacturer's catalog cuts.
 - b. Manufacturer's product specifications.
 - c. Standard color charts.
 - d. Statement of compliance with specified referenced standards.
 - e. Testing by recognized testing agency.
 - f. Application of testing agency labels and seals.
 - g. Notation of coordination requirements.
 - h. Availability and delivery time information.
 4. For equipment, include the following in addition to the above, as applicable:
 - a. Wiring diagrams that show factory-installed wiring.
 - b. Printed performance curves.
 - c. Operational range diagrams.
 - d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.
 5. Submit Product Data before Shop Drawings, and before or concurrent with Samples.
- B. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data unless submittal based on Architect's digital data drawing files is otherwise permitted.
1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
 - a. Identification of products.
 - b. Schedules.
 - c. Compliance with specified standards.
 - d. Notation of coordination requirements.
 - e. Notation of dimensions established by field measurement.
 - f. Relationship and attachment to adjoining construction clearly indicated.
 - g. Seal and signature of professional engineer if specified.
- C. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other materials.
1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
 2. Identification: Permanently attach label on unexposed side of Samples that includes the following:
 - a. Project name and submittal number.
 - b. Generic description of Sample.
 - c. Product name and name of manufacturer.
 - d. Sample source.
 - e. Number and title of applicable Specification Section.
 - f. Specification paragraph number and generic name of each item.
 3. Email Transmittal: Provide PDF transmittal. Include digital image file illustrating Sample characteristics, and identification information for record.
 4. Paper Transmittal: Include paper transmittal including complete submittal information indicated.
 5. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
 - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.

- b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
 - 6. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
 - a. Number of Samples: Submit three sets of Samples. Architect will retain two Sample sets; remainder will be returned. Mark up and retain one returned Sample set as a project record Sample.
 - 1) Submit a single Sample where assembly details, workmanship, fabrication techniques, connections, operation, and other similar characteristics are to be demonstrated.
 - 2) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least three sets of paired units that show approximate limits of variations.
- D. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
 - 1. Type of product. Include unique identifier for each product indicated in the Contract Documents or assigned by Contractor if none is indicated.
 - 2. Manufacturer and product name, and model number if applicable.
 - 3. Number and name of room or space.
 - 4. Location within room or space.
- E. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- F. Design Data: Prepare and submit written and graphic information indicating compliance with indicated performance and design criteria in individual Specification Sections. Include list of assumptions and summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Number each page of submittal.
- G. Certificates:
 - 1. Certificates and Certifications Submittals: Submit a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity. Provide a notarized signature where indicated.
 - 2. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
 - 3. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
 - 4. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.
 - 5. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.
 - 6. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record

of Welding Procedure Specification and Procedure Qualification Record on AWS forms. Include names of firms and personnel certified.

- H. Test and Research Reports:
1. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
 2. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
 3. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
 4. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
 5. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
 6. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
 - a. Name of evaluation organization.
 - b. Date of evaluation.
 - c. Time period when report is in effect.
 - d. Product and manufacturers' names.
 - e. Description of product.
 - f. Test procedures and results.
 - g. Limitations of use.

1.8 DELEGATED-DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
1. If criteria indicated are insufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF file, paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.
1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.
 2. Prepare delegated-design drawings in the following format: Same digital data software program, version, and operating system as original Drawings.
- C. BIM Incorporation: Incorporate delegated-design drawing and data files into BIM established for Project.
1. Prepare delegated-design drawings in the following format: Same digital data software program, version, and operating system as original Drawings.

1.9 CONTRACTOR'S REVIEW

- A. Action Submittals and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Contractor's Approval: Indicate Contractor's approval for each submittal with a uniform approval stamp. Include name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.
 - 1. Architect will not review submittals received from Contractor that do not have Contractor's review and approval.

1.10 ARCHITECT'S REVIEW

- A. Action Submittals: Architect will review each submittal, indicate corrections or revisions required.
 - 1. PDF Submittals: Architect will indicate, via markup on each submittal, the appropriate action.
 - 2. Paper Submittals: Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.
- B. Informational Submittals: Architect will review each submittal and will not return it or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- C. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.
- D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.
- E. Architect will discard submittals received from sources other than Contractor.
- F. Submittals not required by the Contract Documents will be returned by Architect without action.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

THIS PAGE IS INTENTIONALLY LEFT BLANK



SUBMITTAL TRANSMITTAL

Project: _____ Date: _____
A/E Project Number: _____

TRANSMITTAL A To (Contractor): _____ Date: _____ Submittal No. _____
From (Subcontractor): _____ By: _____ Resubmission

Qty.	Reference / Number	Title / Description / Manufacturer	Spec. Section Title and Paragraph / Drawing Detail Reference

- Submitted for review and approval
- Resubmitted for review and approval
- Complies with contract requirements
- Will be available to meet construction schedule
- A/E review time included in construction schedule
- Substitution involved - Substitution request attached
- If substitution involved, submission includes point-by-point comparative data or preliminary details
- Items included in submission will be ordered immediately upon receipt of approval

Other remarks on above submission: _____ One copy retained by sender

TRANSMITTAL B To (A/E): _____ Attn: _____ Date Rec'd by Contractor: _____
From (Contractor): _____ By: _____ Date Trnsmt'd by Contractor: _____

- Approved
- Approved as noted
- Revise / Resubmit
- Rejected / Resubmit

Other remarks on above submission: _____ One copy retained by sender

TRANSMITTAL C To (Contractor): _____ Attn: _____ Date Rec'd by A/E: _____
From (A/E): _____ Other By: _____ Date Trnsmt'd by A/E: _____

- Approved
- Approved as noted
- Not subject to review
- No action required
- Revise / Resubmit
- Rejected / Resubmit
- Approved as noted / Resubmit
- Provide file copy with corrections identified
- Sepia copies only returned
- Point-by-point comparative data required to complete approval process
- Submission Incomplete / Resubmit

Other remarks on above submission: _____ One copy retained by sender

TRANSMITTAL D To (Subcontractor): _____ Attn: _____ Date Rec'd by Contractor: _____
From (Contractor): _____ By: _____ Date Trnsmt'd by Contractor: _____

Copies: Owner Consultants _____ _____ _____ One copy retained by sender

file transfer

contractor requesting

contact

email

At your request, we will provide electronic files for your convenience and use for the project, subject to the following terms and conditions:

Our electronic files (BIM model or other CAD files) are compatible with REVIT 20___ or AutoCAD 20___. We make no representation as to the compatibility of these files with your hardware or your software beyond the specified release of the referred specifications.

Data contained on these electronic files are part of our instruments of service and shall not be used by you or anyone else receiving these data through or from you for any purpose other than as a convenience for the referenced project. Any other use or reuse by you or by others will be at your sole risk and without liability or legal exposure to ajc architects and the consulting engineers for this project. You agree to make no claim and hereby waive, to the fullest extent permitted by law, any claim or cause of action of any nature against us, our officers, directors, employees, agents or sub consultants that may arise out of or in connection with your use of the electronic files.

Furthermore, you shall, to the fullest extent permitted by law, indemnify and hold us harmless against all damages, liabilities or costs, including reasonable attorneys' fees and defense costs, arising out of or resulting from your use of these electronic files.

These electronic files are not construction documents. Differences may exist between these electronic files and corresponding hard-copy construction documents. In the event that a conflict arises between the signed or sealed hardcopy construction documents prepared by ajc architects and consulting engineers, and the electronic files, the signed or sealed hard-copy construction documents shall govern. You are responsible for determining if any conflict exists. By your use of these electronic files, you are not relieved of your duty to fully comply with the contract documents, including, and without limitation, the need to check, confirm and coordinate all dimensions and details, take field measurements, verify field conditions and coordinate your work with that of other contractors for the project.

Under no circumstances shall delivery of the electronic files for use by you be deemed a sale by us, and we make no warranties, either express or implied, of merchantability and fitness for any particular purpose. In no event shall we be liable for any loss of profit or any consequential damages as a result of your use or reuse of these electronic files. The drawings files provided by ajc architects and consulting engineers may not be reproduced or distributed to individuals outside the company or collective organization signing this agreement.

signature of receiver

SECTION 01 40 00
QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspection services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specific quality-assurance and quality-control requirements for individual work results are specified in their respective Specification Sections. Requirements in individual Sections may also cover production of standard products.
 - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and quality-control procedures that facilitate compliance with the Contract Document requirements.
 - 3. Requirements for Contractor to provide quality-assurance and quality-control services required by Architect, Owner or authorities having jurisdiction are not limited by provisions of this Section.
- C. Related Requirements:
 - 1. Section 013200 "Construction Progress Documentation" for developing a schedule of required tests and inspections.
 - 2. Section 018113 "High Performance Building System (HPBS) Design Requirements
 - 3. Divisions 02 through 49 Sections for specific test and inspection requirements.

1.3 DEFINITIONS

- A. Experienced: When used with an entity or individual, "experienced" unless otherwise further described means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.
- B. Field Quality-Control Tests: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- C. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, assembly, and similar operations.
 - 1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).
- D. Mockups: Full-size physical assemblies that are constructed on-site either as freestanding temporary built elements or as part of permanent construction. Mockups are constructed to verify selections made under Sample submittals; to demonstrate aesthetic effects and qualities of materials and execution; to review coordination, testing, or operation; to show interface between dissimilar materials; and to demonstrate

compliance with specified installation tolerances. Mockups are not Samples. Unless otherwise indicated, approved mockups establish the standard by which the Work will be judged.

1. Laboratory Mockups: Full-size physical assemblies constructed and tested at testing facility to verify performance characteristics.
 2. Integrated Exterior Mockups: Mockups of the exterior envelope constructed on-site as part of permanent construction, consisting of multiple products, assemblies, and subassemblies. Refer to Section 019117 – Functional Performance Testing Requirements.
 3. Room Mockups: Mockups of typical interior spaces complete with wall, floor, and ceiling finishes; doors; windows; millwork; casework; specialties; furnishings and equipment; and lighting.
- E. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.
- F. Product Tests: Tests and inspections that are performed by a nationally recognized testing laboratory (NRTL) according to 29 CFR 1910.7, by a testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program (NVLAP), or by a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- G. Source Quality-Control Tests: Tests and inspections that are performed at the source; for example, plant, mill, factory, or shop.
- H. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- I. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- J. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Contractor's quality-control services do not include contract administration activities performed by Architect.

1.4 DELEGATED-DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.

1.5 CONFLICTING REQUIREMENTS

- A. Conflicting Standards and Other Requirements: If compliance with two or more standards or requirements are specified and the standards or requirements establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for direction before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.6 ACTION SUBMITTALS

- A. Shop Drawings: For mockups.
 - 1. Include plans, sections, and elevations, indicating materials and size of mockup construction.
 - 2. Indicate manufacturer and model number of individual components.
 - 3. Provide axonometric drawings for conditions difficult to illustrate in two dimensions.
- B. Provide items required by the County-issued checklist for each High Performance project. Submittals shall include certificates which guarantee material content.
- C. Provide commissioning plan, including qualifications of CxA, CxA responsibilities, and commissioning team members and responsibilities.
- D. Delegated-Design Services Submittal: In addition to Shop Drawings, Product Data, and other required submittals, submit a statement signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional, indicating that the products and systems are in compliance with performance and design criteria indicated. Include list of codes, loads, and other factors used in performing these services.

1.7 INFORMATIONAL SUBMITTALS

- A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.
- B. Qualification Data: For Contractor's quality-control personnel.
- C. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility submitted to authorities having jurisdiction before starting work on the following systems:
 - 1. Seismic-force-resisting system, designated seismic system, or component listed in the Statement of Special Inspections.
 - 2. Main wind-force-resisting system or a wind-resisting component listed in the Statement of Special Inspections.
- D. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- E. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
 - 1. Specification Section number and title.
 - 2. Entity responsible for performing tests and inspections.
 - 3. Description of test and inspection.
 - 4. Identification of applicable standards.
 - 5. Identification of test and inspection methods.
 - 6. Number of tests and inspections required.
 - 7. Time schedule or time span for tests and inspections.
 - 8. Requirements for obtaining samples.
 - 9. Unique characteristics of each quality-control service.
- F. Reports: Prepare and submit certified written reports and documents as specified.
- G. Permits, Licenses, and Certificates: For Owner's record, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents established for compliance with standards and regulations bearing on performance of the Work.

1.8 CONTRACTOR'S QUALITY-CONTROL PLAN (including testing and inspections by Commissioning Authority)

- A. Quality-Control Plan, General: Submit quality-control plan within 10 days of Notice to Proceed, unless otherwise indicated, and not less than five days prior to preconstruction conference. Submit in format acceptable to Architect. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities. Coordinate with Contractor's Construction Schedule.
- B. Quality-Control Personnel Qualifications: Engage qualified personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.
 - 1. Project quality-control manager may also serve as Project superintendent.
- C. Implement an indoor air quality management plan during construction. This plan shall meet the SMACNA IAQ Guidelines for Occupied Buildings Under Construction, 2nd edition ANSI/SMACNA 008–2008.
 - 1. The Contractor shall submit an Indoor Air Quality Plan to the CxA, outlining the implementation strategies to achieve the SMACNA requirements.
 - 2. Implementation of this plan shall be tracked on the weekly Construction Meeting Minutes.
- D. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.
- E. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:
 - 1. Contractor-performed tests and inspections including Subcontractor-performed tests and inspections. Include required tests and inspections and Contractor-elected tests and inspections. Distinguish source quality-control tests and inspections from field quality-control tests and inspections.
 - 2. Special inspections required by authorities having jurisdiction and indicated on the Statement of Special Inspections.
 - 3. Owner-performed tests and inspections indicated in the Contract Documents, including tests and inspections indicated to be performed by Commissioning Authority.
- F. Continuous Inspection of Workmanship: Describe process for continuous inspection during construction to identify and correct deficiencies in workmanship in addition to testing and inspection specified. Indicate types of corrective actions to be required to bring work into compliance with standards of workmanship established by Contract requirements and approved mockups.
- G. Monitoring and Documentation: Maintain testing and inspection reports including log of approved and rejected results. Include work Architect has indicated as nonconforming or defective. Indicate corrective actions taken to bring nonconforming work into compliance with requirements. Comply with requirements of authorities having jurisdiction.

1.9 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
 - 1. Date of issue.
 - 2. Project title and number.
 - 3. Name, address, telephone number, and email address of testing agency.
 - 4. Dates and locations of samples and tests or inspections.
 - 5. Names of individuals making tests and inspections.
 - 6. Description of the Work and test and inspection method.
 - 7. Identification of product and Specification Section.
 - 8. Complete test or inspection data.

9. Test and inspection results and an interpretation of test results.
 10. Record of temperature and weather conditions at time of sample taking and testing and inspection.
 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
 12. Name and signature of laboratory inspector.
 13. Recommendations on retesting and reinspection.
- B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:
1. Name, address, telephone number, and email address of technical representative making report.
 2. Statement on condition of substrates and their acceptability for installation of product.
 3. Statement that products at Project site comply with requirements.
 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 6. Statement whether conditions, products, and installation will affect warranty.
 7. Other required items indicated in individual Specification Sections.
- C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:
1. Name, address, telephone number, and email address of factory-authorized service representative making report.
 2. Statement that equipment complies with requirements.
 3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 4. Statement whether conditions, products, and installation will affect warranty.
 5. Other required items indicated in individual Specification Sections.

1.10 QUALITY ASSURANCE

- A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units. As applicable, procure products from manufacturers able to meet qualification requirements, warranty requirements, and technical or factory-authorized service representative requirements.
- C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- D. Installer Qualifications: A firm or individual experienced in installing, erecting, applying, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar in material, design, and extent to those indicated for this Project.
- F. Specialists: Certain Specification Sections require that specific construction activities shall be performed by entities who are recognized experts in those operations.

Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.

1. Requirements of authorities having jurisdiction shall supersede requirements for specialists.
- G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspection indicated, as documented according to ASTM E 329; and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.
- H. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- I. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- J. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:
1. Contractor responsibilities include the following:
 - a. Provide test specimens representative of proposed products and construction.
 - b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
 - c. Provide sizes and configurations of test assemblies, mockups, and laboratory mockups to adequately demonstrate capability of products to comply with performance requirements.
 - d. Build site-assembled test assemblies and mockups using installers who will perform same tasks for Project.
 - e. Build laboratory mockups at testing facility using personnel, products, and methods of construction indicated for the completed Work.
 - f. When testing is complete, remove test specimens and test assemblies, and mockups, and laboratory mockups; do not reuse products on Project.
 2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect and Commissioning Authority, with copy to Contractor. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.
- K. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:
1. Build mockups of size indicated. Coordinate with Architect.
 2. Build mockups in location indicated or, if not indicated, as directed by Architect.
 3. Integrated Exterior Mock-up for Functional Performance Testing
 4. Notify Architect seven days in advance of dates and times when mockups will be constructed.
 5. Employ supervisory personnel who will oversee mockup construction. Employ workers that will be employed to perform same tasks during the construction at Project.
 6. Demonstrate the proposed range of aesthetic effects and workmanship.
 7. Obtain Architect's approval of mockups before starting corresponding work, fabrication, or construction.
 - a. Allow seven days for initial review and each re-review of each mockup.

8. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
9. Demolish and remove mockups when directed unless otherwise indicated or is to become part of the finished work.

1.11 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
 1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspection they are engaged to perform.
 2. Payment for these services will be made from testing and inspection allowances, as authorized by Change Orders.
 3. Costs for retesting and reinspection construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.
- B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities, whether specified or not, to verify and document that the Work complies with requirements.
 1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
 2. Engage a qualified testing agency to perform quality-control services.
 - a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
 3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspection will be performed.
 4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
 5. Testing and inspection requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
 6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Retesting/Reinspection: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspection, for construction that replaced Work that failed to comply with the Contract Documents.
- D. Testing Agency Responsibilities: Cooperate with Architect, Commissioning Authority and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
 1. Notify Architect, Commissioning Authority and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
 2. Determine the locations from which test samples will be taken and in which in-situ tests are conducted.
 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
 6. Do not perform duties of Contractor.
- E. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation,

including service connections. Report results in writing as specified in Section 013300 "Submittal Procedures."

- F. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.
- G. Associated Contractor Services: Cooperate with agencies and representatives performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
 - 1. Access to the Work.
 - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 - 3. Adequate quantities of representative samples of materials that require testing and inspection. Assist agency in obtaining samples.
 - 4. Facilities for storage and field curing of test samples.
 - 5. Delivery of samples to testing agencies.
 - 6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
 - 7. Security and protection for samples and for testing and inspection equipment at Project site.
- H. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and quality-control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspection.
 - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.
- I. Implement a pre-occupancy air quality plan.
 - 1. At the end of construction, prior to occupancy, conduct an air quality test per Salt Lake County Commissioning requirements.
 - 2. The Test and Balance sub-contractor shall provide documentation to the Commissioning Agent demonstrating the dates and air flows achieved during the building flush.
- J. All interior paints and coatings shall meet the low emitting materials standards set forth by the South Coast Air Quality Management District Rule 1113, as adopted in January 2012 or current version.
- K. All interior adhesives and sealants shall meet the low emitting materials standards set forth by the South Coast Air Quality Management District Rule 1168, as adopted in January 2005 or current version.

1.12 SPECIAL TESTS AND INSPECTIONS

- A. Special Tests and Inspections: Owner will engage a qualified testing agency / special inspector to conduct special tests and inspections required by authorities having jurisdiction as the responsibility of Owner.
 - 1. Notify Architect, Commissioning Authority and Owner of any irregularities or deficiencies in the work observed in the performance of its services.
 - 2. Submit certified written report of each test, inspection and similar quality control service to Architect, Commissioning Authority and Owner.
 - 3. Submit final report of special tests and inspections at substantial completion including a list of unresolved deficiencies.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

- A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:
 - 1. Date test or inspection was conducted.
 - 2. Description of the Work tested or inspected.
 - 3. Date test or inspection results were transmitted to Architect.
 - 4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's and Commissioning Authority reference during normal working hours.

3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspection, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
 - 1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 50 00
TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes requirements for Temporary facilities and controls, including temporary utilities support facilities and security and protection facilities.
- B. Responsibility for temporary facilities will be assigned to the Contractor.
- C. Temporary utilities include, but are not limited to, the following:
 - 1. Water service distribution.
 - 2. Sanitary facilities, including toilets.
 - 3. Ventilation.
 - 4. Electric power distribution service.
 - 5. Lighting.
- D. Support facilities include, but are not limited to, the following:
 - 1. Temporary signs (approved by Owner).
 - 2. Waste disposal facilities.
 - 3. Field offices.
- E. Security and protection facilities include, but are not limited to, the following:
 - 1. Temporary Enclosures for existing construction.
 - 2. Existing utilities.
- F. Related Sections:
 - 1. Division 01 Section "Submittal Procedures" for procedures for submitting copies of implementation and termination schedule.
 - 2. Division 01 section "Execution" for progress cleaning requirements.
 - 3. Division 02 through 33 for temporary heat, ventilation and humidity requirements for products in those Sections.

1.3 USE CHARGES

- A. General: Installation and removal of and use charges for temporary facilities shall be included in the Contract Sum unless otherwise indicated. Allow other entities to use temporary services and facilities without cost, including, but not limited to, Owner's construction forces, Architect, occupants of Project, testing agencies, and authorities having jurisdiction.
- B. Sewer Service: Pay sewer-service use charges for sewer usage by all entities for construction operations.
- C. Water Service: Pay water-service use charges for water used by all entities for construction operations.
- D. Electric Power Service: Pay electric-power-service use charges for electricity used by all entities for construction operations.

1.4 INFORMATIONAL SUBMITTALS

- A. Site Utilization Plan: Show temporary facilities, temporary utility lines and connections, staging areas, construction site entrances, vehicle circulation, and parking areas for construction personnel.
- B. Implementation and Termination Schedule: Within 15 days of date established for commencement of the Work, submit schedule indicating implementation and termination dates of each temporary utility.
- C. Project Identification and Temporary Signs: Show fabrication and installation details, including plans, elevations, details, layouts, typestyles, graphic elements, and message content.
- D. Fire-Safety Program: Show compliance with requirements of NFPA 241 and authorities having jurisdiction. Indicate Contractor personnel responsible for management of fire-prevention program.
- E. Erosion- and Sedimentation-Control Plan: Show compliance with requirements of EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent.

1.5 SUBMITTALS

- A. Implementation and termination Schedule: Within 10 days of date established for submittal of Contractor's Construction Schedule, submit a schedule indicating implementation.

1.6 QUALITY ASSURANCE

- A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.
- C. Accessible Temporary Egress: Comply with applicable provisions in the United States Access Board's ADA-ABA Accessibility Guidelines and ICC/ANSI A117.1.

1.7 PROJECT CONDITIONS

- A. Conditions of Use: The following conditions apply to use of temporary services and facilities by all parties engaged in the Work:
 - 1. Keep temporary services and facilities clean and neat.
 - 2. Relocate temporary services and facilities as required by progress of the Work.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Provide new materials. Undamaged, previously used materials in serviceable condition may be used if approved by Architect. Provide materials suitable for use intended.
- B. Portable Chain-Link Fencing and Gates: Minimum 2-inch, 9 gauge thick, galvanized steel, chain-link fabric fencing; minimum 6 feet high with galvanized steel pipe posts; minimum 2-3/8-inch-OD line posts and 2-7/8-inch-OD corner and pull posts, with 1-5/8-inch-OD top and bottom rails. Provide concrete bases for supporting posts.
- C. Tarpaulins: Fire-resistive labeled with flame-spread rating of 15 or less.
- D. Water: Potable.
- E. Wood Studs, Vis-queen, Walk-off Dust mats.

2.2 EQUIPMENT

- A. General: Provide equipment suitable for use intended.
 - 1. Field Offices: Mobile units with lockable entrances, operable windows and serviceable finishes; heated and air conditioned; on foundations adequate for normal loading.
- B. Fire Extinguishers: Hand carried, portable, UL rated; with class and extinguishing agent as required by locations or a combination of extinguishers of NFPA-recommended classes for exposures. classes of fire exposures.
 - 1. Comply with HFWA 10 and HFWA 241 for classification, extinguishing agent and size requirement by location and class of fire exposure.
- C. Self-Contained Toilet Units: Single-occupant units of chemical, aerated recirculation, or combustion type; vented; fully enclosed with a glass-fiber-reinforced polyester shell or similar nonabsorbent material.
- D. Electrical Outlets: Properly configured, NEMA-polarized outlets to prevent insertion of 110 to 120 v plugs into higher-voltage outlets; equipped with ground-fault circuit interrupters, reset button, and pilot light.
- E. Power distribution System Circuits: Where permitted and overhead and exposed for surveillance, wiring circuits, not exceeding 125V ac, 20A rating, and lighting circuits may be nonmetallic sheathed cable.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.
- B. Provide each facility ready for use when needed to avoid delay. Do not remove from site until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

- A. Electric Power Service: Provide electric power service and distribution system of sufficient size, capacity, and power characteristics required for construction operations.
- B. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.
- C. Temporary Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.

3.3 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:
 - 1. Locate field offices, storage sheds, sanitary facilities and other temporary construction and support facilities for easy access.
 - 2. Provide incombustible construction for offices, shops and sheds located within construction area or within 30 feet of building lines. Comply with NFPA 241.
 - 3. Maintain support facilities until Architect schedules Substantial Completion inspection. Remove before Substantial Completion. Personnel remaining after

Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.

- B. Project Identification and Temporary Signs: Project identification and other signs requires Owners approval. Install signs at locations where Owner has approved and is acceptable by authorities of jurisdiction. Do not permit installation of unauthorized signs.
 - 1. Construct signs of exterior-type Grade B-B high-density concrete form overlay plywood of at least one sheet of ¾ inch thick material. Support on posts or framing of preservative treated wood or steel.
 - 2. Paint sign panel and applied graphics with exterior-grade alkyd gloss enamel over exterior primer.
 - 3. Content and location of direction signs will be at the direction of the Owner.
 - 4. Maintain and touchup signs so they are legible at all times.
- C. Waste Disposal Facilities: Comply with requirements specified in Division 01 Section "Construction Waste Management and Disposal."
- D. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Containerize and clearly label hazardous, dangerous or unsanitary waste materials separately for other waste. Comply with requirements of authorities having jurisdiction. Comply with Division 01 Section "Execution" for progress cleaning requirements.
- E. Common-use Field Office: Provide an insulated, weathertight, air-conditioned field office for use as a common facility by all personnel engaged in construction activities; of sufficient size to accommodate required office personnel at project site. Keep office clean and orderly.
 - 1. Provide fluorescent light fixtures capable of maintaining average illumination of 20 fc at desk height. Provide 110 to 120 V duplex outlets spaced at not more than 12-foot intervals, 1 per wall in each room.
- F. Storage and Fabrication Sheds: provide sheds sized, furnished and equipped to accommodate materials and equipment involved, including temporary utility services. Sheds may be open shelters or fully enclosed spaces within building or elsewhere on site.

3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.
- B. Security Enclosure and Lockup: Install substantial temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each workday.
- C. Barricades, Warning Signs, and Lights: Comply with standards and code required, structurally adequate barricades, including warning signs and lighting. Paint with appropriate colors, graphics and warning signs to inform personnel and public of possible hazard. Where appropriate and needed, provide lighting, including flashing red or amber lights.

3.5 OPERATION, TERMINATION AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Maintenance: Maintain facilities in good operating condition until removal. Protect from damage caused by freezing temperatures and similar elements.
 - 1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.

- C. Temporary facility Changeover: do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.
- D. Termination and removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delays because of interference with temporary facility. Repair damaged work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
 - 1. Materials and facilities that constitute temporary facilities are the property of Contractor. Owner reserves right to take possession of Project identification signs.
 - 2. At substantial Completion, clean and renovate permanent facilities used during construction period. Comply with final cleaning procedures.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 56 39

TREE PROTECTION

PART 1 GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the protection and trimming of trees that interfere with, or are affected by, execution of the Work, whether temporary or new construction.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Qualification Data: For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- C. Certification: From a qualified arborist that trees indicated to remain have been protected during all phases of construction according to recognized standards and those trees were promptly and properly treated and repaired when damaged.
- D. Maintenance Recommendations: From a qualified arborist for care and protection of trees affected by construction during and after completing the Work.

1.4 QUALITY ASSURANCE

- A. Tree Service Qualifications: An experienced tree service firm that has successfully completed tree protection and trimming work similar to that required for this Project and that will assign an experienced, qualified arborist to Project site during execution of the Work.
- B. Arborist Qualifications: An arborist certified by the International Society of Arboriculture or licensed in the jurisdiction where Project is located.
- C. Tree Pruning Standards: Comply with ANSI A300, "Trees, Shrubs, and Other Woody Plant Maintenance--Standard Practices," unless more stringent requirements are indicated.
- D. Pre-installation Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Meetings."
 - 1. Before starting tree protection and trimming, meet with representatives of authorities having jurisdiction, Owner, Architect, consultants, and other concerned entities. Review tree protection and trimming procedures and responsibilities. Notify participants at least three working days before convening conference. Record discussions and agreements and furnish a copy to each participant.

PART 2 PRODUCTS

2.1 MATERIALS

- A. (not used)

PART 3 EXECUTION

3.1 PREPARATION

- A. Protect tree root systems from damage due to noxious materials caused by runoff or spillage while mixing, placing, or storing construction materials. Protect root systems from flooding, eroding, or excessive wetting caused by dewatering operations.
- B. Do not store construction materials, debris, or excavated material within the drip line of existing trees. Do not permit vehicles or foot traffic within the drip line; prevent soil compaction over root systems.
- C. Do not allow fires under or adjacent to remaining trees or other plants.

3.2 EXCAVATION

- A. Install shoring or other protective support systems to minimize sloping or benching of excavations.
- B. Do not excavate within drip line of trees, unless otherwise indicated.
- C. Where excavation for new construction is required within drip line of trees, do not excavate within 10ft. of trunk. Clear by hand or use Air Spade to excavate to minimize damage to root systems. Use narrow-tine spading forks and comb soil to expose roots.
 - 1. Relocate roots in backfill areas where possible. If encountering large, main lateral roots, expose roots beyond excavation limits as required to bend and relocate them without breaking. If encountered immediately adjacent to location of new construction and relocation is not practical, cut roots approximately 3 inches back from new construction.
 - 2. Do not allow exposed roots to dry out before placing permanent backfill. Provide temporary earth cover or pack with peat moss and wrap with burlap. Water and maintain in a moist condition. Temporarily support and protect roots from damage until they are permanently relocated and covered with soil.
- D. Where utility trenches are required within drip line of trees, tunnel under or around roots by drilling, auger boring, pipe jacking, or digging by hand.

3.3 TREE PRUNING

- A. Prune remaining trees affected by temporary and new construction.
- B. Prune remaining trees to compensate for root loss caused by damaging or cutting root system. Provide subsequent maintenance during Contract period as recommended by qualified arborist.
- C. Pruning Standards: Prune trees according to ANSI A300 as follows:
 - 1. Type of Pruning: Crown cleaning.
 - 2. Type of Pruning: Crown thinning.
 - 3. Type of Pruning: Crown raising.
 - 4. Type of Pruning: Crown reduction.
 - 5. Type of Pruning: Vista pruning.
 - 6. Type of Pruning: Crown restoration.
- D. Cut branches with sharp pruning instruments; do not break or chop.

- E. Chip branches removed from trees. Spread chips where indicated or as directed by the Landscape Architect.

3.4 TREE REPAIR AND REPLACEMENT

- A. Promptly repair trees damaged by construction operations within 24 hours. Treat damaged trunks, limbs, and roots according to written instructions of the qualified arborist.
- B. Remove and replace dead and damaged trees that the qualified arborist determines to be incapable of restoring to a normal growth pattern.
 - 1. Provide new trees of the same size and species as those being replaced; plant and maintain as specified in Division 2 Section "Landscaping."
 - 2. Provide new trees of 6-inch caliper size and of a species selected by Project Manager when trees more than 6 inches in caliper size, measured 12 inches above grade, are required to be replaced.
- C. Aerate surface soil, compacted during construction, 10 feet beyond drip line and no closer than 36 inches to tree trunk. Drill 2-inch-diameter holes a minimum of 12 inches deep at 24 inches o.c. Backfill holes with an equal mix of augured soil and sand.

3.5 DISPOSAL OF WASTE MATERIALS

- A. Burning is not permitted.
- B. Disposal: Remove excess excavated material, displaced trees, and excess chips from Owner's property.

END OF SECTION

SECTION 01 60 00
PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.
- B. Related Requirements:
 - 1. Section 012500 "Substitution Procedures" for requests for substitutions.

1.3 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
 - 3. Comparable Product: Product that is demonstrated and approved by Architect through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a single manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation. In addition to the basis-of-design product description, product attributes and characteristics may be listed to establish the significant qualities related to type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other special features and requirements for purposes of evaluating comparable products of additional manufacturers named in the specification.
- C. Subject to Compliance with Requirements: Where the phrase "Subject to compliance with requirements" introduces a product selection procedure in an individual Specification Section, provide products qualified under the specified product procedure. In the event that a named product or product by a named manufacturer does not meet the other requirements of the specifications, select another named product or product from another named manufacturer that does meet the requirements of the specifications. Submit a comparable product request, if applicable.

1.4 ACTION SUBMITTALS

- A. Comparable Product Request Submittal: Submit request for consideration of each comparable product. Identify basis-of-design product or fabrication or installation method

to be replaced. Include Specification Section number and title and Drawing numbers and titles.

1. Include data to indicate compliance with the requirements specified in "Comparable Products" Article.
 2. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
 - a. Form of Architect's Approval of Submittal: As specified in Section 013300 "Submittal Procedures."
 - b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.
- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Section 013300 "Submittal Procedures." Show compliance with requirements.
- C. Provide items required by the County-issued checklist for each High Performance project. Submittals shall include certificates which guarantee material content.
- D. Provide commissioning plan, including qualifications of CxA, CxA responsibilities, and commissioning team members and responsibilities.

1.5 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.
1. Each contractor is responsible for providing products and construction methods compatible with products and construction methods of other contractors.
 2. If a dispute arises between contractors over concurrently selectable but incompatible products, Architect will determine which products shall be used.
- B. Identification of Products: Except for required labels and operating data, do not attach or imprint manufacturer or product names or trademarks on exposed surfaces of products or equipment that will be exposed to view in occupied spaces or on the exterior.

1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.
- B. Delivery and Handling:
1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
 4. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.
- C. Storage:
1. Store products to allow for inspection and measurement of quantity or counting of units.
 2. Store materials in a manner that will not endanger Project structure.

3. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
4. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
5. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
6. Protect stored products from damage and liquids from freezing.
7. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

1.7 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
 1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
 2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.
 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
 2. Specified Form: When specified forms are included with the Specifications, prepare a written document using indicated form properly executed.
 3. See other Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Section 017700 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.
 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
 3. Owner reserves the right to limit selection to products with warranties meeting requirements of the Contract Documents.
 4. Where products are accompanied by the term "as selected," Architect will make selection.
 5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
 6. Or Equal: For products specified by name and accompanied by the term "or equal," or "or approved equal," or "or approved," or "or approved substitution" comply with requirements in "Comparable Products" Article to obtain approval for use of an unnamed product.

- a. Submit additional documentation required by Architect in order to establish equivalency of proposed products. Evaluation of "or equal" product status is by the Architect; whose determination is final.
- B. Product Selection Procedures:
 - 1. Sole Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 - a. Sole product may be indicated by the phrase: "Subject to compliance with requirements, provide the following: ..."
 - 2. Sole Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 - a. Sole manufacturer/source may be indicated by the phrase: "Subject to compliance with requirements, provide products by the following: ..."
 - 3. Limited List of Products: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 - a. Limited list of products may be indicated by the phrase: "Subject to compliance with requirements, provide one of the following: ..."
 - 4. Non-Limited List of Products: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed, or an unnamed product, which complies with requirements.
 - a. Non-limited list of products is indicated by the phrase: "Subject to compliance with requirements, available products that may be incorporated in the Work include, but are not limited to, the following: ..."
 - 5. Limited List of Manufacturers: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 - a. Limited list of manufacturers is indicated by the phrase: "Subject to compliance with requirements, provide products by one of the following: ..."
 - 6. Non-Limited List of Manufacturers: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed, or a product by an unnamed manufacturer, which complies with requirements.
 - a. Non-limited list of manufacturers is indicated by the phrase: "Subject to compliance with requirements, available manufacturers whose products may be incorporated in the Work include, but are not limited to, the following: ..."
 - 7. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.
 - a. For approval of products by unnamed manufacturers, comply with requirements in Section 012500 "Substitution Procedures" for substitutions for convenience.
- C. Visual Matching Specification: Where Specifications require "match Architect's sample," provide a product that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product match.

1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Section 012500 "Substitution Procedures" for proposal of product.
- D. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

- A. Conditions for Consideration of Comparable Products: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:
1. Evidence that proposed product does not require revisions to the Contract Documents, is consistent with the Contract Documents, will produce the indicated results, and is compatible with other portions of the Work. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant product qualities include attributes such as type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other specific features and requirements.
 2. Evidence that proposed product provides specified warranty.
 3. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
 4. Samples, if requested.
- B. Submittal Requirements: Approval by the Architect of Contractor's request for use of comparable product is not intended to satisfy other submittal requirements. Comply with specified submittal requirements.

PART 3 - EXECUTION (Not Used)

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 73 00

EXECUTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work including, but not limited to, the following:
 - 1. Construction layout.
 - 2. Installation of the Work.
 - 3. Cutting and patching.
 - 4. Coordination of Owner-installed products.
 - 5. Progress cleaning.
 - 6. Starting and adjusting.
 - 7. Protection of installed construction.
 - 8. Correction of work.
- B. Related Requirements:
 - 1. Section 013300 "Submittal Procedures" for submitting surveys.
 - 2. Section 017700 "Closeout Procedures" for submitting final property survey with Project Record Documents, recording of Owner-accepted deviations from indicated lines and levels, replacing defective work, and final cleaning.
 - 3. Section 018113 "High Performance Building System (HPBS) Design Requirements
 - 4. Section 019113 "General Commissioning Requirements"

1.3 DEFINITIONS

- A. Cutting: Removal of in-place construction necessary to permit installation or performance of subsequent work.
- B. Patching: Fitting and repair work required to restore construction to original conditions after installation of subsequent work.

1.4 PREINSTALLATION MEETINGS

- A. Cutting and Patching Conference: Conduct conference at Project site.
 - 1. Prior to commencing work requiring cutting and patching, review extent of cutting and patching anticipated and examine procedures for ensuring satisfactory result from cutting and patching work. Require representatives of each entity directly concerned with cutting and patching to attend, including the following:
 - a. Contractor's superintendent.
 - b. Trade supervisor responsible for cutting operations.
 - c. Trade supervisor(s) responsible for patching of each type of substrate.
 - d. Mechanical, electrical, and utilities subcontractors' supervisors, to the extent each trade is affecting by cutting and patching operations.
 - 2. Review areas of potential interference and conflict. Coordinate procedures and resolve potential conflicts before proceeding.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For professional engineer.
- B. Certificates: Submit certificate signed by professional engineer certifying that location and elevation of improvements comply with requirements.
- C. Landfill Receipts: Submit copy of receipts issued by a landfill facility, licensed to accept hazardous materials, for hazardous waste disposal.

1.6 QUALITY ASSURANCE

- A. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.
 - 1. Structural Elements: When cutting and patching structural elements, notify Architect of locations and details of cutting and await directions from Architect before proceeding. Shore, brace, and support structural elements during cutting and patching. Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection.
 - 2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety. Operational elements include the following:
 - a. Primary operational systems and equipment.
 - b. Fire separation assemblies.
 - c. Air or smoke barriers.
 - d. Plumbing piping systems.
 - e. Mechanical systems piping and ducts.
 - f. Control systems.
 - g. Communication systems.
 - h. Electrical wiring systems.
 - i. Operating systems of special construction.
 - 3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety. Other construction elements include but are not limited to the following:
 - a. Water, moisture, or vapor barriers.
 - b. Membranes and flashings.
 - c. Equipment supports.
 - d. Piping, ductwork, vessels, and equipment.
 - e. Noise- and vibration-control elements and systems.
 - 4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- B. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of products and equipment.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.

1. For projects requiring compliance with sustainable design and construction practices and procedures, use products for patching that comply with sustainable design requirements.
- B. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
 1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Existing Conditions: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities, mechanical and electrical systems and other construction affecting the Work.
 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; underground electrical services; and other utilities.
 2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
 1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
 2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
 3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Written Report: Where a written report listing conditions detrimental to performance of the Work is required by other Sections, include the following:
 1. Description of the Work.
 2. List of detrimental conditions, including substrates.
 3. List of unacceptable installation tolerances.
 4. Recommended corrections.
- D. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Existing Utility Information: Furnish information to local utility and Owner that is necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or other utility appurtenances located in or affected by construction. Coordinate with authorities having jurisdiction.
- B. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- C. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.

- D. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents caused by differing field conditions outside the control of Contractor, submit a request for information to Architect according to requirements in Section 013100 "Project Management and Coordination."

3.3 CONSTRUCTION LAYOUT

- A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks. If discrepancies are discovered, notify Architect promptly.
- B. General:
 - 1. Establish limits on use of Project site.
 - 2. Establish dimensions within tolerances indicated. Do not scale Drawings to obtain required dimensions.
 - 3. Inform installers of lines and levels to which they must comply.
 - 4. Check the location, level and plumb, of every major element as the Work progresses.
 - 5. Notify Architect when deviations from required lines and levels exceed allowable tolerances.

3.4 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
 - 1. Make vertical work plumb and make horizontal work level.
 - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
 - 3. Conceal pipes, ducts, and wiring in finished areas unless otherwise indicated.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Tools and Equipment: Where possible, select tools or equipment that minimize production of excessive noise levels.
- F. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other portions of the Work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- G. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions.
 - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
 - 2. Allow for building movement, including thermal expansion and contraction.
 - 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.
- H. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
- I. Repair or remove and replace damaged, defective, or nonconforming Work.

1. Comply with Section 017700 "Closeout Procedures" for repairing or removing and replacing defective Work.

3.5 CUTTING AND PATCHING

- A. Cutting and Patching, General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during installation or cutting and patching operations, by methods and with materials so as not to void existing warranties.
- C. Temporary Support: Provide temporary support of work to be cut.
- D. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- E. Adjacent Occupied Areas: Where interference with use of adjoining areas or interruption of free passage to adjoining areas is unavoidable, coordinate cutting and patching according to requirements in Section 011000 "Summary."
- F. Existing Utility Services and Mechanical/Electrical Systems: Where existing services/systems are required to be removed, relocated, or abandoned, bypass such services/systems before cutting to minimize interruption to occupied areas.
- G. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
 3. Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
 4. Excavating and Backfilling: Comply with requirements in applicable Sections where required by cutting and patching operations.
 5. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
 6. Proceed with patching after construction operations requiring cutting are complete.
- H. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other work. Patch with durable seams that are as invisible as practicable. Provide materials and comply with installation requirements specified in other Sections, where applicable.
 1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will minimize evidence of patching and refinishing.
 - a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
 - b. Restore damaged pipe covering to its original condition.
 3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space.

Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.

- a. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch. Provide additional coats until patch blends with adjacent surfaces.
 4. Ceilings: Patch, repair, or rehang in-place ceilings as necessary to provide an even-plane surface of uniform appearance.
 5. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition and ensures thermal and moisture integrity of building enclosure.
- I. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

3.6 OWNER-INSTALLED PRODUCTS

- A. Site Access: Provide access to Project site for Owner's construction personnel.
- B. Coordination: Coordinate construction and operations of the Work with work performed by Owner's construction personnel.
 1. Construction Schedule: Inform Owner of Contractor's preferred construction schedule for Owner's portion of the Work. Adjust construction schedule based on a mutually agreeable timetable. Notify Owner if changes to schedule are required due to differences in actual construction progress.
 2. Preinstallation Conferences: Include Owner's construction personnel at preinstallation conferences covering portions of the Work that are to receive Owner's work. Attend preinstallation conferences conducted by Owner's construction personnel if portions of the Work depend on Owner's construction.

3.7 PROGRESS CLEANING

- A. General: Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.
 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
 2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F (27 deg C).
 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
 - a. Use containers intended for holding waste materials of type to be stored.
 4. Coordinate progress cleaning for joint-use areas where Contractor and other contractors are working concurrently.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
 1. Remove liquid spills promptly.
 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.
- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.

- F. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways. Comply with waste disposal requirements in Section 017419 "Construction Waste Management and Disposal."
- H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- J. Limiting Exposures: Supervise construction operations to ensure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.8 STARTING AND ADJUSTING

- A. Coordinate startup and adjusting of equipment and operating components.
- B. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- C. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.
- D. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- E. Manufacturer's Field Service: Comply with qualification requirements in Section 014000 "Quality Requirements."

3.9 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Protection of Existing Items: Provide protection and ensure that existing items to remain undisturbed by construction are maintained in condition that existed at commencement of the Work.
- C. Comply with manufacturer's written instructions for temperature and relative humidity.

3.10 CORRECTION OF THE WORK

- A. Repair or remove and replace defective construction. Restore damaged substrates and finishes.
 - 1. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment.
- B. Restore permanent facilities used during construction to their specified condition.
- C. Remove and replace damaged surfaces that are exposed to view if surfaces cannot be repaired without visible evidence of repair.
- D. Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.
- E. Remove and replace chipped and scratches, of reflective surfaces.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 74 19
CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for the following:
 - 1. Recycling nonhazardous demolition and construction waste.
 - 2. Disposing of nonhazardous demolition and construction waste.
- B. Related Requirements:
 - 1. Section 042000 "Unit Masonry" for disposal requirements for masonry waste.
 - 2. Section 047000 "Manufactured Masonry" for disposal requirements for disposal requirements for excess manufactured masonry and manufactured masonry waste.
 - 3. Section 311000 "Site Clearing" for disposition of waste resulting from site clearing and removal of above- and below-grade improvements.

1.3 DEFINITIONS

- A. Construction Waste: Building, structure, and site improvement materials and other solid waste resulting from construction, remodeling, renovation, or repair operations. Construction waste includes packaging.
- B. Demolition Waste: Building, structure, and site improvement materials resulting from demolition operations.
- C. Disposal: Removal of demolition or construction waste and subsequent salvage, sale, recycling, or deposit in landfill, incinerator acceptable to authorities having jurisdiction, or designated spoil areas on Owner's property.
- D. Recycle: Recovery of demolition or construction waste for subsequent processing in preparation for reuse.
- E. Salvage: Recovery of demolition or construction waste and subsequent sale or reuse in another facility.
- F. Salvage and Reuse: Recovery of demolition or construction waste and subsequent incorporation into the Work.

1.4 MATERIALS OWNERSHIP

- A. Unless otherwise indicated, demolition and construction waste becomes property of Contractor.

1.5 ACTION SUBMITTALS

- A. Waste Management Plan: At the beginning of the contract, submit a proposed waste management plan complying with above noted requirements to be reviewed and accepted by the County Project Manager.

1.6 INFORMATIONAL SUBMITTALS

- A. Waste Reduction Progress Reports: Concurrent with each Application for Payment, submit report. Use Form CWM-7 for construction waste. Include the following information:
 - 1. Material category.
 - 2. Generation points of waste.
 - 3. Total quantity of waste in tons.
 - 4. Quantity of waste salvaged, both estimated and actual in tons.
 - 5. Quantity of waste recycled, both estimated and actual in tons.
 - 6. Total quantity of waste recovered (salvaged plus recycled) in tons.
 - 7. Total quantity of waste recovered (salvaged plus recycled) as a percentage of
 - 8. total waste.
- B. Waste Reduction Calculations: Before request for Substantial Completion, submit calculated end-of-Project rates for salvage, recycling, and disposal as a percentage of total waste generated by the Work.
- C. Records of Donations: Indicate receipt and acceptance of salvageable waste donated to individuals and organizations. Indicate whether organization is tax exempt.
- D. Records of Sales: Indicate receipt and acceptance of salvageable waste sold to individuals and organizations. Indicate whether organization is tax exempt.
- E. Recycling and Processing Facility Records: Indicate receipt and acceptance of
- F. recyclable waste by recycling and processing facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.
- G. Landfill and Incinerator Disposal Records: Indicate receipt and acceptance of waste by landfills and incinerator facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.
- H. Qualification Data: For waste management coordinator and refrigerant recovery technician.
- I. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician responsible for recovering refrigerant, stating that all refrigerant that was present was recovered and that recovery was performed according to EPA regulations. Include name and address of technician and date refrigerant was recovered.

1.7 WASTE MANAGEMENT PLAN

- A. General: Develop plan consisting of waste identification and waste reduction. Indicate quantities by weight or volume, but use same units of measure throughout waste management plan at start of construction.
- B. Waste Identification: Indicate anticipated types and quantities of demolition, site-clearing, and construction waste generated by the Work. Include estimated quantities and assumptions for estimates.
- C. Waste Reduction Work Plan: List each type of waste and whether it will be salvaged, recycled, or disposed of in landfill or incinerator. Include points of waste generation, total quantity of each type of waste, quantity for each means of recovery, and handling and transportation procedures.
 - 1. Recycled Materials: Include list of local receivers and processors and type of recycled materials each will accept. Include names, addresses, and telephone numbers.
 - 2. Disposed Materials: Indicate how and where materials will be disposed of. Include name, address, and telephone number of each landfill and incinerator facility.
 - 3. Handling and Transportation Procedures: Include method that will be used for
 - 4. separating recyclable waste including sizes of containers, container labeling, and designated location on Project site where materials separation will be located.
- D. Forms: Prepare waste management plan on format required by the current LEED® version.

1.8 PLAN IMPLEMENTATION

- A. General: Implement waste management plan as approved by Owner. Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during the entire duration of the Contract.
- B. Waste Management Coordinator: Engage a waste management coordinator to be responsible for implementing, monitoring, and reporting status of waste management work plan. Coordinator shall be present at Project site full time for duration of Project.
- C. Training: Train workers, subcontractors, and suppliers on proper waste management procedures, as appropriate for the Work occurring at Project site.
 - 1. Distribute waste management plan to everyone concerned within three days of submittal return.
 - 2. Distribute waste management plan to entities when they first begin work on-site. Review plan procedures and locations established for salvage, recycling, and disposal.
- D. Site Access and Temporary Controls: Conduct waste management operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 - 1. Designate and label specific areas on Project site necessary for separating materials that are to be salvaged, recycled, reused, donated, and sold.

1.9 QUALITY ASSURANCE

- A. Waste Management Conference(s): Conduct conference(s) at Project site to comply with requirements in Section 013100 "Project Management and Coordination." Review methods and procedures related to waste management including, but not limited to, the following:
 - 1. Review and discuss waste management including responsibilities of each contractor and waste management coordinator.
 - 2. Review and finalize procedures for materials separation and verify availability of containers and bins needed to avoid delays.
 - 3. Review procedures for periodic waste collection and transportation to recycling and disposal facilities.
 - 4. Review waste management requirements for each trade.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. General: Use all reasonable means to divert construction and demolition waste from landfills and incinerators. Facilitate recycling and salvage of materials including, but not limited to, the following:
 - 1. Construction Waste:
 - a. Masonry and CMU.
 - b. Lumber.
 - c. Wood sheet materials.
 - d. Metals.
 - e. Roofing.
 - f. Insulation.
 - g. Piping.
 - h. Electrical conduit.
 - i. Packaging: Regardless of salvage/recycle goal indicated in "General" Paragraph above, salvage or recycle 100 percent of the following uncontaminated packaging materials:
 - 1) Paper.

- 2) Cardboard.
 - 3) Boxes.
 - 4) Plastic sheet and film.
 - 5) Polystyrene packaging.
 - 6) Wood crates.
 - 7) Wood pallets.
 - 8) Plastic pails.
- j. Construction Office Waste: Regardless of salvage/recycle goal indicated in "General" Paragraph above, salvage or recycle 100 percent of the following construction office waste materials:
- 1) Paper.
 - 2) Aluminum cans.
 - 3) Glass containers.

PART 3 - EXECUTION

3.1 IMPLEMENTATION

- A. General: Implement waste management. Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during the entire duration of the Contract.
- B. Training: Train workers, subcontractors, and suppliers on proper waste management procedures, as appropriate for the Work.
- C. Site Access and Temporary Controls: Conduct waste management operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 1. Designate and label specific areas on Project site necessary for separating materials that are to be salvaged and recycled.

3.2 RECYCLING DEMOLITION AND CONSTRUCTION WASTE, GENERAL

- A. General: Recycle paper and beverage containers used by on-site workers.
- B. Recycling Incentives: Revenues, savings, rebates, tax credits, and other incentives received for recycling waste materials shall be shared equally by Owner and Contractor.
- C. Preparation of Waste: Prepare and maintain recyclable waste materials according to recycling or reuse facility requirements. Maintain materials free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process.
- D. Procedures: Separate recyclable waste from other waste materials, trash, and debris. Separate recyclable waste by type at Project site to the maximum extent practical according to approved construction waste management plan.
 1. Provide appropriately marked containers or bins for controlling recyclable waste until removed from Project site. Include list of acceptable and unacceptable materials at each container and bin.
 - a. Inspect containers and bins for contamination and remove contaminated materials if found.
 2. Stockpile processed materials on-site without intermixing with other materials. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
 3. Stockpile materials away from construction area. Do not store within drip line of remaining trees.
 4. Store components off the ground and protect from the weather.
 5. Remove recyclable waste from Owner's property and transport to recycling receiver or processor as often as required to prevent overfilling bins.

3.3 RECYCLING DEMOLITION WASTE

- A. Asphalt Paving: Break up and transport paving to asphalt-recycling facility.
- B. Concrete: Remove reinforcement and other metals from concrete and sort with other metals.
 - 1. Pulverize concrete to maximum 4-inch size.
 - 2. Crush concrete and screen to comply with requirements in Section 312000 "Earth Moving" for use as satisfactory soil for fill or subbase.

3.4 RECYCLING CONSTRUCTION WASTE

- A. Packaging:
 - 1. Cardboard and Boxes: Break down packaging into flat sheets. Bundle and store in a dry location.
 - 2. Polystyrene Packaging: Separate and bag materials.
 - 3. Pallets: As much as possible, require deliveries using pallets to remove pallets from Project site. For pallets that remain on-site, break down pallets into component wood pieces and comply with requirements for recycling wood.
 - 4. Crates: Break down crates into component wood pieces and comply with requirements for recycling wood.
- B. Wood Materials:
 - 1. Clean Cut-Offs of Lumber: Grind or chip into small pieces.
 - 2. Clean Sawdust: Bag sawdust that does not contain painted or treated wood.
 - a. Comply with requirements in Section 329300 "Plants" for use of clean sawdust as organic mulch.
- C. Gypsum Board: Stack large clean pieces on wood pallets or in container and store in a dry location.
 - 1. Clean Gypsum Board: Grind scraps of clean gypsum board using small mobile chipper or hammer mill. Screen out paper after grinding.
 - a. Comply with requirements in Section 329300 "Plants" for use of clean ground gypsum board as inorganic soil amendment.
- D. Paint: Seal containers and store by type.

3.5 DISPOSAL OF WASTE

- A. General: Except for items or materials to be salvaged or recycled, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.
 - 1. Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
 - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
- B. General: Except for items or materials to be salvaged or recycled, remove waste materials and legally dispose of at designated spoil areas on Owner's property.
- C. Burning: Do not burn waste materials.
- D. Disposal: Transport waste materials off Owner's property and legally dispose of them.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
FORM CWM-1

FORM CWM-1: CONSTRUCTION WASTE IDENTIFICATION							
MATERIAL CATEGORY	GENERATION POINT	EST. QUANTITY OF MATERIALS RECEIVED* (A)	EST. WASTE - % (B)	TOTAL EST. QUANTITY OF WASTE* (C = A x B)	EST. VOLUME CY (CM)	EST. WEIGHT TONS (TONNES)	REMARKS AND ASSUMPTIONS
Packaging: Cardboard							
Packaging: Boxes							
Packaging: Plastic Sheet or Film							
Packaging: Polystyrene							
Packaging: Pallets or Skids							
Packaging: Crates							
Packaging: Paint Cans							
Packaging: Plastic Pails							
Site-Clearing Waste							
Masonry or CMU							
Lumber: Cut-Offs							
Lumber: Warped Pieces							
Plywood or OSB (scraps)							
Wood Forms							
Wood Waste Chutes							
Wood Trim (cut-offs)							
Metals							
Insulation							
Roofing							
Joint Sealant Tubes							
Gypsum Board (scraps)							
Carpet and Pad (scraps)							
Piping							
Electrical Conduit							
Other:							

* Insert units of measure.

CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
FORM CWM-2

FORM CWM-2: DEMOLITION WASTE IDENTIFICATION				
MATERIAL DESCRIPTION	EST. QUANTITY	EST. VOLUME CY (CM)	EST. WEIGHT TONS (TONNES)	REMARKS AND ASSUMPTIONS
Asphaltic Concrete Paving				
Concrete				
Brick				
CMU				
Lumber				
Plywood and OSB				
Wood Paneling				
Wood Trim				
Miscellaneous Metals				
Structural Steel				
Rough Hardware				
Insulation				
Roofing				
Doors and Frames				
Door Hardware				
Windows				
Glazing				
Acoustical Tile				
Carpet				
Carpet Pad				
Demountable Partitions				
Equipment				
Cabinets				
Plumbing Fixtures				
Piping				
Piping Supports and Hangers				
Valves				
Sprinklers				
Mechanical Equipment				
Electrical Conduit				
Copper Wiring				
Light Fixtures				
Lamps				
Lighting Ballasts				
Electrical Devices				
Switchgear and Panelboards				
Transformers				
Other:				

CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
FORM CWM-3

FORM CWM-3: CONSTRUCTION WASTE REDUCTION WORK PLAN						
MATERIAL CATEGORY	GENERATION POINT	TOTAL EST. QUANTITY OF WASTE TONS (TONNES)	DISPOSAL METHOD AND QUANTITY			HANDLING AND TRANSPORTION PROCEDURES
			EST. AMOUNT SALVAGED TONS (TONNES)	EST. AMOUNT RECYCLED TONS (TONNES)	EST. AMOUNT DISPOSED TO LANDFILL TONS (TONNES)	
Packaging: Cardboard						
Packaging: Boxes						
Packaging: Plastic Sheet or Film						
Packaging: Polystyrene						
Packaging: Pallets or Skids						
Packaging: Crates						
Packaging: Paint Cans						
Packaging: Plastic Pails						
Site-Clearing Waste						
Masonry or CMU						
Lumber: Cut-Offs						
Lumber: Warped Pieces						
Plywood or OSB (scraps)						
Wood Forms						
Wood Waste Chutes						
Wood Trim (cut-offs)						
Metals						
Insulation						
Roofing						
Joint Sealant Tubes						
Gypsum Board (scraps)						
Carpet and Pad (scraps)						
Piping						
Electrical Conduit						
Other:						

CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
FORM CWM-4

FORM CWM-4: DEMOLITION WASTE REDUCTION WORK PLAN						
MATERIAL CATEGORY	GENERATION POINT	TOTAL EST. QUANTITY OF WASTE TONS (TONNES)	DISPOSAL METHOD AND QUANTITY			HANDLING AND TRANSPORTION PROCEDURES
			EST. AMOUNT SALVAGED TONS (TONNES)	EST. AMOUNT RECYCLED TONS (TONNES)	EST. AMOUNT DISPOSED TO LANDFILL TONS (TONNES)	
Asphaltic Concrete Paving						
Concrete						
Brick						
CMU						
Lumber						
Plywood and OSB						
Wood Paneling						
Wood Trim						
Miscellaneous Metals						
Structural Steel						
Rough Hardware						
Insulation						
Roofing						
Doors and Frames						
Door Hardware						
Windows						
Glazing						
Acoustical Tile						
Carpet						
Carpet Pad						
Demountable Partitions						
Equipment						
Cabinets						
Plumbing Fixtures						
Piping						
Supports and Hangers						
Valves						
Sprinklers						
Mechanical Equipment						
Electrical Conduit						
Copper Wiring						
Light Fixtures						
Lamps						
Lighting Ballasts						
Electrical Devices						
Switchgear and Panelboards						
Transformers						
Other:						

SECTION 01 77 00 CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Inspection procedures.
 - 2. Project Record Documents.
 - 3. Operation and maintenance manuals including digital submittal.
 - 4. Substantial Completion procedures.
 - 5. Final completion procedures.
 - 6. Warranties.
 - 7. Final cleaning.
 - 8. Repair of the Work.
- B. Related Requirements:
 - 1. Section 017300 "Execution" for progress cleaning of project site.
 - 2. Section 017839 "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.
 - 3. Section 017900 "Demonstration and Training" for requirements to train the Owner's maintenance personnel to adjust, operate, and maintain products, equipment, and systems.
 - 4. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 5. Section 019113 "General Commissioning Requirements".
 - 6. Divisions 02 through 49 sections for specific closeout and special cleaning requirements for the work in these sections.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of cleaning agent.
- B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- C. Certified List of Incomplete Items: Final submittal at final completion.

1.4 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.
- C. Field Report: For pest control inspection.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Schedule of Maintenance Material Items: For maintenance material submittal items specified in other Sections.

1.6 SUBSTANTIAL COMPLETION PROCEDURES

- A. Preliminary Procedures: Before requesting inspection for determining date of Substantial Completion, complete the following. List items below that are incomplete in request. Coordinate with all requirements listed in the High Performance Building Standard for Commissioning and verification.
1. Prepare a list of items to be completed and corrected (punch list), the value of items on the list, and reasons why the Work is not complete.
 2. Advise Owner of pending insurance changeover requirements.
 3. Submit specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 4. Obtain and submit releases permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
 5. Prepare and submit Project Record Documents, operation and maintenance manuals, and similar final record information.
 6. Deliver tools, spare parts, extra materials, and similar items to location designated by Owner. Label with manufacturer's name and model number where applicable.
 7. Complete startup testing of systems.
 8. Submit test records.
 9. Terminate and remove temporary facilities from Project site, along with construction tools, and similar elements.
 10. Complete final cleaning requirements, including touchup painting.
 11. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects
- B. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.
- C. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
 2. Submit closeout submittals specified in other Division 01 Sections, including project record documents, operation and maintenance manuals, damage or settlement surveys, property surveys, and similar final record information.
 3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 4. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Architect. Label with manufacturer's name and model number.
 - a. Schedule of Maintenance Material Items: Prepare and submit schedule of maintenance material submittal items, including name and quantity of each item and name and number of related Specification Section. Obtain Architect's signature for receipt of submittals.
 5. Submit testing, adjusting, and balancing records.
 6. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
- D. Procedures Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.

1. Advise Owner of pending insurance changeover requirements.
 2. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
 3. Complete startup and testing of systems and equipment.
 4. Perform preventive maintenance on equipment used prior to Substantial Completion.
 5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems. Submit demonstration and training video recordings specified in Section 017900 "Demonstration and Training."
 6. Advise Owner of changeover in utility services; if any.
 7. Participate with Owner in conducting inspection and walkthrough with local emergency responders.
 8. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
 9. Complete final cleaning requirements.
 10. Touch up paint and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- E. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 7 days prior to date the Work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.
1. Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
 2. Results of completed inspection will form the basis of requirements for final completion.

1.7 FINAL COMPLETION PROCEDURES

- A. Preliminary Procedures: Before requesting final inspection for determining date of Final Completion, complete the following:
1. Submit a final Application for Payment according to Division 1 Section "Payment Procedures."
 2. Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. The certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
 3. Submit evidence of final, continuing insurance coverage complying with insurance requirements.
 4. Instruct Owner's personnel in operation, adjustment, and maintenance of, equipment, and systems.
- B. Submittals Prior to Final Completion: Before requesting final inspection for determining final completion, complete the following:
1. Submit a final Application for Payment according to Section 012900 "Payment Procedures."
 2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
 3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
- C. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 10 days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or

notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

1. Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.8 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Preparation: Submit digital copies of list. Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
- B. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
 1. Organize list of spaces in sequential order.
 2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
 3. Include the following information at the top of each page:
 - a. Project name.
 - b. Date.
 - c. Name of Architect.
 - d. Name of Contractor.
 - e. Page number.
 4. Submit list of incomplete items in the following format:
 - a. PDF electronic file. Architect will return annotated file.

1.9 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where warranties are indicated to commence on dates other than date of Substantial Completion, or when delay in submittal of warranties might limit Owner's rights under warranty.
- B. Partial Occupancy: Submit properly executed warranties within 15 days of completion of designated portions of the Work that are completed and occupied or used by Owner during construction period by separate agreement with Contractor.
- C. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.
- D. Warranty Electronic File: Provide warranties and bonds in PDF format. Assemble complete warranty and bond submittal package into a single electronic PDF file with bookmarks enabling navigation to each item. Provide bookmarked table of contents at beginning of document.
 1. Submit on digital media acceptable to Architect.
- E. Warranties in Paper Form:
 1. Provide one (1) set and bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
 3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
- F. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.
 - 1. Use cleaning products that comply with Green Seal's GS-37, or if GS-37 is not applicable, use products that comply with the California Code of Regulations maximum allowable VOC levels.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
 - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
 - c. Remove tools, construction equipment, machinery, and surplus material from Project site.
 - d. Remove snow and ice to provide safe access to building.
 - e. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
 - f. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
 - g. Sweep concrete floors broom clean in unoccupied spaces.
 - h. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean according to manufacturer's recommendations if visible soil or stains remain.
 - i. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.
 - j. Remove labels that are not permanent.
 - k. Wipe surfaces of mechanical and electrical equipment and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
 - l. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
 - m. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.

- n. Clean ducts, blowers, and coils if units were operated without filters during construction or that display contamination with particulate matter on inspection.
 - 1) Clean HVAC system in compliance with NADCA ACR. Provide written report on completion of cleaning.
 - o. Clean luminaires, lamps, globes, and reflectors to function with full efficiency.
 - p. Leave Project clean and ready for occupancy.
- C. Construction Waste Disposal: Comply with waste disposal requirements in Section 015000 "Temporary Facilities and Controls" AND Section 017419 "Construction Waste Management and Disposal".

3.2 REPAIR OF THE WORK

- A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Repair, or remove and replace, defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.
 - 1. Remove and replace chipped, scratched, and broken glass, reflective surfaces, and other damaged transparent materials.
 - 2. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that already show evidence of repair or restoration.
 - a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.
 - 3. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.
 - 4. Replace burned-out bulbs, bulbs noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.

END OF SECTION

SECTION 01 78 23

OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
 - 1. Operation and maintenance manuals.
- B. Related Requirements:
 - 1. Section 013300 "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.
 - 2. Section 019113 "General Commissioning Requirements".

1.3 DEFINITIONS

- A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.
- B. Subsystem: A portion of a system with characteristics similar to a system.

1.4 CLOSEOUT SUBMITTALS

- A. Submit operation and maintenance manuals. Provide content for each manual as specified in individual Specification Sections, and as reviewed and approved at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.
 - 1. Architect will comment on whether content of operation and maintenance submittals is acceptable.
 - 2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.
- B. Format: Submit operation and maintenance manuals in the following format:
 - 1. Submit on digital media acceptable to Architect. Enable reviewer comments on draft submittals.
- C. Initial Manual Submittal: Submit draft copy of each manual at least 30 days before commencing demonstration and training. Architect and Commissioning authority will comment on whether general scope and content of manual are acceptable.
- D. Final Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Architect and Commissioning Authority will return copy with comments.
 - 1. Correct or revise each manual to comply with Architect's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's and Commissioning Authority comments and prior to commencing demonstration and training.
- E. Comply with Section 017700 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

- F. Comply with Section 019113 "General Commissioning Requirements" for submitting required documentation.

1.5 FORMAT OF OPERATION AND MAINTENANCE MANUALS

- A. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic PDF file for each manual type required.
 - 1. Electronic Files: Use electronic files prepared by manufacturer where available. Where scanning of paper documents is required, configure scanned file for minimum readable file size.
 - 2. File Names and Bookmarks: Bookmark individual documents based on file names. Name document files to correspond to system, subsystem, and equipment names used in manual directory and table of contents. Group documents for each system and subsystem into individual composite bookmarked files, then create composite manual, so that resulting bookmarks reflect the system, subsystem, and equipment names in a readily navigated file tree. Configure electronic manual to display bookmark panel on opening file.

1.6 REQUIREMENTS FOR OPERATION AND MAINTENANCE MANUALS

- A. Organization of Manuals: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:
 - 1. Title page.
 - 2. Table of contents.
 - 3. Manual contents.
- B. Title Page: Include the following information:
 - 1. Subject matter included in manual.
 - 2. Name and address of Project.
 - 3. Name and address of Owner.
 - 4. Date of submittal.
 - 5. Name and contact information for Contractor.
 - 6. Name and contact information for Architect.
 - 7. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
 - 8. Cross-reference to related systems in other operation and maintenance manuals.
- C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.
 - 1. If operation or maintenance documentation requires more than one volume to accommodate data, include comprehensive table of contents for all volumes in each volume of the set.
- D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.
- E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation according to ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

1.7 SYSTEMS AND EQUIPMENT OPERATION MANUALS

- A. Systems and Equipment Operation Manual: Assemble a complete set of data indicating operation of each system, subsystem, and piece of equipment not part of a system.

Include information required for daily operation and management, operating standards, and routine and special operating procedures.

1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
- B. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:
1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.
 2. Performance and design criteria if Contractor has delegated design responsibility.
 3. Operating standards.
 4. Operating procedures.
 5. Operating logs.
 6. Wiring diagrams.
 7. Control diagrams.
 8. Piped system diagrams.
 9. Precautions against improper use.
 10. License requirements including inspection and renewal dates.
- C. Descriptions: Include the following:
1. Product name and model number. Use designations for products indicated on Contract Documents.
 2. Manufacturer's name.
 3. Equipment identification with serial number of each component.
 4. Equipment function.
 5. Operating characteristics.
 6. Limiting conditions.
 7. Performance curves.
 8. Engineering data and tests.
 9. Complete nomenclature and number of replacement parts.
- D. Operating Procedures: Include the following, as applicable:
1. Startup procedures.
 2. Equipment or system break-in procedures.
 3. Routine and normal operating instructions.
 4. Regulation and control procedures.
 5. Instructions on stopping.
 6. Normal shutdown instructions.
 7. Seasonal and weekend operating instructions.
 8. Required sequences for electric or electronic systems.
 9. Special operating instructions and procedures.

1.8 PRODUCT MAINTENANCE MANUALS

- A. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.
- B. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
- C. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.
- D. Product Information: Include the following, as applicable:
 1. Product name and model number.
 2. Manufacturer's name.

3. Color, pattern, and texture.
 4. Material and chemical composition.
 5. Reordering information for specially manufactured products.
- E. Maintenance Procedures: Include manufacturer's written recommendations and the following:
1. Inspection procedures.
 2. Types of cleaning agents to be used and methods of cleaning.
 3. List of cleaning agents and methods of cleaning detrimental to product.
 4. Schedule for routine cleaning and maintenance.
 5. Repair instructions.
- F. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.
- G. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
1. Include procedures to follow and required notifications for warranty claims.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 01 78 39
PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for project record documents, including the following:
1. Record Drawings.
 2. Record Specifications.
 3. Record Product Data.
 4. Miscellaneous record submittals.
- B. Related Requirements:
1. Section 017700 "Closeout Procedures" for general closeout procedures.
 2. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.
 3. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 4. Section 019113 "General Commissioning Requirements".
 5. Division 02 through 49 Sections for specific requirements for project record documents of the work in those sections.

1.3 CLOSEOUT SUBMITTALS

- A. Record Drawings:
1. Maintain and submit one set of blue- or black-line white prints of Contract Drawings and Shop Drawings. (Include CD with PDF files of each sheet and BIM drawings with each drawing digitally "bound" so all pertinent information displays when file is opened and each file drawn to meet the current version of the National BIM Standard.)
 - a. Mark Record Prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to prepare the marked-up Record Prints.
 - 1) Give particular attention to information on concealed elements that cannot be readily identified and recorded later.
 - 2) Accurately record information in an understandable drawing technique.
 - 3) Record data as soon as possible after obtaining it. Record and check the markup before enclosing concealed installations.
 - 4) Mark Contract Drawings or Shop Drawings, whichever is most capable of showing actual physical conditions, completely and accurately. Where Shop Drawings are marked, show cross-reference on Contract Drawings.

2. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at the same location.
 3. Mark important additional information that was either shown schematically or omitted from original Drawings.
 4. Note Construction Change Directive numbers, Change Order numbers, alternate numbers, and similar identification where applicable.
 5. Identify and date each Record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location. Organize into manageable sets;
 6. bind each set with durable paper cover sheets. Include identification on cover sheets.
- B. Record Specifications:
1. Record Specifications: Submit one copy of Project's Specifications, including addenda and contract modifications. Mark copy to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
 - a. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 - b. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
 - c. Note related Change Orders, Record Drawings and Product Data, where applicable.
 2. Record Product Data: Submit one copy of each Product Data submittal. Mark one set to indicate the actual product installation where installation varies substantially from that indicated in Product Data.
 - a. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 - b. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
 - c. Note related Change Orders, Record Drawings, and Record Specifications, where applicable.
 3. Miscellaneous Record Submittals: Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.
- C. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Submit annotated PDF electronic files and directories of each submittal.
- D. Reports: Submit written report weekly indicating items incorporated into project record documents concurrent with progress of the Work, including revisions, concealed conditions, field changes, product selections, and other notations incorporated.

1.4 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.
1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
 - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.

- b. Accurately record information in an acceptable drawing technique.
- c. Record data as soon as possible after obtaining it.
- d. Record and check the markup before enclosing concealed installations.
- 2. Content: Types of items requiring marking include, but are not limited to, the following:
 - a. Dimensional changes to Drawings.
 - b. Revisions to details shown on Drawings.
 - c. Locations and depths of underground utilities.
 - d. Revisions to routing of piping and conduits.
 - e. Revisions to electrical circuitry.
 - f. Actual equipment locations.
 - g. Duct size and routing.
 - h. Locations of concealed internal utilities.
 - i. Changes made by Change Order or Construction Change Directive.
 - j. Changes made following Architect's written orders.
 - k. Details not on the original Contract Drawings.
 - l. Field records for variable and concealed conditions.
- 3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
- 4. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
- 5. Mark important additional information that was either shown schematically or omitted from original Drawings.
- 6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.
- B. Record Digital Data Files: Immediately before inspection for Certificate of Substantial Completion, review marked-up record prints with Architect. When authorized, prepare a full set of corrected digital data files of the Contract Drawings, as follows:
 - 1. Format: Annotated PDF electronic file.
 - 2. Incorporate changes and additional information previously marked on record prints. Delete, redraw, and add details and notations where applicable.
 - 3. resolution.
 - 4. Architect will furnish Contractor with one set of digital data files of the Contract Drawings for use in recording information.
 - a. See Section 013100 "Project Management and Coordination" for requirements related to use of Architect's digital data files.
 - b. Architect will provide data file layer information. Record markups in separate layers.

1.5 RECORD SPECIFICATIONS

- A. Preparation: Mark Specifications to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
 - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 - 2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
 - 3. Record the name of manufacturer, supplier, Installer, and other information necessary to provide a record of selections made.
 - 4. For each principal product, indicate whether record Product Data has been submitted in operation and maintenance manuals instead of submitted as record Product Data.

5. Note related Change Orders, record Product Data, and record Drawings where applicable.
- B. Format: Submit record Specifications as annotated PDF electronic file.

1.6 RECORD PRODUCT DATA

- A. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.
- B. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.
- C. Format: Submit record Product Data as annotated PDF electronic file.
 1. Include record Product Data directory organized by Specification Section number and title, electronically linked to each item of record Product Data.

1.7 MISCELLANEOUS RECORD SUBMITTALS

- A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.
- B. Format: Submit miscellaneous record submittals as PDF electronic file.
 1. Include miscellaneous record submittals directory organized by Specification Section number and title, electronically linked to each item of miscellaneous record submittals.

1.8 MAINTENANCE OF RECORD DOCUMENTS

- A. Maintenance of Record Documents: Store record documents in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Architect's reference during normal working hours.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 01 79 00
DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:
 - 1. Demonstration of operation of systems, subsystems, and equipment.
 - 2. Training in operation and maintenance of systems, subsystems, and equipment.
- B. Related Sections:
 - 1. Divisions 02 through 49 Sections for specific requirements for demonstration and training for products in those Sections.

1.3 INFORMATIONAL SUBMITTALS

- A. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module.
- B. Attendance Record: For each training module, submit list of participants and length of instruction time.

1.4 CLOSEOUT SUBMITTALS

- A. Demonstration and Training Instructional Manuals and Materials: Submit two copies within seven days of end of each training module.
 - 1. Identification: On each copy, provide an applied label with the following information:
 - a. Name of Project.
 - b. Name of Architect.
 - c. Name of General Contractor.
 - 2. Prepared on 8-1/2-by-11-inch paper, punched and bound in heavy-duty, three-ring, vinyl-covered binders. Mark appropriate identification on front and spine of each binder. Include a cover sheet with same label information as the corresponding video recording. Include name of Project and date training sessions.
 - 3. At completion of training, submit complete training manual(s) for Owner's use.

1.5 QUALITY ASSURANCE

- A. Facilitator Qualifications: A firm or individual experienced in training or educating maintenance personnel in a training program similar in content and extent to that indicated for this Project, and whose work has resulted in training or education with a record of successful learning performance.
- B. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Division 01 Section "Quality Requirements," experienced in operation and maintenance procedures and training.

1.6 COORDINATION

- A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations.
- B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.
- C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data has been reviewed and approved by Architect.

PART 2 - PRODUCTS

2.1 INSTRUCTION PROGRAM

- A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.
- B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:
 - 1. Basis of System Design, Operational Requirements, and Criteria: Include the following:
 - a. System, subsystem, and equipment descriptions.
 - b. Performance and design criteria if Contractor is delegated design responsibility.
 - c. Operating standards.
 - d. Regulatory requirements.
 - e. Equipment function.
 - f. Operating characteristics.
 - g. Limiting conditions.
 - h. Performance curves.
 - 2. Documentation: Review the following items in detail:
 - a. Emergency manuals.
 - b. Operations manuals.
 - c. Maintenance manuals.
 - d. Project record documents.
 - e. Identification systems.
 - f. Warranties and bonds.
 - g. Maintenance service agreements and similar continuing commitments.
 - 3. Emergencies: Include the following, as applicable:
 - a. Instructions on meaning of warnings, trouble indications, and error messages.
 - b. Instructions on stopping.
 - c. Shutdown instructions for each type of emergency.
 - d. Operating instructions for conditions outside of normal operating limits.
 - e. Sequences for electric or electronic systems.
 - f. Special operating instructions and procedures.
 - 4. Operations: Include the following, as applicable:
 - a. Startup procedures.
 - b. Equipment or system break-in procedures.
 - c. Routine and normal operating instructions.
 - d. Regulation and control procedures.
 - e. Control sequences.
 - f. Safety procedures.

- g. Instructions on stopping.
 - h. Normal shutdown instructions.
 - i. Operating procedures for emergencies.
 - j. Operating procedures for system, subsystem, or equipment failure.
 - k. Seasonal and weekend operating instructions.
 - l. Required sequences for electric or electronic systems.
 - m. Special operating instructions and procedures.
- 5. Adjustments: Include the following:
 - a. Alignments.
 - b. Checking adjustments.
 - c. Noise and vibration adjustments.
 - d. Economy and efficiency adjustments.
 - 6. Troubleshooting: Include the following:
 - a. Diagnostic instructions.
 - b. Test and inspection procedures.
 - 7. Maintenance: Include the following:
 - a. Inspection procedures.
 - b. Types of cleaning agents to be used and methods of cleaning.
 - c. List of cleaning agents and methods of cleaning detrimental to product.
 - d. Procedures for routine cleaning
 - e. Procedures for preventive maintenance.
 - f. Procedures for routine maintenance.
 - g. Instruction on use of special tools.
 - 8. Repairs: Include the following:
 - a. Diagnosis instructions.
 - b. Repair instructions.
 - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - d. Instructions for identifying parts and components.
 - e. Review of spare parts needed for operation and maintenance.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Division 01 Section "Operations and Maintenance Data."
- B. Set up instructional equipment at instruction location.

3.2 INSTRUCTION

- A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location.
- B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
 - 1. Architect will furnish an instructor to describe basis of system design, operational requirements, criteria, and regulatory requirements.
 - 2. Owner will furnish Contractor with names and positions of required training participants.
- C. Scheduling: Provide instruction at mutually agreed on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.
 - 1. Schedule training with Owner, with at least seven days' advance notice.

- D. Evaluation: At conclusion of each training module, assess and document each participant's mastery of module by use of a demonstration performance-based test.
- E. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

END OF SECTION

SECTION 02 41 19

SELECTIVE DEMOLITION AND REPAIR

PART 1 GENERAL

1.1 SUMMARY

- A. This Section includes:
 - 1. Complete demolition and removal of existing facility including footings and associated paving not indicated to remain. Remove utilities and cap outside the extents of the new construction. Identify location of capped utilities. Protect all existing features indicated to remain.
 - 2. Protect existing paving indicated to remain.
 - 3. Protect existing turf and irrigation systems indicated to remain and retain irrigation operation from April through October.
 - 4. It is the responsibility of the contractor to define the limits of demolition necessary and repair / patch to provide final construction required.
 - 5. Coordinate work to remain with Architect and Owner's representative.
 - 6. Investigate existing conditions to determine best routing for power and sanitary sewer lines.

1.2 DEFINITIONS

- A. Remove and Salvage: Detach items from existing construction and roll/palletize items to be returned to owner. Deliver items to owner.
- B. Remove: Detach items from existing construction and legally dispose of them off-site unless indicated to be removed and salvaged or removed and reinstalled.
- C. Remove and Reinstall: Detach items from existing construction, prepare for reuse, and reinstall where indicated.
- D. Existing to Remain: Existing items of construction that are not to be permanently removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.3 PRE-INSTALLATION MEETINGS

- A. Pre-demolition Conference: Conduct conference at Project site.

1.4 SUBMITTALS

- A. Pre-demolition photographs

1.5 FIELD CONDITIONS

- A. Owner will occupy portions of site immediately adjacent to selective demolition area for ongoing operations. Conduct selective demolition so Owner's use of adjacent site will not be disrupted.

- B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
- C. Notify Owner of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- D. Hazardous Materials: refer to "Asbestos Survey Report"
- E. Storage or sale of removed items or materials on-site is not permitted.
- F. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
 - 1. Maintain irrigation services from April through October.

PART 2 PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Contractor is responsible for obtaining approvals from applicable agencies for demolition and for service termination or temporary disconnect (e.g. SLCO Health Department, State of Utah Div. of Environmental Quality, Rocky Mountain Power, sewer district, water district).
- B. Regulatory Requirements: Comply with hauling and disposal regulations of authorities having jurisdiction.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped before starting selective demolition operations.
- B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- C. If unanticipated electrical, mechanical, fire sprinkler or structural elements conflict with intended design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Owner.
- D. Survey of Existing Conditions: Record existing conditions by use of preconstruction photographs.

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage. These systems may be modified as part of the work.
 - 1. Plumbing Systems
 - 2. Electrical Service and conduit.
 - 3. Irrigation Systems

3.3 PREPARATION

- A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with occupied adjacent areas of the ballfields, adjacent parking and other adjacent facilities.

3.4 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by closely examining all existing conditions. Use methods required to complete the Work within limitations of governing regulations and as follows:
 - 1. Neatly cut elements plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools minimize disturbance of adjacent surfaces.
 - 2. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 - 3. Do not use cutting torches.
 - 4. Dispose of demolished items and materials promptly.
- B. Removed and Reinstalled Items:
 - 1. Clean and repair items to functional condition adequate for intended reuse.
 - 2. Protect items from damage during transport and storage.
- C. Existing Items to Remain: Protect existing construction indicated to remain against damage and soiling during selective demolition. Temporarily support as necessary. Reconstruct permanent supports that are altered to comply with all code requirements.

3.5 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Except for items or materials indicated to be reused, salvaged or reinstalled, remove demolished materials from Project site and legally dispose of them in an EPA-approved landfill or recycling facility.
 - 1. Do not allow demolished materials to accumulate on-site.
 - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
- B. Burning: Do not burn demolished materials.

3.6 CLEANING

- A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION

SECTION 03 30 00
CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Cast-in-place concrete, including concrete materials, mixture design, placement procedures, and finishes.
- B. Related Requirements:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 2. Section 312000 "Earth Moving" for drainage fill under slabs-on-ground.
 - 3. Section 321313 "Concrete Paving" for concrete pavement and walks.

1.3 DEFINITIONS

- A. Cementitious Materials: Portland cement alone or in combination with one or more of the following: blended hydraulic cement, fly ash, slag cement, other pozzolans, and silica fume; materials subject to compliance with requirements.
- B. Water/Cement Ratio (w/cm): The ratio by weight of water to cementitious materials.

1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
 - 1. Require representatives of each entity directly concerned with cast-in-place concrete to attend, including the following:
 - a. Contractor's superintendent.
 - b. Independent testing agency responsible for concrete design mixtures.
 - c. Ready-mix concrete manufacturer.
 - d. Concrete Subcontractor.
 - 2. Review the following:
 - a. Special inspection and testing and inspecting agency procedures for field quality control.
 - b. Construction joints, control joints, isolation joints, and joint-filler strips.
 - c. Semirigid joint fillers.
 - d. Vapor-retarder installation.
 - e. Anchor rod and anchorage device installation tolerances.
 - f. Cold and hot weather concreting procedures.
 - g. Concrete finishes and finishing.
 - h. Curing procedures.
 - i. Forms and form-removal limitations.
 - j. Shoring and reshoring procedures.
 - k. Methods for achieving specified floor and slab flatness and levelness.
 - l. Floor and slab flatness and levelness measurements.
 - m. Concrete repair procedures.
 - n. Concrete protection.
 - o. Initial curing and field curing of field test cylinders (ASTM C31/C31M.)

- p. Protection of field cured field test cylinders.

1.5 ACTION SUBMITTALS

- A. Product Data: For each of the following.
 - 1. Portland cement.
 - 2. Fly ash.
 - 3. Aggregates.
 - 4. Admixtures:
 - a. Include limitations of use, including restrictions on cementitious materials, supplementary cementitious materials, air entrainment, aggregates, temperature at time of concrete placement, relative humidity at time of concrete placement, curing conditions, and use of other admixtures.
 - 5. Fiber reinforcement.
 - 6. Floor and slab treatments.
 - 7. Liquid floor treatments.
 - 8. Curing materials.
 - 9. Joint fillers.
 - 10. Repair materials.
- B. High Performance Submittals
 - 1. Product Data: For products having recycled content, documentation indicating percentages by weight of postconsumer and preconsumer recycled content. Include statement indicating costs for each product having recycled content.
 - 2. Design Mixtures: For each concrete mixture containing fly ash as a replacement for portland cement or other portland cement replacements and for equivalent concrete mixtures that do not contain portland cement replacements.
 - 3. Product Certificates: for products and materials required to comply with requirements for regional materials indicating location and distance from Project of material manufacturer and point of extraction, harvest, or recovery for each raw material. Include statement indicating cost for each regional material and the fraction by weight that is considered regional.
- C. Design Mixtures: For each concrete mixture, include the following:
 - 1. Mixture identification.
 - 2. Minimum 28-day compressive strength.
 - 3. Durability exposure class.
 - 4. Maximum w/cm.
 - 5. Calculated equilibrium unit weight, for lightweight concrete.
 - 6. Slump limit.
 - 7. Air content.
 - 8. Nominal maximum aggregate size.
 - 9. Steel-fiber reinforcement content.
 - 10. Synthetic micro-fiber content.
 - 11. Indicate amounts of mixing water to be withheld for later addition at Project site if permitted.
 - 12. Include manufacturer's certification that permeability-reducing admixture is compatible with mix design.
 - 13. Include certification that dosage rate for permeability-reducing admixture matches dosage rate used in performance compliance test.
 - 14. Intended placement method.
 - 15. Submit alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.

- D. Shop Drawings:
 - 1. Construction Joint Layout: Indicate proposed construction joints required to construct the structure.
 - a. Location of construction joints is subject to approval of the Architect.
- E. Samples: For vapor retarder.
- F. Concrete Schedule: For each location of each Class of concrete indicated in "Concrete Mixtures" Article, including the following:
 - 1. Concrete Class designation.
 - 2. Location within Project.
 - 3. Exposure Class designation.
 - 4. Formed Surface Finish designation and final finish.
 - 5. Final finish for floors.
 - 6. Curing process.
 - 7. Floor treatment if any.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For the following:
 - 1. Installer: Include copies of applicable ACI certificates.
 - 2. Ready-mixed concrete manufacturer.
 - 3. Testing agency: Include copies of applicable ACI certificates.
- B. Material Certificates: For each of the following, signed by manufacturers:
 - 1. Cementitious materials.
 - 2. Admixtures.
 - 3. Fiber reinforcement.
 - 4. Curing compounds.
 - 5. Floor and slab treatments.
 - 6. Bonding agents.
 - 7. Adhesives.
 - 8. Vapor retarders.
 - 9. Semirigid joint filler.
 - 10. Joint-filler strips.
 - 11. Repair materials.
- C. Material Test Reports: For the following, from a qualified testing agency:
 - 1. Portland cement.
 - 2. Fly ash.
 - 3. Aggregates.
 - 4. Admixtures:
 - a. Permeability-Reducing Admixture: Include independent test reports, indicating compliance with specified requirements, including dosage rate used in test.
- D. Floor surface flatness and levelness measurements report, indicating compliance with specified tolerances.
- E. Research Reports:
 - 1. For concrete admixtures in accordance with ICC's Acceptance Criteria AC198.
 - 2. For sheet vapor retarder/termite barrier, showing compliance with ICC AC380.
- F. Preconstruction Test Reports: For each mix design.
- G. Field quality-control reports.
- H. Minutes of preinstallation conference.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs on Project personnel qualified as ACI-certified Flatwork Technician and Finisher and a supervisor who is an ACI-certified Concrete Flatwork Technician.

- B. Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C 94/C 94M requirements for production facilities and equipment.
 - 1. Manufacturer certified according to NRMCA's "Certification of Ready Mixed Concrete Production Facilities."
- C. Testing Agency Qualifications: An independent agency, acceptable to authorities having jurisdiction, qualified according to ASTM C 1077 and ASTM E 329 for testing indicated.
 - 1. Personnel conducting field tests shall be qualified as ACI Concrete Field Testing Technician, Grade 1, according to ACI CP-1 or an equivalent certification program.
 - 2. Personnel performing laboratory tests shall be ACI-certified Concrete Strength Testing Technician and Concrete Laboratory Testing Technician, Grade I. Testing agency laboratory supervisor shall be an ACI-certified Concrete Laboratory Testing Technician, Grade II.
- D. Welding Qualifications: Qualify procedures and personnel according to AWS D1.4/D 1.4M.

1.8 PRECONSTRUCTION TESTING

- A. Preconstruction Testing Service: Engage a qualified testing agency to perform preconstruction testing on each concrete mixture.
 - 1. Include the following information in each test report:
 - a. Admixture dosage rates.
 - b. Slump.
 - c. Air content.
 - d. Seven-day compressive strength.
 - e. 28-day compressive strength.
 - f. Permeability.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Comply with ASTM C94/C94M and ACI 301.
- B. Waterstops: Store waterstops under cover to protect from moisture, sunlight, dirt, oil, and other contaminants.

1.10 FIELD CONDITIONS

- A. Cold-Weather Placement: Comply with ACI 301 and ACI 306.1 and as follows.
 - 1. Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.
 - 2. When average high and low temperature is expected to fall below 40 deg F for three successive days, maintain delivered concrete mixture temperature within the temperature range required by ACI 301.
 - 3. Do not use frozen materials or materials containing ice or snow.
 - 4. Do not place concrete in contact with surfaces less than 35 deg F, other than reinforcing steel.
 - 5. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators unless otherwise specified and approved in mixture designs.
- B. Hot-Weather Placement: Comply with ACI 301 and ACI 305.1, and as follows:
 - 1. Maintain concrete temperature at time of discharge to not exceed 95 deg F.
 - 2. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade uniformly moist without standing water, soft spots, or dry areas.

1.11 WARRANTY

- A. Manufacturer's Warranty: Manufacturer agrees to furnish replacement sheet vapor retarder/termite barrier material and accessories for sheet vapor retarder/ termite barrier and accessories that do not comply with requirements or that fail to resist penetration by termites within specified warranty period.
 - 1. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 FORM-FACING MATERIALS

- A. Smooth-Formed Finished Concrete: Form-facing panels that will provide continuous, true, and smooth concrete surfaces. Furnish in largest practicable sizes to minimize number of joints.
 - 1. Exterior-grade plywood panels, suitable for concrete forms, complying with DOC PS 1, select from the following:
 - a. High-density overlay, Class 1 or better.
 - b. Medium-density overlay, Class 1 or better; mill-release agent treated and edge sealed.
 - c. Structural 1, B-B or better; mill oiled and edge sealed.
 - d. B-B (Concrete Form), Class 1 or better; mill oiled and edge sealed.
 - e. Multi-use formwork with quick release surface.
 - f. Douglas fir construction plywood with phenolic film face.
- B. Chamfer Strips: Wood, metal, PVC, or rubber strips, 3/4 by 3/4 inch, minimum.
- C. Form-Release Agent: Commercially formulated form-release agent that does not bond with, stain, or adversely affect concrete surfaces and does not impair subsequent treatments of concrete surfaces.
 - 1. Formulate form-release agent with rust inhibitor for steel form-facing materials.
- D. Form Ties: Factory-fabricated, removable or snap-off metal or glass-fiber-reinforced plastic form ties designed to resist lateral pressure of fresh concrete on forms and to prevent spalling of concrete on removal.
 - 1. Furnish units that will leave no corrodible metal closer than 1 inch to the plane of exposed concrete surface.
 - 2. Furnish ties that, when removed, will leave holes no larger than 1 inch in diameter in concrete surface.
 - 3. Furnish ties with integral water-barrier plates to walls indicated to receive dampproofing or waterproofing.

2.2 STEEL REINFORCEMENT

- A. Reinforcing Bars: ASTM A 615/A 615M, Grade 60, deformed.
- B. Low-Alloy-Steel Reinforcing Bars: ASTM A 706/A 706M, deformed.
- C. Plain-Steel Welded Wire Reinforcement: ASTM A 185/A 185M, plain, fabricated from as-drawn steel wire into flat sheets.

2.3 REINFORCEMENT ACCESSORIES

- A. Bar Supports: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars and welded wire reinforcement in place. Manufacture bar supports from steel wire, plastic, or precast concrete according to CRSI's "Manual of Standard Practice," of greater compressive strength than concrete and as follows:

1. For concrete surfaces exposed to view where legs of wire bar supports contact forms, use CRSI Class 1 plastic-protected steel wire or CRSI Class 2 stainless-steel bar supports.
2. For zinc-coated reinforcement, use galvanized wire or dielectric-polymer-coated wire bar supports.

2.4 CONCRETE, GENERAL

- A. ACI Publications: Comply with ACI 301 unless modified by requirements in the Contract Documents.

2.5 CONCRETE MATERIALS

- A. Regional Materials: Concrete shall be manufactured within 500 miles of Project site.
- B. Source Limitations:
1. Obtain all concrete mixtures from a single ready-mixed concrete manufacturer for entire Project.
 2. Obtain each type or class of cementitious material of the same brand from the same manufacturer's plant.
 3. Obtain aggregate from single source.
 4. Obtain each type of admixture from single source from single manufacturer.
- C. Cementitious Materials:
- A. Cementitious Material: Use the following cementitious materials, of the same type, brand, and source, throughout Project:
1. Portland Cement: ASTM C 150, Type I or 1A, unless otherwise noted, gray. Supplement with the following:
 - a. Fly Ash: ASTM C 618, Class F.
- B. Normal-Weight Aggregates: ASTM C 33, Class 3S coarse aggregate or better, graded. Provide aggregates from a single source with documented service record data of at least 10 years' satisfactory service in similar applications and service conditions using similar aggregates and cementitious materials.
1. Maximum Coarse-Aggregate Size: Refer to General Structural Notes on Drawings.
 2. Fine Aggregate: Free of materials with deleterious reactivity to alkali in cement. Natural sand or blend of natural and crushed sand. Crushed sand shall be less than 50% of the total sand by dry weight.
- C. Set-Accelerating Corrosion-Inhibiting Admixture: Commercially formulated, anodic inhibitor or mixed cathodic and anodic inhibitor; capable of forming a protective barrier and minimizing chloride reactions with steel reinforcement in concrete and complying with ASTM C 494/C 494M, Type C.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BASF Corp. - Construction Chemicals.
 - b. Euclid Chemical Company (The); an RPM company.
 - c. GCP Applied Technologies Inc. (formerly Grace Construction Products).
 - d. Sika Corporation.
- D. Non-Set-Accelerating Corrosion-Inhibiting Admixture: Commercially formulated, non-set-accelerating, anodic inhibitor or mixed cathodic and anodic inhibitor; capable of forming a protective barrier and minimizing chloride reactions with steel reinforcement in concrete.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BASF Corp. - Construction Chemicals.
 - b. Cortec Corporation.
 - c. GCP Applied Technologies Inc. (formerly Grace Construction Products).
 - d. Sika Corporation.
- E. Water: ASTM C 94/C 94M and potable.

2.6 VAPOR RETARDERS

- A. Sheet Vapor Retarder: ASTM E 1745, Class A. Include manufacturer's recommended adhesive or pressure-sensitive tape.
 - 1. Maintain permeance of less than 0.01 Perms as tested in accordance with mandatory conditioning tests per ASTM E1745 Section 7.1 (7.1.1-7.1.5).
 - a. Other performance criteria:
 - 1) Strength: ASTM E1745 Class A.
 - 2) Thickness: 15 mils minimum
 - b. Provide third party documentation that all testing was performed on a single production roll per ASTM E1745 Section 8.1
 - 2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Grace Construction Products; W.R. Grace & Co. -- Conn.
 - b. Poly-America, L.P.
 - c. Stego Industries, LLC.
 - d. W.R. Meadows, Inc.
 - e. Approved Substitution.

2.7 ADMIXTURES

- A. Air-Entraining Admixture: ASTM C 260. Refer to General Structural Notes on Drawings.
- B. Chemical Admixtures: Provide admixtures certified by manufacturer to be compatible with other admixtures and that will not contribute water-soluble chloride ions exceeding those permitted in hardened concrete. Do not use calcium chloride or admixtures containing calcium chloride. Select from the following:
 - 1. Water-Reducing Admixture: ASTM C 494/C 494M, Type A.
 - 2. Retarding Admixture: ASTM C 494/C 494M, Type B.
 - 3. Water-Reducing and Retarding Admixture: ASTM C 494/C 494M, Type D.
 - 4. High-Range, Water-Reducing Admixture: ASTM C 494/C 494M, Type F.
 - 5. Plasticizing and Retarding Admixture: ASTM C 1017/C 1017M, Type II.

2.8 CURING MATERIALS

- A. Moisture-Retaining Cover: ASTM C 171, polyethylene film or white burlap-polyethylene sheet.
- B. Water: Potable.

2.9 RELATED MATERIALS

- A. Semirigid Joint Filler: Two-component, semirigid, 100 percent solids, polyurea with a Type A shore durometer hardness of 80 per ASTM D 2240.
 - 1. Basis of Design: L&M Construction Chemicals, Inc. Joint Tite 750.
 - a. Euclid Chemical, Quickjoint 200
 - b. Approved substitution.
- B. Bonding Agent: ASTM C 1059/C 1059M, Type II, non-redispersible, acrylic emulsion or styrene butadiene.
- C. Epoxy Bonding Adhesive: ASTM C 881, two-component epoxy resin, capable of humid curing and bonding to damp surfaces, of class suitable for application temperature and of grade to suit requirements, and as follows:
 - 1. Types I and II, non-load bearing, or Types IV and V, load bearing, for bonding hardened or freshly mixed concrete to hardened concrete.

2.10 REPAIR MATERIALS

- A. Repair Underlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/8 inch and that can be feathered at edges to match adjacent floor elevations.
 - 1. Cement Binder: ASTM C 150, portland cement or hydraulic or blended hydraulic cement as defined in ASTM C 219.
 - 2. Primer: Product of underlayment manufacturer recommended for substrate, conditions, and application.
 - 3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch or coarse sand as recommended by underlayment manufacturer.
 - 4. Compressive Strength: Not less than 4100 psi at 28 days when tested according to ASTM C 109/C 109M.

2.11 CONCRETE MIXTURES, GENERAL

- A. Prepare design mixtures for each type and strength of concrete, proportioned on the basis of laboratory trial mixture or field test data, or both, in accordance with ACI 301.
 - 1. Use a qualified testing agency for preparing and reporting proposed mixture designs, based on laboratory trial mixtures.
- B. Cementitious Materials: Limit percentage, by weight, of cementitious materials other than portland cement in concrete as follows:
 - 1. Fly Ash or Other Pozzolans: 30 percent by mass maximum.
 - 2. Slag Cement: 50 percent by mass.
 - 3. Silica Fume: 10 percent by mass.
 - 4. Total of Fly Ash or Other Pozzolans, Slag Cement, and Silica Fume: 50 percent by mass, with fly ash or pozzolans not exceeding 30 percent by mass and silica fume not exceeding 10 percent by mass.
 - 5. Total of Fly Ash or Other Pozzolans and Silica Fume: 35 percent by mass with fly ash or pozzolans not exceeding 30 percent by mass and silica fume not exceeding 10 percent by mass.
- C. Admixtures: Use admixtures in accordance with manufacturer's written instructions.
 - 1. Use water-reducing, high-range water-reducing or plasticizing admixture in concrete, as required, for placement and workability.
 - 2. Use water-reducing and -retarding admixture when required by high temperatures, low humidity, or other adverse placement conditions.
 - 3. Use water-reducing admixture in pumped concrete, concrete for heavy-use industrial slabs and concrete with a w/cm below 0.50.
 - 4. Use corrosion-inhibiting admixture in concrete mixtures where indicated.
 - 5. Use permeability-reducing admixture in concrete mixtures where indicated.

2.12 CONCRETE MIXTURES

- A. Normal-weight concrete used for footings.
 - 1. Exposure Class: ACI 318 F2 S0 P0 C1
 - 2. Minimum Compressive Strength: 3000 psi at 28 days.
 - 3. Maximum w/cm: 0.50.
 - 4. Slump Limit: 5 inches, plus or minus 1 inch.
 - 5. Slump Flow Limit: 22 inches, plus or minus 1.5 inches.
 - 6. Air Content:
 - a. Exposure Class F2 and F3: 6 percent, plus or minus 1.5 percent at point of delivery for concrete containing 1-inch nominal maximum aggregate size.
 - 7. Limit water-soluble, chloride-ion content in hardened concrete to 0.15 percent by weight of cement.
- B. Normal-weight concrete used for foundation walls.

1. Exposure Class: ACI 318 F1 S0 P0 C1.
 2. Minimum Compressive Strength: 4000 psi at 28 days.
 3. Maximum w/cm: 0.45.
 4. Slump Limit: 5 inches, plus or minus 1 inch.
 5. Slump Flow Limit: 22 inches, plus or minus 1.5 inches.
 6. Air Content:
 - a. Exposure Class F1: 5.0 percent, plus or minus 1.5 percent at point of delivery for concrete containing 3/4-inch nominal maximum aggregate size.
 7. Limit water-soluble, chloride-ion content in hardened concrete to 0.15 percent by weight of cement.
- C. Normal-weight concrete used for interior slabs-on-ground.
1. Exposure Class: ACI 318 F0 S0 P0 C0.
 2. Minimum Compressive Strength: 3500 psi at 28 days.
 3. Maximum w/cm: 0.50.
 4. Minimum Cementitious Materials Content: 540 lb/cu. yd.
 5. Slump Limit: 5 inches, plus or minus 1 inch.
 6. Slump Flow Limit: 22 inches, plus or minus 1.5 inches.
 7. Air Content:
 - a. Do not use an air-entraining admixture or allow total air content to exceed 3 percent for concrete used in trowel-finished floors.
 8. Limit water-soluble, chloride-ion content in hardened concrete to 0.15 percent by weight of cement.

2.13 CONCRETE MIXING

- A. Ready-Mixed Concrete: Measure, batch, mix, and deliver concrete in accordance with ASTM C94/C94M and ASTM C1116/C1116M, and furnish batch ticket information.
- B. Project-Site Mixing: Measure, batch, and mix concrete materials and concrete in accordance with ASTM C94/C94M. Mix concrete materials in appropriate drum-type batch machine mixer.
 1. For mixer capacity of 1 cu. yd. or smaller, continue mixing at least 1-1/2 minutes, but not more than five minutes after ingredients are in mixer, before any part of batch is released.
 2. For mixer capacity larger than 1 cu. yd., increase mixing time by 15 seconds for each additional 1 cu. yd.
 3. Provide batch ticket for each batch discharged and used in the Work, indicating Project identification name and number, date, mixture type, mixture time, quantity, and amount of water added. Record approximate location of final deposit in structure.

2.14 CURING MATERIALS

- A. Clear, Waterborne, Membrane-Forming, Curing and Sealing Compound: ASTM C1315, Type 1, Class A.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Dayton Superior.
 - b. Euclid Chemical Company (The); an RPM company.
 - c. Kaufman Products, Inc.
 - d. Lambert Corporation.
 - e. Laticrete International, Inc.
 - f. W.R. Meadows, Inc.
- B. Products shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verification of Conditions:
 - 1. Before placing concrete, verify that installation of concrete forms, accessories, and reinforcement, and embedded items is complete and that required inspections have been performed.
 - 2. Do not proceed until unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Provide reasonable auxiliary services to accommodate field testing and inspections, acceptable to testing agency, including the following:
 - 1. Daily access to the Work.
 - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 - 3. Secure space for storage, initial curing, and field curing of test samples, including source of water and continuous electrical power at Project site during site curing period for test samples.
 - 4. Security and protection for test samples and for testing and inspection equipment at Project site.

3.3 INSTALLATION OF EMBEDDED ITEMS

- A. Place and secure anchorage devices and other embedded items required for adjoining Work that is attached to or supported by cast-in-place concrete.
 - 1. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 2. Install anchor rods, accurately located, to elevations required and complying with tolerances in Section 7.5 of ANSI/AISC 303.
 - 3. Install reglets to receive waterproofing and to receive through-wall flashings in outer face of concrete frame at exterior walls, where flashing is shown at lintels, shelf angles, and other conditions.

3.4 INSTALLATION OF VAPOR RETARDER

- A. Sheet Vapor Retarders: Place, protect, and repair sheet vapor retarder in accordance with ASTM E1643 and manufacturer's written instructions.
 - 1. Install vapor retarder with longest dimension parallel with direction of concrete pour.
 - 2. Face laps away from exposed direction of concrete pour.
 - 3. Lap vapor retarder over footings and grade beams not less than 6 inches, sealing vapor retarder to concrete.
 - 4. Lap joints 6 inches and seal with manufacturer's recommended tape.
 - 5. Terminate vapor retarder at the top of floor slabs, grade beams, and pile caps, sealing entire perimeter to floor slabs, grade beams, foundation walls, or pile caps.
 - 6. Seal penetrations in accordance with vapor retarder manufacturer's instructions.
 - 7. Protect vapor retarder during placement of reinforcement and concrete.
 - a. Repair damaged areas by patching with vapor retarder material, overlapping damages area by 6 inches on all sides, and sealing to vapor retarder.

3.5 JOINTS

- A. Construct joints true to line, with faces perpendicular to surface plane of concrete.
- B. Construction Joints: Coordinate with floor slab pattern and concrete placement sequence.
 - 1. Install so strength and appearance of concrete are not impaired, at locations indicated on Drawings or as approved by Architect.
 - 2. Place joints perpendicular to main reinforcement.
 - a. Continue reinforcement across construction joints unless otherwise indicated.
 - b. Do not continue reinforcement through sides of strip placements of floors and slabs.
 - 3. Form keyed joints as indicated. Embed keys at least 1-1/2 inches into concrete.
 - 4. Locate joints for beams, slabs, joists, and girders at third points of spans. Offset joints in girders a minimum distance of twice the beam width from a beam-girder intersection.
 - 5. Locate horizontal joints in walls and columns at underside of floors, slabs, beams, and girders and at the top of footings or floor slabs.
 - 6. Space vertical joints in walls as indicated on Drawings. Unless otherwise indicated on Drawings, locate vertical joints beside piers integral with walls, near corners, and in concealed locations where possible.
 - 7. Use a bonding agent at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
 - 8. Use epoxy-bonding adhesive at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
- C. Control Joints in Slabs-on-Ground: Form weakened-plane control joints, sectioning concrete into areas as indicated. Construct control joints for a depth equal to at least one-fourth of concrete thickness as follows:
 - 1. Grooved Joints: Form control joints after initial floating by grooving and finishing each edge of joint to a radius of 1/8 inch. Repeat grooving of control joints after applying surface finishes. Eliminate groover tool marks on concrete surfaces.
 - 2. Sawed Joints: Form control joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch-wide joints into concrete when cutting action does not tear, abrade, or otherwise damage surface and before concrete develops random cracks.
- D. Isolation Joints in Slabs-on-Ground: After removing formwork, install joint-filler strips at slab junctions with vertical surfaces, such as column pedestals, foundation walls, grade beams, and other locations, as indicated.
 - 1. Extend joint-filler strips full width and depth of joint, terminating flush with finished concrete surface unless otherwise indicated on Drawings.
 - 2. Terminate full-width joint-filler strips not less than 1/2 inch or more than 1 inch below finished concrete surface, where joint sealants, specified in Section 079200 "Joint Sealants," are indicated.
 - 3. Install joint-filler strips in lengths as long as practicable. Where more than one length is required, lace or clip sections together.
- E. Doweled Joints:
 - 1. Install dowel bars and support assemblies at joints where indicated on Drawings.
 - 2. Lubricate or asphalt coat one-half of dowel bar length to prevent concrete bonding to one side of joint.
- F. Dowel Plates: Install dowel plates at joints where indicated on Drawings.

3.6 CONCRETE PLACEMENT

- A. Before placing concrete, verify that installation of formwork, reinforcement, embedded items, and vapor retarder is complete and that required inspections are completed.
 - 1. Immediately prior to concrete placement, inspect vapor retarder for damage and deficient installation, and repair defective areas.

2. Provide continuous inspection of vapor retarder during concrete placement and make necessary repairs to damaged areas as Work progresses.
- B. Notify Architect and testing and inspection agencies 24 hours prior to commencement of concrete placement.
- C. Do not add water to concrete during delivery, at Project site, or during placement unless approved by Architect in writing, but not to exceed the amount indicated on the concrete delivery ticket.
 1. Do not add water to concrete after adding high-range water-reducing admixtures to mixture.
- D. Before test sampling and placing concrete, water may be added at Project site, subject to limitations of ACI 301, but not to exceed the amount indicated on the concrete delivery ticket.
 1. Do not add water to concrete after adding high-range water-reducing admixtures to mixture.
- E. Deposit concrete continuously in one layer or in horizontal layers of such thickness that no new concrete is placed on concrete that has hardened enough to cause seams or planes of weakness.
 1. If a section cannot be placed continuously, provide construction joints as indicated.
 2. Deposit concrete to avoid segregation.
 3. Deposit concrete in horizontal layers of depth not to exceed formwork design pressures and in a manner to avoid inclined construction joints.
 4. Consolidate placed concrete with mechanical vibrating equipment in accordance with ACI 301.
 - a. Do not use vibrators to transport concrete inside forms.
 - b. Insert and withdraw vibrators vertically at uniformly spaced locations to rapidly penetrate placed layer and at least 6 inches into preceding layer.
 - c. Do not insert vibrators into lower layers of concrete that have begun to lose plasticity.
 - d. At each insertion, limit duration of vibration to time necessary to consolidate concrete, and complete embedment of reinforcement and other embedded items without causing mixture constituents to segregate.
- F. Deposit and consolidate concrete for floors and slabs in a continuous operation, within limits of construction joints, until placement of a panel or section is complete.
 1. Do not place concrete floors and slabs in a checkerboard sequence.
 2. Consolidate concrete during placement operations, so concrete is thoroughly worked around reinforcement and other embedded items and into corners.
 3. Maintain reinforcement in position on chairs during concrete placement.
 4. Screed slab surfaces with a straightedge and strike off to correct elevations.
 5. Level concrete, cut high areas, and fill low areas.
 6. Slope surfaces uniformly to drains where required.
 7. Begin initial floating using bull floats or darbies to form a uniform and open-textured surface plane, before excess bleedwater appears on the surface.
 8. Do not further disturb slab surfaces before starting finishing operations.

3.7 FINISHING FORMED SURFACES

- A. As-Cast Surface Finishes:
 1. ACI 301 Surface Finish SF-1.0: As-cast concrete texture imparted by form-facing material.
 - a. Patch voids larger than 1-1/2 inches wide or 1/2 inch deep.
 - b. Remove projections larger than 1 inch.
 - c. Tie holes do not require patching.
 - d. Surface Tolerance: ACI 117 Class D.
 - e. Apply to concrete surfaces not exposed to public view.

2. ACI 301 Surface Finish SF-2.0: As-cast concrete texture imparted by form-facing material, arranged in an orderly and symmetrical manner with a minimum of seams.
 - a. Patch voids larger than 3/4 inch wide or 1/2 inch deep.
 - b. Remove projections larger than 1/4 inch.
 - c. Patch tie holes.
 - d. Surface Tolerance: ACI 117 Class B.
 - e. Locations: Apply to concrete surfaces exposed to public view, or to be covered with a coating or covering material applied directly to concrete.

3.8 FINISHING FLOORS AND SLABS

- A. Comply with ACI 302.1R recommendations for screeding, restraightening, and finishing operations for concrete surfaces. Do not wet concrete surfaces.
- B. Float Finish:
 1. When bleedwater sheen has disappeared and concrete surface has stiffened sufficiently to permit operation of specific float apparatus, consolidate concrete surface with power-driven floats or by hand floating if area is small or inaccessible to power-driven floats.
 2. Repeat float passes and restraightening until surface is left with a uniform, smooth, granular texture and complies with ACI 117 tolerances for conventional concrete.
 3. Apply float finish to surfaces to receive trowel finish.
- C. Trowel Finish:
 1. After applying float finish, apply first troweling and consolidate concrete by hand or power-driven trowel.
 2. Continue troweling passes and restraighten until surface is free of trowel marks and uniform in texture and appearance.
 3. Grind smooth any surface defects that would telegraph through applied coatings or floor coverings.
 4. Do not add water to concrete surface.
 5. Do not apply hard-troweled finish to concrete, which has a total air content greater than 3 percent.
 6. Apply a trowel finish to surfaces exposed to view or to be covered with resilient flooring, carpet, ceramic or quarry tile set over a cleavage membrane, paint, or another thin-film-finish coating system.
 7. Finish surfaces to the following tolerances, in accordance with ASTM E1155, for a randomly trafficked floor surface:
 - a. Slabs on Ground:
 - 1) Finish and measure surface so gap at any point between concrete surface and an unlevelled, freestanding, 10-ft.- long straightedge resting on two high spots and placed anywhere on the surface does not exceed 1/8 inch.
 - 2) Specified overall values of flatness, F_F 25; and of levelness, F_L 20; with minimum local values of flatness, F_F 17; and of levelness, F_L 15.
 - 3) Specified overall values of flatness, F_F 35; and of levelness, F_L 25; with minimum local values of flatness, F_F 24; and of levelness, F_L 17.
 - 4) Specified overall values of flatness, F_F 45; and of levelness, F_L 35; with minimum local values of flatness, F_F 30; and of levelness, F_L 24.
 - 5) Specified Overall Value (SOV): F_F 50 and F_L 25 with minimum local value (MLV): F_F 40 and F_L 17.
 - 6) Specified Overall Value (SOV): F_F 25 and F_L 20 with minimum local value (MLV): F_F 17 and F_L 15.

- D. Trowel and Fine-Broom Finish: Apply a first trowel finish to surfaces indicated on Drawings. While concrete is still plastic, slightly scarify surface with a fine broom perpendicular to main traffic route.
 - 1. Coordinate required final finish with Architect before application.
 - 2. Comply with flatness and levelness tolerances for trowel-finished floor surfaces.
- E. Broom Finish: Apply a broom finish to exterior concrete platforms, steps, ramps, and locations indicated on Drawings.
 - 1. Immediately after float finishing, slightly roughen trafficked surface by brooming with fiber-bristle broom perpendicular to main traffic route.
 - 2. Coordinate required final finish with Architect before application.
- F. Slip-Resistive Finish: Before final floating, apply slip-resistive aggregate finish to concrete stair treads, platforms, ramps as indicated on Drawings
 - 1. Apply in accordance with manufacturer's written instructions and as follows:
 - a. Uniformly spread 25 lb/100 sq. ft. of dampened slip-resistive aggregate over surface in one or two applications.
 - b. Tamp aggregate flush with surface, but do not force below surface.
 - c. After broadcasting and tamping, apply float finish.
 - d. After curing, lightly work surface with a steel wire brush or an abrasive stone and water to expose slip-resistive aggregate.

3.9 INSTALLATION OF MISCELLANEOUS CONCRETE ITEMS

- A. Filling In:
 - 1. Fill in holes and openings left in concrete structures after Work of other trades is in place unless otherwise indicated.
 - 2. Mix, place, and cure concrete, as specified, to blend with in-place construction.
 - 3. Provide other miscellaneous concrete filling indicated or required to complete the Work.
- B. Curbs: Provide monolithic finish to interior curbs by stripping forms while concrete is still green and by steel-troweling surfaces to a hard, dense finish with corners, intersections, and terminations slightly rounded.
- C. Equipment Bases and Foundations:
 - 1. Coordinate sizes and locations of concrete bases with actual equipment provided.
 - 2. Construct concrete bases 4 inches high unless otherwise indicated on Drawings, and extend base not less than 6 inches in each direction beyond the maximum dimensions of supported equipment unless otherwise indicated on Drawings, or unless required for seismic anchor support.
 - 3. Minimum Compressive Strength: 3500 psi at 28 days.
 - 4. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around the full perimeter of concrete base.
 - 5. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete substrate.
 - 6. Prior to pouring concrete, place and secure anchorage devices.
 - a. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - b. Cast anchor-bolt insert into bases.
 - c. Install anchor bolts to elevations required for proper attachment to supported equipment.
- D. Steel Pan Stairs: Provide concrete fill for steel pan stair treads, landings, and associated items.
 - 1. Cast-in inserts and accessories, as shown on Drawings.
 - 2. Screed, tamp, and trowel finish concrete surfaces.

3.10 CONCRETE CURING

- A. Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.
 - 1. Comply with ACI 301 and ACI 306.1 for cold weather protection during curing.
 - 2. Comply with ACI 301 and ACI 305.1 for hot-weather protection during curing.
 - 3. Maintain moisture loss no more than 0.2 lb/sq. ft. x h before and during finishing operations.
- B. Curing Formed Surfaces: Comply with ACI 308.1 as follows:
 - 1. Cure formed concrete surfaces, including underside of beams, supported slabs, and other similar surfaces.
 - 2. Cure concrete containing color pigments in accordance with color pigment manufacturer's instructions.
 - 3. If forms remain during curing period, moist cure after loosening forms.
 - 4. If removing forms before end of curing period, continue curing for remainder of curing period, as follows:
 - a. Continuous Fogging: Maintain standing water on concrete surface until final setting of concrete.
 - b. Continuous Sprinkling: Maintain concrete surface continuously wet.
 - c. Absorptive Cover: Pre-dampen absorptive material before application; apply additional water to absorptive material to maintain concrete surface continuously wet.
 - d. Water-Retention Sheeting Materials: Cover exposed concrete surfaces with sheeting material, taping, or lapping seams.
 - e. Membrane-Forming Curing Compound: Apply uniformly in continuous operation by power spray or roller in accordance with manufacturer's written instructions.
 - 1) Recoat areas subject to heavy rainfall within three hours after initial application.
 - 2) Maintain continuity of coating and repair damage during curing period.
- C. Curing Unformed Surfaces: Comply with ACI 308.1 as follows:
 - 1. Begin curing immediately after finishing concrete.
 - 2. Interior Concrete Floors:
 - a. Floors to Receive Curing and Sealing Compound:
 - 1) Apply uniformly to floors and slabs indicated in a continuous operation by power spray or roller in accordance with manufacturer's written instructions.
 - 2) Recoat areas subjected to heavy rainfall within three hours after initial application.
 - 3) Repeat process 24 hours later and apply a second coat. Maintain continuity of coating, and repair damage during curing period.

3.11 TOLERANCES

- A. Conform to ACI 117.

3.12 JOINT FILLING

- A. Prepare, clean, and install joint filler in accordance with manufacturer's written instructions.
 - 1. Defer joint filling until concrete has aged at least one month(s).
 - 2. Do not fill joints until construction traffic has permanently ceased.
- B. Remove dirt, debris, saw cuttings, curing compounds, and sealers from joints; leave contact faces of joints clean and dry.

- C. Install semirigid joint filler full depth in saw-cut joints and at least 2 inches deep in formed joints.
- D. Overfill joint, and trim joint filler flush with top of joint after hardening.

3.13 CONCRETE SURFACE REPAIRS

- A. Defective Concrete:
 - 1. Repair and patch defective areas when approved by Architect.
 - 2. Remove and replace concrete that cannot be repaired and patched to Architect's approval.
- B. Patching Mortar: Mix dry-pack patching mortar, consisting of 1 part portland cement to 2-1/2 parts fine aggregate passing a No. 16 sieve, using only enough water for handling and placing.
- C. Repairing Formed Surfaces: Surface defects include color and texture irregularities, cracks, spalls, air bubbles, honeycombs, rock pockets, fins and other projections on the surface, and stains and other discolorations that cannot be removed by cleaning.
 - 1. Immediately after form removal, cut out honeycombs, rock pockets, and voids more than 1/2 inch in any dimension to solid concrete.
 - a. Limit cut depth to 3/4 inch.
 - b. Make edges of cuts perpendicular to concrete surface.
 - c. Clean, dampen with water, and brush-coat holes and voids with bonding agent.
 - d. Fill and compact with patching mortar before bonding agent has dried.
 - e. Fill form-tie voids with patching mortar or cone plugs secured in place with bonding agent.
 - 2. Repair defects on surfaces exposed to view by blending white portland cement and standard portland cement, so that, when dry, patching mortar matches surrounding color.
 - a. Patch a test area at inconspicuous locations to verify mixture and color match before proceeding with patching.
 - b. Compact mortar in place and strike off slightly higher than surrounding surface.
 - 3. Repair defects on concealed formed surfaces that will affect concrete's durability and structural performance as determined by Architect.
- D. Repairing Unformed Surfaces:
 - 1. Test unformed surfaces, such as floors and slabs, for finish, and verify surface tolerances specified for each surface.
 - a. Correct low and high areas.
 - b. Test surfaces sloped to drain for trueness of slope and smoothness; use a sloped template.
 - 2. Repair finished surfaces containing surface defects, including spalls, popouts, honeycombs, rock pockets, crazing, and cracks in excess of 0.01 inch wide or that penetrate to reinforcement or completely through unreinforced sections regardless of width, and other objectionable conditions.
 - 3. After concrete has cured at least 14 days, correct high areas by grinding.
 - 4. Correct localized low areas during, or immediately after, completing surface-finishing operations by cutting out low areas and replacing with patching mortar.
 - a. Finish repaired areas to blend into adjacent concrete.
 - 5. Correct other low areas scheduled to receive floor coverings with a repair underlayment.
 - a. Prepare, mix, and apply repair underlayment and primer in accordance with manufacturer's written instructions to produce a smooth, uniform, plane, and level surface.
 - b. Feather edges to match adjacent floor elevations.
 - 6. Correct other low areas scheduled to remain exposed with repair topping.

- a. Cut out low areas to ensure a minimum repair topping depth of 1/4 inch to match adjacent floor elevations.
- b. Prepare, mix, and apply repair topping and primer in accordance with manufacturer's written instructions to produce a smooth, uniform, plane, and level surface.
- 7. Repair defective areas, except random cracks and single holes 1 inch or less in diameter, by cutting out and replacing with fresh concrete.
 - a. Remove defective areas with clean, square cuts, and expose steel reinforcement with at least a 3/4-inch clearance all around.
 - b. Dampen concrete surfaces in contact with patching concrete and apply bonding agent.
 - c. Mix patching concrete of same materials and mixture as original concrete, except without coarse aggregate.
 - d. Place, compact, and finish to blend with adjacent finished concrete.
 - e. Cure in same manner as adjacent concrete.
- 8. Repair random cracks and single holes 1 inch or less in diameter with patching mortar.
 - a. Groove top of cracks and cut out holes to sound concrete, and clean off dust, dirt, and loose particles.
 - b. Dampen cleaned concrete surfaces and apply bonding agent.
 - c. Place patching mortar before bonding agent has dried.
 - d. Compact patching mortar and finish to match adjacent concrete.
 - e. Keep patched area continuously moist for at least 72 hours.
- E. Perform structural repairs of concrete, subject to Architect's approval, using epoxy adhesive and patching mortar.
- F. Repair materials and installation not specified above may be used, subject to Architect's approval.

3.14 FIELD QUALITY CONTROL

- A. Special Inspections: Owner will engage a special inspector to perform field tests and inspections and prepare testing and inspection reports.
- B. Testing Agency: Owner will engage a qualified testing and inspecting agency to perform tests and inspections and to submit reports.
 - 1. Testing agency shall be responsible for providing curing container for composite samples on Site and verifying that field-cured composite samples are cured in accordance with ASTM C31/C31M.
 - 2. Testing agency shall immediately report to Architect, Contractor, and concrete manufacturer any failure of Work to comply with Contract Documents.
 - 3. Testing agency shall report results of tests and inspections, in writing, to Owner, Architect, Contractor, and concrete manufacturer within 48 hours of inspections and tests.
 - a. Test reports shall include reporting requirements of ASTM C31/C31M, ASTM C39/C39M, and ACI 301, including the following as applicable to each test and inspection:
 - 1) Project name.
 - 2) Name of testing agency.
 - 3) Names and certification numbers of field and laboratory technicians performing inspections and testing.
 - 4) Name of concrete manufacturer.
 - 5) Date and time of inspection, sampling, and field testing.
 - 6) Date and time of concrete placement.
 - 7) Location in Work of concrete represented by samples.
 - 8) Date and time sample was obtained.
 - 9) Truck and batch ticket numbers.
 - 10) Design compressive strength at 28 days.

- 11) Concrete mixture designation, proportions, and materials.
 - 12) Field test results.
 - 13) Information on storage and curing of samples before testing, including curing method and maximum and minimum temperatures during initial curing period.
 - 14) Type of fracture and compressive break strengths at seven days and 28 days.
- C. Batch Tickets: For each load delivered, submit three copies of batch delivery ticket to testing agency, indicating quantity, mix identification, admixtures, design strength, aggregate size, design air content, design slump at time of batching, and amount of water that can be added at Project site.
- D. Inspections:
1. Headed bolts and studs.
 2. Verification of use of required design mixture.
 3. Concrete placement, including conveying and depositing.
 4. Curing procedures and maintenance of curing temperature.
 5. Verification of concrete strength before removal of shores and forms from beams and slabs.
 6. Batch Plant Inspections: On a random basis, as determined by Architect.
- E. Concrete Tests: Testing of composite samples of fresh concrete obtained in accordance with ASTM C 172/C 172M shall be performed in accordance with the following requirements:
1. Testing Frequency: Obtain one composite sample for each day's pour of each concrete mixture exceeding 5 cu. yd., but less than 25 cu. yd., plus one set for each additional 50 cu. yd. or fraction thereof.
 - a. When frequency of testing provides fewer than five compressive-strength tests for each concrete mixture, testing shall be conducted from at least five randomly selected batches or from each batch if fewer than five are used.
 2. Slump: ASTM C143/C143M:
 - a. One test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mixture.
 - b. Perform additional tests when concrete consistency appears to change.
 3. Slump Flow: ASTM C1611/C1611M:
 - a. One test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mixture.
 - b. Perform additional tests when concrete consistency appears to change.
 4. Air Content: ASTM C231/C231M pressure method, for normal-weight concrete;.
 - a. One test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
 5. Concrete Temperature: ASTM C1064/C1064M:
 - a. One test hourly when air temperature is 40 deg F and below or 80 deg F and above, and one test for each composite sample.
 6. Unit Weight: ASTM C567/C567M fresh unit weight of structural lightweight concrete.
 - a. One test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
 7. Compression Test Specimens: ASTM C31/C31M:
 - a. Cast and laboratory cure two sets of four 6-inch by 12-inch or 4-inch by 8-inch cylinder specimens for each composite sample.
 - b. Cast, initial cure, and field cure two sets of four standard cylinder specimens for each composite sample.
 8. Compressive-Strength Tests: ASTM C39/C39M.
 - a. Test one set of four laboratory-cured specimens at seven days and one set of two specimens at 28 days.

- b. Test one set of four field-cured specimens at seven days and one set of two specimens at 28 days.
 - c. A compressive-strength test shall be the average compressive strength from a set of two specimens obtained from same composite sample and tested at age indicated.
- 9. When strength of field-cured cylinders is less than 85 percent of companion laboratory-cured cylinders, Contractor shall evaluate operations and provide corrective procedures for protecting and curing in-place concrete.
- 10. Strength of each concrete mixture will be satisfactory if every average of any three consecutive compressive-strength tests equals or exceeds specified compressive strength, and no compressive-strength test value falls below specified compressive strength by more than 500 psi if specified compressive strength is 5000 psi, or no compressive strength test value is less than 10 percent of specified compressive strength if specified compressive strength is greater than 5000 psi.
- 11. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.
- 12. Additional Tests:
 - a. Testing and inspecting agency shall make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Architect.
 - b. Testing and inspecting agency may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C42/C42M or by other methods as directed by Architect.
 - 1) Acceptance criteria for concrete strength shall be in accordance with ACI 301 section 1.6.6.3.
- 13. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.
- 14. Correct deficiencies in the Work that test reports and inspections indicate do not comply with the Contract Documents.
- F. Measure floor and slab flatness and levelness in accordance with ASTM E1155 within 72 hours of completion of floor finishing and promptly report test results to Architect.

3.15 PROTECTION

- A. Protect concrete surfaces as follows:
 - 1. Protect from petroleum stains.
 - 2. Diaper hydraulic equipment used over concrete surfaces.
 - 3. Prohibit vehicles from interior concrete slabs.
 - 4. Prohibit use of pipe-cutting machinery over concrete surfaces.
 - 5. Prohibit placement of steel items on concrete surfaces.
 - 6. Prohibit use of acids or acidic detergents over concrete surfaces.
 - 7. Protect liquid floor treatment from damage and wear during the remainder of construction period. Use protective methods and materials, including temporary covering, recommended in writing by liquid floor treatments installer.
 - 8. Protect concrete surfaces scheduled to receive surface hardener or polished concrete finish using Floor Slab Protective Covering.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 04 22 00
CONCRETE UNIT MASONRY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Concrete masonry units.
 - 2. Mortar and grout.
 - 3. Steel reinforcing bars.
 - 4. Masonry-joint reinforcement.
 - 5. Miscellaneous masonry accessories.
- B. Products Installed but not Furnished under This Section:
 - 1. Cast-stone trim in concrete unit masonry.
 - 2. Concrete wall substrate.
- C. Related Requirements:
 - 1. Section 017419 "Construction Waste Management and Disposal."
 - 2. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 3. Section 061053 "Miscellaneous Rough Carpentry".

1.3 DEFINITIONS

- A. CMU(s): Concrete masonry unit(s).
- B. Reinforced Masonry: Masonry containing reinforcing steel in grouted cells.

1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. High Performance Submittals
 - 1. Product Data: For products having recycled content, documentation indicating percentages by weight of postconsumer and preconsumer recycled content. Include statement indicating costs for each product having recycled content.
 - 2. Product Certificates: For products and materials required to comply with requirements for regional materials indicating location and distance from Project of material manufacturer and point of extraction, harvest, or recovery for each raw material. Include statement indicating cost for each regional material and the fraction by weight that is considered regional.
 - 3. Product Data, including printed statement of VOC content, for products and materials required to be low-emitting. Products that apply may include, but are not limited to: adhesives, sealants, paints, & coatings.
- C. Shop Drawings: For the following:
 - 1. Masonry Units: Show sizes, profiles, coursing, and locations of special shapes.

2. Reinforcing Steel: Detail bending, lap lengths, and placement of unit masonry reinforcing bars. Comply with ACI 315. Show elevations of reinforced walls.
3. Fabricated Flashing: Detail corner units, end-dam units, and other special applications.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For testing agency.
- B. Material Certificates: For each type and size of the following:
 1. Masonry units.
 - a. Include material test reports substantiating compliance with requirements.
 - b. For masonry units used in structural masonry, include data and calculations establishing average net-area compressive strength of units.
 2. Integral water repellent used in CMUs.
 3. Cementitious materials. Include name of manufacturer, brand name, and type.
 4. Mortar admixtures.
 5. Preblended, dry mortar mixes. Include description of type and proportions of ingredients.
 6. Grout mixes. Include description of type and proportions of ingredients.
 7. Reinforcing bars.
 8. Joint reinforcement.
 9. Anchors, ties, and metal accessories.
- C. Mix Designs: For each type of mortar. Include description of type and proportions of ingredients.
 1. Include test reports for mortar mixes required to comply with property specification. Test according to ASTM C109/C109M for compressive strength, ASTM C1506 for water retention, and ASTM C91/C91M for air content.
 2. Include test reports, according to ASTM C1019, for grout mixes required to comply with compressive strength requirement.
- D. Statement of Compressive Strength of Masonry: For each combination of masonry unit type and mortar type, provide statement of average net-area compressive strength of masonry units, mortar type, and resulting net-area compressive strength of masonry determined according to TMS 602/ACI 530.1/ASCE 6.

1.7 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Qualified according to ASTM C1093 for testing indicated.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Store masonry units on elevated platforms in a dry location. If units are not stored in an enclosed location, cover tops and sides of stacks with waterproof sheeting, securely tied. If units become wet, do not install until they are dry.
- B. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.
- C. Store aggregates where grading and other required characteristics can be maintained and contamination avoided.
- D. Deliver preblended, dry mortar mix in moisture-resistant containers. Store preblended, dry mortar mix in delivery containers on elevated platforms in a dry location or in covered weatherproof dispensing silos.
- E. Store masonry accessories, including metal items, to prevent corrosion and accumulation of dirt and oil.

1.9 FIELD CONDITIONS

- A. Protection of Masonry: During construction, cover tops of walls, projections, and sills with waterproof sheeting at end of each day's work. Cover partially completed masonry when construction is not in progress.
 - 1. Extend cover a minimum of 24 inches down both sides of walls, and hold cover securely in place.
- B. Do not apply uniform floor or roof loads for at least 12 hours and concentrated loads for at least three days after building masonry walls or columns.
- C. Hot-Weather Requirements: Comply with hot-weather construction requirements contained in TMS 602/ACI 530.1/ASCE 6.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Source Limitations for Masonry Units: Obtain exposed masonry units of a uniform texture and color, or a uniform blend within the ranges accepted for these characteristics, from single source from single manufacturer for each product required.
- B. Source Limitations for Mortar Materials: Obtain mortar ingredients of a uniform quality, including color for exposed masonry, from single manufacturer for each cementitious component and from single source or producer for each aggregate.

2.2 PERFORMANCE REQUIREMENTS

- A. Provide unit masonry that develops indicated net-area compressive strengths at 28 days.
 - 1. Determine net-area compressive strength of masonry from average net-area compressive strengths of masonry units and mortar types (unit-strength method) according to TMS 602/ACI 530.1/ASCE 6.
 - 2. Determine net-area compressive strength of masonry by testing masonry prisms according to ASTM C1314.

2.3 UNIT MASONRY, GENERAL

- A. Masonry Standard: Comply with TMS 602/ACI 530.1/ASCE 6 except as modified by requirements in the Contract Documents.
- B. Defective Units: Referenced masonry unit standards may allow a certain percentage of units to contain chips, cracks, or other defects exceeding limits stated. Do not use units where such defects are exposed in the completed Work.
- C. Fire-Resistance Ratings: Comply with requirements for fire-resistance-rated assembly designs indicated.
 - 1. Where fire-resistance-rated construction is indicated, units shall be listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction.

2.4 CONCRETE MASONRY UNITS

- A. Shapes: Provide shapes indicated and as follows, with exposed surfaces matching exposed faces of adjacent units unless otherwise indicated.
 - 1. Provide special shapes for lintels, corners, jambs, sashes, movement joints, headers, bonding, and other special conditions.
 - 2. Provide square-edged units for outside corners unless otherwise indicated.
- B. Integral Water Repellent: Provide units made with integral water repellent for exposed units.

1. Integral Water Repellent: Liquid polymeric, integral water-repellent admixture that does not reduce flexural bond strength. Units made with integral water repellent, when tested according to ASTM E514/E514M as a wall assembly made with mortar containing integral water-repellent manufacturer's mortar additive, with test period extended to 24 hours, shall show no visible water or leaks on the back of test specimen.
 - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1) ACM Chemistries.
 - 2) BASF Corporation.
 - 3) Euclid Chemical Company (The); an RPM company.
 - 4) GCP Applied Technologies Inc.
 - 5) Moxie International.
 - 6) Approved substitution.
- C. CMUs: ASTM C90.
 1. Unit Compressive Strength: Provide units with minimum average net-area compressive strength of 1900 psi.
 2. Density Classification: Lightweight unless otherwise indicated.
 3. Size (Width): Manufactured to dimensions 3/8 inch less-than-nominal dimensions.
 4. Exposed Faces: Provide color and texture matching the range represented by Architect's sample.
- D. Decorative CMUs: ASTM C90.
 1. Unit Compressive Strength: Provide units with minimum average net-area compressive strength of 1900 psi.
 2. Density Classification: Lightweight.
 3. Size (Width): Manufactured to dimensions specified in "CMUs" Paragraph.
 4. Pattern and Texture:
 - a. Standard pattern, split-face finish laid in stacked bond.
 - b. Triple scored vertically laid in stacked bond.
 5. Colors: As selected by Architect from manufacturer's full range.

2.5 MASONRY LINTELS

- A. Masonry Lintels: Prefabricated or built-in-place masonry lintels made from bond beam CMUs matching adjacent CMUs in color, texture, and density classification, with reinforcing bars placed as indicated and filled with coarse grout. Cure precast lintels before handling and installing. Temporarily support built-in-place lintels until cured.

2.6 MORTAR AND GROUT MATERIALS

- A. Portland Cement: ASTM C150/C150M, Type I or II, except Type III may be used for cold-weather construction. Provide natural color or white cement as required to produce mortar color indicated.
 1. Alkali content shall not be more than 0.1 percent when tested according to ASTM C114.
- B. Hydrated Lime: ASTM C207, Type S.
- C. Portland Cement-Lime Mix: Packaged blend of portland cement and hydrated lime containing no other ingredients.
- D. Mortar Cement: ASTM C1329/C1329M.
- E. Aggregate for Mortar: ASTM C144.
- F. Aggregate for Grout: ASTM C404.
- G. Water: Potable.

2.7 REINFORCEMENT

- A. Uncoated Steel Reinforcing Bars: ASTM A615/A615M or ASTM A996/A996M, Grade 60.
- B. Reinforcing Bar Positioners: Wire units designed to fit into mortar bed joints spanning masonry unit cells and to hold reinforcing bars in center of cells. Units are formed from 0.148-inch steel wire, hot-dip galvanized after fabrication. Provide units designed for number of bars indicated.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Dur-O-Wal; a Hohmann & Barnard company.
 - b. Heckmann Building Products, Inc.
 - c. Hohmann & Barnard, Inc.
 - d. Wire-Bond.
- C. Masonry-Joint Reinforcement, General: Ladder type complying with ASTM A951/A951M.
 - 1. Interior Walls: Hot-dip galvanized carbon steel.
 - 2. Wire Size for Side Rods: 0.148-inch diameter.
 - 3. Wire Size for Cross Rods: 0.148-inch diameter.
 - 4. Spacing of Cross Rods: Not more than 16 inches o.c.
 - 5. Provide in lengths of not less than 10 feet, with prefabricated corner units.

2.8 MISCELLANEOUS MASONRY ACCESSORIES

- A. Compressible Filler: Premolded filler strips complying with ASTM D1056, Grade 2A1; compressible up to 35 percent; of width and thickness indicated; formulated from neoprene or PVC.
- B. Bond-Breaker Strips: Asphalt-saturated felt complying with ASTM D226/D226M, Type I (No. 15 asphalt felt).

2.9 MORTAR AND GROUT MIXES

- A. General: Do not use admixtures, including pigments, air-entraining agents, accelerators, retarders, water-repellent agents, antifreeze compounds, or other admixtures unless otherwise indicated.
 - 1. Do not use calcium chloride in mortar or grout.
- B. Preblended, Dry Mortar Mix: Furnish dry mortar ingredients in form of a preblended mix. Measure quantities by weight to ensure accurate proportions, and thoroughly blend ingredients before delivering to Project site.
- C. Mortar for Unit Masonry: Comply with ASTM C270, Property Specification. Provide the following types of mortar for applications stated unless another type is indicated.
 - 1. For reinforced masonry, use Type S.
- D. Grout for Unit Masonry: Comply with ASTM C476.
 - 1. Use grout of type indicated or, if not otherwise indicated, of type (fine or coarse) that will comply with TMS 602/ACI 530.1/ASCE 6 for dimensions of grout spaces and pour height.
 - 2. Proportion grout in accordance with ASTM C476, Table 1 or paragraph 4.2.2 for specified 28-day compressive strength indicated, but not less than 3000 psi.
 - 3. Provide grout with a slump of 8 to 11 inches as measured according to ASTM C143/C143M.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
 - 1. For the record, prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.
 - 2. Verify that foundations are within tolerances specified.
 - 3. Verify that reinforcing dowels are properly placed.
 - 4. Verify that substrates are free of substances that would impair mortar bond.
- B. Before installation, examine rough-in and built-in construction for piping systems to verify actual locations of piping.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

- A. Build chases and recesses to accommodate items specified in this and other Sections.
- B. Leave openings for equipment to be installed before completing masonry. After installing equipment, complete masonry to match construction immediately adjacent to opening.
- C. Use full-size units without cutting if possible. If cutting is required to provide a continuous pattern or to fit adjoining construction, cut units with motor-driven saws; provide clean, sharp, unchipped edges. Allow units to dry before laying unless wetting of units is specified. Install cut units with cut surfaces and, where possible, cut edges concealed.

3.3 TOLERANCES

- A. Dimensions and Locations of Elements:
 - 1. For dimensions in cross section or elevation, do not vary by more than plus 1/2 inch or minus 1/4 inch.
 - 2. For location of elements in plan, do not vary from that indicated by more than plus or minus 1/2 inch.
 - 3. For location of elements in elevation, do not vary from that indicated by more than plus or minus 1/4 inch in a story height or 1/2 inch total.
- B. Lines and Levels:
 - 1. For bed joints and top surfaces of bearing walls, do not vary from level by more than 1/4 inch in 10 feet, or 1/2-inch maximum.
 - 2. For conspicuous horizontal lines, such as lintels, sills, parapets, and reveals, do not vary from level by more than 1/8 inch in 10 feet, 1/4 inch in 20 feet, or 1/2-inch maximum.
 - 3. For vertical lines and surfaces do not vary from plumb by more than 1/4 inch in 10 feet, 3/8 inch in 20 feet, or 1/2-inch maximum.
 - 4. For conspicuous vertical lines, such as external corners, door jambs, reveals, and expansion and control joints, do not vary from plumb by more than 1/8 inch in 10 feet, 1/4 inch in 20 feet, or 1/2-inch maximum.
 - 5. For lines and surfaces, do not vary from straight by more than 1/4 inch in 10 feet, 3/8 inch in 20 feet, or 1/2-inch maximum.
 - 6. For vertical alignment of exposed head joints, do not vary from plumb by more than 1/4 inch in 10 feet, or 1/2-inch maximum.
 - 7. For faces of adjacent exposed masonry units, do not vary from flush alignment by more than 1/16 inch.
- C. Joints:
 - 1. For bed joints, do not vary from thickness indicated by more than plus or minus 1/8 inch, with a maximum thickness limited to 1/2 inch.
 - 2. For exposed bed joints, do not vary from bed-joint thickness of adjacent courses by more than 1/8 inch.

3. For head and collar joints, do not vary from thickness indicated by more than plus 3/8 inch or minus 1/4 inch.
4. For exposed head joints, do not vary from thickness indicated by more than plus or minus 1/8 inch.

3.4 LAYING MASONRY WALLS

- A. Lay out walls in advance for accurate spacing of surface bond patterns with uniform joint thicknesses and for accurate location of openings, movement-type joints, returns, and offsets. Avoid using less-than-half-size units, particularly at corners, jambs, and, where possible, at other locations.
- B. Bond Pattern for Exposed Masonry: Unless otherwise indicated, lay exposed masonry in bond pattern indicated on Drawings; do not use units with less-than-nominal 4-inch horizontal face dimensions at corners or jambs.
- C. Lay concealed masonry with all units in a wythe in running bond or bonded by lapping not less than 4 inches. Bond and interlock each course of each wythe at corners. Do not use units with less-than-nominal 4-inch horizontal face dimensions at corners or jambs.
- D. Stopping and Resuming Work: Stop work by stepping back units in each course from those in course below; do not tooth. When resuming work, clean masonry surfaces that are to receive mortar, remove loose masonry units and mortar, and wet brick if required before laying fresh masonry.
- E. Built-in Work: As construction progresses, build in items specified in this and other Sections. Fill in solidly with masonry around built-in items.
- F. Fill space between steel frames and masonry solidly with mortar unless otherwise indicated.
- G. Fill cores in hollow CMUs with grout 24 inches under bearing plates, beams, lintels, posts, and similar items unless otherwise indicated.
- H. Fill cores in hollow CMUs with grout 24 inches (600 mm) under bearing plates, beams, lintels, posts, and similar items unless otherwise indicated.
- I. Build nonload-bearing interior partitions full height of story to underside of roof structure above unless otherwise indicated.
 1. Install compressible filler in joint between top of partition and underside of structure above.

3.5 MORTAR BEDDING AND JOINTING

- A. Lay hollow CMUs as follows:
 1. Bed face shells in mortar and make head joints of depth equal to bed joints.
 2. Bed webs in mortar in all courses of piers, columns, and pilasters.
 3. Bed webs in mortar in grouted masonry, including starting course on footings.
 4. Fully bed entire units, including areas under cells, at starting course on footings where cells are not grouted.
- B. Tool exposed joints slightly concave when thumbprint hard, using a jointer larger than joint thickness unless otherwise indicated.

3.6 MASONRY-CELL FILL

- A. Pour lightweight-aggregate fill into cavities to fill void spaces. Maintain inspection ports to show presence of fill at extremities of each pour area. Close the ports after filling has been confirmed. Limit the fall of fill to one story high, but not more than 20 feet.

3.7 MASONRY-JOINT REINFORCEMENT

- A. General: Install entire length of longitudinal side rods in mortar with a minimum cover of 5/8 inch on exterior side of walls, 1/2 inch elsewhere. Lap reinforcement a minimum of 6 inches.

1. Space reinforcement not more than 16 inches o.c.
 2. Space reinforcement not more than 8 inches o.c. in foundation walls and parapet walls.
 3. Provide reinforcement not more than 8 inches above and below wall openings and extending 12 inches beyond openings in addition to continuous reinforcement.
- B. Interrupt joint reinforcement at control and expansion joints unless otherwise indicated.
- C. Provide continuity at corners by using prefabricated L-shaped units.

3.8 CONTROL AND EXPANSION JOINTS

- A. General: Install control- and expansion-joint materials in unit masonry as masonry progresses. Do not allow materials to span control and expansion joints without provision to allow for in-plane wall or partition movement.
- B. Form control joints in concrete masonry as follows:
1. Install interlocking units designed for control joints. Install bond-breaker strips at joint. Keep head joints free and clear of mortar, or rake out joint for application of sealant.
 2. Install temporary foam-plastic filler in head joints, and remove filler when unit masonry is complete for application of sealant.

3.9 LINTELS

- A. Provide masonry lintels where shown and where openings of more than 12 inches for brick-size units and 24 inches for block-size units are shown without structural steel or other supporting lintels.
- B. Provide minimum bearing of 8 inches at each jamb unless otherwise indicated.

3.10 REINFORCED UNIT MASONRY

- A. Temporary Formwork and Shores: Construct formwork and shores as needed to support reinforced masonry elements during construction.
1. Construct formwork to provide shape, line, and dimensions of completed masonry as indicated. Make forms sufficiently tight to prevent leakage of mortar and grout. Brace, tie, and support forms to maintain position and shape during construction and curing of reinforced masonry.
 2. Do not remove forms and shores until reinforced masonry members have hardened sufficiently to carry their own weight and other loads that may be placed on them during construction.
- B. Placing Reinforcement: Comply with requirements in TMS 602/ACI 530.1/ASCE 6.
- C. Grouting: Do not place grout until entire height of masonry to be grouted has attained enough strength to resist grout pressure.
1. Comply with requirements in TMS 602/ACI 530.1/ASCE 6 for cleanouts and for grout placement, including minimum grout space and maximum pour height.
 2. Limit height of vertical grout pours to not more than 48 inches.

3.11 FIELD QUALITY CONTROL

- A. Testing and Inspecting: Owner will engage special inspectors to perform tests and inspections and prepare reports. Allow inspectors access to scaffolding and work areas as needed to perform tests and inspections. Retesting of materials that fail to comply with specified requirements shall be done at Contractor's expense.
- B. Inspections: Special inspections according to Level B in TMS 402/ACI 530/ASCE 5.
1. Begin masonry construction only after inspectors have verified proportions of site-prepared mortar.

2. Place grout only after inspectors have verified compliance of grout spaces and of grades, sizes, and locations of reinforcement.
 3. Place grout only after inspectors have verified proportions of site-prepared grout.
- C. Testing Prior to Construction: One set of tests.
 - D. Testing Frequency: One set of tests for each 5000 sq. ft. of wall area or portion thereof.
 - E. Concrete Masonry Unit Test: For each type of unit provided, according to ASTM C140 for compressive strength.
 - F. Mortar Aggregate Ratio Test (Proportion Specification): For each mix provided, according to ASTM C780.
 - G. Mortar Test (Property Specification): For each mix provided, according to ASTM C780. Test mortar for mortar air content and compressive strength.
 - H. Grout Test (Compressive Strength): For each mix provided, according to ASTM C1019.
 - I. Prism Test: For each type of construction provided, according to ASTM C1314 at 28 days.

3.12 REPAIRING, POINTING, AND CLEANING

- A. Remove and replace masonry units that are loose, chipped, broken, stained, or otherwise damaged or that do not match adjoining units. Install new units to match adjoining units; install in fresh mortar, pointed to eliminate evidence of replacement.
- B. Pointing: During the tooling of joints, enlarge voids and holes, except weep holes, and completely fill with mortar. Point up joints, including corners, openings, and adjacent construction, to provide a neat, uniform appearance. Prepare joints for sealant application, where indicated.
- C. In-Progress Cleaning: Clean unit masonry as work progresses by dry brushing to remove mortar fins and smears before tooling joints.
- D. Final Cleaning: After mortar is thoroughly set and cured, clean exposed masonry as follows:
 1. Remove large mortar particles by hand with wooden paddles and nonmetallic scrape hoes or chisels.
 2. Test cleaning methods on sample wall panel; leave one-half of panel uncleaned for comparison purposes. Obtain Architect's approval of sample cleaning before proceeding with cleaning of masonry.
 3. Protect adjacent stone and non-masonry surfaces from contact with cleaner by covering them with liquid strippable masking agent or polyethylene film and waterproof masking tape.
 4. Wet wall surfaces with water before applying cleaners; remove cleaners promptly by rinsing surfaces thoroughly with clear water.
 5. Clean concrete masonry by applicable cleaning methods indicated in NCMA TEK 8-4A.

3.13 MASONRY WASTE DISPOSAL

- A. Salvageable Materials: Unless otherwise indicated, excess masonry materials are Contractor's property. At completion of unit masonry work, remove from Project site.
- B. Masonry Waste Recycling: Return broken CMUs not used as fill to manufacturer for recycling.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 06 10 53
MISCELLANEOUS ROUGH CARPENTRY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Framing with dimension lumber.
 - 2. Framing with engineered wood products.
 - 3. Wood blocking and nailers.
- B. Related Requirements:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 2. Section 061600 "Sheathing" for sheathing, subflooring, and underlayment.

1.3 DEFINITIONS

- A. Boards or Strips: Lumber of less than 2 inches nominal size in least dimension.
- B. Dimension Lumber: Lumber of 2 inches nominal or greater size but less than 5 inches nominal size in least dimension.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.
 - 1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used and net amount of preservative retained.
 - 2. For products receiving a waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.
- B. Sustainable Design Submittals:
 - 1. Product Certificates: For regional materials, indicating location of material manufacturer and point of extraction, harvest, or recovery for each raw material. Include distance to Project and cost for each regional material.
 - 2. Chain-of-Custody Certificates: For certified wood products. Include statement of costs.
 - 3. Chain-of-Custody Qualification Data: For manufacturer and vendor. Product Data: For installation adhesives, indicating VOC content.
 - 4. Laboratory Test Reports: For installation adhesives, indicating compliance with requirements for low-emitting materials.

1.5 INFORMATIONAL SUBMITTALS

- A. Evaluation Reports: For the following, from ICC-ES:
 - 1. Preservative-treated wood.

2. Power-driven fasteners.
3. Post-installed anchors.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Stack lumber flat with spacers beneath and between each bundle to provide air circulation. Protect lumber from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

- A. Lumber: DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, provide lumber that complies with the applicable rules of any rules-writing agency certified by the ALSC Board of Review. Provide lumber graded by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.
 1. Factory mark each piece of lumber with grade stamp of grading agency.
 2. For exposed lumber indicated to receive a stained or natural finish, mark grade stamp on end or back of each piece or omit grade stamp and provide certificates of grade compliance issued by grading agency.
- B. Maximum Moisture Content of Lumber: 15 percent for 2-inch nominal thickness or less, 19 percent for more than 2-inch nominal thickness unless otherwise indicated.

2.2 WOOD-PRESERVATIVE-TREATED MATERIALS

- A. Preservative Treatment by Pressure Process: AWPA U1; Use Category UC2 for interior construction not in contact with ground, Use Category UC3b for exterior construction not in contact with ground, and Use Category UC4a for items in contact with ground.
 1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.
 2. For exposed items indicated to receive a stained or natural finish, chemical formulations shall not require incising, contain colorants, bleed through, or otherwise adversely affect finishes.
- B. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or does not comply with requirements for untreated material.
- C. Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board of Review.
 1. For exposed lumber indicated to receive a stained or natural finish, mark end or back of each piece or omit marking and provide certificates of treatment compliance issued by inspection agency.
- D. Application: Treat items indicated on Drawings, and the following:
 1. Wood framing and furring attached directly to the interior of below-grade exterior masonry or concrete walls.
- E. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Kiln-dry plywood after treatment to a maximum moisture content of 15 percent.
- F. For exposed items indicated to receive a stained or natural finish, chemical formulations shall not bleed through, contain colorants, or otherwise adversely affect finishes.
- G. Application: Treat items indicated on Drawings.

2.3 DIMENSION LUMBER FRAMING

- A. Other Framing: No. 2 grade of the following specie:

1. Douglas fir-larch; WCLIB or WWP.

2.4 ENGINEERED WOOD PRODUCTS

- A. Source Limitations: Obtain each type of engineered wood product from single source from a single manufacturer.
- B. Laminated-Veneer Lumber: Structural composite lumber made from wood veneers with grain primarily parallel to member lengths, evaluated and monitored according to ASTM D5456 and manufactured with an exterior-type adhesive complying with ASTM D2559.
 1. Extreme Fiber Stress in Bending, Edgewise: As indicated in General Structural Notes on drawings.
 2. Modulus of Elasticity, Edgewise: As indicated in General Structural Notes on drawings.
- C. Wood I-Joists: Prefabricated units, I-shaped in cross section, made with solid or structural composite lumber flanges and wood-based structural panel webs, let into and bonded to flanges. Comply with material requirements of and with structural capacities established and monitored according to ASTM D5055.
 1. Web Material: Either OSB or plywood, complying with DOC PS 1 or DOC PS 2, Exposure 1.
 2. Structural Properties: Depths and design values not less than those indicated.
 3. Comply with APA PRI-400. Factory mark I-joists with APA-EWS trademark indicating nominal joist depth, joist class, span ratings, mill identification, and compliance with APA-EWS standard.

2.5 MISCELLANEOUS LUMBER

- A. General: Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:
 1. Blocking.
 2. Furring.
- B. Dimension Lumber Items: Construction or No. 2 grade lumber of the following species:
 1. Western woods; WCLIB or WWP.
- C. For blocking and nailers used for attachment of other construction, select and cut lumber to eliminate knots and other defects that will interfere with attachment of other work.
- D. For furring strips for installing plywood or hardboard paneling, select boards with no knots capable of producing bent-over nails and damage to paneling.

2.6 FASTENERS

- A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.
 1. Where carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A153/A153M or of Type 304 stainless steel.
- B. Nails, Brads, and Staples: ASTM F1667.
- C. Power-Driven Fasteners: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.
- D. Post-Installed Anchors: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC01 as appropriate for the substrate.
 1. Material: Carbon-steel components, zinc plated to comply with ASTM B633, Class Fe/Zn 5.
 2. Material: Stainless steel with bolts and nuts complying with ASTM F593 and ASTM F594, Alloy Group 1 or 2.

2.7 MISCELLANEOUS MATERIALS

- A. Adhesives for Gluing Sleepers to Concrete or Masonry: Formulation complying with ASTM D3498 that is approved for use indicated by adhesive manufacturer.
 - 1. Adhesives shall have a VOC content of 70 g/L or less.
- B. Flexible Flashing: Composite, self-adhesive, flashing product consisting of a pliable, butyl rubber or rubberized-asphalt compound, bonded to a high-density polyethylene film, aluminum foil, or spunbonded polyolefin to produce an overall thickness of not less than 0.025 inch.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Framing Standard: Comply with AF&PA's WCD 1, "Details for Conventional Wood Frame Construction," unless otherwise indicated.
- B. Set carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit carpentry accurately to other construction. Locate nailers, blocking, and similar supports to comply with requirements for attaching other construction.
- C. Do not splice structural members between supports unless otherwise indicated.
- D. Provide blocking and framing as indicated and as required to support facing materials, fixtures, specialty items, and trim.
 - 1. Provide metal clips for fastening gypsum board or lath at corners and intersections where framing or blocking does not provide a surface for fastening edges of panels. Space clips not more than 16 inches o.c.
- E. Provide fire blocking in concealed cavities as indicated and as follows:
 - 1. Fire block concealed spaces behind combustible cornices and exterior trim at not more than 20 feet o.c.
- F. Sort and select lumber so that natural characteristics do not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.
- G. Comply with AWPA M4 for applying field treatment to cut surfaces of preservative-treated lumber.
 - 1. Use inorganic boron for items that are continuously protected from liquid water.
 - 2. Use copper naphthenate for items not continuously protected from liquid water.
- H. Where wood-preservative-treated lumber is installed adjacent to metal decking, install continuous flexible flashing separator between wood and metal decking.
- I. Securely attach carpentry work to substrate by anchoring and fastening as indicated, complying with the following:
 - 1. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code.
 - 2. ICC-ES evaluation report for fastener.
- J. Use steel common nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.

3.2 INSTALLATION OF CEILING JOIST FRAMING

- A. General: Install floor joists with crown edge up and support ends of each member with not less than 1-1/2 inches of bearing on wood, or 3 inches on masonry. Attach joists as follows:
 - 1. Where supported on wood members, by toe nailing or by using metal framing anchors.

- B. Provide collar beams (ties) as indicated or, if not indicated, provide 1-by-6-inch nominal-size boards between every third pair of rafters, but not more than 48 inches o.c. Locate below ridge member, at third point of rafter span. Cut ends to fit roof slope and nail to rafters.
- C. Provide special framing as indicated for eaves, overhangs, and similar conditions if any.

3.3 INSTALLATION OF WOOD BLOCKING AND NAILER

- A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.
- B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces unless otherwise indicated.
- C. Provide permanent grounds of dressed, pressure-preservative-treated, key-beveled lumber not less than 1-1/2 inches wide and of thickness required to bring face of ground to exact thickness of finish material. Remove temporary grounds when no longer required.

3.4 PROTECTION

- A. Protect wood that has been treated with inorganic boron (SBX) from weather. If, despite protection, inorganic boron-treated wood becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.
- B. Protect miscellaneous rough carpentry from weather. If, despite protection, miscellaneous rough carpentry becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 06 16 00 SHEATHING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Roof sheathing.
 - 2. Composite nail base insulated roof sheathing.
 - 3. Sheathing joint and penetration treatment.
- B. Related Requirements:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 2. Section 061053 "Miscellaneous Rough Carpentry" for roof framing members.

1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.
 - 1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated plywood complies with requirements. Indicate type of preservative used and net amount of preservative retained.
 - 2. For products receiving waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.
- B. Sustainable Design Submittals:
 - 1. Chain-of-Custody Certificates: For certified wood products. Include statement of costs.
 - 2. Chain-of-Custody Qualification Data: For manufacturer and vendor.:
 - 3. Product Data: For installation adhesives, indicating VOC content.
 - 4. Laboratory Test Reports: For installation adhesives, indicating compliance with requirements for low-emitting materials.
- C. Shop Drawings: For air-barrier and water-resistant glass-mat gypsum sheathing assemblies.
 - 1. Show locations and extent of sheathing, accessories, and assemblies specific to Project conditions.
 - 2. Include details for sheathing joints and cracks, counterflashing strips, penetrations, inside and outside corners, terminations, and tie-ins with adjoining construction.
 - 3. Include details of interfaces with other materials that form part of air barrier.

1.5 INFORMATIONAL SUBMITTALS

- A. Evaluation Reports: For the following, from ICC-ES:
 - 1. Wood-preservative-treated plywood.
- B. Field quality-control reports.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer of air-barrier and water-resistant glass-mat gypsum sheathing.
 - 1. Installer shall be licensed by ABAA according to ABAA's Quality Assurance Program and shall employ ABAA-certified installers and supervisors on Project.
- B. Testing Agency Qualifications:
 - 1. For testing agency providing classification marking for fire-retardant-treated material, an inspection agency acceptable to authorities having jurisdiction that periodically performs inspections to verify that the material bearing the classification marking is representative of the material tested.
 - 2. For testing and inspecting agency providing tests and inspections related to air-barrier and water-resistant glass-mat gypsum sheathing: an independent agency, qualified according to ASTM E329 for testing indicated, and certified by Air Barrier Association of America, Inc.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Stack panels flat with spacers beneath and between each bundle to provide air circulation. Protect sheathing from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD PANEL PRODUCTS

- A. Emissions: Products shall meet the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- B. Thickness: As needed to comply with requirements specified, but not less than thickness indicated.
- C. Factory mark panels to indicate compliance with applicable standard.

2.2 PRESERVATIVE-TREATED PLYWOOD

- A. Preservative Treatment by Pressure Process: AWPA U1; Use Category UC2 for interior construction not in contact with ground, Use Category UC3b for exterior construction not in contact with ground, and Use Category UC4a for items in contact with ground.
 - 1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.
- B. Mark plywood with appropriate classification marking of an inspection agency acceptable to authorities having jurisdiction.
- C. Application: Treat all plywood unless otherwise indicated.

2.3 ROOF SHEATHING

- A. Plywood Sheathing: Exposure 1 sheathing.
 - 1. Span Rating: Not less than 32/16.
 - 2. Nominal Thickness: Not less than 15/32 inch.

***** OR *****

- Oriented-Strand-Board Sheathing: DOC PS 2, Exposure 1 sheathing.
 - 3. Span Rating: Not less than 32/16.
 - 4. Nominal Thickness: Not less than 15/32 inch.

2.4 COMPOSITE NAIL BASE INSULATED ROOF SHEATHING

- A. Oriented-Strand-Board-Surfaced, Polyisocyanurate-Foam Sheathing: ASTM C1289, Type V with DOC PS 2, Exposure 1 oriented strand board on one face.
 - 1. Basis-of-Design Product: Subject to compliance with requirements, provide Rmax, Inc; ECOBASEci or a comparable product by one of the following:
 - a. Atlas Molded Products; a Division of Atlas Roofing Corporation.
 - b. Cornell Corporation.
 - c. Dow Chemical Company (The).
 - d. Hunter Panels.
 - e. Johns Manville; a Berkshire Hathaway company.
 - f. Approved substitution.
 - 2. Polyisocyanurate-Foam Thickness: 3 inches.
 - 3. Oriented-Strand-Board Nominal Thickness: 7/16 inch.

2.5 FASTENERS

- A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.
 - 1. For roof sheathing, provide fasteners with hot-dip zinc coating complying with ASTM A153/A153M or of Type 304 stainless steel.
- B. Nails, Brads, and Staples: ASTM F1667.
- C. Power-Driven Fasteners: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.
- D. Screws for Fastening Sheathing to Wood Framing: ASTM C1002.

2.6 MISCELLANEOUS MATERIALS

- A. Adhesives for Field Gluing Panels to Wood Framing: Formulation complying with APA AFG-01 that is approved for use with type of construction panel indicated by manufacturers of both adhesives and panels.
 - 1. Adhesive shall have a VOC content of 50 g/L or less.
 - 2. Adhesive shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Do not use materials with defects that impair quality of sheathing or pieces that are too small to use with minimum number of joints or optimum joint arrangement. Arrange joints so that pieces do not span between fewer than three support members.
- B. Cut panels at penetrations, edges, and other obstructions of work; fit tightly against abutting construction unless otherwise indicated.
- C. Securely attach to substrate by fastening as indicated, complying with the following:
 - 1. Table 2304.9.1, "Fastening Schedule," in the ICC's International Building Code.
 - 2. Table R602.3(1), "Fastener Schedule for Structural Members," and Table R602.3(2), "Alternate Attachments," in the ICC's International Residential Code for One- and Two-Family Dwellings.
 - 3. ICC-ES evaluation report for fastener.
- D. Use common wire nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections. Install fasteners without splitting wood.
- E. Coordinate roof sheathing installation with flashing and joint-sealant installation so these materials are installed in sequence and manner that prevent exterior moisture from passing through completed assembly.
- F. Coordinate sheathing installation with installation of materials installed over sheathing so sheathing is not exposed to precipitation or left exposed at end of the workday when rain is forecast.

3.2 COMPOSITE NAIL BASE INSULATED ROOF SHEATHING INSTALLATION

- A. General: Comply with applicable recommendations in Manufacturer's written instructions.
- B. Panel Supports: Provide level and square structural system to support roof panels. Provide adequate bracing of panels during erection. Remove debris from panel edge prior to attachment of plates.
- C. Panel Fastening: Connect panels to structure by construction adhesive and screws as required. Where screw fasteners are used, provide a minimum of 2" penetration into support. Join panels using plates. Apply adhesive and foam sealant to all joints, penetrations, cracks and voids to fill and seal, following manufacturer recommendations.
- D. Tape: Provide tape at joints between panels and at intersection of roof and wall.

3.3 WOOD STRUCTURAL PANEL INSTALLATION

- A. General: Comply with applicable recommendations in APA Form No. E30, "Engineered Wood Construction Guide," for types of structural-use panels and applications indicated.
- B. Fastening Methods: Fasten panels as indicated below:
 - 1. Roof Sheathing:
 - a. Nail or screw to wood framing.
 - b. Space panels 1/8 inch apart at edges and ends.

END OF SECTION

SECTION 06 64 00
PLASTIC PANELING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Plastic sheet paneling.
- B. Related Requirements:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 2. Section 042200 "Concrete Unit Masonry".

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Sustainable Design Submittals:
 - 1. Product Data: For adhesives, indicating VOC content.
 - 2. Laboratory Test Reports: For adhesives, indicating compliance with requirements for low-emitting materials.
 - 3. Product Data: For sealants, indicating VOC content.
 - 4. Laboratory Test Reports: For sealants, indicating compliance with requirements for low-emitting materials.
- C. Samples: For plastic paneling and trim accessories, in manufacturer's standard sizes.

1.4 PROJECT CONDITIONS

- A. Environmental Limitations: Do not deliver or install plastic paneling until spaces are enclosed and weathertight and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Source Limitations: Obtain plastic paneling and trim accessories from single manufacturer.

2.2 PLASTIC SHEET PANELING

- A. Glass-Fiber-Reinforced Plastic Paneling: Gelcoat-finished, glass-fiber-reinforced plastic panels complying with ASTM D5319.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Crane Composites, Inc.
 - b. Glasteel.

- c. Marlite.
 - d. Newcourt, Inc.
 - e. Nudo Products, Inc.
 - f. Parkland Plastics, Inc.
2. Surface-Burning Characteristics: As follows when tested by a qualified testing agency according to ASTM E84. Identify products with appropriate markings of applicable testing agency.
 - a. Flame-Spread Index: 200 or less.
 - b. Smoke-Developed Index: 450 or less.
 3. Nominal Thickness: Not less than 0.09 inch.
 4. Surface Finish: As selected by Architect from manufacturer's full range.
 5. Color: As selected by Architect from manufacturer's full range.

2.3 ACCESSORIES

- A. Trim Accessories: Manufacturer's standard two-piece, snap-on vinyl extrusions designed to retain and cover edges of panels. Provide division bars, inside corners, and caps as needed to conceal edges.
 1. Color: Match panels.
- B. Exposed Fasteners: Nylon drive rivets recommended by panel manufacturer.
- C. Concealed Mounting Splines: Continuous, H-shaped aluminum extrusions designed to fit into grooves routed in edges of factory-laminated panels and to be fastened to substrate.
- D. Adhesive: As recommended by plastic paneling manufacturer.
 1. Adhesives shall have a VOC content of 50 g/L or less.
- E. Sealant: Mildew-resistant, single-component, neutral-curing silicone sealant recommended by plastic paneling manufacturer and complying with requirements in Section 079200 "Joint Sealants."
 1. Sealant shall have a VOC content of 250 g/L or less.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean substrates of substances that could impair adhesive bond, including oil, grease, dirt, and dust.
- B. Condition panels by unpacking and placing in installation space before installation according to manufacturer's written recommendations.
- C. Lay out paneling before installing. Locate panel joints to provide equal panels at ends of walls not less than half the width of full panels.
 1. Mark plumb lines on substrate at panel joint locations for accurate installation.
 2. Locate panel joints to allow clearance at panel edges according to manufacturer's written instructions.

3.3 INSTALLATION

- A. Install plastic paneling according to manufacturer's written instructions.
- B. Install panels in a full spread of adhesive.

- C. Install panels with fasteners. Layout fastener locations and mark on face of panels so that fasteners are accurately aligned.
 - 1. Drill oversized fastener holes in panels and center fasteners in holes.
 - 2. Apply sealant to fastener holes before installing fasteners.
- D. Install factory-laminated panels using concealed mounting splines in panel joints.
- E. Install trim accessories with adhesive.
- F. Fill grooves in trim accessories with sealant before installing panels, and bed inside corner trim in a bead of sealant.
- G. Maintain uniform space between panels and wall fixtures. Fill space with sealant.
- H. Maintain uniform space between adjacent panels and between panels and floors, ceilings, and fixtures. Fill space with sealant.
- I. Remove excess sealant and smears as paneling is installed. Clean with solvent recommended by sealant manufacturer and then wipe with clean dry cloths until no residue remains.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 07 11 13
BITUMINOUS DAMPPROOFING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Cold-applied, emulsified-asphalt dampproofing for concrete shallow building foundations.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1.4 FIELD CONDITIONS

- A. Weather Limitations: Proceed with application only when existing and forecasted weather conditions permit dampproofing to be performed according to manufacturers' written instructions.
- B. Ventilation: Provide adequate ventilation during application of dampproofing in enclosed spaces. Maintain ventilation until dampproofing has cured.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

- A. Source Limitations: Obtain primary dampproofing materials and primers from single source from single manufacturer. Provide protection course and auxiliary materials recommended in writing by manufacturer of primary materials.
- B. VOC Content: Products shall comply with VOC content limits of authorities having jurisdiction unless otherwise required.

2.2 COLD-APPLIED, EMULSIFIED-ASPHALT DAMPPROOFING

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. BASF Construction Chemicals - Building Systems; Sonneborn Brand Products.
 - 2. Henry Company.
 - 3. Karnak Corporation.
 - 4. Koppers Inc.
 - 5. Meadows, W. R., Inc.
 - 6. Approved substitution.
- B. Trowel Coats: ASTM D 1227, Type II, Class 1.
- C. Fibered Brush and Spray Coats: ASTM D 1227, Type II, Class 1.
- D. Brush and Spray Coats: ASTM D 1227, Type III, Class 1.
- E. VOC Content: 30 g/L or less.

2.3 AUXILIARY MATERIALS

- A. General: Furnish auxiliary materials recommended in writing by dampproofing manufacturer for intended use and compatible with bituminous dampproofing.
- B. Emulsified-Asphalt Primer: ASTM D 1227, Type III, Class 1, except diluted with water as recommended in writing by manufacturer.
 - 1. Primer shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- C. Asphalt-Coated Glass Fabric: ASTM D 1668, Type I.
- D. Patching Compound: Epoxy or latex-modified repair mortar of type recommended in writing by dampproofing manufacturer.
- E. Protection Course: ASTM D 6506, 1/8-inch-thick, semirigid sheets of fiberglass or mineral-reinforced-asphaltic core, pressure laminated between two asphalt-saturated fibrous liners.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions with Applicator present, for compliance with requirements for surface smoothness, surface moisture, and other conditions affecting performance of bituminous dampproofing work.
 - 1. Test for surface moisture according to ASTM D 4263.
- B. Proceed with application only after substrate construction and penetrating work have been completed and unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Mask or otherwise protect adjoining exposed surfaces from being stained, spotted, or coated with dampproofing. Prevent dampproofing materials from entering and clogging weep holes and drains.
- B. Clean substrates of projections and substances detrimental to the dampproofing work; fill voids, seal joints, and remove bond breakers if any, as recommended in writing by prime material manufacturer.
- C. Apply patching compound to patch and fill tie holes, honeycombs, reveals, and other imperfections; cover with asphalt-coated glass fabric.

3.3 APPLICATION, GENERAL

- A. Comply with manufacturer's written instructions for dampproofing application, cure time between coats, and drying time before backfilling unless more stringent requirements are indicated.
 - 1. Apply dampproofing to provide continuous plane of protection.
 - 2. Apply additional coats if recommended in writing by manufacturer or to achieve a smooth surface and uninterrupted coverage.
- B. Where dampproofing footings and foundation walls, apply from finished-grade line to top of footing; extend over top of footing and down a minimum of 6 inches over outside face of footing.
 - 1. Extend dampproofing 12 inches onto intersecting walls and footings, but do not extend onto surfaces exposed to view when Project is completed.
 - 2. Install flashings and corner protection stripping at internal and external corners, changes in plane, construction joints, cracks, and where shown as "reinforced,"

by embedding an 8-inch-wide strip of asphalt-coated glass fabric in a heavy coat of dampproofing. Dampproofing coat for embedding fabric is in addition to other coats required.

3.4 COLD-APPLIED, EMULSIFIED-ASPHALT DAMPPROOFING

- A. Concrete Foundations: Apply two brush or spray coats at not less than 1.5 gal./100 sq. ft. for first coat and 1 gal./100 sq. ft. for second coat.

3.5 INSTALLATION OF PROTECTION COURSE

- A. Install protection course over completed-and-cured dampproofing. Comply with dampproofing-material and protection-course manufacturers' written instructions for attaching protection course.
 - 1. Support protection course over cured coating with spot application of adhesive type recommended in writing by protection-board manufacturer.
 - 2. Install protection course on same day of installation of dampproofing (while coating is tacky) to ensure adhesion.

3.6 CLEANING

- A. Clean spillage and soiling from adjacent construction using cleaning agents and procedures recommended in writing by manufacturer of affected construction.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 07 21 00
THERMAL INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Molded (expanded) polystyrene foam-plastic board insulation.
- B. Related Requirements:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 2. Section 061600 "Sheathing" for foam-plastic board sheathing installed directly over wood framing.
 - 3. Section 075419 "Polyvinyl-Chloride (PVC) Roofing" for insulation specified as part of roofing construction.
 - 4. Section 092900 "Gypsum Board" for sound attenuation blanket used as acoustic insulation.

1.3 ACTION SUBMITTALS

- A. Product Data: For the following:
 - 1. Molded (expanded) polystyrene foam-plastic board insulation.
 - 2. Glass-fiber blanket insulation.
 - 3. Mineral-wool blanket insulation.
 - 4. Loose-fill insulation.
- B. High Performance Submittals
 - 1. Product Data: For products having recycled content, documentation indicating percentages by weight of postconsumer and preconsumer recycled content. Include statement indicating costs for each product having recycled content.
 - 2. Product Certificates: For products and materials required to comply with requirements for regional materials indicating location and distance from Project of material manufacturer and point of extraction, harvest, or recovery for each raw material. Include statement indicating cost for each regional material and the fraction by weight that is considered regional.
 - 3. Product Data, including printed statement of VOC content, for products and materials required to be low-emitting. Products that apply may include, but are not limited to: adhesives, sealants, paints, & coatings.
 - 4. Product Test Reports for roof, indicating that materials comply with solar reflectance index requirement.

1.4 INFORMATIONAL SUBMITTALS

- A. Installer's Certification: Listing type, manufacturer, and R-value of insulation installed in each element of the building thermal envelope.
 - 1. For blown-in or sprayed fiberglass and cellulosic-fiber loose-fill insulation, indicate initial installed thickness, settled thickness, settled R-value, installed density, coverage area, and number of bags installed.
 - 2. Sign, date, and post the certification in a conspicuous location on Project site.
- B. Product Test Reports: For each product, for tests performed by a qualified testing agency.
- C. Research Reports: For foam-plastic insulation, from ICC-ES.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Protect insulation materials from physical damage and from deterioration due to moisture, soiling, and other sources. Store inside and in a dry location. Comply with manufacturer's written instructions for handling, storing, and protecting during installation.
- B. Protect foam-plastic board insulation as follows:
 - 1. Do not expose to sunlight except to necessary extent for period of installation and concealment.
 - 2. Protect against ignition at all times. Do not deliver foam-plastic board materials to Project site until just before installation time.
 - 3. Quickly complete installation and concealment of foam-plastic board insulation in each area of construction.

PART 2 - PRODUCTS

2.1 MOLDED (EXPANDED) POLYSTYRENE FOAM-PLASTIC BOARD INSULATION

- A. Molded (Expanded) Polystyrene Board Insulation, Type VIII: ASTM C578, Type VIII, 13-psi minimum compressive strength.
 - 1. Basis-of-Design Product: Subject to compliance with requirements, provide ACH Foam Technologies, Inc.; Foam-Control Plus+ or a comparable product by one of the following:
 - a. Atlas EPS; a Division of Atlas Roofing Corporation.
 - b. DiversiFoam Products.
 - c. Plymouth Foam, Inc.
 - 2. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches and wider in width.

2.2 INSULATION FASTENERS

- A. Anchor Adhesive: Product with demonstrated capability to bond insulation anchors securely to substrates without damaging insulation, fasteners, or substrates.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. AGM Industries, Inc.
 - b. Gemco.
 - c. Approved substitution.

2.3 ACCESSORIES

- A. Adhesive for Bonding Insulation: Product compatible with insulation and air and water barrier materials, and with demonstrated capability to bond insulation securely to substrates without damaging insulation and substrates.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Clean substrates of substances that are harmful to insulation, including removing projections capable of puncturing insulation or vapor retarders, or that interfere with insulation attachment.

3.2 INSTALLATION, GENERAL

- A. Comply with insulation manufacturer's written instructions applicable to products and applications.
- B. Install insulation that is undamaged, dry, and unsoiled and that has not been left exposed to ice, rain, or snow at any time.
- C. Install insulation with manufacturer's R-value label exposed after insulation is installed.
- D. Extend insulation to envelop entire area to be insulated. Fit tightly around obstructions and fill voids with insulation. Remove projections that interfere with placement.
- E. Provide sizes to fit applications and selected from manufacturer's standard thicknesses, widths, and lengths. Apply single layer of insulation units unless multiple layers are otherwise shown or required to make up total thickness or to achieve R-value.

3.3 INSTALLATION OF SLAB INSULATION

- A. On vertical slab edge and foundation surfaces, set insulation units using manufacturer's recommended adhesive according to manufacturer's written instructions.
 - 1. If not otherwise indicated, extend insulation a minimum of 36 inches below exterior grade line.
- B. On horizontal surfaces, loosely lay insulation units according to manufacturer's written instructions. Stagger end joints and tightly abut insulation units.
 - 1. If not otherwise indicated, extend insulation a minimum of 48 inches in from exterior walls.

3.4 INSTALLATION OF FOUNDATION WALL INSULATION

- A. Butt panels together for tight fit.
- B. Adhesive Installation: Install with adhesive or press into tacky waterproofing or dampproofing according to manufacturer's written instructions.

3.5 PROTECTION

- A. Protect installed insulation from damage due to harmful weather exposures, physical abuse, and other causes.
- B. Provide temporary coverings or enclosures where insulation is subject to abuse and cannot be concealed and protected by permanent construction immediately after installation.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 07 41 13.16
STANDING-SEAM METAL ROOF PANELS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Standing-seam metal roof panels.
- B. Related Sections:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 2. Section 061053 "Miscellaneous Rough Carpentry".
 - 3. Section 061600 "Sheathing".

1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
 - 1. Meet with Owner, Architect, Owner's insurer if applicable, metal panel Installer, metal panel manufacturer's representative, structural-support Installer, and installers whose work interfaces with or affects metal panels, including installers of roof accessories and roof-mounted equipment.
 - 2. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
 - 3. Review methods and procedures related to metal panel installation, including manufacturer's written instructions.
 - 4. Examine support conditions for compliance with requirements, including alignment between and attachment to structural members.
 - 5. Review structural loading limitations of deck during and after roofing.
 - 6. Review flashings, special details, drainage, penetrations, equipment curbs, and condition of other construction that affect metal panels.
 - 7. Review governing regulations and requirements for insurance, certificates, and tests and inspections if applicable.
 - 8. Review temporary protection requirements for metal panel systems during and after installation.
 - 9. Review procedures for repair of metal panels damaged after installation.
 - 10. Document proceedings, including corrective measures and actions required, and furnish copy of record to each participant.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of panel and accessory.
- B. Sustainable Design Submittals:
 - 1. Product Test Reports: For roof materials, documentation indicating that roof materials comply with Solar Reflectance Index requirements.

2. Product Data: For recycled content, indicating postconsumer and preconsumer recycled content and cost.
- C. Shop Drawings:
 1. Include fabrication and installation layouts of metal panels; details of edge conditions, joints, panel profiles, corners, anchorages, attachment system, trim, flashings, closures, and accessories; and special details.
 2. Accessories: Include details of the flashing, trim, and anchorage systems, at a scale of not less than 1-1/2 inches per 12 inches.
- D. Samples for Initial Selection: For each type of metal panel indicated with factory-applied color finishes.
 1. Include similar Samples of trim and accessories involving color selection.
- E. Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below.
 1. Metal Panels: 12 inches long by actual panel width. Include clips, fasteners, closures, and other metal panel accessories.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Test Reports: For each product, for tests performed by a qualified testing agency.
- C. Field quality-control reports.
- D. Sample Warranties: For special warranties.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For metal panels to include in maintenance manuals.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.
- B. UL-Certified, Portable Roll-Forming Equipment: UL-certified, portable roll-forming equipment capable of producing metal panels warranted by manufacturer to be the same as factory-formed products. Maintain UL certification of portable roll-forming equipment for duration of work.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Deliver components, metal panels, and other manufactured items so as not to be damaged or deformed. Package metal panels for protection during transportation and handling.
- B. Unload, store, and erect metal panels in a manner to prevent bending, warping, twisting, and surface damage.
- C. Stack metal panels horizontally on platforms or pallets, covered with suitable weathertight and ventilated covering. Store metal panels to ensure dryness, with positive slope for drainage of water. Do not store metal panels in contact with other materials that might cause staining, denting, or other surface damage.
- D. Retain strippable protective covering on metal panels during installation.
- E. Copper Panels: Wear gloves when handling to prevent fingerprints and soiling of surface.

1.9 FIELD CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit assembly of metal panels to be performed according to manufacturers' written instructions and warranty requirements.

1.10 COORDINATION

- A. Coordinate sizes and locations of roof curbs, equipment supports, and roof penetrations with actual equipment provided.
- B. Coordinate metal panel installation with rain drainage work, flashing, trim, construction of soffits, and other adjoining work to provide a leakproof, secure, and noncorrosive installation.

1.11 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of metal panel systems that fail in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Structural failures including rupturing, cracking, or puncturing.
 - b. Deterioration of metals and other materials beyond normal weathering.
 - 2. Warranty Period: Two years from date of Substantial Completion.
- B. Special Warranty on Panel Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.
 - 1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:
 - a. Color fading more than 5 Delta E units when tested according to ASTM D2244.
 - b. Chalking in excess of a No. 8 rating when tested according to ASTM D4214.
 - c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.
 - 2. Finish Warranty Period: 20 years from date of Substantial Completion.
- C. Special Weathertightness Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace standing-seam metal roof panel assemblies that fail to remain weathertight, including leaks, within specified warranty period.
 - 1. Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Energy Performance: Provide roof panels that are listed on the EPA/DOE's ENERGY STAR "Roof Product List" for low-slope roof products.
- B. Energy Performance: Provide roof panels according to one of the following when tested according to CRRC-1:
 - 1. Three-year, aged solar reflectance of not less than 0.55 and emissivity of not less than 0.75.
 - 2. Three-year, aged Solar Reflectance Index of not less than 64 when calculated according to ASTM E1980.
- C. Structural Performance: Provide metal panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E1592:
 - 1. Wind Loads: As indicated on Drawings.

- D. Air Infiltration: Air leakage of not more than 0.06 cfm/sq. ft. when tested according to ASTM E1680 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 1.57 lbf/sq. ft.
- E. Water Penetration under Static Pressure: No water penetration when tested according to ASTM E1646 or ASTM E331 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 2.86 lbf/sq. ft.
- F. Hydrostatic-Head Resistance: No water penetration when tested according to ASTM E2140.
- G. Wind-Uplift Resistance: Provide metal roof panel assemblies that comply with UL 580 for wind-uplift-resistance class indicated.
 - 1. Uplift Rating: UL 60.
- H. FM Global Listing: Provide metal roof panels and component materials that comply with requirements in FM Global 4471 as part of a panel roofing system and that are listed in FM Global's "Approval Guide" for Class 1 or noncombustible construction, as applicable. Identify materials with FM Global markings.
 - 1. Fire/Windstorm Classification: Class 1A-60.
- I. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 - 1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.

2.2 STANDING-SEAM METAL ROOF PANELS

- A. Provide factory-formed metal roof panels designed to be installed by lapping and interconnecting raised side edges of adjacent panels with joint type indicated and mechanically attaching panels to supports using concealed clips in side laps. Include clips, cleats, pressure plates, and accessories required for weathertight installation.
 - 1. Steel Panel Systems: Unless more stringent requirements are indicated, comply with ASTM E1514.
 - 2. Aluminum Panel Systems: Unless more stringent requirements are indicated, comply with ASTM E1637.
- B. Vertical-Rib, Snap-Joint, Standing-Seam Metal Roof Panels: Formed with vertical ribs at panel edges and a flat pan between ribs; designed for sequential installation by mechanically attaching panels to supports using concealed clips located under one side of panels, engaging opposite edge of adjacent panels, and snapping panels together.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. AEP Span; A BlueScope Steel Company.
 - b. Berridge Manufacturing Company.
 - c. Morin - A Kingspan Group Company.
 - d. PAC-CLAD; Petersen Aluminum Corporation; a Carlisle company.
 - 2. Metallic-Coated Steel Sheet: Zinc-coated (galvanized) steel sheet complying with ASTM A653/A653M, G90 coating designation, or aluminum-zinc alloy-coated steel sheet complying with ASTM A792/A792M, Class AZ50 coating designation; structural quality. Prepainted by the coil-coating process to comply with ASTM A755/A755M.
 - a. Nominal Thickness: 0.025 inch.
 - b. Exterior Finish: Finish shall be Kynar 500 or Hylar 5000 Fluorocarbon coating with a top side film thickness of 0.70 to 0.90 mil over a 0.25 to 0.3 mil prime coat to provide a total dry film thickness of 0.95 to 1.25 mil, to meet AAMA 621. Bottom side shall be coated with a primer with a dry film thickness of 0.25 mil. Finish shall conform to all tests for adhesions,

- flexibility and longevity as specified by Kynar 500 or Hylar 5000 finish supplier.
- c. Color: As selected by Architect from manufacturer's full range.
 3. Panel Coverage: 12 inches.
 4. Panel Height: 1.5 inches.

2.3 UNDERLAYMENT MATERIALS

- A. Self-Adhering, High-Temperature Underlayment: Provide self-adhering, cold-applied, sheet underlayment, a minimum of 30 mils thick, consisting of slip-resistant, polyethylene-film top surface laminated to a layer of butyl or SBS-modified asphalt adhesive, with release-paper backing. Provide primer when recommended by underlayment manufacturer.
 1. Thermal Stability: Stable after testing at 240 deg F; ASTM D1970.
 2. Low-Temperature Flexibility: Passes after testing at minus 20 deg F; ASTM D1970.
 3. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Carlisle WIP Products; a brand of Carlisle Construction Materials.
 - b. GCP Applied Technologies Inc.
 - c. Henry Company.
 - d. Owens Corning.

2.4 MISCELLANEOUS MATERIALS

- A. Miscellaneous Metal Subframing and Furring: ASTM C645; cold-formed, metallic-coated steel sheet, ASTM A653/A653M, G90 coating designation or ASTM A792/A792M, Class AZ50 coating designation unless otherwise indicated. Provide manufacturer's standard sections as required for support and alignment of metal panel system.
- B. Panel Accessories: Provide components required for a complete, weathertight panel system including trim, copings, fasciae, mullions, sills, corner units, clips, flashings, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal panels unless otherwise indicated.
 1. Closures: Provide closures at eaves and ridges, fabricated of same metal as metal panels.
 2. Backing Plates: Provide metal backing plates at panel end splices, fabricated from material recommended by manufacturer.
- C. Flashing and Trim: Provide flashing and trim formed from same material as metal panels as required to seal against weather and to provide finished appearance. Locations include, but are not limited to, eaves, rakes, corners, bases, framed openings, ridges, fasciae, and fillers. Finish flashing and trim with same finish system as adjacent metal panels.
- D. Panel Fasteners: Self-tapping screws designed to withstand design loads.
- E. Panel Sealants: Provide sealant type recommended by manufacturer that are compatible with panel materials, are nonstaining, and do not damage panel finish.
 1. Sealant Tape: Pressure-sensitive, 100 percent solids, gray polyisobutylene compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape 1/2 inch wide and 1/8 inch thick.
 2. Joint Sealant: ASTM C920; elastomeric polyurethane or silicone sealant; of type, grade, class, and use classifications required to seal joints in metal panels and remain weathertight; and as recommended in writing by metal panel manufacturer.
 3. Butyl-Rubber-Based, Solvent-Release Sealant: ASTM C1311.

2.5 FABRICATION

- A. Fabricate and finish metal panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.
- B. Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of panel.
- C. Fabricate metal panel joints with factory-installed captive gaskets or separator strips that provide a weathertight seal and prevent metal-to-metal contact, and that minimize noise from movements.
- D. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's recommendations and recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, metal, and other characteristics of item indicated.
 - 1. Form exposed sheet metal accessories that are without excessive oil canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.
 - 2. Seams for Other Than Aluminum: Fabricate nonmoving seams in accessories with flat-lock seams. Tin edges to be seamed, form seams, and solder.
 - 3. Sealed Joints: Form nonexpansion, but movable, joints in metal to accommodate sealant and to comply with SMACNA standards.
 - 4. Conceal fasteners and expansion provisions where possible. Exposed fasteners are not allowed on faces of accessories exposed to view.
 - 5. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal recommended in writing by metal panel manufacturer.
 - a. Size: As recommended by SMACNA's "Architectural Sheet Metal Manual" or metal panel manufacturer for application, but not less than thickness of metal being secured.

2.6 FINISHES

- A. Protect mechanical and painted finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in same piece are unacceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.
- C. Steel Panels and Accessories:
 - 1. Kynar 500 or Hylar 5000 Fluorocarbon: Top side film thickness of 0.70 to 0.90 mil over a 0.25 to 0.3 mil prime coat to provide a total dry film thickness of 0.95 to 1.25 mil, to meet AAMA 621. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, metal panel supports, and other conditions affecting performance of the Work.
 - 1. Examine primary and secondary roof framing to verify that rafters, purlins, angles, channels, and other structural panel support members and anchorages

- have been installed within alignment tolerances required by metal roof panel manufacturer.
2. Examine solid roof sheathing to verify that sheathing joints are supported by framing or blocking and that installation is within flatness tolerances required by metal roof panel manufacturer.
 - a. Verify that air- or water-resistive barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.
 - B. Examine roughing-in for components and systems penetrating metal panels to verify actual locations of penetrations relative to seam locations of metal panels before installation.
 - C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Miscellaneous Supports: Install subframing, furring, and other miscellaneous panel support members and anchorages according to ASTM C754 and metal panel manufacturer's written recommendations.

3.3 INSTALLATION OF UNDERLAYMENT

- A. Self-Adhering Sheet Underlayment: Apply primer if required by manufacturer. Comply with temperature restrictions of underlayment manufacturer for installation. Apply at locations indicated below, wrinkle free, in shingle fashion to shed water, and with end laps of not less than 6 inches staggered 24 inches between courses. Overlap side edges not less than 3-1/2 inches. Roll laps with roller. Cover underlayment within 14 days.
 1. Apply over the entire roof surface to receive Standing-Seam Metal Roof.
- B. Flashings: Install flashings to cover underlayment to comply with requirements specified in Section 076200 "Sheet Metal Flashing and Trim."

3.4 INSTALLATION OF STANDING SEAM METAL ROOF PANELS

- A. Install metal panels according to manufacturer's written instructions in orientation, sizes, and locations indicated. Install panels perpendicular to supports unless otherwise indicated. Anchor metal panels and other components of the Work securely in place, with provisions for thermal and structural movement.
 1. Shim or otherwise plumb substrates receiving metal panels.
 2. Flash and seal metal panels at perimeter of all openings. Fasten with self-tapping screws. Do not begin installation until air- or water-resistive barriers and flashings that will be concealed by metal panels are installed.
 3. **Install screw fasteners in predrilled holes to fasten through Composite Nail Base Insulated Roof Sheathing to roof framing members.**
 4. Locate and space fastenings in uniform vertical and horizontal alignment.
 5. Install flashing and trim as metal panel work proceeds.
 6. Locate panel splices over, but not attached to, structural supports. Stagger panel splices and end laps to avoid a four-panel lap splice condition.
 7. Align bottoms of metal panels and fasten with blind rivets, bolts, or self-tapping screws. Fasten flashings and trim around openings and similar elements with self-tapping screws.
 8. Provide weathertight escutcheons for pipe- and conduit-penetrating panels.
- B. Fasteners:
 1. Steel Panels: Use stainless steel fasteners for surfaces exposed to the exterior; use galvanized-steel fasteners for surfaces exposed to the interior.
- C. Metal Protection: Where dissimilar metals contact each other or corrosive substrates, protect against galvanic action as recommended in writing by metal panel manufacturer.

- D. Clipless Metal Panel Installation: Fasten metal panels to supports with screw fasteners at each lapped joint at location and spacing recommended by manufacturer.
- E. Accessory Installation: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.
 - 1. Install components required for a complete metal panel system including trim, copings, corners, seam covers, flashings, sealants, gaskets, fillers, closure strips, and similar items. Provide types indicated by metal roof panel manufacturers; or, if not indicated, types recommended by metal roof panel manufacturer.
- F. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that will be permanently watertight and weather resistant.
 - 1. Install exposed flashing and trim that is without buckling and tool marks, and that is true to line and levels indicated, with exposed edges folded back to form hems. Install sheet metal flashing and trim to fit substrates and achieve waterproof and weather-resistant performance.
 - 2. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at a maximum of 10 feet with no joints allowed within 24 inches of corner or intersection. Where lapped expansion provisions cannot be used or would not be sufficiently weather resistant and waterproof, form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with mastic sealant (concealed within joints).
- G. Pipe Flashing: Form flashing around pipe penetration and metal roof panels. Fasten and seal to metal roof panels as recommended by manufacturer.

3.5 ERECTION TOLERANCES

- A. Installation Tolerances: Shim and align metal panel units within installed tolerance of 1/4 inch in 20 feet on slope and location lines as indicated and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.

3.6 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect metal roof panel installation, including accessories. Report results in writing.
- B. Remove and replace applications of metal roof panels where tests and inspections indicate that they do not comply with specified requirements.
- C. Additional tests and inspections, at Contractor's expense, are performed to determine compliance of replaced or additional work with specified requirements.
- D. Prepare test and inspection reports.

3.7 CLEANING AND PROTECTION

- A. Remove temporary protective coverings and strippable films, if any, as metal panels are installed, unless otherwise indicated in manufacturer's written installation instructions. On completion of metal panel installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.
- B. Replace metal panels that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION

SECTION 07 62 00
SHEET METAL FLASHING AND TRIM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Formed low-slope roof sheet metal fabrications.
 - 2. Formed wall sheet metal fabrications.
 - 3. Formed equipment support flashing.
- B. Related Requirements:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 2. Section 061053 "Miscellaneous Rough Carpentry" for wood framing, nailers, and blocking.
 - 3. Section 074113.16 "Standing-Seam Metal Roof Panels" for materials and installation of manufactured sheet metal flashing and trim.
 - 4. Section 079200 "Joint Sealants".

1.3 COORDINATION

- A. Coordinate sheet metal flashing and trim layout and seams with sizes and locations of penetrations to be flashed, and joints and seams in adjacent materials.
- B. Coordinate sheet metal flashing and trim installation with adjoining roofing and wall materials, joints, and seams to provide leakproof, secure, and noncorrosive installation.

1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
 - 1. Review construction schedule. Verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
 - 2. Review special roof details, roof drainage, roof-penetration flashing, equipment curbs, and condition of other construction that affect sheet metal flashing and trim.
 - 3. Review requirements for insurance and certificates if applicable.
 - 4. Review sheet metal flashing observation and repair procedures after flashing installation.

1.5 ACTION SUBMITTALS

- A. Product Data: For each of the following
 - 1. Underlayment materials.
 - 2. Elastomeric sealant.
 - 3. Butyl sealant.
 - 4. Epoxy seam sealer.
- B. Sustainable Design Submittals:
 - 1. Product Data: For recycled content, indicating postconsumer and preconsumer recycled content and cost.

- C. Shop Drawings: For sheet metal flashing and trim.
 - 1. Include plans, elevations, sections, and attachment details.
 - 2. Detail fabrication and installation layouts, and keyed details. Distinguish between shop- and field-assembled Work.
 - 3. Include identification of material, thickness, weight, and finish for each item and location in Project.
 - 4. Include details for forming, including profiles, shapes, seams, and dimensions.
 - 5. Include details for joining, supporting, and securing, including layout and spacing of fasteners, cleats, clips, and other attachments. Include pattern of seams.
 - 6. Include details of termination points and assemblies.
 - 7. Include details of roof-penetration flashing.
 - 8. Include details of edge conditions, including eaves, ridges, valleys, rakes, crickets, flashings, and counterflashings.
 - 9. Include details of special conditions.
 - 10. Include details of connections to adjoining work.
 - 11. Detail formed flashing and trim at scale of not less than 1-1/2 inches per 12 inches.
- D. Samples: For each exposed product and for each color and texture specified, 12 inches long by actual width.
- E. Samples for Initial Selection: For each type of sheet metal and accessory indicated with factory-applied finishes.
- F. Samples for Verification: For each type of exposed finish.
 - 1. Sheet Metal Flashing: 12 inches long by actual width of unit, including finished seam and in required profile. Include fasteners, cleats, clips, closures, and other attachments.
 - 2. Trim, Metal Closures, Expansion Joints, Joint Intersections, and Miscellaneous Fabrications: 12 inches long and in required profile. Include fasteners and other exposed accessories.
 - 3. Unit-Type Accessories and Miscellaneous Materials: Full-size Sample.
 - 4. Anodized Aluminum Samples: Samples to show full range to be expected for each color required.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For fabricator.
- B. Product Certificates: For each type of coping and roof edge flashing that is ANSI/SPRI/FM 4435/ES-1 tested and FM Approvals approved.
- C. Product Test Reports: For each product, for tests performed by a qualified testing agency.
- D. Evaluation Reports: For copings and roof edge flashing, from ICC-ES showing compliance with ANSI/SPRI/FM 4435/ES-1.
- E. Sample Warranty: For special warranty.

1.7 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For sheet metal flashing and trim, and its accessories, to include in maintenance manuals.
- B. Special warranty.

1.8 QUALITY ASSURANCE

- A. Fabricator Qualifications: Employs skilled workers who custom fabricate sheet metal flashing and trim similar to that required for this Project and whose products have a record of successful in-service performance.

1. For copings and roof edge flashings that are ANSI/SPRI/FM 4435/ES-1 tested and FM Approvals approved, shop shall be listed as able to fabricate required details as tested and approved.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Do not store sheet metal flashing and trim materials in contact with other materials that might cause staining, denting, or other surface damage.
 1. Store sheet metal flashing and trim materials away from uncured concrete and masonry.
 2. Protect stored sheet metal flashing and trim from contact with water.
- B. Protect strippable protective covering on sheet metal flashing and trim from exposure to sunlight and high humidity, except to extent necessary for period of sheet metal flashing and trim installation.

1.10 WARRANTY

- A. Special Warranty on Finishes: Manufacturer agrees to repair finish or replace sheet metal flashing and trim that shows evidence of deterioration of factory-applied finishes within specified warranty period.
 1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:
 - a. Color fading more than 5 Delta E units when tested in accordance with ASTM D2244.
 - b. Chalking in excess of a No. 8 rating when tested in accordance with ASTM D4214.
 - c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.
 2. Finish Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Sheet metal flashing and trim assemblies, including cleats, anchors, and fasteners, shall withstand wind loads, structural movement, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Completed sheet metal flashing and trim shall not rattle, leak, or loosen, and shall remain watertight.
- B. Sheet Metal Standard for Flashing and Trim: Comply with NRCA's "The NRCA Roofing Manual: Architectural Metal Flashing, Condensation and Air Leakage Control, and Reroofing" and SMACNA's "Architectural Sheet Metal Manual" requirements for dimensions and profiles shown unless more stringent requirements are indicated.
- C. SPRI Wind Design Standard: Manufacture and install copings tested in accordance with ANSI/SPRI/FM 4435/ES-1 and capable of resisting the following design pressure:
 1. Design Pressure: As indicated on Drawings.
- D. FM Approvals Listing: Manufacture and install copings that are listed in FM Approvals' "RoofNav" and approved for windstorm classification, Class 1-90. Identify materials with name of fabricator and design approved by FM Approvals.
- E. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes to prevent buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 SHEET METALS

- A. Protect mechanical and other finishes on exposed surfaces from damage by applying strippable, temporary protective film before shipping.
- A. Metallic-Coated Steel Sheet: Provide zinc-coated (galvanized) steel sheet in accordance with ASTM A653/A653M, G90 coating designation; prepainted by coil-coating process to comply with ASTM A755/A755M.
 - 1. Surface: Smooth, flat and with manufacturer's standard clear acrylic coating on both sides.
 - 2. Exposed Coil-Coated Finish:
 - a. Two-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent polyvinylidene fluoride (PVDF) resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
 - 3. Color: As selected by Architect from manufacturer's full range.
 - 4. Concealed Finish: Pretreat with manufacturer's standard white or light-colored acrylic or polyester backer finish, consisting of prime coat and wash coat with minimum total dry film thickness of 0.5 mil.

2.3 UNDERLAYMENT MATERIALS

- A. Self-Adhering, High-Temperature Sheet Underlayment: Minimum 30 mils thick, consisting of a slip-resistant polyethylene- or polypropylene-film top surface laminated to a layer of butyl- or SBS-modified asphalt adhesive, with release-paper backing; specifically designed to withstand high metal temperatures beneath metal roofing. Provide primer in accordance with underlayment manufacturer's written instructions.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Carlisle WIP Products; a brand of Carlisle Construction Materials.
 - b. GCP Applied Technologies Inc.
 - c. Henry Company.
 - d. Owens Corning.
 - e. Protecto Wrap Company.
 - 2. Source Limitations: Obtain underlayment from single source from single manufacturer.
 - 3. Low-Temperature Flexibility: ASTM D1970/D1970M; passes after testing at minus 20 deg F or lower.
- B. Slip Sheet: Rosin-sized building paper, 3 lb/100 sq. ft. minimum.

2.4 MISCELLANEOUS MATERIALS

- A. Provide materials and types of fasteners, protective coatings, sealants, and other miscellaneous items as required for complete sheet metal flashing and trim installation and as recommended by manufacturer of primary sheet metal or manufactured item unless otherwise indicated.
- B. Fasteners: Wood screws, annular threaded nails, self-tapping screws, self-locking rivets and bolts, and other suitable fasteners designed to withstand design loads and recommended by manufacturer of primary sheet metal or manufactured item.
 - 1. General: Blind fasteners or self-drilling screws, gasketed, with hex-washer head.
 - a. Exposed Fasteners: Heads matching color of sheet metal using plastic caps or factory-applied coating. Provide metal-backed EPDM or PVC sealing washers under heads of exposed fasteners bearing on weather side of metal.
 - b. Blind Fasteners: High-strength aluminum or stainless steel rivets suitable for metal being fastened.

- c. Spikes and Ferrules: Same material as gutter; with spike with ferrule matching internal gutter width.
- 2. Fasteners for Aluminum Sheet: Aluminum or Series 300 stainless steel.
- 3. Fasteners for Aluminum-Zinc Alloy-Coated Steel Sheet: Series 300 stainless steel or hot-dip galvanized steel in accordance with ASTM A153/A153M or ASTM F2329.
- 4. Fasteners for Zinc Sheet: Series 300 stainless steel or hot-dip galvanized steel in accordance with ASTM A153/A153M or ASTM F2329.
- C. Sealant Tape: Pressure-sensitive, 100 percent solids, polyisobutylene compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape 1/2 inch wide and 1/8 inch thick.
- D. Elastomeric Sealant: ASTM C920, elastomeric silicone polymer sealant; of type, grade, class, and use classifications required to seal joints in sheet metal flashing and trim and remain watertight.
- E. Butyl Sealant: ASTM C1311, single-component, solvent-release butyl rubber sealant; polyisobutylene plasticized; heavy bodied for hooked-type expansion joints with limited movement.

2.5 FABRICATION, GENERAL

- A. Custom fabricate sheet metal flashing and trim to comply with details indicated and recommendations in cited sheet metal standard that apply to design, dimensions, geometry, metal thickness, and other characteristics of item required.
 - 1. Fabricate sheet metal flashing and trim in shop to greatest extent possible.
 - 2. Fabricate sheet metal flashing and trim in thickness or weight needed to comply with performance requirements, but not less than that specified for each application and metal.
 - 3. Verify shapes and dimensions of surfaces to be covered and obtain field measurements for accurate fit before shop fabrication.
 - 4. Form sheet metal flashing and trim to fit substrates without excessive oil-canning, buckling, and tool marks; true to line, levels, and slopes; and with exposed edges folded back to form hems.
 - 5. Conceal fasteners and expansion provisions where possible. Do not use exposed fasteners on faces exposed to view.
- B. Fabrication Tolerances:
 - 1. Fabricate sheet metal flashing and trim that is capable of installation to a tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.
 - 2. Fabricate sheet metal flashing and trim that is capable of installation to tolerances specified.
- C. Expansion Provisions: Form metal for thermal expansion of exposed flashing and trim.
 - 1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with butyl sealant concealed within joints.
 - 2. Use lapped expansion joints only where indicated on Drawings.
- D. Sealant Joints: Where movable, nonexpansion-type joints are required, form metal in accordance with cited sheet metal standard to provide for proper installation of elastomeric sealant.
- E. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal.
- F. Seams:
 - 1. Fabricate nonmoving seams with flat-lock seams. Form seams and seal with elastomeric sealant unless otherwise recommended by sealant manufacturer for intended use.
 - 2. Seams for Aluminum: Fabricate nonmoving seams with flat-lock seams. Form seams and seal with epoxy seam sealer.

- G. Do not use graphite pencils to mark metal surfaces.

2.6 LOW-SLOPE ROOF SHEET METAL FABRICATIONS

- A. Base Flashing: Shop fabricate interior and exterior corners. Fabricate from the following materials:
 - 1. Aluminum: 0.040 inch thick.
 - 2. Aluminum-Zinc Alloy-Coated Steel: 0.028 inch thick.
- B. Counterflashing: Shop fabricate interior and exterior corners. Fabricate from the following materials:
 - 1. Aluminum: 0.032 inch thick.
 - 2. Aluminum-Zinc Alloy-Coated Steel: 0.022 inch thick.
- C. Flashing Receivers: Fabricate from the following materials:
 - 1. Aluminum: 0.032 inch thick.
 - 2. Aluminum-Zinc Alloy-Coated Steel: 0.022 inch thick.
- D. Roof-Penetration Flashing: Fabricate from the following materials:
 - 1. Stainless Steel: 0.0188 inch thick.
 - 2. Aluminum-Zinc Alloy-Coated Steel: 0.028 inch thick.

2.7 WALL SHEET METAL FABRICATIONS

- A. Through-Wall Flashing: Fabricate continuous flashings in minimum 96-inch-long, but not exceeding 12-foot-long, sections, under copings, and at shelf angles. Fabricate discontinuous lintel, sill, and similar flashings to extend 6 inches beyond each side of wall openings; and form with 2-inch-high, end dams. Fabricate from the following materials:
 - 1. Stainless Steel: 0.0156 inch thick.
 - 2. Zinc-Tin Alloy-Coated Copper: 16 oz./sq. ft..
- B. Opening Flashings in Frame Construction: Fabricate head, sill, and similar flashings to extend 4 inches beyond wall openings. Form head and sill flashing with 2-inch-high, end dams. Fabricate from the following materials:
 - 1. Aluminum: 0.032 inch thick.
 - 2. Aluminum-Zinc Alloy-Coated Steel: 0.022 inch thick.

2.8 MISCELLANEOUS SHEET METAL FABRICATIONS

- A. Equipment Support Flashing: Fabricate from one of the following materials:
 - 1. Stainless Steel: 0.0188 inch thick.
 - 2. Galvanized Steel: 0.028 inch thick.
 - 3. Aluminum-Zinc Alloy-Coated Steel: 0.028 inch thick.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with installer present, for compliance with requirements for installation tolerances, substrate, and other conditions affecting performance of the Work.
 - 1. Verify compliance with requirements for installation tolerances of substrates.
 - 2. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.
 - 3. Verify that air- or water-resistant barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF UNDERLAYMENT

- A. Synthetic Underlayment: Install synthetic underlayment, wrinkle free, in accordance with manufacturers' written instructions, and using adhesive where possible to minimize use of mechanical fasteners under sheet metal.
 - 1. Lap horizontal joints not less than 4 inches.
 - 2. Lap end joints not less than 12 inches.
- B. Self-Adhering, High-Temperature Sheet Underlayment:
 - 1. Install self-adhering, high-temperature sheet underlayment; wrinkle free.
 - 2. Prime substrate if recommended by underlayment manufacturer.
 - 3. Comply with temperature restrictions of underlayment manufacturer for installation; use primer for installing underlayment at low temperatures.
 - 4. Apply in shingle fashion to shed water, with end laps of not less than 6 inches staggered 24 inches between courses.
 - 5. Overlap side edges not less than 3-1/2 inches. Roll laps and edges with roller.
 - 6. Roll laps and edges with roller.
 - 7. Cover underlayment within 14 days.
- C. Install slip sheet, wrinkle free, directly on substrate before installing sheet metal flashing and trim.
 - 1. Install in shingle fashion to shed water.
 - 2. Lapp joints not less than 4 inches.

3.3 INSTALLATION, GENERAL

- A. Install sheet metal flashing and trim to comply with details indicated and recommendations of cited sheet metal standard that apply to installation characteristics required unless otherwise indicated on Drawings.
 - 1. Install fasteners, protective coatings, separators, sealants, and other miscellaneous items as required to complete sheet metal flashing and trim system.
 - 2. Install sheet metal flashing and trim true to line, levels, and slopes. Provide uniform, neat seams with minimum exposure of sealant.
 - 3. Anchor sheet metal flashing and trim and other components of the Work securely in place, with provisions for thermal and structural movement.
 - 4. Install sheet metal flashing and trim to fit substrates and to result in watertight performance.
 - 5. Install continuous cleats with fasteners spaced not more than 12 inches o.c.
 - 6. Space individual cleats not more than 12 inches apart. Attach each cleat with at least two fasteners. Bend tabs over fasteners.
 - 7. Install exposed sheet metal flashing and trim with limited oil-canning, and free of buckling and tool marks.
 - 8. Do not field cut sheet metal flashing and trim by torch.
 - 9. Do not use graphite pencils to mark metal surfaces.
- B. Metal Protection: Where dissimilar metals contact each other, or where metal contacts pressure-treated wood or other corrosive substrates, protect against galvanic action or corrosion by painting contact surfaces with bituminous coating or by other permanent separation as recommended by sheet metal manufacturer or cited sheet metal standard.
 - 1. Coat concealed side of uncoated-aluminum sheet metal flashing and trim with bituminous coating where flashing and trim contact wood, ferrous metal, or cementitious construction.
 - 2. Underlayment: Where installing sheet metal flashing and trim directly on cementitious or wood substrates, install underlayment and cover with slip sheet.
- C. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim.
 - 1. Space movement joints at maximum of 10 feet with no joints within 24 inches of corner or intersection.

2. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with sealant concealed within joints.
3. Use lapped expansion joints only where indicated on Drawings.
- D. Fasteners: Use fastener sizes that penetrate substrate not less than recommended by fastener manufacturer to achieve maximum pull-out resistance.
- E. Conceal fasteners and expansion provisions where possible in exposed work and locate to minimize possibility of leakage. Cover and seal fasteners and anchors as required for a tight installation.
- F. Seal joints as required for watertight construction.
 1. Use sealant-filled joints unless otherwise indicated.
 - a. Embed hooked flanges of joint members not less than 1 inch into sealant.
 - b. Form joints to completely conceal sealant.
 - c. When ambient temperature at time of installation is between 40 and 70 deg F, set joint members for 50 percent movement each way.
 - d. Adjust setting proportionately for installation at higher ambient temperatures.
 - 1) Do not install sealant-type joints at temperatures below 40 deg F.
 2. Prepare joints and apply sealants to comply with requirements in Section 079200 "Joint Sealants."

3.4 INSTALLATION OF ROOF FLASHINGS

- A. Install sheet metal flashing and trim to comply with performance requirements and cited sheet metal standard.
 1. Provide concealed fasteners where possible, and set units true to line, levels, and slopes.
 2. Install work with laps, joints, and seams that are permanently watertight and weather resistant.
- B. Counterflashing: Coordinate installation of counterflashing with installation of base flashing.
 1. Extend counterflashing 4 inches over base flashing.
 2. Lap counterflashing joints minimum of 4 inches.
 3. Secure in waterproof manner by means of anchor and washer spaced at 12 inches o.c. along perimeter and 6 inches o.c. at corners areas unless otherwise indicated.
- C. Roof-Penetration Flashing: Coordinate installation of roof-penetration flashing with installation of roofing and other items penetrating roof. Seal with elastomeric sealant and clamp flashing to pipes that penetrate roof.

3.5 INSTALLATION OF WALL FLASHINGS

- A. Install sheet metal wall flashing to intercept and exclude penetrating moisture in accordance with cited sheet metal standard unless otherwise indicated. Coordinate installation of wall flashing with installation of wall-opening components such as windows, doors, and louvers.
- B. Opening Flashings in Frame Construction: Install continuous head, sill, and similar flashings to extend 4 inches beyond wall openings.

3.6 INSTALLATION TOLERANCES

- A. Installation Tolerances: Shim and align sheet metal flashing and trim within installed tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.

3.7 CLEANING

- A. Clean exposed metal surfaces of substances that interfere with uniform oxidation and weathering.
- B. Clean and neutralize flux materials. Clean off excess solder.
- C. Clean off excess sealants.

3.8 PROTECTION

- A. Remove temporary protective coverings and strippable films as sheet metal flashing and trim are installed unless otherwise indicated in manufacturer's written installation instructions.
- B. On completion of sheet metal flashing and trim installation, remove unused materials and clean finished surfaces as recommended in writing by sheet metal flashing and trim manufacturer.
- C. Maintain sheet metal flashing and trim in clean condition during construction.
- D. Replace sheet metal flashing and trim that have been damaged or that have deteriorated beyond successful repair by finish touchup or similar minor repair procedures, as determined by Architect.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 07 92 00 JOINT SEALANTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Silicone joint sealants.
 - 2. Urethane joint sealants.
 - 3. Mildew-resistant joint sealants.
 - 4. Latex joint sealants.
- B. Related Requirements:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".

1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.4 ACTION SUBMITTALS

- A. Product Data: For each joint-sealant product.
- B. Sustainable Design Submittals:
 - 1. Product Data: For sealants, indicating VOC content.
 - 2. Laboratory Test Reports: For sealants, indicating compliance with requirements for low-emitting materials.
- C. Samples for Initial Selection: Manufacturer's color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.
- D. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch-wide joints formed between two 6-inch-long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.
- E. Joint-Sealant Schedule: Include the following information:
 - 1. Joint-sealant application, joint location, and designation.
 - 2. Joint-sealant manufacturer and product name.
 - 3. Joint-sealant formulation.
 - 4. Joint-sealant color.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified testing agency.
- B. Product Test Reports: For each kind of joint sealant, for tests performed by a qualified testing agency.
- C. Preconstruction Laboratory Test Schedule: Include the following information for each joint sealant and substrate material to be tested:
 - 1. Joint-sealant location and designation.
 - 2. Manufacturer and product name.
 - 3. Type of substrate material.

4. Proposed test.
5. Number of samples required.
- D. Preconstruction Laboratory Test Reports: From sealant manufacturer, indicating the following:
 1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants.
 2. Interpretation of test results and written recommendations for primers and substrate preparation are needed for adhesion.
- E. Preconstruction Field-Adhesion-Test Reports: Indicate which sealants and joint preparation methods resulted in optimum adhesion to joint substrates based on testing specified in "Preconstruction Testing" Article.
- F. Field-Adhesion-Test Reports: For each sealant application tested.
- G. Sample Warranties: For special warranties.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An authorized representative who is trained and approved by manufacturer.
- B. Product Testing: Test joint sealants using a qualified testing agency.
 1. Testing Agency Qualifications: Qualified according to ASTM C1021 to conduct the testing indicated.
- C. Mockups: Install sealant in mockups of assemblies specified in other Sections that are indicated to receive joint sealants specified in this Section. Use materials and installation methods specified in this Section.

1.7 PRECONSTRUCTION TESTING

- A. Preconstruction Laboratory Testing: Submit to joint-sealant manufacturers, for testing indicated below, samples of materials that will contact or affect joint sealants.
 1. Adhesion Testing: Use ASTM C794 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.
 2. Compatibility Testing: Use ASTM C1087 to determine sealant compatibility when in contact with glazing and gasket materials.
 3. Stain Testing: Use ASTM C1248 to determine stain potential of sealant when in contact with masonry substrates.
 4. Submit manufacturer's recommended number of pieces of each type of material, including joint substrates, joint-sealant backings, and miscellaneous materials.
 5. Schedule sufficient time for testing and analyzing results to prevent delaying the Work.
 6. For materials failing tests, obtain joint-sealant manufacturer's written instructions for corrective measures, including use of specially formulated primers.
 7. Testing will not be required if joint-sealant manufacturers submit data that are based on previous testing, not older than 24 months, of sealant products for adhesion to, staining of, and compatibility with joint substrates and other materials matching those submitted.
- B. Preconstruction Field-Adhesion Testing: Before installing sealants, field test their adhesion to Project joint substrates as follows:
 1. Locate test joints where indicated on Project or, if not indicated, as directed by Architect.
 2. Conduct field tests for each kind of sealant and joint substrate.
 3. Notify Architect seven days in advance of dates and times when test joints will be erected.
 4. Arrange for tests to take place with joint-sealant manufacturer's technical representative present.

- a. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1.1 in ASTM C1193 or Method A, Tail Procedure, in ASTM C1521.
 - 1) For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.
- 5. Report whether sealant failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. For sealants that fail adhesively, retest until satisfactory adhesion is obtained.
- 6. Evaluation of Preconstruction Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing, in absence of other indications of noncompliance with requirements, will be considered satisfactory. Do not use sealants that fail to adhere to joint substrates during testing.

1.8 FIELD CONDITIONS

- A. Do not proceed with installation of joint sealants under the following conditions:
 - 1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
 - 2. When joint substrates are wet.
 - 3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
 - 4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

1.9 WARRANTY

- A. Special Installer's Warranty: Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
 - 1. Warranty Period: Two years from date of Substantial Completion.
- B. Special Manufacturer's Warranty: Manufacturer agrees to furnish joint sealants to repair or replace those joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
 - 1. Warranty Period: Five years from date of Substantial Completion.
- C. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:
 - 1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
 - 2. Disintegration of joint substrates from causes exceeding design specifications.
 - 3. Mechanical damage caused by individuals, tools, or other outside agents.
 - 4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

PART 2 - PRODUCTS

2.1 JOINT SEALANTS, GENERAL

- A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.
- B. Provide to the greatest extent possible, pickproof sealants meeting the requirements of ASTM C920 of type and grade required per condition.

- C. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

2.2 SILICONE JOINT SEALANTS

- A. Silicone, S, NS, 25, T, NT: Single-component, nonsag, plus 25 percent and minus 25 percent movement capability, traffic- and nontraffic-use, neutral-curing silicone joint sealant; ASTM C920, Type S, Grade NS, Class 25, Uses T and NT.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. May National Associates, Inc.; a subsidiary of Sika Corporation.
 - b. Pecora Corporation.
 - c. Sika Corporation; Joint Sealants.

2.3 URETHANE JOINT SEALANTS

- A. Urethane, S, NS, 25, NT: Single-component, nonsag, nontraffic-use, plus 25 percent and minus 25 percent movement capability, urethane joint sealant; ASTM C920, Type S, Grade NS, Class 25, Use NT.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BASF Corporation.
 - b. Bostik, Inc.
 - c. Pecora Corporation.
 - d. Sherwin-Williams Company (The).
 - e. Sika Corporation; Joint Sealants.
 - f. Tremco Incorporated.
- B. Urethane, S, P, 25, T, NT: Single-component, pourable, plus 25 percent and minus 25 percent movement capability, traffic- and nontraffic-use, urethane joint sealant; ASTM C920, Type S, Grade P, Class 25, Uses T and NT.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BASF Corporation.
 - b. Pecora Corporation.
 - c. Polymeric Systems, Inc.
 - d. Sherwin-Williams Company (The).

2.4 MILDEW-RESISTANT JOINT SEALANTS

- A. Mildew-Resistant Joint Sealants: Formulated for prolonged exposure to humidity with fungicide to prevent mold and mildew growth.
- B. Silicone, Mildew Resistant, Acid Curing, S, NS, 25, NT: Mildew-resistant, single-component, nonsag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, acid-curing silicone joint sealant; ASTM C920, Type S, Grade NS, Class 25, Use NT.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. GE Construction Sealants; Momentive Performance Materials Inc.
 - b. Pecora Corporation.
 - c. The Dow Chemical Company.
 - d. Tremco Incorporated.

2.5 LATEX JOINT SEALANTS

- A. Acrylic Latex: Acrylic latex or siliconized acrylic latex, ASTM C834, Type OP, Grade NF.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. May National Associates, Inc.; a subsidiary of Sika Corporation.
 - b. Pecora Corporation.
 - c. Sherwin-Williams Company (The).
 - d. Tremco Incorporated.

2.6 JOINT-SEALANT BACKING

- A. Sealant Backing Material, General: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Adfast.
 - b. Alcot Plastics Ltd.
 - c. BASF Corporation.
 - d. Construction Foam Products; a division of Nomaco, Inc.
- B. Cylindrical Sealant Backings: ASTM C1330, Type C (closed-cell material with a surface skin), Type B (bicellular material with a surface skin) or any of the preceding types, as approved in writing by joint-sealant manufacturer for joint application indicated, and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.
- C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

2.7 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.
- C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
 2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:
 - a. Concrete.
 - b. Masonry.
 - c. Unglazed surfaces of ceramic tile.
 - d. Exterior insulation and finish systems.
 3. Remove laitance and form-release agents from concrete.
 4. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:
 - a. Metal.
 - b. Glass.
 - c. Porcelain enamel.
 - d. Glazed surfaces of ceramic tile.
- B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.
- C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

- A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.
- B. Sealant Installation Standard: Comply with recommendations in ASTM C1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- C. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
 1. Do not leave gaps between ends of sealant backings.
 2. Do not stretch, twist, puncture, or tear sealant backings.
 3. Remove absorbent sealant backings that have become wet before sealant application, and replace them with dry materials.
- D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.
- E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:
 1. Place sealants so they directly contact and fully wet joint substrates.
 2. Completely fill recesses in each joint configuration.
 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.

1. Remove excess sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
3. Provide concave joint profile per Figure 8A in ASTM C1193 unless otherwise indicated.
4. Provide flush joint profile at waterfall edges of solid surfacing according to Figure 8B in ASTM C1193.
5. Provide recessed joint configuration of recess depth and at aluminum storefront systems according to Figure 8C in ASTM C1193.
 - a. Use masking tape to protect surfaces adjacent to recessed tooled joints.

3.4 CLEANING

- A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.5 PROTECTION

- A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

3.6 JOINT-SEALANT SCHEDULE

- A. Joint-Sealant Application: Exterior joints in vertical surfaces and horizontal nontraffic surfaces.
 1. Joint Locations:
 - a. Construction joints in cast-in-place concrete.
 - b. Control and expansion joints in unit masonry.
 - c. Joints between metal panels.
 - d. Joints between different materials listed above.
 - e. Perimeter joints between materials listed above and frames of doors.
 - f. Other joints as indicated on Drawings.
 2. Joint Sealant: Silicone, nonstaining, S, NS, 50, NT.
 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- B. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces.
 1. Joint Locations:
 - a. Control and expansion joints on exposed interior surfaces of exterior walls.
 - b. Vertical joints on exposed surfaces of unit masonry walls and partitions.
 - c. Other joints as indicated on Drawings.
 2. Joint Sealant: Urethane, S, NS, 25, NT.
 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- C. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces not subject to significant movement.
 1. Joint Locations:
 - a. Control joints on exposed interior surfaces of exterior walls.
 - b. Other joints as indicated on Drawings.
 2. Joint Sealant: Acrylic latex.

3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- D. Joint-Sealant Application: Mildew-resistant interior joints in vertical surfaces and horizontal nontraffic surfaces.
1. Joint Locations:
 - a. Joints between plumbing fixtures and adjoining walls, floors, and counters.
 - b. Other joints as indicated on Drawings.
 2. Joint Sealant: Silicone, mildew resistant, acid curing, S, NS, 25, NT.
 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

END OF SECTION

SECTION 08 11 13
HOLLOW METAL DOORS AND FRAMES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes:
 - 1. Exterior standard steel doors and frames.
- B. Related Requirements:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 2. Section 042200 "Concrete Unit Masonry".
 - 3. Section 079200 "Joint Sealants".
 - 4. Section 087100 "Door Hardware" for door hardware for hollow-metal doors.

1.3 DEFINITIONS

- A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or ANSI/SDI A250.8.

1.4 COORDINATION

- A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.
- B. Coordinate requirements for installation of door hardware, electrified door hardware, and access control and security systems.

1.5 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.6 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, core descriptions, fire-resistance ratings, temperature-rise ratings, and finishes.
- B. High Performance Submittals
 - 1. Product Data: For products having recycled content, documentation indicating percentages by weight of postconsumer and preconsumer recycled content. Include statement indicating costs for each product having recycled content.
 - 2. Product Data: For regional products extracted and manufactured within 500 miles of project site.
 - 3. Test Reports: For primers, adhesives, coatings and sealants, documentation indicating that products comply with low emitting VOC requirements.
- C. Shop Drawings: Include the following:

1. Elevations of each door type.
 2. Details of doors, including vertical- and horizontal-edge details and metal thicknesses.
 3. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
 4. Locations of reinforcement and preparations for hardware.
 5. Details of each different wall opening condition.
 6. Details of anchorages, joints, field splices, and connections.
 7. Details of accessories.
 8. Details of moldings, removable stops, and glazing.
 9. Details of conduit and preparations for power, signal, and control systems.
- D. Samples for Verification:
1. For each type of exposed finish required, prepared on Samples of not less than 3 by 5 inches.
- E. Schedule: Provide a schedule of hollow-metal work prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final Door Hardware Schedule.

1.7 INFORMATIONAL SUBMITTALS

- A. Product Test Reports: For each type of hollow-metal door and frame assembly, for tests performed by a qualified testing agency.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Deliver hollow-metal work palletized, packaged, or crated to provide protection during transit and Project-site storage. Do not use non-vented plastic.
1. Provide additional protection to prevent damage to factory-finished units.
- B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.
- C. Store hollow-metal work vertically under cover at Project site with head up. Place on minimum 4-inch-high wood blocking. Provide minimum 1/4-inch space between each stacked door to permit air circulation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Ceco Door; ASSA ABLOY.
 2. Curries Company; ASSA ABLOY.
 3. Republic Doors and Frames.
 4. Rocky Mountain Metals, Inc.
 5. Steelcraft; an Allegion brand.
 6. Approved substitution.

2.2 EXTERIOR STANDARD STEEL DOORS AND FRAMES

- A. Construct hollow-metal doors and frames to comply with standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.
- B. Extra-Heavy-Duty Doors and Frames: ANSI/SDI A250.8, Level 3; ANSI/SDI A250.4, Level A..

1. Doors:
 - a. Type: As indicated in the Door and Frame Schedule.
 - b. Thickness: 1-3/4 inches.
 - c. Face: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum A40 coating.
 - d. Edge Construction: Model 2, Seamless.
 - e. Edge Bevel: Provide manufacturer's standard beveled or square edges.
 - f. Top Edge Closures: Close top edges of doors with flush closures of same material as face sheets. Seal joints against water penetration.
 - g. Bottom Edges: Close bottom edges of doors where required for attachment of weather stripping with end closures or channels of same material as face sheets. Provide weep-hole openings in bottoms of exterior doors to permit moisture to escape.
 - h. Core: Manufacturer's standard.
2. Frames:
 - a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum A40 coating.
 - b. Construction: Full profile welded.
3. Exposed Finish: Painted unless otherwise indicated..

2.3 FRAME ANCHORS

- A. Jamb Anchors:
 1. Type: Anchors of minimum size and type required by applicable door and frame standard, and suitable for performance level indicated.
 2. Quantity: Minimum of three anchors per jamb, with one additional anchor for frames with no floor anchor. Provide one additional anchor for each 24 inches of frame height above 7 feet.
- B. Material: ASTM A879/A879M, Commercial Steel (CS), 04Z coating designation; mill phosphatized.
 1. For anchors built into exterior walls, steel sheet complying with ASTM A1008/A1008M or ASTM A1011/A1011M; hot-dip galvanized according to ASTM A153/A153M, Class B.

2.4 MATERIALS

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Cold-Rolled Steel Sheet: ASTM A1008/A1008M, Commercial Steel (CS), Type B; suitable for exposed applications.
- C. Metallic-Coated Steel Sheet: ASTM A653/A653M, Commercial Steel (CS), Type B.
- D. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A153/A153M.

2.5 FABRICATION

- A. Hollow-Metal Frames: Fabricate in one piece except where handling and shipping limitations require multiple sections. Where frames are fabricated in sections, provide alignment plates or angles at each joint, fabricated of metal of same or greater thickness as frames.
 1. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
 2. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers as follows. Keep holes clear during construction.
 - a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.

- b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.
- B. Hardware Preparation: Factory prepare hollow-metal doors and frames to receive templated mortised hardware, and electrical wiring; include cutouts, reinforcement, mortising, drilling, and tapping according to ANSI/SDI A250.6, the Door Hardware Schedule, and templates.
 - 1. Reinforce doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.
 - 2. Comply with BHMA A156.115 for preparing hollow-metal doors and frames for hardware.

2.6 STEEL FINISHES

- A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.
 - 1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with ANSI/SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces. Touch up factory-applied finishes where spreaders are removed.
- B. Drill and tap doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.

3.2 INSTALLATION

- A. Install hollow-metal doors and frames plumb, rigid, properly aligned, and securely fastened in place. Comply with approved Shop Drawings and with manufacturer's written instructions.
- B. Hollow-Metal Frames: Comply with ANSI/SDI A250.11.
 - 1. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces without damage to completed Work.
 - a. Where frames are fabricated in sections, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces. Touch-up finishes.
 - b. Install frames with removable stops located on secure side of opening.
 - 2. Floor Anchors: Secure with postinstalled expansion anchors.
 - a. Floor anchors may be set with power-actuated fasteners instead of postinstalled expansion anchors if so indicated and approved on Shop Drawings.
 - 3. Solidly pack mineral-fiber insulation inside frames.
 - 4. Masonry Walls: Coordinate installation of frames to allow for solidly filling space between frames and masonry with grout or mortar.
 - 5. Installation Tolerances: Adjust hollow-metal frames to the following tolerances:
 - a. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
 - b. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.

- c. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
 - d. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.
 - C. Hollow-Metal Doors: Fit and adjust hollow-metal doors accurately in frames, within clearances specified below.
 - 1. Non-Fire-Rated Steel Doors: Comply with ANSI/SDI A250.8.

3.3 FIELD QUALITY CONTROL

- A. Repair or remove and replace installations where inspections indicate that they do not comply with specified requirements.
- B. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.

3.4 REPAIR

- A. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.
- B. Metallic-Coated Surface Touchup: Clean abraded areas and repair with galvanizing repair paint according to manufacturer's written instructions.
- C. Touchup Painting: Cleaning and touchup painting of abraded areas of paint are specified in painting Sections.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 08 33 23
OVERHEAD COILING DOORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Service doors.
- B. Related Requirements:
 - 1. Section 055000 "Metal Fabrications" for miscellaneous steel supports, door-opening framing, corner guards, and bollards.
 - 2. Section 099113 "Exterior Painting" for finish painting of factory-primed doors.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type and size of overhead coiling door and accessory.
 - 1. Include construction details, material descriptions, dimensions of individual components, profiles for slats, and finishes.
 - 2. Include rated capacities, operating characteristics, electrical characteristics, and furnished accessories.
 - 3. Include description of automatic-closing device and testing and resetting instructions.
- B. Shop Drawings: For each installation and for special components not dimensioned or detailed in manufacturer's product data.
 - 1. Include plans, elevations, sections, and mounting details.
 - 2. Include details of equipment assemblies, and indicate dimensions, required clearances, method of field assembly, components, and location and size of each field connection.
 - 3. Include points of attachment and their corresponding static and dynamic loads imposed on structure.
 - 4. For exterior components, include details of provisions for assembly expansion and contraction and for excluding and draining moisture to the exterior.
 - 5. Show locations of controls, locking devices, and other accessories.
 - 6. Include diagrams for power, signal, and control wiring.
- C. Samples for Initial Selection: Manufacturer's finish charts showing full range of colors and textures available for units with factory-applied finishes.
 - 1. Include similar Samples of accessories involving color selection.
- D. Samples for Verification: For each type of exposed finish on the following components, in manufacturer's standard sizes:
 - 1. Curtain slats.
 - 2. Bottom bar with sensor edge.
 - 3. Guides.
 - 4. Brackets.
 - 5. Hood.
 - 6. Locking device(s).
 - 7. Include similar Samples of accessories involving color selection.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Special warranty.
- B. Maintenance Data: For overhead coiling doors to include in maintenance manuals.
- C. Record Documents: For fire-rated doors, list of door numbers and applicable room name and number to which door accesses.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer for both installation and maintenance of units required for this Project.
 - 1. Maintenance Proximity: Not more than two hours' normal travel time from Installer's place of business to Project site.

1.7 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of doors that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Source Limitations: Obtain overhead coiling doors from single source from single manufacturer.
 - 1. Obtain operators and controls from overhead coiling-door manufacturer.

2.2 PERFORMANCE REQUIREMENTS

- A. Accessibility Standard: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1.
- B. Structural Performance, Exterior Doors: Capable of withstanding the following design wind loads:
 - 1. Design Wind Load: As indicated on Drawings.
 - 2. Deflection Limits: Design overhead coiling doors to withstand design wind load without evidencing permanent deformation or disengagement of door components.
 - 3. Operability under Wind Load: Design overhead coiling doors to remain operable under design wind load, acting inward and outward.
- C. Seismic Performance: Overhead coiling doors shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
 - 1. Component Importance Factor: 1.0.

2.3 DOOR ASSEMBLY

- A. Service Door: Overhead coiling door formed with curtain of interlocking metal slats.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. C.H.I. Overhead Doors, Inc.

- b. Cookson Company.
 - c. Cornell.
 - d. Overhead Door Corporation.
 - e. Raynor.
 - f. Approved substitution.
- B. Operation Cycles: Door components and operators capable of operating for not less than 100,000. One operation cycle is complete when a door is opened from the closed position to the fully open position and returned to the closed position.
 - 1. Include tamperproof cycle counter.
- C. Air Infiltration: Maximum rate of 1.0 cfm/sq. ft. at 15 and 25 mph when tested according to ASTM E283.
- D. Door Curtain Material: Galvanized steel.
- E. Door Curtain Slats: Flat profile slats of 3-1/4-inch center-to-center height.
- F. Bottom Bar: Two angles, each not less than 1-1/2 by 1-1/2 by 1/8 inch thick; fabricated from hot-dip galvanized steel and finished to match door.
- G. Curtain Jamb Guides: Galvanized steel with exposed finish matching curtain slats.
- H. Hood: Match curtain material and finish.
 - 1. Shape: As indicated on Drawings.
 - 2. Mounting: Face of wall.
- I. Locking Devices: Equip door with locking device assembly.
 - 1. Locking Device Assembly: Single-jamb side locking bars, operable from inside with thumbturn outside with cylinder.
- J. Manual Door Operator: Push-up operation.
 - 1. Provide operator with through-wall shaft operation.
 - 2. Provide operator with manufacturer's standard removable operating arm.
- K. Curtain Accessories: Equip door with weatherseals and pull-down strap.
- L. Door Finish:
 - 1. Factory Prime Finish: Manufacturer's standard color.

2.4 DOOR CURTAIN MATERIALS AND CONSTRUCTION

- A. Door Curtains: Fabricate overhead coiling-door curtain of interlocking metal slats, designed to withstand wind loading indicated, in a continuous length for width of door without splices. Unless otherwise indicated, provide slats of thickness and mechanical properties recommended by door manufacturer for performance, size, and type of door indicated, and as follows:
 - 1. Steel Door Curtain Slats: Zinc-coated (galvanized), cold-rolled structural-steel sheet; complying with ASTM A653/A653M, with G90 zinc coating; nominal sheet thickness (coated) of 0.028 inch; and as required.
 - 2. Metal Interior Curtain-Slat Facing: Match metal of exterior curtain-slat face, with minimum steel thickness of 0.010 inch.
- B. Curtain Jamb Guides: Manufacturer's standard angles or channels and angles of same material and finish as curtain slats unless otherwise indicated, with sufficient depth and strength to retain curtain, to allow curtain to operate smoothly, and to withstand loading. Slot bolt holes for guide adjustment. Provide removable stops on guides to prevent overtravel of curtain.
 - 1. Thresholds: Equip pass doors with integral thresholds that comply with the accessibility standard of authorities having jurisdiction.

2.5 HOODS

- A. General: Form sheet metal hood to entirely enclose coiled curtain and operating mechanism at opening head. Contour to fit end brackets to which hood is attached. Roll and reinforce top and bottom edges for stiffness. Form closed ends for surface-mounted hoods and fascia for any portion of between-jamb mounting that projects beyond wall face. Equip hood with intermediate support brackets as required to prevent sagging.

1. Galvanized Steel: Nominal 0.028-inch-thick, hot-dip galvanized-steel sheet with G90 zinc coating, complying with ASTM A653/A653M.
 2. Stainless Steel: 0.025-inch-thick, stainless steel sheet, Type 304, complying with ASTM A240/A240M or ASTM A666.
 3. Aluminum: 0.040-inch-thick aluminum sheet complying with ASTM B209, of alloy and temper recommended by manufacturer and finisher for type of use and finish indicated.
 4. Include automatic drop baffle on fire-rated doors to guard against passage of smoke or flame.
 5. Exterior-Mounted Doors: Fabricate hood to act as weather protection and with a perimeter sealant-joint-bead profile for applying joint sealant.
- B. Removable Metal Soffit: Formed or extruded from same metal and with same finish as curtain if hood is mounted above ceiling unless otherwise indicated.

2.6 LOCKING DEVICES

- A. Slide Bolt: Fabricate with side-locking bolts to engage through slots in tracks for locking by padlock, located on both left and right jamb sides, operable from coil side.
- B. Locking Device Assembly: Fabricate with cylinder lock, spring-loaded dead bolt, operating handle, cam plate, and adjustable locking bars to engage through slots in tracks.
1. Lock Cylinders: As standard with manufacturer and keyed to Parks and Recreation keying system.
 2. Keys: Three for each cylinder.
- C. Chain Lock Keeper: Suitable for padlock.
- D. Safety Interlock Switch: Equip power-operated doors with safety interlock switch to disengage power supply when door is locked.

2.7 CURTAIN ACCESSORIES

- A. Smoke Seals: Equip each fire-rated door with replaceable smoke-seal perimeter gaskets or brushes for smoke and draft control as required for door listing and labeling by a qualified testing agency.
- B. Weatherseals for Exterior Doors: Equip each exterior door with weather-stripping gaskets fitted to entire exterior perimeter of door for a weather-resistant installation unless otherwise indicated.
1. At door head, use 1/8-inch-thick, replaceable, continuous-sheet baffle secured to inside of hood or field-installed on the header.
 2. At door jambs, use replaceable, adjustable, continuous, flexible, 1/8-inch-thick seals of flexible vinyl, rubber, or neoprene.
- C. Pull-Down Strap: Provide pull-down straps for doors more than 84 inches high.

2.8 COUNTERBALANCE MECHANISM

- A. General: Counterbalance doors by means of manufacturer's standard mechanism with an adjustable-tension, steel helical torsion spring mounted around a steel shaft and contained in a spring barrel connected to top of curtain with barrel rings. Use grease-sealed bearings or self-lubricating graphite bearings for rotating members.
- B. Counterbalance Barrel: Fabricate spring barrel of manufacturer's standard hot-formed, structural-quality, seamless or welded carbon-steel pipe, of sufficient diameter and wall thickness to support rolled-up curtain without distortion of slats and to limit barrel deflection to not more than 0.03 in./ft. of span under full load.
- C. Counterbalance Spring: One or more oil-tempered, heat-treated steel helical torsion springs. Size springs to counterbalance weight of curtain, with uniform adjustment accessible from outside barrel. Secure ends of springs to barrel and shaft with cast-steel barrel plugs.

1. Fire-Rated Doors: Equip with auxiliary counterbalance spring and prevent tension release from main counterbalance spring when automatic-closing device operates.
- D. Torsion Rod for Counterbalance Shaft: Fabricate of manufacturer's standard cold-rolled steel, sized to hold fixed spring ends and carry torsional load.
- E. Brackets: Manufacturer's standard mounting brackets of either cast iron or cold-rolled steel plate.

2.9 MANUAL DOOR OPERATORS

- A. General: Equip door with manual door operator by door manufacturer.
- B. Push-up Door Operation: Lift handles and pull rope for raising and lowering doors, with counterbalance mechanism designed so that required lift or pull for door operation does not exceed 25 lbf.

2.10 GENERAL FINISH REQUIREMENTS

- A. Comply with NAAMM/NOMMA 500 for recommendations for applying and designating finishes.
- B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.11 STEEL AND GALVANIZED-STEEL FINISHES

- A. Baked-Enamel or Powder-Coat Finish: Manufacturer's standard baked-on finish consisting of prime coat and thermosetting topcoat. Comply with coating manufacturer's written instructions for cleaning, pretreatment, application, and minimum dry film thickness.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates areas and conditions, with Installer present, for compliance with requirements for substrate construction and other conditions affecting performance of the Work.
- B. Examine locations of electrical connections.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install overhead coiling doors and operating equipment complete with necessary hardware, anchors, inserts, hangers, and equipment supports; according to manufacturer's written instructions and as specified.
- B. Install overhead coiling doors, hoods, controls, and operators at the mounting locations indicated for each door.

3.3 ADJUSTING

- A. Adjust hardware and moving parts to function smoothly so that doors operate easily, free of warp, twist, or distortion.
 1. Adjust exterior doors and components to be weather resistant.
- B. Lubricate bearings and sliding parts as recommended by manufacturer.

- C. Adjust seals to provide tight fit around entire perimeter.

3.4 MAINTENANCE SERVICE

- A. Initial Maintenance Service: Beginning at Substantial Completion, maintenance service shall include three months' full maintenance by skilled employees of coiling-door Installer. Include quarterly preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper door operation. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.
 - 1. Perform maintenance, including emergency callback service, during normal working hours.
 - 2. Include 24-hour-per-day, seven-day-per-week, emergency callback service.

3.5 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain overhead coiling doors.

END OF SECTION

SECTION 08 45 23
FIBERGLASS SANDWICH PANEL ASSEMBLIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Translucent sandwich panel wall systems.
- B. Related Requirements:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 2. Section 042200 "Concrete Unit Masonry".
 - 3. Section 061100 "Miscellaneous Rough Carpentry".
 - 4. Section 079200 "Joint Sealants".

1.3 SUBMITTALS

- A. Product Data: Manufacturer's data sheets on each product to be used, including preparation instructions and recommendations, storage and handling requirements, installation methods and maintenance instructions.
- B. Sustainable Design Submittals:
 - 1. Submit material as requested – including percentages by weight of post-consumer/ post-industrial recycled content, locally manufactured/ harvested materials and any applicable VOC content.
- C. Samples:
 - 1. Submit sample sets of color chips for initial selection representing manufacturer's full range of available colors and finishes.
 - 2. Submit samples for verification, consisting of at least one sample, minimum 6 inches high by 12 inches wide, representing actual product (including framing) and color(s).
- D. Shop Drawings: Include plans, elevations, sections, and details, indicating dimensions, tolerances, profiles, anchorage, connections, fasteners, provisions for expansion and contraction, drainage, flashing, finish, glazing, and attachments to other Work.
- E. Design Data:
 - 1. Submit manufacturer's structural calculations showing sizes of framing members and loads applied to supporting structure based on design loads.
 - 2. Submit any required signed and sealed structural calculations prepared by a qualified professional engineer who is licensed in the state where system is to be installed.
- F. Manufacturer's Certificates: Submit documentation in writing certifying that products meet or exceed the specified requirements.
- G. Test Reports: Submit certified test reports from a qualified independent testing agency, indicating wall systems comply with specified requirements. Submit results from the following:
 - 1. Flame spread and smoke development, ASTM E 84.
 - 2. Burn extent, ASTM D 635.
 - 3. Color change, ASTM D 2244 in accordance with ASTM D 1435.
 - 4. Accelerated aging, ASTM D 1037.
 - 5. Bond strength, ASTM C 297.

6. Insulating U-factor, ASTM C 1199.
7. Self-ignition, ASTM D 1929.
8. Air infiltration, ASTM E 283.
9. Water penetration, ASTM E 331.
10. Uniform load deflection, ASTM E 72 and E 330.

1.4 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Minimum ten years documented experience in the fabrication of wall systems of the type required for this project and capable of providing field service representation during installation.
- B. Installer Qualifications: Minimum five years documented experience in the work of this section, specializing in work similar to project requirements and approved by manufacturer.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Delivery: Deliver to site in manufacturer's original, unopened containers and packaging, with labels clearly identifying product name, manufacturer, and installation location.
- B. Storage/Handling: Store products above the floor and under cover in a clean, dry area until installation. Protect materials and finish from damage during handling and installation.

1.6 SITE CONDITIONS

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's recommended limits.

1.7 WARRANTIES

- A. Exterior Fiberglass Color Change (select unless otherwise specified):
 1. Provide manufacturer's standard 5 year warranty.
- B. Material Workmanship:
 1. Provide manufacturer's standard 1 year warranty.
- C. Fiberglass Fiberbloom: Provide manufacturer's standard 10 year warranty.
- D. Metal Finishes:
 1. Anodize: Provide manufacturer's standard 5 year warranty.

PART 2 - PRODUCTS

2.1 TRANSLUCENT WALL SYSTEMS

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Major Industries, Inc.; LightBasic™ Translucent Wall System or a comparable product by one of the following:
 1. Kalwall
 2. Kingspan Light + Air | CPI
 3. Approved substitution.

2.2 DESIGN / PERFORMANCE REQUIREMENTS

- A. Framing Members: Sufficient sizes as required to support design loads.
- B. Deflection Limits: Shall not exceed: L/120 per IBC code requirements.

- C. Safety Factors: Allowable stresses shall incorporate following safety factors, unless otherwise specified:
 - 1. Load Carrying Members: 1.65, Load Carrying Fasteners: 2.0.
 - 2. Expansion and Contraction: Design and install components with provisions for expansion and contraction due to a 100 degree F (56 degrees C) temperature variation.
- D. Design Loads: Framing components shall be designed to support the following loads:
 - 1. Live Load: As indicated on the Drawings.
 - 2. Wind Load: As indicated on the Drawings.
- E. Design Calculations:
 - 1. Prepare structural calculations in accordance with Aluminum Association Specifications for Aluminum Structures SAS30.
 - 2. Provide calculations prepared and stamped by a registered professional engineer, qualified in the design of wall systems and licensed in the state where wall systems are to be installed.

2.3 COMPONENTS

- A. Translucent Panel Units:
 - 1. Construction: Facings of architectural-grade fiberglass reinforced face sheets bonded under controlled heat and pressure to a mechanically-interlocked aluminum I-beam grid core to form double-faced, self-supporting, structural composite sandwich panels.
 - a. Thickness: 2-3/4 inches.
 - b. Panel Maximums: 5 feet wide / 16 feet long.
 - c. U-Factor: Center of Panel U-factor (for glazing comparison only)
 - 1) 0.48.
 - d. U-Factor: Values for complete system (including internal grid and perimeter framing)
 - 1) 0.60.
 - e. Grid Pattern:
 - 1) In-line Shoji.
 - f. Nominal Grid Size:
 - 1) 12 inches by 24 inches.
 - g. Unbonded Areas: Maximum of 4 unbonded areas, a maximum of 3/64 inch in diameter, in an area a maximum of 40 square feet of panel surface.
 - h. Panel Weeps: Weep holes provided on down slope side of installed panels to permit condensation to leave panel interior.
 - i. Panel Corners: Notch and interlock or reinforce with aluminum for radius conditions.
 - j. Assembly: Factory assembled. Field assembly of panels not allowed.
 - 2. Physical Properties:
 - a. ASTM E 72 and E 330 - Uniform Load Deflection.
 - b. ASTM E 661 - Concentrated and Impact.
 - c. ASTM E 283 - Air Infiltration through fixed panel system and perimeter framing: less than 0.01 cfm/ft air leakage at 6.24 psf air pressure.
 - d. ASTM E 331 - Water penetration through fixed panel system and perimeter framing. No leakage when water is applied to entire panel surface at rate of 5 gal/hr/sq ft for 15 minutes at 12 psf air pressure.
 - 3. I-Beam Grid Core:
 - a. Material: Aluminum Alloy 6061-T6.
 - b. 7/16 inch minimum flange width, 0.050 inch web thickness.
 - c. Mechanically interlocked.

- d. Full surface contact with face sheets.
- 4. Adhesive:
 - a. Waterproof resin for use in laminating face sheet to aluminum grid core.
 - b. Impact and Thermal Shock: Adhesive capable of withstanding impact and thermal shock normally encountered in exterior construction.
 - c. Adhesive Bond Line: Straight, black, cover entire width of I-beam, with neat edge.
 - d. Initial Adhesive Bond Strength: Shear Strength, ASTM D 1002: 563 psi, Tensile Strength, ASTM C 297: 557 psi minimum.
 - e. Aged Adhesive Bond Strength, ASTM D 1037: Shear Strength, ASTM D 1002: 1212 psi, Tensile Strength, ASTM C 297: 914 psi.
- 5. Translucent Face Sheets:
 - a. Appearance of Face Sheets:
 - 1) Uniform in color to prevent splotchy appearance.
 - 2) Free of ridges, wrinkles, clusters of air bubbles and pinholes.
 - b. Exterior Face Sheet:
 - 1) ASTM D 2244: Color change shall not exceed 3.0 Delta E units after 5 years of weathering (accelerated Arizona / simulated South Florida testing).
 - 2) Thickness:
 - a) Standard - 70 foot-pounds / 0.070 inches.
 - 3) Color: White
 - c. Interior Face Sheet:
 - 1) Flame Spread, ASTM E 84: 10 maximum.
 - 2) Smoke Development, ASTM E 84: 300 maximum.
 - 3) Burn Rate, ASTM D 635: 1.0 inch per minute maximum.
 - 4) Self-Ignition, ASTM D 1929: Greater than 650 degrees F.
 - 5) Thickness: 0.045 inches.
 - 6) Color: White
- B. Components and Framing:
 - 1. Aluminum:
 - a. Extruded Aluminum: ASTM B 221, Alloy 6063-T5/T6, 6061-T5/T6.
 - b. Formed Aluminum Components and Flashing: ASTM B 209, Alloy 5005-H34.
 - 2. Glazing Gaskets:
 - a. Factory provided sealing tape.
- C. Condensation Control System:
 - 1. Mechanically design to function properly with minimal dependency upon sealants.
- D. Custom Designs: 3D modeling used to verify custom fitting and assembly.
- E. Expansion and Contraction: Design and install components with provisions for expansion and contraction due to a 100 degree F temperature variation.
- F. Fasteners:
 - 1. Clips for Attachment: Aluminum - attach using bolted fastening methods.
 - 2. Construction and Glazing Cap Fasteners: 18-8 stainless steel - include gasketed sealing washers.
 - 3. Field Anchors: Cadmium plated, unless otherwise specified.
 - 4. Exposed Fasteners: Finish to match aluminum.

2.4 FABRICATION

- A. Weep Holes in Sill Components: Located as required to control condensation that may enter system by allowing it to pass to exterior.

- B. Construct wall systems of extruded aluminum shapes similar to sections indicated on the Drawings.

2.5 ALUMINUM FINISHES

- A. Anodized Coating: Architectural Class II clear anodized, Type AA-M10C22A31.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas to receive translucent wall system with installer and manufacturer's representative present, including supporting structure and substrate for dimensions, tolerances, material conditions, and support.
- B. Notify Architect of conditions that would adversely affect installation or subsequent utilization of wall system and do not proceed until conditions are corrected.

3.2 PREPARATION

- A. Ensure supports to receive wall system are clean, flat, level, plumb, and square.
- B. Aluminum Protection: Where aluminum will contact dissimilar materials, apply a coating of bituminous paint or other neutral material or separate with a nonabsorbent isolator.

3.3 INSTALLATION

- A. Install wall systems level, plumb, square, and accurately aligned, and in accordance with manufacturer's instructions at locations indicated on the approved drawings. Do not install wall system components with deficiencies or dimensional errors or proceed with installation until unsatisfactory components are replaced.
- B. Anchor wall system securely to supports using attachment methods that permit adjustment for construction tolerances, irregularities, alignment, and expansion and contraction.
- C. Install wall system including flashings, fasteners, hardware, sealants, and glazing materials required for a complete, weatherproof installation.

3.4 FIELD QUALITY CONTROL

- A. Water Test: Test wall system according to procedures in AAMA 501.2.
- B. Repair or replace work that does not comply with specified requirements and retest work.
- C. Examine installation of sheet metal flashing and sealants.
- D. Examine all face sheets for cracks, deep scratches, and other damage, and inspect protective weathering surface of exterior sheet. Repair in accordance with manufacturer's instructions.

3.5 CLEANING

- A. Clean wall system inside and outside, including member connections and inside corners, immediately after installation and after sealants have cured, but not more than 10 days after installation.
- B. Follow related cleaning instructions in accordance with manufacturer's recommendations.

3.6 PROTECTION

- A. Protect installed products until completion of project.

- B. Touch-up, repair or replace damaged products before Substantial Completion.

END OF SECTION

SECTION 09 96 00
HIGH-PERFORMANCE COATINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes surface preparation and the application of high-performance coating systems on the following substrates:
 - 1. Exterior Substrates:
 - a. Galvanized metal.
 - 2. Interior Substrates:
 - a. Concrete
 - b. Concrete masonry units (CMUs).
- B. Related Requirements:
 - 1. Section 018113 "High Performance Building System (HPBS) Design Requirements".
 - 2. Section 033000 "Cast-In-Place Concrete".
 - 3. Section 042200 "Concrete Unit Masonry".

1.3 DEFINITIONS

- A. MPI Gloss Level 5: 35 to 70 units at 60 degrees, according to ASTM D523.
- B. MPI Gloss Level 6: 70 to 85 units at 60 degrees, according to ASTM D523.
- C. MPI Gloss Level 7: More than 85 units at 60 degrees, according to ASTM D523.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include preparation requirements and application instructions.
 - 1. Include printout of current "MPI Approved Products List" for each product category specified, with the proposed product highlighted.
 - 2. Indicate VOC content.
- B. Sustainable Design Submittals:
 - 1. Product Data: For paints and coatings, indicating VOC content.
 - 2. Laboratory Test Reports: For paints and coatings, indicating compliance with requirements for low-emitting materials.
- C. Samples for Initial Selection: For each type of topcoat product indicated.
- D. Samples for Verification: For each type of coating system and each color and gloss of topcoat indicated.
 - 1. Submit Samples on rigid backing, 8 inches square.
 - 2. Apply coats on Samples in steps to show each coat required for system.
 - 3. Label each coat of each Sample.
 - 4. Label each Sample for location and application area.
- E. Product List: Cross-reference to coating system and locations of application areas. Use same designations indicated on Drawings and in schedules. Include color designations.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Coatings: 5 percent, but not less than 1 gal. of each material and color applied.

1.6 QUALITY ASSURANCE

- A. Mockups: Apply mockups of each coating system indicated to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
 - 1. Architect will select one surface to represent surfaces and conditions for application of each coating system.
 - a. Wall and Ceiling Surfaces: Provide samples of at least 100 sq. ft..
 - b. Other Items: Architect will designate items or areas required.
 - 2. Final approval of color selections will be based on mockups.
 - a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Architect at no added cost to Owner.
 - 3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 - 4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.
 - 1. Maintain containers in clean condition, free of foreign materials and residue.
 - 2. Remove rags and waste from storage areas daily.

1.8 FIELD CONDITIONS

- A. Apply coatings only when temperature of surfaces to be coated and ambient air temperatures are between 50 and 95 deg F.
- B. Do not apply coatings when relative humidity exceeds 85 percent; at temperatures less than 5 deg F above the dew point; or to damp or wet surfaces.
- C. Do not apply exterior coatings in snow, rain, fog, or mist.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Benjamin Moore & Co.
 - 2. PPG Paints.
 - 3. Sherwin-Williams Company (The).
- B. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to products listed in the Exterior High-Performance Coating Schedule or Interior High-Performance Coating Schedule for the coating category indicated.

2.2 HIGH-PERFORMANCE COATINGS, GENERAL

- A. MPI Standards: Products shall comply with MPI standards indicated and shall be listed in its "MPI Approved Products Lists."
- B. Material Compatibility:
 - 1. Materials for use within each paint system shall be compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
 - 2. For each coat in a paint system, products shall be recommended in writing by topcoat manufacturers for use in paint system and on substrate indicated.
 - 3. Products shall be of same manufacturer for each coat in a coating system.
- C. VOC Content: For field applications that are inside the weatherproofing system, paints and coatings shall comply with VOC content limits of authorities having jurisdiction and the following VOC content limits:
 - 1. Flat Paints and Coatings: 50 g/L.
 - 2. Nonflat Paints and Coatings: 150 g/L.
 - 3. Primers, Sealers, and Undercoaters: 200 g/L.
 - 4. Anticorrosive and Antirust Paints Applied to Ferrous Metals: 250 g/L.
 - 5. Zinc-Rich Industrial Maintenance Primers: 340 g/L.
 - 6. Pretreatment Wash Primers: 420 g/L.
 - 7. Floor Coatings: 100 g/L.
 - 8. Shellacs, Clear: 730 g/L.
 - 9. Shellacs, Pigmented: 550 g/L.
- D. Low-Emitting Materials: Interior paints and coatings shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- E. Colors: As selected by Architect from manufacturer's full range.

2.3 SOURCE QUALITY CONTROL

- A. Testing of Coating Materials: Owner reserves the right to invoke the following procedure:
 - 1. Owner will engage the services of a qualified testing agency to sample coating materials. Contractor will be notified in advance and may be present when samples are taken. If coating materials have already been delivered to Project site, samples may be taken at Project site. Samples will be identified, sealed, and certified by testing agency.
 - 2. Testing agency will perform tests for compliance with product requirements.
 - 3. Owner may direct Contractor to stop applying coatings if test results show materials being used do not comply with product requirements. Contractor shall remove noncomplying coating materials from Project site, pay for testing, and recoat surfaces coated with rejected materials. Contractor will be required to remove rejected materials from previously coated surfaces if, on recoating with complying materials, the two coatings are incompatible.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
 - 1. Concrete: 12 percent.

2. Fiber-Cement Board: 12 percent.
 3. Masonry (Clay and CMUs): 12 percent.
 4. Wood: 15 percent.
 5. Gypsum Board: 12 percent.
 6. Plaster: 12 percent.
- C. Gypsum Board Substrates: Verify that finishing compound is sanded smooth.
 - D. Plaster Substrates: Verify that plaster is fully cured.
 - E. Verify suitability of substrates, including surface conditions and compatibility, with existing finishes and primers.
 - F. Proceed with coating application only after unsatisfactory conditions have been corrected.
 1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Comply with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual" applicable to substrates and coating systems indicated.
- B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.
 1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.
- C. Clean substrates of substances that could impair bond of coatings, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
 1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce coating systems indicated.
- D. Concrete Substrates: Remove release agents, curing compounds, efflorescence, and chalk. Do not coat surfaces if moisture content or alkalinity of surfaces to be coated exceeds that permitted in manufacturer's written instructions.
 1. Clean surfaces with pressurized water. Use pressure range of 1500 to 4000 psi at 6 to 12 inches.
 2. Abrasive blast clean surfaces to comply with SSPC-SP 7/NACE No. 4.
- E. Masonry Substrates: Remove efflorescence and chalk. Do not coat surfaces if moisture content, alkalinity of surfaces, or alkalinity of mortar joints exceeds that permitted in manufacturer's written instructions.
 1. Clean surfaces with pressurized water. Use pressure range of 1500 to 4000 psi at 6 to 12 inches.
- F. Steel Substrates: Remove rust, loose mill scale, and shop primer if any. Clean using methods recommended in writing by paint manufacturer.
- G. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and areas where shop paint is abraded. Paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.
- H. Galvanized-Metal Substrates: Remove grease and oil residue from galvanized sheet metal by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied coatings.
- I. Wood Substrates:
 1. Scrape and clean knots. Before applying primer, apply coat of knot sealer that is recommended in writing by topcoat manufacturer for coating system indicated.
 2. Sand surfaces that will be exposed to view and dust off.
 3. Prime edges, ends, faces, undersides, and backsides of wood.
 4. After priming, fill holes and imperfections in the finish surfaces with filler that is recommended in writing by topcoat manufacturer for coating system indicated. Sand smooth when dried.

3.3 APPLICATION

- A. Apply high-performance coatings according to manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual."
 - 1. Use applicators and techniques suited for coating and substrate indicated.
 - 2. Coat surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, coat surfaces behind permanently fixed equipment or furniture with prime coat only.
 - 3. Coat backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
 - 4. Do not apply coatings over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
- B. Tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of the same material are to be applied. Tint undercoats to match color of finish coat, but provide sufficient difference in shade of undercoats to distinguish each separate coat.
- C. If undercoats or other conditions show through final coat, apply additional coats until cured film has a uniform coating finish, color, and appearance.
- D. Apply coatings to produce surface films without cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness, or other surface imperfections. Produce sharp glass lines and color breaks.

3.4 FIELD QUALITY CONTROL

- A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test coatings for dry film thickness.
 - 1. Contractor shall touch up and restore coated surfaces damaged by testing.
 - 2. If test results show that dry film thickness of applied coating does not comply with coating manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with coating manufacturer's written recommendations.

3.5 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
- B. After completing coating application, clean spattered surfaces. Remove spattered coatings by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from coating operation. Correct damage to work of other trades by cleaning, repairing, replacing, and recoating, as approved by Architect, and leave in an undamaged condition.
- D. At completion of construction activities of other trades, touch up and restore damaged or defaced coated surfaces.

3.6 EXTERIOR HIGH-PERFORMANCE COATING SCHEDULE

- A. Galvanized-Metal Substrates:
 - 1. Pigmented Polyurethane over Epoxy Primer System MPI EXT 5.3L:
 - a. Prime Coat: Primer, epoxy, anti-corrosive, for metal, MPI #101.
 - 1) Sherwin-Williams Company (The): Protective & Marine; Dura-Plate 235 Multi-Purpose Epoxy.
 - b. Intermediate Coat: Polyurethane, two component, pigmented, gloss matching topcoat.
 - c. Topcoat: Polyurethane, two component, pigmented, gloss (MPI Gloss Level 6), MPI #72.

- 1) Benjamin Moore & Co: Corotech; Aliphatic Acrylic Urethane Gloss.
- 2) PPG Paints: Protective and Marine Coatings; Pitthane Ultra Gloss 95-812 Series.
- 3) Sherwin-Williams Company (The): Protective & Marine; Acrolon 218 HS.

3.7 INTERIOR HIGH-PERFORMANCE COATING SCHEDULE

A. Concrete Substrates, Horizontal Surfaces.

1. Epoxy System MPI INT 3.2C:
 - a. Prime Coat: Epoxy, matching topcoat.
 - b. Intermediate Coat: Epoxy, matching topcoat.
 - c. Topcoat: Epoxy, Semi-gloss, MPI #177.
 - 1) Benjamin Moore & Co: Corotech; Polyamide Epoxy Semi-Gloss.
 - 2) Sherwin-Williams Company (The): Protective & Marine; Macropoxy 646 Fast Cure Epoxy.

END OF SECTION

SECTION 10 28 00
TOILET, BATH, AND LAUNDRY ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Public-use washroom accessories.
- B. Related Requirements:
 - 1. Section 061053 "Miscellaneous Rough Carpentry".
 - 2. Section 093013 "Ceramic Tiling".

1.3 COORDINATION

- A. Coordinate accessory locations with other work to prevent interference with clearances required for access by people with disabilities, and for proper installation, adjustment, operation, cleaning, and servicing of accessories.
- B. Deliver inserts and anchoring devices set into concrete or masonry as required to prevent delaying the Work.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
 - 2. Include anchoring and mounting requirements, including requirements for cutouts in other work and substrate preparation.
 - 3. Include electrical characteristics.
- B. Samples: Full size, for each exposed product and for each finish specified.
 - 1. Approved full-size Samples will be returned and may be used in the Work.
- C. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.
 - 1. Identify locations using room designations indicated.
 - 2. Identify accessories using designations indicated.

1.5 INFORMATIONAL SUBMITTALS

- A. Sample Warranty: For manufacturer's special warranty.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For accessories to include in maintenance manuals.

1.7 WARRANTY

- A. Manufacturer's Special Warranty for Mirrors: Manufacturer agrees to repair or replace mirrors that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, visible silver spoilage defects.
2. Warranty Period: 15 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURER

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. AJW Architectural Products.
 2. American Specialties, Inc.
 3. Bobrick Washroom Equipment, Inc.
 4. Bradley Corporation.
 5. Royce Rolls Ringer Co.
 6. Approved Substitution.

2.2 PUBLIC-USE WASHROOM ACCESSORIES

- A. Source Limitations: Obtain public-use washroom accessories from single source from single manufacturer.
- B. Toilet Tissue (Roll) Dispenser:
1. Basis of Design Product: TP-3; Royce Rolls Ringer Co.
 2. Description: Triple-roll dispenser.
 3. Mounting: Surface mounted.
 4. Operation Noncontrol delivery with theft-resistant spindles locked with padlock.
 5. Capacity: Designed for three 4-1/2-inch-diameter tissue rolls.
 6. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).
- C. Liquid-Soap Dispenser:
1. Basis of Design Product: 6562; Bradley
 2. Description: Designed for dispensing antibacterial soap in liquid or lotion form.
 3. Mounting: Horizontally oriented, surface mounted.
 4. Capacity: 40 oz.
 5. Materials: Satin Finish Stainless Steel with Chrome-Plated Brass Valve
 6. Lockset: Tumbler type.
 7. Refill Indicator: Window type.
- D. Grab Bar:
1. Basis of Design Product: 857; Bradley
 2. Mounting: Flanges with exposed fasteners.
 3. Material: Stainless steel, 0.05 inch thick.
 - a. Finish: Smooth, ASTM A480/A480M No. 4 finish (satin).
 4. Outside Diameter: 1 inch.
 5. Configuration and Length: As indicated on Drawing Sheet AE410.
- E. Mirror Unit:
1. Basis of Design Product: 748; Bradley.
 2. Frame: Frameless.
 - a. Corners: Manufacturer's standard.
 3. Hangers: Tempered hardboard backer bonded to mirror with adhesive.
 4. Size: As indicated on Drawing Sheet AE410.

2.3 HAND DRYERS

- A. Source Limitations: Obtain hand dryers from single source from single manufacturer.
- B. High-Speed Air Dryer:
1. Description: High-speed, warm-air hand dryer for rapid hand drying.

2. Mounting: Surface mounted.
 - a. Protrusion Limit: Installed unit protrudes maximum 4 inches (102 mm) from wall surface.
3. Operation: Infrared-sensor activated with timed power cut-off switch.
 - a. Average Dry Time: 12 seconds.
 - b. Automatic Shut Off: At 60 seconds.
4. Maximum Sound Level: 69 dB.
5. Cover Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).
6. Electrical Requirements: 115 V, 15 A, 1200 W.

2.4 CUSTODIAL ACCESSORIES

- A. Source Limitations: Obtain custodial accessories from single source from single manufacturer.
- B. Custodial Mop and Broom Holder:
 1. Basis of Design Product: 9983; Bradley
 2. Description: Unit with shelf, hooks, holders, and rod suspended beneath shelf.
 3. Length: 36 inches.
 4. Hooks: Two.
 5. Mop/Broom Holders: Three, spring-loaded, rubber hat, cam type.
 6. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).
 - a. Shelf: Not less than nominal 0.05-inch-thick stainless steel.
 - b. Rod: Approximately 1/4-inch-diameter stainless steel.

2.5 MATERIALS

- A. Stainless Steel: ASTM A240/A240M or ASTM A666, Type 304, 0.031-inch minimum nominal thickness unless otherwise indicated.
- B. Brass: ASTM B19, flat products; ASTM B16/B16M, rods, shapes, forgings, and flat products with finished edges; or ASTM B30, castings.
- C. Steel Sheet: ASTM A1008/A1008M, Designation CS (cold rolled, commercial steel), 0.036-inch minimum nominal thickness.
- D. Galvanized-Steel Sheet: ASTM A653/A653M, with G60 hot-dip zinc coating.
- E. Galvanized-Steel Mounting Devices: ASTM A153/A153M, hot-dip galvanized after fabrication.
- F. Fasteners: Screws, bolts, and other devices of same material as accessory unit and tamper-and-theft resistant where exposed, and of galvanized steel where concealed.
- G. Chrome Plating: ASTM B456, Service Condition Number SC 2 (moderate service).
- H. Mirrors: ASTM C1503, Mirror Glazing Quality, clear-glass mirrors, nominal 6.0 mm thick.

2.6 FABRICATION

- A. General: Fabricate units with tight seams and joints, and exposed edges rolled. Hang doors and access panels with full-length, continuous hinges. Equip units for concealed anchorage and with corrosion-resistant backing plates.
- B. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to Owner's representative.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.
- B. Grab Bars: Install to withstand a downward load of at least 250 lbf, when tested according to ASTM F446.

3.2 ADJUSTING AND CLEANING

- A. Adjust accessories for unencumbered, smooth operation. Replace damaged or defective items.
- B. Remove temporary labels and protective coatings.
- C. Clean and polish exposed surfaces according to manufacturer's written instructions.

END OF SECTION

DIVISION 22 - PLUMBING

22 01 00	GENERAL REQUIREMENTS
22 05 00	COMMON WORK RESULTS FOR PLUMBING
22 05 19	METERS AND GAUGES FOR PLUMBING PIPING
22 05 23	GENERAL-DUTY VALVES FOR PLUMBING PIPING
22 05 29	HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT
22 05 48	VIBRATION AND SEISMIC CONTROLS FOR PLUMBING PIPING AND EQUIPMENT
22 05 53	PLUMBING IDENTIFICATION
22 07 00	PLUMBING INSULATION
22 11 16	DOMESTIC WATER PIPING
22 11 19	DOMESTIC WATER PIPING SPECIALTIES
22 13 16	SANITARY WASTE AND VENT PIPING
22 13 19	SANITARY WASTE PIPING SPECIALTIES
22 33 00	ELECTRIC WATER HEATERS
22 46 00	SECURITY PLUMBING FIXTURES

SECTION 22 01 00

GENERAL REQUIREMENTS

PART 1 GENERAL

1.1 GENERAL

- A. General Conditions and Division 01 apply to this Division.

1.2 SCOPE

- A. Includes -

1. Furnish all labor, materials, and equipment necessary for the completion of the mechanical and plumbing scope of work.
2. Furnish and install all motors specified in this Division and be responsible for the proper operation of electrical powered equipment furnished by this Division.
3. Furnish exact location of electrical connections and information on motor controls to Division 26.
4. Mechanical Contractor shall obtain the services of independent Test and Balance Agency.
5. Placing the air conditioning, heating, ventilating, and exhaust systems into full operation and continuing their operation during each working day of testing and balancing.
6. Making changes in pulleys, belts, and dampers, or adding dampers, as required for the correct balance as recommended by Balancing Contractor at no additional cost to Owner.
7. Air balance, final adjustment and test run.
8. The satisfactory performance of the completed systems is a requirement of this specification.

- B. Related Work Specified Elsewhere

1. Conduit, line voltage wiring, outlets, and disconnect switches specified in Division 26.
2. Magnetic starters and thermal protective devices (heaters) not a factory mounted integral part of packaged equipment are specified in Division 26.

1.3 SITE OBSERVATION

- A. The Contractor shall examine the site and understand the conditions which may affect the performance of work of this Division before submitting proposals for this work.
- B. No subsequent allowance for time or money will be considered for any consequence related to failure to examine existing site conditions.

1.4 DRAWINGS

- A. Mechanical drawings show general arrangement of piping, ductwork, equipment, etc; however, locations are to be regarded as shown diagrammatically only. Follow as closely as actual building construction and work of other trades will permit.
- B. Because of the small scale of mechanical drawings, it is not possible to indicate all offsets, fittings, and accessories which may be required. Investigate existing structural and finished conditions affecting this work and arrange work accordingly, providing such fittings, valves, and accessories required to meet conditions.
If changes in location of piping, equipment, ducts, etc. are required due to lack of coordination of work under this division, such changes shall be made without charge. Contractor shall review drawings with local and state agencies having jurisdiction and any changes required by them shall be brought to the attention of the Engineer prior to bidding or commencement of work. It is understood that while Drawings are to be followed as closely as circumstances permit, this Division will be held responsible for the installation of systems according to the true intent and meaning of the Contract Documents. Anything not clear or in conflict will be explained by making application to the Engineer in writing. Should conditions arise where certain changes would be advisable, secure Owner's and Engineer approval for these changes before proceeding with work.

1.5 COORDINATION OF WORK:

- A. Coordinate work of various trades in installing interrelated work. Before installation of mechanical items, make proper provision to avoid interferences in a manner approved by Engineer. Changes required in work specified in Division 22 and 23 caused by neglect to secure approval shall be made at no cost to Owner.
- B. Arrange piping, ductwork, and equipment to permit ready access to valves, unions, starters, motors, control components, and to clear openings of doors and access panels. Contractor shall provide all necessary access doors and/or panels to provide complete access to all mechanical equipment, dampers, or accessories. Doors for dampers, etc. shall be minimum 12" x 12" and doors for mechanical equipment shall be minimum 24" x 24".
- C. Furnish and install inserts and supports required by Division 22 and 23 unless otherwise noted. Furnish sleeves, inserts, supports, and equipment that are an integral part of other Divisions involved in sufficient time to be built into the construction as the Work proceeds. Locate these items and see that they are properly installed. Expense resulting from improper location or installation of items above shall be borne by Contractor.
- D. Be responsible for required digging, cutting, and patching incident to work of this Division and make required repairs afterwards to satisfaction of Owner and Architect. Cut carefully to minimize necessity for repairs to existing work. Do not cut beams, columns, or trusses.
 - 1. Patch and repair walls, floors and roofs with materials of same quality and appearance as adjacent surfaces unless otherwise shown. Surface finishes shall exactly match existing finishes of same materials.
 - 2. This Division shall bear expense of cutting, patching, repairing, and replacing of work of other Divisions because of its fault, error, tardiness, or because of damage done by it.
 - 3. Provide the necessary cutting, patching, repairing, and replacing pavements, sidewalks, etc. to permit installation of work of this Division.
- E. Adjust locations of piping, ductwork, equipment, etc, to accommodate work from interferences anticipated and encountered. Determine exact route and location of each pipe and cut prior to fabrication.

1. Make offsets, transitions, and changes in direction of piping, ductwork, and electrical raceways as required to maintain proper head room and pitch of sloping lines whether or not indicated on Drawings.
- F. Slots and openings through floors, walls and roofs shall be provided by this Division.
- G. This Contractor shall schedule his work, store his equipment and materials, and work in harmony with other Contractors so as to not delay or jeopardize the construction.
- H. This Division shall coordinate with electrical contractor to insure that all required components of control work are included and fully understood. Any discrepancies shall be called to the attention of the Engineer before completion of bids. No additional cost shall accrue to the Owner as a result of lack of such coordination.

1.6 EQUIPMENT & MATERIALS:

- A. Requests for substitution shall be received in writing a minimum of seven days prior to bidding. Prior acceptance shall be by Manufacturer's name only. Items not listed in this specification or subsequent addendums shall not be considered. No oral approvals will be acceptable. Manufacturers listed in this specification are acceptable only for items listed. All other items manufacturer wishes to bid must be prior approved. All equipment shall be subject to final review in accordance with "Project Submittals".
- B. Product Approvals -
 1. If approval is received to use other than specified items, responsibility for specified capacities and insuring that items to be furnished will fit space available lies with this Division.
 2. In the event other than specified equipment is used and will not fit job site conditions, this Division assumes responsibility for replacement with items named in Specification.
- C. Use domestic made pipe, pipe fittings, and motors on Project.
- D. Motor and equipment name plates as well as applicable UL labels shall be in place when Project is turned over to Owner.
- E. Insure that items to be furnished fit spaces available. Make necessary field measurements to ascertain space requirements including those for connections and furnish and install equipment of size and shape so final installation shall suit true intent and meaning of Contract Documents. Do not scale off drawings.
- F. All materials shall be of the best commercial quality obtainable, consistent with specified materials and for the purpose or function intended. Materials shall be new unless specifically excepted.
- G. Equipment catalog or model numbers shown define the basic equipment types and quality standard only. Catalog numbers shall not be considered as all inclusive and shall be verified to include all devices, controls, operators, and appurtenances necessary for the satisfactory and complete operation of the equipment.
- H. Follow manufacturer's directions in delivery, storage, protection, and installation of equipment and materials.

1. Promptly notify Engineer in writing of conflicts between requirements of Contract Documents and Manufacturer's directions and obtain Engineer's written instructions before proceeding with work. Contractor shall bear all expenses arising from correcting deficiencies of work that does not comply with Manufacturer's directions or such written instructions.
- I. Deliver equipment and material to site and tightly cover and protect against dirt, water, and chemical or mechanical injury but have readily accessible for inspection. Store items subject to moisture damage (such as controls) in a dry, heated space.

1.7 PROJECT SUBMITTALS:

- A. Furnish complete catalog data for manufactured items of equipment to be used in the Work to for review within 15 days after award of Contract.
- B. Submittal shall include, but not be limited to the following:
 1. equipment scheduled
 2. balancing contractor
 3. insulation
 4. grilles, and diffusers
 5. automatic temperature controls
 6. certificates of guarantee
 7. valves
 8. plumbing fixtures, accessories, and specialties
 9. any item for which more than one manufacturer is mentioned
- C. Submit a minimum of five copies of data in binders and index in same order and name as they appear in Specification. - Optional: Provide electronic submittals. Electronic submittals shall be in .pdf format, and shall be compiled into a single file, with bookmarks for each piece of equipment.
 1. State sizes, capacities, brand names, motor HP, electrical requirements, accessories, materials, gauges, dimensions, and other pertinent information.
 2. List on catalog covers page numbers of submitted items.
 3. Underline or highlight applicable data.
- D. If material or equipment is not as specified or submittal is not complete, it will be rejected.
- E. Catalog data or shop drawings for equipment which are noted as approved shall not supersede Contract Documents.
- F. Review comments shall not relieve this Division from responsibility for deviations from Contract Documents unless attention has been called to such deviations in writing at time of submission, nor shall they relieve this Division from responsibility for errors in items submitted.
- G. Check work described by catalog data with Contract Documents for deviations and errors.
- H. All items other than first named specified equipment shall show and state all exceptions and deviations taken and shall include design calculations and drawing layouts.

- I. The Contractor shall review the submittals prior to submission to the to make sure that the submittals are complete in all details. No submittal will be reviewed which does not bear the contractor's notation that such checking has been made.
- J. No partial submittals will be considered unless approved by the Engineer.
- K. Manufacturers' names shall be mentioned as acceptable prior to bidding.
- L. Contractor shall verify equipment dimensions to fit the spaces provided with sufficient clearance for servicing the equipment.
- M. Contractor shall review equipment submittals for compliance with schedules, specifications, and drawing plans and details. Equipment submittal shall show the proper arrangements to suit installation and maintenance such as motor location, access doors, filter removal, piping connections, etc.
- N. Equipment submittal sheets shall be clearly marked indicating equipment symbol and exact selection of proposed equipment. Submittals shall clearly indicate name of manufacturer of each item.
- O. For unacceptable items, the right shall be reserved to require the first named specified items.
- P. Where submittals are sent with any of the above listed information missing or are incomplete they will be returned to the contractor unchecked to be completed and resubmitted. No additional time or money shall be allowed for failure to provide complete submittals on the first review.
- Q. If an item requiring submittal review is ordered, purchased, shipped, or installed prior to the submittal review and is subsequently disapproved the item shall be removed from the job site and replaced with an approved item at contractors expense.

1.8 CLEANING & FINISHING:

- A. Contractor shall, at all times, keep the premises free from waste material and rubbish. Upon completion of this Section of the work, Contractor shall remove all surplus materials and rubbish; clean all spots resulting from the mechanical work from hardware, floors, glass, walls, etc.; do all required patching up and repair all work of other trades damaged by Contractor under this Section of the work, and leave the premises in a clean orderly condition. Clean heating and cooling coils, internally and externally, and replace all air filters prior to final mechanical inspection. Remove rust, plaster, dirt, grease and oil before painting, insulating, or exposing to view the equipment, piping, ductwork, etc. in completed structure. Refinish any damaged surfaces and leave in proper working order at final completion.

1.9 EQUIPMENT SERVICING:

- A. Prior to starting mechanical equipment, all motors, bearings and moving parts shall be properly oiled, greased and lubricated as required. Full and adequate maintenance service shall be given and upon completion all equipment shall be cleaned and checked and placed in perfect condition for the Owner.
- B. Amount and type of lubricant shall be per manufacturer's specification.

1.10 SUPERVISION:

- A. The Contractor shall supervise and direct the work with his best skill and attention. He will be solely responsible for the means, methods, techniques, sequences and procedures of construction. The Contractor will be responsible to see that the finished work complies accurately with the Contract Documents.

1.11 SAFETY REGULATIONS:

- A. Contractor shall provide equipment, supervision, construction, procedures, and everything necessary to assure safety of life or property.
- B. Refer also to General Condition and Special Conditions for protection clauses.

1.12 LEAK DAMAGE:

- A. Contractor shall be responsible for damages to the work of other Contractors or to the building, or to its contents, people, etc., caused by leaks in any of the equipment or piping installed by him through equipment or material failures, leaking joints or disconnected pipes, fittings, or by overflows and shall make at his own expense all repairs to fixtures, building interior, contents, paint, rugs, furniture, ceiling tile, and equipment so damaged.

1.13 TOOLS AND STORAGE OF EQUIPMENT:

- A. The Contractor shall furnish all necessary tools, staging and whatever may be necessary for the installation of this work and shall at all times protect this work and others, and the materials to be used therein from damage by the weather, accident and other causes, and shall repair and make good any damage thus occurring.

1.14 WORKMANSHIP:

- A. Workmanship shall be the best quality of its kind for respective industries, trades, crafts and practices and shall be acceptable in every respect to the Owner and Engineer. Nothing contained herein shall relieve the Contractor from performing good work, perfect in all details of construction.

1.15 TEMPORARY FACILITIES:

- A. Furnishing of temporary water, space heating, sanitary facilities, drainage lines, light and power will be as specified in Division 01 General Conditions. Contractor shall arrange to bring facilities to required location of premises. All expenses involved shall be paid by the Contractor as described in General and Special Conditions.

1.16 EQUIPMENT BASES:

- A. Provide reinforced concrete bases under boilers, chillers, pumps, air handling units, and other equipment as necessary or as indicated on the drawings. Coordinate work with Division 03.
- B. Bases shall be 6" high, above the finish floor. The base shall extend beyond the equipment 6" in all directions, where possible. Inserts and vibration isolation systems shall be provided and installed by the Mechanical Contractor at the time the concrete is poured to accommodate and anchor the equipment used. Coordinate with vibration isolation manufacturer's requirements and Section 22 and 23. Provide a one inch beveled edge all around.

1.17 BELT GUARDS:

- A. Shall be provided, properly enclosing each belt drive system. Guards shall be easily removable, constructed of expanded metal with suitable frames corresponding with SMACNA standard and with tachometer openings. Coordinate with equipment suppliers to avoid duplication of belt guards supplied with equipment. Guards shall comply with OSHA Regulations.

1.18 ELECTRICAL WORK:

- A. Power wiring to all electrically driven apparatus shall be done under the electrical contract. See Electrical Specifications.
- B. Unless specifically noted otherwise on documents, Electrical Contractor shall furnish and install all magnetic starters including properly sized heaters, and disconnect switches as indicated on drawings or required by code.
- C. The Contractor shall verify the proper operation of equipment furnished by him. Costs for repair, replacing, re-wiring and retesting shall be borne by the Contractor without additional costs to the Owner.
- D. Motors shall be as specified.

1.19 CONTRACTOR'S USE OF BUILDING EQUIPMENT:

- A. The Contractor may use equipment such as electric motors, fans, filters, etc. when permanently installed as part of the project and with the written permission of the Owner. As each piece of equipment is used, maintenance procedures approved by the manufacturer shall be followed, a careful record shall be kept of the time used, maintenance procedure following and of any difficulty experienced with equipment. The Contractor's records on the equipment shall be

submitted to the Owner upon acceptance of project. All fan belts and filter media shall be new at the beginning of the Mechanical System Operating Test Run and System Balancing. Wearing surfaces (such as bearings) shall be carefully inspected just prior to acceptance. Any excessive wear noted shall require replacement.

1.20 INSPECTION NOTICE:

- A. The following is a basic list of guideline items so that the Architect, district building inspector/Owner's representative can be at job site for these inspections as the building progresses. Mechanical Contractor shall inform these people one week in advance of test time.
1. Water tests on all sewer, waste, and rainwater piping prior to piping being concealed.
 2. Pressure tests on all water service piping.
 3. Pressure tests on hot, chilled, and condenser water supply and return piping.
 4. All duct work prior to installation of finished ceilings, including ductwork pressure testing.
 5. The initial start-up of mechanical equipment, etc.
 6. Any changes or problems occurring at job site.
 7. Inspect all vent flashings on roof prior to roofing.
 8. Periodic inspection at their discretion will be made to insure compliance to Contract Documents and codes. Contractor shall provide ladders, access and other assistance as requested during inspections.
 9. Control piping pressure tests.
 10. Final inspection before giving approval for final payment.

1.21 WARRANTY GUARANTEE:

- A. The Contractor shall warrant all materials and equipment to be of quality consistent with specifications as represented by manufacturer's published data.
- B. The Contractor shall guarantee that the installation and operation of the equipment shall be free from defects for a period of one year beginning at date of substantial completion and acceptance. The Contractor shall replace or repair any part of the installation that is found to be defective or incomplete within the guarantee period.
- C. The one year guarantee on equipment and systems shall commence when equipment has been demonstrated to work and has been accepted. (Example: If an equipment item fails to perform and it takes 9 months after substantial completion to correct, then the guarantee shall commence after the item has been demonstrated to perform and has been accepted.)
- D. Substantial completion and acceptance in no way relieves the Contractor from providing the systems and equipment as specified.

1.22 COMPLETION SCHEDULE:

- A. Start-up and verification of basic equipment items shall be done prior to the date of substantial completion with sufficient time to allow balancing and adjusting to be performed.

- B. At the time of the final inspection a date shall be agreed upon for completion of any remaining items. At least double the estimated cost of the work will be withheld from the Contractor's payment.

1.23 CODE REQUIREMENTS, FEES, AND PERMITS

- A. The work shall be installed in accordance with the following applicable codes, ordinances and standards unless otherwise specified. The codes and standards shall include but not be limited to and be of the latest and current editions.
 - 1. American Boiler and Affiliated Industries (AB and AI)
 - 2. American Gas Association (AGA)
 - 3. Air Movement and Control Association (AMCA)
 - 4. American National Standards Institute (ANSI)
 - 5. Air Conditioning & Refrigeration Institute (ARI)
 - 6. American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE) - ASHRAE 90.1-2007
 - 7. American Society of Mechanical Engineers (ASME)
 - 8. American Society of Testing Materials (ASTM)
 - 9. American Standards Association (ASA)
 - 10. American Water Works Association (AWWA)
 - 11. American Welding Society (AWS)
 - 12. Associated Air Balance Council (AABC)
 - 13. Heat Exchange Institute (HEI)
 - 14. Hydraulic Institute (HI)
 - 15. BR
 - 16. National Electrical Code (NEC)
 - 17. National Fire Protection Association (NFPA)
 - 18. Sheet Metal and Air Conditioning contractors National Association (SMACNA)
 - 19. Underwriters Laboratories (UL)
 - 20. International Building Code (IBC) 2012 Ed
 - 21. International Mechanical Code (IMC) 2012 Ed
 - 22. International Plumbing Code (IPC) with Utah Amendments 2012 Ed
 - 23. International Energy Conservation Code (IECC) 2009 Ed
 - 24. Utah State Safety Orders (OSHA/UOSH)
 - 25. Utah Fire Rating Bureau
 - 26. Utah Boiler and Pressure Vessel Law
 - 27. Utah Air Conservation Regulations/Waste Disposal regulations.
 - 28. ASHRAE Ventilation STD.62-2007
- B. Should drawings conflict with any code, the code shall govern. If drawings and specifications establish a quality exceeding the code, the drawings and specifications shall govern. If conflicts do exist among the drawings, specifications and codes, the same shall be brought to the attention of the Engineer in writing prior to bidding, otherwise Contractor shall comply with applicable codes.
- C. The latest edition of all codes shall be used.
- D. Contractor shall give all notices, obtain all necessary permits, file necessary plans, prepare documents and obtain approvals, and pay all fees required for completion of the mechanical and plumbing work outlined in this Division of the specifications and shown on the Mechanical Drawings.

1.24 OPERATION AND MAINTENANCE MANUAL FOR MECHANICAL SYSTEMS

- A. Upon completion of work and before final payment, Contractor shall furnish and deliver to the Owner, through the Engineer, installation, operation and maintenance manuals with instructions for all new materials and equipment used in the building. The contractor shall provide three (3) hard copies of the manuals, and three (3) CD's with electronic copies of the manuals. Electronic information shall be .PDF format. The CD's shall include the same information as the hard copies, and shall be organized in the same manner with electronic bookmarks for each section. CD case and the CD itself shall be labeled the same as the hard copies of the manuals.
- B. Bind Operation and Maintenance Manual for Mechanical Systems in a hard-backed piano hinge loose-leaf binder with strong sturdy cover. The project name shall be on the spine and the front of the binder. The front of the binder shall include the following information:

OPERATION
AND
MAINTENANCE
MANUAL
for MECHANICAL SYSTEMS of
(Name of Project)
(Location of Project)
(Date of Project Award)
(Name of Architect)

- C. Introduction
1. Title page including name of project, project number, date awarded and date of substantial completion.
 2. Second page shall contain the names, phone numbers and addresses of Architect, Consulting Engineers, Mechanical Contractor, and General Contractor.
 3. Third page shall include a Table of Contents for the entire manual.
- D. First Section - Summary information including:
1. First page shall contain the contractor's warranties.
 2. Second page shall contain a list of names, addresses and phone numbers of contractors and all sub-contractors and work to which each was assigned.
 3. Final page or pages shall contain an equipment list. The list shall contain each item of equipment or material for which a submittal was required giving ID or tag no as contained on the drawings make and model No. Serial No. Identification No. Location in building, function along with the name, address, and phone number of the supplier.
- E. Second Section - Mechanical Equipment O&M data including:
1. Mechanical maintenance schedule, including a lubrication list when necessary.
 2. Mechanical Equipment Operation and Maintenance Data including:
 - a. Equipment descriptions

- b. Detailed installation instruction, operating and maintenance instructions. Instructions include in a step by step manner identifying start-up, operating, shutdown and emergency action sequence sufficiently clear so a person unfamiliar with the equipment could perform its operations.
 - c. Equipment drawings, performance curves, operating characteristics, etc.
 - d. Name addresses and phone number of manufacturer, fabricator and local vender clearly printed or stamped on cover.
 - e. Complete parts listing which include catalog number, serial number, contract number or other accurate provision for ordering replacement and spare parts.
 - f. Certified drawings, where applicable, showing assembly of parts and general dimensions.
3. Approved Mechanical submittals
- F. Third Section - Plumbing Equipment O&M data including:
- 1. Section shall contain general product catalog cuts, as well as exploded view drawings with parts lists for all valves and other items with multiple parts.
 - 2. Approved Plumbing submittals
- G. Fourth Section - Controls O&M data including:
- 1. Sequence of Operation
 - 2. Description of each operating system included location of switches, breakers, thermostats, and control devices. Provide a single line diagram, showing set points, normal operating parameters for all loads, pressures, temperatures and flow check points; Describe all alarms and cautions for operation.
 - 3. Provide schematic control diagrams, panel diagrams, wiring diagrams, etc. for each separate fan system, chilled water system, hot water system, exhaust air system, pumps, etc. Each control diagram shall show a schematic representation of mechanical equipment and location of start-stop switches, insertion thermostats, thermometers, pressure gauges, automatic valves, etc. The correct reading for each control instrument shall be marked on the diagram.
- H. The Fifth Section shall contain a complete air and water test and balance report. The report shall contain the name, address and phone number of the agency. It shall also include:
- 1. Floor plans showing all air openings and thermometer locations clearly marked and cross referenced with data sheets. Format may be 8 1/2 x 11 or 11x14 if legible.
 - 2. Data sheets showing amount of air and water at each setting. See sections 230593.
 - 3. List of equipment with date of last calibration.
- I. Drawings and reproducible masters of drawings as required in individual specification sections, are not to be bound in volumes but are to be delivered separate with the maintenance manuals.
- J. See the following checklist for assistance in assembling manual:

Item #	Description	Y, N, or NA
1.	3 ring heavy duty binder with Project name, number and date on cover and project name on spine.	

2.	O&M manual on CD (with label on CD matching label on manual). Electronic copy shall be a PDF file with bookmarks that match the tabs in the hard copy.	
3.	Title Page [including project name, number, address, date awarded, date of substantial completion]	
4.	Second Page Contact List [including architect (if applicable), mechanical engineer, mechanical contractor, and general contractor (if applicable)]	
5.	Table of Contents	
6.	Section 1 - Summary	
A.	Warranty	
B.	Mechanical's Sub-contractor List	
C.	Vendor List	
D.	Equipment List	
7.	Section 2 – Mechanical Equipment	
A.	Maintenance Schedule (including lubrication list)	
B.	Mechanical Equipment O&M Data (for each piece of equipment submitted) per specifications	
C.	Approved mechanical submittals	
8.	Section 3 – Plumbing Equipment	
A.	Plumbing equipment O&M data	
B.	Approved plumbing submittals	
9.	Section 4 - Controls	
A.	Sequence of Operation	
B.	Controls diagrams	
C.	Controls Equipment	
10.	Section 5 – Test and Balance Report	
A.	Complete Test and Balance Report per specifications	

1.25 OPERATION AND MAINTENANCE INSTRUCTIONS

- A. Contractor shall instruct building maintenance personnel in the operation and maintenance of the installed mechanical systems utilizing the Operation and Maintenance Manual when so doing.
- B. Minimum instruction periods shall be as follows -
 - 1. Mechanical - Two hours.
 - 2. Plumbing - Two hours.
 - 3. Temperature Control - Two hours.
- C. Instruction periods shall occur before final site observation when systems are properly working and before final payment is made.
- D. None of these instructional periods shall overlap each other.

- E. An additional four hours of instruction will be provided by each contractor, after 60 days of system operation by owner to insure proper system operation and answer questions.

1.26 RECORD DRAWINGS

- A. Contractor shall keep an up-to-date set of mechanical and plumbing drawings in his custody showing all changes in red, clearly defined and neatly drafted by him. At the end of construction, he shall turn these drawings over to the Engineer. Record drawings must be completed and submitted prior to final site observation

PART 2 - PRODUCTS
(Not Used)

PART 3 - EXECUTION
(Not Used)

END OF SECTION

SECTION 22 05 00

COMMON WORK RESULTS FOR PLUMBING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Piping materials and installation instructions common to most piping systems.
 - 2. Dielectric fittings.
 - 3. Mechanical sleeve seals.
 - 4. Sleeves.
 - 5. Escutcheons.
 - 6. Mechanical demolition.
 - 7. Equipment installation requirements common to equipment sections.

1.3 DEFINITIONS

- A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, crawlspace, and tunnels.
- B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- C. Exposed, Exterior Installations: Exposed to view outdoors or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- D. Concealed, Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in duct shafts.
- E. Concealed, Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.
- F. The following are industry abbreviations for plastic materials:
 - 1. ABS: Acrylonitrile-butadiene-styrene plastic.
 - 2. CPVC: Chlorinated polyvinyl chloride plastic.
 - 3. PVC: Polyvinyl chloride plastic.

1.4 SUBMITTALS

- A. Product Data: For the following:
 - 1. Dielectric fittings.
 - 2. Mechanical sleeve seals.
- B. Welding certificates.

1.5 QUALITY ASSURANCE

- A. Steel Pipe Welding: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications."
 - 1. Comply with provisions in ASME B31 Series, "Code for Pressure Piping."
 - 2. Certify that each welder has passed AWS qualification tests for welding processes involved and that certification is current.
- B. All materials, piping, etc. shall be new, and domestically made of the best commercial quality obtainable, consistent with specified materials and for the purpose or function intended unless specifically approved in writing prior to bid.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.
- B. Store plastic pipes protected from direct sunlight. Support to prevent sagging and bending.

1.7 COORDINATION

- A. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction, to allow for mechanical installations.
- B. Coordinate installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- C. Coordinate requirements for access panels and doors for mechanical items requiring access that are concealed behind finished surfaces.

1.8 PIPE, TUBE, AND FITTINGS

- A. Refer to individual Division 22 and 23 piping Sections for pipe, tube, and fitting materials and joining methods.
- B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.

1.9 JOINING MATERIALS

- A. Refer to individual Division 22 and 23 piping Sections for special joining materials not listed below.
- B. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.
 - 1. ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch maximum thickness unless thickness or specific material is indicated.
 - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.
 - 2. AWWA C110, rubber, flat face, 1/8 inch thick, unless otherwise indicated; and full-face or ring type, unless otherwise indicated.
- C. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.
- D. Plastic, Pipe-Flange Gasket, Bolts, and Nuts: Type and material recommended by piping system manufacturer, unless otherwise indicated.
- E. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- F. Brazing Filler Metals: AWS A5.8, BCuP Series, copper-phosphorus alloys for general-duty brazing, unless otherwise indicated; and AWS A5.8, BAg1, silver alloy for refrigerant piping, unless otherwise indicated.
- G. Welding Filler Metals: Comply with AWS D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.
- H. Solvent Cements for Joining Plastic Piping:
 - 1. ABS Piping: ASTM D 2235.
 - 2. CPVC Piping: ASTM F 493.
 - 3. PVC Piping: ASTM D 2564. Include primer according to ASTM F 656.
 - 4. PVC to ABS Piping Transition: ASTM D 3138.

1.10 DIELECTRIC FITTINGS

- A. Description: Combination fitting of copper alloy and ferrous materials with threaded, solder-joint, plain, or weld-neck end connections that match piping system materials.
- B. Insulating Material: Suitable for system fluid, pressure, and temperature.
- C. Dielectric Unions: Factory-fabricated, union assembly, for 250-psig minimum working pressure at 180 deg F.
 - 1. Available Manufacturers:
 - a. Capitol Manufacturing Co.
 - b. Central Plastics Company.
 - c. Eclipse, Inc.

- d. Epco Sales, Inc.
- e. Hart Industries, International, Inc.
- f. Watts Industries, Inc.; Water Products Div.
- g. Zurn Industries, Inc.; Wilkins Div.
- h. Prior Approved Equal.

1.11 MECHANICAL SLEEVE SEALS

A. Description: Modular sealing element unit, designed for field assembly, to fill annular space between pipe and sleeve.

1. Available Manufacturers:

- a. Advance Products & Systems, Inc.
- b. Calpico, Inc.
- c. Metraflex Co.
- d. Pipeline Seal and Insulator, Inc.
- e. Linkseal.
- f. Prior Approved Equal.

- 2. Sealing Elements: EPDM interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
- 3. Pressure Plates: Carbon steel. Include two for each sealing element.
- 4. Connecting Bolts and Nuts: Carbon steel with corrosion-resistant coating of length required to secure pressure plates to sealing elements. Include one for each sealing element.

1.12 SLEEVES

A. Galvanized-Steel Sheet: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.

B. Steel Pipe: ASTM A 53, Type E, Grade B, Schedule 40, galvanized, plain ends.

C. Cast Iron: Cast or fabricated "wall pipe" equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.

D. Molded PVC: Permanent, with nailing flange for attaching to wooden forms.

E. PVC Pipe: ASTM D 1785, Schedule 40.

1.13 ESCUTCHEONS

A. Description: Manufactured wall and ceiling escutcheons and floor plates, with an ID to closely fit around pipe, tube, and insulation of insulated piping and an OD that completely covers opening.

B. One-Piece, Stamped-Steel Type: With set screw or spring clips and chrome-plated finish.

1.14 GROUT

- A. Description: ASTM C 1107, Grade B, nonshrink and nonmetallic, dry hydraulic-cement grout.
 - 1. Characteristics: Post-hardening, volume-adjusting, nonstaining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.
 - 3. Packaging: Premixed and factory packaged.

PART 2 - EXECUTION

2.1 PIPING SYSTEMS - COMMON REQUIREMENTS

- A. Install piping according to the following requirements and Division 22 and 23 Sections specifying piping systems.
- B. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Drawings do not show every offset, or bend that may be required. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- C. Install piping in concealed locations, unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- F. Install piping to permit valve servicing.
- G. Install piping at indicated slopes.
- H. Install piping free of sags and bends.
- I. Install fittings for changes in direction and branch connections.
- J. Install piping to allow application of insulation.
- K. Select system components with pressure rating equal to or greater than system operating pressure.
- L. Install escutcheons for penetrations of walls, ceilings, and floors where indicated on drawings and where penetrating will be visible to public.
- M. Install sleeves for pipes passing through concrete and masonry walls, gypsum-board partitions, and concrete floor and roof slabs.
 - 1. Cut sleeves to length for mounting flush with both surfaces.

- a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified.
 - 2. Install sleeves in new walls and slabs as new walls and slabs are constructed.
 - 3. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation. Use the following sleeve materials:
 - 4. Except for underground wall penetrations, seal annular space between sleeve and pipe or pipe insulation, using joint sealants appropriate for size, depth, and location of joint.
- N. Aboveground, Exterior-Wall Pipe Penetrations: Seal penetrations using sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
- O. Underground, Exterior-Wall Pipe Penetrations: Install cast-iron "wall pipes" for sleeves. Seal pipe penetrations using mechanical sleeve seals. Select sleeve size to allow for 1-inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
- 1. Mechanical Sleeve Seal Installation: Select type and number of sealing elements required for pipe material and size. Position pipe in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.
- P. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials.
- Q. Verify final equipment locations for roughing-in.
- R. Refer to equipment specifications in other Sections of these Specifications for roughing-in requirements.

2.2 PIPING JOINT CONSTRUCTION

- A. Join pipe and fittings according to the following requirements and Division 22 and 23 Sections specifying piping systems.
- B. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- D. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.
- E. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8.
- F. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:

1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- G. Welded Joints: Construct joints according to AWS D10.12, using qualified processes and welding operators according to Part 1 "Quality Assurance" Article.
- H. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.
- I. Plastic Piping Solvent-Cement Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:
1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
 2. ABS Piping: Join according to ASTM D 2235 and ASTM D 2661 Appendixes.
 3. CPVC Piping: Join according to ASTM D 2846/D 2846M Appendix.
 4. PVC Pressure Piping: Join schedule number ASTM D 1785, PVC pipe and PVC socket fittings according to ASTM D 2672. Join other-than-schedule-number PVC pipe and socket fittings according to ASTM D 2855.
 5. PVC Nonpressure Piping: Join according to ASTM D 2855.
 6. PVC to ABS Nonpressure Transition Fittings: Join according to ASTM D 3138 Appendix.
- J. Plastic Nonpressure Piping Gasketed Joints: Join according to ASTM D 3212.

2.3 PIPING CONNECTIONS

- A. Make connections according to the following, unless otherwise indicated:
1. Install unions, in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.
 2. Install flanges, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.
 3. Dry Piping Systems: Install dielectric unions and flanges to connect piping materials of dissimilar metals.
 4. Wet Piping Systems: Install dielectric coupling and nipple fittings to connect piping materials of dissimilar metals.

2.4 EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

- A. Install equipment to allow maximum possible headroom unless specific mounting heights are not indicated.
- B. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.
- C. Install mechanical equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.
- D. Install equipment to allow right of way for piping installed at required slope.

END OF SECTION

SECTION 22 05 19

METERS AND GAGES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Bimetallic-actuated thermometers.
2. Filled-system thermometers.
3. Liquid-in-glass thermometers.
4. Light-activated thermometers.
5. Thermowells.
6. Dial-type pressure gages.
7. Gage attachments.
8. Test plugs.
9. Test-plug kits.
10. Sight flow indicators.

- B. Related Sections:

1. Division 2 Section "Water Distribution" for domestic water meters and combined domestic and fire-protection water-service meters outside the building.
2. Division 2 Section "Facility Fire-Suppression Water-Service Piping" for fire-protection water-service meters outside the building.
3. Division 22 Section "Domestic Water Piping" for water meters inside the building.

- C. Product Data: For each type of product indicated.

- D. Product Certificates: For each type of meter and gage, from manufacturer.

- E. Operation and Maintenance Data: For meters and gages to include in operation and maintenance manuals.

- F. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Ashcroft Inc.
2. Ernst Flow Industries.
3. Marsh Bellofram.
4. Miljoco Corporation.
5. Nanmac Corporation.
6. Noshok.
7. Palmer Wahl Instrumentation Group.
8. REOTEMP Instrument Corporation.

9. Tel-Tru Manufacturing Company.
 10. Terice, H. O. Co.
 11. Watts Regulator Co.; a div. of Watts Water Technologies, Inc.
 12. Weiss Instruments, Inc.
 13. WIKA Instrument Corporation - USA.
 14. Winters Instruments - U.S.
 15. Prior approved equal.
- G. Standard: ASME B40.200.
- H. Case: Liquid-filled type(s); stainless steel with 3-inch nominal diameter.
- I. Dial: Nonreflective aluminum with permanently etched scale markings and scales in deg F.
- J. Connector Type(s): Union joint, adjustable angle, with unified-inch screw threads.
- K. Connector Size: 1/2 inch, with ASME B1.1 screw threads.
- L. Stem: 0.25 or 0.375 inch in diameter; stainless steel.
- M. Window: plastic.
- N. Ring: Stainless steel.
- O. Element: Bimetal coil.
- P. Pointer: Dark-colored metal.
- Q. Accuracy: Plus or minus 1.5 percent of scale range.

1.3 FILLED-SYSTEM THERMOMETERS

- A. Direct-Mounted, Metal-Case, Vapor-Actuated Thermometers:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ashcroft Inc.
 - b. Marsh Bellofram.
 - c. Miljoco Corporation.
 - d. Palmer Wahl Instrumentation Group.
 - e. REOTEMP Instrument Corporation.
 - f. Terice, H. O. Co.
 - g. Weiss Instruments, Inc.
 - h. Prior approved equal.
 2. Standard: ASME B40.200.
 3. Case: Sealed type, cast aluminum or drawn steel; 4-1/2-inch nominal diameter.
 4. Element: Bourdon tube or other type of pressure element.
 5. Movement: Mechanical, with link to pressure element and connection to pointer.
 6. Dial: Nonreflective aluminum with permanently etched scale markings graduated in deg F.
 7. Pointer: Dark-colored metal.
 8. Window: plastic.

9. Ring: Stainless steel.
10. Connector Type(s): Union joint, rigid, back; with ASME B1.1 screw threads.
11. Thermal System: Liquid-filled bulb in copper-plated steel, aluminum, or brass stem and of length to suit installation.
 - a. Design for Thermowell Installation: Bare stem.
12. Accuracy: Plus or minus 1 percent of scale range.

1.4 THERMOWELLS

A. Thermowells:

1. Standard: ASME B40.200.
2. Description: Pressure-tight, socket-type fitting made for insertion into piping tee fitting.
3. Material for Use with Copper Tubing: CNR.
4. Material for Use with Steel Piping: CRES.
5. Type: Stepped shank unless straight or tapered shank is indicated.
6. External Threads: NPS 1/2, NPS 3/4, or NPS 1, ASME B1.20.1 pipe threads.
7. Internal Threads: 1/2, 3/4, and 1 inch, with ASME B1.1 screw threads.
8. Bore: Diameter required to match thermometer bulb or stem.
9. Insertion Length: Length required to match thermometer bulb or stem.
10. Lagging Extension: Include on thermowells for insulated piping and tubing.
11. Bushings: For converting size of thermowell's internal screw thread to size of thermometer connection.

B. Heat-Transfer Medium: Mixture of graphite and glycerin.

1.5 PRESSURE GAGES

A. Direct-Mounted, Metal-Case, Dial-Type Pressure Gages:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. AMETEK, Inc.; U.S. Gauge.
 - b. Ashcroft Inc.
 - c. Ernst Flow Industries.
 - d. Flo Fab Inc.
 - e. Marsh Bellofram.
 - f. Miljoco Corporation.
 - g. Noshok.
 - h. Palmer Wahl Instrumentation Group.
 - i. REOTEMP Instrument Corporation.
 - j. Tel-Tru Manufacturing Company.
 - k. Trerice, H. O. Co.
 - l. Watts Regulator Co.; a div. of Watts Water Technologies, Inc.
 - m. Weiss Instruments, Inc.
 - n. WIKA Instrument Corporation - USA.
 - o. Winters Instruments - U.S.
 - p. Prior approved equal.
2. Standard: ASME B40.100.

3. Case: Liquid-filled type(s); cast aluminum or drawn steel; 4-1/2-inch nominal diameter.
4. Pressure-Element Assembly: Bourdon tube unless otherwise indicated.
5. Pressure Connection: Brass, with NPS 1/2, ASME B1.20.1 pipe threads and bottom-outlet type unless back-outlet type is indicated.
6. Movement: Mechanical, with link to pressure element and connection to pointer.
7. Dial: Nonreflective aluminum with permanently etched scale markings graduated in psi.
8. Pointer: Dark-colored metal.
9. Window: plastic.
10. Ring: Metal.
11. Accuracy: Grade B, plus or minus 2 percent of middle half of scale range.

1.6 GAGE ATTACHMENTS

- A. Snubbers: ASME B40.100, brass; with NPS 1/2, ASME B1.20.1 pipe threads and porous-metal-type surge-dampening device. Include extension for use on insulated piping.
- B. Valves: Brass ball, with NPS 1/2, ASME B1.20.1 pipe threads.

1.7 TEST PLUGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. Flow Design, Inc.
 2. Miljoco Corporation.
 3. National Meter, Inc.
 4. Peterson Equipment Co., Inc.
 5. Sisco Manufacturing Company, Inc.
 6. Trerice, H. O. Co.
 7. Watts Regulator Co.; a div. of Watts Water Technologies, Inc.
 8. Weiss Instruments, Inc.
 9. Prior approved equal.
- B. Description: Test-station fitting made for insertion into piping tee fitting.
- C. Body: Brass or stainless steel with core inserts and gasketed and threaded cap. Include extended stem on units to be installed in insulated piping.
- D. Thread Size: NPS 1/2, ASME B1.20.1 pipe thread.
- E. Minimum Pressure and Temperature Rating: 200 deg F.
- F. Core Inserts: Chlorosulfonated polyethylene synthetic and EPDM self-sealing rubber.

1.8 TEST-PLUG KITS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. Flow Design, Inc.
 2. Miljoco Corporation.
 3. National Meter, Inc.

4. Peterson Equipment Co., Inc.
 5. Sisco Manufacturing Company, Inc.
 6. Trerice, H. O. Co.
 7. Watts Regulator Co.; a div. of Watts Water Technologies, Inc.
 8. Weiss Instruments, Inc.
 9. Prior approved equal.
- B. Furnish one test-plug kit(s) containing one thermometer(s), one pressure gage and adapter, and carrying case. Thermometer sensing elements, pressure gage, and adapter probes shall be of diameter to fit test plugs and of length to project into piping.
 - C. Low-Range Thermometer: Small, bimetallic insertion type with 1- to 2-inch- diameter dial and tapered-end sensing element. Dial range shall be at least 25 to 125 deg F.
 - D. Pressure Gage: Small, Bourdon-tube insertion type with 2- to 3-inch- diameter dial and probe. Dial range shall be at least 0 to 200 psig.
 - E. Carrying Case: Metal or plastic, with formed instrument padding.

PART 2 - EXECUTION

2.1 INSTALLATION

- A. Install thermowells with socket extending to center of pipe and in vertical position in piping tees.
- B. Install thermowells of sizes required to match thermometer connectors. Include bushings if required to match sizes.
- C. Install thermowells with extension on insulated piping.
- D. Fill thermowells with heat-transfer medium.
- E. Install direct-mounted thermometers in thermowells and adjust vertical and tilted positions.
- F. Install remote-mounted thermometer bulbs in thermowells and install cases on panels; connect cases with tubing and support tubing to prevent kinks. Use minimum tubing length.
- G. Install direct-mounted pressure gages in piping tees with pressure gage located on pipe at the most readable position.
- H. Install remote-mounted pressure gages on panel.
- I. Install valve and snubber in piping for each pressure gage for fluids.
- J. Install test plugs in piping tees.
- K. Install thermometers in the following locations:
 1. Outlet of each water heater.
- L. Install pressure gages in the following locations:

1. Inlet and outlet of each pressure-reducing valve.

2.2 CONNECTIONS

- A. Install meters and gages adjacent to machines and equipment to allow service and maintenance of meters, gages, machines, and equipment.

2.3 ADJUSTING

- A. Adjust faces of meters and gages to proper angle for best visibility.

2.4 THERMOMETER SCHEDULE

- A. Thermometers at inlet and outlet of each domestic water heater shall be one of the following:
 1. Liquid-filled, bimetallic-actuated type.
 2. Direct-mounted, metal-case, vapor-actuated type.
 3. Compact-style, liquid-in-glass type.
 4. Test plug with chlorosulfonated polyethylene synthetic self-sealing rubber inserts.
- B. Thermometer stems shall be of length to match thermowell insertion length.

2.5 THERMOMETER SCALE-RANGE SCHEDULE

- A. Scale Range for Domestic Hot-Water Piping: 0 to 250 deg F.

2.6 PRESSURE-GAGE SCHEDULE

- A. Pressure gages at discharge of each water service into building shall be one of the following:
 1. Liquid-filled, direct-mounted, metal case.
 2. Sealed, direct-mounted, plastic case.
 3. Test plug with chlorosulfonated polyethylene synthetic self-sealing rubber inserts.
- B. Pressure gages at inlet and outlet of each water pressure-reducing valve shall be one of the following:
 1. Liquid-filled, direct-mounted, metal case.
 2. Sealed, direct-mounted, plastic case.
 3. Test plug with chlorosulfonated polyethylene synthetic self-sealing rubber inserts.

2.7 PRESSURE-GAGE SCALE-RANGE SCHEDULE

- A. Scale Range for Water Service Piping: 0 to 200 psi.

END OF SECTION

SECTION 22 05 23

GENERAL- DUTY VALVES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following general-duty valves:
 - 1. Bronze ball valves.
 - 2. Ferrous-alloy butterfly valves.
 - 3. Bronze check valves.
- B. Related Sections include the following:
 - 1. Division 22 and 23 Section "Mechanical Identification" for valve tags and charts.
 - 2. Division 22 and 23 Section "HVAC Instrumentation and Controls" for control valves and actuators.
 - 3. Division 22 and 23 piping Sections for specialty valves applicable to those Sections only.

1.3 DEFINITIONS

- A. The following are standard abbreviations for valves:
 - 1. CWP: Cold working pressure.
 - 2. EPDM: Ethylene-propylene-diene terpolymer rubber.
 - 3. NRS: Nonrising stem.
 - 4. OS&Y: Outside screw and yoke.
 - 5. PTFE: Polytetrafluoroethylene plastic.
 - 6. SWP: Steam working pressure.
 - 7. TFE: Tetrafluoroethylene plastic.

1.4 SUBMITTALS

- A. Product Data: For each type of valve indicated. Include body, seating, and trim materials; valve design; pressure and temperature classifications; end connections; arrangement; dimensions; and required clearances. Include list indicating valve and its application. Include rated capacities; shipping, installed, and operating weights; furnished specialties; and accessories.

1.5 QUALITY ASSURANCE

- A. ASME Compliance: ASME B31.9 for building services piping valves.

1. Exceptions: Domestic hot- and cold-water piping valves unless referenced.
- B. ASME Compliance for Ferrous Valves: ASME B16.10 and ASME B16.34 for dimension and design criteria.
- C. NSF Compliance: NSF 61 for valve materials for potable-water service.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
 1. Protect internal parts against rust and corrosion.
 2. Protect threads, flange faces, grooves, and weld ends.
 3. Set angle, gate, and globe valves closed to prevent rattling.
 4. Set ball and plug valves open to minimize exposure of functional surfaces.
 5. Set butterfly valves closed or slightly open.
 6. Block check valves in either closed or open position.
- B. Use the following precautions during storage:
 1. Maintain valve end protection.
 2. Store valves indoors and maintain at higher than ambient dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use handwheels or stems as lifting or rigging points.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where subparagraph titles below introduce lists, the following requirements apply for product selection:
 1. Manufacturers: Subject to compliance with requirements, provide products by the manufacturers specified.

2.2 VALVES, GENERAL

- A. Refer to Part 3 "Valve Applications" Article for applications of valves.
- B. Bronze valves shall be made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted.
- C. Bronze Valves: NPS 2 and smaller with threaded ends, unless otherwise indicated.
- D. Ferrous Valves: NPS 2-1/2 and larger with flanged ends, unless otherwise indicated.
- E. Valve Pressure and Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.

- F. Valve Sizes: Same as upstream pipe, unless otherwise indicated.
- G. Valves in Insulated Piping: Valves shall have 2-inch stem extensions and the following features:
 - 1. Gate Valves: Shall be rising-stem type.
 - 2. Ball Valves: Shall have extended operating handle of non-thermal-conductive material, protective sleeve that allows operation of valve without breaking the vapor seal or disturbing insulation, and memory stops that are fully adjustable after insulation is applied.
 - a. Manufactures: NIBCO Nib-seal handle extension or a comparable product by one of the following:
 - 1) Conbraco Industries, Inc.; Apollo Div.
 - 2) American.
 - 3) Crane.
 - 4) Grinnel.
 - 5) Kitz.
 - 6) Watts.
 - 7) Prior approved equal.
 - 3. Butterfly Valves: Shall have extended necks.
- H. Valve Flanges: ASME B16.1 for cast-iron valves, ASME B16.5 for steel valves, and ASME B16.24 for bronze valves.
- I. Valve Grooved Ends: AWWA C606.
- J. Solder Joint: With sockets according to ASME B16.18.
 - 1. Caution: Use solder with melting point below 840 deg F for angle, check, gate, and globe valves; below 421 deg F for ball valves.
- K. Threaded: With threads according to ASME B1.20.1.
- L. Valve Bypass and Drain Connections: MSS SP-45.

2.3 BRONZE BALL VALVES

- A. Bronze Ball Valves, General: MSS SP-110 and have bronze body complying with ASTM B 584, except for Class 250 which shall comply with ASTM B 61, full-depth ASME B1.20.1 threaded or solder ends, and blowout-proof stems.
- B. Two-Piece, Full-Port, Bronze Ball Valves with Bronze Trim: Chrome-plated bronze ball and bronze stem and; reinforced TFE seats; threaded body packnut design (no threaded stem designs allowed) with adjustable stem packing, solder or threaded ends; and 150 psig SWP 600-psigCWP rating.
 - 1. Manufacturers: NIBCO Model S-585-70 or T-585-70, or a comparable product by one of the following:
 - a. NIBCO Model S-585-70 or T-585-70
 - b. American Valve, Inc.

- c. Conbraco Industries, Inc.; Apollo Div.
- d. Crane Co.; Crane Valve Group; Jenkins Valves.
- e. Crane Co.; Crane Valve Group; Stockham Div.
- f. Grinnell Corporation.
- g. Kitz Corporation of America.
- h. NIBCO INC.
- i. Watts Industries, Inc.; Water Products Div.

2.4 BRONZE CHECK VALVES

- A. Bronze Check Valves, General: MSS SP-80.
- B. Class 125, Bronze, Lift Check Valves with TFE Disc: ASTM B-584 bronze body and integral seat with soldered or threaded end connections, and having 250-psig CWP rating.
 - 1. Manufacturers: NIBCO Model S-480-Y or T-480-Y, or a comparable product by one of the following:
 - a. Cincinnati Valve Co.
 - b. Crane Co.; Crane Valve Group; Crane Valves.
 - c. Crane Co.; Crane Valve Group; Stockham Div.
 - d. Red-White Valve Corp.
 - e. Walworth Co.
- C. Class 125, Bronze, Lift Check Valves with BUNA Disc: ASTM B-584 bronze body and integral seat with nonmetallic BUNA disc, soldered or threaded end connections, and having 250-psig CWP rating.
 - 1. Manufacturers: NIBCO Model S-480 or T-480, or a comparable product by one of the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Powell, Wm. Co.
- D. Class 300, Bronze, Swing Check Valves with Bronze Disc: ASTM B-61 bronze body and seat with regrinding-type bronze disc, Y-pattern design, threaded end connections, and having 600 psig CWP rating.
 - 1. Manufacturers: NIBCO Model T-473-B, or a comparable product by one of the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Powell, Wm. Co.
- E. Class 125, Bronze, Swing Check Valves with TFE Disc: ASTM B-62 bronze body and seat with TFE disc in bronze seat holder, Y-pattern design, soldered or threaded end connections, and having 200 psig CWP rating.
 - 1. Manufacturers: NIBCO Model S-413-Y or T-413-Y, or a comparable product by one of the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Powell, Wm. Co.

- F. Class 125, Bronze, Swing Check Valves with BUNA Disc: ASTM B-62 bronze body and seat with BUNA disc in bronze seat holder, Y-pattern design, soldered or threaded end connections, and having 200 psig CWP rating.
1. Manufacturers: NIBCO Model S-413-W or T-413-W, or a comparable product by one of the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Powell, Wm. Co.
- G. Class 150, Bronze, Swing Check Valves with TFE Disc: ASTM B-62 bronze body and seat with TFE disc in bronze seat holder, Y-pattern design, soldered or threaded end connections, and having 300 psig CWP rating.
1. Manufacturers: NIBCO Model S-433-Y or T-433-Y, or a comparable product by one of the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Powell, Wm. Co.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine piping system for compliance with requirements for installation tolerances and other conditions affecting performance.
1. Proceed with installation only after unsatisfactory conditions have been corrected.
- B. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- C. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.
- D. Examine threads on valve and mating pipe for form and cleanliness.
- E. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.
- F. Do not attempt to repair defective valves; replace with new valves.

3.2 VALVE APPLICATIONS

- A. Refer to piping Sections for specific valve applications. If valve applications are not indicated, use the following:
1. Shutoff Service: Ball or butterfly valves.
 2. Throttling Service: Angle, ball, butterfly, or globe valves.

3. Pump Discharge: Spring-loaded, lift-disc or dual-plate check valves; lever and weight swing check valves; or lever and spring swing check valves.
- B. If valves with specified SWP classes or CWP ratings are not available, the same types of valves with higher SWP class or CWP ratings may be substituted.
 - C. Domestic Water Piping: Use the following types of valves:
 1. Ball Valves, NPS 2 and Smaller: Two -piece, full port, stainless-steel trim, bronze.
 2. Lift Check Valves, NPS 2 and Smaller: Class 125 , bronze with TFE disc.
 - D. Select valves, except wafer and flangeless types, with the following end connections:
 1. For Copper Tubing, NPS 2 and Smaller: Solder-joint or threaded ends, except provide valves with threaded ends for heating hot water.

3.3 VALVE INSTALLATION

- A. Piping installation requirements are specified in other Division 22 and 23 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- C. Locate valves for easy access and provide separate support where necessary.
- D. Install valves in horizontal piping with stem at or above center of pipe. Butterfly valves may be installed with stem horizontal to allow support for the disc and the cleaning action of the disc.
- E. Install valves in position to allow full stem movement.
- F. Install check valves for proper direction of flow and as follows:
 1. Swing Check Valves: In horizontal position with hinge pin level.
 2. Dual-Plate Check Valves: In horizontal or vertical position, between flanges.
 3. Lift Check Valves: With stem upright and plumb.
- G. Butterfly valves shall be installed with stems horizontal.

3.4 JOINT CONSTRUCTION

- A. Refer to Division 22 and 23 Section "Basic Mechanical Materials and Methods" for basic piping joint construction.
- B. Grooved Joints: Assemble joints with keyed coupling housing, gasket, lubricant, and bolts according to coupling and fitting manufacturer's written instructions.
- C. Soldered Joints: Use ASTM B 813, water-flushable, lead-free flux; ASTM B 32, lead-free-alloy solder; and ASTM B 828 procedure, unless otherwise indicated.

3.5 ADJUSTING

- A. Adjust or replace valve packing after piping systems have been tested and put into service but before final adjusting and balancing. Replace valves if persistent leaking occurs.

END OF SECTION

SECTION 22 05 29

HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following hangers and supports for plumbing system piping and equipment:
 - 1. Trapeze pipe hangers.
 - 2. Fiberglass pipe hangers.
 - 3. Metal framing systems.
 - 4. Fiberglass strut systems.
 - 5. Thermal-hanger shield inserts.
 - 6. Fastener systems.
 - 7. Pipe stands.
 - 8. Pipe positioning systems.
 - 9. Equipment supports.
- B. Related Sections include the following:
 - 1. Division 5 Section "Metal Fabrications" for structural-steel shapes and plates for trapeze hangers for pipe and equipment supports.
 - 2. Division 13 Section "Fire-Suppression Piping" for pipe hangers for fire-suppression piping.
 - 3. Division 22 and 23 Section "Expansion Fittings and Loops for Plumbing Piping" for pipe guides and anchors.
 - 4. Division 22 and 23 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment" for vibration isolation devices.

1.3 DEFINITIONS

- A. MSS: Manufacturers Standardization Society for The Valve and Fittings Industry Inc.
- B. Terminology: As defined in MSS SP-90, "Guidelines on Terminology for Pipe Hangers and Supports."

1.4 PERFORMANCE REQUIREMENTS

- A. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.

- B. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
- C. Design seismic-restraint hangers and supports for piping and equipment and obtain approval from authorities having jurisdiction.

1.5 SUBMITTALS

- A. Product Data: For the following:
 - 1. Steel pipe hangers and supports.
 - 2. Fiberglass pipe hangers.
 - 3. Thermal-hanger shield inserts.
 - 4. Powder-actuated fastener systems.
 - 5. Pipe positioning systems.
- B. Shop Drawings: Signed and sealed by a qualified professional engineer. Show fabrication and installation details and include calculations for the following:
 - 1. Trapeze pipe hangers. Include Product Data for components.
 - 2. Metal framing systems. Include Product Data for components.
 - 3. Fiberglass strut systems. Include Product Data for components.
 - 4. Pipe stands. Include Product Data for components.
 - 5. Equipment supports.
- C. Welding certificates.

1.6 QUALITY ASSURANCE

- A. Welding: Qualify procedures and personnel according to AWS D1.1, "Structural Welding Code--Steel."
- B. Welding: Qualify procedures and personnel according to the following:
 - 1. AWS D1.1, "Structural Welding Code--Steel."
 - 2. AWS D1.2, "Structural Welding Code--Aluminum."
 - 3. AWS D1.4, "Structural Welding Code--Reinforcing Steel."
 - 4. ASME Boiler and Pressure Vessel Code: Section IX.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, manufacturers specified.
 - 2. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.2 TRAPEZE PIPE HANGERS

- A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural-steel shapes with MSS SP-58 hanger rods, nuts, saddles, and U-bolts.

2.3 FIBERGLASS PIPE HANGERS

- A. Clevis-Type, Fiberglass Pipe Hangers: Similar to MSS Type 1, steel pipe hanger except hanger is made of fiberglass and continuous-thread rod and nuts are made of polyurethane or stainless steel.

- 1. Manufacturers:

- a. B-Line Systems, Inc.; a division of Cooper Industries.
- b. Champion Fiberglass, Inc.
- c. Cope, T. J., Inc.; Tyco International, Ltd.
- d. Seasafe, Inc.
- e. Unistrut Corp.; Tyco International, Ltd.
- f. Wesanco, Inc.

- B. Strap-Type, Fiberglass Pipe Hangers: Made of fiberglass loop with stainless-steel continuous-thread rod, nuts, and support hook.

- 1. Manufacturers:

- a. Plasti-Fab, Inc.

2.4 METAL FRAMING SYSTEMS

- A. Description: MFMA-3, shop- or field-fabricated pipe-support assembly made of steel channels and other components.

- B. Manufacturers:

- 1. B-Line Systems, Inc.; a division of Cooper Industries.
- 2. ERICO/Michigan Hanger Co.; ERISTRUT Div.
- 3. GS Metals Corp.
- 4. Power-Strut Div.; Tyco International, Ltd.
- 5. Thomas & Betts Corporation.
- 6. Tolco Inc.
- 7. Unistrut Corp.; Tyco International, Ltd.

- C. Coatings: Manufacturer's standard finish unless bare metal surfaces are indicated.

- D. Nonmetallic Coatings: Plastic coating, jacket, or liner.

2.5 FIBERGLASS STRUT SYSTEMS

- A. Description: Shop- or field-fabricated pipe-support assembly, similar to MFMA-3, made of fiberglass channels and other components.

- B. Manufacturers:

1. B-Line Systems, Inc.; a division of Cooper Industries.
2. Champion Fiberglass, Inc.
3. Cope, T. J., Inc.; Tyco International Ltd.
4. Seasafe, Inc.

2.6 THERMAL-HANGER SHIELD INSERTS

- A. Description: 100-psig- minimum, compressive-strength insulation insert encased in sheet metal shield.
- B. Manufacturers:
 1. Carpenter & Paterson, Inc.
 2. ERICO/Michigan Hanger Co.
 3. PHS Industries, Inc.
 4. Pipe Shields, Inc.
 5. Rilco Manufacturing Company, Inc.
 6. Value Engineered Products, Inc.
- C. Insulation-Insert Material for Cold Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate with vapor barrier.
- D. Insulation-Insert Material for Hot Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate.
- E. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- F. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- G. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.7 FASTENER SYSTEMS

- A. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
 1. Manufacturers:
 - a. Hilti, Inc.
 - b. ITW Ramset/Red Head.
 - c. Masterset Fastening Systems, Inc.
 - d. MKT Fastening, LLC.
 - e. Powers Fasteners.
- B. Mechanical-Expansion Anchors: Insert-wedge-type stainless steel, for use in hardened portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
 1. Manufacturers:
 - a. B-Line Systems, Inc.; a division of Cooper Industries.

- b. Empire Industries, Inc.
- c. Hilti, Inc.
- d. ITW Ramset/Red Head.
- e. MKT Fastening, LLC.
- f. Powers Fasteners.

2.8 PIPE STAND FABRICATION

- A. Pipe Stands, General: Shop or field-fabricated assemblies made of manufactured corrosion-resistant components to support roof-mounted piping.
- B. Compact Pipe Stand: One-piece plastic unit with integral-rod-roller, pipe clamps, or V-shaped cradle to support pipe, for roof installation without membrane penetration.
 - 1. Manufacturers:
 - a. ERICO/Michigan Hanger Co.
 - b. MIRO Industries.
- C. Low-Type, Single-Pipe Stand: One-piece stainless-steel base unit with plastic roller, for roof installation without membrane penetration.
 - 1. Manufacturers:
 - a. MIRO Industries.
- D. High-Type, Single-Pipe Stand: Assembly of base, vertical and horizontal members, and pipe support, for roof installation without membrane penetration.
 - 1. Manufacturers:
 - a. ERICO/Michigan Hanger Co.
 - b. MIRO Industries.
 - c. Portable Pipe Hangers.
 - 2. Base: Stainless steel.
 - 3. Vertical Members: Two or more cadmium-plated-steel or stainless-steel, continuous-thread rods.
 - 4. Horizontal Member: Cadmium-plated-steel or stainless-steel rod with plastic or stainless-steel, roller-type pipe support.
- E. High-Type, Multiple-Pipe Stand: Assembly of bases, vertical and horizontal members, and pipe supports, for roof installation without membrane penetration.
 - 1. Manufacturers:
 - a. Portable Pipe Hangers.
 - 2. Bases: One or more plastic.
 - 3. Vertical Members: Two or more protective-coated-steel channels.
 - 4. Horizontal Member: Protective-coated-steel channel.
 - 5. Pipe Supports: Galvanized-steel, clevis-type pipe hangers.

- F. Curb-Mounting-Type Pipe Stands: Shop- or field-fabricated pipe support made from structural-steel shape, continuous-thread rods, and rollers for mounting on permanent stationary roof curb.

2.9 PIPE POSITIONING SYSTEMS

- A. Description: IAPMO PS 42, system of metal brackets, clips, and straps for positioning piping in pipe spaces for plumbing fixtures for commercial applications.
- B. Manufacturers:
 - 1. C & S Mfg. Corp.
 - 2. HOLDRITE Corp.; Hubbard Enterprises.
 - 3. Samco Stamping, Inc.

2.10 EQUIPMENT SUPPORTS

- A. Description: Welded, shop- or field-fabricated equipment support made from structural-steel shapes.

2.11 MISCELLANEOUS MATERIALS

- A. Structural Steel: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
 - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT APPLICATIONS

- A. Specific hanger and support requirements are specified in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-69 for pipe hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized, metallic coatings for piping and equipment that will not have field-applied finish.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use padded hangers for piping that is subject to scratching.
- F. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated stationary pipes, NPS 1/2 to NPS 30.
2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of 120 to 450 deg F pipes, NPS 4 to NPS 16, requiring up to 4 inches of insulation.
3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes, NPS 3/4 to NPS 24, requiring clamp flexibility and up to 4 inches of insulation.
4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes, NPS 1/2 to NPS 24, if little or no insulation is required.
5. Pipe Hangers (MSS Type 5): For suspension of pipes, NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated stationary pipes, NPS 3/4 to NPS 8.
7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 8.
8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 8.
9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 2.
10. Split Pipe-Ring with or without Turnbuckle-Adjustment Hangers (MSS Type 11): For suspension of noninsulated stationary pipes, NPS 3/8 to NPS 8.
11. Extension Hinged or 2-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated stationary pipes, NPS 3/8 to NPS 3.
12. U-Bolts (MSS Type 24): For support of heavy pipes, NPS 1/2 to NPS 30.
13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
14. Pipe Saddle Supports (MSS Type 36): For support of pipes, NPS 4 to NPS 36, with steel pipe base stanchion support and cast-iron floor flange.
15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes, NPS 4 to NPS 36, with steel pipe base stanchion support and cast-iron floor flange and with U-bolt to retain pipe.
16. Adjustable, Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes, NPS 2-1/2 to NPS 36, if vertical adjustment is required, with steel pipe base stanchion support and cast-iron floor flange.
17. Single Pipe Rolls (MSS Type 41): For suspension of pipes, NPS 1 to NPS 30, from 2 rods if longitudinal movement caused by expansion and contraction might occur.
18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes, NPS 2-1/2 to NPS 20, from single rod if horizontal movement caused by expansion and contraction might occur.
19. Complete Pipe Rolls (MSS Type 44): For support of pipes, NPS 2 to NPS 42, if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.
20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes, NPS 2 to NPS 24, if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.
21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes, NPS 2 to NPS 30, if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.

G. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers, NPS 3/4 to NPS 20.
2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers, NPS 3/4 to NPS 20, if longer ends are required for riser clamps.

- H. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
 3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
 4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
 5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.
- I. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction to attach to top flange of structural shape.
 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 6. C-Clamps (MSS Type 23): For structural shapes.
 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
 11. Malleable Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 12. Welded-Steel Brackets: For support of pipes from below, or for suspending from above by using clip and rod. Use one of the following for indicated loads:
 - a. Light (MSS Type 31): 750 lb.
 - b. Medium (MSS Type 32): 1500 lb.
 - c. Heavy (MSS Type 33): 3000 lb.
 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- J. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
 3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.
- K. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41 roll hanger with springs.
 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from hanger.
 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from base support.
 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from trapeze support.
 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.
 - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- L. Comply with MSS SP-69 for trapeze pipe hanger selections and applications that are not specified in piping system Sections.
- M. Comply with MFMA-102 for metal framing system selections and applications that are not specified in piping system Sections.
- N. Use mechanical-expansion anchors instead of building attachments where required in concrete construction.
- O. Use pipe positioning systems in pipe spaces behind plumbing fixtures to support supply and waste piping for plumbing fixtures.

3.2 HANGER AND SUPPORT INSTALLATION

- A. Steel Pipe Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.
- B. Trapeze Pipe Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping and support together on field-fabricated trapeze pipe hangers.
1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified above for individual pipe hangers.
 2. Field fabricate from ASTM A 36/A 36M, steel shapes selected for loads being supported. Weld steel according to AWS D1.1.

- C. Fiberglass Pipe Hanger Installation: Comply with applicable portions of MSS SP-69 and MSS SP-89. Install hangers and attachments as required to properly support piping from building structure.
- D. Metal Framing System Installation: Arrange for grouping of parallel runs of piping and support together on field-assembled metal framing systems.
- E. Fiberglass Strut System Installation: Arrange for grouping of parallel runs of piping and support together on field-assembled fiberglass struts.
- F. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.
- G. Fastener System Installation:
 - 1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual.
 - 2. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.
- H. Pipe Stand Installation:
 - 1. Pipe Stand Types except Curb-Mounting Type: Assemble components and mount on smooth roof surface. Do not penetrate roof membrane.
 - 2. Curb-Mounting-Type Pipe Stands: Assemble components or fabricate pipe stand and mount on permanent, stationary roof curb. Refer to Division 7 Section "Roof Accessories" for curbs.
- I. Pipe Positioning System Installation: Install support devices to make rigid supply and waste piping connections to each plumbing fixture. Refer to Division 22 and 23 Section "Plumbing Fixtures" for plumbing fixtures.
- J. Install hangers and supports complete with necessary inserts, bolts, rods, nuts, washers, and other accessories.
- K. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- L. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- M. Install lateral bracing with pipe hangers and supports to prevent swaying.
- N. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- O. Load Distribution: Install hangers and supports so piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- P. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and so maximum pipe deflections allowed by ASME B31.9 (for building services piping) are not exceeded.

Q. Insulated Piping: Comply with the following:

1. Attach clamps and spacers to piping.
 - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
 - b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits according to ASME B31.9 for building services piping.
2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
 - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
 - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
4. Shield Dimensions for Pipe: Not less than the following:
 - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
 - b. NPS 4: 12 inches long and 0.06 inch thick.
 - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
 - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
 - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
5. Pipes NPS 8 and Larger: Include wood inserts.
6. Insert Material: Length at least as long as protective shield.
7. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.3 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make smooth bearing surface.
- C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.4 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1 procedures for shielded metal arc welding, appearance and quality of welds, and methods used in correcting welding work, and with the following:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. Finish welds at exposed connections so no roughness shows after finishing and contours of welded surfaces match adjacent contours.

3.5 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.6 PAINTING

- A. Touch Up: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils.
- B. Touch Up: Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal are specified in Division 9 painting Sections.
- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION

SECTION 22 05 48

VIBRATION AND SEISMIC CONTROLS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Isolation pads.
 - 2. Freestanding and restrained spring isolators.
 - 3. Seismic snubbers.
 - 4. Restraining braces and cables.

1.3 SCOPE

- A. Provide letter of design intent.
- B. Provide full set of seismic submittals.
- C. Provide a minimum of 2 on site observations.
- D. Provide final letter of compliance completion.

1.4 DEFINITIONS

- A. IBC: International Building Code.
- B. ICC-ES: ICC-Evaluation Service.

1.5 PERFORMANCE REQUIREMENTS

- A. Wind-Restraint Loading:
 - 1. Basic Wind Speed: Per owner's design standards.
 - 2. Building Classification Category: As defined in the IBC.
 - 3. Minimum 10 lb/sq. ft. multiplied by the maximum area of the HVAC component projected on a vertical plane that is normal to the wind direction, and 45 degrees either side of normal.
- B. Seismic-Restraint Loading:

1. Site Class: As defined in the IBC.
2. Assigned Seismic Use Group or Building Category: As defined in the IBC.
 - a. Component Importance Factor: 1.0.

1.6 SUBMITTALS

- A. Product Data: For the following:
 1. Include rated load, rated deflection, and overload capacity for each vibration isolation device.
 2. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of seismic-restraint component used.
 - a. Tabulate types and sizes of seismic restraints, complete with report numbers and rated strength in tension and shear as evaluated by an evaluation service member of ICC-ES or an agency acceptable to authorities having jurisdiction.
 - b. Annotate to indicate application of each product submitted and compliance with requirements.
 3. Interlocking Snubbers: Include ratings for horizontal, vertical, and combined loads.
- B. Letter of Design intent, stating company, design criteria, compliance with specifications and only exceptions that will apply. Letter shall be stamped and signed by a licensed and qualified professional engineer in this jurisdiction.
- C. Delegated-Design Submittal: For vibration isolation and seismic-restraint details indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
 1. Design Calculations: Calculate static and dynamic loading due to equipment weight and operation, seismic and wind forces required to select vibration isolators, seismic and wind restraints, and for designing vibration isolation bases.
 - a. Coordinate design calculations with wind load calculations required for equipment mounted outdoors. Comply with requirements in other Division 22 and 23 Sections for equipment mounted outdoors.
 2. Riser Supports: Include riser diagrams and calculations showing anticipated expansion and contraction at each support point, initial and final loads on building structure, spring deflection changes, and seismic loads. Include certification that riser system has been examined for excessive stress and that none will exist.
 3. Vibration Isolation Base Details: Detail overall dimensions, including anchorages and attachments to structure and to supported equipment. Include auxiliary motor slides and rails, base weights, equipment static loads, power transmission, component misalignment, and cantilever loads.
 4. Seismic- and Wind-Restraint Details:
 - a. Design Analysis: To support selection and arrangement of seismic and wind restraints. Include calculations of combined tensile and shear loads.
 - b. Details: Indicate fabrication and arrangement. Detail attachments of restraints to the restrained items and to the structure. Show attachment locations, methods, and spacing's. Identify components, list their strengths, and indicate directions

and values of forces transmitted to the structure during seismic events. Indicate association with vibration isolation devices.

- c. Coordinate seismic-restraint and vibration isolation details with wind-restraint details required for equipment mounted outdoors. Comply with requirements in other Division 22 and 23 Sections for equipment mounted outdoors.
 - d. Preapproval and Evaluation Documentation: By an evaluation service member of ICC-ES or an agency acceptable to authorities having jurisdiction, showing maximum ratings of restraint items and the basis for approval (tests or calculations).
- D. Coordination Drawings: Show coordination of seismic bracing for HVAC piping and equipment with other systems and equipment in the vicinity, including other supports and seismic restraints.
 - E. Welding certificates.
 - F. Qualification Data: For professional engineer and testing agency.
 - G. Field quality-control test reports.

1.7 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a nationally recognized testing laboratory (NRTL) as defined by OSHA in 29 CFR 1910.7, and that is acceptable to authorities having jurisdiction.
- B. Comply with seismic-restraint requirements in the IBC unless requirements in this Section are more stringent.
- C. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- D. Seismic-restraint devices shall have horizontal and vertical load testing and analysis and shall bear anchorage preapproval OPA number from OSHPD, preapproval by ICC-ES, or preapproval by another agency acceptable to authorities having jurisdiction, showing maximum seismic-restraint ratings. Ratings based on independent testing are preferred to ratings based on calculations. If preapproved ratings are not available, submittals based on independent testing are preferred. Calculations (including combining shear and tensile loads) to support seismic-restraint designs must be signed and sealed by a qualified professional engineer.
- E. Provide a minimum of 2 site observations, and additional observations if required.
- F. Upon project completion provide a final letter of acceptance for seismic restraints system and installation.

PART 2 - PRODUCTS

2.1 VIBRATION ISOLATORS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Amber/Booth Company, Inc.
 2. Vibro-acoustics.
 3. ISAT
 4. Mason Industries.
 5. Prior approved equal.
- B. Pads: Arranged in single or multiple layers of sufficient stiffness for uniform loading over pad area, molded with a nonslip pattern and galvanized-steel baseplates, and factory cut to sizes that match requirements of supported equipment.
1. Resilient Material: Oil- and water-resistant neoprene or rubber.
- C. Restrained Spring Isolators: Freestanding, steel, open-spring isolators with seismic or limit-stop restraint.
1. Housing: Steel with resilient vertical-limit stops to prevent spring extension due to weight being removed; factory-drilled baseplate bonded to 1/4-inch- thick, neoprene or rubber isolator pad attached to baseplate underside; and adjustable equipment mounting and leveling bolt that acts as blocking during installation.
 2. Restraint: Seismic or limit stop as required for equipment and authorities having jurisdiction.
 3. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 4. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 5. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
 6. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.

2.2 SEISMIC-RESTRAINT DEVICES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Amber/Booth Company, Inc.
 2. Hilti, Inc.
 3. ISAT
 4. Kinetics Noise Control.
 5. Mason Industries.
 6. Vibro-acoustics.
 7. Unistrut; Tyco International, Ltd.
 8. Prior approved equal.
- B. General Requirements for Restraint Components: Rated strengths, features, and applications shall be as defined in reports by an evaluation service member of ICC-ES or an agency acceptable to authorities having jurisdiction.
1. Structural Safety Factor: Allowable strength in tension, shear, and pullout force of components shall be at least four times the maximum seismic forces to which they will be subjected.
- C. Snubbers: Factory fabricated using welded structural-steel shapes and plates, anchor bolts, and replaceable resilient isolation washers and bushings.

1. Anchor bolts for attaching to concrete shall be seismic-rated, drill-in, and stud-wedge or female-wedge type.
 2. Resilient Isolation Washers and Bushings: Oil- and water-resistant neoprene.
 3. Maximum 1/4-inch air gap, and minimum 1/4-inch- thick resilient cushion.
- D. Channel Support System: MFMA-3, shop- or field-fabricated support assembly made of slotted steel channels with accessories for attachment to braced component at one end and to building structure at the other end and other matching components and with corrosion-resistant coating; and rated in tension, compression, and torsion forces.
- E. Restraint Cables: -steel cables with end connections made of steel assemblies with thimbles, brackets, swivel, and bolts designed for restraining cable service; and with a minimum of two clamping bolts for cable engagement.
- F. Hanger Rod Stiffener: Steel tube or steel slotted-support-system sleeve with internally bolted connections or Reinforcing steel angle clamped to hanger rod.
- G. Bushings for Floor-Mounted Equipment Anchor Bolts: Neoprene bushings designed for rigid equipment mountings, and matched to type and size of anchor bolts and studs.
- H. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for rigid equipment mountings, and matched to type and size of attachment devices used.
- I. Resilient Isolation Washers and Bushings: One-piece, molded, oil- and water-resistant neoprene, with a flat washer face.
- J. Mechanical Anchor Bolts: Drilled-in and stud-wedge or female-wedge type in zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488. Minimum length of eight times diameter.
- K. Adhesive Anchor Bolts: Drilled-in and capsule anchor system containing polyvinyl or urethane methacrylate-based resin and accelerator, or injected polymer or hybrid mortar adhesive. Provide anchor bolts and hardware with zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488.

2.3 FACTORY FINISHES

- A. Finish: Manufacturer's standard paint applied to factory-assembled and -tested equipment before shipping.
1. Powder coating on springs and housings.
 2. All hardware shall be galvanized. Hot-dip galvanize metal components for exterior use.
 3. Baked enamel or powder coat for metal components on isolators for interior use.
 4. Color-code or otherwise mark vibration isolation and seismic- and wind-control devices to indicate capacity range.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and equipment to receive vibration isolation and seismic- and wind-control devices for compliance with requirements for installation tolerances and other conditions affecting performance.
- B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLICATIONS

- A. Multiple Pipe Supports: Secure pipes to trapeze member with clamps approved for application by an evaluation service member of ICC-ES or an agency acceptable to authorities having jurisdiction.
- B. Hanger Rod Stiffeners: Install hanger rod stiffeners where indicated or scheduled on Drawings to receive them and where required to prevent buckling of hanger rods due to seismic forces.
- C. Strength of Support and Seismic-Restraint Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static and seismic loads within specified loading limits.

3.3 VIBRATION-CONTROL AND SEISMIC-RESTRAINT DEVICE INSTALLATION

- A. Equipment Restraints:
 - 1. Install seismic snubbers on HVAC equipment mounted on vibration isolators. Locate snubbers as close as possible to vibration isolators and bolt to equipment base and supporting structure.
 - 2. Install resilient bolt isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch.
 - 3. Install seismic-restraint devices using methods approved by an evaluation service member of ICC-ES or an agency acceptable to authorities having jurisdiction providing required submittals for component.
- B. Piping Restraints:
 - 1. Comply with requirements in MSS SP-127.
 - 2. Space lateral supports a maximum of 40 feet o.c., and longitudinal supports a maximum of 80 feet o.c.
 - 3. Brace a change of direction longer than 12 feet.
- C. Install cables so they do not bend across edges of adjacent equipment or building structure.
- D. Install seismic-restraint devices using methods approved by an evaluation service member of ICC-ES or an agency acceptable to authorities having jurisdiction providing required submittals for component.

- E. Install bushing assemblies for anchor bolts for floor-mounted equipment, arranged to provide resilient media between anchor bolt and mounting hole in concrete base.
- F. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- G. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, at upper truss chords of bar joists, or at concrete members.
- H. Drilled-in Anchors:
 1. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not damage existing reinforcing or embedded items during coring or drilling. Notify the structural engineer if reinforcing steel or other embedded items are encountered during drilling. Locate and avoid prestressed tendons, electrical and telecommunications conduit, and gas lines.
 2. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength.
 3. Wedge Anchors: Protect threads from damage during anchor installation. Heavy-duty sleeve anchors shall be installed with sleeve fully engaged in the structural element to which anchor is to be fastened.
 4. Adhesive Anchors: Clean holes to remove loose material and drilling dust prior to installation of adhesive. Place adhesive in holes proceeding from the bottom of the hole and progressing toward the surface in such a manner as to avoid introduction of air pockets in the adhesive.
 5. Set anchors to manufacturer's recommended torque, using a torque wrench.
 6. Install zinc-coated steel anchors for interior and stainless-steel anchors for exterior applications.

3.4 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

- A. Install flexible connections in piping where they cross seismic joints, where adjacent sections or branches are supported by different structural elements, and where the connections terminate with connection to equipment that is anchored to a different structural element from the one supporting the connections as they approach equipment. Comply with requirements in Division 23 Section "Hydronic Piping" for piping flexible connections.

3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Leave a qualified testing agency to perform tests and inspections.
- B. Perform tests and inspections.
- C. Tests and Inspections:
 1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.
 2. Schedule test with Owner, through Architect, before connecting anchorage device to restrained component (unless postconnection testing has been approved), and with at least seven days' advance notice.
 3. Obtain Architect's approval before transmitting test loads to structure. Provide temporary load-spreading members.

4. Test at least four of each type and size of installed anchors and fasteners selected by Architect.
 5. Test to 90 percent of rated proof load of device.
 6. Measure isolator restraint clearance.
 7. Measure isolator deflection.
 8. Verify snubber minimum clearances.
 9. If a device fails test, modify all installations of same type and retest until satisfactory results are achieved.
- D. Remove and replace malfunctioning units and retest as specified above.
- E. Prepare test and inspection reports.

3.6 ADJUSTING

- A. Adjust isolators after piping system is at operating weight.
- B. Adjust limit stops on restrained spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.
- C. Adjust air-spring leveling mechanism.
- D. Adjust active height of spring isolators.
- E. Adjust restraints to permit free movement of equipment within normal mode of operation.

3.7 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain air-mounting systems. Refer to Division 1 Section "Demonstration and Training."

END OF SECTION

SECTION 22 05 53

PLUMBING IDENTIFICATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following mechanical identification materials and their installation:
 - 1. Equipment nameplates.
 - 2. Equipment signs.
 - 3. Access panel and door markers.
 - 4. Pipe markers.
 - 5. Warning tags.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Valve numbering scheme.
- D. Valve Schedules: For each piping system. Furnish extra copies (in addition to mounted copies) to include in maintenance manuals.

1.4 QUALITY ASSURANCE

- A. ASME Compliance: Comply with ASME A13.1, "Scheme for the Identification of Piping Systems," for letter size, length of color field, colors, and viewing angles of identification devices for piping.

1.5 COORDINATION

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with location of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 EQUIPMENT IDENTIFICATION DEVICES

- A. Equipment Nameplates: Metal, with data engraved or stamped, for permanent attachment on equipment.
 - 1. Data:
 - a. Manufacturer, product name, model number, and serial number.
 - b. Capacity, operating and power characteristics, and essential data.
 - c. Labels of tested compliances.
 - 2. Location: Accessible and visible.
 - 3. Fasteners: As required to mount on equipment.
- B. Equipment Signs: ASTM D 709, Type I, cellulose, paper-base, phenolic-resin-laminate engraving stock; Grade ES-2, black surface, black phenolic core, with white melamine subcore, unless otherwise indicated. Fabricate in sizes required for message. Provide holes for mechanical fastening.
 - 1. Data: Instructions for operation of equipment and for safety procedures.
 - 2. Engraving: Manufacturer's standard letter style, 1/4" or larger with terms to match equipment identification.
 - 3. Thickness: 1/8 inch, unless otherwise indicated.
 - 4. Fasteners: Self-tapping, stainless-steel screws or contact-type, permanent adhesive.
- C. Access Panel and Door Markers: 1/16" thick, engraved laminated plastic, with abbreviated terms and numbers corresponding to identification. Provide 1/8" center hole for attachment.
 - 1. Fasteners: Self-tapping, stainless-steel screws or contact-type, permanent adhesive.

2.2 PIPING IDENTIFICATION DEVICES

- A. Manufactured Pipe Markers, General: Preprinted, color-coded, with lettering indicating service, and showing direction of flow.
 - 1. Colors: Comply with ASME A13.1, unless otherwise indicated.
 - 2. Lettering: Use piping system terms indicated and abbreviate only as necessary for each application length.
 - 3. Pipes with OD, Including Insulation, Less Than 6 Inches: Full-band pipe markers extending 360 degrees around pipe at each location.
 - 4. Pipes with OD, Including Insulation, 6 Inches and Larger: Either full-band or strip-type pipe markers at least three times letter height and of length required for label.
 - 5. Arrows: Integral with piping system service lettering to accommodate both directions; or as separate unit on each pipe marker to indicate direction of flow.
- B. Self-Adhesive Pipe Markers: Plastic with pressure-sensitive, permanent-type, self-adhesive back.

PART 3 - EXECUTION

3.1 APPLICATIONS, GENERAL

- A. Products specified are for applications referenced in other Division 22 and 23 Sections. If more than single-type material, device, or label is specified for listed applications, selection is Installer's option.

3.2 EQUIPMENT IDENTIFICATION

- A. Install and permanently fasten equipment nameplates on each major item of mechanical equipment that does not have nameplate or has nameplate that is damaged or located where not easily visible. Locate nameplates where accessible and visible. Include nameplates for the following general categories of equipment:
 - 1. Fuel-burning units, including boilers, furnaces, heaters, etc.
 - 2. Pumps, compressors, chillers, condensers, and similar motor-driven units.
 - 3. Heat exchangers, coils, evaporators, cooling towers, heat recovery units, and similar equipment.
 - 4. Fans, blowers, primary balancing dampers, and mixing boxes.
 - 5. Packaged HVAC central-station and zone-type units.
- B. Install equipment signs with screws or permanent adhesive on or near each major item of mechanical equipment. Locate signs where accessible and visible.
 - 1. Identify mechanical equipment with black equipment markers with white lettering.
 - 2. Letter Size: Minimum 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
 - 3. Data: Distinguish among multiple units, indicate operational requirements, indicate safety and emergency precautions, warn of hazards and improper operations, and identify units.
 - 4. Include signs for the following general categories of equipment:
 - a. Main control and operating valves, including safety devices and hazardous units such as gas outlets.
 - b. Fuel-burning units, including boilers, furnaces, heaters, etc.
 - c. Pumps, compressors, chillers, condensers, and similar motor-driven units.
 - d. Heat exchangers, coils, evaporators, cooling towers, heat recovery units, and similar equipment.
 - e. Fans, blowers, primary balancing dampers, and mixing boxes.
 - f. Packaged HVAC central-station and zone-type units.
 - g. Tanks and pressure vessels.
 - h. Strainers, filters, humidifiers, water-treatment systems, and similar equipment.
- C. Install access panel markers with screws on equipment access panels.

3.3 PIPING IDENTIFICATION

- A. Install manufactured pipe markers indicating service on each piping system. Install with flow indication arrows showing direction of flow.

- B. Locate pipe markers and color bands where piping is exposed in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior nonconcealed locations as follows:
 - 1. Near each valve and control device.
 - 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
 - 3. Near penetrations through walls, floors, ceilings, and nonaccessible enclosures.
 - 4. At access doors, manholes, and similar access points that permit view of concealed piping.
 - 5. Near major equipment items and other points of origination and termination.
 - 6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
 - 7. On piping above removable acoustical ceilings. Omit intermediately spaced markers.

- C. Locate markers near points where ducts enter into concealed spaces and at maximum intervals of 50 feet in each space where ducts are exposed or concealed by removable ceiling system.

3.4 ADJUSTING

- A. Relocate mechanical identification materials and devices that have become visually blocked by other work.

3.5 CLEANING

- A. Clean faces of mechanical identification devices and glass frames of valve schedules.

END OF SECTION

SECTION 22 07 00

HVAC AND PLUMBING INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Insulation Materials:
 - a. Mineral fiber.
 - 2. Insulating cements.
 - 3. Adhesives.
 - 4. Lagging adhesives.
 - 5. Factory-applied jackets.
 - 6. Field-applied jackets.
 - 7. Tapes.
 - 8. Securements.
 - 9. Corner angles.
- B. Related Sections:
 - 1. Division 23 Section "Metal Ducts" for duct liners.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated. Include thermal conductivity, thickness, and jackets (both factory and field applied, if any).
- B. Qualification Data: For qualified Installer.
- C. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.
- D. Field quality-control reports.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.
- B. Fire-Test-Response Characteristics: Insulation and related materials shall have fire-test-response characteristics indicated, as determined by testing identical products per ASTM E 84, by a testing and inspecting agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing and inspecting agency.
 - 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
 - 2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.6 COORDINATION

- A. Coordinate size and location of supports, hangers, and insulation shields specified in Division 22 and 23 Section "Hangers and Supports."
- B. Coordinate clearance requirements with piping Installer for piping insulation application, duct Installer for duct insulation application, and equipment Installer for equipment insulation application. Before preparing piping and ductwork Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.

1.7 SCHEDULING

- A. Schedule insulation application after pressure testing systems. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 INSULATION MATERIALS

- A. Comply with requirements in Part 3 schedule articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.

- C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.
- E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- F. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type I. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
 - 1. Duct insulation shall have a minimum R value = 5 for installation in an unconditioned space, and a minimum R value = 8 for installation outdoors. Provide a weather protective sheet metal jacket for outdoor installation.
 - 2. Products: Subject to compliance with requirements, provide one of the following:
 - a. CertainTeed Corp.; Duct Wrap.
 - b. Johns Manville; Microlite.
 - c. Knauf Insulation; Duct Wrap.
 - d. Manson Insulation Inc.; Alley Wrap.
 - e. Owens Corning; All-Service Duct Wrap.
 - f. Prior approved equal.
- G. Mineral-Fiber, Preformed Pipe Insulation:
 - 1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Fibrex Insulations Inc.; Coreplus 1200.
 - b. Johns Manville; Micro-Lok.
 - c. Knauf Insulation; 1000 Pipe Insulation.
 - d. Manson Insulation Inc.; Alley-K.
 - e. Owens Corning; Fiberglas Pipe Insulation.
 - f. Prior approved equal.
 - 2. Type I, 850 deg F Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A.

2.2 INSULATING CEMENTS

- A. Mineral-Fiber Insulating Cement: Comply with ASTM C 195.
 - 1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Insulco, Division of MFS, Inc.; Triple I.
 - b. P. K. Insulation Mfg. Co., Inc.; Super-Stik.
 - c. Prior approved equal.

2.3 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated, unless otherwise indicated.
- B. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.
 - 1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Childers Products, Division of ITW; CP-127.
 - b. Foster Products Corporation, H. B. Fuller Company; 85-60/ 85-70.
 - c. Marathon Industries, Inc.; 225.
 - d. Mon-Eco Industries, Inc.; 22-25.
 - e. Prior approved equal.

2.4 LAGGING ADHESIVES

- A. Description: Comply with MIL-A-3316C Class I, Grade A and shall be compatible with insulation materials, jackets, and substrates.
 - 1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Childers Products, Division of H.B. Fuller; CR 50 AHV2.
 - b. Foster Products Corporation, H. B. Fuller Company; 30-36.
 - c. Vimasco Corporation; 713 and 714.
 - d. Prior approved equal.
 - 2. Service Temperature Range: Minus 50 to plus 180 deg F.
 - 3. Color: White.

2.5 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
 - 1. ASJ: White, kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C 1136, Type I.
 - 2. ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C 1136, Type I.
 - 3. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with kraft-paper backing; complying with ASTM C 1136, Type II.

2.6 TAPES

- A. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C 1136.
 - 1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Avery Dennison Corporation, Specialty Tapes Division; Fasson 0836.
 - b. Compac Corp.; 104 and 105.
 - c. Ideal Tape Co., Inc., an American Biltrite Company; 428 AWF ASJ.

- d. Venture Tape; 1540 CW Plus, 1542 CW Plus, and 1542 CW Plus/SQ.
 - e. Prior approved equal.
2. Width: 3 inches.
 3. Thickness: 11.5 mils.
 4. Adhesion: 90 ounces force/inch in width.
 5. Elongation: 2 percent.
 6. Tensile Strength: 40 lbf/inch in width.
 7. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.
- B. FSK Tape: Foil-face, vapor-retarder tape matching factory-applied jacket with acrylic adhesive; complying with ASTM C 1136.
1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Avery Dennison Corporation, Specialty Tapes Division; Fasson 0827.
 - b. Compac Corp.; 110 and 111.
 - c. Ideal Tape Co., Inc., an American Biltrite Company; 491 AWF FSK.
 - d. Venture Tape; 1525 CW, 1528 CW, and 1528 CW/SQ.
 - e. Prior approved equal.
 2. Width: 3 inches.
 3. Thickness: 6.5 mils.
 4. Adhesion: 90 ounces force/inch in width.
 5. Elongation: 2 percent.
 6. Tensile Strength: 40 lbf/inch in width.
 7. FSK Tape Disks and Squares: Precut disks or squares of FSK tape.
 8. Adhesion: 64 ounces force/inch in width.
 9. Elongation: 500 percent.
 10. Tensile Strength: 18 lbf/inch in width.
- C. Aluminum-Foil Tape: Vapor-retarder tape with acrylic adhesive.
1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Avery Dennison Corporation, Specialty Tapes Division; Fasson 0800.
 - b. Compac Corp.; 120.
 - c. Ideal Tape Co., Inc., an American Biltrite Company; 488 AWF.
 - d. Venture Tape; 3520 CW.
 - e. Prior approved equal.
 2. Width: 2 inches.
 3. Thickness: 3.7 mils.
 4. Adhesion: 100 ounces force/inch in width.
 5. Elongation: 5 percent.
 6. Tensile Strength: 34 lbf/inch in width.

2.7 SECUREMENTS

- A. Bands:
1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Childers Products; Bands.

- b. PABCO Metals Corporation; Bands.
 - c. RPR Products, Inc.; Bands.
 - d. Prior approved equal.
2. Stainless Steel: ASTM A 167 or ASTM A 240/A 240M, Type 304 or Type 316; 0.015 inch thick, 1/2 inch wide.
 3. Aluminum: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 1/2 inch wide.
 4. Springs: Twin spring set constructed of stainless steel with ends flat and slotted to accept metal bands. Spring size determined by manufacturer for application.

2.8 CORNER ANGLES

- A. PVC Corner Angles: 30 mils thick, minimum 1 by 1 inch, PVC according to ASTM D 1784, Class 16354-C. White or color-coded to match adjacent surface.
- B. Aluminum Corner Angles: 0.040 inch thick, minimum 1 by 1 inch, aluminum according to ASTM B 209, Alloy 3003, 3005, 3105 or 5005; Temper H-14.
- C. Stainless-Steel Corner Angles: 0.024 inch thick, minimum 1 by 1 inch, stainless steel according to ASTM A 167 or ASTM A 240/A 240M, Type 304 or 316.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation and other conditions affecting performance of insulation application.
 1. Verify that systems and equipment to be insulated have been tested and are free of defects.
 2. Verify that surfaces to be insulated are clean and dry.
 3. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.
- B. Surface Preparation: Clean and prepare surfaces to be insulated.
- C. Mix insulating cements with clean potable water; if insulating cements are to be in contact with stainless-steel surfaces, use demineralized water.

3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of equipment, ducts and fittings, and piping including fittings, valves, and specialties.

- B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of equipment, duct system, and pipe system as specified in insulation system schedules.
- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.
- G. Keep insulation materials dry during application and finishing.
- H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- I. Install insulation with least number of joints practical.
- J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
 - 1. Install insulation continuously through hangers and around anchor attachments.
 - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
 - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
 - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.
- K. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- L. Install insulation with factory-applied jackets as follows:
 - 1. Draw jacket tight and smooth.
 - 2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
 - 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 2 inches o.c.
 - a. For below ambient services, apply vapor-barrier mastic over staples.
 - 4. Cover joints and seams with tape as recommended by insulation material manufacturer to maintain vapor seal.
 - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to duct and pipe flanges and fittings.

- M. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- N. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- O. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.
- P. For above ambient services, do not install insulation to the following:
 - 1. Vibration-control devices.
 - 2. Testing agency labels and stamps.
 - 3. Nameplates and data plates.
 - 4. Manholes.
 - 5. Handholes.
 - 6. Cleanouts.

3.4 GENERAL PIPE INSULATION INSTALLATION

- A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.
- B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:
 - 1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity, unless otherwise indicated.
 - 2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
 - 3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
 - 4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
 - 5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below ambient services, provide a design that maintains vapor barrier.
 - 6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.

7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below ambient services and a breather mastic for above ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.
 8. For services not specified to receive a field-applied jacket except for flexible elastomeric and polyolefin, install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing using PVC tape.
 9. Stencil or label the outside insulation jacket of each union with the word "UNION." Match size and color of pipe labels.
- C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes, vessels, and equipment. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.
- D. Install removable insulation covers at locations indicated. Installation shall conform to the following:
1. Make removable flange and union insulation from sectional pipe insulation of same thickness as that on adjoining pipe. Install same insulation jacket as adjoining pipe insulation.
 2. When flange and union covers are made from sectional pipe insulation, extend insulation from flanges or union long at least two times the insulation thickness over adjacent pipe insulation on each side of flange or union. Secure flange cover in place with stainless-steel or aluminum bands. Select band material compatible with insulation and jacket.
 3. Construct removable valve insulation covers in same manner as for flanges except divide the two-part section on the vertical center line of valve body.
 4. When covers are made from block insulation, make two halves, each consisting of mitered blocks wired to stainless-steel fabric. Secure this wire frame, with its attached insulation, to flanges with tie wire. Extend insulation at least 2 inches over adjacent pipe insulation on each side of valve. Fill space between flange or union cover and pipe insulation with insulating cement. Finish cover assembly with insulating cement applied in two coats. After first coat is dry, apply and trowel second coat to a smooth finish.
 5. Unless a PVC jacket is indicated in field-applied jacket schedules, finish exposed surfaces with a metal jacket.

3.5 MINERAL-FIBER INSULATION INSTALLATION

- A. Insulation Installation on Straight Pipes and Tubes:
1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
 2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
 3. For insulation with factory-applied jackets on above ambient surfaces, secure laps with outward clinched staples at 6 inches o.c.
 4. For insulation with factory-applied jackets on below ambient surfaces, do not staple longitudinal tabs but secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.
- B. Insulation Installation on Pipe Flanges:
1. Install preformed pipe insulation to outer diameter of pipe flange.

2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch, and seal joints with flashing sealant.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
4. Install insulation to flanges as specified for flange insulation application.

E. Blanket Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.

1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
 - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
 - b. On duct sides with dimensions larger than 18 inches, place pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
 - c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
 - d. Do not overcompress insulation during installation.
 - e. Impale insulation over pins and attach speed washers.
 - f. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.
4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from 1 edge and 1 end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.

- a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
 - b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to 2 times the insulation thickness but not less than 3 inches.
5. Overlap unfaced blankets a minimum of 2 inches on longitudinal seams and end joints. At end joints, secure with steel bands spaced a maximum of 18 inches o.c.
 6. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
 7. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch- wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

3.6 FIELD-APPLIED JACKET INSTALLATION

- A. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints; for horizontal applications, install with longitudinal seams along top and bottom of tanks and vessels. Seal with manufacturer's recommended adhesive.
 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

3.7 FIELD QUALITY CONTROL

- A. Tests and Inspections:
 1. Inspect ductwork, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location(s) for each duct system defined in the "Duct Insulation Schedule, General" Article.
 2. Inspect field-insulated equipment, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location(s) for each type of equipment defined in the "Equipment Insulation Schedule" Article. For large equipment, remove only a portion adequate to determine compliance.
 3. Inspect pipe, fittings, strainers, and valves, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to three locations of straight pipe, three locations of threaded fittings, three locations of welded fittings, two locations of threaded strainers, two locations of welded strainers, three locations of threaded valves, and three locations of flanged valves for each pipe service defined in the "Piping Insulation Schedule, General" Article.
- B. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

3.8 DUCT INSULATION SCHEDULE, GENERAL

A. Plenums and Ducts Requiring Insulation:

1. Indoor, concealed supply and outdoor air.
2. Indoor, exposed supply and outdoor air.
3. Indoor, concealed return, Air.
4. Indoor, exposed return, Air.
5. Indoor, concealed, Type I, commercial, kitchen hood exhaust.
6. Indoor, concealed exhaust.
7. Indoor, exposed exhaust.

B. Items Not Insulated:

1. Fibrous-glass ducts.
2. Metal ducts with duct liner of sufficient thickness to comply with energy code and ASHRAE/IESNA 90.1.
3. Factory-insulated flexible ducts.
4. Factory-insulated plenums and casings.
5. Flexible connectors.
6. Vibration-control devices.
7. Factory-insulated access panels and doors.

3.9 INDOOR DUCT AND PLENUM INSULATION SCHEDULE

A. Concealed, round and flat-oval duct insulation shall be the following:

1. Mineral-Fiber Blanket: 1-1/2 inches thick and 1.5-lb/cu. ft. nominal density.

B. Concealed, low pressure, round rectangular, and flat-oval exhaust-air duct insulation shall be the following:

1. Mineral-Fiber Blanket: 1-1/2 inches thick and 1.5-lb/cu. ft. nominal density.

C. Rectangular, low pressure, supply-air duct insulation shall be lined per Section "Metal Ducts".

D. Rectangular, return-air duct insulation shall be lined per Section "Metal Ducts".

E. Concealed, Type I, Commercial, Kitchen Hood Exhaust Duct and Plenum Insulation: Fire-rated blanket or board; thickness as required to achieve 2-hour fire rating.

F. Exposed or medium pressure, round and flat-oval, supply-air, and return air duct insulation shall be a perforated linear. See Section "Metal Ducts".

3.10 PIPING INSULATION SCHEDULE, GENERAL

A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.

B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:

1. Drainage piping located in crawl spaces.

2. Underground piping.
3. Chrome-plated pipes and fittings unless there is a potential for personnel injury.
4. Vertical roof drain piping.

C. Piping System insulation:

1. Domestic Cold Water Piping -Mineral Fiber, ½"
2. Domestic Hot Water Piping -Mineral Fiber, per chart

3.11 INDOOR PIPING INSULATION SCHEDULE

- A. Minimum Pipe Insulation Thickness from ANSI/ASHRAE/IESNA Standard 90.1-2016, with modifications per 2018 IECC

Fluid Operating Temperature Range and usage (F°)	Insulation Conductivity		Nominal Pipe or Tube Size (inches)				
	Conductivity Btu-in./(h-ft ² -F°)	Mean Rating Temp. F°	<1	1 to <1-1/2	1-1/2 to <4	4 to <8	≥8
Heating Systems (Hot Water)							
141-200	0.25-0.29	125	1.5	1.5	2.0	2.0	2.0
105-140	0.21-0.28	100	1.0	1.0	1.5	1.5	1.5

3.12 INDOOR, FIELD-APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Piping, Exposed:
1. PVC: 20 mils thick.
- D. Minimum Pipe Insulation Thickness from ANSI/ASHRAE/IESNA Standard 90.1-2016, with modifications per 2018 IECC

3.13 DUCT INSULATION SCHEDULE

- A. Minimum Duct Insulation R-Value, Cooling and Heating Supply Ducts and Return Ducts ANSI/ASHRAE/IES Standard 90.1-2016.

Duct Location							
Climate Zone	Exterior	Ventilated Attic	Unvented Attic	Unvented Attic with	Unconditioned Space	Indirectly Conditioned	Buried

			Above Insulated Ceiling	Roof Insulation		Space	
Heating- Only Ducts							
5	R-6	R-3.5	none	none	none	none	R-3.5
Cooling-Only Ducts							
5,6	R-3.5	R-1.9	R-3.5	R-1.9	R-1.9	none	none
Return Ducts							
1 to 8	R-3.5	R-3.5	R-3.5	none	none	none	none
Combine Heating and Cooling							
Supply Ducts							
5	R-6	R-6	R-6	R-1.9	R-3.5	none	R-3.5
Return Ducts							
1 to 8	R-3.5	R-3.5	R-3.5	none	none	none	none

3.14 OUTDOOR, FIELD APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Exterior piping, Exposed:
 - 1. Aluminum jacket.

END OF SECTION

SECTION 22 11 16
DOMESTIC WATER PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Under-building slab and aboveground domestic water pipes, tubes, fittings, and specialties inside the building.
 - 2. Flexible connectors.
 - 3. Escutcheons.
 - 4. Sleeves and sleeve seals.
 - 5. Wall penetration systems.

1.3 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Domestic water piping and support and installation shall withstand effects of earthquake motions determined according to 2006 IBC.

1.4 SUBMITTALS

- A. Product Data: For the following products:
 - 1. Specialty valves.
 - 2. Transition fittings.
 - 3. Dielectric fittings.
 - 4. Escutcheons.
 - 5. Sleeves and sleeve seals.
- B. Water Samples: Specified in "Cleaning" Article.
- C. Field quality-control reports.

1.5 QUALITY ASSURANCE

- A. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 61 for potable domestic water piping and components.

1.6 PROJECT CONDITIONS

- A. Interruption of Existing Water Service: Do not interrupt water service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary water service according to requirements indicated:
 - 1. Notify Owner no fewer than two days in advance of proposed interruption of water service.
 - 2. Do not proceed with interruption of water service without Owner's written permission.

1.7 COORDINATION

- A. Coordinate sizes and locations of concrete bases with actual equipment provided.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

- A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

2.2 COPPER TUBE AND FITTINGS

- A. Hard Copper Tube: ASTM B 88, Type L water tube, drawn temper.
 - 1. Cast-Copper Solder-Joint Fittings: ASME B16.18, pressure fittings.
 - 2. Wrought-Copper Solder-Joint Fittings: ASME B16.22, wrought-copper pressure fittings.
 - 3. Bronze Flanges: ASME B16.24, Class 150, with solder-joint ends.
 - 4. Copper Unions: MSS SP-123, cast-copper-alloy, hexagonal-stock body, with ball-and-socket, metal-to-metal seating surfaces, and solder-joint or threaded ends.

2.3 PIPING JOINING MATERIALS

- A. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- B. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys for general-duty brazing unless otherwise indicated.

2.4 ESCUTCHEONS

- A. General: Manufactured ceiling, floor, and wall escutcheons and floor plates.
- B. One Piece, Cast Brass: Polished, chrome-plated finish with setscrews.
- C. One Piece, Deep Pattern: Deep-drawn, box-shaped brass with chrome-plated finish.
- D. One Piece, Stamped Steel: Chrome-plated finish with setscrew or spring clips.

- E. Split Casting, Cast Brass: Polished, chrome-plated finish with concealed hinge and setscrew.
- F. Split Plate, Stamped Steel: Chrome-plated finish with concealed hinge, setscrew or spring clips.
- G. One-Piece Floor Plates: Cast-iron flange with holes for fasteners.
- H. Split-Casting Floor Plates: Cast brass with concealed hinge.

2.5 SLEEVES

- A. Cast-Iron Wall Pipes: Fabricated of cast iron, and equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.
- B. Galvanized-Steel-Sheet Sleeves: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- C. Molded-PE Sleeves: Reusable, PE, tapered-cup shaped, and smooth outer surface with nailing flange for attaching to wooden forms.
- D. Molded-PVC Sleeves: Permanent, with nailing flange for attaching to wooden forms.
- E. PVC-Pipe Sleeves: ASTM D 1785, Schedule 40.
- F. Galvanized-Steel-Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc-coated, with plain ends.
- G. Stack Sleeve Fittings: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring and bolts and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with setscrews.

2.6 SLEEVE SEALS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Advance Products & Systems, Inc.
 - 2. Calpico, Inc.
 - 3. Metraflex, Inc.
 - 4. Pipeline Seal and Insulator, Inc.
 - 5. Prior approved equal.
- B. Description: Modular sealing element unit, designed for field assembly, used to fill annular space between pipe and sleeve.
 - 1. Sealing Elements: EPDM-rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 2. Pressure Plates: Carbon steel.
 - 3. Connecting Bolts and Nuts: Carbon steel, with corrosion-resistant coating, of length required to secure pressure plates to sealing elements.

2.7 GROUT

- A. Standard: ASTM C 1107, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
- B. Characteristics: Nonshrink; recommended for interior and exterior applications.
- C. Design Mix: 5000-psi, 28-day compressive strength.
- D. Packaging: Premixed and factory packaged.

PART 3 - EXECUTION

3.1 EARTHWORK

- A. Comply with requirements in Division 2 Section "Earthwork" for excavating, trenching, and backfilling.

3.2 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of domestic water piping. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- B. Install copper tubing under building slab according to CDA's "Copper Tube Handbook."
- C. Install ductile-iron piping under building slab with restrained joints according to AWWA C600 and AWWA M41.
- D. Install underground copper tube and ductile-iron pipe in PE encasement according to ASTM A 674 or AWWA C105.
- E. Install shutoff valve, hose-end drain valve, strainer, pressure gage, and test tee with valve, inside the building at each domestic water service entrance. Comply with requirements in Division 22 and 23 Section "Meters and Gages for Plumbing Piping" for pressure gages and Division 22 Section "Domestic Water Piping Specialties" for drain valves and strainers.
- F. Install shutoff valve immediately upstream of each dielectric fitting.
- G. Install water-pressure-reducing valves downstream from shutoff valves. Comply with requirements in Division 22 Section "Domestic Water Piping Specialties" for pressure-reducing valves.
- H. Install domestic water piping level without pitch and plumb.
- I. Rough-in domestic water piping for water-meter installation according to utility company's requirements.
- J. Install seismic restraints on piping. Comply with requirements in Division 22 and 23 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment" for seismic-restraint devices.

- K. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- L. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- M. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.
- N. Install piping adjacent to equipment and specialties to allow service and maintenance.
- O. Install piping to permit valve servicing.
- P. Install nipples, unions, special fittings, and valves with pressure ratings the same as or higher than system pressure rating used in applications below unless otherwise indicated.
- Q. Install piping free of sags and bends.
- R. Install fittings for changes in direction and branch connections.
- S. Install unions in copper tubing at final connection to each piece of equipment, machine, and specialty.
- T. Install thermostats in hot-water circulation piping. Comply with requirements in Division 22 Section "Domestic Water Pumps" for thermostats.
- U. Install thermometers on outlet piping from each water heater. Comply with requirements in Division 22 and 23 Section "Meters and Gages for Plumbing Piping" for thermometers.

3.3 JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.
- C. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
- D. Brazed Joints: Join copper tube and fittings according to CDA's "Copper Tube Handbook," "Braze Joints" Chapter.
- E. Soldered Joints: Apply ASTM B 813, water-flushable flux to end of tube. Join copper tube and fittings according to ASTM B 828 or CDA's "Copper Tube Handbook."
- F. Flanged Joints: Select appropriate asbestos-free, nonmetallic gasket material in size, type, and thickness suitable for domestic water service. Join flanges with gasket and bolts according to ASME B31.9.

- G. Dissimilar-Material Piping Joints: Make joints using adapters compatible with materials of both piping systems.

3.4 VALVE INSTALLATION

- A. General-Duty Valves: Comply with requirements in Division 22 and 23 Section "General-Duty Valves for Plumbing Piping" for valve installations.
- B. Install shutoff valve close to water main on each branch and riser serving plumbing fixtures or equipment, on each water supply to equipment, and on each water supply to plumbing fixtures that do not have supply stops. Use ball or gate valves for piping NPS 2 and smaller. Use butterfly or gate valves for piping NPS 2-1/2 and larger.
- C. Install drain valves for equipment at base of each water riser, at low points in horizontal piping, and where required to drain water piping. Drain valves are specified in Division 22 Section "Domestic Water Piping Specialties."
 - 1. Hose-End Drain Valves: At low points in water mains, risers, and branches.
 - 2. Stop-and-Waste Drain Valves: Instead of hose-end drain valves where indicated.
- D. Install balancing valve in each hot-water circulation return branch and discharge side of each pump and circulator. Set balancing valves partly open to restrict but not stop flow. Use ball valves for piping NPS 2 and smaller and butterfly valves for piping NPS 2-1/2 and larger. Comply with requirements in Division 22 Section "Domestic Water Piping Specialties" for balancing valves.

3.5 TRANSITION FITTING INSTALLATION

- A. Install transition couplings at joints of dissimilar piping.
- B. Transition Fittings in Underground Domestic Water Piping:
 - 1. NPS 1-1/2 and Smaller: Fitting-type coupling.
 - 2. NPS 2 and Larger: Sleeve-type coupling.

3.6 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements in Division 22 and 23 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment" for seismic-restraint devices.
- B. Comply with requirements in Division 22 and 23 Section "Hangers and Supports for Plumbing Piping and Equipment" for pipe hanger and support products and installation.
 - 1. Vertical Piping: MSS Type 8 or 42, clamps.
 - 2. Individual, Straight, Horizontal Piping Runs:
 - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
 - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
 - c. Longer Than 100 Feet If Indicated: MSS Type 49, spring cushion rolls.
 - 3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.

4. Base of Vertical Piping: MSS Type 52, spring hangers.
- C. Support vertical piping and tubing at base and at each floor.
- D. Rod diameter may be reduced one size for double-rod hangers, to a minimum of 3/8 inch.
- E. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
 1. NPS 3/4 and Smaller: 60 inches with 3/8-inch rod.
 2. NPS 1 and NPS 1-1/4: 72 inches with 3/8-inch rod.
 3. NPS 1-1/2 and NPS 2: 96 inches with 3/8-inch rod.
 4. NPS 2-1/2: 108 inches with 1/2-inch rod.
- F. Install supports for vertical copper tubing every 10 feet.
- G. Install supports for vertical steel piping every 15 feet.
- H. Support piping and tubing not listed in this article according to MSS SP-69 and manufacturer's written instructions.

3.7 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to equipment and machines to allow service and maintenance.
- C. Connect domestic water piping to exterior water-service piping. Use transition fitting to join dissimilar piping materials.
- D. Connect domestic water piping to water-service piping with shutoff valve; extend and connect to the following:
 1. Water Heaters: Cold-water inlet and hot-water outlet piping in sizes indicated, but not smaller than sizes of water heater connections.
 2. Plumbing Fixtures: Cold- and hot-water supply piping in sizes indicated, but not smaller than required by plumbing code. Comply with requirements in Division 15 plumbing fixture Sections for connection sizes.
 3. Equipment: Cold- and hot-water supply piping as indicated, but not smaller than equipment connections. Provide shutoff valve and union for each connection. Use flanges instead of unions for NPS 2-1/2 and larger.

3.8 ESCUTCHEON INSTALLATION

- A. Install escutcheons for penetrations of walls, ceilings, and floors.
- B. Escutcheons for New Piping:
 1. Piping with Fitting or Sleeve Protruding from Wall: One piece, deep pattern.
 2. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One piece, cast brass with polished chrome-plated finish.

3. Bare Piping at Ceiling Penetrations in Finished Spaces: One piece, cast brass with polished chrome-plated finish.
4. Bare Piping in Unfinished Service Spaces: One piece, stamped steel with set screw or spring clips.
5. Bare Piping in Equipment Rooms: One piece, stamped steel with set screw or spring clips.
6. Bare Piping at Floor Penetrations in Equipment Rooms: One-piece floor plate.

3.9 SLEEVE INSTALLATION

- A. General Requirements: Install sleeves for pipes and tubes passing through penetrations in floors, partitions, roofs, and walls.
- B. Sleeves are not required for core-drilled holes.
- C. Permanent sleeves are not required for holes formed by removable PE sleeves.
- D. Cut sleeves to length for mounting flush with both surfaces unless otherwise indicated.
- E. Install sleeves in new partitions, slabs, and walls as they are built.
- F. For interior wall penetrations, seal annular space between sleeve and pipe or pipe insulation using joint sealants appropriate for size, depth, and location of joint.
- G. For exterior wall penetrations above grade, seal annular space between sleeve and pipe using joint sealants appropriate for size, depth, and location of joint.
- H. For exterior wall penetrations below grade, seal annular space between sleeve and pipe using sleeve seals specified in this Section.
- I. Seal space outside of sleeves in concrete slabs and walls with grout.
- J. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation unless otherwise indicated.
- K. Install sleeve materials according to the following applications:
 1. Sleeves for Piping Passing through Concrete Floor Slabs: Steel pipe.
 2. Sleeves for Piping Passing through Concrete Floor Slabs of Mechanical Equipment Areas or Other Wet Areas: Steel pipe.
 - a. Extend sleeves 2 inches above finished floor level.
 - b. For pipes penetrating floors with membrane waterproofing, extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified. Secure flashing between clamping flanges. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level. Comply with requirements in Division 7 Section "Sheet Metal Flashing and Trim" for flashing.
 3. Sleeves for Piping Passing through Gypsum-Board Partitions:
 - a. PVC pipe sleeves for pipes smaller than NPS 6.
 - b. Galvanized-steel sheet sleeves for pipes NPS 6 and larger.
 - c. Exception: Sleeves are not required for water supply tubes and waste pipes for individual plumbing fixtures if escutcheons will cover openings.

4. Sleeves for Piping Passing through Concrete Roof Slabs: Steel pipe Insert type.
5. Sleeves for Piping Passing through Exterior Concrete Walls:
 - a. Steel pipe sleeves for pipes smaller than NPS 6.
 - b. Cast-iron wall pipe sleeves for pipes NPS 6 and larger.
 - c. Install sleeves that are large enough to provide 1-inch annular clear space between sleeve and pipe or pipe insulation when sleeve seals are used.
 - d. Do not use sleeves when wall penetration systems are used.
6. Sleeves for Piping Passing through Interior Concrete Walls:
 - a. Steel pipe sleeves for pipes smaller than NPS 6.
 - b. Galvanized-steel sheet sleeves for pipes NPS 6 and larger.
- L. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements in Division 7 Section "Through-Penetration Firestop Systems" for firestop materials and installations.

3.10 SLEEVE SEAL INSTALLATION

- A. Install sleeve seals in sleeves in exterior concrete walls at water-service piping entries into building.
- B. Select type and number of sealing elements required for pipe material and size. Position pipe in center of sleeve. Assemble sleeve seal components and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

3.11 WALL PENETRATION SYSTEM INSTALLATION

- A. Install wall penetration systems in new, exterior concrete walls.
- B. Assemble wall penetration system components with sleeve pipe. Install so that end of sleeve pipe and face of housing are flush with wall. Adjust locking devices to secure sleeve pipe in housing.

3.12 IDENTIFICATION

- A. Identify system components. Comply with requirements in Division 22 and 23 Section "Identification for Plumbing Piping and Equipment" for identification materials and installation.
- B. Label pressure piping with system operating pressure.

3.13 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Piping Inspections:

1. Do not enclose, cover, or put piping into operation until it has been inspected and approved by authorities having jurisdiction.
2. During installation, notify authorities having jurisdiction at least one day before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:
 - a. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
 - b. Final Inspection: Arrange final inspection for authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
3. Reinspection: If authorities having jurisdiction find that piping will not pass tests or inspections, make required corrections and arrange for reinspection.
4. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

C. Piping Tests:

1. Fill domestic water piping. Check components to determine that they are not air bound and that piping is full of water.
2. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit a separate report for each test, complete with diagram of portion of piping tested.
3. Leave new, altered, extended, or replaced domestic water piping uncovered and unconcealed until it has been tested and approved. Expose work that was covered or concealed before it was tested.
4. Cap and subject piping to static water pressure of 100 psig, without exceeding pressure rating of piping system materials. Isolate test source and allow to stand for four hours. Leaks and loss in test pressure constitute defects that must be repaired.
5. Repair leaks and defects with new materials and retest piping or portion thereof until satisfactory results are obtained.
6. Prepare reports for tests and for corrective action required.

D. Domestic water piping will be considered defective if it does not pass tests and inspections.

E. Prepare test and inspection reports.

3.14 ADJUSTING

A. Perform the following adjustments before operation:

1. Close drain valves, hydrants, and hose bibbs.
2. Open shutoff valves to fully open position.
3. Open throttling valves to proper setting.
4. Adjust balancing valves in hot-water-circulation return piping to provide adequate flow.
 - a. Manually adjust ball-type balancing valves in hot-water-circulation return piping to provide flow of hot water in each branch.
 - b. Adjust calibrated balancing valves to flows indicated.
5. Remove plugs used during testing of piping and for temporary sealing of piping during installation.
6. Remove and clean strainer screens. Close drain valves and replace drain plugs.

7. Remove filter cartridges from housings and verify that cartridges are as specified for application where used and are clean and ready for use.
8. Check plumbing specialties and verify proper settings, adjustments, and operation.

3.15 CLEANING

- A. Clean and disinfect potable and non-potable domestic water piping as follows:
 1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
 2. Use purging and disinfecting procedures prescribed by authorities having jurisdiction; if methods are not prescribed, use procedures described in either AWWA C651 or AWWA C652 or follow procedures described below:
 - a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
 - b. Fill and isolate system according to either of the following:
 - 1) Fill system or part thereof with water/chlorine solution with at least 50 ppm of chlorine. Isolate with valves and allow to stand for 24 hours.
 - 2) Fill system or part thereof with water/chlorine solution with at least 200 ppm of chlorine. Isolate and allow to stand for three hours.
 - c. Flush system with clean, potable water until no chlorine is in water coming from system after the standing time.
 - d. Submit water samples in sterile bottles to authorities having jurisdiction. Repeat procedures if biological examination shows contamination.
- B. Clean non-potable domestic water piping as follows:
 1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
 2. Use purging procedures prescribed by authorities having jurisdiction or; if methods are not prescribed, follow procedures described below:
 - a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
 - b. Submit water samples in sterile bottles to authorities having jurisdiction. Repeat procedures if biological examination shows contamination.
- C. Prepare and submit reports of purging and disinfecting activities.
- D. Clean interior of domestic water piping system. Remove dirt and debris as work progresses.

3.16 PIPING SCHEDULE

- A. Transition and special fittings with pressure ratings at least equal to piping rating may be used in applications below unless otherwise indicated.
- B. Flanges and unions may be used for aboveground piping joints unless otherwise indicated.
- C. Aboveground domestic water piping, NPS 2 and smaller, shall be the following:

1. Hard copper tube, ASTM B 88, Type L; cast- or wrought- copper solder-joint fittings; and soldered joints.

3.17 VALVE SCHEDULE

- A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:
 1. Shutoff Duty: Use ball valves for piping NPS 2 and smaller. Use butterfly, ball, or gate valves with flanged ends for piping NPS 2-1/2 and larger.
 2. Throttling Duty: Use ball or globe valves for piping NPS 2 and smaller. Use butterfly or ball valves with flanged ends for piping NPS 2-1/2 and larger.
 3. Hot-Water Circulation Piping, Balancing Duty: Memory-stop balancing valves.
 4. Drain Duty: Hose-end drain valves.
- B. Use check valves to maintain correct direction of domestic water flow to and from equipment.

END OF SECTION

SECTION 22 11 19

DOMESTIC WATER PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following domestic water piping specialties:
 - 1. Vacuum breakers.
 - 2. Backflow preventers.
 - 3. Water pressure-reducing valves.
 - 4. Temperature-actuated water mixing valves.
 - 5. Strainers.
 - 6. Hose bibbs.
 - 7. Drain valves.
 - 8. Water hammer arresters.
 - 9. Air vents.

1.3 PERFORMANCE REQUIREMENTS

- A. Minimum Working Pressure for Domestic Water Piping Specialties: 125 psig, unless otherwise indicated.

1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Diagram power, signal, and control wiring.
- C. Field quality-control test reports.
- D. Operation and Maintenance Data: For domestic water piping specialties to include in operation, and maintenance manuals.

1.5 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. NSF Compliance:

1. Comply with NSF 61, "Drinking Water System Components - Health Effects; Sections 1 through 9."

PART 2 - PRODUCTS

2.1 VACUUM BREAKERS

A. Pipe-Applied, Atmospheric-Type Vacuum Breakers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ames Co.
 - b. Cash Acme.
 - c. Conbraco Industries, Inc.
 - d. FEBCO; SPX Valves & Controls.
 - e. Rain Bird Corporation.
 - f. Toro Company (The); Irrigation Div.
 - g. Watts Industries, Inc.; Water Products Div.
 - h. Zurn Plumbing Products Group; Wilkins Div.
 - i. Prior approved equal.
2. Standard: ASSE 1001.
3. Size: NPS 1/4 to NPS 3, as required to match connected piping.
4. Body: Bronze.
5. Inlet and Outlet Connections: Threaded.
6. Finish: Rough bronze.

B. Hose-Connection Vacuum Breakers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Arrowhead Brass Products, Inc.
 - b. Cash Acme.
 - c. Conbraco Industries, Inc.
 - d. Legend Valve.
 - e. MIFAB, Inc.
 - f. Prier Products, Inc.
 - g. Watts Industries, Inc.; Water Products Div.
 - h. Woodford Manufacturing Company.
 - i. Zurn Plumbing Products Group; Light Commercial Operation.
 - j. Zurn Plumbing Products Group; Wilkins Div.
 - k. Prior approved equal.
2. Standard: ASSE 1011.
3. Body: Bronze, nonremovable, with manual drain.
4. Outlet Connection: Garden-hose threaded complying with ASME B1.20.7.
5. Finish: Chrome or nickel plated.

2.2 BACKFLOW PREVENTERS

A. Reduced-Pressure-Principle Backflow Preventers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ames Co.
 - b. Conbraco Industries, Inc.
 - c. FEBCO; SPX Valves & Controls.
 - d. Flomatic Corporation.
 - e. Watts Industries, Inc.; Water Products Div.
 - f. Zurn Plumbing Products Group; Wilkins Div.
 - g. Prior approved equal.
2. Standard: ASSE 1013.
3. Operation: Continuous-pressure applications.
4. Pressure Loss: 12 psig maximum, through middle 1/3 of flow range.
5. Body: Bronze for NPS 2 and smaller; steel with interior lining complying with AWWA C550 or that is FDA approved for NPS 2-1/2 and larger.
6. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and larger.
7. Accessories:
 - a. Valves: Ball type with threaded ends on inlet and outlet of NPS 2 and smaller; outside screw and yoke gate-type with flanged ends on inlet and outlet of NPS 2-1/2 and larger.
 - b. Air-Gap Fitting: ASME A112.1.2, matching backflow-preventer connection.

B. Hose-Connection Backflow Preventers:

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Conbraco Industries, Inc.
 - b. Watts Industries, Inc.; Water Products Div.
 - c. Woodford Manufacturing Company.
 - d. Prior approved equal.
3. Standard: ASSE 1052.
4. Operation: Up to 10-foot head of water back pressure.
5. Inlet Size: NPS 1/2 or NPS 3/4.
6. Outlet Size: Garden-hose thread complying with ASME B1.20.7.
7. Capacity: At least 3-gpm flow.

2.3 WATER PRESSURE-REDUCING VALVES

A. Water Regulators:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Cash Acme.
 - b. Conbraco Industries, Inc.
 - c. Honeywell Water Controls.
 - d. Watts Industries, Inc.; Water Products Div.
 - e. Zurn Plumbing Products Group; Wilkins Div.
 - f. Prior approved equal.
- 2. Standard: ASSE 1003.
 - 3. Pressure Rating: Initial working pressure of 150 psig.
 - 4. Body: Bronze for NPS 2 and smaller; cast iron with interior lining complying with AWWA C550 or that is FDA approved for NPS 2-1/2 and NPS 3.
 - 5. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and NPS 3.

2.4 TEMPERATURE-ACTUATED WATER MIXING VALVES

A. Primary, Thermostatic, Water Mixing Valves:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Armstrong International, Inc.
 - b. Lawler Manufacturing Company, Inc.
 - c. Leonard Valve Company.
 - d. Powers; a Watts Industries Co.
 - e. Symmons Industries, Inc.
 - f. Or equal by.
- 2. Standard: ASSE 1017.
- 3. Pressure Rating: 125 psig (860 kPa).
- 4. Type: Exposed-mounting, thermostatically controlled water mixing valve.
- 5. Material: Bronze body with corrosion-resistant interior components.
- 6. Connections: Threaded inlets and outlet.
- 7. Accessories: Manual temperature control, check stops on hot- and cold-water supplies, and adjustable, temperature-control handle.
- 8. Valve Pressure Rating: 125 psig (860 kPa) minimum, unless otherwise indicated.
- 9. Tempered-Water Setting: 110E F.
- 10. Tempered-Water Design Flow Rate: See drawings.
- 11. Pressure Drop at Design Flow Rate: See Drawings.
- 12. Valve Finish: Rough bronze.
- 13. Piping Finish: Copper.
- 14. Cabinet: Factory-fabricated, stainless steel, for surface mounting and with hinged, stainless-steel door.

B. Individual-Fixture, Water Tempering Valves:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Sloan.
 - b. Watts.
 - c. Prior approved equal.
- 2. Standard: ASSE 1016, thermostatically controlled water tempering valve.
- 3. Pressure Rating: 125 psig (860 kPa) minimum, unless otherwise indicated.

4. Body: Bronze body with corrosion-resistant interior components.
5. Temperature Control: Adjustable.
6. Inlets and Outlet: Threaded.
7. Finish: Rough or chrome-plated bronze.
8. Tempered-Water Setting: 110E F.
9. Tempered-Water Design Flow Rate:

2.5 STRAINERS FOR DOMESTIC WATER PIPING

A. Y-Pattern Strainers:

1. Pressure Rating: 125 psig minimum, unless otherwise indicated.
2. Body: Bronze for NPS 2 and smaller; cast iron with interior lining complying with AWWA C550 or FDA-approved, epoxy coating and for NPS 2-1/2 and larger.
3. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and larger.
4. Screen: Stainless steel with round perforations, unless otherwise indicated.
5. Drain: Factory-installed, hose-end drain valve.

2.6 HOSE BIBBS

A. Hose Bibbs:

1. Standard: ASME A112.18.1 for sediment faucets.
2. Body Material: Bronze.
3. Seat: Bronze, replaceable.
4. Supply Connections: NPS 1/2 or NPS 3/4 threaded or solder-joint inlet.
5. Outlet Connection: Garden-hose thread complying with ASME B1.20.7.
6. Pressure Rating: 125 psig.
7. Vacuum Breaker: Integral nonremovable, drainable, hose-connection vacuum breaker complying with ASSE 1011.
8. Finish for Equipment Rooms: Rough bronze, or chrome or nickel plated.
9. Finish for Service Areas: Chrome or nickel plated.
10. Finish for Finished Rooms: Chrome or nickel plated.
11. Operation for Equipment Rooms: Wheel handle or operating key.
12. Operation for Service Areas: Wheel handle.
13. Operation for Finished Rooms: Operating key.
14. Include operating key with each operating-key hose bibb.
15. Include integral wall flange with each chrome- or nickel-plated hose bibb.

2.7 DRAIN VALVES

A. Ball-Valve-Type, Hose-End Drain Valves:

1. Standard: MSS SP-110 for standard-port, two-piece ball valves.
2. Pressure Rating: 400-psig minimum CWP.
3. Size: NPS 3/4.
4. Body: Copper alloy.
5. Ball: Chrome-plated brass.
6. Seats and Seals: Replaceable.
7. Handle: Vinyl-covered steel.
8. Inlet: Threaded or solder joint.

9. Outlet: Threaded, short nipple with garden-hose thread complying with ASME B1.20.7 and cap with brass chain.

2.8 WATER HAMMER ARRESTERS

A. Water Hammer Arresters:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. AMTROL, Inc.
 - b. Josam Company.
 - c. MIFAB, Inc.
 - d. PPP Inc.
 - e. Sioux Chief Manufacturing Company, Inc.
 - f. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
 - g. Tyler Pipe; Wade Div.
 - h. Watts Drainage Products Inc.
 - i. Zurn Plumbing Products Group; Specification Drainage Operation.
 - j. Or equal by.
2. Standard: ASSE 1010 or PDI-WH 201.
3. Type: Metal bellows Copper tube with piston.
4. Size: ASSE 1010, Sizes AA and A through F or PDI-WH 201, Sizes A through F.

2.9 AIR VENTS

A. Bolted-Construction Automatic Air Vents:

1. Body: Bronze.
2. Pressure Rating: 125-psig minimum pressure rating at 140 deg F.
3. Float: Replaceable, corrosion-resistant metal.
4. Mechanism and Seat: Stainless steel.
5. Size: NPS 1/2 minimum inlet.
6. Inlet and Vent Outlet End Connections: Threaded.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Refer to Division 22 and 23 Section "Common work results" for piping joining materials, joint construction, and basic installation requirements.
- B. Install backflow preventers in each water supply to mechanical equipment and systems and to other equipment and water systems that may be sources of contamination. Comply with authorities having jurisdiction.
 1. Locate backflow preventers in same room as connected equipment or system.
 2. Install drain for backflow preventers with atmospheric-vent drain connection with air-gap fitting, fixed air-gap fitting, or equivalent positive pipe separation of at least two pipe

diameters in drain piping and pipe to floor drain. Locate air-gap device attached to or under backflow preventer. Simple air breaks are not acceptable for this application.

3. Do not install bypass piping around backflow preventers.
- C. Install water regulators with inlet and outlet shutoff valves and bypass with memory-stop balancing valve. Install pressure gages on inlet and outlet.
- D. Install balancing valves in locations where they can easily be adjusted. Install on hot water recirculating lines where they connect to hot water lines.
- E. Install temperature-actuated water mixing valves with check stops or shutoff valves on inlets and with shutoff valve on outlet.
 1. Install thermometers.
 2. Install cabinet-type units recessed in or surface mounted on wall as specified.
- F. Install Y-pattern strainers for water on supply side of each water pressure-reducing valve.
- G. Install water hammer arresters in water piping according to PDI-WH 201.
- H. Install air vents at high points of water piping. Install drain piping and discharge onto floor drain.

3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 and 23 Sections. Drawings indicate general arrangement of piping and specialties.
- B. Ground equipment according to Division 26 Section "Grounding and Bonding."
- C. Connect wiring according to Division 26 Section "Conductors and Cables."

3.3 LABELING AND IDENTIFYING

- A. Equipment Nameplates and Signs: Install engraved plastic-laminate equipment nameplate or sign on or near each of the following:
 1. Pressure vacuum breakers.
 2. Reduced-pressure-principle backflow preventers.
 3. Water pressure-reducing valves.
 4. Calibrated balancing valves.
 5. Primary, thermostatic, water mixing valves.
- B. Distinguish among multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to identifying unit.

3.4 FIELD QUALITY CONTROL

- A. Perform the following tests and prepare test reports:
 1. Test each reduced-pressure-principle backflow preventer according to authorities having jurisdiction and the device's reference standard.

- B. Remove and replace malfunctioning domestic water piping specialties and retest as specified above.

3.5 ADJUSTING

- A. Set field-adjustable pressure set points of water pressure-reducing valves.
- B. Set field-adjustable flow set points of balancing valves.
- C. Set field-adjustable temperature set points of temperature-actuated water mixing valves.

END OF SECTION

SECTION 22 13 16

SANITARY WASTE AND VENT PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following for soil, waste, and vent piping inside the building:
 - 1. Pipe, tube, and fittings.

1.3 DEFINITIONS

- A. ABS: Acrylonitrile-butadiene-styrene plastic.
- B. EPDM: Ethylene-propylene-diene terpolymer rubber.
- C. LLDPE: Linear, low-density polyethylene plastic.
- D. NBR: Acrylonitrile-butadiene rubber.
- E. PE: Polyethylene plastic.
- F. PVC: Polyvinyl chloride plastic.
- G. TPE: Thermoplastic elastomer.

1.4 PERFORMANCE REQUIREMENTS

- A. Components and installation shall be capable of withstanding the following minimum working pressure, unless otherwise indicated:
 - 1. Soil, Waste, and Vent Piping: 10-foot head of water Insert pressure.
 - 2. Sanitary Sewer, Force-Main Piping: 100 psig.

1.5 SUBMITTALS

- A. Product Data: For pipe, tube, fittings, and couplings.
- B. Field quality-control inspection and test reports.

1.6 QUALITY ASSURANCE

- A. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 14, "Plastics Piping Systems Components and Related Materials," for plastic piping components. Include marking with "NSF-dwv" for plastic drain, waste, and vent piping; "NSF-drain" for plastic drain piping; "NSF-tubular" for plastic continuous waste piping; and "NSF-sewer" for plastic sewer piping.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, manufacturers specified.
 - 2. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.2 PIPING MATERIALS

- A. Refer to Part 3 "Piping Applications" Article for applications of pipe, tube, fitting, and joining materials.

2.3 ABS PIPE AND FITTINGS

- A. Solid-Wall ABS Pipe: ASTM D 2661, Schedule 40.
- B. Cellular-Core ABS Pipe: ASTM F 628, Schedule 40.
- C. ABS Socket Fittings: ASTM D 2661, made to ASTM D 3311, drain, waste, and vent patterns.
- D. Solvent Cement: ASTM D 2235.
 - 1. Use ABS solvent cement that has a VOC content of 325 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

2.4 PVC PIPE AND FITTINGS

- A. Solid-Wall PVC Pipe: ASTM D 2665, drain, waste, and vent.
- B. Cellular-Core PVC Pipe: ASTM F 891, Schedule 40.
- C. PVC Socket Fittings: ASTM D 2665, made to ASTM D 3311, drain, waste, and vent patterns and to fit Schedule 40 pipe.
- D. Adhesive Primer: ASTM F 656.

1. Use adhesive primer that has a VOC content of 550 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- E. Solvent Cement: ASTM D 2564.
1. Use PVC solvent cement that has a VOC content of 510 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

PART 3 - EXECUTION

3.1 EXCAVATION

- A. Refer to Division 2 Section "Earthwork" for excavating, trenching, and backfilling.

3.2 PIPING APPLICATIONS

- A. Flanges and unions may be used on aboveground pressure piping, unless otherwise indicated.
- B. Aboveground, soil and waste piping NPS 4 and smaller shall be any of the following:
1. Install aboveground ABS piping according to ASTM D 2661.
 2. Install aboveground PVC piping according to ASTM D 2665.

3.3 PIPING INSTALLATION

- A. Sanitary sewer piping outside the building is specified in Division 2 Section "Sanitary Sewerage."
- B. Plastic piping is not allowed in ceiling return plenums. Where piping is exposed to ceiling plenums, cast iron shall only be allowed.
- C. Basic piping installation requirements are specified in Division 22 and 23 Section "Common Work Results."
- D. Install seismic restraints on piping. Seismic-restraint devices are specified in Division 22 and 23 Section "Mechanical Vibration and Seismic Controls."
- E. Install cleanouts at grade and extend to where building sanitary drains connect to building sanitary sewers.
- F. Install cleanout fitting with closure plug inside the building in sanitary force-main piping.
- G. Install cast-iron sleeve with water stop and mechanical sleeve seal at each service pipe penetration through foundation wall. Select number of interlocking rubber links required to make installation watertight. Sleeves and mechanical sleeve seals are specified in Division 22 and 23 Section "Common Work Results."
- H. Install wall-penetration fitting at each service pipe penetration through foundation wall. Make installation watertight.

- I. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
 - 1. Install encasement on underground piping according to ASTM A 674 or AWWA C105.
- J. Make changes in direction for soil and waste drainage and vent piping using appropriate branches, bends, and long-sweep bends. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical. Use long-turn, double Y-branch and 1/8-bend fittings if 2 fixtures are installed back to back or side by side with common drain pipe. Straight tees, elbows, and crosses may be used on vent lines. Do not change direction of flow more than 90 degrees. Use proper size of standard increasers and reducers if pipes of different sizes are connected. Reducing size of drainage piping in direction of flow is prohibited.
- K. Lay buried building drainage piping beginning at low point of each system. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements. Maintain swab in piping and pull past each joint as completed.
- L. Install soil and waste drainage and vent piping at the following minimum slopes, unless otherwise indicated:
 - 1. Building Sanitary Drain: 2 percent downward in direction of flow for piping NPS 3 and smaller; 1 percent downward in direction of flow for piping NPS 4 and larger.
 - 2. Horizontal Sanitary Drainage Piping: 2 percent downward in direction of flow.
 - 3. Vent Piping: 1 percent down toward vertical fixture vent or toward vent stack.
- M. Install engineered soil and waste drainage and vent piping systems as follows:
 - 1. Combination Waste and Vent: Comply with standards of authorities having jurisdiction.
 - 2. Solvent Drainage System: Comply with ASSE 1043 and solvent fitting manufacturer's written installation instructions.
 - 3. Reduced-Size Venting: Comply with standards of authorities having jurisdiction.
- N. Sleeves are not required for cast-iron soil piping passing through concrete slabs-on-grade if slab is without membrane waterproofing.
- O. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.

3.4 JOINT CONSTRUCTION

- A. Basic piping joint construction requirements are specified in Division 22 and 23 Section "Common Work Results."
- B. Join hub-and-spigot, cast-iron soil piping with gasket joints according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for compression joints.
- C. Join hub-and-spigot, cast-iron soil piping with calked joints according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for lead and oakum calked joints.
- D. Join hubless cast-iron soil piping according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless-coupling joints.

3.5 HANGER AND SUPPORT INSTALLATION

- A. Seismic-restraint devices are specified in Division 22 and 23 Section "Mechanical Vibration Controls and Seismic Restraints."
- B. Pipe hangers and supports are specified in Division 22 and 23 Section "Hangers and Supports." Install the following:
 - 1. Vertical Piping: MSS Type 8 or Type 42, clamps.
 - 2. Install individual, straight, horizontal piping runs according to the following:
 - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
 - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
 - c. Longer Than 100 Feet, if Indicated: MSS Type 49, spring cushion rolls.
 - 3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
 - 4. Base of Vertical Piping: MSS Type 52, spring hangers.
- C. Install supports according to Division 22 and 23 Section "Hangers and Supports."
- D. Support vertical piping and tubing at base and at each floor.
- E. Rod diameter may be reduced 1 size for double-rod hangers, with 3/8-inch minimum rods.
- F. Install hangers for cast-iron soil piping with the following maximum horizontal spacing and minimum rod diameters:
 - 1. NPS 1-1/2 and NPS 2: 60 inches with 3/8-inch rod.
 - 2. NPS 3: 60 inches with 1/2-inch rod.
 - 3. NPS 4 and NPS 5: 60 inches with 5/8-inch rod.
 - 4. NPS 6: 60 inches with 3/4-inch rod.
 - 5. NPS 8 to NPS 12: 60 inches with 7/8-inch rod.
- G. Install supports for vertical cast-iron soil piping every 15 feet.
- H. Support piping and tubing not listed above according to MSS SP-69 and manufacturer's written instructions.

3.6 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect soil and waste piping to exterior sanitary sewerage piping. Use transition fitting to join dissimilar piping materials.
- C. Connect drainage and vent piping to the following:
 - 1. Plumbing Fixtures: Connect drainage piping in sizes indicated, but not smaller than required by plumbing code.
 - 2. Plumbing Fixtures and Equipment: Connect atmospheric vent piping in sizes indicated, but not smaller than required by authorities having jurisdiction.
 - 3. Plumbing Specialties: Connect drainage and vent piping in sizes indicated, but not smaller than required by plumbing code.

3.7 FIELD QUALITY CONTROL

- A. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.
 - 1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
 - 2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
- B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
- C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
- D. Test sanitary drainage and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:
 - 1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
 - 2. Leave uncovered and unconcealed new, altered, extended, or replaced drainage and vent piping until it has been tested and approved. Expose work that was covered or concealed before it was tested.
 - 3. Roughing-in Plumbing Test Procedure: Test drainage and vent piping, except outside leaders, on completion of roughing-in. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water. From 15 minutes before inspection starts to completion of inspection, water level must not drop. Inspect joints for leaks.
 - 4. Finished Plumbing Test Procedure: After plumbing fixtures have been set and traps filled with water, test connections and prove they are gastight and watertight. Plug vent-stack openings on roof and building drains where they leave building. Introduce air into piping system equal to pressure of 1-inch wg. Use U-tube or manometer inserted in trap of water closet to measure this pressure. Air pressure must remain constant without introducing additional air throughout period of inspection. Inspect plumbing fixture connections for gas and water leaks.
 - 5. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
 - 6. Prepare reports for tests and required corrective action.

3.8 CLEANING

- A. Clean interior of piping. Remove dirt and debris as work progresses.
- B. Protect drains during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- C. Place plugs in ends of uncompleted piping at end of day and when work stops.

END OF SECTION

SECTION 22 13 19

SANITARY WASTE PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following sanitary drainage piping specialties:
 - 1. Cleanouts.
 - 2. Floor drains.
 - 3. Air-admittance valves.
 - 4. Trap Guards.
 - 5. Roof flashing assemblies.
 - 6. Miscellaneous sanitary drainage piping specialties.
 - 7. Flashing materials.

1.3 DEFINITIONS

- A. ABS: Acrylonitrile-butadiene-styrene plastic.
- B. FRP: Fiberglass-reinforced plastic.
- C. HDPE: High-density polyethylene plastic.
- D. PE: Polyethylene plastic.
- E. PVC: Polyvinyl chloride plastic.

1.4 SUBMITTALS

- A. Product Data: For each type of product indicated. Include manufacturer, rated capacities, operating characteristics, and accessories for the following:
 - 1. Cleanouts.
 - 2. Floor drains.
 - 3. Air admittance valves.

1.5 QUALITY ASSURANCE

- A. Drainage piping specialties shall bear label, stamp, or other markings of specified testing agency.

- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Comply with NSF 14, "Plastics Piping Components and Related Materials," for plastic sanitary piping specialty components.

1.6 COORDINATION

- A. Coordinate size and location of roof penetrations.

PART 2 - PRODUCTS

2.1 CLEANOUTS

- A. Exposed Metal Cleanouts:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Josam Company; Josam Div.
 - b. MIFAB, Inc.
 - c. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
 - d. Tyler Pipe; Wade Div.
 - e. Watts Drainage Products Inc.
 - f. Zurn Plumbing Products Group; Specification Drainage Operation.
 - g. Prior approved equal.
 - 2. Standard: ASME A112.36.2M for cast iron for cleanout test tee.
 - 3. Size: Same as connected drainage piping
 - 4. Body Material: Hub-and-spigot, cast-iron soil pipe T-branch or Hubless, cast-iron soil pipe test tee as required to match connected piping.
 - 5. Closure: Countersunk or raised-head, cast-iron plug.
 - 6. Closure Plug Size: Same as or not more than one size smaller than cleanout size.

2.2 FLOOR DRAINS

- A. Cast-Iron Floor Drains:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Commercial Enameling Co.
 - b. Josam Company; Josam Div.
 - c. MIFAB, Inc.
 - d. Prier Products, Inc.
 - e. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
 - f. Tyler Pipe; Wade Div.
 - g. Watts Drainage Products Inc.
 - h. Zurn Plumbing Products Group; Light Commercial Operation.
 - i. Zurn Plumbing Products Group; Specification Drainage Operation.

- j. Prior approved equal.
- 2. Standard: ASME A112.6.3.
- 3. Pattern: Floor drain.
- 4. Body Material: Gray iron.
- 5. Clamping Device: Required.
- 6. Outlet: Bottom.
- 7. Top or Strainer Material: Stainless steel.
- 8. Top Shape: Round.
- 9. Top Loading Classification: Medium Duty.
- 10. Inlet Fitting: Gray iron, with threaded inlet and threaded or spigot outlet, and trap-seal primer valve connection.
- 11. Trap Pattern: Deep-seal P-trap.
- 12. Trap Features: Trap-seal primer valve drain connection.

2.3 AIR-ADMITTANCE VALVES

A. Wall Box:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Durgo, Inc.
 - b. Oatey.
 - c. RectorSeal.
 - d. Studor, Inc.
 - e. Prior approved equal.
- 2. Description: White plastic housing with white plastic grille, made for recessed installation. Include bottom pipe connection and space to contain one air-admittance valve.
- 3. Size: About 9 inches wide by 8 inches high by 4 inches deep.

2.4 ROOF FLASHING ASSEMBLIES

A. Roof Flashing Assemblies:

- 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Acorn Engineering Company; Elmdor/Stoneman Div.
 - b. Thaler Metal Industries Ltd.
 - c. Prior approved equal.

B. Description: Manufactured assembly made of 4.0-lb/sq. ft., 0.0625-inch- thick, lead flashing collar and skirt extending at least 8 inches from pipe, with galvanized-steel boot reinforcement and counterflashing fitting.

- 1. Open-Top Vent Cap: Without cap.
- 2. Low-Silhouette Vent Cap: With vandal-proof vent cap.
- 3. Extended Vent Cap: With field-installed, vandal-proof vent cap.

2.5 MISCELLANEOUS SANITARY DRAINAGE PIPING SPECIALTIES

- A. Deep-Seal Traps:
 - 1. Description: Cast-iron or bronze casting, with inlet and outlet matching connected piping and cleanout trap-seal primer valve connection.
 - 2. Size: Same as connected waste piping.
 - a. NPS 2: 4-inch- minimum water seal.
 - b. NPS 2-1/2 and Larger: 5-inch- minimum water seal.
- B. Floor-Drain, Trap-Seal Primer Fittings:
 - 1. Description: Cast iron, with threaded inlet and threaded or spigot outlet, and trap-seal primer valve connection.
 - 2. Size: Same as floor drain outlet with NPS 1/2 side inlet.

2.6 FLASHING MATERIALS

- A. Copper Sheet: ASTM B 152/B 152M, of the following minimum weights and thicknesses, unless otherwise indicated:
 - 1. General Applications: 12 oz./sq. ft. thickness.
 - 2. Vent Pipe Flashing: 8 oz./sq. ft. thickness.
- B. Zinc-Coated Steel Sheet: ASTM A 653/A 653M, with 0.20 percent copper content and 0.04-inch minimum thickness, unless otherwise indicated. Include G90 hot-dip galvanized, mill-phosphatized finish for painting if indicated.
- C. Elastic Membrane Sheet: ASTM D 4068, flexible, chlorinated polyethylene, 40-mil minimum thickness.
- D. Fasteners: Metal compatible with material and substrate being fastened.
- E. Metal Accessories: Sheet metal strips, clamps, anchoring devices, and similar accessory units required for installation; matching or compatible with material being installed.
- F. Solder: ASTM B 32, lead-free alloy.
- G. Bituminous Coating: SSPC-Paint 12, solvent-type, bituminous mastic.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Refer to Division 22 and 23 Section "Common Work Results for Plumbing" for piping joining materials, joint construction, and basic installation requirements.
- B. Install cleanouts in aboveground piping and building drain piping according to the following, unless otherwise indicated:

1. Size same as drainage piping up to NPS 4. Use NPS 4 for larger drainage piping unless larger cleanout is indicated.
 2. Locate at each change in direction of piping greater than 45 degrees.
 3. Locate at minimum intervals of 50 feet for piping NPS 4 and smaller and 100 feet for larger piping.
 4. Locate at base of each vertical soil and waste stack.
- C. For floor cleanouts for piping below floors, install cleanout deck plates with top flush with finished floor.
- D. For cleanouts located in concealed piping, install cleanout wall access covers, of types indicated, with frame and cover flush with finished wall.
- E. Install floor drains at low points of surface areas to be drained. Set grates of drains flush with finished floor, unless otherwise indicated.
1. Position floor drains for easy access and maintenance.
 2. Set floor drains below elevation of surrounding finished floor to allow floor drainage. Set with grates depressed according to the following drainage area radii:
 - a. Radius, 30 Inches or Less: Equivalent to 1 percent slope, but not less than 1/4-inch total depression.
 - b. Radius, 30 to 60 Inches: Equivalent to 1 percent slope.
 - c. Radius, 60 Inches or Larger: Equivalent to 1 percent slope, but not greater than 1-inch total depression.
 3. Install floor-drain flashing collar or flange so no leakage occurs between drain and adjoining flooring. Maintain integrity of waterproof membranes where penetrated.
 4. Install individual traps for floor drains connected to sanitary building drain, unless otherwise indicated.
- F. Install trench drains at low points of surface areas to be drained. Set grates of drains flush with finished surface, unless otherwise indicated.
- G. Install air-admittance-valve wall boxes recessed in wall where indicated on drawings.
- H. Install roof flashing assemblies on sanitary stack vents and vent stacks that extend through roof.
- I. Install flashing fittings on sanitary stack vents and vent stacks that extend through roof.
- J. Install deep-seal traps on all floor drains.
- K. Install floor-drain, trap-seal primer fittings on inlet to floor drains that require trap-seal primer connection.
1. Exception: Fitting may be omitted if trap has trap-seal primer connection.
 2. Size: Same as floor drain inlet.
- L. Install air-gap fittings on draining-type backflow preventers and on indirect-waste piping discharge into sanitary drainage system.
- M. Install sleeve flashing device with each riser and stack passing through floors with waterproof membrane.

- N. Install escutcheons at wall, floor, and ceiling penetrations in exposed finished locations and within cabinets and millwork. Use deep-pattern escutcheons if required to conceal protruding pipe fittings.

3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 and 23 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to equipment to allow service and maintenance.

3.3 FLASHING INSTALLATION

- A. Fabricate flashing from single piece unless large pans, sumps, or other drainage shapes are required. Join flashing according to the following if required:
 - 1. Lead Sheets: Burn joints of lead sheets 6.0-lb/sq. ft., 0.0938-inch thickness or thicker. Solder joints of lead sheets 4.0-lb/sq. ft., 0.0625-inch thickness or thinner.
 - 2. Copper Sheets: Solder joints of copper sheets.
- B. Install sheet flashing on pipes, sleeves, and specialties passing through or embedded in floors and roofs with waterproof membrane.
 - 1. Pipe Flashing: Sleeve type, matching pipe size, with minimum length of 10 inches, and skirt or flange extending at least 8 inches around pipe.
 - 2. Sleeve Flashing: Flat sheet, with skirt or flange extending at least 8 inches around sleeve.
 - 3. Embedded Specialty Flashing: Flat sheet, with skirt or flange extending at least 8 inches around specialty.
- C. Set flashing on floors and roofs in solid coating of bituminous cement.
- D. Secure flashing into sleeve and specialty clamping ring or device.
- E. Install flashing for piping passing through roofs with counterflashing or commercially made flashing fittings, according to Division 7 Section "Sheet Metal Flashing and Trim."
- F. Extend flashing up vent pipe passing through roofs and turn down into pipe, or secure flashing into cast-iron sleeve having calking recess.
- G. Fabricate and install flashing and pans, sumps, and other drainage shapes.

3.4 FIELD QUALITY CONTROL

- A. Tests and Inspections:
 - 1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
 - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

3.5 PROTECTION

- A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.
- B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION

SECTION 22 33 00

ELECTRIC WATER HEATERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following electric water heaters:
 - 1. Flow-control, instantaneous electric water heaters.
 - 2. Light-commercial electric water heaters.
 - 3. Compression tanks.
 - 4. Water heater accessories.

1.3 SUBMITTALS

- A. Product Data: For each type and size of water heater indicated. Include rated capacities, operating characteristics, furnished specialties, and accessories.
- B. Shop Drawings: Diagram power, signal, and control wiring.
- C. Product Certificates: For each type of commercial and instantaneous electric water heater, signed by product manufacturer.
- D. Manufacturer Seismic Qualification Certification: Submit certification that commercial water heaters, accessories, and components will withstand seismic forces defined in Division 22 and 23 Section "Mechanical Vibration and Seismic Controls." Include the following:
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - a. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified."
 - b. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- E. Source quality-control test reports.
- F. Field quality-control test reports.

- G. Operation and Maintenance Data: For electric water heaters to include in emergency, operation, and maintenance manuals.
- H. Warranty: Special warranty specified in this Section.

1.4 QUALITY ASSURANCE

- A. Source Limitations: Obtain same type of electric water heaters through one source from a single manufacturer.
- B. Product Options: Drawings indicate size, profiles, and dimensional requirements of electric water heaters and are based on the specific system indicated. Refer to Division 1 Section "Product Requirements."
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- D. ASME Compliance: Where indicated, fabricate and label commercial water heater storage tanks to comply with ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.
- E. Comply with NSF 61, "Drinking Water System Components - Health Effects; Sections 1 through 9," for all components that will be in contact with potable water.

1.5 COORDINATION

- A. Coordinate size and location of concrete bases with Architectural and Structural Drawings.

1.6 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of electric water heaters that fail in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Structural failures including storage tank and supports.
 - b. Faulty operation of controls.
 - c. Deterioration of metals, metal finishes, and other materials beyond normal use.
 - 2. Warranty Period(s): From date of Substantial Completion:
 - a. Instantaneous Electric Water Heaters: One year.
 - b. Light-Commercial Electric Water Heaters:
 - 1) Storage Tank: Five years.
 - 2) Controls and Other Components: Two years.
 - c. Compression Tanks: One year.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.2 INSTANTANEOUS ELECTRIC WATER HEATERS

- A. Flow-Control, Instantaneous Electric Water Heaters: Comply with UL 499 for tankless electric (water heater) heating appliance.
1. Manufacturers:
 - a. Chronomite Laboratories, Inc.
 - b. Controlled Energy Corporation.
 - c. Eemax, Inc.
 - d. Hot Aqua, Inc.
 - e. IMI Waterheating, Ltd.
 - f. Stiebel Eltron, Inc.
 - g. Prior approved equal.
 2. Construction: Copper piping or tubing complying with NSF 61 barrier materials for potable water, without storage capacity.
 - a. Connections: ASME B1.20.1 pipe thread.
 - b. Pressure Rating: 150 psig.
 - c. Heating Element: Resistance heating system.
 - d. Temperature Control: Flow-control fitting.
 - e. Safety Control: High-temperature-limit cutoff device or system.
 - f. Jacket: Aluminum or steel with enameled finish or plastic.
 3. Support: Bracket for wall mounting.
 4. Capacity and Characteristics:
 - a. Temperature Control: Flow-control fitting.
 - b. See drawings for capacity, electrical service, etc.

2.3 COMPRESSION TANKS

- A. Description: Steel pressure-rated tank constructed with welded joints and factory-installed butyl-rubber diaphragm. Include air precharge to minimum system-operating pressure at tank.
1. Manufacturers:
 - a. AMTROL Inc.
 - b. Armstrong Pumps, Inc.
 - c. Flexcon Industries.
 - d. Honeywell Sparco.

- e. Myers, F. E.; Pentair Pump Group (The).
 - f. Smith, A. O.; Aqua-Air Div.
 - g. State Industries, Inc.
 - h. Taco, Inc.
 - i. Watts Regulator Co.
 - j. Wessels Co.
 - k. Prior approved equal.
2. Construction:
- a. Tappings: Factory-fabricated steel, welded to tank before testing and labeling. Include ASME B1.20.1, pipe thread.
 - b. Interior Finish: Comply with NSF 61 barrier materials for potable-water tank linings, including extending finish into and through tank fittings and outlets.
 - c. Air-Charging Valve: Factory installed.
3. Capacity and Characteristics: See drawings.

2.4 WATER HEATER ACCESSORIES

- A. Combination Temperature and Pressure Relief Valves: ASME rated and stamped and complying with ASME PTC 25.3. Include relieving capacity at least as great as heat input, and include pressure setting less than water heater working-pressure rating. Select relief valves with sensing element that extends into storage tank.
- B. Pressure Relief Valves: ASME rated and stamped and complying with ASME PTC 25.3. Include pressure setting less than water heater working-pressure rating.
- C. Water Heater Stand and Drain-Pan Units: High-density-polyethylene-plastic, 18-inch- high, enclosed-base stand complying with IAPMO PS 103 and IAS No. 2. Include integral or separate drain pan with raised edge and NPS 1 drain outlet with ASME B1.20.1 pipe thread.
- D. Water Heater Stands: Water heater manufacturer's factory-fabricated steel stand for floor mounting and capable of supporting water heater and water. Include dimension that will support bottom of water heater a minimum of 18 inches above the floor.
- E. Water Heater Mounting Brackets: Water heater manufacturer's factory-fabricated steel bracket for wall mounting and capable of supporting water heater and water.
- F. Drain Pans: Corrosion-resistant metal with raised edge. Include dimensions not less than base of water heater and include drain outlet not less than NPS 3/4.
- G. Piping Manifold Kits: Water heater manufacturer's factory-fabricated inlet and outlet piping arrangement for multiple-unit installation. Include piping and valves for field assembly that are capable of isolating each water heater and of providing balanced flow through each water heater.
- H. Piping-Type Heat Traps: Field-fabricated piping arrangement according to ASHRAE/IESNA 90.1 or ASHRAE 90.2.
- I. Water Regulators: ASSE 1003, water-pressure reducing valve. Set at 25-psig- maximum outlet pressure, unless otherwise indicated.
- J. Shock Absorbers: ASSE 1010 or PDI WH 201, Size A water hammer arrester.

PART 3 - EXECUTION

3.1 WATER HEATER INSTALLATION

- A. Install water heaters level and plumb, according to layout drawings, original design, and referenced standards. Maintain manufacturer's recommended clearances. Arrange units so controls and devices needing service are accessible.
- B. Install seismic restraints for light-commercial and commercial water heaters. Anchor to substrate.
- C. Install combination temperature and pressure relief valves in top portion of storage tanks. Use relief valves with sensing elements that extend into tanks. Extend commercial-water-heater relief-valve outlet, with drain piping same as domestic water piping in continuous downward pitch, and discharge by positive air gap onto closest floor drain.
- D. Install combination temperature and pressure relief valves in water piping for water heaters without storage. Extend commercial-water-heater relief-valve outlet, with drain piping same as domestic water piping in continuous downward pitch, and discharge by positive air gap onto closest floor drain.
- E. Install water-heater drain piping as indirect waste to spill by positive air gap into open drains or over floor drains. Install hose-end drain valves at low points in water piping for water heaters that do not have tank drains. Refer to Division 15 Section "Plumbing Specialties" for hose-end drain valves.
- F. Install thermometer on outlet piping of water heaters. Refer to Division 15 Section "Meters and Gages" for thermometers.
- G. Install thermometers on inlet and outlet piping of household, collector-to-tank, solar-electric water heaters. Refer to Division 22 and 23 Section "Meters and Gages" for thermometers.
- H. Install pressure gage(s) on inlet and outlet of commercial electric water- heater piping. Refer to Division 22 and 23 Section "Meters and Gages" for pressure gages.
- I. Assemble and install inlet and outlet piping manifold kits for multiple water heaters. Fabricate, modify, or arrange manifolds for balanced water flow through each water heater. Include shutoff valve, thermometer in each water heater inlet and outlet, and throttling valve in each water heater outlet. Refer to Division 22 and 23 Section "Valves" for general-duty valves and to Division 22 and 23 Section "Meters and Gages" for thermometers.
- J. Install water regulator, with integral bypass relief valve, in booster-heater inlet piping and water hammer arrester in booster-heater outlet piping.
- K. Install piping-type heat traps on inlet and outlet piping of water heater storage tanks without integral or fitting-type heat traps.
- L. Fill water heaters with water.
- M. Charge compression tanks with air.

3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Division 15 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to water heaters to allow service and maintenance. Arrange piping for easy removal of water heaters.
- C. Ground equipment according to Division 16 Section "Grounding and Bonding."
- D. Connect wiring according to Division 16 Section "Conductors and Cables."

3.3 FIELD QUALITY CONTROL

- A. Perform the following field tests and inspections and prepare test reports:
 - 1. Leak Test: After installation, test for leaks. Repair leaks and retest until no leaks exist.
 - 2. Operational Test: After electrical circuitry has been energized, confirm proper operation.
 - 3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- B. Remove and replace water heaters that do not pass tests and inspections and retest as specified above.

3.4 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain commercial and instantaneous electric water heaters. Refer to Division 1 Section "Closeout Procedures Demonstration and Training."

END OF SECTION

SECTION 22 46 00

SECURITY PLUMBING FIXTURES

PART 1 GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Water closets.
 - 2. Urinals.
 - 3. Lavatories.
 - 4. Drinking fountains.

1.3 DEFINITIONS

- A. Accessible Service Space: Service area in secure space behind wall-mounted fixtures.
- B. Back-Access Fixture: Security plumbing fixture designed to mount on wall sleeve built into wall or on wall, so installation and removal of fixture, piping, and other components are accessible only from service space behind wall.
- C. Front-Access Fixture: Security plumbing fixture designed to mount on wall with installation and removal from fixture side of wall, and with piping and other components accessible only from access panel in fixture.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for security plumbing fixtures.
 - 2. Include rated capacities, operating characteristics, and furnished specialties and accessories.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For security plumbing fixtures and components to include in maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Flushometer-Valve Repair Kits: Equal to 10 percent of quantity of each type installed, but no fewer than one of each type.
 - 2. Toilet Seats: Equal to five percent of quantity of each type installed.

PART 2 - PRODUCTS

2.1 STAINLESS-STEEL WATER CLOSETS

- A. Water Closets WC-1,2: Back access, off floor, back outlet, cabinet.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by the following:
 - a. Acorn Engineering Company.
 - b. Metcraft Industries Inc.
 - c. Willoughby Industries, Inc.
 - 2. Material: 0.078-inch- (2.0-mm-) minimum-thick stainless steel; corrosion-resistant metal for internal piping and bracing.
 - 3. Finish: ASTM A 480/A 480M, No. 4 polished finish on exposed surfaces.
 - 4. Cabinet: Rectangular apron, with backsplash.
 - a. Water-Closet Bowl Location: Centered on front of apron.
 - 5. Mounting: Bolts through wall sleeve into accessible service space.
 - 6. Water Closet:
 - a. Standard: IAPMO PS 61.
 - b. Bowl:
 - 1) Type: Elongated, with back inlet, integral trap, and blowout design with back outlet and contoured seat.
 - 2) Type: Elongated, with back inlet, integral trap, and siphon-jet design with bottom outlet and contoured seat.
 - 3) Back-Outlet Connection: NPS 4 (DN 100), horizontal with cleanout and slip joint.
 - 4) Seat Surface: ASTM A 480/A 480M, No. 7 polished finish.
 - 5) Punching: Two holes for installation of separate toilet seat.
 - 7. Flushometer Valve: Concealed push button.
 - 8. Wall Sleeve: Galvanized-steel frame of dimensions required to match fixture. Include steel bars or other design to prevent escape if fixture is removed.
 - a. Configuration: Modify wall sleeve for water-closet mounting height according to ICC A117.1.

2.2 FLUSHOMETER VALVES

- A. Flushometer Valves: Concealed Push button, diaphragm.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by the following:
 - a. Delany Flush Valves.
 - b. Sloan Valve Company.
 - c. Zurn Industries, LLC; Commercial Brass and Fixtures.
 - 2. Standard: ASSE 1037.
 - 3. Minimum Pressure Rating: 125 psig (860 kPa).
 - 4. Features: Integral check stops and backflow-prevention device.
 - 5. Material: Brass body with corrosion-resistant components.
 - 6. Exposed Flushometer-Valve Finish: Chrome plated.
 - 7. Panel Finish: Chrome plated or stainless steel.
 - 8. Style: Concealed battery operated.
 - 9. Consumption: 1.6 gal. (water closets) and 1.0 gal. (urinals) per flush.
 - 10. Minimum Inlet: NPS 1 (DN 25).
 - 11. Minimum Outlet: NPS 1-1/4 (DN 32).

2.3 URINALS

- A. Urinals U-1: Back access, back outlet, single.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by the following:
 - a. Acorn Engineering Company.
 - b. Bradley Corporation.
 - c. Metcraft Industries Inc.
 - 2. Fixture:
 - a. Standard: IAPMO PS 61.
 - b. Material: 0.078-inch- (2.0-mm-) minimum-thick stainless steel; corrosion-resistant metal for internal piping and bracing.
 - c. Finish: ASTM A 480/A 480M, No. 4 polished finish on exposed surfaces.
 - d. Type and Configuration: Blowout, with back inlet.
 - e. Drain: Strainer with NPS 2 (DN 50) tailpiece and trap.
 - 3. Mounting: Bolts through wall sleeve into accessible service space.
 - 4. Flushometer Valve
 - 5. Wall Sleeve: Galvanized-steel frame of dimensions required to match fixture.

2.4 STAINLESS-STEEL LAVATORIES

- A. Lavatories L-1: Back access.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by the following:

- a. Acorn Engineering Company.
 - b. Bradley Corporation.
 - c. Metcraft Industries Inc.
 - d. Willoughby Industries, Inc.
2. Fixture:
- a. Standard: ASME A112.19.3/CSA B45.4.
 - b. Material: 0.078-inch- (2.0-mm-) minimum-thick stainless steel; corrosion-resistant metal for internal piping and bracing.
 - c. Finish: ASTM A 480/A 480M, No. 4 polished finish on exposed surfaces.
 - d. Receptor: rectangular bowl with integral soap depression and backsplash.
 - e. Hot- and Cold-Water and Bubbler Supply Valves: Mechanical-metering type with push-button actuation, individual check stops, and backsplash-mounted filler spouts complying with ASME A112.18.1/CSA B125.1.
 - f. Drain: Integral punched grid with NPS 1-1/4 (DN 32) minimum horizontal waste and trap complying with ASME A112.18.2/CSA B125.2.
3. Mounting: Bolts through wall into accessible service space.

2.5 DRINKING FOUNTAINS

A. Drinking Fountains DF-1 Front access.

1. Manufacturers: Subject to compliance with requirements, provide products by the following:
- a. MDF 24P or equal by one of the following:
 - b. Acorn Engineering Company.
 - c. Bradley Corporation.
 - d. Metcraft Industries Inc.
 - e. Willoughby Industries, Inc.
2. Fixture:
- a. Standard: ASME A112.19.3/CSA B45.4.
 - b. Material: 0.078-inch- (2.0-mm-) minimum-thick stainless steel; corrosion-resistant metal for internal piping and bracing.
 - c. Finish: ASTM A 480/A 480M, No. 4 polished finish on exposed surfaces.
 - d. Receptor: Bowl with backsplash.
 - e. Bubbler Supply Valve: Push-button actuation and deck-mounted filler spouts complying with ASME A112.18.1/CSA B125.1.
 - f. Drain: Field piped.
 - g. Color shall be green.
3. Waste Fittings: NPS 1-1/4 (DN 32) minimum waste and trap complying with ASME A112.18.2/CSA B125.2.
4. Mounting: Bolts from fixture-mounted flanges into wall.

PART 3 EXECUTION

2.6 EXAMINATION

- A. Examine roughing-in for water supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before fixture installation.
- B. Examine walls and floors for suitable conditions where fixtures will be installed.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

2.7 INSTALLATION

- A. Install security plumbing fixtures level and plumb according to roughing-in drawings.
- B. Install back-access, stainless-steel fixtures as follows:
 - 1. Install wall sleeve in wall if indicated.
 - 2. Install fixture on wall sleeve or wall, as indicated, with access from accessible service space.
 - 3. Extend supply piping from service space to fixture.
 - 4. Install soil and waste piping from fixture and extend into service space.
 - 5. Install fixture trap in service space instead of below fixture drain.
- C. Install front-access, stainless-steel fixtures as follows:
 - 1. Install fixture support or mounting bracket.
 - 2. Install fixture on support; mount components inside of or attached to fixture.
 - 3. Extend supply piping from pipe space to fixture.
 - 4. Install trap below fixture and extend soil and waste piping into pipe space.
- D. Install vitreous-china fixture service space as follows:
 - 1. Install fixture support in service space.
 - a. Use combination support and waste fitting assembly for water closet.
 - b. Use chair carrier for lavatory.
 - 2. Install fixture on support.
 - 3. Install components in service space.
- E. Install fixture outlets with gasket seals.
- F. Install fixtures designated "accessible" according to ICC A117.1 for heights, dimensions, and clearances.
- G. Install toilet seats on water closets if seats are indicated.
- H. Install protective shielding pipe covers and enclosures on exposed supplies and waste piping of accessible fixtures. Comply with requirements in Section 220719 "Plumbing Piping Insulation."

- I. Seal joints between fixtures, floors, and walls using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to fixture color. Comply with sealant requirements specified in Section 079200 "Joint Sealants."
- J. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Use deep-pattern escutcheons if required to conceal protruding fittings. Comply with escutcheon requirements specified in Section 220518 "Escutcheons for Plumbing Piping."

2.8 CONNECTIONS

- A. Connect fixtures with water supplies, stops, and risers, and with traps, soil, waste, and vent piping. Use size fittings required to match fixtures.
- B. Comply with requirements for water piping specified in Section 221116 "Domestic Water Piping."
- C. Comply with requirements for soil and waste drainage piping specified in Section 221316 "Sanitary Waste and Vent Piping."

2.9 ADJUSTING

- A. Operate and adjust flushometer valves and flow-control valves on fixtures.

2.10 CLEANING AND PROTECTION

- A. After installing fixtures, inspect and repair damaged finishes.
- B. Clean fixtures, faucets, and other fittings with manufacturers' recommended cleaning methods and materials.
- C. Provide protective covering for installed fixtures and fittings.
- D. Do not allow use of fixtures for temporary facilities unless approved in writing by Owner.

END OF SECTION

DIVISION 23 - HEATING VENTILATING AND AIR CONDITIONING

23 01 00	GENERAL REQUIREMENTS
23 05 00	COMMON WORK RESULTS FOR HVAC
23 05 13	COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT
23 05 29	HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT
23 05 48	VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT
23 05 53	MECHANICAL IDENTIFICATION
23 05 93	TESTING, ADJUSTING, AND BALANCING FOR HVAC
23 07 00	HVAC INSULATION
23 31 13	METAL DUCTS
23 33 00	DUCT ACCESSORIES
23 34 23	EXHAUST FANS
23 37 13	DIFFUSERS, REGISTERS, AND GRILLES
23 37 14	LOUVERS AND VENTS

SECTION 23 01 00
GENERAL REQUIREMENTS

PART 1 - GENERAL

1.1 GENERAL

- A. General Conditions and Division 01 apply to this Division.
- B. See Division 22 "General Requirements"

1.2 SCOPE

- A. All requirements and information contained in Division 22 "General Requirements" shall apply to both divisions 22 and 23.

1.3 SITE OBSERVATION

- A. The Contractor shall examine the site and understand the conditions which may affect the performance of work of this Division before submitting proposals for this work.
- B. No subsequent allowance for time or money will be considered for any consequence related to failure to examine existing site conditions.

1.4 DRAWINGS

- A. See Division 22 "General Requirements".

1.5 COORDINATION OF WORK:

- A. See Division 22 "General Requirements"

1.6 EQUIPMENT & MATERIALS:

- A. See Division 22 "General Requirements"

1.7 PROJECT SUBMITTALS:

- A. See Division 22 "General Requirements."

1.8 WARRANTY GUARANTEE:

- A. See Division 22 "General Requirements."
- B. The Contractor shall warrant all materials and equipment to be of quality consistent with specifications as represented by manufacturer's published data.
- C. The Contractor shall guarantee that the installation and operation of the equipment shall be free from defects for a period of one year beginning at date of substantial completion and acceptance. The Contractor shall replace or repair any part of the installation that is found to be defective or incomplete within the guarantee period.
- D. The one year guarantee on equipment and systems shall commence when equipment has been demonstrated to work and has been accepted. (Example: If an equipment item fails to perform and it takes 9 months after substantial completion to correct, then the guarantee shall commence after the item has been demonstrated to perform and has been accepted.)
- E. Substantial completion and acceptance in no way relieves the Contractor from providing the systems and equipment as specified.

1.9 OPERATION AND MAINTENANCE MANUAL FOR MECHANICAL SYSTEMS

- A. See Division 22 "General Requirements".

PART 2 - PRODUCTS
(Not Used)

PART 3 - EXECUTION
(Not Used)

END OF SECTION

SECTION 23 05 00

COMMON WORK RESULTS FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. Division 22 "Basic Mechanical and Plumbing Materials and Methods."

1.2 SUMMARY

- A. All requirements in Division 22 "Basic Mechanical and Plumbing Materials and Methods" shall apply to both Divisions 22 and 23.
 - 1. Equipment installation requirements common to equipment sections.

PART 2 - PRODUCTS

- 2.1 See Division 22 "Basic Mechanical and Plumbing Materials and Methods"

PART 3 - EXECUTION

- 3.1 See Division 22 "Basic Mechanical and Plumbing Materials and Methods"

END OF SECTION

SECTION 23 05 13

COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes general requirements for single-phase and polyphase, general-purpose, horizontal, small and medium, squirrel-cage induction motors for use on ac power systems up to 600 V and installed at equipment manufacturer's factory or shipped separately by equipment manufacturer for field installation.

1.3 COORDINATION

- A. Coordinate features of motors, installed units, and accessory devices to be compatible with the following:
 - 1. Motor controllers.
 - 2. Torque, speed, and horsepower requirements of the load.
 - 3. Ratings and characteristics of supply circuit and required control sequence.
 - 4. Ambient and environmental conditions of installation location.

PART 2 PRODUCTS

1.4 GENERAL MOTOR REQUIREMENTS

- A. Comply with requirements in this Section except when stricter requirements are specified in HVAC equipment schedules or Sections.
- B. Comply with NEMA MG 1 unless otherwise indicated.
- C. Comply with IEEE 841 for severe-duty motors.

1.5 MOTOR CHARACTERISTICS

- A. Duty: Continuous duty at ambient temperature of 40 deg C and at altitude of 3300 feet above sea level.
- B. Capacity and Torque Characteristics: Sufficient to start, accelerate, and operate connected loads at designated speeds, at installed altitude and environment, with indicated operating sequence, and without exceeding nameplate ratings or considering service factor.

1.6 SINGLE-PHASE MOTORS

- A. Motors larger than 1/20 hp shall be one of the following, to suit starting torque and requirements of specific motor application:
 - 1. Permanent-split capacitor.
 - 2. Split phase.
 - 3. Capacitor start, inductor run.
 - 4. Capacitor start, capacitor run.
- B. Multispeed Motors: Variable-torque, permanent-split-capacitor type.
- C. Bearings: Prelubricated, antifriction ball bearings or sleeve bearings suitable for radial and thrust loading.
- D. Motors 1/20 HP and Smaller: Shaded-pole type.
- E. Thermal Protection: Internal protection to automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature rating of motor insulation. Thermal-protection device shall automatically reset when motor temperature returns to normal range.

PART 2 - EXECUTION (Not Applicable)

END OF SECTION

SECTION 23 05 29

HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section 22 “Hangers and Supports for Plumbing” shall apply to both divisions 22 and 23.

PART 2 - PRODUCTS

2.1 SEE SECTION “Hangers and supports for plumbing”

PART 3 - EXECUTION

3.1 SEE SECTION “Hangers and supports for plumbing”

END OF SECTION

SECTION 23 05 48

VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. Section 220548 "Vibration and Seismic Controls for HVAC Piping and Equipment" shall apply to both divisions 22 and 23.

1.2 SUBMITTALS

- A. See section 220548:

PART 2 - PRODUCTS

- 2.1 See section 220548 "Vibration and Seismic Controls for HVAC Piping and Equipment"

PART 3 - EXECUTION

- 3.1 See section 220548 "Vibration and Seismic Controls for HVAC Piping and Equipment"

END OF SECTION

SECTION 23 05 53

MECHANICAL IDENTIFICATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. Section 22 "Mechanical and Plumbing Identification"

1.2 SUMMARY

- A. Section 22 "Mechanical and Plumbing Identification" shall apply to both divisions 22 and 23.

PART 2 - PRODUCTS

- 2.1 **SEE SECTION 22 "Mechanical and Plumbing Identification"**

PART 3 - EXECUTION

- 3.1 **SEE SECTION "Mechanical and Plumbing Identification"**

END OF SECTION

SECTION 23 05 93

TESTING, ADJUSTING, AND BALANCING FOR HVAC

GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes TAB to produce design objectives for the following:
 - 1. Air Systems:
 - a. Constant-volume air systems.
 - 2. HVAC equipment quantitative-performance settings.
 - 3. Existing systems TAB.
 - 4. Verifying that automatic control devices are functioning properly.
 - 5. Reporting results of activities and procedures specified in this Section.

1.3 DEFINITIONS

- A. Adjust: To regulate fluid flow rate and air patterns at the terminal equipment, such as to reduce fan speed or adjust a damper.
- B. Balance: To proportion flows within the distribution system, including submains, branches, and terminals, according to indicated quantities.
- C. Barrier or Boundary: Construction, either vertical or horizontal, such as walls, floors, and ceilings that are designed and constructed to restrict the movement of airflow, smoke, odors, and other pollutants.
- D. Draft: A current of air, when referring to localized effect caused by one or more factors of high air velocity, low ambient temperature, or direction of airflow, whereby more heat is withdrawn from a person's skin than is normally dissipated.
- E. NC: Noise criteria.
- F. Procedure: An approach to and execution of a sequence of work operations to yield repeatable results.
- G. RC: Room criteria.
- H. Report Forms: Test data sheets for recording test data in logical order.
- I. Static Head: The pressure due to the weight of the fluid above the point of measurement. In a closed system, static head is equal on both sides of the pump.

- J. Suction Head: The height of fluid surface above the centerline of the pump on the suction side.
- K. System Effect: A phenomenon that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
- L. System Effect Factors: Allowances used to calculate a reduction of the performance ratings of a fan when installed under conditions different from those presented when the fan was performance tested.
- M. TAB: Testing, adjusting, and balancing.
- N. Terminal: A point where the controlled medium, such as fluid or energy, enters or leaves the distribution system.
- O. Test: A procedure to determine quantitative performance of systems or equipment.
- P. Testing, Adjusting, and Balancing (TAB) Firm: The entity responsible for performing and reporting TAB procedures.

1.4 SUBMITTALS

- A. Qualification Data: Within 15 days from Contractor's Notice to Proceed, submit 4 copies of evidence that TAB firm and this Project's TAB team members meet the qualifications specified in "Quality Assurance" Article.
- B. Contract Documents Examination Report: Within 30 days from Contractor's Notice to Proceed, submit 4 copies of the Contract Documents review report as specified in Part 3.
- C. Strategies and Procedures Plan: Within 60 days from Contractor's Notice to Proceed, submit 4 copies of TAB strategies and step-by-step procedures as specified in Part 3 "Preparation" Article. Include a complete set of report forms intended for use on this Project.
- D. Certified TAB Reports: Submit two copies of reports prepared, as specified in this Section, on approved forms certified by TAB firm.
- E. Sample Report Forms: Submit two sets of sample TAB report forms.
- F. Warranties specified in this Section.

1.5 QUALITY ASSURANCE

- A. TAB Firm Qualifications: Engage a TAB firm certified by AABC or NEBB.
- B. TAB Conference: Meet with Owner's and Architect's representatives on approval of TAB strategies and procedures plan to develop a mutual understanding of the details. Ensure the participation of TAB team members, equipment manufacturers' authorized service representatives, HVAC controls installers, and other support personnel. Provide seven days' advance notice of scheduled meeting time and location.
 - 1. Agenda Items: Include at least the following:
 - a. Submittal distribution requirements.
 - b. The Contract Documents examination report.

- c. TAB plan.
 - d. Work schedule and Project-site access requirements.
 - e. Coordination and cooperation of trades and subcontractors.
 - f. Coordination of documentation and communication flow.
- C. Certification of TAB Reports: Certify TAB field data reports. This certification includes the following:
- 1. Review field data reports to validate accuracy of data and to prepare certified TAB reports.
 - 2. Certify that TAB team complied with approved TAB plan and the procedures specified and referenced in this Specification.
- D. TAB Report Forms: Use standard forms from AABC's "National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems" or NEBB's "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems."
- E. Instrumentation Type, Quantity, and Accuracy: As described in AABC's "National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems or NEBB's "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems," Section II, "Required Instrumentation for NEBB Certification."
- F. Instrumentation Calibration: Calibrate instruments at least every six months or more frequently if required by instrument manufacturer.
- 1. Keep an updated record of instrument calibration that indicates date of calibration and the name of party performing instrument calibration.
- G. Approved TAB agencies:
- 1. Bonneville Test and Balance.
 - 2. BTC Services.
 - 3. Certified Test and Balance.
 - 4. Danis Test and Balance.
 - 5. Intermountain Test and Balance.
 - 6. RS Analysis.
 - 7. Testing and Balancing, Inc.

1.6 PROJECT CONDITIONS

- A. Full Owner Occupancy: Owner will occupy the site and existing building during entire TAB period. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.
- B. Partial Owner Occupancy: Owner may occupy completed areas of building before Substantial Completion. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.

1.7 COORDINATION

- A. Coordinate the efforts of factory-authorized service representatives for systems and equipment, HVAC controls installers, and other mechanics to operate HVAC systems and equipment to support and assist TAB activities.

- B. Notice: Provide seven days' advance notice for each test. Include scheduled test dates and times.
- C. Perform TAB after leakage and pressure tests on air and water distribution systems have been satisfactorily completed.

1.8 WARRANTY

- A. National Project Performance Guarantee: Provide a guarantee on AABC's "National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems" forms stating that AABC will assist in completing requirements of the Contract Documents if TAB firm fails to comply with the Contract Documents. Guarantee includes the following provisions:
 - 1. The certified TAB firm has tested and balanced systems according to the Contract Documents.
 - 2. Systems are balanced to optimum performance capabilities within design and installation limits.

PRODUCTS

(Not Applicable)

EXECUTION

1.9 EXAMINATION

- A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems' designs that may preclude proper TAB of systems and equipment.
 - 1. Contract Documents are defined in the General and Supplementary Conditions of Contract.
 - 2. Verify that balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers, are required by the Contract Documents. Verify that quantities and locations of these balancing devices are accessible and appropriate for effective balancing and for efficient system and equipment operation.
- B. Examine approved submittal data of HVAC systems and equipment.
- C. Examine Project Record Documents described in Division 1 Section "Project Record Documents."
- D. Examine design data, including HVAC system descriptions, statements of design assumptions for environmental conditions and systems' output, and statements of philosophies and assumptions about HVAC system and equipment controls.
- E. Examine equipment performance data including fan and pump curves. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system. Calculate system effect factors to reduce performance ratings of HVAC equipment when installed under

conditions different from those presented when the equipment was performance tested at the factory. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," Sections 7 through 10; or in SMACNA's "HVAC Systems--Duct Design," Sections 5 and 6. Compare this data with the design data and installed conditions.

- F. Examine system and equipment installations to verify that they are complete and that testing, cleaning, adjusting, and commissioning specified in individual Sections have been performed.
- G. Examine system and equipment test reports.
- H. Examine HVAC system and equipment installations to verify that indicated balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers, are properly installed, and that their locations are accessible and appropriate for effective balancing and for efficient system and equipment operation.
- I. Examine systems for functional deficiencies that cannot be corrected by adjusting and balancing.
- J. Examine HVAC equipment to ensure that clean filters have been installed, bearings are greased, belts are aligned and tight, and equipment with functioning controls is ready for operation.
- K. Examine terminal units, such as variable-air-volume boxes, to verify that they are accessible and their controls are connected and functioning.
- L. Examine plenum ceilings used for supply air to verify that they are airtight. Verify that pipe penetrations and other holes are sealed.
- M. Examine strainers for clean screens and proper perforations.
- N. Examine three-way valves for proper installation for their intended function of diverting or mixing fluid flows.
- O. Examine heat-transfer coils for correct piping connections and for clean and straight fins.
- P. Examine system pumps to ensure absence of entrained air in the suction piping.
- Q. Examine equipment for installation and for properly operating safety interlocks and controls.
- R. Examine automatic temperature system components to verify the following:
 - 1. Dampers, valves, and other controlled devices are operated by the intended controller.
 - 2. Dampers and valves are in the position indicated by the controller.
 - 3. Integrity of valves and dampers for free and full operation and for tightness of fully closed and fully open positions. This includes dampers in multizone units, mixing boxes, and variable-air-volume terminals.
 - 4. Automatic modulating and shutoff valves, including two-way valves and three-way mixing and diverting valves, are properly connected.
 - 5. Thermostats and humidistats are located to avoid adverse effects of sunlight, drafts, and cold walls.
 - 6. Sensors are located to sense only the intended conditions.
 - 7. Sequence of operation for control modes is according to the Contract Documents.
 - 8. Controller set points are set at indicated values.
 - 9. Interlocked systems are operating.

10. Changeover from heating to cooling mode occurs according to indicated values.

- S. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

1.10 PREPARATION

- A. Prepare a TAB plan that includes strategies and step-by-step procedures.
- B. Complete system readiness checks and prepare system readiness reports. Verify the following:
1. Permanent electrical power wiring is complete.
 2. Hydronic systems are filled, clean, and free of air.
 3. Automatic temperature-control systems are operational.
 4. Equipment and duct access doors are securely closed.
 5. Balance, smoke, and fire dampers are open.
 6. Isolating and balancing valves are open and control valves are operational.
 7. Ceilings are installed in critical areas where air-pattern adjustments are required and access to balancing devices is provided.
 8. Windows and doors can be closed so indicated conditions for system operations can be met.

1.11 GENERAL PROCEDURES FOR TESTING AND BALANCING

- A. Perform testing and balancing procedures on each system according to the procedures contained in AABC's "National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems" or NEBB's "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems" and this Section.
- B. Cut insulation, ducts, pipes, and equipment cabinets for installation of test probes to the minimum extent necessary to allow adequate performance of procedures. After testing and balancing, close probe holes and patch insulation with new materials identical to those removed. Restore vapor barrier and finish according to insulation Specifications for this Project.
- C. Mark equipment and balancing device settings with paint or other suitable, permanent identification material, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, to show final settings.
- D. Take and report testing and balancing measurements in inch-pound (IP) units.

1.12 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

- A. Prepare test reports for both fans and outlets. Obtain manufacturer's outlet factors and recommended testing procedures. Crosscheck the summation of required outlet volumes with required fan volumes.
- B. Prepare schematic diagrams of systems' "as-built" duct layouts.
- C. For variable-air-volume systems, develop a plan to simulate diversity.
- D. Determine the best locations in main and branch ducts for accurate duct airflow measurements.

- E. Check airflow patterns from the outside-air louvers and dampers and the return- and exhaust-air dampers, through the supply-fan discharge and mixing dampers.
- F. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.
- G. Verify that motor starters are equipped with properly sized thermal protection.
- H. Check dampers for proper position to achieve desired airflow path.
- I. Check for airflow blockages.
- J. Check condensate drains for proper connections and functioning.
- K. Check for proper sealing of air-handling unit components.
- L. Check for proper sealing of air duct system.

1.13 PROCEDURES FOR CONSTANT-VOLUME AIR SYSTEMS

- A. Adjust fans to deliver total indicated airflows within the maximum allowable fan speed listed by fan manufacturer.
 - 1. Measure fan static pressures to determine actual static pressure as follows:
 - a. Measure outlet static pressure as far downstream from the fan as practicable and upstream from restrictions in ducts such as elbows and transitions.
 - b. Measure static pressure directly at the fan outlet or through the flexible connection.
 - c. Measure inlet static pressure of single-inlet fans in the inlet duct as near the fan as possible, upstream from flexible connection and downstream from duct restrictions.
 - d. Measure inlet static pressure of double-inlet fans through the wall of the plenum that houses the fan.
 - 2. Measure static pressure across each component that makes up an air-handling unit, rooftop unit, and other air-handling and -treating equipment.
 - a. Simulate dirty filter operation and record the point at which maintenance personnel must change filters.
 - 3. Measure static pressures entering and leaving other devices such as sound traps, heat recovery equipment, and air washers, under final balanced conditions.
 - 4. Compare design data with installed conditions to determine variations in design static pressures versus actual static pressures. Compare actual system effect factors with calculated system effect factors to identify where variations occur. Recommend corrective action to align design and actual conditions.
 - 5. Obtain approval from Architect for adjustment of fan speed higher or lower than indicated speed. Make required adjustments to pulley sizes, motor sizes, and electrical connections to accommodate fan-speed changes.
 - 6. Do not make fan-speed adjustments that result in motor overload. Consult equipment manufacturers about fan-speed safety factors. Modulate dampers and measure fan-motor amperage to ensure that no overload will occur. Measure amperage in full cooling, full heating, economizer, and any other operating modes to determine the maximum required brake horsepower.

- B. Adjust volume dampers for main duct, submain ducts, and major branch ducts to indicated airflows within specified tolerances.
 - 1. Measure static pressure at a point downstream from the balancing damper and adjust volume dampers until the proper static pressure is achieved.
 - a. Where sufficient space in submain and branch ducts is unavailable for Pitot-tube traverse measurements, measure airflow at terminal outlets and inlets and calculate the total airflow for that zone.
 - 2. Remeasure each submain and branch duct after all have been adjusted. Continue to adjust submain and branch ducts to indicated airflows within specified tolerances.
- C. Measure terminal outlets and inlets without making adjustments.
 - 1. Measure terminal outlets using a direct-reading hood or outlet manufacturer's written instructions and calculating factors.
- D. Adjust terminal outlets and inlets for each space to indicated airflows within specified tolerances of indicated values. Make adjustments using volume dampers rather than extractors and the dampers at air terminals.
 - 1. Adjust each outlet in same room or space to within specified tolerances of indicated quantities without generating noise levels above the limitations prescribed by the Contract Documents.
 - 2. Adjust patterns of adjustable outlets for proper distribution without drafts.

1.14 PROCEDURES FOR MOTORS

- A. Motors, 1/2 HP and Larger: Test at final balanced conditions and record the following data:
 - 1. Manufacturer, model, and serial numbers.
 - 2. Motor horsepower rating.
 - 3. Motor rpm.
 - 4. Efficiency rating.
 - 5. Nameplate and measured voltage, each phase.
 - 6. Nameplate and measured amperage, each phase.
 - 7. Starter thermal-protection-element rating.
- B. Motors Driven by Variable-Frequency Controllers: Test for proper operation at speeds varying from minimum to maximum. Test the manual bypass for the controller to prove proper operation. Record observations, including controller manufacturer, model and serial numbers, and nameplate data.

1.15 PROCEDURES FOR TESTING DUCT SYSTEMS

- A. Perform duct leakage tests and duct cleanliness tests.
- B. Duct system will be considered defective if it does not pass initial tests and inspections. The sheet metal contractor shall be responsible to make corrections and repairs as necessary to pass the tests. TAB contractor shall include initial test and 1 follow up test. Any additional follow up tests required due to system not passing shall be performed by the TAB contractor at the Division 22 and 23 contractor's expense.

1.16 TOLERANCES

- A. Set HVAC system airflow and water flow rates within the following tolerances:
 - 1. Supply, Return, and Exhaust Fans and Equipment with Fans: Plus 5 to plus 10 percent.
 - 2. Air Outlets and Inlets: 0 to minus 10 percent.
 - 3. Heating-Water Flow Rate: 0 to minus 10 percent.
 - 4. Cooling-Water Flow Rate: 0 to minus 5 percent.

1.17 REPORTING

- A. Initial Construction-Phase Report: Based on examination of the Contract Documents as specified in "Examination" Article, prepare a report on the adequacy of design for systems' balancing devices. Recommend changes and additions to systems' balancing devices to facilitate proper performance measuring and balancing. Recommend changes and additions to HVAC systems and general construction to allow access for performance measuring and balancing devices.
- B. Status Reports: As Work progresses, prepare reports to describe completed procedures, procedures in progress, and scheduled procedures. Include a list of deficiencies and problems found in systems being tested and balanced. Prepare a separate report for each system and each building floor for systems serving multiple floors.

1.18 FINAL REPORT

- A. General: Typewritten, or computer printout in letter-quality font, on standard bond paper, in three-ring binder, tabulated and divided into sections by tested and balanced systems.
- B. Include a certification sheet in front of binder signed and sealed by the certified testing and balancing engineer.
 - 1. Include a list of instruments used for procedures, along with proof of calibration.
- C. Provide final report on standard AABC or NEBB forms.

1.19 INSPECTIONS

- A. Initial Inspection:
 - 1. After testing and balancing are complete, operate each system and randomly check measurements to verify that the system is operating according to the final test and balance readings documented in the Final Report.
 - 2. Randomly check the following for each system:
 - a. Measure airflow of at least 10 percent of air outlets.
 - b. Measure water flow of at least 5 percent of terminals.
 - c. Measure room temperature at each thermostat/temperature sensor. Compare the reading to the set point.
 - d. Measure sound levels at two locations.
 - e. Measure space pressure of at least 10 percent of locations.
 - f. Verify that balancing devices are marked with final balance position.
 - g. Note deviations to the Contract Documents in the Final Report.

B. Final Inspection:

1. After initial inspection is complete and evidence by random checks verifies that testing and balancing are complete and accurately documented in the final report, request that a final inspection be made by Architect.
2. TAB firm test and balance engineer shall conduct the inspection in the presence of Architect.
3. Architect shall randomly select measurements documented in the final report to be rechecked. The rechecking shall be limited to either 10 percent of the total measurements recorded, or the extent of measurements that can be accomplished in a normal 8-hour business day.
4. If the rechecks yield measurements that differ from the measurements documented in the final report by more than the tolerances allowed, the measurements shall be noted as "FAILED."
5. If the number of "FAILED" measurements is greater than 10 percent of the total measurements checked during the final inspection, the testing and balancing shall be considered incomplete and shall be rejected.
6. TAB firm shall recheck all measurements and make adjustments. Revise the final report and balancing device settings to include all changes and resubmit the final report.
7. Request a second final inspection. If the second final inspection also fails, Owner shall contract the services of another TAB firm to complete the testing and balancing in accordance with the Contract Documents and deduct the cost of the services from the final payment.

1.20 ADDITIONAL TESTS

- A. Within 90 days of completing TAB, perform additional testing and balancing to verify that balanced conditions are being maintained throughout and to correct unusual conditions.
- B. Seasonal Periods: If initial TAB procedures were not performed during near-peak summer and winter conditions, perform additional testing, inspecting, and adjusting during near-peak summer and winter conditions.

END OF SECTION

SECTION 23 07 00
HVAC INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. See section 22070 for HVAC and plumbing insulation.

1.2 SUMMARY

- A. Section 220700 HVAC and Plumbing insulation shall apply to insulation requirements for both division 22 and 23.
- B. Division 23 Section "Metal Ducts" for duct liners.

1.3 SUBMITTALS

- A. See section 220700.

PART 2 - PRODUCTS

- 2.1 See section 220700.**

PART 3 - EXECUTION

- 3.1 See section 220700**

END OF SECTION

SECTION 23 31 13

METAL DUCTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Single-wall rectangular ducts and fittings.
2. Single-wall round and flat-oval ducts and fittings.
3. Double-wall round and flat-oval ducts and fittings.
4. Sheet metal materials.
5. Duct liner.
6. Sealants and gaskets.
7. Hangers and supports.
8. Seismic-restraint devices.

- B. Related Sections:

1. Division 22 and 23 Section "Duct Accessories" for dampers, sound-control devices, duct-mounting access doors and panels, turning vanes, and flexible ducts.
2. Division 22 and 23 Section "Testing, Adjusting, and Balancing" for testing, adjusting, and balancing requirements for metal ducts.

1.3 PERFORMANCE REQUIREMENTS

- A. Delegated Duct Design: Duct construction, including sheet metal thicknesses, seam and joint construction, reinforcements, and hangers and supports, shall comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" and performance requirements and design criteria indicated.

1. Static-Pressure Classes:

- a. Supply Ducts (except in Mechanical Rooms): 2-inch wg.
- b. Supply Ducts (Upstream from Air Terminal Units): 3-inch wg.
- c. Supply Ducts (Downstream from Air Terminal Units): 1-inch wg.
- d. Supply Ducts (in Mechanical Equipment Rooms): 2-inch wg.
- e. Return Ducts (Negative Pressure): 1-inch wg.
- f. Exhaust Ducts (Negative Pressure): 1-inch wg.

2. Leakage Class:

- a. Round Supply-Air Duct: 3 cfm/100 sq. ft. at 1-inch wg.
- b. Flat-Oval Supply-Air Duct: 3 cfm/100 sq. ft. at 1-inch wg.

- c. Rectangular Supply-Air Duct: 6 cfm/100 sq. ft. at 1-inch wg.
 - d. Flexible Supply-Air Duct: 6 cfm/100 sq. ft. at 1-inch wg.
- B. Structural Performance: Duct hangers and supports and seismic restraints shall withstand the effects of gravity and seismic loads and stresses within limits and under conditions described in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" SMACNA's "Seismic Restraint Manual: Guidelines for Mechanical Systems."
- 1. Seismic Hazard Level A: Seismic force to weight ratio, 0.48.
 - 2. Seismic Hazard Level B: Seismic force to weight ratio, 0.30.
 - 3. Seismic Hazard Level C: Seismic force to weight ratio, 0.15.

1.4 SUBMITTALS

- A. Product Data: For each type of the following products:
- 1. Liners and adhesives.
 - 2. Sealants and gaskets.
 - 3. Seismic-restraint devices.
- B. Welding certificates.
- C. Field quality-control reports.

1.5 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel according to the following:
- 1. AWS D1.1/D1.1M, "Structural Welding Code - Steel," for hangers and supports.
 - 2. AWS D1.2/D1.2M, "Structural Welding Code - Aluminum," for aluminum supports.
 - 3. AWS D9.1M/D9.1, "Sheet Metal Welding Code," for duct joint and seam welding.

PART 2 - PRODUCTS

2.1 SINGLE-WALL RECTANGULAR DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" based on indicated static-pressure class unless otherwise indicated.
- B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 1-4, "Transverse (Girth) Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 1-5, "Longitudinal Seams - Rectangular Ducts," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

- D. Elbows, Transitions, Offsets, Branch Connections, and Other Duct Construction: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 2, "Fittings and Other Construction," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

2.2 SINGLE-WALL ROUND AND FLAT-OVAL DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on indicated static-pressure class unless otherwise indicated.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Lindab Inc.
 - b. McGill AirFlow LLC.
 - c. SEMCO Incorporated.
 - d. Sheet Metal Connectors, Inc.
 - e. Spiral Manufacturing Co., Inc.
 - f. Metco.
 - g. Prior approved equal.
- B. Flat-Oval Ducts: Indicated dimensions are the duct width (major dimension) and diameter (diameter of the round sides connecting the flat portions of the duct).
- C. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-2, "Transverse Joints - Round Duct," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
 - 1. Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged.
- D. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-1, "Seams - Round Duct and Fittings," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
 - 1. Fabricate round ducts larger than 90 inches in diameter with butt-welded longitudinal seams.
 - 2. Fabricate flat-oval ducts larger than 72 inches in width (major dimension) with butt-welded longitudinal seams.
- E. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-4, "90 Degree Tees and Laterals," and Figure 3-5, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

2.3 DOUBLE-WALL ROUND AND FLAT-OVAL DUCTS AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Lindab Inc.
 2. McGill AirFlow LLC.
 3. SEMCO Incorporated.
 4. Sheet Metal Connectors, Inc.
 5. Metco.
 6. Prior approved equal.
- B. Flat-Oval Ducts: Indicated dimensions are the duct width (major dimension) and diameter (diameter of the round sides connecting the flat portions of the duct) of the inner duct.
- C. Outer Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on static-pressure class unless otherwise indicated.
1. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-2, "Transverse Joints - Round Duct," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
 - a. Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged.
 2. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-1, "Seams - Round Duct and Fittings," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
 - a. Fabricate round ducts larger than 90 inches in diameter with butt-welded longitudinal seams.
 - b. Fabricate flat-oval ducts larger than 72 inches in width (major dimension) with butt-welded longitudinal seams.
 3. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-4, "90 Degree Tees and Laterals," and Figure 3-5, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- D. Inner Duct: Minimum 0.028-inch perforated galvanized sheet steel having 3/32-inch- diameter perforations, with overall open area of 23 percent.
- E. Interstitial Insulation: Fibrous-glass liner complying with ASTM C 1071, NFPA 90A, or NFPA 90B; and with NAIMA AH124, "Fibrous Glass Duct Liner Standard."
1. Maximum Thermal Conductivity: 0.27 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
 2. Install spacers that position the inner duct at uniform distance from outer duct without compressing insulation.
 3. Coat insulation with antimicrobial coating.

4. Cover insulation with polyester film complying with UL 181, Class 1.

2.4 SHEET METAL MATERIALS

- A. General Material Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- B. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
 1. Galvanized Coating Designation: G60.
 2. Finishes for Surfaces Exposed to View: Mill phosphatized.
- C. Reinforcement Shapes and Plates: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
 1. Where black- and galvanized-steel shapes and plates are used to reinforce aluminum ducts, isolate the different metals with butyl rubber, neoprene, or EPDM gasket materials.
- D. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.5 DUCT LINER

- A. Fibrous-Glass Duct Liner: Comply with ASTM C 1071, NFPA 90A, or NFPA 90B; and with NAIMA AH124, "Fibrous Glass Duct Liner Standard."
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. CertainTeed Corporation; Insulation Group.
 - b. Johns Manville.
 - c. Knauf Insulation.
 - d. Owens Corning.
 - e. Prior approved equal.
 - f. Maximum Thermal Conductivity:
 - 1) Type I, Flexible: 0.27 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
 - 2) Type II, Rigid: 0.23 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
 2. Antimicrobial Erosion-Resistant Coating: Apply to the surface of the liner that will form the interior surface of the duct to act as a moisture repellent and erosion-resistant coating. Antimicrobial compound shall be tested for efficacy by an NRTL and registered by the EPA for use in HVAC systems.
 3. Solvent-Based Liner Adhesive: Comply with NFPA 90A or NFPA 90B and with ASTM C 916.
 4. Duct insulation shall have a minimum R value = 5 for installation in an unconditioned space, and a minimum R value = 8 for installation outdoors.

- B. Insulation Pins and Washers:
1. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch- diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
 2. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch- thick galvanized steel; with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
- C. Shop Application of Duct Liner: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-19, "Flexible Duct Liner Installation."
1. Adhere a single layer of indicated thickness of duct liner with at least 90 percent adhesive coverage at liner contact surface area. Attaining indicated thickness with multiple layers of duct liner is prohibited.
 2. Apply adhesive to transverse edges of liner facing upstream that do not receive metal nosing.
 3. Butt transverse joints without gaps, and coat joint with adhesive.
 4. Fold and compress liner in corners of rectangular ducts or cut and fit to ensure butted-edge overlapping.
 5. Do not apply liner in rectangular ducts with longitudinal joints, except at corners of ducts, unless duct size and dimensions of standard liner make longitudinal joints necessary.
 6. Apply adhesive coating on longitudinal seams in ducts with air velocity of 2500 fpm.
 7. Secure liner with mechanical fasteners 4 inches from corners and at intervals not exceeding 12 inches transversely; at 3 inches from transverse joints and at intervals not exceeding 18 inches longitudinally.
 8. Secure transversely oriented liner edges facing the airstream with metal nosings that have either channel or "Z" profiles or are integrally formed from duct wall. Fabricate edge facings at the following locations:
 - a. Fan discharges.
 - b. Intervals of lined duct preceding unlined duct.
 - c. Upstream edges of transverse joints in ducts where air velocities are higher than 2500 fpm or where indicated.
 9. Secure insulation between perforated sheet metal inner duct of same thickness as specified for outer shell. Use mechanical fasteners that maintain inner duct at uniform distance from outer shell without compressing insulation.
 - a. Sheet Metal Inner Duct Perforations: 3/32-inch diameter, with an overall open area of 23 percent.
 10. Terminate inner ducts with buildouts attached to fire-damper sleeves, dampers, turning vane assemblies, or other devices. Fabricated buildouts (metal hat sections) or other buildout means are optional; when used, secure buildouts to duct walls with bolts, screws, rivets, or welds.

2.6 SEALANT AND GASKETS

- A. General Sealant and Gasket Requirements: Surface-burning characteristics for sealants and gaskets shall be a maximum flame-spread index of 25 and a maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.
- B. Water-Based Joint and Seam Sealant:

1. Application Method: Brush on.
2. Solids Content: Minimum 65 percent.
3. Shore A Hardness: Minimum 20.
4. Water resistant.
5. Mold and mildew resistant.
6. VOC: Maximum 75 g/L (less water).
7. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
8. Service: Indoor or outdoor.
9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.

C. Flanged Joint Sealant: Comply with ASTM C 920.

1. General: Single-component, acid-curing, silicone, elastomeric.
2. Type: S.
3. Grade: NS.
4. Class: 25.
5. Use: O.

D. Flange Gaskets: Butyl rubber, neoprene, or EPDM polymer with polyisobutylene plasticizer.

E. Round Duct Joint O-Ring Seals:

1. Seal shall provide maximum leakage class of 3 cfm/100 sq. ft. at 1-inch wg and shall be rated for 10-inch wg static-pressure class, positive or negative.
2. EPDM O-ring to seal in concave bead in coupling or fitting spigot.
3. Double-lipped, EPDM O-ring seal, mechanically fastened to factory-fabricated couplings and fitting spigots.

2.7 HANGERS AND SUPPORTS

A. Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts.

B. Hanger Rods for Corrosive Environments: Electrogalvanized, all-thread rods or galvanized rods with threads painted with zinc-chromate primer after installation.

C. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 4-1, "Rectangular Duct Hangers Minimum Size," and Table 4-2, "Minimum Hanger Sizes for Round Duct."

D. Steel Cables for Galvanized-Steel Ducts: Galvanized steel complying with ASTM A 603.

E. Steel Cables for Stainless-Steel Ducts: Stainless steel complying with ASTM A 492.

F. Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.

G. Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.

H. Trapeze and Riser Supports:

1. Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.
2. Supports for Stainless-Steel Ducts: Stainless-steel shapes and plates.

3. Supports for Aluminum Ducts: Aluminum or galvanized steel coated with zinc chromate.

PART 3 - EXECUTION

3.1 DUCT INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of duct system. Indicated duct locations, configurations, and arrangements were used to size ducts and calculate friction loss for air-handling equipment sizing and for other design considerations. Install duct systems as indicated unless deviations to layout are approved on Shop Drawings and Coordination Drawings.
- B. Install ducts according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" unless otherwise indicated.
- C. Install round and flat-oval ducts in maximum practical lengths.
- D. Install ducts with fewest possible joints.
- E. Install factory- or shop-fabricated fittings for changes in direction, size, and shape and for branch connections.
- F. Unless otherwise indicated, install ducts vertically and horizontally, and parallel and perpendicular to building lines.
- G. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building.
- H. Install ducts with a clearance of 1 inch, plus allowance for insulation thickness.
- I. Route ducts to avoid passing through transformer vaults and electrical equipment rooms and enclosures.
- J. Where ducts pass through non-fire-rated interior partitions and exterior walls and are exposed to view, cover the opening between the partition and duct or duct insulation with sheet metal flanges of same metal thickness as the duct. Overlap openings on four sides by at least 1-1/2 inches.
- K. Where ducts pass through fire-rated interior partitions and exterior walls, install fire dampers. Comply with requirements in Division 22 Section "Duct Accessories" for fire and smoke dampers.
- L. Protect duct interiors from moisture, construction debris and dust, and other foreign materials. Comply with SMACNA's "Duct Cleanliness for New Construction Guidelines."

3.2 SEAM AND JOINT SEALING

- A. Seal duct seams and joints for duct static-pressure and leakage classes specified in "Performance Requirements" Article, according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 1-2, "Standard Duct Sealing Requirements," unless otherwise indicated.

1. For static-pressure classes 1- and 1/2-inch wg, comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Seal Class C, except as follows:
 - a. Ducts that are located directly in zones they serve.

3.3 HANGER AND SUPPORT INSTALLATION

- A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 4, "Hangers and Supports."
- B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
 1. Where practical, install concrete inserts before placing concrete.
 2. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
 3. Use powder-actuated concrete fasteners for standard-weight aggregate concretes or for slabs more than 4 inches thick.
 4. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes or for slabs less than 4 inches thick.
 5. Do not use powder-actuated concrete fasteners for seismic restraints.
- C. Hanger Spacing: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 4-1, "Rectangular Duct Hangers Minimum Size," and Table 4-2, "Minimum Hanger Sizes for Round Duct," for maximum hanger spacing; install hangers and supports within 24 inches of each elbow and within 48 inches of each branch intersection.
- D. Hangers Exposed to View: Threaded rod and angle or channel supports.
- E. Support vertical ducts with steel angles or channel secured to the sides of the duct with welds, bolts, sheet metal screws, or blind rivets; support at each floor and at a maximum intervals of 16 feet.
- F. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

3.4 CONNECTIONS

- A. Make connections to equipment with flexible connectors complying with Division 22 and 23 Section "Duct Accessories."
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for branch, outlet and inlet, and terminal unit connections.

3.5 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Leakage Tests:
 1. Comply with SMACNA's "HVAC Air Duct Leakage Test Manual."
 2. Test the following systems:

- a. Supply air.
 - 3. Disassemble, reassemble, and seal segments of systems to accommodate leakage testing and for compliance with test requirements.
 - 4. Test for leaks before insulation application.
 - 5. Conduct tests at static pressures equal to maximum design pressure of system or section being tested. If static-pressure classes are not indicated, test entire system at maximum system design pressure. Do not pressurize systems above maximum design operating pressure. Give seven days' advance notice for testing.
- C. Duct System Cleanliness Tests:
- 1. Visually inspect duct system to ensure that no visible contaminants are present.
 - 2. Test sections of metal duct system, chosen randomly by Owner, for cleanliness according to "Vacuum Test" in NADCA ACR, "Assessment, Cleaning and Restoration of HVAC Systems."
 - a. Acceptable Cleanliness Level: Net weight of debris collected on the filter media shall not exceed 0.75 mg/100 sq. cm.
- D. Duct system will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

3.6 DUCT CLEANING

- A. Clean new duct system(s) before testing, adjusting, and balancing.
- B. Use service openings for entry and inspection.
 - 1. Create new openings and install access panels appropriate for duct static-pressure class if required for cleaning access. Provide insulated panels for insulated or lined duct. Patch insulation and liner as recommended by duct liner manufacturer. Comply with Division 22 and 23 Section "Duct Accessories" for access panels and doors.
 - 2. Disconnect and reconnect flexible ducts as needed for cleaning and inspection.
 - 3. Remove and reinstall ceiling to gain access during the cleaning process.
- C. Particulate Collection and Odor Control:
 - 1. When venting vacuuming system inside the building, use HEPA filtration with 99.97 percent collection efficiency for 0.3-micron-size (or larger) particles.
 - 2. When venting vacuuming system to outdoors, use filter to collect debris removed from HVAC system, and locate exhaust downwind and away from air intakes and other points of entry into building.
- D. Clean the following components by removing surface contaminants and deposits:
 - 1. Air outlets and inlets (registers, grilles, and diffusers).
 - 2. Supply, return, and exhaust fans including fan housings, plenums (except ceiling supply and return plenums), scrolls, blades or vanes, shafts, baffles, dampers, and drive assemblies.
 - 3. Air-handling unit internal surfaces and components including mixing box, coil section, air wash systems, spray eliminators, condensate drain pans, humidifiers and dehumidifiers, filters and filter sections, and condensate collectors and drains.

4. Coils and related components.
5. Return-air ducts, dampers, actuators, and turning vanes except in ceiling plenums and mechanical equipment rooms.
6. Supply-air ducts, dampers, actuators, and turning vanes.
7. Dedicated exhaust and ventilation components and makeup air systems.

E. Mechanical Cleaning Methodology:

1. Clean metal duct systems using mechanical cleaning methods that extract contaminants from within duct systems and remove contaminants from building.
2. Use vacuum-collection devices that are operated continuously during cleaning. Connect vacuum device to downstream end of duct sections so areas being cleaned are under negative pressure.
3. Use mechanical agitation to dislodge debris adhered to interior duct surfaces without damaging integrity of metal ducts, duct liner, or duct accessories.
4. Clean fibrous-glass duct liner with HEPA vacuuming equipment; do not permit duct liner to get wet. Replace fibrous-glass duct liner that is damaged, deteriorated, or delaminated or that has friable material, mold, or fungus growth.
5. Clean coils and coil drain pans according to NADCA 1992. Keep drain pan operational. Rinse coils with clean water to remove latent residues and cleaning materials; comb and straighten fins.
6. Provide drainage and cleanup for wash-down procedures.
7. Antimicrobial Agents and Coatings: Apply EPA-registered antimicrobial agents if fungus is present. Apply antimicrobial agents according to manufacturer's written instructions after removal of surface deposits and debris.

3.7 DUCT SCHEDULE

A. Fabricate ducts with galvanized sheet steel:

B. Intermediate Reinforcement:

1. Galvanized-Steel Ducts: Galvanized steel.
2. Stainless-Steel Ducts: Galvanized steel.
3. Aluminum Ducts: Aluminum or galvanized sheet steel coated with zinc chromate.

C. Liner:

1. Supply- and Return-Air Ducts: Fibrous glass, Type I.

D. Double-Wall Duct Interstitial Insulation:

1. Supply- and Return-Air Ducts: 1 inch thick.

E. Elbow Configuration:

1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Elbows."
 - a. Velocity 1000 fpm or Lower:
 - 1) Radius Type RE 1 with minimum 0.5 radius-to-diameter ratio.
 - 2) Mitered Type RE 4 without vanes.

- b. Velocity 1000 to 1500 fpm:
 - 1) Radius Type RE 1 with minimum 1.0 radius-to-diameter ratio.
 - 2) Radius Type RE 3 with minimum 0.5 radius-to-diameter ratio and two vanes.
 - 3) Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-3, "Vanes and Vane Runners," and Figure 2-4, "Vane Support in Elbows."
 - c. Velocity 1500 fpm or Higher:
 - 1) Radius Type RE 1 with minimum 1.5 radius-to-diameter ratio.
 - 2) Radius Type RE 3 with minimum 1.0 radius-to-diameter ratio and two vanes.
 - 3) Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-3, "Vanes and Vane Runners," and Figure 2-4, "Vane Support in Elbows."
2. Round Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-3, "Round Duct Elbows."
- a. Minimum Radius-to-Diameter Ratio and Elbow Segments: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 3-1, "Mitered Elbows." Elbows with less than 90-degree change of direction have proportionately fewer segments.
 - 1) Velocity 1000 fpm or Lower: 0.5 radius-to-diameter ratio and three segments for 90-degree elbow.
 - 2) Velocity 1000 to 1500 fpm: 1.0 radius-to-diameter ratio and four segments for 90-degree elbow.
 - 3) Velocity 1500 fpm or Higher: 1.5 radius-to-diameter ratio and five segments for 90-degree elbow.
 - b. Round Elbows, 12 Inches and Smaller in Diameter: Stamped or pleated.
 - c. Round Elbows, 14 Inches and Larger in Diameter: Standing seam.

F. Branch Configuration:

- 1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-6, "Branch Connections."
 - a. Rectangular Main to Rectangular Branch: 45-degree entry.
 - b. Rectangular Main to Round Branch: Spin in.
- 2. Round and Flat Oval: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-4, "90 Degree Tees and Laterals," and Figure 3-5, "Conical Tees." Saddle taps are permitted in existing duct.
 - a. Velocity 1000 fpm or Lower: 90-degree tap.
 - b. Velocity 1000 to 1500 fpm: Conical tap.
 - c. Velocity 1500 fpm or Higher: 45-degree lateral.

G. Duct Schedule

- 1. Rectangular duct with liner:
 - a. Low pressure supply and return.

2. Rectangular duct wrapped with insulation:
 - a. Low pressure exhaust and fresh air.
3. Single wall round with wrapped insulation.
 - a. Low pressure supply and return.
4. Double wall round and flat oval:
 - a. Medium pressure supply (upstream of VAV).

END OF SECTION

SECTION 23 33 00

DUCT ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Backdraft dampers.
 - 2. Volume dampers.
 - 3. High Efficiency Take-Offs.
 - 4. Turning vanes.
 - 5. Duct-mounting access doors.
 - 6. Flexible connectors.
 - 7. Flexible ducts.
 - 8. Duct accessory hardware.
- B. Related Sections include the following:
 - 1. Division 22 and 23 Section "HVAC Instrumentation and Controls" for electric and pneumatic damper actuators.

1.3 SUBMITTALS

- A. Product Data: For the following:
 - 1. Backdraft dampers.
 - 2. Volume dampers.
 - 3. High Efficiency Take-Offs.
 - 4. Turning vanes.
 - 5. Duct-mounting access doors.
 - 6. Flexible connectors.
 - 7. Flexible ducts.

1.4 QUALITY ASSURANCE

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."

1.5 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Fusible Links: Furnish quantity equal to 10 percent of amount installed.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, manufacturers specified.
 - 2. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.2 SHEET METAL MATERIALS

- A. Comply with SMACNA's "HVAC Duct Construction Standards--Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods, unless otherwise indicated.
- B. Galvanized Sheet Steel: Lock-forming quality; complying with ASTM A 653/A 653M and having G60 coating designation; ducts shall have mill-phosphatized finish for surfaces exposed to view.
- C. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.
- D. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.3 BACKDRAFT DAMPERS

- A. Manufacturers:
 - 1. Air Balance, Inc.
 - 2. American Warming and Ventilating.
 - 3. CESCO Products.
 - 4. Duro Dyne Corp.
 - 5. Greenheck.
 - 6. Penn Ventilation Company, Inc.
 - 7. Prefco Products, Inc.
 - 8. Ruskin Company.
 - 9. Tamco
 - 10. Vent Products Company, Inc.
 - 11. Air Rite.
 - 12. Prior approved equal.

- B. Description: Multiple-blade, parallel action gravity balanced, with blades of maximum 6-inch width, with sealed edges, assembled in rattle-free manner with 90-degree stop, steel ball bearings, and axles; adjustment device to permit setting for varying differential static pressure.
- C. Frame: 0.052-inch- thick, galvanized sheet steel, with welded corners and mounting flange.
- D. Blades: 0.025-inch- thick, roll-formed aluminum.
- E. Blade Seals: Neoprene.
- F. Blade Axles: Galvanized steel.
- G. Tie Bars and Brackets: Galvanized steel.
- H. Return Spring: Adjustable tension.

2.4 VOLUME DAMPERS

- A. Manufacturers:
 1. Air Balance, Inc.
 2. American Warming and Ventilating.
 3. Clifco
 4. Flexmaster U.S.A., Inc.
 5. Leader
 6. McGill AirFlow Corporation.
 7. METALAIRE, Inc.
 8. Nailor Industries Inc.
 9. Penn Ventilation Company, Inc.
 10. Ruskin Company.
 11. Vent Products Company, Inc.
 12. Air Rite.
 13. Prior approved equal.
- B. General Description: Factory fabricated, with required hardware and accessories. Stiffen damper blades for stability. Include locking device to hold single-blade dampers in a fixed position without vibration. Close duct penetrations for damper components to seal duct consistent with pressure class.
 1. Pressure Classes of 3-Inch wg or Higher: End bearings or other seals for ducts with axles full length of damper blades and bearings at both ends of operating shaft.
- C. Standard Volume Dampers: Opposed-blade design, standard leakage rating, with linkage outside airstream, and suitable for horizontal or vertical applications.
 1. Steel Frames: Hat-shaped, galvanized sheet steel channels, minimum of 0.064 inch thick, with mitered and welded corners; frames with flanges where indicated for attaching to walls and flangeless frames where indicated for installing in ducts.
 2. Roll-Formed Steel Blades: 0.064-inch- thick, galvanized sheet steel.
 3. Aluminum Frames: Hat-shaped, 0.10-inch- thick, aluminum sheet channels; frames with flanges where indicated for attaching to walls; and flangeless frames where indicated for installing in ducts.
 4. Roll-Formed Aluminum Blades: 0.10-inch- thick aluminum sheet.
 5. Extruded-Aluminum Blades: 0.050-inch- thick extruded aluminum.

6. Blade Axles: Galvanized steel.
7. Bearings: Oil-impregnated bronze.
8. Tie Bars and Brackets: Aluminum.
9. Tie Bars and Brackets: Galvanized steel.

- D. Damper Hardware: Zinc-plated, die-cast core with dial and handle made of 3/32-inch- thick zinc-plated steel, and a 3/4-inch hexagon locking nut. Include center hole to suit damper operating-rod size. Include elevated platform for insulated duct mounting.

2.5 HIGH EFFICIENCY TAKE-OFF

- A. Factory-manufactured rectangular-to-round or round-to-round 45 degree leading tap fabricated of 24 ga zinc-coated lockforming quality steel sheets meeting requirements of ASTM A 653, with G-90 coating.
- B. One inch wide mounting flange with die formed corner clips, pre-punched mounting holes, and adhesive coated gasket.
- C. Manual Volume Damper:
1. Single blade, 22 ga minimum.
 2. 3/8 inch minimum square rod with brass damper bearings at each end.
 3. Heavy duty locking quadrant on 1-1/2 inch high stand-off mounting bracket attached to side of round duct.
- D. Approved Manufacturers:
1. HETD-L by Daniel Manufacturing.
 2. STO by Flexmaster USA Inc.
 3. HET by Sheet Metal Connectors Inc.
 4. Hercules.
 5. Clifco
 6. Air-Rite.
 7. Prior approved equal.

2.6 TURNING VANES

- A. Fabricate to comply with SMACNA's "HVAC Duct Construction Standards--Metal and Flexible" for vanes and vane runners. Vane runners shall automatically align vanes.
- B. Manufactured Turning Vanes: Fabricate 1-1/2-inch- wide, single-vane, curved blades of galvanized sheet steel set 3/4 inch o.c.; support with bars perpendicular to blades set 2 inches o.c.; and set into vane runners suitable for duct mounting.
1. Available Manufacturers:
- a. Ductmate Industries, Inc.
 - b. Duro Dyne Corp.
 - c. METALAIR, Inc.
 - d. Ward Industries, Inc.
 - e. Prior approved equal.

- C. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.

2.7 DUCT-MOUNTING ACCESS DOORS

- A. General Description: Fabricate doors airtight and suitable for duct pressure class.
- B. Door: Double wall, duct mounting, and rectangular; fabricated of galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class. Include vision panel where indicated. Include 1-by-1-inch butt or piano hinge and cam latches.
 - 1. Manufacturers:
 - a. American Warming and Ventilating.
 - b. CESCO Products.
 - c. Ductmate Industries, Inc.
 - d. Flexmaster U.S.A., Inc.
 - e. Greenheck.
 - f. McGill AirFlow Corporation.
 - g. Nailor Industries Inc.
 - h. Ventfabrics, Inc.
 - i. Ward Industries, Inc.
 - j. Air Rite.
 - k. Prior approved equal.
 - 2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
 - 3. Provide number of hinges and locks as follows:
 - a. Less Than 12 Inches Square: Secure with two sash locks.
 - b. Up to 18 Inches Square: Two hinges and two sash locks.
 - c. Up to 24 by 48 Inches: Three hinges and two compression latches.
 - d. Sizes 24 by 48 Inches and Larger: One additional hinge.
- C. Seal around frame attachment to duct and door to frame with neoprene or foam rubber.
- D. Insulation: 1-inch- thick, fibrous-glass or polystyrene-foam board.

2.8 FLEXIBLE CONNECTORS

- A. Manufacturers:
 - 1. Ductmate Industries, Inc.
 - 2. Duro Dyne Corp.
 - 3. Ventfabrics, Inc.
 - 4. Ward Industries, Inc.
 - 5. Prior approved equal.
- B. General Description: Flame-retardant or noncombustible fabrics, coatings, and adhesives complying with UL 181, Class 1.
- C. Metal-Edged Connectors: Factory fabricated with a fabric strip 3-1/2 inches wide attached to two strips of 2-3/4-inch- wide, 0.028-inch- thick, galvanized sheet steel or 0.032-inch- thick aluminum sheets. Select metal compatible with ducts.

- D. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.
 - 1. Minimum Weight: 26 oz./sq. yd..
 - 2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
 - 3. Service Temperature: Minus 40 to plus 200 deg F.

- E. Outdoor System, Flexible Connector Fabric: Glass fabric double coated with weatherproof, synthetic rubber resistant to UV rays and ozone.
 - 1. Minimum Weight: 24 oz./sq. yd..
 - 2. Tensile Strength: 530 lbf/inch in the warp and 440 lbf/inch in the filling.
 - 3. Service Temperature: Minus 50 to plus 250 deg F.

2.9 FLEXIBLE DUCTS

- A. Manufacturers:
 - 1. Flexmaster U.S.A., Inc.
 - 2. Hart & Cooley, Inc.
 - 3. McGill AirFlow Corporation.
 - 4. Themaflex.
 - 5. Prior approved equal.

- B. Insulated-Duct Connectors: UL 181, Class 1, multiple layers of aluminum laminate supported by helically wound, spring-steel wire; fibrous-glass insulation; polyethylene or aluminized vapor barrier film.
 - 1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
 - 2. Maximum Air Velocity: 4000 fpm.
 - 3. Temperature Range: Minus 20 to plus 210 deg F.

- C. Flexible Duct Clamps: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action, in sizes 3 through 18 inches to suit duct size.

2.10 DUCT ACCESSORY HARDWARE

- A. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct insulation thickness.

- B. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.

PART 3 - EXECUTION

3.1 APPLICATION AND INSTALLATION

- A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards--Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.

- B. Provide duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, stainless-steel accessories in stainless-steel ducts, and aluminum accessories in aluminum ducts.
- C. Install backdraft dampers on exhaust fans or exhaust ducts nearest to outside and where indicated.
- D. Install volume dampers in ducts with liner; avoid damage to and erosion of duct liner.
- E. Provide balancing dampers at points on supply, return, and exhaust systems where branches lead from larger ducts as required for air balancing. Install at a minimum of two duct widths from branch takeoff.
- F. Provide test holes at fan inlets and outlets and elsewhere as indicated.
- G. Install fire and smoke dampers, with fusible links, according to manufacturer's UL-approved written instructions.
- H. Install duct access doors to allow for inspecting, adjusting, and maintaining accessories and terminal units as follows:
 - 1. On both sides of duct coils.
 - 2. Adjacent to fire or smoke dampers, providing access to reset or reinstall fusible links.
 - 3. To interior of ducts for cleaning; before and after each change in direction, at maximum 50-foot spacing.
 - 4. On sides of ducts where adequate clearance is available.
- I. Install the following sizes for duct-mounting, rectangular access doors:
 - 1. One-Hand or Inspection Access: 8 by 5 inches.
 - 2. Two-Hand Access: 12 by 6 inches.
 - 3. Head and Hand Access: 18 by 10 inches.
 - 4. Head and Shoulders Access: 21 by 14 inches.
 - 5. Body Access: 25 by 14 inches.
 - 6. Body Plus Ladder Access: 25 by 17 inches.
- J. Install the following sizes for duct-mounting, round access doors:
 - 1. One-Hand or Inspection Access: 8 inches in diameter.
 - 2. Two-Hand Access: 10 inches in diameter.
 - 3. Head and Hand Access: 12 inches in diameter.
 - 4. Head and Shoulders Access: 18 inches in diameter.
 - 5. Body Access: 24 inches in diameter.
- K. Label access doors according to Division 22 and 23 Section "Mechanical Identification."
- L. Install flexible connectors immediately adjacent to equipment in ducts associated with fans and motorized equipment supported by vibration isolators.
- M. For fans developing static pressures of 5-inch wg and higher, cover flexible connectors with loaded vinyl sheet held in place with metal straps.
- N. Connect terminal units to supply ducts with maximum 12-inch lengths of flexible duct. Do not use flexible ducts to change directions.

- O. Connect diffusers to low pressure ducts with maximum 60-inch lengths of flexible duct clamped or strapped in place.
- P. Connect flexible ducts to metal ducts with adhesive plus sheet metal screws.
- Q. Install duct test holes where indicated and required for testing and balancing purposes.

3.2 ADJUSTING

- A. Adjust duct accessories for proper settings.
- B. Adjust fire and smoke dampers for proper action.
- C. Final positioning of manual-volume dampers is specified in Division 22 and 23 Section "Testing, Adjusting, and Balancing."

END OF SECTION

SECTION 23 34 23

EXHAUST FANS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:

- 1. Inline Ventilator.

1.3 PERFORMANCE REQUIREMENTS

- A. Project Altitude: Base fan-performance ratings on actual Project site elevations.
- B. Operating Limits: Classify according to AMCA 99.

1.4 SUBMITTALS

- A. Product Data: Include rated capacities, furnished specialties, and accessories for each type of product indicated and include the following:
 - 1. Certified fan performance curves with system operating conditions indicated.
 - 2. Certified fan sound-power ratings.
 - 3. Motor ratings and electrical characteristics, plus motor and electrical accessories.
 - 4. Material thickness and finishes, including color charts.
 - 5. Dampers, including housings, linkages, and operators.
 - 6. Roof curbs.
 - 7. Fan speed controllers.
- B. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 1. Wiring Diagrams: Power, signal, and control wiring.
 - 2. Design Calculations: Calculate requirements for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.
 - 3. Vibration Isolation Base Details: Detail fabrication, including anchorages and attachments to structure and to supported equipment. Include auxiliary motor slides and rails, and base weights.
- C. Field quality-control test reports.

- D. Operation and Maintenance Data: For power ventilators to include in operation, and maintenance manuals.

1.5 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. AMCA Compliance: Products shall comply with performance requirements and shall be licensed to use the AMCA-Certified Ratings Seal.
- C. NEMA Compliance: Motors and electrical accessories shall comply with NEMA standards.
- D. UL Standard: Power ventilators shall comply with UL 705.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver fans as factory-assembled unit, to the extent allowable by shipping limitations, with protective crating and covering.
- B. Disassemble and reassemble units, as required for moving to final location, according to manufacturer's written instructions.
- C. Lift and support units with manufacturer's designated lifting or supporting points.

1.7 COORDINATION

- A. Coordinate size and location of structural-steel support members.
- B. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 3.
- C. Coordinate installation of roof curbs, equipment supports, and roof penetrations. These items are specified in Division 7 Section "Roof Accessories."

1.8 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Belts: One set for each belt-driven unit.

PART 2 - PRODUCTS

2.1 INLINE VENTILATORS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Loren Cook Company. Gemini or equal by.
 2. American Coolair Corp.
 3. Carnes Company HVAC.
 4. Greenheck.
 5. JencoFan; Div. of Breidert Air Products.
 6. NuTone Inc.
 7. Penn Ventilation.
 8. Twin City
 9. Prior approved equal.
- B. Description: Centrifugal fans designed for installing in ceiling or wall or for concealed in-line applications.
- C. Housing: Steel, lined with acoustical insulation.
- D. Fan Wheel: Centrifugal wheels directly mounted on motor shaft. Fan shrouds, motor, and fan wheel shall be removable for service.
- E. Grille: Plastic, louvered grille with flange on intake and thumbscrew attachment to fan housing.
- F. Electrical Requirements: Junction box for electrical connection on housing and receptacle for motor plug-in.
- G. Accessories:
1. Manual Starter Switch: Single-pole rocker switch assembly with cover and pilot light.
 2. Time-Delay Switch: Assembly with single-pole rocker switch, timer, and cover plate.
 3. Motion Sensor: Motion detector with adjustable shutoff timer.
 4. Manufacturer's standard roof jack or wall cap, and transition fittings.
- H. Capacities and Characteristics: See drawings.

2.2 MOTORS

- A. Enclosure Type: Totally enclosed, fan cooled.

2.3 SOURCE QUALITY CONTROL

- A. Sound-Power Level Ratings: Comply with AMCA 301, "Methods for Calculating Fan Sound Ratings from Laboratory Test Data." Factory test fans according to AMCA 300, "Reverberant Room Method for Sound Testing of Fans." Label fans with the AMCA-Certified Ratings Seal.
- B. Fan Performance Ratings: Establish flow rate, pressure, power, air density, speed of rotation, and efficiency by factory tests and ratings according to AMCA 210, "Laboratory Methods of Testing Fans for Rating."

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install power ventilators level and plumb.

- B. Support units using restrained spring isolators having a static deflection of 1 inch. Vibration- and seismic-control devices are specified in Division 22 and 23 Section "Mechanical Vibration and Seismic Controls."
 - 1. Secure vibration and seismic controls to concrete bases using anchor bolts cast in concrete base.
- C. Ceiling Units: Suspend units from structure; use steel wire or metal straps.
- D. Support suspended units from structure using threaded steel rods and spring hangers with vertical-limit stops Insert device having a static deflection of 1 inch. Vibration-control devices are specified in Division 22 and 23 Section "Mechanical Vibration and Seismic Controls."
- E. Install units with clearances for service and maintenance.
- F. Label units according to requirements specified in Division 22 and 23 Section "Mechanical Identification."

3.2 CONNECTIONS

- A. Duct installation and connection requirements are specified in other Division 22 and 23 Sections. Drawings indicate general arrangement of ducts and duct accessories. Make final duct connections with flexible connectors. Flexible connectors are specified in Division 22 Section "Duct Accessories."
- B. Install ducts adjacent to power ventilators to allow service and maintenance.
- C. Ground equipment according to Division 26 Section "Grounding and Bonding."
- D. Connect wiring according to Division 26 Section "Conductors and Cables."

3.3 FIELD QUALITY CONTROL

- A. Perform the following field tests and inspections and prepare test reports:
 - 1. Verify that shipping, blocking, and bracing are removed.
 - 2. Verify that unit is secure on mountings and supporting devices and that connections to ducts and electrical components are complete. Verify that proper thermal-overload protection is installed in motors, starters, and disconnect switches.
 - 3. Verify that cleaning and adjusting are complete.
 - 4. Disconnect fan drive from motor, verify proper motor rotation direction, and verify fan wheel free rotation and smooth bearing operation. Reconnect fan drive system, align and adjust belts, and install belt guards.
 - 5. Adjust belt tension.
 - 6. Adjust damper linkages for proper damper operation.
 - 7. Verify lubrication for bearings and other moving parts.
 - 8. Verify that manual and automatic volume control and fire and smoke dampers in connected ductwork systems are in fully open position.
 - 9. Disable automatic temperature-control operators, energize motor and adjust fan to indicated rpm, and measure and record motor voltage and amperage.
 - 10. Shut unit down and reconnect automatic temperature-control operators.
 - 11. Remove and replace malfunctioning units and retest as specified above.

- B. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

3.4 ADJUSTING

- A. Adjust damper linkages for proper damper operation.
- B. Adjust belt tension.
- C. Refer to Division 23 Section "Testing, Adjusting, and Balancing" for testing, adjusting, and balancing procedures.
- D. Replace fan and motor pulleys as required to achieve design airflow.
- E. Lubricate bearings.

END OF SECTION

SECTION 23 37 13

DIFFUSERS, REGISTERS, AND GRILLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes ceiling- and wall-mounted diffusers, registers, and grilles.
- B. Related Sections include the following:
 - 1. Division 23 Section "Duct Accessories" for fire and smoke dampers and volume-control dampers not integral to diffusers, registers, and grilles.

1.3 SUBMITTALS

- A. Product Data: For each product indicated, include the following:
 - 1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
 - 2. Diffuser, Register, and Grille Schedule: Indicate Drawing designation, room location, quantity, model number, size, and accessories furnished.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Products: Subject to compliance with requirements, provide one of the products specified.

2.2 GRILLES AND REGISTERS

- A. Adjustable Bar Side Wall Supply Grille:
 - 1. Products:
 - a. Carnes; RVEA.
 - b. Krueger; 5815.
 - c. METALAIR, Inc., Metal Industries Inc.; 422.

- d. Price Industries; LBMR.
- e. Titus; 1707.
- f. Tuttle & Bailey; VF5.
- g. Or equal by:
 - 1) A-J Manufacturing Co., Inc.
 - 2) Anemostat; a Mestek Company.
 - 3) Dayus Register & Grille.
 - 4) Hart & Cooley, Inc.; Hart & Cooley Div.
 - 5) Nailor Industries of Texas Inc.

- 2. Material: Aluminum.
- 3. Finish: Baked enamel, white.
- 4. Face Blade Arrangement: Adjustable horizontal spaced 1/4 inch apart.
- 5. Frame: 1 inch wide.

B. Fixed Face Ceiling Return, Exhaust, or Transfer Air Grille:

- 1. Products:
 - a. Carnes; RSLA.
 - b. Krueger; S85H.
 - c. Price Industries; 535.
 - d. Titus; 355RL.
 - e. Tuttle & Bailey; T70D.
 - f. Or equal by:
 - 1) A-J Manufacturing Co., Inc.
 - 2) Anemostat; a Mestek Company.
 - 3) Dayus Register & Grille.
 - 4) Hart & Cooley, Inc.; Hart & Cooley Div.
 - 5) Nailor Industries of Texas Inc.
- 2. Material: Steel.
- 3. Finish: Baked enamel, white.
- 4. Face Arrangement: 1/2 inch horizontal blade spacing.
- 5. Frame: 1-1/4 inches wide.

C. Low Sidewall Return Grilles

- 1. Finish – Standard white baked enamel.
- 2. Zero degree deflection.
- 3. Approved Manufacturers And Models
 - a. Carnes - RSHA
 - b. J & J - S-590
 - c. Krueger - S480H
 - d. Metalaire - HD-RH
 - e. Price - 90-L
 - f. Titus - 30RL or 30 SL
 - g. Tuttle & Bailey - T110 or equal by
 - h. Agitair
 - i. Anemostat
 - j. Barber Colman
 - k. Environmental Air Products
 - l. Air Control Products

- m. Nailor

2.3 SOURCE QUALITY CONTROL

- A. Verification of Performance: Rate diffusers, registers, and grilles according to ASHRAE 70, "Method of Testing for Rating the Performance of Air Outlets and Inlets."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas where diffusers, registers, and grilles are to be installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install diffusers, registers, and grilles level and plumb.
- B. Ceiling-Mounted Outlets and Inlets: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practicable. For units installed in lay-in ceiling panels, provide lay-in ceiling module. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.
- C. Install diffusers, registers, and grilles with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

3.3 ADJUSTING

- A. After installation, adjust diffusers, registers, and grilles to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION

SECTION 23 37 14

LOUVERS AND VENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Fixed, extruded-aluminum louvers.

1.3 DEFINITIONS

- A. Louver Terminology: Definitions of terms for metal louvers contained in AMCA 501 apply to this Section unless otherwise defined in this Section or in referenced standards.
- B. Horizontal Louver: Louver with horizontal blades; i.e., the axes of the blades are horizontal.
- C. Vertical Louver: Louver with vertical blades; i.e., the axes of the blades are vertical.
- D. Drainable-Blade Louver: Louver with blades having gutters that collect water and drain it to channels in jambs and mullions, which carry it to bottom of unit and away from opening.
- E. Storm-Resistant Louver: Louver that provides specified wind-driven rain performance, as determined by testing according to AMCA 500-L.

1.4 PERFORMANCE REQUIREMENTS

- A. Louver Performance Ratings: Provide louvers complying with requirements specified, as demonstrated by testing manufacturer's stock units identical to those provided, except for length and width according to AMCA 500-L.

1.5 SUBMITTALS

- A. Product Data: For each type of product indicated.
 - 1. For louvers specified to bear AMCA seal, include printed catalog pages showing specified models with appropriate AMCA Certified Ratings Seals.
- B. Shop Drawings: For louvers and accessories. Include plans, elevations, sections, details, and attachments to other work. Show frame profiles and blade profiles, angles, and spacing.

1. Show weep paths, gaskets, flashing, sealant, and other means of preventing water intrusion.
 2. Show mullion profiles and locations.
 3. Wiring Diagrams: For power, signal, and control wiring for motorized adjustable louvers.
- C. Samples for Initial Selection: For units with factory-applied color finishes.
- D. Samples for Verification: For each type of metal finish required.
- E. Product Test Reports: Based on evaluation of comprehensive tests performed according to AMCA 500-L by a qualified testing agency or by manufacturer and witnessed by a qualified testing agency, for each type of louver and showing compliance with performance requirements specified.

1.6 QUALITY ASSURANCE

- A. Source Limitations: Obtain louvers and vents from single source from a single manufacturer where indicated to be of same type, design, or factory-applied color finish.
- B. Welding: Qualify procedures and personnel according to the following:
1. AWS D1.2/D1.2M, "Structural Welding Code - Aluminum."
 2. AWS D1.3, "Structural Welding Code - Sheet Steel."
 3. AWS D1.6, "Structural Welding Code - Stainless Steel."
- C. SMACNA Standard: Comply with recommendations in SMACNA's "Architectural Sheet Metal Manual" for fabrication, construction details, and installation procedures.
- D. UL and NEMA Compliance: Provide motors and related components for motor-operated louvers that are listed and labeled by UL and comply with applicable NEMA standards.

1.7 PROJECT CONDITIONS

- A. Field Measurements: Verify actual dimensions of openings by field measurements before fabrication.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Aluminum Extrusions: ASTM B 221, Alloy 6063-T5, T-52, or T6.
- B. Aluminum Sheet: ASTM B 209, Alloy 3003 or 5005 with temper as required for forming, or as otherwise recommended by metal producer for required finish.
- C. Aluminum Castings: ASTM B 26/B 26M, Alloy 319.
- D. Fasteners: Use types and sizes to suit unit installation conditions.
1. Use hex-head or Phillips pan-head screws for exposed fasteners unless otherwise indicated.

2. For fastening aluminum, use aluminum or 300 series stainless-steel fasteners.
 3. For fastening galvanized steel, use hot-dip-galvanized steel or 300 series stainless-steel fasteners.
 4. For fastening stainless steel, use 300 series stainless-steel fasteners.
 5. For color-finished louvers, use fasteners with heads that match color of louvers.
- E. Postinstalled Fasteners for Concrete and Masonry: Torque-controlled expansion anchors, made from stainless-steel components, with capability to sustain, without failure, a load equal to 4 times the loads imposed, for concrete, or 6 times the load imposed, for masonry, as determined by testing per ASTM E 488, conducted by a qualified independent testing agency.
- F. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D 1187.

2.2 FABRICATION, GENERAL

- A. Assemble louvers in factory to minimize field splicing and assembly. Disassemble units as necessary for shipping and handling limitations. Clearly mark units for reassembly and coordinated installation.
- B. Include supports, anchorages, and accessories required for complete assembly.
- C. Provide subsills made of same material as louvers or extended sills for recessed louvers.

2.3 FIXED, EXTRUDED-ALUMINUM LOUVERS

- A. Horizontal, Nondrainable-Blade Louver:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ruskin Company; Tomkins PLC. Model ELF811 or equal by.
 - b. Airolite Company, LLC (The).
 - c. American Warming and Ventilating, Inc.; a Mestek company.
 - d. Arrow United Industries; a division of Mestek, Inc.
 - e. Carnes Company, Inc.
 - f. Cesco Products; a division of Mestek, Inc.
 - g. Greenheck Fan Corporation.
 - h. NCA Manufacturing, Inc.
 - i. Pottrof
 - j. Prior approved equal.
 2. Fabrication: Continuous blade style.
 - a. Frame:
 - 1) Frame Depth: 4 inches (102mm).
 - 2) Material: Extruded aluminum, Alloy 6063-T5.
 - 3) Wall Thickness: 0.125 inch (3.2mm), nominal.
 - b. Blades:
 - 1) Style: Horizontal "K".
 - 2) Material: Formed aluminum, Alloy 6063-T5.

- 3) Wall Thickness: 0.125 inch (3.2 mm), nominal.
- 4) Angle: 45 degrees.
- 5) Centers: 4-1/2 inches (114 mm), nominal.
- 6) Continuous Blade Style – Design incorporates visible mullions or frames at the perimeter of the louver only. Rear-mounted hidden blade supports are utilized at section joints and at intermediate locations as needed. Louver blade sightlines are not interrupted at section joints or blade support locations. The rear-mounted blade support depth varies depending on louver height and the design windload.

c. Assembly:

- 1) Factory assembled louver components. Mechanically fastened construction.

B. Performance Data:

1. Performance Ratings:

- a. Based on testing 48 inch by 48 inch (1219 mm by 1219 mm) size unit in accordance with AMCA 500.
2. Free Area: 44 percent, nominal.
3. Maximum Recommended Air Flow through Free Area: 707 feet per minute (214 m/min).
4. Air Flow: 5027 cubic feet per minute (142 cu. m/min).
5. Maximum Pressure Drop (Intake): .06 inches w.g. (14.9 Pa).
6. Water Penetration: Maximum of 0.01 ounces per square foot (3.1 g/sm) of free area at an air flow of 707 feet per minute (214 m/min) free area velocity when tested for 15 minutes.

C. Design Load: Incorporate structural supports required to withstand wind load of:

1. 20 lb/sf (0.96 kPa).
2. Per Code.
3. Louvers shall be factory engineered to withstand the specified seismic loads.
 - a. Minimum design loads shall be calculated to comply with ASCE – 7, or local requirements of Authority Having Jurisdiction.

2.4 ACCESSORIES

- A. Aluminum Insulated Blank-Off Panels: 1 inch (25 mm), aluminum skin, insulated core, factory installed with removable screws and neoprene gaskets.
- B. Hinged Frame: Continuous piano hinge attached to angle subframe.
- C. Hinged Frame: Continuous piano hinge attached to channel subframe.
- D. Bird Screen:
 1. Aluminum: Aluminum, 3/4 inch by 0.051 inch (19 mm by 1.3 mm), expanded, flattened.

2. Aluminum: Aluminum, 5/8 inch by 0.040 inch (16 mm by 1 mm), expanded, flattened.
3. Aluminum: Aluminum, 1/2 inch mesh by 0.063 inch (13 mm mesh by 1.6 mm), intercrimp.
4. Steel: Galvanized steel, 1/2 inch mesh by 19 gage (13 mm mesh by 1.1 mm), intercrimp.
5. Frame: Removable, rewireable.

2.5 FINISHES

A. Kynar:

1. Coating shall conform to AAMA 2605. Apply coating following cleaning and pretreatment. Cleaning: AA-C12C42R1X.
2. Standard 2-coat.
3. Pearledize 70 (2-coat mica).

B. 50 percent Floropolymer-Based Painted Finishes:

1. Coating shall conform to AAMA 2604, sections 4.2 and 4.3. Apply coating following cleaning and pretreatment. Cleaning: AA-C12C42R1X.
2. Baked Enamel.
3. Pearledize 50 (2-coat mica).

C. Color for Kynar Finish:

1. Color: Custom. Refer to Drawings.

D. Anodized Finishes:

1. Class 2 Clear Anodized.
 - a. Comply with Aluminum Association AA-C22A41. Clear anodized finish 215-R1.
 - b. Apply finish following chemical etching and pretreatment.
 - c. Minimum Thickness: 0.7 mils (0.018 mm), 60 minute anodizing process.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and openings, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Coordinate setting drawings, diagrams, templates, instructions, and directions for installation of anchorages that are to be embedded in concrete or masonry construction. Coordinate delivery of such items to Project site.

3.3 INSTALLATION

- A. Locate and place louvers and vents level, plumb, and at indicated alignment with adjacent work.
- B. Use concealed anchorages where possible. Provide brass or lead washers fitted to screws where required to protect metal surfaces and to make a weathertight connection.
- C. Form closely fitted joints with exposed connections accurately located and secured.
- D. Provide perimeter reveals and openings of uniform width for sealants and joint fillers, as indicated.
- E. Repair finishes damaged by cutting, welding, soldering, and grinding. Restore finishes so no evidence remains of corrective work. Return items that cannot be refinished in the field to the factory, make required alterations, and refinish entire unit or provide new units.
- F. Protect unpainted galvanized and nonferrous-metal surfaces that will be in contact with concrete, masonry, or dissimilar metals from corrosion and galvanic action by applying a heavy coating of bituminous paint or by separating surfaces with waterproof gaskets or nonmetallic flashing.
- G. Install concealed gaskets, flashings, joint fillers, and insulation as louver installation progresses, where weathertight louver joints are required. Comply with Division 7 Section "Joint Sealants" for sealants applied during louver installation.

3.4 ADJUSTING AND CLEANING

- A. Test operation of adjustable louvers and adjust as needed to produce fully functioning units that comply with requirements.
- B. Clean exposed surfaces of louvers and vents that are not protected by temporary covering, to remove fingerprints and soil during construction period. Do not let soil accumulate during construction period.
- C. Before final inspection, clean exposed surfaces with water and a mild soap or detergent not harmful to finishes. Thoroughly rinse surfaces and dry.
- D. Restore louvers and vents damaged during installation and construction so no evidence remains of corrective work. If results of restoration are unsuccessful, as determined by Architect, remove damaged units and replace with new units.
 - 1. Touch up minor abrasions in finishes with air-dried coating that matches color and gloss of, and is compatible with, factory-applied finish coating.

END OF SECTION

SECTION 26 05 00

ELECTRICAL GENERAL PROVISIONS

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Architectural, Structural, Mechanical and other applicable documents are considered a part of the electrical documents insofar as they apply as if referred to in full. Contractor must review the entire set of plans and specifications. Reviewing only the electrical set is not acceptable.

1.2 DESCRIPTION OF WORK:

- A. The extent of electrical work is indicated on drawings and/or specified in Divisions 26, 27 and 28 sections of the specification. Provide all labor, materials, equipment, supervision and service necessary for a complete electrical system. Work includes, but is not necessarily limited to, the following items.

<u>ITEM</u>	<u>SECTION</u>
1. Electrical General Provisions	26 0500
2. Mechanical and Electrical Coordination	26 0501
3. Electrical Submittals and Spare Parts	26 0502
4. Electrical Connections for Equipment	26 0507
5. Conductors and Cables	26 0519
6. Grounding	26 0526
7. Supporting Devices	26 0529
8. Conduit Raceway	26 0532
9. Electrical Boxes and Fittings	26 0533
10. Electrical Identification	26 0553
11. Occupancy Sensors	26 0923
12. Lighting Control Equipment	26 0943
13. Transformers	26 2200
14. Switchgear and Switchboards	26 2413
15. Panelboards	26 2416
16. Wiring Devices	26 2726
17. Overcurrent Protective Devices	26 2815
18. Motor and Circuit Disconnects	26 2816
19. Motor Starters	26 2913
20. Surge Protection devices	26 4313
21. Interior and Exterior Building Lighting	26 5100
22. Fire Alarm and Detection System	28 3111

- B. Use of standard industry symbols together with the special symbols, notes, and instructions indicated on the drawings describe the work, materials, apparatus and systems required as a portion of this work.
- C. Visit the site during the bidding period to determine existing conditions affecting electrical and other work. All costs arising from site conditions and/or preparation shall be included

in the base bid. No additional charges will be allowed due to inadequate site inspection.

1.3 DEFINITION OF TERMS

- A. The following terms used in Divisions 26, 27 and 28 documents are defined as follows:
1. "Provide": Means furnish, install and connect, unless otherwise indicated.
 2. "Furnish": Means purchase and deliver to project site.
 3. "Install": Means to physically install the items in-place.
 4. "Connect": Means make final electrical connections for a complete operating piece of equipment.

1.4 RELATED SECTIONS:

- A. Consult all other sections, determine the extent and character of related work and properly coordinate work specified herein with that specified elsewhere to produce a complete installation.
- B. General and Supplementary Conditions: Drawings and general provisions of contract and Division 1 of the Specifications, apply to all Division 26, 27 and 28 sections.
- C. Earthwork:
1. Provide trenching, backfilling, boring and soil compaction as required for the installation of underground conduit, buried cable, in-grade pull boxes, manholes, lighting pole foundations, etc. See Division 31, Sitework, and other portions of Divisions 26, 27 and 28, for material and installation requirements.
- D. Concrete Work:
1. Provide forming, steel bar reinforcing, cast-in-place concrete, finishing and grouting as required for underground conduit encasement, light pole foundations, pull box slabs, vaults, equipment pads, etc. See Division 3, Concrete for material and installation requirements.
- E. Miscellaneous Metal Work:
1. Provide fittings, brackets, backing, supports, rods, welding and pipe as required for support and bracing of raceways, lighting fixtures, panelboards, distribution boards, switchboards, motor controls centers, etc. See Division 5, Metals for material and installation requirements.
- F. Miscellaneous Lumber and Framing Work:
1. Provide wood grounds, nailers, blocking, fasteners, and anchorage for support of electrical materials and equipment. See Division 6, Rough Carpentry for material and installation requirements.
- G. Moisture Protection:
1. Provide membrane clamps, sheet metal flashing, counter flashing, caulking and sealants as required for waterproofing of conduit penetrations and sealing penetrations in or through fire walls, floors and ceiling slabs and foundation walls. All penetrations through vapor barriers at slabs on grade shall be taped and made vapor tight. See Division 7, Thermal and Moisture Protection for material and installation requirements.
- H. Access panels and doors:
1. Provide in walls, ceiling, and floors for access to electrical devices and equipment. See Division 8, Doors and Windows for material and installation requirements.
- I. Painting:

1. Provide surface preparation, priming and finish coating as required for electrical cabinets, exposed conduit, pull and junction boxes, poles, surface metal raceways, etc. See Division 9, Finishes for material and installation requirements.

1.5 WORK FURNISHED AND INSTALLED UNDER ANOTHER SECTION REQUIRING CONNECTIONS UNDER THIS SECTION:

- A. Provide electrical service, make requisite connections and perform operational test. Items furnished and installed under other sections and connected under this section, include but are not limited to the following:
1. Electric motors.
 2. Package mechanical equipment: fans, fan coil units, pumps, boilers, duplex compressors, etc.
 3. Irrigation controllers.
 4. Electric hardware.
 5. Laboratory equipment including hoods, cold rooms, autoclaves, drying ovens, glassware washers and dryers, refrigerators, freezers, etc.
 6. Shop equipment including saw dust collectors, saws, lathes, grinders, welders, planers, presses, etc.
 7. Water coolers.
 8. Fire sprinkler alarm bells.
 9. Electric heat trace cable for domestic and industrial hot water piping systems.
 10. Electric heat trace cable for guttering, drain lines, etc.
 11. Hand dryers, hair dryers.

1.6 ITEMS FURNISHED UNDER ANOTHER DIVISION, BUT INSTALLED AND CONNECTED UNDER THIS DIVISION:

- A. Items furnished under other Divisions, but turned over to Division 26 for installation and final connection include, but are not necessarily limited to, the following:
1. Wall mounted control stations for motorized roll-up doors/grills.
 2. Wall mounted control stations for motorized projection screens.

1.7 WORK NOT INCLUDED IN THIS DIVISION:

- A. Items of work provided under another contract include, but are not necessarily limited to, the following:
1. Telephone cables and electronic equipment.
 2. Data system cables, fittings, coverplates and electronic equipment.
 3. Control wires for irrigation control valves.
 4. Energy management/temperature control system; both line and low voltage including conductors and conduit.
 5. Television monitors and projection equipment.
 6. Security system equipment, cables, fittings, and coverplates.
 7. CCTV cabling and electronic equipment.
 8. MATV cabling and electronic equipment

1.8 INTERPRETATION OF DRAWINGS AND SPECIFICATIONS:

- A. Before bidding, Contractor shall familiarize himself with the drawings, specifications and project site. Submit requests for clarification to Architect/Engineer in writing prior to issuance of final addendum. After signing the contract, the Contractor shall meet the intent, purpose, and function of the Contract Documents. Any costs of materials, labor and equipment arising therefrom, to make each system complete and operable, is the

responsibility of the Contractor.

1.9 QUALITY ASSURANCE:

- A. Reference to codes, standards, specifications and recommendations of technical societies, trade organizations and governmental agencies refers to the latest edition of such publications adopted and published prior to submittal of the bid proposed, unless noted otherwise herein. Such codes or standards are considered a part of this specification as though fully repeated herein.
- B. When codes, standards, regulations, etc. allow work of lesser quality or extent than is specified under this Division, nothing in said codes shall be construed or inferred as reducing the quality, requirements or extent of the Drawings and Specifications. Perform work in accordance with applicable requirements of all governing codes, rules and regulations including the following minimum standards, whether statutory or not:
 - 1. National Electric Code (NEC).
 - 2. International Building Code (IBC).
 - 3. International Fire Code (IFC).
 - 4. International Mechanical Code (IMC).
- C. Standards: Comply with the following standards where applicable for equipment and materials specified under this Division.
 - 1. UL Underwriters' Laboratories
 - 2. ASTM American Society for Testing Materials
 - 3. CBN Certified Ballast Manufacturers
 - 4. IPCEA Insulated Power Cable Engineers Association
 - 5. NEMA National Electrical Manufacturer's Association
 - 6. ANSI American National Standards Institute
 - 7. ETL Electrical Testing Laboratories
- D. All electrical apparatus furnished under this Section shall conform to (NEMA) standards and the NEC and bear the Underwriters' Laboratories (UL) label where such label is applicable.
- E. Comply with requirements of State and Local Ordinances. If a conflict occurs between these requirements and the Contract Documents, the most stringent requirements shall govern. The Contractor accepts this responsibility upon submitting his bid, and no extra charge will be allowed after the contract is awarded. This shall not be construed as relieving the Contractor from complying with any requirements of the Contract Documents that may be in excess of the aforementioned requirements, and not contrary to same.
- F. Obtain all permits, inspections, etc. required by authority having jurisdiction. Include all fees in bid. Furnish a certificate of approval to the Owner's Representative from the Inspection Authority at completion of the work.
- G. Employ only qualified craftsmen with at least three years of experience. Workmanship shall be neat, have a good mechanical appearance and conform to best electrical construction practices. Provide a competent superintendent to direct the work at all times. Any person found incompetent shall be discharged from the project and replaced by satisfactory personnel.
- H. Contractor shall have a current state contracting license applicable to type of work to be performed under this contract.

1.10 CONSTRUCTION CHANGE ORDER PROPOSALS

- A. In the event that a submission of a change order is issued by the contractor, the following information will be required to be submitted by the contractor, prior to any consideration by the owner/architect.
- a. Where project manager or project engineer work is required, the labor cost shall not exceed 2% of the electrical portion of the change order.
 - b. All equipment, including conduit and wire, shall be itemized, identifying unit costs and quantities of equipment. Distributor quotes shall accompany all change order requests. The distributor quotes shall include costs for all equipment including conduit and wire. Lot pricing for equipment is not acceptable.
 - c. The general contractor shall review and confirm that the quantity and costs of materials submitted appear reasonable for the scope proposed.
 - d. Labor units shall not exceed base NECA #1 standards. No adjustment factors shall be approved.
 - e. Any research and labeling time, shall be the responsibility of the electrical contractor and shall not be included in the change order request.
 - f. Any costs associated with the purchase of tools or transportation shall be fully itemized for review by architect/owner.
 - g. Overtime rates shall only be approved where additional manpower cannot achieve the same result.
 - h. Change order form shall follow the following format:
 - i. PCO number
 - ii. Detailed description of work being performed
 - iii. Location on project where work is performed
 - iv. Chosen NECA column
 - v. Identified material:
 1. QTY
 2. Unit cost
 3. Mark up
 4. Material total
 - vi. Identified labor:
 1. QTY
 2. Unit cost
 3. Composite labor rate
 4. Labor total

1.11 RECORD DRAWINGS:

- A. Maintain, on a daily basis, a complete set of "Record Drawings", reflecting an accurate record of work in accordance with the following:
1. Show the complete routing and location of all feeders rated 100 amps and larger. Locate work buried below grade or under slab, work concealed above ceilings, and work in concealed spaces, dimensionally from fixed structural elements (not partition walls, etc.)
 2. Show the complete routing and location of all telecommunications conduits, systems raceways, and empty raceways, 1-1/4" and larger. Locate work buried below grade or under slab, work concealed above ceilings, and work in concealed spaces, dimensionally from fixed structural elements (not partition walls, etc.).
 3. Show all changes, deviations, addendum items, change orders, job instructions, etc., that change the work from that shown on the contract documents, including wall relocations, fixtures and device changes, branch circuiting changes, etc. Where locations of boxes, raceways, equipment, etc. are adjusted in the field to

fit conditions, but such new locations may not be obvious by referring to the contract document, show new locations on the record drawings.

- B. At the discretion of the Architect/Engineer, the drawings will be reviewed on a periodic basis and used as a pre-requisite for progress payments. This requirement shall not be construed as authorization for the Contractor to make changes in the layout, or work without written authorization for such changes. The "Record Drawings" for daily recording shall consist of a set of blue line prints of the Contract Drawings.
- C. Upon completion of the work, purchase a complete set of electronic drawings. Transfer all "Record" information from the blue line prints to the drawings via the current CAD program that it was written. The Architect/Engineer shall review the drawings and the Contractor shall incorporate the resulting comments into the final record drawings. The Contractor shall make two complete copies of the drawings electronically and forward this to the Engineer.
- D. Certify the "Record Drawings" for correctness by placing and signing the following certifications of the first sheet of the drawings:

"CERTIFIED CORRECT (3/8" high letters)

(Name of General Contractor)

By: _____ Date: _____

(Name of Electrical Contractor)

By: _____ Date: _____

1.12 GUARANTEE:

- A. Ensure that electrical system installed under this contract is in proper working order and in compliance with drawings, specifications, and/or authorized changes. Without additional charge, replace any work or materials that develop defect, except from ordinary wear and tear, within one year from the date of substantial completion. Exception: Incandescent and fluorescent lamps shall be guaranteed for a period of two months from the date of substantial completion.

1.13 OTHER:

- A. Right to Hire. "Client" agrees that during the project and for a period of twenty four (24) months following substantial completion that it will not, directly or indirectly, employ or solicit to employ BNA Personnel.

PART 2 PRODUCTS

2.1 GENERAL:

- A. Products are specified by manufacturer name, description, and/or catalog number. Discrepancies between equipment specified and the intended function of equipment shall be brought to the attention of the Architect/Engineer in writing prior to bidding. Failure to report any conflict, including catalog numbers, discontinued products, etc., does not relieve the Contractor from meeting the intent of the contract documents nor shall it change the contract cost. If the Contractor is unable to interpret any part of the plans and/or specifications, or should he find discrepancies therein, he shall bring this to the attention of the Architect/Engineer who will issue interpretation and/or additional instructions to Bidders before the project is bid.

2.2 MANUFACTURERS:

- A. Provide products of manufacturers specified. Manufacturers catalog numbers and

descriptions establish the quality of product required. Substitutions will be considered if a duplicate written application (2-copies) is at the office of the Architect/Engineer eight (8) working days prior to the day of the bidding. The application shall include the following: 1) A statement certifying that the equipment proposed is equal to that specified; that it has the same electrical and physical characteristics, compatible dimensions, and meets the functional intent of the contract documents; 2) The specified and submittal catalog numbers of the equipment under consideration; 3) A pictorial and specification brochure.

- B. Any conflict arising from the use of substituted equipment shall be the responsibility of the Contractor, who shall bear all costs required to make the equipment comply with the intent of the contract documents.
- C. Samples may be required for non-standard or substituted items before installation during construction. Provide all samples as required.
- D. No materials or apparatus may be substituted after the bid opening except where the equipment specified has been discontinued.
- E. Provide only equipment specified in the Contract Documents or approved by addendum.

2.3 SPARE PARTS:

- A. Provide spare parts (fuses, diffusers, lamps, etc.) as specified. Transmit all spare parts to Owner's Representative prior to substantial completion.

PART 3 EXECUTION

3.1 INSTALLATION:

- A. Layout electrical work in advance of construction to eliminate unnecessary cutting, drilling, channeling, etc. Where such cutting, drilling, or channeling becomes necessary for proper installation; perform with care. Use skilled mechanics of the trades involved. Repair damage to building and equipment at no additional cost to the contract. Cutting work of other Contractors shall be done only with the consent of that Contractor. Cutting structural members shall not be permitted.
- B. Provide equipment enclosures appropriate to the environment to which they are installed. For example, provide NEMA 3R for exterior enclosures and NEMA 1 for interior enclosures unless otherwise noted.
- C. Since the drawings of floor, wall, and ceiling installation are made at small scale; outlets, devices, equipment, etc., are indicated only in their approximate location unless dimensioned. Locate outlets and apparatus symmetrically on floors, walls and ceilings where not dimensioned, and coordinate such locations with work of other trades to prevent interferences. Verify all dimensions on the job. Do not scale the electrical drawings, but refer to the architectural and mechanical shop drawings and project drawings for dimensions as applicable.
- D. Perform for other trades, the electrical wiring and connection for all devices, equipment or apparatus. Consult Architectural, Mechanical, and other applicable drawings, and all applicable shop drawings to avoid switches, outlets, and other equipment from being hidden behind doors, cabinets, counters, heating equipment, etc., or from being located in chalkboards, tackboards, glass panels, etc. Relocate buried electrical devices and/or connections as directed at no additional cost.
- E. Coordinate the location of outlets, devices, connections, and equipment with the supplier of the systems furniture prior to rough-in.
- F. Where conduit, outlets or apparatus are to be encased in concrete, it must be located and secured by a journeyman or foreman present at the point of installation. Check locations of the electrical items before and after concrete and/or masonry installation and relocate displaced items.

- G. Provide block-outs, sleeves, demolition work, etc., required for installation of work specified in this division.

3.2 CLEAN:

- A. Clean up all equipment, conduit, fittings, packing cartons and other debris that is a direct result of the installation of the work of this Division.
- B. Clean fixtures, interiors and exteriors of all equipment, and raceways. Replace all filters in electrical equipment upon request for Substantial Completion.

3.3 POWER OUTAGES:

- A. All power outages required for execution of this work shall occur during non-standard working hours and at the convenience of the Owner. Include all costs for overtime work in bid.
- B. Submit written request at least 7 days in advance of scheduled outage and proceed with outage only after receiving authorization from the Owner's Representative.
- C. Keep all outages to an absolute minimum.

3.4 STORAGE AND PROTECTION OF MATERIALS:

- A. Provide storage space for storage of materials and apparatus and assume complete responsibility for all losses due to any cause whatsoever. In no case shall storage interfere with traffic conditions in any public thoroughfare or constitute a hazard to persons in the vicinity. Protect completed work, work underway, and apparatus against loss or damage.

3.5 EXCAVATING FOR ELECTRICAL WORK:

- A. General: Locate and protect existing utilities and other underground work in manner that will ensure that no damage or service interruption will result from excavating and backfilling. Perform excavation in a manner that protects walls, footings, and other structural members from being disturbed or damaged in any way. Burial depths must comply with NEC Section 300-5 (or State of Utah requirement, whichever is more stringent), unless noted otherwise on drawings.
- B. Protect persons from injury at excavations, by barricades, warnings and illumination.
- C. Coordinate excavations with weather conditions, to minimize possibility of washouts, settlements and other damages and hazards.
- D. Provide temporary covering or enclosure and temporary heat as necessary to protect bottoms of excavations from freezing and frost action. Do not install electrical work on frozen excavation bases or sub-bases.
- E. Do not excavate for electrical work until the work is ready to proceed without delay, so that total time lapse from excavation to completion of backfilling will be minimum. See other sections of specification for additional requirements for excavating.
- F. Store excavated material (temporarily) near excavation, in a manner that will not interfere with or damage excavation or other work. Do not store under trees (within drip line).
- G. Retain excavated material that complies with requirements for backfill material. Dispose of excavated material that is either in excess of quantity needed for backfilling or does not comply with requirements for backfill material. Remove unused material from project site, and dispose of in lawful manner.

3.6 BACKFILL MATERIALS:

- A. For buried conduit or cable (other than below slab-on-grade, or concrete encased) - 2"

thickness of well graded sand on all side of conduit or cable.

- B. For trench backfill to within 6" of final grade - soil material suitable for compacting to required densities.
- C. For top 6" of excavation - Top soil.
- D. Backfill excavations in 8" high courses of backfill material, uniformly compacted to the following densities (percent of maximum density, ASTM D 1557), using power-driven hand-operated compaction equipment.
 - 1. Lawn/Landscaped Areas: 85 percent for cohesive soils, 95 percent for cohesionless soils.
 - 2. Paved Areas, Other than Roadways (90 percent for cohesive soils, 95 percent for cohesionless soils).
- E. Subsidence: Where subsidence is measurable or observable at electrical work excavations during general project warranty period, remove surface (pavement, lawn or other finish), add backfill material, compact, and replace surface treatment. Restore appearance, quality and condition of the surface or finish to match adjacent work, and eliminate evidence of restoration to greatest extent possible.

3.7 CONCRETE BASES:

- A. Unless otherwise noted, provide 4" high reinforced concrete bases for all floor mounted or floor standing electrical equipment, including generators, transformers, switchgear, battery racks, motor control centers, etc. Extend bases 6" beyond equipment or mounting rails on all sides or as shown on the drawings. Notwithstanding this requirement, coordinate with equipment manufacturer, shop drawings, and height of base to ensure compliance with NEC 404.8.
- B. Concrete bases shall be provided under Divisions 26, 27 and 28. Coordinate size and location of all bases and furnish all required anchor bolts, sleeves, reinforcing and templates as required to obtain a proper installation.
- C. Provide and locate properly sized concrete pads for power company furnished pad mounted transformers in accordance with power company clearance requirements. Where the serving utility is Rocky Mountain Power, the electrical contractor shall conform to the requirements of Electrical Service Requirements, Section 6.4.

3.8 ROOF PENETRATIONS:

- A. Where raceways penetrate roofing or similar structural area, provide appropriate roof jack coordinate with the roofing contractor and the Architect in order to match the vent with the roof construction. The jack shall be sized to fit tightly to raceway for weather-tight seal, and with flange extending a minimum of 9" under roofing in all sides or as required by the roof type of construction. Completely seal opening between inside diameter of roof flashing and outside diameter of penetrating raceways. Coordinate all work with work required under roofing section of specifications.

3.9 FIRE PENETRATION SEALS:

- A. Seal all penetrations for work of this section through fire rated floors, walls and ceilings to prevent the spread of smoke, fire, toxic gas or water through the penetration either before, during or after fire. The fire rating of the penetration seal shall be at least that of the floor, wall or ceiling that it is installed, so that the original fire rating of the floor or wall is maintained as required by Article 300-21 of the National Electrical Code. Where applicable, provide OZ Type CFSF/I and CAFSF/I fire seal fittings for conduit and cable penetrations through concrete and masonry walls, floors, slabs, and similar structures. Where applicable, provide [3M](#) CID cast-in device for floor slabs. Where applicable, provide [3M](#) fire barrier sealing penetration system, and/or IPC Flame Safe Fire Stop System, and/or Chase Foam fire stop system, including wall wrap, partitions, caps, and

other accessories as required. All materials to comply with UL 1479 (ASTM E-814). Comply with manufacturer's instructions and recommendations for installation of sealing fittings and barrier sealing systems.

3.10 PROJECT FINALIZATION AND START-UP:

- A. Upon completion of equipment and system installation, assemble all equipment Factory Representatives and Subcontractors for system start-up.
- B. Each Representative and Subcontractor shall assist in start-up and check out their respective system and remain at the site until the total system operation is accepted by the Owner's representative.
- C. The Factory Representative and/or System Subcontractor shall give personal instruction on operating and maintenance of their equipment to the Owner's maintenance and/or operation personnel. To certify acceptance of operation and instruction by the Owner's Representative, the contractor shall prepare a written statement as follows:
 - 1. This is to certify that the Factory Representative and System Subcontractor for each of the systems listed below have performed start-up and final check out of their respective systems.
 - 2. The Owner's Representative has received complete and thorough instruction in the operation and maintenance of each system.

SYSTEM	FACTORY REPRESENTATIVE
(List systems included)	(List name and address of Factory Representative)

Owner's Representative

Contractor

- D. Send copy of acceptance to Architect/Engineer.

3.11 FINAL REVIEW:

- A. At the time of final review, the project foreman shall accompany the reviewing party, and remove coverplates, panel covers and other access panels as requested, to allow review of the entire electrical system.

END OF SECTION

SECTION 26 0501

MECHANICAL AND ELECTRICAL COORDINATION

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Architectural, Structural, Vertical Transportation, Mechanical and other applicable documents are considered a part of the electrical documents insofar as they apply as if referred to in full. Contractor must review the entire set of plans and specifications. Reviewing only the electrical set is not acceptable.

1.2 CONTRACTOR RESPONSIBILITIES

- A. Electrical Contractor shall verify electrical service provided prior to ordering any electrical equipment serving mechanical equipment, and Electrical Contractor shall have the final responsibility for properly coordinating the electrical work, including the exact location, quantity and sizes of the electrical connection(s).
 - 1. Circuit breakers, disconnects, starters, fuses, conduit sizes, wire sizes, VFDs, etc. have been coordinated by Engineers and sized according to the mechanical systems "Basis of Design". Coordinate with Division 23 Contractor for any changes arising from substituted equipment or changes to the basis of design in any way. Coordinate all requirements of multi-motor VFD control (including fanwall units) and ensure all provisions accordingly. Prepare documentation showing changes in the electrical characteristics of each piece of equipment that has changed and submit for acceptance. All costs arising from said changes shall be the responsibility of Division 23.
- B. Obtain submittals of all mechanical equipment from Division 21 through 23 contractor(s) as they are submitted to design team.
 - 1. Notify engineer of any modifications between contract documents and submittals. It shall be the contractor's responsibility to ensure compliance with the documents.
- C. Electrical contractor shall be responsible for coordinating all their own blockouts and coordinating their space of a shared blockout.
- D. Coordinate all interfaces between Mechanical and Electrical/Communications/Security Divisions before submitting any equipment for review or beginning installation.

1.3 ABBREVIATIONS

- A. MC: Mechanical Contractor = Divisions 21 through 23 Contractor who provides equipment and motor.
- B. TC: Temperature Controls = Division 23 09 00 Contractor who provides control.
- C. EC: Electrical Contractor = Divisions 26 through 28 Contractor who provides power/data.
- D. FA: Fire Alarm Contractor = Division 28 Contractor who furnishes Fire Alarm System.

1.4 RESPONSIBILITY SCHEDULE

- A. Responsibility: Unless otherwise indicated, all equipment, motors, and controls for Divisions 21 through 23 equipment shall be furnished, set in place and wired in accordance with the following schedule:

ITEM -	Furnished Under	Set In Place Under	Power Wiring Under	Control Wiring Under
Equipment Motors	MC	MC	EC	--
Automatically or Manually Controlled Starters/Contactors: (Note 4)				
-Separate	MC	EC	EC	TC
-Factory Mounted and Wired	MC	MC	EC	TC
Motor Speed Controllers: (Note 4)				
-Separate	MC	EC	EC	TC
-Factory Mounted and Wired	MC	MC	EC	TC
Disconnect Switches (Note 1)	EC	EC	EC	--
Thermal Overload Switches (Note 1)	EC	EC	EC	--
Switches (Manual or Automatic other than disconnect) (Note 2)	MC or TC	MC or TC	EC or TC	TC or MC
Control Relays (Note 2)	MC or TC	MC or TC	--	TC
Control Transformers	MC or TC	MC or TC	TC	TC
Thermostat and Controls: Integral with Equipment or Directly Attached to Ducts, Pipes, etc. (Note 2)	MC or TC	MC or TC	TC	TC
Equipment in Temperature Control Panels	TC	TC	EC	TC
Standalone Control Panels (BAS) (Note 6)	TC	TC	EC	TC
Valve Motors, Damper Motors, Solenoid Valves, etc.	TC	TC	TC	TC
EP Valves or Switches, P.E. Switches, etc.	TC	TC	--	TC
Fire Alarm System (Note 3)	FA	FA	EC	FA

B. Responsibility Schedule Notes:

1. If furnished as part of factory wired equipment furnished and set in place by MC, wiring and connections by EC.
2. If float switches, line thermostats, P.E. switches, time switches, or other controls carry the FULL LOAD CURRENT to any motor, they shall be furnished by MC, but they shall be set in place and connected by EC, except that where such items are an integral part of the mechanical equipment, or directly attached to ducts, piping, or other mechanical equipment, they shall be furnished and set in place by MC and connected by EC. If they do not carry the FULL LOAD CURRENT to any motor, they shall be furnished, set in place and wired by TC contractor.
3. Electrical contractor is responsible for wiring from starter to motor, unless factory wired.
4. Temperature control contractor shall provide conduit and wire from auxiliary contact in motor starter to the detector so that the unit shuts down in all operating modes. Fire Alarm Contractor to wire from detector to fire alarm panel.
5. Each division shall be fully responsible for any control panels as called for on the drawings or specifications.
 - a. Division 26 and 28 shall provide all power and control wiring to fire/smoke or smoke dampers. Division 23 shall provide parallel control wiring (with 28 fire alarm having priority signal) to dampers and equipment utilized in both normal and smoke control modes. Refer to Smoke Control and Fire Alarm Drawings and the Fire Alarm Matrix.
 - b. Fire alarm system shall override automated building control system during smoke exhaust mode.
 - c. TC wiring required only when damper also serves HVAC system.

6. FA wires from the fire alarm control panel necessary for the initiation and monitoring of the Smoke Management System Control Panel. TC wires to components and smoke control fans and dampers utilized in the control and monitoring of the Automated Building Control System.
 7. Division 26 shall provide power to junction box on the exterior of the AHU.
- C. Power Wiring by Divisions 21 through 23: The electrical power for certain equipment provided under Divisions 21 through 23 has not been specifically indicated on the electrical drawings and must be provided by and field coordinated by the Divisions 21 through 23 trades requiring such power. Electrical contractor shall review Division 21 through 23 drawings and coordinate with said contractors to confirm power needs.
1. Sufficient power for this purpose shall be furnished as “spare” dedicated circuit capacity in Division 26’s panelboards. All wiring, conduit and electrical devices downstream of the panelboards are the responsibility of the Divisions 21 through 23 trades requiring the power.
 - a. Such equipment is hereby defined as:
 - b. Fire protection air compressors, dry-pipe control panels and valves. Required connections are included in the Division 21 work, and will be shown by that contractor’s engineered system design drawings.
 - c. Pre-action system alarm and trouble initiation signals (such as smoke detectors or general alarm conditions in a pre-action zone) shall be provided under Division 28 fire alarm work.
 - d. Division 21 shall provide pre-action control panel and interconnection between pre-action panel and location of pre-action valve(s).
 - e. Division 28 shall provide interconnection between fire command center alarm panel (provided under Division 28) and remote communication fire alarm panel (provided under Division 28).
 - f. Infrared plumbing fixtures. Fixtures requiring power are shown on the plumbing drawings and schedules. Provide junction box and or receptacle as required by manufacturer.
 - g. Temperature control panels, control air compressors and line voltage power for 24v control transformers. Required connections are included in Division 23 09 00 and will be shown by that contractor’s control submittal drawings.
 - h. Condensate pumps. Provide power from associated unit or from nearby panelboard.
 - i. BAS or Control System Gateways. Provide power from nearest panelboard and single data cable from nearest telecommunications room.

1.5 GENERAL REQUIREMENTS

- A. Special Requirements:
1. Motors, starters and other electrical equipment installed in moist areas or areas of special conditions, such as explosion proof, shall be designed and approved

1.6 CEILING AND CHASE CAVITY PRECEDENCE

- A. Coordinate ceiling cavity space carefully with all trades. In the event of conflict, install mechanical and electric systems within the cavity space allocation in the following order of precedence. A system with higher precedence may direct that systems of lower precedence be relocated from space, which is required for expedient routing of the precedent system.

1. Plumbing waste, cooling coil drain piping, and roof drain mains and leaders.
 2. Condensate piping.
 3. Hydronic main piping (8" and larger).
 4. Plumbing vent piping.
 5. Supply, return and exhaust ductwork.
 6. Cable tray systems.
 7. Electrical conduit 4" diameter or greater.
 8. Hydronic branch and mains (greater than 2", but less than 8").
 9. Domestic water piping.
 10. Fire sprinkler mains and leaders.
 11. Hydronic branch piping (2" and less).
 12. Domestic hot and cold-water branches.
 13. Electrical branch conduits.
 14. Pneumatic control piping.
 15. Fire sprinkler branch piping and sprinkler runouts.
- B. Light fixtures have precedence in a zone, which is the same height above the ceiling as the depth of the fixture (plus 2").
- C. Examine the contract documents of all trades (e.g. all Divisions 21 through 23 and 26 through 28 drawings, the architectural floor plans, reflected ceiling plans, elevations and sections, structural plans and sections, etc.).
- D. Coordinate necessary equipment, ductwork and piping locations so that the final installation is compatible with the materials and equipment of the other trades.
- E. Prepare shop drawings for installation of all new work before installation to verify coordination of work between trades.
- F. Provide access doors for all electrical and communications equipment which require access for adjustment or servicing and which are in otherwise inaccessible locations. All access door locations must be approved by the architect prior to installation and be in as inconspicuous location as possible.
1. For equipment located in "accessible locations" such as lay-in ceilings: Locate equipment to provide adequate service clearance for normal maintenance without removing architectural, mechanical, electrical or structural elements such as the ceiling support system, electrical fixtures, etc. "Normal maintenance" includes, but is not limited to: replacement of drivers, fuses, etc.

1.7 BLOCKOUT USAGE

- A. Electrical and Mechanical Contractors shall review the contract documents and advise if additional blockouts are necessary for the execution of work. Electrical and Mechanical Contractors shall coordinate and hold meetings with other contractors who will occupy the blockouts to ensure sufficient space is allocated for their scope of work. It is not acceptable to delay this meeting until conduit/piping/tray is being installed. Change orders are not acceptable due to a lack of contractor coordination prior to commencing rough in.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION 26 0501

SECTION 26 05 02

ELECTRICAL SUBMITTALS, O & M MANUALS AND SPARE PARTS

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to all Division 26, 27 and 28 sections.
- B. Architectural, Structural, Mechanical and other applicable documents are considered a part of the electrical documents insofar as they apply as if referred to in full. Contractor must review the entire set of plans and specifications. Reviewing only the electrical set is not acceptable.
- C. Consult all other sections, determine the extent and character of related work and properly coordinate work specified herein with that specified elsewhere to produce a complete installation.

1.2 SUBMITTAL REQUIREMENTS:

A. GENERAL:

- 1. After the Contract is awarded but prior to ordering, manufacture, or installation of any equipment, prepare complete Submittals including shop drawings, product data, brochures, etc. for materials and equipment as required by each section of the specification.
- 2. Review of Submittals shall not relieve the Contractor of responsibility for dimensions and/or errors that may be contained therein, or deviations from the Contract Document's requirements. It shall be clearly understood that the noting of some errors but overlooking others does not grant the Contractor permission to proceed in error. Regardless of any information contained in the Shop Drawings and Brochures, the requirements of the Contract Document's shall govern and are not waived, or superseded in any way by the review of the Shop Drawings and Brochures.
- 3. Submittals are reviewed, not approved. Comments made within submittals do not alter the contract documents in any way. The contractor is still responsible, regardless of comments (if any) made within submittals, for complying with drawings and specifications.
- 4. Notify engineer in writing if any of the comments noted in the submittals alter the contract cost. A comment within the submittal process which increases/decreases cost of product is not an authorization to the contractor under any circumstances to proceed.
- 5. Notify engineer of any modifications between contract documents and submittals. It is the responsibility of the contractor to ensure compliance.
- 6. ELECTRONIC SUBMITTAL REQUIREMENTS:
 - a. Provide submittals in Portable Document Format (PDF).
 - b. Documents must be electronically bookmarked by Division e.g. 26, 27 and 28, Specification section e.g. 26 0510 and individually for each item submitted for light fixtures, switchgear, transformer, panelboard etc. and keyword searchable using Adobe Acrobat (<http://www.adobe.com/acrobat>) or Bluebeam Revu (<http://www.bluebeam.com>) for each relevant section.

- c. Electronically highlight all options for light fixtures, electrical equipment, etc. Manual highlighting and scanning of the documents is NOT acceptable and will NOT be reviewed.
- d. Provide only completed cutsheets for all fixture and equipment types. Blank cutsheets submitted with a schedule are NOT acceptable and will NOT be reviewed.
- e. At the time of submission, the electrical contractor shall provide a complete and comprehensive submission of all required specification sections/shop drawings at the same time. Exceptions may be given, with prior approval, for time-sensitive equipment.
- f. A maximum of one submittal per specification section is allowed. It is NOT acceptable to provide a product by product submittal. Single product by product submittals will NOT be reviewed.

B. SCHEDULING

1. GENERAL

- a. A minimum period of two weeks, exclusive of transmittal time, will be required each time Submittals are submitted or resubmitted for review. This time period shall be considered by the Contractor when scheduling submittal data.
- b. If the shop drawings are rejected twice, the contractor shall reimburse the engineering firm the sum of \$1,200.00 for the third review and any additional reviews required prior to the commencement of additional review.

C. QUALITY ASSURANCE

1. PRE-SUBMITTAL PREPARATION

- a. Prior to submission of the Shop Drawings and Project Data, review and certify that they are in compliance with the Contract Documents. Verify all dimensional information to ensure proper clearance for installation of equipment.
- b. Shop drawings requiring the use of electronic documents (floor plans, Lighting plans, fire alarm plans, etc.) shall be requested via a request for information (RFI) through the general contractor. Electronic documents will be provided to the Architect for distribution. No direct vendor requests will be accepted.
- c. Contractor is completely responsible for the content of the submittal

2. SUBMITTAL REQUIREMENTS

- a. Provide a stamp or statement on each submittal as follows:
 - i. I hereby certify that this Shop Drawing and/or Brochure has been checked prior to submittal and that it complies in all respects with the requirements of the Contract Drawings and Specifications for this Project.
(Name of Electrical Subcontractor)

Name_____.

Position_____ Date_____
 - i. Failure to provide certification will result in submittals being rejected and returned without review.
- b. Brochures to be submitted as supplementary information shall be published by the Manufacturers and shall contain complete and detailed

engineering and dimensional information. Brochures submitted shall contain only information relevant to the particular equipment or materials to be furnished. The Contractor shall not submit catalogs that describe several different items in addition to those items to be used, unless all irrelevant information is marked out, or unless relevant information is clearly marked. Brochures from each manufacturer shall be identified and submitted separately.

- c. Shop Drawings shall be done in an easily legible scale and shall contain sufficient plans, elevations, sections, and isometrics to clearly describe the equipment or apparatus, and its location. Drawings shall be prepared by an Engineer/Draftsman skilled in this type of work. Shop Drawings shall be drawn to at least 1/4" = 1'0" scale.
- d. Observe the following rules when submitting the Shop Drawings and Brochures.
 - i. Each Shop Drawing shall indicate in the lower right hand corner, and each Brochure shall indicate on the front cover the following: Title of the sheet or brochure, name and location of the building; names of the Architect and Electrical Engineer, Contractor, Subcontractors, Manufacturer, Supplier/Vendor, etc., date of submittal, and the date of correction and revision. Unless the above information is included the submittal will be rejected and returned without being reviewed.
 - 1. Submittal Identification shall include the following:
 - a. A unique number, sequentially assigned, shall be noted on the transmittal form accompanying each item submitted.
 - b. Original submittal numbers shall have the following format: "XXX-Y;" where "XXX" is the originally assigned submittal number and "Y" is a sequential letter assigned for resubmittals (for example, A, B, or C being the first, second, and third resubmittals, respectively). Submittal 25B, for example, is the second resubmittal of Submittal 25.

D. POST-SUBMITTAL

- 1. Check all materials and equipment after arrival on the job site and verify compliance with the Contract Documents.

1.3 PROVIDE SUBMITTALS AS REQUESTED FOR EACH OF THE SECTIONS LISTED BELOW:

- A. 26 0519 Conductors and Cables
 - 1. (600V and Below)
 - a. Submit megohmmeter test data for circuits under 600 volts. Megger all circuits of 100 amp and greater rating.
- B. 26 0526 Grounding
 - 1. Submit the name of test agency to be used for testing specified in this section. Submit results of tests specified in this section. Also include test results in

Operation and Maintenance Manuals as specified.

- C. 26 0532 Conduit Raceway
 - 1. Submit manufacturer's data on MC-PCS Power & Control/Signal Cable.
- D. 26 0533 Electrical Boxes and Fittings
 - 1. Submit manufacturer's data including specifications, installation instruction and general recommendations for each type of floor box used on project.
- E. 26 0923 Occupancy Sensors
 - 1. Submit manufacturer's data on occupancy sensors, control modules, wiring diagrams, instructions for installation, interconnection diagrams and any related accessories.
 - 2. Submit scaled drawings with lighting fixtures shown and sensor equipment/devices clearly marked by manufacturer showing proper product, location, coverage pattern and orientation of each sensor.
- F. 26 0943 Lighting Control Equipment
 - 1. Submit manufacturer's data on lighting control equipment including, but not limited to published catalog data sheets, rough-in diagrams and instructions for installation, operating and maintenance, suitable for inclusion in maintenance manuals.
 - 2. Submit detailed drawings and documentation of lighting control components and interconnection including, but not necessarily limited to:
 - a. Electronic controllers
 - b. Control stations
 - c. Photo sensors
 - d. Occupancy sensors
 - e. Network wiring details
 - f. Input and output wiring details
 - g. Lighting control panel load schedules
 - h. Accurately scaled equipment layouts, wire/cable routing and connections to control wiring and electrical power feeders.
 - i. Submit scaled drawings/floor plans with locations of all equipment and
- G. 26 2413 Switchgear and Switchboards
 - 1. Submit manufacturer's data and shop drawings only after completion of the preliminary protective device study (see Section 26 0573 as applicable). Any Section 26 2413 submittals received prior to submission of the preliminary protective device study will be REJECTED.
 - 2. Submit manufacturer's data on switchgear and switchboards.
 - 3. Submit dimensioned drawings of switchgear and switchboards showing accurately scaled basic sections including, but not necessarily limited to, auxiliary compartments, section components, and combination sections. Show plan view of equipment with dimensioned clearances to proximate equipment. Failure to submit said plan view shall not relieve contractor of responsibility to verify required clearances before release of equipment for fabrication.
- H. 26 2416 Panelboards
 - 1. Submit manufacturer's data and shop drawings only after completion of the

preliminary protective device study (see Section 26 0573 as applicable). Any Section 26 2416 submittals received prior to submission of the preliminary protective device study will be REJECTED.

2. Submit dimensioned drawings of panelboards and enclosures showing accurately scaled layouts of enclosures and required individual panelboard devices, including but not necessarily limited to, circuit breakers, fusible switches, fuses, ground-fault circuit interrupters, and accessories.
 3. Submit manufacturer data including specifications, installation instructions and general recommendations, for each type of panelboard required.
- I. 26 2726 Wiring Devices
1. Submit manufacturer's data on electrical wiring devices.
- J. 26 2815 Overcurrent Protective Devices
1. Submit manufacturer's data and shop drawings only after completion of the preliminary protective device study (see Section 26 0573 as applicable). Any Section 26 2815 submittals received prior to submission of the preliminary protective device study will be REJECTED.
 2. Submit manufacturer's data on overcurrent protective devices, including catalog cuts, time-current trip characteristic curves, and mounting requirements.
 3. Submit layout drawings of overcurrent protective devices, with layouts of circuit breakers, including spatial relationships to proximate equipment. Failure to submit said spatial layouts does not relieve contractor of responsibility to verify all required clearances before release of equipment for fabrication.
 4. Submit time-current trip curves (in log-log format) and trip setting parameter/range information (for each trip function) for all solid-state circuit breakers.
 5. Manufacturer shall also provide recommended trip settings with the shop drawing submittal (including ground fault settings) for coordination with downstream overcurrent devices. Manufacturer shall base recommendations on the AIC rating of the electrical equipment.
 6. Where the Protective Device Study specification section 260573 is included in the project, the time-current curves and recommended trip settings for all solid-state circuit breakers shall be submitted as part of the protective device study.
- K. 26 2816 Motor and Circuit Disconnects
1. Submit manufacturer's data including specifications, installation and general recommendations, for each type of motor and circuit disconnect switch required.
 2. Submit dimensioned drawings of electrical motor and circuit disconnect switches that have rating of 100 amperes and larger.
- L. 26 2913 Motor Starters
1. Submit manufacturer's data on motor starters.
 2. Submit dimensioned drawings of motor starters showing accurately scaled equipment layouts.
- M. 26 5100 Interior and Exterior Building Lighting
1. Submit manufacturer's data on interior and exterior building lighting fixtures.
 2. Submit dimensioned drawings of lighting fixtures. Submit fixture shop drawings in PDF format with separate sheet for each fixture, assembled in luminaire "type" alphabetical order, with each "type" individually bookmarked, with proposed fixture catalog number and accessories clearly indicated on each sheet.

3. When applicable submit standard color samples with the shop drawings. If standard colors are not acceptable, a color sample will be provided to the fixture manufacturer. Return of the shop drawings will be delayed until color samples are provided.
 4. Submit ballast and/or driver manufacturer cut sheets.
 5. Submit a list of all lamps used on projects.
- N. 28 3111 Fire Alarm and Detection System
1. Submit manufacturer's data on fire alarm and detection systems including, but not limited to, roughing-in diagrams and instructions for installation, operating and maintenance, suitable for inclusion in maintenance manuals.
 2. Provide shop drawings showing equipment/device locations and connecting wiring of entire fire alarm and detection system. Include wiring diagrams and riser diagrams of panel. Provide dimensioned drawing of Fire Alarm Control Panel and Building Graphic. Shop drawings shall be prepared by an individual with a minimum NICET III (Fire Protection Engineering Technology/Fire Alarm Systems) certification. The individual's name and certification number shall be shown on the submittal design drawings.
 3. Submit a written statement to the Architect and the state and local Fire Marshal's Office that each device of the fire alarm system will be installed, inspected and tested in accordance with applicable requirements of NFPA Standard 72.
 4. A complete set of shop drawings indicating:
 - a. Location of all alarm-initiating and alarm-signaling devices.
 - b. Point-to-point wiring diagrams for all alarm-initiating and alarm-signaling devices.
 - c. Standby battery calculations, including voltage drop calculation.
 5. Wiring diagrams for:
 - a. Alarm control panels.
 - b. Auxiliary function relays and solenoids.
 - c. Remote signaling equipment.
 6. A complete equipment list identifying:
 - a. Type
 - b. Model
 - c. Manufacturer
 - d. Manufacturer catalog data sheets
 - e. UL Listing and/or FM approval showing compatibility of device with Fire Alarm Control Panel (FACP)
 7. A complete zone list identifying all:
 - a. Alarm-initiating and alarm-signaling devices.
 - b. Remote signaling and auxiliary function zones.
 - c. Specific devices associated with each zone.
 8. Submit to State and Local Fire Marshall, a complete Certificate of Compliance

1.4 OPERATION & MAINTENANCE MANUALS

- A. Provide operating instruction and maintenance data books for all equipment and materials furnished under this Division.
- B. Submit four copies of operating and maintenance data books for review at least four weeks before final review of the project. Assemble all data in a completely indexed volume or volumes and identify the size, model, and features indicated for each item. The binder (sized to the material) shall be a 2" slide lock unit (Wilson-Jones WLJ36544B). The cover shall be engraved with the job title in 1/2" high letters and the name and address of the Contractor in 1/4" high letters. Provide the same information in 1/8" letters on the spine.
- C. Include complete cleaning and servicing data compiled in clearly and easily understandable form. Show serial numbers of each piece of equipment, complete lists of replacement parts, motor ratings, etc. Each unit shall have its own individual sheet. (Example: If two items of equipment A and D appear on the same sheet, an individual sheet shall be provided for each unit specified).
- D. Include the following information where applicable.
 - 1. Identifying name and mark number.
 - 2. Certified outline Drawings and Shop Drawings.
 - 3. Parts lists.
 - 4. Performance curves and data.
 - 5. Wiring diagrams.
 - 6. Light fixture schedule with the lamps and ballast data used on the project for all fixtures
 - 7. Manufacturer's recommended operating and maintenance instructions.
 - 8. Vendor's name and address for each item.
- E. The engineer shall review the manuals and when approved, will forward the manuals on to the architect. If the manuals are rejected twice, the contractor shall reimburse the engineer the sum of \$1,200.00 for each review afterwards.
- F. Provide Operation and Maintenance Manual information for each section listed below in addition to the general requirements listed above.
 - 1. 26 0526 Grounding
 - a. Test Results of measured resistance values
 - 2. 26 0923 Occupancy Sensors
 - a. Record Drawings
 - i. A complete set of 'as-builts' drawings showing installed wiring, specific interconnections between all equipment, and internal wiring of this equipment shall be included in the operating and maintenance manuals upon complete of the system.
 - ii. Provide a CD to the owner containing the information specified below. The CD shall include all information required to allow the Owner to change the schedules themselves. The CD shall contain a minimum of following:
 - 1. CAD drawing files of 'as-built' lighting control components and point to point connections.
 - 2. General configuration programming.
 - 3. Job specific configuration programming to

- include schedule.
 - 4. Tutorial file on complete programming of lighting control system.
- 3. 26 0943 Lighting Control Equipment
 - a. Record Drawings
 - i. A complete set of 'as-builts' drawings showing installed wiring, specific interconnections between all equipment, and internal wiring of this equipment shall be included in the operating and maintenance manuals upon complete of the system.
 - ii. Provide a CD to the owner containing the information specified below. The CD shall include all information required to allow the Owner to change the schedules themselves. The CD shall contain a minimum of following:
 - 1. CAD drawing files of 'as-built' lighting control components and point to point connections.
 - 2. General configuration programming.
 - 3. Job specific configuration programming to include schedule.
 - 4. Tutorial file on complete programming of lighting
- 4. 26 2913 Motor Starters
 - a. After installation is complete, including water and air balancing, measure voltage (L-L and L-N) and full load current of each phase of each motor. Submit report showing field readings of voltage, amperage, service factor, and thermal heater size installed for each motor.
- 5. 28 3111 Fire Alarm and Detection System
 - a. Manual Requirements
 - i. Operating and maintenance manuals shall be submitted prior to testing of the system. Manuals shall include all service, installation, and programming information.
 - b. Record Drawings
 - i. A complete set of CAD "as-built" drawings showing installed wiring, color coding, specific interconnections between all equipment, and internal wiring of the equipment shall be delivered to the owner upon completion of the system. Vendor shall not request drawings from the Engineer. Vendor shall request current architectural drawings from the Architect and include all cost with bid.
 - ii. A building map shall be supplied to the owner indicating the exact location of all devices along with the addresses of the individual devices. Install building fire alarm map adjacent to the fire alarm panel and all remote operating panels. Provide high quality plastic sign (map holder) with two layers. The back layer shall be painted black. The front layer shall be a clear center for viewing the CAD fire alarm drawing. Edges of the sign shall be colored to match the building interior. The building map shall indicate

the various devices and wiring by the use of different colors (minimum of five colors).

- iii. Provide a CD to the Owner containing the information specified below. The CD shall include all information required to allow the Owner to change the fire alarm program themselves. The CD shall contain a minimum of the following:
 1. CAD drawing files of building fire alarm map.
 2. CAD drawing files of as-built fire alarm components and point to point connections.
 3. General configuration programming.
 4. Job specific configuration programming.
 5. Tutorial file on complete programming of fire alarm system

1.5 SPARE PARTS:

- A. Provide spare parts (fuses, diffusers, lamps, etc.) as specified. Stock of all spare items shall be delivered as directed to Owner's storage space prior to substantial completion. All components shall be labeled to match construction document nomenclature.

Section	Section Name	Description	Qty. Required	Qty. Received	Fulfilled?
26 0532	Conduit Raceway	Provide 1000 feet of ¾" conduit with 3 #12 conductors and 1000 feet of ¾" conduit with 3 #10 conductors. Provide all supports, fittings, boxes, terminations, etc. as required for installation. Install only as directed by engineer. Credit back all unused material and labor to Owner.	Per description		
26 0923	Occupancy Sensors	Spare sensors for each type used on project.	5 per type		
26 2413	Switchgear and Switchboards	Maintenance Stock Fuses: For types and ratings required, furnish additional fuses, amounting to one unit for every 5 installed units, but not less than 3 units of each.	Per description		
26 2815	Overcurrent Protective Devices	For types and ratings required, furnish additional fuses, amounting to one unit for every 5 installed units, but not less than two units of each size and type, unless specified otherwise in another section of these specifications.	Per description		
26 2816	Motor and Circuit Disconnects	Spare fuses amounting to one spare fuse for each 10 installed but not less than three of any one type and size.	Per description		
26 2913	Motor Starters	Maintenance Stock Fuses: For types and ratings required, furnish additional fuses, amounting to one unit for every 10 installed, but not less than 5 units of each, for both power and control circuit fuses.	Per description		
26 5100	Interior and Exterior Building Lighting	Furnish stock of replacement LED drivers for each type and size provided on the project. A minimum quantity of 15% but no less than two (2) shall be furnished.	Per description		
		Furnish stock of replacement serviceable LED components (ie: boards, drivers, etc.) for each type and size provided on the project. A minimum quantity of 15% but no less than two (2) shall be furnished.	Per description		
		Furnish stock of replacement LED light fixtures for each type and size provided on the project. A minimum quantity of two (2) fixtures shall be furnished. For linear pendant fixtures, provide three (3) four-foot modules.	Per description		
		Furnish stock of replacement lamps for all other fixtures for each type and size provided on the project. A minimum	Per description		

		quantity of 15% but no less than one (1) lamp shall be furnished.			
		Provide a complete spare parts list in lighting shop drawing review			
27 5123	Sound and Intercommunication System	Type 1 speakers	10		
		Type 2 speakers	10		
		Back boxes	20		
		Call switches	20		
		15 feet of conduit and cable per each spare device	Per description		
28 3111	Fire Alarm and Detection	Smoke detectors with base	10		
		Thermal detectors with base	10		
		Strobe/horns	10		
		Manual pull stations with addressable modules	5		
		Duct smoke detectors	4		
		20 feet of conduit with wiring (completely installed and wired) for each spare device	Per description		

END OF SECTION

SECTION 26 05 07

ELECTRICAL CONNECTIONS FOR EQUIPMENT

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-23 section making reference to electrical connections.

1.2 DESCRIPTION OF WORK:

- A. Extent of electrical connection for equipment includes final electrical connection of all equipment having electrical requirements. Make final connections for all owner furnished equipment. See other applicable portions of specification for building temperature control wiring requirements.
- B. Refer to Division-23 sections for motor starters and controls furnished integrally with equipment; not work of this section.
- C. Refer to Division-23 section for control system wiring; not work of this section.
- D. Refer to sections of other Divisions for specific individual equipment power requirements.

1.3 QUALITY ASSURANCE:

- A. NEC COMPLIANCE: Comply with applicable portions of NEC as to type products used and installation of electrical power connections.
- B. UL LABELS: Provide electrical connection products and materials that have been UL-listed and labeled.

PART 2 PRODUCTS

2.1 GENERAL:

- A. For each electrical connection indicated, provide complete assembly of materials, including but not necessarily limited to, raceways, conductors, cords, cord caps, wiring devices, pressure connectors, terminals (lugs), electrical insulating tape, heat-shrinkable insulating tubing, cable ties, solderless wire nuts, and other items and accessories as needed to complete splices, terminations, and connections as required. Crimp on or slip-on type splicing materials (insulation displacement type) designed to be used without wire stripping are not acceptable. See Section 26 0532, Conduit Raceways; Section 26 2726 Wiring Devices; and Section 26 0519 Conductors and Cables for additional requirements. Provide final connections for equipment consistent with the following:
 - 1. Permanently installed fixed equipment - flexible seal-tite conduit from branch circuit terminal equipment, or raceway; to equipment, control cabinet, terminal junction box or wiring terminals. Totally enclose all wiring in raceway.
 - 2. Movable and/or portable equipment - wiring device, cord cap, and multi-conductor cord suitable for the equipment and in accordance with NEC requirements (Article 400).
 - 3. Other methods as required by the National Electrical Code and/or as required by special equipment or field conditions.

PART 3 EXECUTION

3.1 INSTALLATION OF ELECTRICAL CONNECTIONS:

- A. Make electrical connections in accordance with connector manufacturer's written instructions and with recognized industry practices, and complying with requirements of NEC and NECA's "Standard of Installation" to ensure that products fulfill requirements.
- B. Connect electrical power supply conductors to equipment conductors in accordance with equipment manufacturer's written instructions and wiring diagrams.
- C. Coordinate installation of electrical connections for equipment with equipment installation work.
- D. Verify all electrical loads (voltage, phase, horse power, full load amperes, number and point of connections, minimum circuit ampacity, etc.) for equipment furnished under other Divisions of this specification, by reviewing respective shop drawings furnished under each division. Meet with each subcontractor furnishing equipment requiring electrical service and review equipment electrical characteristics. Report any variances from electrical characteristics noted on the electrical drawings to Architect before proceeding with rough-work. In summary it is not in the Electrical Engineers scope to review the shop drawings from other trades/divisions.
- E. Obtain and review the equipment shop drawings to determine particular final connection requirements before rough-in begins for each equipment item.
- F. Refer to basic materials and methods Section 26 0553 Electrical Identification, Conductors, for identification of electrical power supply conductor terminations.

END OF SECTION

SECTION 26 05 19

CONDUCTORS AND CABLES (600V AND BELOW)

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to conductors and cables specified herein.

1.2 DESCRIPTION OF WORK:

- A. Extent of electrical conductor and electrical cable work is indicated by drawings and schedules.
- B. Types of conductors and cables in this section include the following:
 - 1. Aluminum Conductor (600V)
- C. Applications for conductors and cables required for project include:
 - 1. Power Distribution
 - 2. Feeders
 - 3. Branch Circuits

1.3 RECORDS SUBMITTAL: Refer to Section 26 0502 for requirements.

1.4 QUALITY ASSURANCE:

- A. Comply with NEC as applicable to construction and installation of electrical conductors and cable. Comply with UL standards and provide electrical conductors and cables that have been UL-listed and labeled.
- B. Comply with applicable portions of NEMA/Insulated Cable Engineers Association standards pertaining to materials, construction and testing of conductors and cable.
- C. Comply with applicable portions of ANSI/ASTM and IEEE standards pertaining to construction of conductors and cable.

1.5 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 ALUMINUM CONDUCTORS (600V):

- A. Provide factory-fabricated conductors of sizes, ratings, materials, and types indicated for each service. Where not indicated provide proper selection to comply with project's installation requirements and NEC standards. Provide conductors in accordance with the following:
 - 1. Service Entrance Conductors – [Aluminum] conductor; see drawings for insulation type.
 - 2. Distribution and Panelboard Feeders; and Other Conductors, #2 AWG and Larger – [Aluminum] conductor; see drawings for insulation type.

3. Branch Circuit Conductors and All Conductors #3 AWG and Smaller - Copper conductor, with THHN/THWN insulation. Size all conductors in accordance with NEC; minimum size to be #12 AWG. Provide solid conductors for #10 AWG and smaller. Provide stranded conductors for #8 AWG and larger.
4. [Aluminum Conductors. Where aluminum conductors are specified for use, provide compact stranded Aluminum Association 8000- series alloy conductor material.
 - a. [Stabiloy - Alcan Cable](#)
 - b. [Triple E - Southwire](#)
- B. Provide a maximum of three phase conductors in any one conduit or as approved by electrical engineer. Where phase conductors share a common neutral they must have a means to simultaneously disconnect all ungrounded conductors at the point where the branch circuits originate. The ungrounded and neutral conductors of a multi-wire branch circuit must be grouped together by wire ties at the point of origination.
- C. Provide neutral and ground wire as specified elsewhere in documents.
- D. Provide separate neutral conductor for all single phase branch circuits installed. No shared neutrals are allowed. Neutral conductor shall be the same size as the phase conductor.

PART 3 EXECUTION

3.1 INSTALLATION:

- A. General: Install electric conductors and cables as indicated, in compliance with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standards of Installation", and in accordance with recognized industry practices.
- B. Coordinate installation work with electrical raceway and equipment installation work, as necessary for proper interface.
- C. Cables may be pulled by direct attachment to conductors or by use of basket weave pulling grip applied over cables. Attachment to pulling device shall be made through approved swivel connection. Nonmetallic jacketed cables of small size may be pulled directly by conductors by forming them into a loop that pull wires can be attached; remove insulation from conductors before forming the loop. Larger sizes of cable may be pulled by using basket weave pulling grip, provided the pulling force does not exceed limits recommended by manufacturer; if pulling more than one cable, bind them together with friction tape before applying the grip. For long pulls requiring heavy pulling force, use pulling eyes attached to conductors.
- D. Do not exceed manufacturer's recommendations for maximum allowable pulling tension, side wall pressure, and minimum allowable bending radius. In all cases, pulling tension applied to the conductors shall be limited to 0.008 lbs. per circular mil of conductor cross-section area.
- E. Pull in cable from the end having the sharpest bend; i.e. bend shall be closest to reel. Keep pulling tension to minimum by liberal use of lubricant, and turning of reel, and slack feeding of cable into duct entrance. Employ not less than one man at reel and one in pullhole during this operation.
- F. For training of cables, minimum bend radius to inner surface of cable shall be 12 times cable diameter.
- G. Where cable is pulled under tension over sheaves, conduit bends, or other curved surfaces, make minimum bend radius 50% greater than specified above for training.
- H. Use only wire and cable pulling compound recommended by the specific cable

manufacturer, and that is listed by UL.

- I. Seal all cable ends unless splicing is to be done immediately. Conduit bodies shall not contain splices.
- J. Support all cables in pullholes, concrete trenches, and similar locations by cable racks and secure to rack insulators with nylon cord or self-locking nylon cable ties. Place each cable on separate insulator. In manholes, pullholes, concrete trenches, and similar locations, wrap strips of fire-proofing tape (approx. 1/16 inch thick by 3 inches wide) tightly around each cable spirally in half-lapped wrapping or in two butt-joined wrappings with the second wrapping covering the joints in the first. Apply tape with the coated side toward the cable, and extend tape one inch into the ducts. To prevent unraveling, random wrap the fireproofing tape the entire length of the fireproofing with pressure sensitive glass cloth tape. Provide fireproofing tape of a flexible, conformable fabric having one side coated with flame retardant, flexible, polymeric coating and/or a chlorinated elastomer not less than 0.050 inch thick weighing not less than 2.5 pounds per square yard. Provide tape that is noncorrosive to cable sheath, self-extinguishing, and that will not support combustion. Construct tape of materials that do not deteriorate when subjected to oil, water, gases, salt water, sewage and fungus.
- K. Follow manufacturer's instructions for splicing and cable terminations.

3.2 AFTER INSTALLATION TEST FOR CABLE 600 VOLTS AND BELOW:

- A. Prior to energization, test cable and wire for continuity of circuitry, and for short circuits, Megger all circuits of 100 amp and greater rating. Correct malfunctions. Record all test data and provide written test report.
- B. Subsequent to wire and cable connections, energize circuitry and demonstrate functioning in accordance with requirements.

3.3 IDENTIFICATION OF FEEDERS: Refer to Section 26 0553 for requirements.

END OF SECTION

SECTION 26 05 26

GROUNDING

PART 1 GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Division-26 Basic Materials and Methods sections apply to work specified in this section.

1.2 DESCRIPTION OF WORK:

- A. Provide grounding as specified herein, and as indicated on drawings.
- B. Provide grounding and bonding of all electrical and communication apparatus, machinery, appliances, building components, and items required by the NEC to provide a permanent, continuous, low impedance, grounding system.
- C. Unless otherwise indicated, ground the complete electrical installation including the system neutral, metallic conduits and raceways, boxes, fittings, devices, cabinets, and equipment in accordance with all code requirements.
- D. Ground each separately derived system, as described in NEC Section 250-30, unless otherwise indicated.
- E. Types of grounding in this section include the following:
 - 1. Underground Metal Water Piping
 - 2. Metal Building Frames
 - 3. Grounding Electrodes
 - 4. Grounding Rods
 - 5. Reference Ground Buses
 - 6. Isolated Grounding Systems
 - 7. Separately Derived Systems
 - 8. Service Equipment
 - 9. Enclosures
 - 10. Systems
 - 11. Equipment
 - 12. Other items indicated on drawings
- F. Requirements of this section apply to electrical grounding work specified elsewhere in these specifications.

1.3 QUALITY ASSURANCE:

- A. Comply with NEC as applicable to electrical grounding and ground fault protection systems. Comply with applicable ANSI and IEEE requirements. Provide products that have been UL listed and labeled.
- B. Resistance from the service entrance ground bus, through the grounding electrode to earth, shall not exceed 5 ohms.

1.4 **SUBMITTALS:** Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 MATERIALS AND COMPONENTS:

- A. **GENERAL:** Except as otherwise indicated, provide each electrical grounding system as specified herein, and as shown on drawings, including but not necessarily limited to, cables/wires, connectors, terminals (solderless lugs), grounding rods/electrodes and plate electrodes, bonding jumper braid, and other items and accessories needed for complete installation. Where materials or components are not otherwise indicated, comply with NEC, NEMA and established industry standards for applications indicated.
- B. **ELECTRICAL GROUNDING CONDUCTORS:** Unless otherwise indicated, provide electrical grounding conductors for grounding connections matching power supply wiring materials and sized according to NEC. Provide with green insulation.
- C. **GROUND RODS:** Steel with copper welded exterior, 3/4" dia. x 10' long. Weaver or Cadweld.
- D. **GROUND WELL BOXES FOR GROUND RODS:** Precast concrete box 9-1/2" W. x 16" L. X 18" D. with light duty concrete cover for non-traffic areas or rated steel plate for traffic areas. Provide covers with lifting holes. Engrave cover with "GROUND ROD".
- E. **CONCRETE ENCASED GROUNDING ELECTRODE (UFER GROUND):** #2/0 AWG bare copper conductor.
- F. **INSULATED GROUNDING BUSHINGS:** Plated malleable iron body with 150 degree Centigrade molded plastic insulating throat, lay-in grounding lug with hardened stainless steel fasteners, OZ-Gedney BLG, or Thomas & Betts #TIGB series.
- G. **CONNECTIONS TO PIPE:** For cable to pipe, OZ-Gedney G-100B series or Thomas & Betts #390X series, or Burndy type GAR.
- H. **CONNECTIONS TO STRUCTURAL STEEL, GROUND RODS, OR SPLICES:** For splicing and/or connecting conductors, use exothermic welds or high pressure compression type connectors. Provide exothermic weld kits manufactured by Cadweld or Thermoweld. If high compression type connectors are used for cable-to-cable, or cable-to-steel, or cable-to-ground rod connections, provide Thomas & Betts #53000 series, or Burndy Hyground series.
- I. **BONDING JUMPERS:** OZ-Gedney Type BJ, or Thomas & Betts #3840 series, or Burndy type GG and type B braid.
- J. **MAIN BUILDING REFERENCE GROUND BUS:** Provide one 18" L. X 2" H X 1/4" thick copper bus bar (or size noted on drawings). Mount on walls in locations shown, on insulating stand offs, 18" AFF. Furnish complete with lugs for connecting grounding system cables. All holes shall be drilled and tapped for single hole lugs. Provide 6 spare lugs and 6 lug spaces.
- K. **INTERSYSTEM BONDING TERMINAL:** Provide one 12" L. x 2" H x 1/4" thick copper bus bar. Mount on wall adjacent to Main Electrical Service Equipment on insulating standoffs, 18" A.F.F. Furnish complete with lugs for connecting systems grounding cables. All holes shall be drilled for 2 hole compression lugs. Provide 6 spare lugs. Connect to equipment grounding bus in Main Electrical Service Equipment with No. 4 AWG copper conductor.

PART 3 EXECUTION

3.1 INSTALLATION OF GROUNDING SYSTEMS:

- A. Install electrical grounding systems in accordance with manufacturer's written instructions and with recognized industry practices to ensure grounding devices comply with

requirements.

- B. Install clamp-on connectors only on thoroughly cleaned and metal contact surfaces, to ensure electrical conductivity and circuit integrity.
- C. Provide grounding for the entire raceway, enclosure, equipment and device system in accordance with NEC. All non-metallic raceways shall include copper grounding conductor sized in accordance with NEC. Include copper grounding conductor in all raceway installed in suspended slabs.
- D. Provide service entrance grounding by means of ground rods (quantity of two, driven exterior to building), by means of bonding to water main, and by means of bonding to building structural steel. In addition, provide a grounding electrode for not less than 30 lineal feet in concrete footing or foundation that is in direct contact with earth. Size electrode in accordance with NEC, but in no case, smaller than No. 4 AWG bare copper. Support electrode so as to be below finished grade near the bottom of the trench, and approximately three inches from the bottom or sides of the concrete. Locate a point of connection for inspection.
- E. Provide grounding conductors for dimming systems in accordance with manufacturer's requirement.

3.2 GROUNDING ELECTRODES:

- A. Concrete Encased Grounding Electrode (UFER Ground): Provide a #2/0 AWG minimum bare copper conductor encased along the bottom of concrete foundation or footings that are in direct contact with the earth and where there is no impervious water-proofing membrane between the footing and the soil. Extend electrode through a horizontal length of 30 feet minimum and encase with not less than 2 nor more than 5 inches of concrete separating it from surrounding soils. At point of emergence from concrete, run electrode through a protective non-metallic sleeve and extend to the main building reference ground bus.
- B. Supplementary Grounding Electrode (Ground Ring, Grid, and Driven Rods): Provide driven ground rod(s) installed in listed ground well box(s) and filled with gravel after connection is made. Interconnect ground rod(s) with structural steel and adjacent rods with minimum #4 AWG bare copper conductor. Locate ground rod a minimum of 10 feet from any electrode of another electrical system or from adjacent ground rod(s).
- C. Separately Derived Electrical System Grounding Electrode: Ground each separately derived system per requirements in NEC Section 250-26 unless indicated otherwise.
- D. GROUNDING ELECTRODE CONDUCTOR: Provide grounding electrode conductor sized per NEC table 250-94 or as indicated.
- E. POWER SYSTEM GROUNDING: Connect the following items using NEC sized copper grounding conductors to lugs on the Main Building Ground Bus Service Ground Bus.
 - 1. Grounding electrode conductor from concrete encased electrode, and from ground rods, and from service entrance ground bus.
 - 2. Conductor from main incoming cold water piping system.
 - 3. Conductor from building structural steel.
 - 4. Ground for separately derived systems.
- F. Run main grounding conductors exposed or in metallic conduit if protection or concealment is required.
- G. EQUIPMENT BONDING/GROUNDING: Provide a NEC sized conductor, whether indicated or not on the drawings, in raceways as follows:
 - 1. Non-metallic conduits and ducts.
 - 2. Distribution feeders.

3. Motor and equipment branch circuits.
 4. Device and lighting branch circuits.
 5. Provide grounding bushings and bonding jumpers for all conduit terminating in reducing washers, concentric, eccentric or oversized knockouts at panelboards, cabinets and gutters.
- H. Provide bonding jumpers across expansion and deflection couplings in conduit runs, across pipe connections at water meters, and across dielectric couplings in metallic cold water piping system.
- I. Provide bonding wire in all flexible conduit.

3.3 TESTING:

- A. Obtain and record ground resistance measurements both from service entrance ground bus to the ground electrode and from the ground electrode to earth. Install additional bonding and grounding electrodes as required to comply with resistance limits specified under this Section.
- B. Include typewritten records of measured resistance values in the Operation and Maintenance Manual.
- C. Use independent testing agency for all testing.
- D. Use test equipment expressly designed for the purpose intended. Submit name of testing agency for review and approval, in writing, to the Engineer prior to the performance of any testing.

END OF SECTION

SECTION 26 05 29

SUPPORTING DEVICES

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification section, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is a part of each Division-26, 27 and 28 section making reference to supports, anchors, sleeves, and seals, specified herein.

1.2 DESCRIPTION OF WORK:

- A. Extent of supports, anchors, and sleeves is indicated by drawings and schedules and/or specified in other Division-26 sections. See Section 260532, Raceways, for additional requirements.
- B. Work of this section includes supports, anchors, sleeves and seals required for a complete raceway support system, including but not limited to: clevis hangers, riser clamps, C-clamps, beam clamps, one and two hole conduit straps, offset conduit clamps, expansion anchors, toggle bolts, threaded rods, U-channel strut systems, threaded rods and all associated accessories.

1.3 QUALITY ASSURANCE:

- A. Comply with NEC as applicable to construction and installation of electrical supporting devices. Comply with applicable requirements of ANSI/NEMA Std. Pub No. FB 1, "Fittings and Supports for Conduit and Cable Assemblies". Provide electrical components that are UL-listed and labeled.

PART 2 PRODUCTS

2.1 MANUFACTURED SUPPORTING DEVICES:

A. GENERAL:

- 1. Provide supporting devices; complying with manufacturer's standard materials, design and construction in accordance with published product information, and as required for a complete installation; and as herein specified. See drawings for additional requirements.

PART 3 EXECUTION

3.1 INSTALLATION OF SUPPORTING DEVICES:

- A. Install hangers, anchors, sleeves, and seals as required, in accordance with manufacturer's written instructions and with recognized industry practices to ensure supporting devices comply with requirements. Comply with requirements of NECA, NEC and ANSI/NEMA for installation of supporting devices.
- B. Coordinate with other electrical work, including raceway and wiring work, as necessary to interface installation of supporting devices with other work.
- C. Install hangers, supports, clamps and attachments to support piping properly from building structures. Arrange for grouping of parallel runs of horizontal conduits to be supported together on trapeze type hangers where possible. For pre-and post tensioned

construction, use pre-set inserts for support of all electrical work. Do not use toggle bolts, moly bolts, wood plugs or screws in sheetrock or plaster as support for any equipment or raceway.

D. RACEWAYS:

1. Support raceways that are rigidly attached to structure at intervals not to exceed 8 feet on center, minimum of two straps per 10 foot length of raceway, and within 12" of each junction box, coupling, outlet or fitting. Support raceway at each 90° degree bend. Support raceway (as it is installed) in accordance with the following:

<u>NUMBER OF RUNS</u>	<u>3/4" TO 1-1/4" Ø</u>	<u>1-1/2" & LARGER Ø</u>
1	Full straps, clamps or hangers.	Hanger
2	Full straps, clamps or hangers.	Mounting Channel
3 or more	Mounting Channel	Mounting Channel

2. Support suspended raceways on trapeze hanger systems; or individually by means of threaded rod and straps, clamps, or hangers suitable for the application. Do not use "tie wire" as a portion of any raceway support system; do not support raceway from ceiling support wires.

E. FLOOR MOUNTED EQUIPMENT:

1. Provide rigid attachment of all floor mounted equipment to the floor slab or structural system. Provide 5/8" bolts or expansion anchors at each 90 degree corner and at intervals not to exceed 48" on center along entire perimeter of the equipment. Provide rigid attachment for all floor mounted switchboards, panelboards, power and control equipment, motor control centers, dimmer cabinets, transformers (provide neoprene vibrations isolators at anchor points), oil switches, battery packs and racks, and similar equipment furnished under Division 26, 27 and 28.

F. WIREWAYS, BUS DUCTS AND CABLE TRAYS:

1. Provide vertical and lateral support systems for all wireways, busway, and cable trays that are supported from overhead structure. See Sections 260536 and 262500 for additional requirements.

END OF SECTION

SECTION 26 05 32

CONDUIT RACEWAY

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to electrical raceways and specified herein.

1.2 DESCRIPTION OF WORK:

- A. Extent of raceways is indicated by drawings and schedules.
- B. Types of raceways in this section include the following:
 - 1. Electrical Metallic Tubing
 - 2. Flexible Metal Conduit
 - 3. Intermediate Metal Conduit
 - 4. Liquid-tight Flexible Metal Conduit
 - 5. Rigid Metal Conduit
 - 6. Rigid Non-metallic Conduit

1.3 QUALITY ASSURANCE:

- A. **MANUFACTURERS:** Firms regularly engaged in manufacture of raceway systems of types and sizes required, whose products have been in satisfactory use in similar service for not less than three (3) years.
- B. **STANDARDS:** Comply with applicable portions of NEMA standards pertaining to raceways. Comply with applicable portions of UL safety standards pertaining to electrical raceway systems; and provide products and components that have been UL-listed and labeled. Comply with NEC requirements as applicable to construction and installation of raceway systems.
- C. **SUBMITTALS:** Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 METAL CONDUIT AND TUBING:

- A. **GENERAL:**
 - 1. Provide metal conduit, tubing and fittings of types, grades, sizes and weights (wall thicknesses) as indicated; with minimum trade size of 3/4".
- B. **RIGID METAL CONDUIT (RMC):** FS WW-C-0581 and ANSI C80.1.
- C. **INTERMEDIATE STEEL CONDUIT (IMC):** FS WW-C-581.
- D. **PVC EXTERNALLY COATED RIGID STEEL CONDUIT:** ANSI C80.1 and NEMA Std. Pub. No. RN 1.
- E. **ALUMINUM CONDUIT:** Not acceptable.
- F. **MC CABLE:**

1. MC Cable is acceptable for all branch circuits installed in gypsum wallboard walls from the home run device box to the last device box on the branch circuit and all boxes in between, from the home run device box to the branch panel, the circuit shall be installed in an approved raceway. MC Cable is acceptable for all light fixture whips not longer than six feet in length. Located in removable grid ceilings. MC Cable is unacceptable to be installed from light fixture to light fixture. All MC Cable shall be provided with anti short fittings.

G. RIGID AND INTERMEDIATE STEEL CONDUIT FITTINGS:

1. Provide fully threaded malleable steel couplings; raintight and concrete tight where required by application. Provide double locknuts and metal bushings at all conduit terminations. Install OZ Type B bushings on conduits 1-1/4" and larger.

H. ELECTRICAL METALLIC TUBING (EMT): FS WW-C-563 and ANSI C80.3.

I. EMT FITTINGS:

1. Provide insulated throat nylon bushings with non-indenter type malleable steel fittings at all conduit terminations. Install OZ Type B bushings on conduits 1" larger. Cast or indenter type fittings are not acceptable.

J. FLEXIBLE METAL CONDUIT: FS WW-C-566, of the following type;

1. Zinc-coated steel.

K. FLEXIBLE METAL CONDUIT FITTINGS: FS W-F-406, Type 1, Class 1, and Style A.

L. LIQUID TIGHT FLEXIBLE METAL CONDUIT:

1. Provide liquid-tight, flexible metal conduit; constructed of single strip, flexible continuous, interlocked, and double-wrapped steel; galvanized inside and outside; coated with liquid-tight jacket of flexible polyvinyl chloride (PVC).

M. LIQUID-TIGHT FLEXIBLE METAL CONDUIT FITTINGS: FS W-F-406, Type 1, Class 3, Style G.

N. EXPANSION FITTINGS: OZ Type AX, or equivalent to suit application.

2.2 NON-METALLIC CONDUIT AND DUCTS:

A. GENERAL:

1. Provide non-metallic conduit, ducts and fittings of types, sizes and weights as indicated; with minimum trade size of 3/4".

B. UNDERGROUND PVC PLASTIC UTILITIES DUCT:

1. Minimum requirements shall be schedule 40 for encased burial in concrete and for Type II for direct burial.

C. PVC AND ABS PLASTIC UTILITIES DUCT FITTINGS:

D. ANSI/NEMA TC 9, match to duct type and material.

E. HDPE CONDUIT: Not acceptable.

2.3 CONDUIT; TUBING; AND DUCT ACCESSORIES:

- A. Provide conduit, tubing and duct accessories of types and sizes, and materials, complying with manufacturer's published product information, that mate and match conduit and tubing. Provide manufactured spacers in all duct bank runs.

2.4 SEALING BUSHINGS:

- A. Provide OZ Type FSK, WSK, or CSMI as required by application. Provide OZ type CSB

internal sealing bushings.

2.5 CABLE SUPPORTS:

- A. Provide OZ cable supports for vertical risers, type as required by application.

PART 3 EXECUTION

3.1 INSTALLATION OF ELECTRICAL RACEWAYS:

- A. Install electrical raceways where indicated; in accordance with manufacturer's written instructions, applicable requirements of NEC and NECA "Standard of Installation", and in accordance with the following:
1. SERVICE ENTRANCE CONDUCTORS, AND CONDUCTORS OVER 600 VOLTS:
 - a. Install in rigid metal conduit (RMC), or intermediate metal conduit (IMC); except where buried below grade, install in non-metallic conduit or duct, individually encased in concrete. See duct banks.
 2. FEEDERS UNDER 600 VOLTS:
 - a. Install feeders to panels and motor control centers and individual equipment feeders rated 100 amps and greater, in rigid metal conduit (RMC), or intermediate metal conduit (IMC), or Electrical Metallic Tubing (EMT); except where buried below grade, install in non-metallic conduit or duct. Encase feeders 1-1/4" and larger, individually in concrete where installed below grade. See duct banks.
 3. BRANCH CIRCUITS, SIGNAL AND CONTROL CIRCUITS, AND INDIVIDUAL EQUIPMENT CIRCUITS RATED LESS THAN 100 AMPS:
 - a. Install in electric metallic tubing (EMT). Below concrete slab-on-grade or in earth fill, install in non-metallic plastic duct. In areas exposed to weather, moisture, or physical damage, install in RMC or IMC. In suspended slabs, install in PVC. Encase non-metallic duct 40-amp circuits, 1-1/4" and larger in concrete. See duct banks.
- B. Coordinate with other work including metal and concrete deck work, as necessary to interface installation of electrical raceways and components.
- C. Install raceway in accordance with the following:
1. Provide a minimum of 12" clearance measured from outside of insulation from flues, steam and hot water piping, etc. Avoid installing raceways in immediate vicinity of boilers and similar heat emitting equipment. Conceal raceways in finished walls, ceilings and floor (other than slab-on-grade), except in mechanical, electrical and/or communication rooms, conceal all conduit and connections to motors, equipment, and surface mounted cabinets unless exposed work is indicated on the drawings. Run concealed conduits in as direct a line as possible with gradual bends. Where conduit is exposed in mechanical spaces, etc., install parallel with or at right angles to building or room structural lines. Do not install lighting raceway until piping and duct work locations have been determined in order to avoid fixtures being obstructed by overhead equipment.
 2. Where cutting raceway is necessary, remove all inside and outside burrs; make cuts smooth and square with raceway. Paint all field threads (or portions of raceway where corrosion protection has been damaged) with primer and enamel finish coat to match adjacent raceway surface.
 3. Provide a minimum of 1 1/2" from nearest surface of the roof decking to raceway.

4. Provide a maximum of three phase conductors in any one conduit or as approved by electrical engineer. Where phase conductors share a common neutral they must have a means to simultaneously disconnect all ungrounded conductors at the point where the branch circuits originate. The ungrounded and neutral conductors of a multi-wire branch circuit must be grouped together by wire ties at the point of origination.
 5. Provide neutral and ground wire as specified elsewhere in documents.
 6. Provide separate neutral conductor for all single phase branch circuits installed. No shared neutrals are allowed. Neutral conductor shall be the same size as the phase conductor.
- D. Comply with NEC for requirements for installation of pull boxes in long runs.
 - E. Cap open ends of conduits and protect other raceways as required against accumulation of dirt and debris. Pull a mandrel and swab through all conduit before installing conductors. Install a 200 lb. nylon pull cord in each empty conduit run.
 - F. Replace all crushed, wrinkled or deformed raceway before installing conductors.
 - G. Do not use flame type devices as a heat application to bend PVC conduit. Use a heating device that supplies uniform heat over the entire area without scorching the conduit.
 - H. Provide rigid metal conduit (RMC) for all bends greater than 22 degrees in buried conduit. Provide protective coating for RMC bend as specified herein.
 - I. Where raceways penetrate building, area ways, manholes or vault walls and floors below grade, install rigid metal conduit (RMC) for a minimum distance of 10 feet on the exterior side of the floor or wall measured from interior face. Provide OZ, Type FSK, WSK or CSMI sealing bushings (with external membrane clamps as applicable) for all conduit penetrations entering walls or slabs below grade. Provide segmented type CSB internal sealing bushings in all raceways penetrating building walls and slabs below grade, and in all above grade raceway penetrations susceptible to moisture migration into building through raceway.
 - J. Install liquid-tight flexible conduit for connection of motors, transformers, and other electrical equipment where subject to movement and vibration.
 - K. Install spare 3/4" conduits (capped) from each branch panelboard into the ceiling and floor space. Run five into the ceiling space and five into the floor space. Where the floor is not accessible run six conduits into the ceiling space. Run conduits the required distance necessary to reach accessible ceiling space.
 - L. Provide OZ expansion fittings on all conduits crossing building expansion joints, both in slab and suspended.
 - M. Provide OZ cable supports in all vertical risers in accordance with NEC 300-19; type as required by application.
 - N. Complete installation of electrical raceways before starting installation of cables/conductors within raceways.
 - O. Raceway installation below grade:
 1. Apply protective coating to metallic raceways in direct contact with earth or fill of any type; consisting of spirally wrapped PVC tape (1/2" minimum overlap of scotch wrap tape or equal); or factory applied vinyl cladding (minimum thickness .020 inches). Completely wrap and tape all field joints.
 2. Burial depths must comply with NEC Section 300-5 but in no case be less than 24", unless noted otherwise on drawings.
 - P. Raceway installation below slab-on-grade, or below grade:

1. For slab-on-grade construction, install runs of rigid plastic conduit (PVC) below slab. All raceway shall be located a minimum of 8" below bottom of slab. Install RMC (with protective coating) for raceways passing vertically through slab-on-grade. Slope raceways as required to drain away from electrical enclosures and to avoid collection of moisture in raceway low points.
 2. Apply protective coating to metallic raceways in direct contact with earth or fill of any type; consisting of spirally wrapped PVC tape (1/2" minimum overlap of scotch wrap tape or equal); or factory applied vinyl cladding (minimum thickness .020 inches). Completely wrap and tape all field joints.
 3. Mark all buried conduits that do not require concrete encasement by placing yellow plastic marker tape (minimum 6" wide) along entire length of run 12" below final grade. Where multiple small lines are buried in a common trench and do not exceed an overall width of 16", install a single line marker.
 4. Burial depths must comply with NEC Section 300-5 but in no case be less than 24", unless noted otherwise on drawings.
- Q. MC CABLE:
1. MC Cable shall be supported and secured as follows:
 - a. Cables shall be supported at intervals not exceeding 6 feet.
 - b. Cables shall be secured with 12 inches of every box, cabinet, fitting or other cable termination.
- R. Raceway installation in suspended slabs:
1. Install conduit as close to the middle of concrete slab as practicable without disturbing reinforcement. Do not install conduits of diameter greater than 1/3 of the slab thickness. Space conduits not less than 3 diameters on center (except at stub up locations). Provide OZ expansion fittings at all expansion joints. All raceways shall be installed with concrete tight fittings. Include copper ground conductor in all raceways installed in suspended slabs.
- S. Raceway installation in hazardous locations:
1. Install RMC in all hazardous locations as defined by NEC. Provide suitable fittings, seal-offs, boxes, etc. to comply with requirements.
 2. Engage at least five full threads on all fittings. Provide inspection fittings with explosion proof drains to prevent water accumulation in conduit runs. Install seal-offs for arcing or high temperature equipment, at housing with splices or taps and where conduits enter or leave the hazardous area. Provide seal-offs of the appropriate type for vertical or horizontal installation. Ground all metallic parts.
- T. DUCTBANKS:
1. Provide ductbank construction as indicated using 3000 psi at 28 day strength concrete. Use Type II low alkali per ASTM C150. Use ASTM C-33 aggregate gradation with maximum size of 3/4". Use W/C ratio of 0.50. Install #4 reinforcing bar per ASTM 615 grade 50 in each corner of ductbank. Provide minimum 4" concrete cover on all sides of exterior conduits. Provide polypropylene pull rope in all spare duct.
- U. Electrical Identification: Refer to Section 260553 for requirements.
- V. SPARE PARTS: Refer to Section 26 0502 for requirements.

END OF SECTION

SECTION 26 05 33

ELECTRICAL BOXES AND FITTINGS

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specifications sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is a part of each Division-26, 27 and 28 section making reference to electrical wiring boxes and fittings specified herein. See Section 260532, Raceways, for additional requirements.

1.2 DESCRIPTION OF WORK:

- A. The extent of electrical box and electrical fitting work is indicated by drawings and schedules.
- B. Types of electrical boxes and fittings in this section include the following:
 - 1. Outlet Boxes
 - 2. Junction Boxes
 - 3. Pull Boxes
 - 4. Conduit Bodies
 - 5. Bushings
 - 6. Locknuts
 - 7. Knockout Closures
 - 8. Miscellaneous Boxes and Fittings

1.3 QUALITY ASSURANCE:

- A. Comply with NEC as applicable to construction and installation of electrical boxes and fittings. Comply with ANSI C 134,1 (NEMA Standards Pub No. OS 1) as applicable to sheet-steel outlet boxes, device boxes, covers and box supports. Provide electrical boxes and fittings that have been UL-listed and labeled.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 FABRICATED MATERIALS:

- A. INTERIOR OUTLET BOXES:
 - 1. Provide one piece, galvanized flat rolled sheet steel interior outlet wiring boxes with accessory rings, of types, shapes and sizes, including box depths, to suit each respective location and installation, construct with stamped knockouts in back and sides, and with threaded screw holes with corrosion-resistant screws for securing box and covers and wiring devices; minimum size 4"x4"x2-1/8".
 - 2. Provide an 'FS' box, with no knockouts when surface mounted in a finished, non-utility space. Surface mounting is only acceptable when approved by the Architect.
- B. INTERIOR OUTLET BOX ACCESSORIES:

1. Provide outlet box accessories as required for each installation, including mounting brackets, hangers, extension rings, fixture studs, cable clamps and metal straps for supporting outlet boxes, that are compatible with outlet boxes being used and fulfilling requirements of individual wiring applications.
- C. WEATHERPROOF OUTLET BOXES:
1. Provide corrosion-resistant cast-metal weatherproof outlet wiring boxes, of types, shapes and sizes (including depth) required, with threaded conduit ends, cast-metal face plates with spring-hinged waterproof caps suitably configured for each application, with face plate gaskets and corrosion-resistant fasteners.
- D. JUNCTION AND PULL BOXES:
1. Provide code-gage sheet steel junction and pull boxes, with screw-on covers; of types, shapes and sizes to suit each respective location and installation; with welded seams and equipped with stainless steel nuts, bolts, screws and washers.
- E. CONDUIT BODIES:
1. Provide galvanized cast-metal conduit bodies, of types, shapes and sizes to suit respective locations and installation, construct with threaded-conduit-entrance ends, removable covers, and corrosion-resistant screws.
- F. BUSHINGS, KNOCKOUT CLOSURES AND LOCKNUTS:
1. Provide corrosion-resistant punched-steel box knockout closures, conduit locknuts and malleable steel conduit bushings and offset connectors, of types and sizes to suit respective uses and installation.

PART 3 EXECUTION

3.1 INSTALLATION OF ELECTRICAL BOXES AND FITTINGS:

- A. GENERAL:
1. Install electrical boxes and fittings where indicated, complying with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standard of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.
 2. Coordinate installation of electrical boxes and fittings with wire/cable and raceway installation work.
 3. Provide coverplates for all boxes. See Section 262726, Wiring Devices.
 4. Provide weatherproof outlets for interior and exterior locations exposed to weather or moisture.
 5. Provide knockout closures to cap unused knockout holes where blanks have been removed.
 6. Install boxes and conduit bodies to ensure ready accessibility of electrical wiring. Do not install boxes above ducts or behind equipment. Install recessed boxes with face of box or ring flush with adjacent surface. Seal between switch, receptacle and other outlet box openings and adjacent surfaces with plaster, grout, or similar suitable material.
 7. Fasten boxes rigidly to substrates or structural surfaces, or solidly embed electrical boxes in concrete or masonry. Use bar hangers for stud construction. Use of nails for securing boxes is prohibited. Set boxes on opposite sides of common wall with minimum 10" of conduit between them. Set boxes on opposite sides of fire resistant walls with minimum of 24" separation.
 8. Provide a minimum of 1 ½" from the nearest surface of the roof decking to the installed boxes.

9. Provide electrical connections for installed boxes.

END OF SECTION

SECTION 26 05 53

ELECTRICAL IDENTIFICATION

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Requirements of the following Division 26 Sections apply to this section:
 - 1. "Basic Electrical Requirements".
 - 2. "Basic Electrical Materials and Methods".

1.2 SUMMARY

- A. This section includes identification of electrical materials, equipment and installations. It includes requirements for electrical identification components including but not limited to the following:
 - 1. Identification labels for raceways, cables and conductors.
- B. Related Sections: The following sections contain requirements that relate to this section:
- C. Division 9 Section "Painting" for related identification requirements.
- D. Refer to other Division 26 sections for additional specific electrical identification associated with specific items.

1.3 QUALITY ASSURANCE

- A. Electrical Component Standard: Components and installation shall comply with NFPA 70 "National Electrical Code"

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by the following:
 - 1. American Labelmark Co.
 - 2. Calpico, Inc.
 - 3. Cole-Flex Corp.
 - 4. Emed Co., Inc.
 - 5. George-Ingraham Corp.
 - 6. Ideal Industries, Inc.
 - 7. Kraftbilt
 - 8. LEM Products, Inc.
 - 9. Markal Corp
 - 10. National Band and Tag Co.
 - 11. Panduit Corp.

12. Radar Engineers Div., EPIC Corp.
13. Seton Name Plate Co.
14. Standard Signs, Inc.
15. W.H Brady, Co.

2.2 ELECTRICAL IDENTIFICATION PRODUCTS

- A. Wire/Cable Designation Tape Markers:
 1. Vinyl or vinyl-cloth, self-adhesive, wraparound, cable/conductor markers with pre-printed numbers and letters.
- B. Brass or Aluminum Tags:
 1. Metal tags with stamped legend, punched for fastener.
 2. Dimensions: 2" X 2" 19 gage.
- C. Engraved, Plastic Laminated Labels, Signs and Instruction Plates:
 1. Engraving stock plastic laminate, 1/16" minimum thickness for signs up to 20 sq. in. or 8" in length; 1/8 " thick for larger sizes. Engraved legend in 1/4" high white letters on black face and punched for mechanical fasteners.
- D. Equipment Labels:
 1. Adhesive backed polyester with self-laminating flap. Chemical, abrasion and heat resistant.
 2. Dimensions: minimum 5" x 2"
 3. Conductor-Identification-Means Labels:
 - a. Information contained: the method utilized for identifying ungrounded conductors within switchboards, distribution panels and branch circuit panels.
 4. Available-Fault-Current Labels:
 - a. Information contained: maximum available fault current at the respective piece of equipment, and date of calculation of fault current.
 5. Source-of-Supply Labels:
 - a. Information contained: indicate the device or equipment where the power supply originates.
- E. Baked Enamel Warning and Caution Signs for Interior Use:
 1. Preprinted aluminum signs, punched for fasteners, with colors legend and size appropriate to location.
- F. Fasteners for Plastic-Laminated and Metal Signs:
 1. Self-tapping stainless steel screws or # 10/32 stainless steel machine screws with nuts, flat and lock washers.
- G. Cable Ties:
 1. Fungus-inert, self-extinguishing, one-piece, self-locking nylon cable ties, 0.18" minimum width, 50-lb. Minimum tensile strength, and suitable for a temperature range from minus 40° F. to 185° F. Provide ties for specified colors when used for color coding.
- H. Colored Support Wires:
 1. When electrical equipment/wiring is supported by wires within the ceiling cavity, these wires shall be independent of the ceiling support assembly and shall be distinguishable by painting entire length in bright yellow.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Lettering and Graphics:
1. Coordinate names, abbreviations, colors and other designations used in electrical identification work with corresponding designations specified or indicated. Install numbers, lettering and colors as approved in submittals and as required by code.
- B. Install identification devices in accordance with manufacturer's written instructions and requirements of NEC.
- C. Sequence of Work:
1. Where identification is to be applied to surfaces that require a finish, install identification after completion of finish work.
- D. Conductor Color Coding.
1. Provide color coding for secondary service, feeder and branch circuit conductors throughout the project secondary electrical system as follows:

<u>CONDUCTOR</u>	<u>208Y / 120V System</u>	<u>480Y / 277V System</u>
Phase A	Black	Brown
Phase B	Red	Orange
Phase C	Blue	Yellow
Shared/Single Neutral	White	Gray
Neutral A (dedicated)	White w/Black Stripe	Gray w/Black Stripe
Neutral B (dedicated)	White w/Red Stripe	Gray w/Orange Stipe
Neutral C (dedicated)	White w/Blue Stripe	Gray w/Yellow Stipe
Equipment Ground	Green	Green
Isolated Ground	Green w/Yellow Strip	Green w/Yellow Stripe

2. Switch legs, travelers and other wiring for branch circuits shall be of colors other than those listed above.
3. Use conductors with color factory applied the entire length of the conductors except as follows:
 - a. The following field-applied color-coding methods may be used in lieu of factory-coded wire for sizes larger than No. 10 AWG.
 - b. Apply colored, pressure-sensitive plastic tape in half-lapped turns for a distance of 6 inches from terminal points and in boxes where splices or taps are made. Apply the last two laps of tape with no tension to prevent possible unwinding. Use 1-inch-wide tape in colors as specified. Do not obliterate cable identification markings by taping. Tape locations may be adjusted slightly to prevent such obliteration.
 - c. In lieu of pressure-sensitive tape, colored cable ties may be used for color identification. Apply three ties of specified color to each wire at each terminal or splice point starting 3 inches from the terminal and spaced 3 inches apart. Apply with a special tool or pliers, tighten for snug fit, and cut off excess length.

E. Power Circuit Identification.

1. Securely fasten identifying metal tags or aluminum wraparound marker bands to cables, feeders, and power circuits in vaults, pull boxes, junction boxes, manholes, and switchboard rooms with 1/4-inch steel letter and number stamps with legend to correspond with designations on Drawings. If metal tags are provided, attach them with approximately 55-lb monofilament line or one-piece self-locking nylon cable ties.
2. Tag or label conductors as follows:
 - a. Future Connections: Conductors indicated to be for future connection or connection under another contract with identification indicating source and circuit numbers.
 - b. Multiple Circuits: Where multiple branch circuits or control wiring or communications/ signal conductors are present in the same box or enclosure (except for three-circuit, four-wire home runs), label each conductor or cable. Provide legend indicating source, voltage, circuit number, and phase for branch circuit wiring. Phase and voltage of branch circuit wiring may be indicated by mean of coded color of conductor insulation. For control and communications/signal wiring, use color coding or wire/cable marking tape at terminations and at intermediate locations where conductors appear in wiring boxes, troughs, and control cabinets. Use consistent letter/number conductor designations throughout on wire/cable marking tapes.
3. Match identification markings with designations used in panelboards shop drawings, Contract Documents, and similar previously established identification schemes for the facility's electrical installations.

F. Apply warning, caution and instruction signs and stencils as follows:

1. Install warning, caution, or instruction signs where required by NEC, where indicated, or where reasonably required to assure safe operation and maintenance of electrical systems and of the items they connect. Install engraved plastic-laminated instruction signs with approved legend where instructions or explanations are needed for system or equipment operation. Install butyrate signs with metal backing for outdoor items. Warning and caution signs shall be furnished and installed on, but not be limited to the following equipment and locations:
 - a. Entrances to rooms and other guarded locations that contain exposed live parts 600 volts or less; signs shall forbid unqualified personnel to enter.
 - b. Switch and Overcurrent device enclosures with splices, taps and feed-through conductors. Provide warning label on the enclosures that identifies the nearest disconnecting means for any feed-through conductors.
 - c. Entrances to buildings, vaults, rooms or enclosures containing exposed live parts or exposed conductors operating at over 600 volts: DANGER-HIGH VOLTAGE-KEEP OUT.
 - d. Metal-enclosed switchgear, unit substations, transformers, enclosures, pull boxes, connection boxes and similar equipment operating at over 600 volts shall have appropriate caution signs and warning labels.
 - e. Indoor and Outdoor substations operating over 600 volts. Provide warning signs, instructional signs and single-line diagrams in accordance with NEC 225.70.

G. Install equipment/system circuit/device identification as follows:

1. Apply equipment identification labels of engraved plastic-laminate on each major unit of electrical equipment in building, including central or master unit of each electrical system. This includes communication/signal/alarm systems, unless unit is specified with its own self-explanatory identification. Except as otherwise indicated, provide single line of text, with 1/4"-high lettering on 1-inch-high label (1 1/2-inch-high where two lines are required) white lettering in black field. White lettering in red field for Emergency Power Systems. Text shall match terminology and numbering of the Contract Documents and shop drawings. Apply labels for each unit of the following categories of electrical equipment.
 - a. Each service disconnect, to identify it as a service disconnect.
 - b. Panelboards (exterior and interior), electrical cabinets, and enclosures. For subpanels, identify feeder circuit served from.
 - c. Switches in fusible panelboards shall be labeled. Main switches shall be identified.
 - d. Access doors and panels for concealed electrical items.
 - e. Electrical switchgear and switchboards.
 - f. Motor control centers.
 - g. Motor starters, including circuit origination, HP, heater size, FLA, and mechanical equipment designation.
 - h. Disconnect switches.
 - i. Power transfer equipment.
 - j. Contactors.
 - k. Dimmers.
 - l. Control devices.
 - m. Fire alarm master station or control panel.
 - n. Lighting Control Equipment.
- H. Post Conductor-Identification-Means labels at locations of switchboards, distribution panels and branch circuit panels. The labels shall identify the color-coding used on ungrounded conductors for each voltage system used on the premises.
- I. The label shall identify the device or equipment where the power supply originates, and the system voltage and phase. For example: Feeder Power Supply for Panel "XX" Originates at Panel "XX" (or Switchboard "XX", Transformer "XX", Switch "XX", etc.); 120/208 volts, 3-phase (or 120/240, 277/480, etc.).
- J. Apply circuit/control/item designation labels of engraved plastic laminate for disconnect switches, breakers, pushbuttons, pilot lights, motor control centers, and similar items for power distribution and control components above, except panelboards and alarm/signal components, where labeling is specified elsewhere.
- K. Install labels at locations indicated and at locations for best convenience of viewing without interference with operation and maintenance of equipment.
- L. Engrave all receptacle plates other than those serving 120 volt, single phase devices. State voltage and amperage characteristics: Example; "208V 30A".
- M. Mark each device box (for each type of wiring device) with a permanent ink felt tip marker, indicating the circuit that the device is connected to: Example; "CKT A-1"
- N. Label circuit breaker feeding fire alarm panel "Fire Alarm Circuit". Using plastic laminate label, white lettering on a red background.

END OF SECTION

SECTION 26 09 23

OCCUPANCY SENSORS

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to wiring devices specified herein.

1.2 DESCRIPTION OF WORK:

- A. The extent of occupancy sensor work is indicated by drawings and schedules.
- B. Types of occupancy sensors in this section include the following:
 - 1. Dual Technology Wall Switch with Dimming and Daylight Control.
 - 2. Dual Technology Ceiling Sensor w/ Control Pack

1.3 QUALITY ASSURANCE:

- A. Comply with NEC and NEMA standards as applicable to construction and installation of occupancy sensors. Provide occupancy sensors that have been UL listed and labeled.
- B. All sensors shall be capable of operating normally with electronic ballasts, PL lamp systems, motor loads and any other passive infrared or microwave systems.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 MANUFACTURER: The manufacturer shall have a minimum of five years of experience in the sensor and lighting control industry. Sensors and related relays shall be compatible with the specific lighting types controlled. All sensors shall be of the same manufacturer, mixing brands of sensors is not acceptable.

- A. ULTRASONIC (MICROPHONICS) CEILING SENSORS: Where units are indicated, provide a sensor that meets the following minimum requirements:
 - 1. The sensor shall be Class 2, low voltage device capable of mounting to a wall or ceiling as required for optimum coverage.
 - 2. Sensor shall incorporate one transmitter for each receiver oriented in the same direction.
 - 3. Sensor shall be capable of being networked with additional units to achieve adequate coverage.
 - 4. Sensor shall utilize a dry contact relay for control of lighting relay.
 - 5. Sensor shall have adjustable sensitivity from 0% to 100% for coverage pattern.
 - 6. Sensor shall have time out adjustment from 15 seconds to 32 minutes. Timer shall use a timer chip and be linear in adjustment.
 - 7. Sensitivity and timer controls shall be accessible on the front of the sensor, but recessed to inhibit tampering.
 - 8. Sensor shall incorporate an accessible, but recessed, ON override device.

9. Sensor shall be easily mounted to a suspended ceiling tile without using large holes, or to a standard 4 x 4 box.
 10. Sensor shall be available with more than one pair of transmitters/receivers to achieve coverage required.
 11. Sensor shall incorporate a real time motion indicator visible from the front of the unit.
 12. Transmitters/receivers shall be protected from damage.
- B. DUAL TECHNOLOGY WALL SWITCH: Where units are indicated provide a sensor that meets the following minimum requirements:
1. Sensor shall utilize PIR (Passive Infrared) to turn on the lights and then PIR or US (Ultrasonic) technologies to keep lights on.
 2. Sensor shall incorporate an inrush current limiter circuit to protect the relay contacts.
 3. Sensor shall utilize single or dual dry relay contacts for control of the lighting loads. Contractor shall verify requirements in coordination with the drawings.
 4. Sensor shall have a self-adjusting time delay, selectable 5, 15 and 30 minutes.
 5. Sensor shall have automatic sensitivity adjustment and be microprocessor controlled.
 6. Sensor shall have light level sensing 0 to 200 footcandles.
 7. Sensor shall have a 180 degree field of view, coverage up to 800 square feet and shall detect 6 inches of hand movement towards the sensor up to 300 square feet; and body motion towards the sensor up to 1000 square feet.
 8. Sensor shall be rated for 0 to 800 watts at 120VAC and 0 to 1200 watts at 277VAC.
 9. Sensor shall be automatic on and shall have an automatic to off override switch on the unit. Switch shall be equipped with an air gap switch to disconnect power to the lighting load.
 10. Sensor shall have real time motion indicator on the front of the unit.
 11. Sensor shall mount to a single gang switch box.
 12. Subject to compliance with the above requirements. Provide models of one of the following:
 - a. Greengate ONW-DT
 - b. Sensor Switch WSX PDT Series
 - c. Douglas WOS Series
- C. DUAL TECHNOLOGY WALL SWITCH WITH DIMMING AND DAY-LIGHT CONTROL: Where units are indicated, provide a sensor that meets the following minimum requirements:
1. Dual technology sensors shall have one of its two technologies, not require motion to detect occupancy.
 2. Sensors shall offer a minimum on timer of at least 15 minutes, in order to prevent all cycling of lamps before they have burned for the lamp manufacturers minimum recommended time period.
 3. Sensors shall utilize an occupancy time delay that keeps lights on after last detected occupancy. Factory default setting of the occupancy time delay shall be 15 minutes.

4. Manual adjustment to the occupancy time delay so as to increase it shall be accommodated.
 5. Sensor shall be capable of switching both 120 VAC and 277 VAC.
 6. Sensor shall recess into single gang switch box and fit standard GFI opening.
 7. Sensor shall meet NEC grounding requirements by providing a dedicated ground connection and intrinsically grounding through its mounting strap.
 8. Line and load wire connections shall be interchangeable.
 9. Wall switch sensor shall have field programmable adjustments for selecting operational modes, occupancy time delays, minimum on time, and photocell set-point.
 10. Sensor shall be capable of both auto-on and manual operation.
 11. Combination photocell/dimming sensors set point and deadband shall be automatically calibrated through the sensors microprocessor by initiating the automatic set point programming procedure. Min and max dim settings as well as set point may be manually entered.
 12. Subject to compliance with the above requirements, provide models of one of the following:
 - a. Sensor-Switch – WSX-PDT-D Series
 - b. Green Gate – CSW-d-010
- D. DUAL TECHNOLOGY CEILING SENSOR: Where units are indicated, provide a sensor that meets the following minimum requirements:
1. Sensor shall incorporate ultrasonic (microphonics) and infrared technologies in a single unit.
 2. Sensor shall be Class 2, low voltage; capable of mounting in the ceiling for maximum coverage.
 3. Sensor shall use internal microprocessor for motion signal analysis and automatic self-adjustment.
 4. Sensor shall have automatic self-adjustment algorithm that adjusts timer and sensitivity settings to maximize performance and minimize energy usage.
 5. Sensor shall have manual time-out adjustment from 8 minutes to 32 minutes and automatic time out from 8 minutes to 100 minutes.
 6. Sensor shall have test time-out setting of 8 seconds, with automatic return to 8 minutes after one hour if sensor is left in test mode.
 7. Sensor's microprocessor shall automatically extend timer by 1 hour in response to recognition to false off condition. After 5 hours, sensor reduces extended time by 30 minutes and continues to reduce by 30 minute increments over the next few days.
 8. Sensor's microprocessor shall automatically reduce either PIR or ultrasonic sensitivity in response to false on condition.
 9. Sensor microprocessor will automatically monitor PIR background threshold signal level and makes corresponding sensitivity adjustments automatically.

10. Sensor microprocessor algorithm shall incorporate automatic adaptation to continuous airflow.
 11. For airflow that is so intense as to mask motion, sensor shall flash indicator LED code to indicate excessive airflow.
 12. Sensor's microprocessor shall use a four week learning period and develop a circadian calendar.
 13. An internal 24 hour 7 day clock establishes what periods the room is typically occupied, biasing sensor to keep lights on while normally occupied and off when normally unoccupied.
 14. Sensor shall have selection settings for the following dual technology schemes:
 - a. High Sensitivity and High Confidence (miser mode)
 15. Sensor shall be available with either 180 degrees or 360 degrees coverage pattern.
 16. Infrared lens shall have 360 degree field of view. Two types of lens shall be available, standard and extra dense.
 17. Sensor shall have a variety of mask inserts for PIR coverage rejection to prevent false tripping.
 18. Transducers shall be protected from tampering.
 19. Sensor shall have manual adjustments for timer and sensitivities and override switches to force manual adjustment mode.
 20. Sensor shall have adjustable sensitivity from 0% to 100% for both ultrasonic and infrared.
 21. Controls shall be behind cover to resist tampering. All adjustments shall be accessible from the front of the sensor.
 22. Sensor shall be available with a photocell adjustment from 20 to 3,000 Lux.
 23. Sensor shall provide internal operating status and settings confirmation via LED motion lamp indicator.
 24. Sensor shall have two (if 180 degree) or three (if 360 degree) real time LED motion indicators visible from the front of the unit: Red = infrared; green = ultrasonic.
 25. Subject to compliance with the above requirements, provide models of one of the following:
 - a. Hubbell-ATD Series
 - b. Sensor Switch-CM-PDT 9/10 Series
 - c. Wattstopper-DT Series
 - d. Mytech-Omni-DT Series
 - e. Leviton – OSC UOW Series
 - f. Greengate OAC– DT Series
 - g. Douglas – WOR Series
- E. 24 VDC POWER/CONTROL PACK: Where units are indicated, provide a power/control pack that meets the following minimum requirements:
1. Control module shall consist of a DC power supply and a dry contact relay for switching a lighting load.
 2. Control module shall be available in versions to accept 120, and 277 VAC line voltages.
 3. Output shall be 24VDC nominal, and shall be inherently safe, low voltage, limited power output (Class 2).

4. Output shall supply 100mA current, in addition to current consumed internally to operate internal relay.
5. Relay shall utilize normally open, silver alloy dry contacts, and shall be rated for a 20A ballast load at 120V and 277V.
6. Relay function shall not require more than 5 mA control current to operate.
7. Control module shall have line voltage wiring, consisting of input voltage and relay contact connections, exiting from one end, and low voltage DC connections, consisting of ground, power, and control wires, exiting from the other end.
8. Control module shall be sized to fit inside a standard 4" x 4" junction box.
9. Control module shall be equipped with a 1/2" EMT threaded male fitting on the line voltage end, such that it may be mounted to the outside of a junction box with the line voltage wiring internal to the box and the low voltage wiring external.
10. Control module shall be equipable with accessory 1/2" EMT threaded male fitting on the low voltage end, such that it may be mounted to the inside of a ballast cavity with the box and line voltage wiring internal to the cavity and the low voltage wiring external.
11. Slave module shall be available for switching additional circuits. Slave module has same construction and specifications as control module except without power supply function.
12. Subject to compliance with the above requirements, provide models of one of the following:
 - a. Hubbell-CU Series
 - b. Sensor Switch-MP20 Series
 - c. Wattstopper-BEP Series
 - d. Mytech-MP Series
 - e. Greengate SP20-MV Series
 - f. Leviton – OSC/OSA Series
 - g. Douglas – WP-PP

PART 3 EXECUTION

3.1 INSTALLATION OF LIGHTING CONTROL EQUIPMENT:

- A. Install occupancy lighting control system components and ancillary equipment as indicated, in accordance with equipment manufacturer's written instructions, and with recognized industry practices, to ensure that lighting control equipment complies with requirements.
- B. Comply with requirements of NEC, and applicable portions of NECA's "Standard of Installation" pertaining to general electrical installation practices.
- C. Coordinate with other electrical work, including raceways, and electrical boxes and fittings, as necessary to interface installation of lighting control equipment work with other work.
- D. Contractor shall be on site as required, to adjust lighting control units for proper operation.
- E. Mount the switchpack in a standard 4" junction box. Mount sensor to a standard 4" junction boxes. Refer to manufacturer supplied mounting instructions.
- F. Spare Parts: Refer to Section 26 0502 for requirements.

3.2 FIELD QUALITY CONTROL:

- A. Upon completion of installation and after circuitry has been energized, demonstrate capability and compliance of system with requirements.
- B. System start-up: Provide a factory authorized technician to verify the installation and test the system.
- C. Where possible, correct malfunctioning units at site, then retest to demonstrate compliance; otherwise, remove and replace with new units, and proceed with retesting.
- D. Contractor shall visit the job site 3 months after the owner has taken occupancy and adjust any units not operating properly, otherwise remove and replace with new units.

3.3 PRODUCT SUPPORT AND SERVICES:

- A. System Start-Up: Provide a factory authorized technician to verify the installation, test the system, and train the owner on proper operation and maintenance of the system. Before requesting start-up services, the installing contractor shall verify that:
 - 1. The sensors have been fully installed in accordance with manufacturer's installation instructions.
 - 2. Low voltage wiring for overrides and sensors is completed.
 - 3. Accurate 'as-built' load schedules have been prepared.
 - 4. Proper notification of the impending start-up has been provided to the owner's representative.
 - 5. Programming of all switches, sensors, power packs, relays, etc. shall be completed by factory authorized technician, prior to final and training.
- B. Factory support: Factory telephone support shall be available at no cost to the owner during the warranty period. Factory assistance shall consist of assistance in solving programming or other application issues pertaining to the control equipment. The factory shall provide a toll free number for technical support.
- C. Functional Testing:
 - 1. The owner shall hire a third party that will conduct and certify the functional testing.
 - 2. Lighting controls devices shall be tested to ensure that control hardware and software are calibrated, adjusted, programmed, and in proper working conditions in accordance with the construction documents, manufacturer's instructions and code requirements. The following shall be performed:
 - a. Certify that sensors have been located, aimed and calibrated per manufacturer recommendations.
 - b. Status indicator operates properly.
 - c. Fixtures that are controlled by auto-on controls turn on to permitted level.
 - d. Fixtures that are controlled by manual on controls operate when manually activated.
 - e. Fixtures do not turn on incorrectly due to HVAC or movement outside the controlled area.
 - f. Confirm that occupancy sensors turn off after space is vacated and do

not turn on unless space is occupied.

g. Simulate unoccupied conditions and confirm that vacancy sensors only turn on manually and turn off after space is vacated.

3. The party responsible for the functional testing shall provide documentation that the installed lighting controls meet or exceed all performance criteria and shall not be directly involved in the design or construction of the project.

3.4 WARRANTY:

A. Manufacturer shall provide a one (1) year limited warranty on lighting control system. A ten (10) year limited warranty shall be provided on the lighting control relays.

3.5 RECORD DRAWINGS: Refer to Section 26 0502 for requirements.

3.6 TRAINING

A. Provide four (4) hours of video taped training in two 2 hour sessions on the operation and use of the lighting control equipment, at job site, at no cost to the Owner.

3.7 MANUFACTURER AUTHORIZED PERSONNEL TRAINING:

A. Building Operating Personnel Training: Train Owner's building personnel in procedures for starting-up, testing and operating lighting control system equipment.

END OF SECTION

SECTION 26 09 43

LIGHTING CONTROL EQUIPMENT

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Division-26 Basic Materials and Methods sections apply to work specified in this section.

1.2 DESCRIPTION OF WORK

- A. Extent of lighting control equipment work is indicated by drawings and schedules, and is hereby defined to include, but not by way of limitation, lighting control panels, control stations and other user interface devices, wiring and ancillary equipment.
- B. Types of lighting control equipment specified in this section, includes the following:
 - 1. Low voltage relay control panels
 - 2. Occupancy sensors
- C. Requirements are indicated elsewhere in these specifications for work including but not limited to raceways, electrical boxes and fittings required for installation of lighting control equipment, not work of this section.

1.3 QUALITY ASSURANCE:

- A. Manufacturers: Firms regularly engaged in manufacture of lighting control equipment and ancillary equipment, of types and capacities required, whose products have been in satisfactory use in similar service for not less than 5 years. To ensure a uniform installation and single responsibility, all switching and dimming equipment described herein shall be supplied by a single manufacturer.
- B. Installer: Qualified with at least 3 years of successful installation experience on projects with lighting control equipment installation work similar to that required for project.
- C. NEC Compliance: The control system shall comply with all applicable National Electrical Codes regarding electrical wiring standards.
- D. NEMA Compliance: The control system shall comply with all applicable portions of the NEMA Standard regarding the types of electrical equipment enclosure.
- E. Codes and Standards: Provide units that meet the requirements of IEEE Std. 2000.1.1999.
- F. Independent Testing Laboratory: Provide units that have been tested and listed under UL 916 energy management equipment.
- G. Component Pre-testing: All control equipment shall undergo strict inspection standards. The equipment shall be previously tested and burned-in at the factory prior to installation.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

- A. Manufacturer: Subject to compliance with requirements, provide lighting control equipment of one of the following;
1. [Douglas Lighting Controls](#)
 2. [Greengate Lighting Control](#)
 3. [Lighting Control & Design](#)
 4. [Lutron](#)
 5. [Nexlight](#)
 6. [Wattstopper](#)
 7. [Hubbell Automation](#)

2.2 SYSTEM DESCRIPTION

- A. The lighting control system shall provide seamless control and monitoring of all lighting included in the scope of work regardless of whether it is relay switched or dimmed.
- B. The lighting control system shall consist of low voltage relay control panels with programmable switch inputs, the panel shall be microprocessor controlled with a touchscreen interface display. The touchscreen shall provide relay status information viewable through a protected windowed enclosure. All local programming shall be permissible through the self-prompting touchscreen.
- C. Programmable intelligence shall include:
1. Time of day control (64 time-of-day/holiday schedules)
 2. 32 holiday dates
 3. Timed inputs (adjustable from 1 to 99 minutes)
 4. Timed override (from touchscreen, adjustable from 1 to 999 minutes, then resumes normal schedule)
 5. Pre-set controls
 6. Auto daylight savings adjust
 7. Astronomical clock with offsets
 8. Local control (from touchscreen and local switch)
 9. Digital switches
 10. Flash warning of impending off for occupants
 11. Network override
- D. The controller shall permit lighting to be overridden on for after-hours use or cleaning. The controller shall provide priority and masking choices to allow for customizing the functions of switch inputs, thereby enabling switches to function differently at different times of day. These overrides shall be digital, network or hard-wired inputs.
- E. The lighting control system shall be fully programmable through PC programming software. Programming shall be permitted through a direct RS-232 connection, modem or TCP/IP.

- F. The control system shall provide networking between lighting control panels. The network shall support up to a maximum of 254 control panels. Panels shall permit data sharing for global controls. All inputs shall be transferable over the network to create any switching pattern.
- G. The lighting control system shall log all control events. Log reports shall be available through the integral touchscreen or enterprise software.

2.3 EQUIPMENT

A. Relay Panel

1. Enclosure: Shall be NEMA 1 rated, code gauge steel cabinet. Enclosure and contents shall be designed to operate in interior spaces with temperatures of 32°F - 104°F (0°-40°C) and 0-90% non-condensing humidity. Enclosure shall be available with optional recessed mounting hardware. See drawings for mounting requirements and refer to schedules on drawings for sizes.
2. Interior: Interiors shall be sized to accept relays and will provide true on/off indication of relay status through LED's. The system shall employ all modular connectors to avoid repeat wiring in case of component failure. The system CPU board shall be mounted on quick release hinge pins. All connections for the dry contact inputs shall incorporate modular connectors.
3. Power Supply: The control panel shall incorporate the use of a multi-tapped transformer. The panel shall not require specification of voltage for each control location. The voltage of 120 and 277 VAC shall be available with each control panel.
4. Cover: Provide surface cover with captive screws in hinged, lockable configuration. A wiring schedule directory card shall be affixed to the covers back to allow identification of circuits/relays/load controlled. Schedules must be typed and related to final room names and numbers (not bid document room names and numbers).
5. High Voltage Barrier: The controller shall provide the ability to provide for either voltage separation or emergency circuit separation.
6. Relays: The system shall utilize normally open control relays, that are rated to 20A at 120/277 VAC. The relays shall be mechanically latching, and shall permit individual override and LED configuration of relay status. The relays shall be rated for 10 million operations.
7. System Controller: The system controller shall consist of an integral touchscreen that provides access to the main programming features. The touchscreen shall permit the user to manually command any or all relays individually.
 - a. Provide master on/off control of a relay group while still allowing individual relays to be overridden by their local switch.
 - b. The control system shall permit up to 32 dry contact inputs for override purposes. Momentary 3 wire or 2 wire (toggle) inputs shall be supported. Any input shall be software linked to any number or relays.
 - c. The controller shall provide timers for each override. Each override timer shall be capable of 0-999 minutes. Software shall enable or disable overrides based on priorities, masks or time of day scheduling.
 - d. The controller shall accept either dry contact or analog ambient light sensors. The controller shall provide power for the sensor. Sensors shall provide for outdoor, indoor or skylight applications and issue a command to the controller once the threshold is reached.
 - e. Each control panel shall incorporate diagnostic aids for confirmation of

proper operation. The control panel shall employ both a backlit touchscreen and LED's to indicate:

- i. Power
 - ii. System OK
 - iii. Network communications
 - iv. System clock and date
 - v. Programming confirmation
 - vi. Control panel subnet network communications
8. Switches: The lighting controller shall support digitally addressable LED annunciated switches. Provide low voltage push-button switches in up to 6 button configurations. Provide factory engraved labeling for individual push-buttons. Provide in color to match wiring devices and coverplate to match devices and plates in Wiring Devices (Section 26 2726).
9. Wiring:
- a. Provide CAT5 cable between switches and controller to create a digital switch network.
 - b. Provide CAT5 cable between controller and other controllers via a RS-485 network. The RS-485 network shall support up to 250 controllers with a maximum distance of 4000 feet.
 - c. Programming: Provide a RS-232 (RJ-R Connection) to allow programming through either a local connection or remotely through a modem.
 - d. Provide wiring in conduit located within the walls and non-accessible ceilings. Provide wiring above accessible ceilings in (conduit to system enclosure) to system enclosure.
10. Ceiling Mounted Occupancy Sensors: Sensors shall utilize dual-technology (ultrasonic and infrared technologies) and have the following additional features:
- a. Sensor shall be class 2, low voltage; capable of mounting in the ceiling for maximum coverage.
 - b. Sensor shall have automatic self-adjustment algorithm that adjusts timer and sensitivity settings to maximize performance and minimize energy usage.
 - c. Sensor shall have 360 degree field of view.
 - d. Sensor shall incorporate non-volatile memory such that all settings and parameters are saved in protected memory.
 - e. Sensor shall have time delays from 10 to 30 minutes.
 - f. Sensor shall provide a visual means of indication that motion is being detected via an LED.
 - g. Sensors shall have readily accessible, user adjustable settings for time delay and sensitivity.

PART 3 EXECUTION:

3.1 INSTALLATION OF LIGHTING CONTROL EQUIPMENT:

- A. Install lighting control system components and ancillary equipment as indicated, in accordance with equipment manufacturers written instructions, and with recognized industry practices, to ensure that lighting control equipment complies with requirements.
- B. Comply with Requirements of NEC, and applicable portions of NECA's 'Standard of Installation' pertaining to general electrical installation practices.

- C. Coordinate with other electrical work, including raceways, electrical boxes and fittings, as necessary to interface installation of lighting control equipment work with other work.
- D. Electrical Identification: Refer to Section 26 0553 for requirements.

3.2 FIELD QUALITY CONTROL:

- A. Upon completion of installation and after circuitry has been energized, demonstrate capability and compliance of system with requirements.
- B. Where possible, correct malfunctioning units at site, then retest to demonstrate compliance; otherwise, remove and replace with new units, and proceed with retesting.

3.3 PRODUCT SUPPORT AND SERVICES:

- A. System Start-Up: Provide a factory authorized technician to verify the installation, test the system, and train the owner on proper operation and maintenance of the system. Before requesting start-up services, the installing contractor shall verify that:
 - 1. The control system has been fully installed in accordance with manufacturer's installation instructions.
 - 2. Low voltage wiring for overrides and sensors is completed.
 - 3. Accurate 'as-built' load schedules have been prepared for each lighting control panel.
 - 4. Proper notification of the impending start-up has been provided to the owner's representative.
 - 5. Programming of all switches, relays, groups of shall be completed by factory authorized technician, prior to final and training.
- B. Factory support: Factory telephone support shall be available at no cost to the owner during the warranty period. Factory assistance shall consist of assistance in solving programming or other application issues pertaining to the control equipment. The factory shall provide a toll free number for technical support.

3.4 WARRANTY:

- A. Manufacturer shall provide a one (1) year limited warranty on lighting control system. A ten (10) year limited warranty shall be provided on the lighting control relays.

3.5 RECORD DRAWINGS: Refer to Section 26 0502 for requirements.

3.6 TRAINING

- A. Provide four (4) hours of video taped training in two 2 hour sessions on the operation and use of the lighting control equipment, at job site, at no cost to the Owner.

END OF SECTION

SECTION 26 2200

TRANSFORMERS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Division-26 Basic Materials and Methods sections apply to work specified in this section.

1.2 DESCRIPTION OF WORK:

- A. Extent of transformer work is indicated by drawings and schedules. Work includes complete installation and electrical connections.
- B. Types of transformers in this section include the following:
 - 1. Liquid-filled transformers
 - 2. Dry-type Distribution Transformers

1.3 QUALITY ASSURANCE:

- A. Comply with NEC as applicable to installation and construction of electrical power/distribution transformers; with applicable portions of NEMA Std. Pub. Nos. TR1 and TR27; and with applicable ANSI/IEEE standards pertaining to power/distribution transformers.
- B. Comply with applicable portions of ANSI/UL 506; "Safety Standard for Specialty Transformers". Provide distribution transformers that have been UL listed and labeled.
- C. All characteristics, definitions, and terminology, except as specifically covered in this specification, shall be in accordance with the latest revision of the following ANSI/IEEE, NEMA, and Department of Energy standards.
 - 1. C57.12.00 – IEEE Standard for Standard General Requirements for Liquid-Immersed Distribution, Power, and Regulating Transformers.
 - 2. C57.12.28 – Pad-Mounted Equipment - Enclosure Integrity.
 - 3. C57.12.34 – IEEE Standard Requirements for Pad-Mounted, Compartmental-Type, Self-Cooled, Three-Phase Distribution Transformers (2500 kVA and Smaller) - High Voltage: 34500GrdY/19920 Volts and Below; Low-Voltage: 480 Volt 2500 kVA and Smaller (issued in March 2005 - combines C57.12.22 and C57.12.26).
 - 4. C57.12.90 – IEEE Standard Test Code for Liquid-Immersed Distribution, Power, and Regulating Transformers and IEEE Guide for Short-Circuit Testing of Distribution and Power Transformers.
 - 5. C57.12.91 – Guide for Loading Mineral-Oil-Immersed Transformers.
 - 6. NEMA TR 1-1993 (R2000) – Transformers, Regulators and Reactors, Table 0-2 Audible Sound Levels for Liquid-Immersed Power Transformers.
 - 7. NEMA 260-1996 (2004) – Safety Labels for Pad-Mounted Switchgear and Transformers Sited in Public Areas.
 - 8. 10 CFR Part 431 – Department of Energy – Energy Conservation Program for Commercial Equipment: Distribution Transformers Energy Conservation Standards; Final Rule.

9. NEMA ST-20 - Dry-Type Transformers for General Applications
10. NEMA TP-1-2002 – Standards for transformer energy efficiency.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

- A. MAINTENANCE STOCK FUSES: Refer to Section 26 0502 for requirements.

PART 2 -PRODUCTS

2.1 POWER/DISTRIBUTION TRANSFORMERS: (LIQUID-FILLED):

- A. GENERAL: Except as otherwise indicated, provide manufacturer's standard materials and components as indicated by published product information, designed and constructed as recommended by manufacturer, and as required for complete installation.
- B. MANUFACTURER: Subject to compliance with requirements, provide products of one of the following (for each type of transformer):
1. General Electric Company
 2. Waukesha Electric Systems, General Signal Corp.
 3. Cooper Power Systems, Cooper Industries
 4. Standard/Balteau Transformer Div. Amer. Gage & Mach. Co.
 5. Siemens Energy & Automation, Inc.
- C. The percent impedance voltage, as measured on the rated voltage connection, shall be per Table 1.

Table 1	
Percent Impedance Voltage (Liquid-Filled)	
KVA Rating (Secondary voltage < 700 V)	Impedance
0 – 75	3.00 – 5.75%
112.5 – 225	4.00 – 5.75%
300 – 500	5.00 – 5.75%
750 – 3000	5.00 – 5.75%

- D. LIQUID-FILLED DISTRIBUTION TRANSFORMERS: Provide factory-assembled, liquid-filled, outdoor type tamper-resistant, pad mounted distribution transformers where shown; of sizes, and characteristics indicated; 3-phase, 60-hertz and with ratings as follow:
1. Primary Voltage: [] (Delta)(Wye), 95 KV BIL
 2. Taps: Provide externally operable, de-energized tap changing operation as required in Section 4.3 of ANSI C57.12.34 with [(2) 2-1/2% taps above rated voltage, (2) 2-1/2% taps below rated voltage], [(4) – 2-1/2% taps below rated voltage], [NEMA taps (14,400, 13800, 13200, 12470, 12540)], [No taps].
 3. Secondary Voltage: [] (Delta)(Wye)
 4. Windings: (aluminum)
 5. Dielectric Coolant: (FR3 high firepoint, non-propagating dielectric coolant)
- E. The average winding temperature rise above ambient temperature, when tested at the transformer rating, shall not (exceed 65°C at transformer rating), (shall not exceed 55°C at transformer rating), (shall not exceed 55°C at transformer rating and when tested at 112% of the base rating, shall not exceed 65°C).
- F. Equip with high voltage terminations and provide equipment of dead front construction, conforming to ANSI C57.12,26 requirements. Provide (universal type bushing wells)(one

piece integrated bushings for use with load-break elbow terminations) and parking stands for mounting accessory equipment. Clamp bushings or wells externally. Arrange terminations/equipment for (radial) feed. Provide Bay-O-Net type oil immersed fuses in series with oil immersed ELSP current limiting fuses. Verify fuse size with manufacturer's recommendation. Equip with tank grounding provision in high and low voltage compartments. Provide low voltage bushings consisting of molded epoxy blade type spade terminals with standard hole spacing for vertical take off. Provide low voltage, insulated neutral, grounded to transformer tank; tie to primary and secondary neutrals of wye-wye systems by means of a removable link. Equip sealed transformer tank with drain and sampling valves, filter-press connection, magnetic oil gage with alarm contacts, automatic pressure relief device, grounding block, and top-oil dial type thermometer. Provide steel enclosure with hinged lift-off cabinet doors capable of locking. Equip with three elbow valve lightning arrestors with a minimum duty cycle of 18 kV, and high voltage compartment barrier. Apply manufacturer's standard blue-green outdoor enamel over cleaned and phosphatized steel enclosure.

- G. The dielectric coolant shall be listed less-flammable fluid meeting the requirements of National Electrical Code Section 450-23 and the requirements of the National Electrical Safety Code (IEEE C2-2002), Section 15. The dielectric coolant shall be non-toxic*, non-bioaccumulating and be readily and completely biodegradable per EPA OPPTS 835.3100. The base fluid shall be 100% derived from edible seed oils and food grade performance enhancing additives. The fluid shall not require genetically altered seeds for its base oil. The fluid shall result in zero mortality when tested on trout fry *. The fluid shall be certified to comply with the US EPA Environmental Technology Verification (ETV) requirements, and tested for compatibility with transformer components. The fluid shall be Factory Mutual Approved, UL Classified Dielectric Medium (UL-EOUV) and UL Classified Transformer Fluid (UL-EOVK), Envirotemp® FR3 fluid. *(Per OECD G.L. 203)
- H. Tank and Cabinet Enclosure
 - 1. The high-voltage and low-voltage compartments, separated by a metal barrier, shall be located side-by-side on one side of the transformer tank. When viewed from the front, the low-voltage compartment shall be on the right. Each compartment shall have a door that is constructed so as to provide access to the high-voltage compartment only after the door to the low-voltage compartment has been opened. There shall be one or more additional fastening devices that must be removed before the high-voltage door can be opened. Where the low-voltage compartment door is of a flat panel design, the compartment door shall have three-point latching with a handle provided for a locking device. Hinge pins and associated barrels shall be constructed of corrosion-resistant material, passivated AISI Type 304 or the equivalent.
- I. Finish Performance Requirements
 - 1. The tank coating shall meet all requirements in ANSI C57.12.28 including:
 - a. Salt Spray
 - b. Crosshatch adhesion
 - c. Humidity
 - d. Impact
 - e. Oil resistance
 - f. Ultraviolet accelerated weathering
 - g. Abrasion resistance – taber abraser

2. The enclosure integrity of the tank and cabinet shall meet the requirements for tamper resistance set forth in ANSI C57.12.28 including but not limited to the pry test, pull test, and wire probe test.
- J. Production Testing
1. All units shall be tested for the following:
 - a. No-Load (85°C or 20°C) losses at rated current
 - b. Total (85°C) losses at rated current
 - c. Percent Impedance (85°C) at rated current
 - d. Excitation current (100% voltage) test
 - e. Winding resistance measurement tests
 - f. Ratio tests using all tap settings
 - g. Polarity and phase relation tests
 - h. Induced potential tests
 - i. Full wave and reduced wave impulse test
- K. Minimally, transformers shall conform to efficiency levels for liquid immersed distribution transformers, as specified in Table I.1 of the Department of Energy ruling. "10 CFR Part 431 Energy Conservation Program for Commercial Equipment: Distribution Transformers Energy Conservation Standards; Final Rule; October 12, 2007." Manufacturer shall comply with the intent of all regulations set forth in noted ruling. This efficiency standard does not apply to step-up transformers.
- L. In addition, the manufacturer shall provide certification upon request for all design and other tests listed in C57.12.00, including verification that the design has passed short circuit criteria per ANSI C57.12.00 and C57.12.90.
- M. Manufacturer shall conform to guaranteed average losses as specified in ANSI C57.12.00. The no-load losses of a transformer shall not exceed the specified no-load losses by more than 10%, and the total losses of a transformer shall not exceed the specified total losses by more than 6%.

2.2 DRY -TYPE DISTRIBUTION TRANSFORMERS:

- A. GENERAL: Except as otherwise indicated, provide manufacturer's standard materials and components as indicated by published product information, designed and constructed as recommended by manufacturer, and as required for complete installation.
- B. MANUFACTURER: Subject to compliance with requirements, provide products of one of the following (for each type of transformer):
1. Acme Transformer Company
 2. General Electric Company
 3. Cutler Hammer Products, Eaton Corp.
 4. Federal Pacific
 5. Hevi-Duty Electric Div., General Signal Corp.
 6. Jefferson Electric
 7. Schneider Electric/Square D Co.
 8. Hammond Power Solutions
 9. Siemens Energy & Automation, Inc.

C. DRY-TYPE DISTRIBUTION TRANSFORMERS (GENERAL PURPOSE):

1. Provide factory-assembled, general-purpose, air-cooled, (aluminum) wound dry-type distribution transformers where shown; of sizes, characteristics, and rated capacities indicated. Provide primary winding with minimum of 4 full capacity taps; each 2-1/2 percent, two above and two below full-rated voltage for de-energized tap-changing operation.
2. Insulate with 220 degree C. UL recognized insulation system for (115)° degree C rise above 40o ambient at full load.
3. Limit sound levels to the following (as determined by ANSI/NEMA standards):
 - a. 15-50 KVA (42) dB
4. Provide terminal enclosure, with cover, to accommodate primary and secondary coil wiring connections. Equip terminal leads with connectors installed, suitable for copper or aluminum wiring. Cushion-mount transformer with vibration isolation supports. Provide transformers with ventilated, heavy gauge sheet steel enclosures. Apply manufacturer's standard light gray indoor enamel over cleaned and phosphatized steel enclosure. Provide transformers suitable for wall and floor mounting as indicated.
5. The percent impedance voltage, as measured on the rated voltage connection, shall be per Table 2.

Table 2 Percent Impedance Voltage (Dry-Type)	
KVA Rating (Secondary Voltage < 700 V)	Impedance
0 - 75	3.00 – 5.75%
112.5 - 225	4.00 - 5.75%
300 and above	5.00 - 5.75%

2.3 INSTALLATION OF TRANSFORMERS

- A. Install transformers as indicated, complying with manufacturer's written instructions, applicable requirements of NEC, NEMA and IEEE standards, and in accordance with recognized industry practices to ensure that products fulfill requirements.
- B. Coordinate transformer installation work with electrical raceway and wire/cable work, as necessary for proper interface.
- C. Connect transformer units to electrical wiring system; comply with requirements of other Division-26 sections.
- D. MOUNTING: Provide concrete pad under all floor mounted equipment and equipment mounted at grade. Secure equipment to pad. Refer to Section 26 0548 Electrical Seismic Control. Provide vertical and lateral support systems for all transformers that are supported from overhead structure. See drawings for support and attachment details. Provide neoprene vibration isolators at each anchor point.
- E. GROUNDING: Provide tightly fastened equipment grounding and bonding connections for transformers.
- F. TESTING: Upon completion of installation of transformers, energize primary circuit at rated voltage and frequency from normal power source and test transformers, including, but not limited to, audible sound levels, to demonstrate capability and compliance with requirements. Where possible, correct malfunctioning units at the site, then retest to demonstrate compliance; otherwise, remove and replace with new units and proceed with retesting.

END OF SECTION 26 2200

SECTION 26 24 13

SWITCHGEAR AND SWITCHBOARDS

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Division-26 Basic Materials and methods sections apply to work of this section except as otherwise indicated. See Section 262713 Service Entrance, for metering requirements. See Section 264313 for SPD requirements.

1.2 DESCRIPTION OF WORK:

- A. Extent of switchgear and switchboards is indicated by drawings and schedules.
- B. Types of switchgear and switchboards in this section include the following:
 - 1. AC Dead Front Switchboards (600V)

1.3 QUALITY ASSURANCE:

- A. Comply with NEC as applicable to construction and installation of electrical switchgear and switchboards. Provide switchgear and switchboards that have been UL listed and labeled.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

- A. MAINTENANCE STOCK FUSES: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

- A. Subject to compliance with requirements, provide products of one of the following (for each type of switchgear and switchboard):
- B. AC DEAD FRONT SWITCHBOARDS (600V):
 - 1. Cutler-Hammer Products, Eaton Corp.
 - 2. General Electric Co.
 - 3. Siemens Energy & Automation, Inc.
 - 4. Square D Co.

2.2 EQUIPMENT SECTIONS AND COMPONENTS:

- A. GENERAL: Except as otherwise indicated, provide switchgear and switchboards of types, sizes, characteristics, and ratings indicated, that comply with manufacturer's standard design, materials, components, and construction in accordance with published product information, and as required for a complete installation. See drawings and Section 262815. Series rated systems are not accepted.
- B. Overcurrent Protection Devices, for main and branch devices. Provide switchgear, switchboards, and overcurrent devices of one manufacturer.
- C. Provide each service entrance switchboard with surge protective device (SPD) mounted

in a separate enclosure adjacent to the switchboard/switchgear. See Section 264313 for SPD unit requirements. Provide in-line fusing for each phase of the device, and wire in accordance with manufacturer's instructions, with conductor length not exceeding 18".

2.3 AC DEAD-FRONT SWITCHBOARDS (600V):

- A. Provide factory assembled, dead front, metal enclosed, floor standing, self supporting, group mounted, secondary power switch boards, of sizes, electrical ratings and characteristics indicated consisting of panel (vertical) units, and containing circuit breaker and fusible switch assemblies of quantities, ratings and types indicated. Provide aluminum main bus and connections to switching devices of sufficient capacity to limit rated continuous current operating temperature rise to UL standard; with main bus and tap connections silver-surfaced or tin-plated and tightly bolted for maximum interrupting capacity. Provide accessibility of line and load terminations from front of switchboard. Prime and paint switchboard with manufacturer's standard finish and color. Equip units with built-in lifting eyes and yokes; provide individual panel (vertical) units, suitable for bolting together at project site, and constructed for the following environment:
 - 1. Installation: Indoors, NEMA Type 1.
- B. Limit height of upper most overcurrent device handle to 6'-2" to accommodate 4" curb.

PART 3 EXECUTION

3.1 INSTALLATION OF SWITCHGEAR AND SWITCHBOARDS:

- A. Install switchgear and switchboards where shown, in accordance with manufacturer's written instructions with recognized industry practices to ensure that switchgear and switchboards comply with requirements of NEMA and NEC standards, and applicable portions of NECA's "Standard of Installation".
- B. Install all switchgear and switchboards on 4" high concrete curb. Install concrete wiring trench under switchgear and switchboards; 18" deep, and 4" smaller in length and width than equipment base. Install grounding bushings on conduits penetrating trench. Secure equipment to pad/trench. Refer to section 26 0548 Electrical Seismic Control.
- C. Arrange conductors within switchgear and switchboards in neat fashion, and secure with suitable ties.
- D. Tighten fuses, if any, in each switchgear and switchboard.
- E. Provide and install spare fuse cabinet in main electrical room.
- F. Electrical Identification: Refer to Section 260553 for requirements.
- G. Provide a surge protective device on each switchboard located on the emergency distribution system. Refer to Section 26 4313 for requirements.

3.2 ADJUST AND CLEAN:

- A. Adjust operating mechanisms for free mechanical movement.
- B. Touch-up scratched or marred surfaces to match original finish.

3.3 FIELD QUALITY CONTROL:

- A. Prior to energization of switchgear and switchboards, check with ground resistance tester phase to phase and phase to ground insulation resistance levels to ensure requirements are fulfilled.
- B. Prior to energization, check switchgear and switchboards for electrical continuity of circuits, and for short circuits.

- C. Subsequent to wire and cable connections, energize switchgear and switchboard and demonstrate functioning in accordance with requirements.

END OF SECTION

SECTION 26 24 16

PANELBOARDS

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to panelboards specified herein.

1.2 DESCRIPTION OF WORK:

- A. The extent of panelboard and enclosure work, is indicated by drawings and schedules.
- B. Types of panelboards and enclosures in this section include lighting and appliance panelboards, and power distribution panelboards.

1.3 QUALITY ASSURANCE:

- A. Provide units that have been UL listed and labeled. Comply with NEC as applicable to installation of panelboards, cabinets, and cutout boxes. Comply with NEC pertaining to installation of wiring and equipment in hazardous locations. Comply with NEMA Stds. Pub No. 250, "Enclosures for Electrical Equipment (1000 volt maximum). Pub No. 1, "Instructions for Safe Installation, Operation and Maintenance of Panelboards Rated 600 Volts or Less".

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

- A. Subject to compliance with requirements, provide of one of the following:
 - 1. Cutler Hammer Products, Eaton Corp.
 - 2. General Electric Company
 - 3. Siemens Energy & Automation, Inc.
 - 4. Square D Company

2.2 PANELBOARDS:

- A. GENERAL:
 - 1. Except as otherwise indicated, provide panelboards, enclosures and ancillary components, of types, sizes, and ratings indicated. Equip with number of unit panelboard devices as required for complete installation. Fully equip "spaces" with hardware to receive breaker or switch of size indicated. Provide CU/AL rated lugs of proper size to accommodate conductors specified.
- B. POWER DISTRIBUTION PANELBOARDS:
 - 1. Provide dead-front safety type power distribution panelboards as indicated, with switching and protective devices in quantities, ratings, types and with arrangement shown. Equip with aluminum bus bars, full-sized neutral bus and ground bus. Provide fusible or circuit breaker branch and main devices as

indicated. Series rated systems are not acceptable. See Section 262815, Overcurrent Protection Devices.

C. LIGHTING AND APPLIANCE PANELBOARDS:

1. Provide dead-front safety type lighting and appliance panelboards as indicated, with switching and protective devices in quantities, ratings, types, and arrangement shown. Provide bolt-on thermal magnetic type branch breakers. Where multiple breakers are indicated, provide with common trip handle. Series rated systems are not acceptable. Equip with aluminum bus bars, full-sized neutral bus, and ground bus.

D. PANELBOARD ENCLOSURES:

1. Provide galvanized sheet steel cabinet type enclosures, in sizes and NEMA types as indicated, code-gage minimum 16-gage thickness. Provide door-in-door hinged fronts. Provide fronts with adjustable indicating trim clamps, and doors with flush locks and keys, all panelboard enclosures keyed alike, with concealed door hinges and door swings as indicated. Equip with interior circuit-directory frame, and card with clear plastic covering. Provide baked gray enamel finish over a rust inhibitor. Provide enclosures fabricated by same manufacturer as overcurrent devices contained therein Bolt engraved plastic laminate labels indicating panel name and voltage on the interior and exterior of panelboards.

E. FINISH:

1. Coat interior and exterior of surface with manufacturer's standard color; baked on enamel finish.

F. ELECTRICAL IDENTIFICATION:

1. Refer to Section 260553 for requirements.

PART 3 EXECUTION

3.1 INSTALLATION OF PANELBOARDS:

A. GENERAL:

1. Install panelboards and enclosures where indicated, in accordance with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standard of Installation", in compliance with recognized industry practices to ensure products fulfill requirements.

B. MOUNTING:

1. Provide 4" high concrete curb under floor standing distribution panelboards.
2. Coordinate installation of panelboards and enclosures with cable and raceway installation work. Anchor enclosures firmly to walls and structural surfaces, ensuring they are permanently and mechanically secure. Arrange conductors neatly within enclosure, and secure with suitable nylon ties. Fill out panelboard's circuit directory card upon completion of installation work. Utilize actual final building room numbers, not architectural numbers used on drawings. Identify individual lighting circuits and individual receptacle circuits by room served. Label circuit breakers to identify location of subpanel or equipment supplied using room numbers and equipment names. Include room number with equipment circuit designations. All directories to be typewritten.

END OF SECTION

SECTION 26 2726

WIRING DEVICES

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to wiring devices specified herein.

1.2 DESCRIPTION OF WORK:

- A. The extent of wiring device work is indicated by drawings and schedules. Wiring devices are defined as single discrete units of electrical distribution systems that are intended to carry but not utilize electric energy.
- B. Types of electrical wiring devices in this section include the following:
 - 1. Receptacles
 - 2. Switches
 - 3. Dimmer controls
 - 4. Cord caps
 - 5. Cord connectors

1.3 QUALITY ASSURANCE:

- A. Comply with NEC and NEMA standards as applicable to construction and installation of electrical wiring devices. Provide electrical wiring devices that have been UL listed and labeled.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 - PRODUCTS

2.1 FABRICATED WIRING DEVICES:

- A. GENERAL:
 - 1. Provide factory-fabricated wiring devices, in types, and electrical ratings for applications indicated and complying with NEMA Stds. Pub No. WD 1.
- B. Provide wiring devices (of proper voltage rating) as follows:

	<u>RECEPTACLE</u>	<u>SWITCHES</u>			
<u>MFGR</u>		<u>1-POLE</u>	<u>3-WAY</u>	<u>4-WAY</u>	<u>W-PILOT</u>
Hubbell	HBL 5352	HBL 1221	HBL 1223	HBL 1224	HBL 1221-PL
Bryant	5352	1221	1223	1224	1221-PL
Pass Seymour	5352	20AC1	20AC3	20AC4	20AC1-RPL
Leviton	5362	1221	1223	1224	
Cooper	5352	1221	1273	1224	1221-PL

- C. Provide devices in colors selected by Architect. Provide red devices on all emergency circuits.

D. GROUND-FAULT INTERRUPTER:

1. Provide general-duty, duplex receptacle, ground-fault circuit interrupters; feed-thru types, capable of protecting connected downstream receptacles on single circuit; grounding type UL-rated Class A, Group A, 20-amperes rating; 120-volts, 60 Hz; with solid-state ground-fault sensing and signaling; with 5 milliamperes ground-fault trip level; color as selected by Architect. Provide Hospital grade where required elsewhere by specification or drawings. Provide units of one of the following:
 - a. P&S/Sierra
 - b. Hubbell
 - c. Leviton
 - d. Square D

E. WEATHER-RESISTANT RECEPTACLES

1. Provide weather-resistant receptacles in outdoor locations such as under roofed open porches, canopies, marquees, etc.
2. Provide products of one of the following:
 - a. Pass & Seymour 2095TRWRXXX.
 - b. Hubbell GFTR20XX

F. CORD CAPS AND CONNECTORS:

1. Provide 3, 4 and 5-wire grounding, cap plugs, and connectors of ampere and voltage rating required, for final equipment, and as indicated otherwise on drawings.
2. Provide products of one of the following:
 - a. Cooper
 - b. General Electric
 - c. Hubbell
 - d. Leviton
 - e. P&S

2.2 WIRING DEVICE ACCESSORIES:

A. WALL PLATES:

1. Provide coverplates for wiring devices; plate color to match attached wiring devices. Provide nylon or Lexan coverplates in all finished areas. Provide galvanized steel plates in unfinished areas. Provide blank coverplates for all empty outlet boxes.

B. WEATHER-PROTECTING DEVICE ENCLOSURES:

1. Where required for compliance with NEC 406-8 (receptacles installed outdoors for use other than with portable tools or equipment), provide weather-tight device covers that provide complete protection with the cord and cap inserted into the wiring device. Provide units that mount on either single or double gang devices.
2. Provide products of one of the following for In Box Horizontal for brick and cast stone:
 - a. Arlington Industries
 - i. DSHB1C Clear Cover
 - ii. DSHB1W White Cover

- iii. DSHB1BR Brown Cover
 - iv. DSHB1BRC Brown Clear Cover
 - 3. Provide products of one of the following for In Box Vertical or Horizontal for Stucco and Metal Sidings:
 - a. Arlington Industries
 - i. DSBVM1C Clear Cover
 - ii. DSBVM1W White Cover
 - iii. DSBHM1C Clear Cover
 - iv. DSBHM1W White Cover
 - 4. Provide products of one of the following for roof mounted installations:
 - a. Intermatic WP1020 or WP1030
 - b. P&S WIUC10C or WIUC20c

PART 3 – EXECUTION

3.1 GENERAL

- A. Install wiring devices as indicated, in compliance with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standard of Installation" and in accordance with recognized industry practices to fulfill project requirements.
- B. Coordinate with other work, including painting, electrical box and wiring work, as necessary to interface installation of wiring devices with other work. Install devices in boxes such that front of device is flush and square with coverplate. Drawings are small scale and, unless dimensioned, indicate approximate locations only of outlets, devices, equipment, etc. Locate outlets and apparatus symmetrically on floors, walls and ceilings where not dimensioned and coordinate with other work. Verify all dimensioned items on job site. Consult architectural cabinet, millwork, and equipment shop drawings before beginning rough-in of electrical work. Adjust locations of all electrical outlets as required to accommodate work in area, and to avoid conflicts with wainscoat, back splash, tackboards, and other items.
- C. Provide receptacles in surface raceway at 12" 18" 24" 36" on center unless indicated otherwise.
- D. Install wiring devices only in electrical boxes that are clean; free from excess building materials, dirt, and debris.
- E. Install blank plates on all boxes without devices.
- F. Delay installation of wiring devices until wiring work and painting is completed. Provide separate neutral conductor from panel to each GFI receptacle.
- G. Install GFI receptacles for all receptacles installed in the following locations:
 - 1. Restrooms, locker rooms, kitchens, within 6 feet of any sink, or when serving vending machines and electric drinking fountains.
 - 2. Indoor wet locations, non-dwelling garages, elevator rooms and pits.
 - 3. Outdoors, and on rooftops.
 - 4. Dwelling unit garages, crawlspaces and unfinished basements, accessory buildings, boathouses, and receptacles for boat hoists.
- H. Where light switches or wall box dimmers are specified, provide a separate neutral for each phase of the branch circuits that switches or dimmers are connected.
- I. Electrical Identification: Refer to Section 260553 for requirements.

3.2 PROTECTION OF WALL PLATES AND RECEPTACLES:

- A. At time of substantial completion, replace those items, that have been damaged, including those stained, burned and scored.

3.3 GROUNDING:

- A. Provide electrically continuous, tight grounding connections for wiring devices, unless otherwise indicated.

3.4 TESTING:

- A. Prior to energizing circuitry, test wiring devices for electrical continuity and proper polarity connections. After energizing circuitry, test wiring devices to demonstrate compliance with requirements.

END OF SECTION 26 2726

SECTION 26 28 15

OVERCURRENT PROTECTIVE DEVICES

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to overcurrent protective devices specified herein.

1.2 DESCRIPTION OF WORK:

- A. Extent of overcurrent protective device work is indicated by drawings and schedules and specified herein. Overcurrent protective devices specified herein are for installation as individual components in separate enclosures; and for installation as integral components of switchboard and panelboards. See Section 262413, Switchgear and Switchboards, and Section 262416, Panelboards.
- B. Types of overcurrent protective devices in this section include the following for operation at 600 Volts and below:
 - 1. Molded case thermal circuit breakers
 - 2. Molded case solid-state circuit breakers
 - 3. Insulated case circuit breakers
 - 4. Power circuit breakers
 - 5. Fusible switches
 - 6. Bolted pressure switches
 - 7. Fuses
- C. Refer to other Division-26 sections for cable/wire and connector work required in conjunction with overcurrent protective devices.

1.3 QUALITY ASSURANCE

- A. Comply with NEC requirements and NEMA and ANSI standards as applicable to construction and installation of overcurrent devices.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

- A. Subject to compliance with requirements, provide products of one of the following (main and branch device manufacturer must be same as panelboard and/or switchboard manufacturer):
- B. CIRCUIT BREAKERS AND FUSIBLE SWITCHES:
 - 1. Cutler Hammer Products, Eaton Corp.
 - 2. General Electric Co.
 - 3. Square D Co.

4. Siemens Energy and Automation
- C. BOLTED PRESSURE SWITCHES:
1. Bolt Switch Co.
 2. General Electric Co. (HPC; High Pressure Contact Switches)
 3. Pringle Switch Co.
 4. Square D Co.
- D. MOLDED CASE THERMAL TRIP CIRCUIT BREAKERS:
1. Provide factory-assembled, molded case circuit breaker for power distribution panelboards and switchboards; and for individual mounting, as indicated. Provide breakers of amperage, voltage, and RMS interrupting rating shown, with permanent thermal trip and adjustable instantaneous magnetic trip in each pole. Series rated systems are not acceptable. Construct with overcenter, trip-free, toggle type operating mechanisms with quick-make, quick-break action and positive handle indication. Construct breakers for mounting and operating in any physical position and in an ambient temperature of 40 degrees C. Provide with mechanical screw type removable connector lugs, AL/CU rated, of proper size to accommodate conductors specified.
 2. Circuit breakers 15 amps through 599 amps shall be molded case thermal trip circuit breakers.

2.2 FUSES

- A. GENERAL: Except as otherwise indicated, provided fuses of type, sizes and ratings and electrical characteristics of a single manufacturer as follows. Provide fuses labeled UL Class L or UL Class R, current limiting and rated for up to 200,000 amperes. Provide Buss KAZ signal activating fuses where required elsewhere in specification.
- B. Where fuses are shown feeding individual or groups of equipment items, comply with manufacturer's recommendation for fusing; adjust fuse size and type as necessary to comply with manufacturer's recommendation.
- C. Provide and install spare fuse cabinet in main electrical room.
- D. MAIN SERVICE AND FEEDER CIRCUITS: For fuse ratings over 600 amperes provide UL Class L Fuses (KRP-C, or A4BQ or LCL or KLPC). For fuse ratings up to 600 amperes, provide UL Class RK1 (KTN-R, KTS-R or A2K-R, A6K-R or NCCR, SCLR or KLN-R, KLS-R). If fuse directly feeds motors, transformers or other inductive load provide UL RK5 time delay (FRN-R, FRS-R or TR-R, TRS-R or ECN-R, ECS-R or FLN-R, FLS-R).
- E. BRANCH CIRCUITS: For motor circuits, transformer circuits, or other inductive loads, provide UL Class RK5 (FRN-R, FRS-R or TR-R, TRS-R or ECN-R, ECN-S or FLN-R, FLS-A). For other circuits, provide UL Class RK1, (KTN-R, KTS-R OR A2K-R, A6K-R or NCLR, SCLR OR KLNR, KLSR).
- F. MANUFACTURER: Subject to compliance with requirements, provide fuses of one of the following:
1. Bussman Mfg. Co.
 2. Mersen (Ferraz Shawmut)
 3. Reliance Fuse Div./Brush Fuse Inc.
 4. Littlefuse, Inc.

PART 3 EXECUTION

3.1 INSTALLATION OF OVERCURRENT PROTECTIVE DEVICES:

- A. Install overcurrent protective devices as indicated, in accordance with the manufacturer's written instructions and with recognized industry practices to ensure that protective devices comply with requirements. Comply with NEC and NEMA standards for installation of overcurrent protective devices.
- B. Coordinate with work as necessary to interface installations of overcurrent protective devices with other work.
- C. Install fuses in overcurrent protective devices. For motor circuits, fuse sizes shown on drawings are for general guidance only. Size fuses in accordance with fuse manufacturer's recommendation for given motor nameplate ampere rating. Test operation. If nuisance tripping occurs, increase fuse size and disconnect device (if necessary) as required to provide nuisance free tripping. Adjust fuse size properly for ambient temperature, frequent starting and stopping of motor loads, and for loads with long start times. Include all costs in bid.
- D. After the switchgear is energized and just prior to Substantial Completion, the contractor shall ensure that the field-adjustable circuit breakers and solid-state circuit breakers and associated trip mechanisms have been set to the appropriate settings as recommended by the equipment Manufacturer (or as recommended by the electrical contractor's Protective Device Study if section 260573 has been included in the project). Time-current trip curves and trip setting information as was required in the Submittal portion of this specification shall be made available by the contractor at this time.
- E. Field test all ground fault protective devices for proper operation; test to be performed by representative of the manufacturer. Include verification of complete time current trip characteristics.
- F. Electrical Identification: Refer to Section 260553 for requirements.

3.2 FIELD QUALITY CONTROL

- A. Prior to energization of overcurrent protective devices, test devices for continuity of circuitry and for short-circuits. Correct malfunctioning units, and then demonstrate compliance with requirements.

END OF SECTION

SECTION 26 28 16

MOTOR AND CIRCUIT DISCONNECTS

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to motor and circuit disconnect switches specified herein.

1.2 DESCRIPTION OF WORK:

- A. Extent of motor and circuit disconnect switch work is indicated by drawings and schedule. Work includes complete installations and electrical connections.

1.3 QUALITY ASSURANCE:

- A. Provide motor and circuit disconnect switches that have been UL listed and labeled. Comply with applicable requirements of NEMA Standards Pub. No. KS 1, and NEC.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

- A. MANUFACTURER: Subject to compliance with requirements, provide products of one of the following (for each type of switch):
 - 1. Cutler Hammer Products, Eaton Corp.
 - 2. Square D Company
 - 3. General Electric Company
 - 4. Siemens Energy & Automation, Inc.

2.2 FABRICATED SWITCHES:

- A. GENERAL: Provide disconnect and safety switches as indicated herein. Provide:
 - 1. General duty switches on 240 Volt rated circuits.
 - 2. Heavy duty switches on 480 volt rated circuits.
 - 3. HP rated switches on all motor circuits.
- B. GENERAL DUTY SWITCHES: Provide general-duty type, sheet-steel enclosed switches, fusible or non-fusible as indicated of types, sizes and electrical characteristics indicated; rated 240 volts, 60 hertz; incorporating spring assisted, quick-make, quick-break mechanisms. Provide single phase or three phase and with solid neutral as required by application. Equip with operating handle that is capable of being padlocked in OFF position. Provide NEMA 1 or NEMA 3R as required by application, unless noted. Provide fusible switches with Class R rejection fuse clip kits.
- C. HEAVY-DUTY SWITCHES: Provide heavy-duty type, sheet-steel enclosed safety switches, fusible or non-fusible as indicated, of types, sizes and electrical characteristics

indicated; rated 600 volts, 60 hertz; incorporating quick-make, quick-break type mechanisms. Provide single phase or 3 phase, and with solid neutral as required by application, Equip with operating handle that is capable of being padlocked in OFF position. Provide NEMA 1 or NEMA 3R as required by application unless noted. Provide fusible switches with Class R rejection fuse clip kits.

- D. FUSES: Provide fuses for switches, as required of classes, types and ratings needed to fulfill electrical requirements for service indicated. See Section 262815 Overcurrent Protective Devices for fuse types. Refer to Section 26 0502 for requirements.
- E. Electrical Identification: Refer to Section 260553 for requirements.

PART 3 EXECUTION

3.1 INSTALLATION OF MOTOR AND CIRCUIT DISCONNECT SWITCHES:

- A. Install motor and circuit disconnect switches where indicated, complying with manufacturer's written instructions, applicable requirements of NEC, NEMA, and NECA's "Standard of Installation" and in accordance with recognized industry practices to ensure that products fulfill requirements.
- B. Coordinate motor and circuit disconnect switch installation work with electrical raceway and cable work, as necessary for proper interface.
- C. Install disconnect switches used with motor driven appliances, and motors and controllers within sight of controller position.
- D. For disconnect switches serving motors controlled by variable frequency drives, provide late-make, early-break auxiliary contacts on each disconnect switch. (Provide Heavy-Duty switch). Wire auxiliary contact to VFD safety contact, such that disconnecting the motor will shut down the drive first, and closing the switch will start the drive only after power is applied to the motor.

END OF SECTION

SECTION 26 29 13

MOTOR STARTERS

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of Division-26 sections making reference to motor starters specified herein.

1.2 DESCRIPTION OF WORK:

- A. Extent of motor starter work is indicated by drawings and schedules.
- B. Types of motor starters in this section include the following:
 - 1. AC Fraction Horsepower Manual Starters
 - 2. AC Line Voltage Manual Starters
 - 3. AC Non-Reversing Magnetic Starters
 - 4. AC Combination Non-Reversing Magnetic Starters

1.3 QUALITY ASSURANCE:

- A. Comply with NEC and NEMA Standards as applicable to wiring methods, construction and installation of motor starters. Comply with applicable requirements of UL 508, "Electric Industrial Control Equipment", pertaining to electrical motor starters. Provide units that have been UL-listed and labeled.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 MANUFACTURER:

- A. Subject to compliance with requirements, provide products of one of the following (for each type and rating of motor starter):
 - 1. Allen-Bradley Co.
 - 2. Appleton Electric Co.
 - 3. Crouse-Hinds Co.
 - 4. Eaton Corp., Cutler Hammer Products
 - 5. General Electric Co.
 - 6. Siemens Energy & Automation, Inc.
 - 7. Square D Co.
- B. MAINTENANCE STOCK, FUSES: Refer to Section 26 0502 for requirements.

2.2 MOTOR STARTERS:

- A. GENERAL: Except as otherwise indicated, provide motor starters and ancillary components; of types, sizes, ratings and electrical characteristics indicated that comply with manufacturer's standard materials, design and construction in accordance with published information and as required for complete installations.

- B. THERMAL OVERLOAD UNITS: Provide thermal overload units, sized to actual running full load current, not to motor plate current. Size heaters for mechanical equipment after air and water balancing have been completed.
- C. AC FRACTIONAL HP MANUAL STARTERS (EQUAL TO SQUARE D CLASS 2510): Provide manual, single-phase, 1 and 2 pole, 300 volt AC max, fractional HP motor starters, of types, ratings and electrical characteristics indicated; equip with one piece thermal overload relay with field adjustment capability of plus or minus 10 percent of nominal overload heater rating; for protection of AC motors of 1 HP and less. (For manually controlled motors in excess of 1 HP, see Line Voltage Manual Starters specified herein). Provide starter with quick-make, quick-break trip free toggle mechanisms, green pilot lights, and with lock-off toggle operated handle. Mount surface units in NEMA 1 enclosures, unless noted otherwise. Provide NEMA 3R enclosure in exterior or damp location unless noted otherwise. Provide flush mounted units with coverplate to match wiring device coverplates.
- D. AC LINE VOLTAGE MANUAL STARTERS (EQUAL TO SQUARE D CLASS 2510): Provide line voltage manual starters, of types, ratings and electrical characteristics indicated; 2 or 3 pole, 600 volt AC max; equip with pushbutton operator, low voltage protection feature, and green pilot light. Provide starters with trip free mechanism such that contacts will open under load and remain open until thermal element has cooled, and unit is reset. Mount surface units in NEMA 1 enclosure, unless noted otherwise. Provide NEMA 3R enclosure in exterior or damp location, unless noted otherwise. Provide overlapping trim for flush mounted units.
- E. AC NON-REVERSING MAGNETIC STARTERS (EQUAL TO SQUARE D CLASS 8536): Provide line voltage magnetic starters, of types, ratings and electrical characteristics indicated; 2 or 3 pole, 600 volt max, with thermal overload protection in all phases and inherent under voltage release. Equip units with holding contact, 2 normally open, and 2 normally closed auxiliary contacts, unless noted otherwise. Provide fused control transformer in each starter and 120V control coil. Mount hand-off-auto switch, red pilot light, and reset button in face of enclosure. Provide NEMA 1 enclosure unless noted otherwise. Provide NEMA 3R enclosure in exterior or damp location, unless noted otherwise. Equip all spare starters complete with items as specified herein.
- F. AC COMBINATION NON-REVERSING MAGNETIC STARTERS (EQUAL TO SQUARE D CLASS 8539): Provide line voltage combination starters, of types, ratings and electrical characteristics indicated; 2 or 3 pole, 600 volts max with non-reversing magnetic starters as specified herein; in common cubicle or enclosure with motor circuit protector. Provide motor circuit protector, instantaneous trip circuit breaker as indicated and adjust to comply with manufacturer's recommendations. Mount hand-off-auto switch, red pilot light, and reset button in face of enclosure. Provide combination starters for individual mounting, or for group mounting in motor control center as indicated. Provide NEMA 3R enclosure in exterior or damp locations, unless noted otherwise. Provide NEMA 1 enclosures unless otherwise indicated.
- G. AC COMBINATION NON-REVERSING MAGNETIC STARTERS (EQUAL TO SQUARE D CLASS 8538): Provide line voltage combination starters, of types, ratings, and electrical characteristics; 2 or 3 pole, 600 volt maximum with non-reversing magnetic starters as specified herein; in common cubicle or enclosure with fusible disconnect switch. Provide quick-make, quick-break, disconnect for NEMA sizes 1, 2, 3, and 4; and visible blade, automatic circuit interrupters with push-to-trip feature and separate fuse clips for larger NEMA sizes. Fuse all starters with dual-element (time-delay) fuses equal to Bussman FRN/FRS-R. Equip disconnect switch with Class R rejection fuse kits. Mount hand-off-auto switch, red pilot light, and reset button in face of enclosure. Provide combination starters for individual mounting, or for group mounting in motor control centers as indicated. Provide NEMA 1 enclosures unless otherwise indicated. Provide NEMA 3R enclosure in exterior or damp locations, unless noted otherwise.

PART 3 EXECUTION

3.1 INSTALLATION OF MOTOR STARTERS:

- A. Install motor starters as indicated, in accordance with manufacturer's written instructions, applicable requirements of NEC, NEMA standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.
- B. Install fuses in fusible disconnects, if any. Mount chart inside each starter indicating heater type, size, and ampere ratings available.
- C. Electrical Identification: Refer to Section 260553 for requirements.

3.2 ADJUST AND CLEAN:

- A. Inspect operating mechanisms for malfunctioning and, where necessary, adjust units for free mechanical movement.
- B. Touch-up scratched or marred surfaces to match original finish.

3.3 FIELD QUALITY CONTROL:

- A. Subsequent to wire/cable hook-up, energize motor starters and demonstrate functioning of equipment in accordance with requirements.

END OF SECTION

SECTION 26 4313

SURGE PROTECTIVE DEVICES (SPD)

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Division 26 Basic Materials and Methods sections apply to work specified in this section.

1.2 DESCRIPTION OF WORK:

- A. Extent of SPD's work is indicated by drawings, schedules and specified herein. Work includes complete installation, electrical connections, testing, and commissioning.

1.3 QUALITY ASSURANCE:

- A. Comply with NEC, NEMA and IEEE Standards as applicable to wiring methods, construction and installation of SPD's. Comply with applicable requirements of ANSI/IEEE C62.11, C62.41.2 and C62.45; NFPA 70 285 (Type 2), 75, and 78; and ANSI/UL 1449 4th edition. Provide complete packaged units that have been listed and labeled by Underwriters Laboratory. UL surge ratings (UL 1449) must be permanently affixed to the SPD's device.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 - PRODUCTS:

2.1 ACCEPTABLE MANUFACTURERS:

- A. Subject to compliance with requirements, provide products manufactured by one of the following as indicated by "Location Category" herein.
 - 1. Advanced Protection Technologies Inc.
 - 2. Current Technology Inc.
 - 3. Cutler Hammer, Inc.
 - 4. L.E.A. International
 - 5. Emerson Network Power Surge Protection Inc.
 - 6. United Power Corporation
 - 7. GE
 - 8. Eaton
 - 9. Surgellogic (Square D)
 - 10. Siemens Energy & Automation, Inc.

2.2 GENERAL:

- A. Except as otherwise indicated, provide high energy surge protective devices, with high frequency line noise filtering, suitable for application in Category A, B, and C environments as indicated. Provide types, sizes, ratings and electrical characteristics indicated that comply with manufacturer's standard materials, design, and construction in accordance with published information and as required for a complete installation.

2.3 VOLTAGE SURGE SUPPRESSION – GENERAL:

- A. Electrical Requirements
- SURGE PROTECTIVE DEVICES (SPD)

1. Unit Operating Voltage – Refer to drawings for operating voltage and unit configuration.
2. Maximum Continuous Operating Voltage (MCOV) – The MCOV shall not be less than 115% of the nominal system operating voltage.
3. The suppression system shall incorporate thermally protected metal-oxide varistors (MOVs) as the core surge suppression component for the service entrance and all other distribution levels. The system shall not utilize silicon avalanche diodes, selenium cells, air gaps, or other components that may crowbar the system voltage leading to system upset or create any environmental hazards.
4. Protection Modes – The SPD must protect all modes of the electrical system being utilized. The required protection modes are indicated by bullets in the following table:

Configuration	Protection Modes			
	L-N	L-G	L-L	N-G
Wye	•	•	•	•
Delta	N/A	•	•	N/A
Single Split Phase	•	•	•	•
High Leg Delta	•	•	•	•

5. Nominal Discharge Current (In) – All SPDs applied to the distribution system shall have a 20kA In rating regardless of their SPD Type (includes Types 1 and 2) or operating voltage. SPDs having an In less than 20kA shall be rejected.
6. ANSI/UL 1449 4th Edition Voltage Protection Rating (VPR) – The maximum ANSI/UL 1449 4th Edition VPR for the device shall not exceed the following:

B. SPD Design

1. Maintenance Free Design – The SPD shall be maintenance free and shall not require any user intervention throughout its life. SPDs containing items such as replaceable modules, replaceable fuses, or replaceable batteries shall not be accepted. SPDs requiring any maintenance of any sort such as periodic tightening of connections shall not be accepted. SPDs requiring user intervention to test the unit via a diagnostic test kit or similar device shall not be accepted.
2. Balanced Suppression Platform – The surge current shall be equally distributed to all MOV components to ensure equal stressing and maximum performance. The surge suppression platform must provide equal impedance paths to each matched MOV. Designs incorporating replaceable SPD modules shall not be accepted.
3. Electrical Noise Filter – Each unit shall include a high-performance EMI/RFI noise rejection filter. Noise attenuation for electric line noise shall be up to 50 dB from 10 kHz to 100 MHz using the MIL-STD-220A insertion loss test method. Products unable able to meet this specification shall not be accepted.
4. Internal Connections – No plug-in component modules or printed circuit boards shall be used as surge current conductors. All internal components shall be soldered, hardwired with connections utilizing low impedance conductors.
5. Monitoring Diagnostics – Each SPD shall provide the following integral monitoring options:
 - a. Protection Status Indicators - Each unit shall have a green / red solid-state indicator light that reports the status of the protection on each phase.

- i. For wye configured units, the indicator lights must report the status of all protection elements and circuitry in the L-N and L-G modes. Wye configured units shall also contain an additional green / red solid-state indicator light that reports the status of the protection elements and circuitry in the N-G mode. SPDs that indicate only the status of the L-N and L-G modes shall not be accepted.
 - ii. For delta configured units, the indicator lights must report the status of all protection elements and circuitry in the L-G and L-L modes.
 - iii. The absence of a green light and the presence of a red light shall indicate that damage has occurred on the respective phase or mode. All protection status indicators must indicate the actual status of the protection on each phase or mode. If power is removed from any one phase, the indicator lights must continue to indicate the status of the protection on all other phases and protection modes. Diagnostics packages that simply indicate whether power is present on a particular phase shall not be accepted.
 - b. Remote Status Monitor – The SPD must include Form C dry contacts (one NO and one NC) for remote annunciation of its status. Both the NO and NC contacts shall change state under any fault condition.
 - c. Audible Alarm and Silence Button – The SPD shall contain an audible alarm that will be activated under any fault condition. There shall also be an audible alarm silence button used to silence the audible alarm after it has been activated.
 - d. Surge Counter – The SPD shall be equipped with an LCD display that indicates to the user how many surges have occurred at the location. The surge counter shall trigger each time a surge event with a peak current magnitude of a minimum of $50 \pm 20A$ occurs. A reset pushbutton shall also be standard, allowing the surge counter to be zeroed. The reset button shall contain a mechanism to prevent accidental resetting of the counter via a single, short-duration button press. In order to prevent accidental resetting, the surge counter reset button shall be depressed for a minimum of 2 seconds in order to clear the surge count total.
 - i. The ongoing surge count shall be stored in non-volatile memory. If power to the SPD is completely interrupted, the ongoing count indicated on the surge counter's display prior to the interruption shall be stored in non-volatile memory and displayed after power is restored. The surge counter's memory shall not require a backup battery in order to achieve this functionality.
- 6. Overcurrent Protection
 - a. The unit shall contain thermally protected MOVs. These thermally protected MOVs shall have a thermal protection element packaged together with the MOV in order to achieve overcurrent protection of the MOV. The thermal protection element shall disconnect the MOV(s) from the system in a fail-safe manner should a condition occur that would cause them to enter a thermal runaway condition.
- 7. Fully Integrated Component Design – All of the SPD's components and diagnostics shall be contained within one discrete assembly. SPDs or individual

SPD modules that must be ganged together in order to achieve higher surge current ratings or other functionality shall not be accepted.

8. Safety Requirements

- a. The SPD shall minimize potential arc flash hazards by containing no user serviceable / replaceable parts and shall be maintenance free. SPDs containing items such as replaceable modules, replaceable fuses, or replaceable batteries shall not be accepted. SPDs requiring any maintenance of any sort such as periodic tightening of connections shall not be accepted. SPDs requiring user intervention to test the unit via a diagnostic test kit or similar device shall not be accepted.
- b. SPDs designed to interface with the electrical assembly via conductors shall require no user contact with the inside of the unit. Such units shall have any required conductors be factory installed.
- c. Sidemount SPDs shall be factory sealed in order to prevent access to the inside of the unit. Sidemount SPDs shall have factory installed phase, neutral, ground and remote status contact conductors factory installed and shall have a pigtail of conductors protruding outside of the enclosure for field installation.

2.4 SYSTEM APPLICATION

- A. The SPD applications covered under this section include distribution and branch panel locations, busway, motor control centers (MCC), switchgear, and switchboard assemblies. All SPDs shall be tested and demonstrate suitability for application within ANSI/IEEE C62.41 Category C, B, and A environments.
- B. Provide a surge protective device on each switchboard and panelboard located on the emergency distribution system. Refer to table below for category type.

Minimum surge current capacity based on ANSI / IEEE C62.41 location category			
CATEGORY	Application	Per Phase	Per Mode
C	Service Entrance Locations (Switchboards, Switchgear, MCC, Main Entrance)	250 kA	125 kA
B	High Exposure Roof Top Locations (Distribution Panelboards)	160 kA	80 kA
A	Branch Locations (Panelboards, MCCs, Busway)	120 kA	60 kA

- C. Surge Current Capacity – The minimum surge current capacity the device is capable of withstanding shall be as shown in the following table:
- D. SPD Type – all SPDs installed on the line side of the service entrance disconnect shall be Type 1 SPDs. All SPDs installed on the load side of the service entrance disconnect shall be Type 1 or Type 2 SPDs.

2.5 LIGHTING AND DISTRIBUTION PANELBOARD REQUIREMENTS

- A. The SPD application covered under this section includes lighting and distribution panelboards. The SPD units shall be tested and demonstrate suitability for application within ANSI/IEEE C62.41 Category B environments.
1. The SPD shall not limit the use of through-feed lugs, sub-feed lugs, and sub-feed breaker options.
 2. SPDs shall be installed immediately following the load side of the main breaker. SPDs installed in main lug only panelboards shall be installed immediately following the incoming main lugs.
 3. The panelboard shall be capable of re-energizing upon removal of the SPD.
 4. The SPD shall be interfaced to the panelboard via a direct bus bar connection. Alternately, an SPD connected to a 30A circuit breaker for disconnecting purposes may be installed using short lengths of conductors as long as the conductors originate integrally to the SPD. The SPD shall be located directly adjacent to the 30A circuit breaker.
 5. The SPD shall be included and mounted within the panelboard by the manufacturer of the panelboard.
 6. The SPD shall be of the same manufacturer as the panelboard.
 7. The complete panelboard including the SPD shall be UL67 listed.
- B. Switchgear, Switchboard, MCC and Busway Requirements
1. The SPD application covered under this section is for switchgear, switchboard, MCC, and busway locations. Service entrance located SPDs shall be tested and demonstrate suitability for application within ANSI/IEEE C62.41 Category C environments.
 2. The SPD shall be of the same manufacturer as the switchgear, switchboard, MCC, and busway
 3. The SPD shall be factory installed inside the switchgear, switchboard, MCC, and/or bus plug at the assembly point by the original equipment manufacturer
 4. Locate the SPD on the load side of the main disconnect device, as close as possible to the phase conductors and the ground/neutral bar.
 5. The SPD shall be connected through a disconnect (30A circuit breaker). The disconnect shall be located in immediate proximity to the SPD. Connection shall be made via bus, conductors, or other connections originating in the SPD and shall be kept as short as possible.
 6. The SPD shall be integral to switchgear, switchboard, MCC, and/or bus plug as a factory standardized design.
 7. All monitoring and diagnostic features shall be visible from the front of the equipment.

2.6 ENCLOSURES

- A. All enclosed equipment shall have NEMA 1 general purpose enclosures, unless otherwise noted. Provide enclosures suitable for locations as indicated on the drawings and as described below:
1. NEMA 1 – Constructed of a polymer (units integrated within electrical assemblies) or steel (sidemount units only), intended for indoor use to provide a degree of protection to personal access to hazardous parts and provide a degree of protection against the ingress of solid foreign objects (falling dirt).
 2. NEMA 4 – Constructed of steel intended for either indoor or outdoor use to provide a degree of protection against access to hazardous parts; to provide a

degree of protection of the equipment inside the enclosure against ingress of solid foreign objects (dirt and windblown dust); to provide a degree of protection with respect to the harmful effects on the equipment due to the ingress of water (rain, sleet, snow, splashing water, and hose directed water); and that will be undamaged by the external formation of ice on the enclosure. (sidemount units only)

3. NEMA 4X – Constructed of stainless steel providing the same level of protection as the NEMA 4 enclosure with the addition of corrosion protection. (sidemount units only)

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install SPD's as indicated in accordance with manufacturers recommendations and as necessary to meet requirements. Install with conductors of minimum length practicable, but in no case exceeding 30" in length; minimum conductor size - #8 AWG copper.
- B. Install conductors in straight runs with a minimum of turns or bends (minimum bend radius to be 90 degrees). Do not splice phase or ground conductors in SPD's circuit. Torque all conductor terminations in accordance with manufacturer's recommendations.

3.2 FIELD QUALITY CONTROL:

- A. Upon completion of installation of equipment, energize and demonstrate capability and compliance with requirements. Remove malfunctioning units, replace with new units and proceed with retesting.

END OF SECTION 26 4313

SECTION 26 51 00

INTERIOR AND EXTERIOR BUILDING LIGHTING

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Division-26 Basic Materials and Methods sections apply to work specified in this section.

1.2 DESCRIPTION OF WORK:

- A. Types of lighting fixtures in this section are indicated by schedule and include the following:
 - 1. High-Intensity-Discharge (HID)
 - 2. Fluorescent
 - 3. Incandescent/Halogen
 - 4. LED (Light Emitting Diode)

1.3 QUALITY ASSURANCE:

- A. Comply with NEC, NEMA and ANSI 132,1 as applicable to installation and construction of lighting fixtures. Provide lighting fixtures that have been UL-listed and labeled.
- B. Components and fixtures shall be listed and approved for the intended use by a National Recognized Testing Laboratory (NRTL) including: UL, ETL, and CSA or equivalent
- C. All led products shall comply with the latest version of Illuminating Engineer Society (IES) publications LM-79 and LM-80.

1.4 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

- A. Subject to compliance with requirements, provide products of one of the following (for each type of fixture):
 - 1. LED:
 - a. Cree
 - b. Nichia
 - c. Samsung
 - d. Philips Lumiled
 - e. Osram
 - f. Xicato

2.2 INTERIOR AND EXTERIOR LIGHTING FIXTURES:

A. GENERAL:

1. Provide lighting fixtures, of sizes, types and ratings indicated complete with, but not necessarily limited to, housings, lamps, lamp holders, reflectors, ballasts, LED drivers, starters, and wiring. Label each fixture with manufacturer's name and catalog number. Provide all enclosed fixtures with positive latch mechanisms; spring tension clips not acceptable. Provide all exterior fixtures with damp or wet location label as required by application.

B. SUPPORT REQUIREMENTS:

1. Provide all pendant and stem hung fixtures with flexible ball joint hangers at all points of support. Equip hooks used to hang fixtures with safety latches. Provide all detachable fixture parts, luminous ceiling accessories, louvers, diffusers, lenses, and reflectors with locking catches, screws, safety chain, or safety cable.

C. LIGHT EMITTING DIODE (LED) LUMINAIRES:

1. LED luminaires that can be serviced in place shall have a disconnecting means internal to the luminaires to disconnect simultaneously from the source of supply all conductors of the driver, including the grounded conductor. Disconnects shall not be required under the following exceptions:
 - a. Luminaires located in hazardous locations.
 - b. Luminaires used for egress lighting.
 - c. Cord-and-plug luminaires.
 - d. In industrial establishments with restricted public access where conditions of maintenance and supervision ensure that only qualified persons service the installation.
 - e. Where more than one luminaire is installed in a space and where disconnecting the supply conductors to the luminaire will not leave the space in total darkness.
 - f. Provide LED luminaires which are tested in accordance with IES LM-79, diodes tested in accordance with IES LM-80, and provide a minimum R9 rating of ≥ 50 (unless specified differently), a CRI rating of \geq than 80 and L70 (6K) = 50,000 hours (IES TM-21). Provide with 0-10V dimming drivers as standard.
 - g. The fixture manufacturer(s) shall warrant the luminaires, in their entirety, to be free from defects in material or workmanship for at least 5 years from date of manufacture. Provide warranty in accordance with other sections of this specification and include a certificate of warranty from the fixture manufacturer with extended warranty information and proper

PART 3 EXECUTION

3.1 INSTALLATION OF LIGHTING FIXTURES

- A. Install lighting fixtures at locations and heights as indicated, in accordance with fixture manufacturer's written instructions, applicable requirements of NEC, NECA's "Standards of Installation", NEMA standards, and with recognized industry practices to ensure that lighting fixtures fulfill requirements.
- B. Coordinate with other work as appropriate to properly interface installation of lighting fixtures with other work. Consult architectural reflected ceiling plan for exact location of all

lighting fixtures.

- C. Provide all necessary supports, brackets, and miscellaneous equipment for mounting of fixtures. Support all ceiling mounted fixtures from the building structure; independent of the ceiling system, unless noted. Support each recessed fixture (fluorescent incandescent, and/or HID) from the building structure with #12 ga. steel wire attached to each corner (in addition to supports normally provided for attachment to the ceiling system). Provide backing supports above (or behind) sheetrock, plaster and similar ceiling and wall materials. Support surface mounted ceiling fixtures from channel. Support ceiling mounted outlet boxes independent of the raceway system, and capable of supporting 200 pounds. Feed each recessed fixture directly from an outlet box with flex conduit as required; do not loop from fixture to fixture. See plans for additional details.
- D. FIXTURE WHIPS:
 - 1. Provide each lay-in light fixture with at least 36" (Not to exceed 72") of 3/8" steel flexible conduit.
- E. Coordinate lighting in mechanical room with duct and equipment locations to avoid obstruction of illumination.
- F. Provide gypsum board protection as required, (acceptable to fire official having jurisdiction) to ensure fire rating of each ceiling that the fixtures are installed in.
- G. COORDINATION MEETINGS:
 - 1. Meet at least twice with the ceiling installer. Hold first meeting before submittal of shop drawings to coordinate each light fixture mounting condition with ceiling type. During second meeting, coordinate fixture layout in each area.
 - 2. Meet at least once with the mechanical installer prior to fabrication and installation of duct work. Coordinate depth and location of all fixtures and duct work in all areas.
- H. ADJUST AND CLEAN:
 - 1. Clean lighting fixtures of dirt and debris upon completion of installation.
 - 2. Protect installed fixtures from damage during remainder of construction period. Repair all nicks and scratches to appearance of original finish.
- I. SPARE PARTS: Refer to Section 26 0502 for requirements.

3.2 FIELD QUALITY CONTROL:

- A. Upon completion of installation of lighting fixtures, and after building circuitry has been energized, apply electrical energy to demonstrate capability and compliance with requirements.
- B. Where possible, correct malfunctioning units at site, then retest to demonstrate compliance; otherwise remove and replace with new units, and proceed with retesting.
- C. At the time of Substantial Completion, replace lamps in interior lighting fixtures that are observed to be noticeably dimmed after the Contractor's use and testing, as judged by Architect/Engineer.
- D. GROUNDING:
 - 1. Provide equipment grounding connections for each lighting fixture.

END OF SECTION

SECTION 28 31 11

FIRE ALARM AND DETECTION SYSTEM

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Division-26 Basic Materials and Methods sections apply to work specified in this section.

1.2 DESCRIPTION OF WORK:

- A. Extent of fire alarm and detection systems work is indicated by drawings, schedules and as specified herein.
- B. Comply with NEC as applicable to construction and installation of fire alarm and detection system components and accessories. Provide components and systems that are UL-listed and labeled for fire alarm. Provide fire alarm and detection systems and accessories that are FM approved. Comply with State and local requirements as applicable.
- C. Comply with applicable provisions of current NFPA Standards 72, National Fire Alarm Code, local building codes, and meet requirements of local authorities having jurisdiction.
- D. Carefully review all Division 23 drawings for all fire/smoke dampers. Fire/smoke dampers are NOT shown on electrical plans. Electrical contractor is responsible for coordinating 120V power to all dampers and providing fire alarm connections to each one. See mechanical drawings for all locations.

1.3 SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

- A. MANUFACTURER: Subject to compliance with requirements, provide fire alarm and detection systems of one of the following:
 - 1. Grinnell
 - 2. EST
 - 3. Gamewell - FCI
 - 4. Simplex (Tyco Safety Products)
 - 5. Mirtone
 - 6. Mircom
 - 7. Notifier
 - 8. Silent Knight
 - 9. Siemens Fire
- B. The job foreman or lead technician shall be factory trained and certified on the system being installed. Individual shall have a minimum NICET II certification.

2.2 FIRE ALARM AND DETECTION SYSTEMS:

- A. GENERAL: Provide an electrically operated, electrically supervised fire alarm system as

described herein. Include control units, power supplies, alarm initiating and indicating devices, conduit, wire, fittings and accessories required to provide a complete operating system. Enclose entire system in raceway. Provide basic wiring materials that comply with Division 26, Basic Materials and Methods Sections for raceways, conductors, boxes, fittings, supports, etc. Minimum wire size to be #14 AWG copper.

- B. SYSTEM TYPE: Analog addressable, non-coded. Either manual activation of a fire alarm station or activation of an automatic initiating device energizes all fire alarm signaling devices, sounding a non-coded alarm and providing device identification on an annunciator panel.
- C. SYSTEM OPERATION: Provide system such that any manual station or automatic initiating device annunciates all alarm indicating units (bells, horns, buzzers, chimes, visual alarm lamps, etc.) continuously until the manual station or initiating device is restored to normal and the fire alarm control unit reset. Annunciate alarm signals by device at the control panel and all remote annunciators. Provide all conductors, raceway, equipment and labor to accomplish the following:
 - D. For fans that are not part of the smoke evacuation system, deactivate air supply and return fan units simultaneously by means of a supervised master fan shutdown relay with slave relays as required. Restart air units automatically after panel has been reset. Provide a bypass switch for master fan shut down relay for drill purposes, and indicate by a locked-in lamp that the circuit has been bypassed.
 - E. Selectively activate and/or deactivate fan units as required.
 - F. Release all magnetic door holders upon activation of an alarm from any device by use of a master relay in the control panel.
 - G. Provide supervised circuits for the following:
 - 1. Close dampers upon activation of an alarm from any device through the HVAC interface relays at the Fire Command Center.
 - 2. Recall elevators, upon activation of an alarm, to the floor of building egress unless the alarm is on the egress floor, in that case recall elevator to the level designated by the Fire Marshall. Cooperate with the elevator supplier to ensure complete operable system. Provide shunt trip breaker(s) as required.
 - 3. At the Fire Command Center, provide (1) dry contact HVAC interface relay per smoke zone for connection into the smoke management system. This is for all air handling units and fans that are used for the smoke evacuation system. The smoke evacuation system shall be provided by another Division of the specifications.
 - H. Central Station Monitoring. Provide a UL listed fire control communicator in accordance with NFPA 71 with a minimum of two reporting zones to the central station. Provide a communicator with dual phone lines for central station reporting by using BFSK or pulsed single round fast format. Provide integral trouble annunciator. Provide with compatibility for automatic test reports every 24 hours. Provide system and components that comply with UL 2635 and UL 864.
 - I. Provide fire alarm control panel with capability of shutting down individual initiating devices for maintenance purposes without affecting the continued operation of other initiating devices.
 - J. Provide manual fire alarm stations in boiler rooms, and main administrative office. Provide external alarm horns sufficient to be heard in all parking areas.
 - K. Sprinkler Supervision. Provide a signal initiating and supervisory circuit to each PIV (post indicator) valve, and to each sprinkler riser and subdivision. Provide continuous alarm signal upon actuation of any water flow signal initiating device. Sound alarm until the condition has been corrected and the panel manually reset as required by UL864.

Provide separate alarm zones for: (1) alarm zones from “waterflow alarms”, (2) alarm zones from “supervisory alarm” indicating sprinkler system trouble. Provide power to all alarm bells furnished under Division 21 Review final fire sprinkler drawings and coordinate for panel, flow and tamper switch locations.

- L. Provide relays, monitor modules and connections as required at control panel of kitchen hood suppression system for initiation of alarm signal to fire alarm control panel. Connect hood suppression control panel to shunt trip breakers as required.
- M. Provide all required wiring from gas shut off valve to the hood suppression control panel. Make all connections to ensure a properly operating system. Verify with Mechanical Contractor.

2.3 SCOPE OF THE WORK:

- A. Provide a new addressable fire alarm system with 08 ANALOG initiating loops/minimum of 1500 points.
- B. Provide all fire alarm devices.
- C. Provide duct smoke detectors and fan relays at all fan units 2000 CFM and over. Shut down all supply and return fans upon a general alarm signal.
- D. Provide a fire alarm duct detector within 5-feet of any fire/smoke damper as required to comply with IMC 607.5.4.1. The duct detector shall be listed for the air velocity, temperature and humidity at the point where it is to be installed. A duct detector will not be required at a fire/smoke damper located on a corridor wall where the corridor has smoke detection devices installed. For dampers installed within an un-ducted opening in a wall, a spot-type detector listed for releasing service shall be installed within 5-foot horizontally of the damper. Provide a fire alarm relay at each fire/smoke damper. Provide a test switch at each location where the damper is located above an inaccessible ceiling or is located more than 10 feet above the finished floor. Coordinate the location of test switches with owner/architect.
- E. All initiating devices connected to the fire alarm control panel shall be analog addressable.
- F. All wiring shall be in conduit (3/4" minimum). All conduit and connectors, shall be made of steel. All conduit runs shall form a complete loop from the fire alarm control panel.
- G. Provide vandal resistant cages to protect horn/strobes, smoke and heat detectors as indicated and, in gyms whether shown or not. Securely fasten security cages as required. Provide backing and bracing as required to ensure that attachment extends beyond the ceiling materials. Cages shall have two pieces, one backplate and one cover to attach to backplate.

2.4 FIRE ALARM CONTROL PANEL:

- A. The fire alarm control panel shall be microprocessor-based. Each loop shall be capable of 99 analog addresses and 98 monitor and/or control addresses.
- B. If the microprocessor fails, the system shall execute a default signaling program. This program will enable the panel to sound the audible signals and summon the Fire Department. In addition, a red LED shall light to indicate the device wherein the alarm originated. Inability of the system to sound signals or summon the fire department during microprocessor failure shall not be acceptable.
- C. The fire alarm control panel shall contain a 80 digit alphanumeric display and permit the user to perform all necessary functions including but not limited to the following:
 - 1. Alarm/Trouble Acknowledge
 - 2. Alarm Silence

3. Reset
 4. Lamp Test
 5. Control of Initiating Devices (on/off)
 6. Control of output modules (on/off)
 7. Change sensitivity of devices
 8. Change time
 9. Walk test
 10. Check system on battery voltage and current
- D. The fire alarm control panel shall be capable of alarm verification. The control panel shall indicate which smoke detector is in alarm during the pre-alarm window.
 - E. All alarm signals shall be locked in at the panel until the operated device is returned to its normal condition and the control panel is manually reset.
 - F. Alarm or trouble activation of initiating points shall be represented in English on the alphanumeric display on both the remote operating panel and the fire alarm control panel indicating the address of the specific device, i.e. Device L4S76, Smoke Detector, 1st floor Rm. 17.
 - G. Each initiating and signal circuit shall be electrically supervised for opens, shorts, and ground faults in the wiring.
 - H. The occurrence of any fault shall activate the system trouble circuitry but shall not interfere with the proper operation of any circuit that does not have a fault condition.
 - I. The system communication loops shall be capable of being wired using Class "A" (Style 6) supervised circuits (a ground fault on either conductor or a break shall not prevent a device from operating on either side of the break)
 - J. The fire alarm control panel shall contain circuitry permitting the transmission of trouble and alarm signals over leased phone lines by the means of reverse polarity. There shall be a supervised disconnect switch to allow testing of the fire alarm control panel without transmitting an alarm to the central station.
 - K. The fire alarm control panel shall include the following features:
 1. Auxiliary SPDT alarm actuated contacts.
 2. Auxiliary SPDT trouble actuated contacts.
 3. A solid-state power transfer circuit that shall switch to standby power automatically and instantaneously if normal power fails or falls below 15% of normal ("brown out" conditions). This electronic circuit shall allow the batteries to be effectively "floated" on the operating system to avoid upsetting the normal microprocessor scan and minimize resultant nuisance troubles and/or alarms.
 4. A ground fault detector to detect positive or negative grounds on the initiating circuits, signal circuits, power circuits, and telephone line circuit. A ground fault code on the alphanumeric display shall provide indication of either a positive or negative ground fault and shall operate a general trouble but shall not cause an alarm to be sounded
 5. A short circuit error message shall be a standard feature of the fire alarm control panel. Each communication loop shall be monitored and shall have a distinctive error message.
 6. Lightning protection shall be a standard feature of the fire alarm control panel and shall be incorporated in the power supply circuit, common control circuits, signal circuits, and telephone line circuit.

7. Individual circuit breakers shall be provided for the following: smoke detector power, main power supply, signal circuit #1, signal circuit #2, battery standby power, and auxiliary output.
 8. The fire alarm control panel shall be of dead-front construction. One key shall allow access to all electronics or to the dead-front access to the operator functions
 9. Opening the main door shall expose all components for inspection or adjustment without further dismantling of the cabinet, control unit, or wiring.
 10. It shall be possible to check and adjust the sensitivity of all analog devices from the main fire alarm panel.
- L. The fire alarm control panel shall have batteries capable of powering the system for (24) hours in standby condition and (5) minutes in alarm.
- M. There shall be no special tools required for the programming of devices. A standard slot head screwdriver only.

2.5 PRINTER (#FCI-PTR):

- A. The fire alarm control panel shall report all status changes to an 80 column wide carriage printer using 8.5"x11 standard printer paper. The printer shall be supervised by the control panel. In the event of a power outage, the control panel shall be capable of storing and printing out the last 500 events, including event during the power outage.
- B. The panel shall report a supervisory signal to the printer every 8 hours.

2.6 MONITOR MODULE (FCI AMM-2):

- A. Remote identification module devices shall be attached to any single normally open initiating device (heat detector, waterflow switch, duct detectors, sprinkler, tamper switches, kitchen hood, pull station, etc.). The modules shall supply addressing and status information to the Fire Alarm Control Panel through the dual loop module.

2.7 CONTROL POINT MODULE (FCI AOM):

- A. The control point module shall be connected to the same loop as the initiating devices, and shall provide a relay output (Form "C" 2 Amp @ 24 VDC, resistive only).
- B. This relay output shall be used to perform auxiliary functions.
- C. When the AOM is activated, the red "ACTIVE" LED shall be on solid. Under normal

2.8 MANUAL FIRE ALARM STATION (FCI, MS-2, W/AMM-2):

- A. Provide red enclosure, manual fire alarm stations with the following features:
 1. Aluminum construction, for flush mounting.
 2. Addressable alarm type electrically compatible with system requirements.
 3. Double Action
 4. Dual-Action design requiring unit to be opened for resetting, and requiring resetting before closing. Key reset, keyed like fire control panel.

2.9 IONIZATION SMOKE DETECTORS (FCI ASD-I W/ADB-F BASE):

- A. All ionization smoke detectors shall be capable of being replaced without disconnecting any wires or wire connectors from the base of the detector. Each detector shall be installed on a separate base. The detector base shall be capable of receiving a photoelectric, ionization, or electronic thermal detector. All ionization fire detectors shall be UL 268 listed. All detectors shall have (2) viewable LEDs to indicate the status of the device.

2.10 STROBES (FCI Model STS, FLUSH MOUNT):

- A. Provide strobe with flashing light unit, with Lexan lens with block letters "FIRE", and minimum flash rate of ONE per second, and high intensity 110 candela minimum. Strobes shall be synchronized when there are three or more within sight and less than 55 feet of viewer. Furnish in Red/White (color by Architect).

2.11 PORTABLE PLUGABLE PHONE (FCI 3200): Not Required

2.12 AUXILIARY RELAY (FCI, ARB-C):

- A. Remote auxiliary relay boards shall be rated at 10 AMPS @ 120 VAC. A red LED shall light to indicate relay activation. All relays shall transfer on general alarm and latch on until reset. All relays shall be supervised. The control output provided can be used in conjunction with fire alarm applications (i.e. fan controls, dampers, doors, and any other general alarm control).

2.13 INITIATING MODULES:

- A. Provide style "6" initiating modules capable of receiving and annunciating an alarm from any detector, even with a single fault condition on any initiating circuit.
- B. Power all smoke detectors from the "Style 6" initiating loop wiring. For systems that power smoke detectors separately from the "Style 6" loop, provide monitoring for both the power source and the independent initiating wiring, so that complete trouble and alarm indication is achieved by loop. Provide capability to operate all smoke detectors, even with a single fault condition on the smoke detector power wiring. Provide one spare initiating circuit.

2.14 SIGNALING MODULES:

- A. Provide signaling as required. Provide power adequate to sound all signaling devices concurrently. Provide supervised indicating circuits for polarized 24V D.C. alarm signaling devices. Provide 2 spare signaling circuits.
- B. Each signal circuit shall have a separate disconnect switch for servicing the fire alarm system. Each and every indicating circuit shall have a distinct location description. Power supply shall be at fire alarm control panel. Remote power supplies and indicating circuits will not be acceptable.

2.15 SUPPLEMENTAL NOTIFICATION CIRCUITS (FCI SNAC-4):

- A. Provide supplementary notification appliance circuit panel(s) as required. The 'SNAC' shall be capable of supplying up to four, Class A, Style Z notification appliance circuits. The panel shall contain its own battery charger, regulated power supply, and shall be supervised for ground fault, overcurrent, open circuits and low battery conditions. Ground fault, battery and circuit trouble conditions shall transmit a trouble signal to the main fire alarm control panel.

2.16 SYSTEM CONFIGURATION PROGRAMMING:

- A. To help the owner in programming, system changes, and servicing, the fire alarm system shall have the following functions.
 - 1. The FACP shall be capable of an auto-configuration, that via a password, all analog devices and panel modules are automatically programmed into the system. At this point the system will operate as a general alarm system without any other programming.
 - 2. If any two devices are addressed the same, the LED's on both devices will light steady and the panel will read "extra address and the address number".

3. If any device is installed and not programmed into the system the LED will light steady and the panel will read the same as above.

2.17 BATTERIES/POWER SUPPLIES:

- A. Provide standby batteries capable of operating fire alarm system for minimum of 24 hours, then operating all indicating units for at least five minutes. Locate batteries in fire alarm control unit, or in similar type enclosure located as directed. Provide all interconnecting wiring. Place batteries that vent hydrogen gas in separate enclosure. Provide 30 percent spare capacity.

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS:

- A. Approved Plans: A copy of the approved and stamped plans shall be on site during the installation and at the time of inspection to verify that the system is installed according to the approved plans.
- B. Install fire alarm and detection systems as indicated, in accordance with equipment manufacturer's written instructions and complying with applicable portions of NEC and NECA's "standard of installation".
- C. Install wiring, raceways, and electrical boxes and fittings in accordance with Division 26 Basic Materials and Methods section, "Raceways", "Wires and Cables", and "Electrical Boxes and Fittings", and in accordance with other sections, as applicable.
- D. All wire used on the fire alarm system shall be U.L. Listed as fire alarm protective signaling circuit cable per NEC, Article 760.
- E. If twisted or shielded wire is required or recommended by the manufacturer it must be used.
- F. Review proper installation procedure for each type of device with equipment supplier before installation.
- G. Provide a minimum of one 3/4" conduit with (2) Cat 5e telephone cables from FACP to main telephone terminal.
- H. Where smoke or heat detectors are specified, install device a minimum of three feet from adjacent air supply diffusers to ensure proper operation of device.
- I. Refer to NFPA for spacing and exact placement of fire alarm devices.
- J. Electrical Identification: Refer to Section 260553 for requirements.

PART 4 FINAL ACCEPTANCE AND GUARANTEE

4.1 GUARANTEE:

- A. Furnish a three-year guarantee for all equipment, materials and installation, including all labor, transportation, and equipment.
- B. Emergency Response. The fire alarm equipment supplier shall provide an emergency response within four hours of any reported system failure to resolve the problem on a continuous basis.

4.2 PRE-TEST:

- A. The contractor shall with a representative of the manufacturer conduct a test 3 days before the final test to verify operation of all devices. Any problems must be corrected before the final test.

4.3 FINAL TEST:

- A. Before the installation shall be considered completed and acceptable, a test on the system shall be performed as follows:
 - 1. The contractor's job foreman, a representative of the manufacturer, a representative of the owner, shall operate every building fire alarm device to ensure proper operation and correct annunciation at the control panel. Fan shutdown and door holder circuits shall operate.
 - 2. Conduct a full 24 hour test of battery operation. System shall be put on the batteries for a full 24 hours and all notification appliances shall be operational for a period of 5 minutes.

The supervisory circuitry of the initiating and indicating circuits shall also be verified.

4.4 SPARE PARTS: Refer to Section 26 0502 for requirements.

PART 5 AS BUILT DRAWINGS AND OPERATION AND MAINTENANCE MANUALS:

5.1 LABELING:

- A. All devices shall be labeled with their appropriate address. The labels shall be 18 point pressure sensitive labels.
- B. All initiating devices shall be programmed to include the device address and a complete user text English location description, i.e. Device L4S76, Smoke Detector, 1st floor Rm.17

5.2 RECORD DRAWINGS: Refer to Section 26 0502 for requirements.

5.3 OPERATING AND MAINTENANCE MANUALS: Refer to Section 26 0502 for requirements.

5.4 TRAINING:

- A. Provide four (4) hours training on the operation and installation of fire alarm system, at job site, at no cost to owner. Provide programming training and software sub-licensing in owner's name. Sub-licensing agreement shall include the U.L. requirement to allow the owner to do any programming that the supplier is allowed to do during commissioning, testing, service and field additions or deletions to the fire alarm system. The fire alarm supplier shall provide this training and licensing at no cost to the owner.

END OF SECTION

SECTION 26 09 43

LIGHTING CONTROL EQUIPMENT

PART 1 GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Division-26 Basic Materials and Methods sections apply to work specified in this section.

1.2 DESCRIPTION OF WORK

- A. Extent of lighting control equipment work is indicated by drawings and schedules, and is hereby defined to include, but not by way of limitation, lighting control panels, control stations and other user interface devices, wiring and ancillary equipment.
- B. Types of lighting control equipment specified in this section, includes the following:
 - 1. Low voltage relay control panels
 - 2. Occupancy sensors
- C. Requirements are indicated elsewhere in these specifications for work including but not limited to raceways, electrical boxes and fittings required for installation of lighting control equipment, not work of this section.

1.3 QUALITY ASSURANCE:

- A. Manufacturers: Firms regularly engaged in manufacture of lighting control equipment and ancillary equipment, of types and capacities required, whose products have been in satisfactory use in similar service for not less than 5 years. To ensure a uniform installation and single responsibility, all switching and dimming equipment described herein shall be supplied by a single manufacturer.
- B. Installer: Qualified with at least 3 years of successful installation experience on projects with lighting control equipment installation work similar to that required for project.
- C. NEC Compliance: The control system shall comply with all applicable National Electrical Codes regarding electrical wiring standards.
- D. NEMA Compliance: The control system shall comply with all applicable portions of the NEMA Standard regarding the types of electrical equipment enclosure.
- E. Codes and Standards: Provide units that meet the requirements of IEEE Std. 2000.1.1999.
- F. Independent Testing Laboratory: Provide units that have been tested and listed under UL 916 energy management equipment.
- G. Component Pre-testing: All control equipment shall undergo strict inspection standards. The equipment shall be previously tested and burned-in at the factory prior to installation.

1.4 **SUBMITTALS:** Refer to Section 26 0502 for requirements.

PART 2 PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

- A. Manufacturer: Subject to compliance with requirements, provide lighting control equipment of one of the following;
1. [Douglas Lighting Controls](#)
 2. [Greengate Lighting Control](#)
 3. [Lighting Control & Design](#)
 4. [Lutron](#)
 5. [Nexlight](#)
 6. [Wattstopper](#)
 7. [Hubbell Automation](#)

2.2 SYSTEM DESCRIPTION

- A. The lighting control system shall provide seamless control and monitoring of all lighting included in the scope of work regardless of whether it is relay switched or dimmed.
- B. The lighting control system shall consist of low voltage relay control panels with programmable switch inputs, the panel shall be microprocessor controlled with a touchscreen interface display. The touchscreen shall provide relay status information viewable through a protected windowed enclosure. All local programming shall be permissible through the self-prompting touchscreen.
- C. Programmable intelligence shall include:
1. Time of day control (64 time-of-day/holiday schedules)
 2. 32 holiday dates
 3. Timed inputs (adjustable from 1 to 99 minutes)
 4. Timed override (from touchscreen, adjustable from 1 to 999 minutes, then resumes normal schedule)
 5. Pre-set controls
 6. Auto daylight savings adjust
 7. Astronomical clock with offsets
 8. Local control (from touchscreen and local switch)
 9. Digital switches
 10. Flash warning of impending off for occupants
 11. Network override
- D. The controller shall permit lighting to be overridden on for after-hours use or cleaning. The controller shall provide priority and masking choices to allow for customizing the functions of switch inputs, thereby enabling switches to function differently at different times of day. These overrides shall be digital, network or hard-wired inputs.
- E. The lighting control system shall be fully programmable through PC programming software. Programming shall be permitted through a direct RS-232 connection, modem or TCP/IP.

- F. The control system shall provide networking between lighting control panels. The network shall support up to a maximum of 254 control panels. Panels shall permit data sharing for global controls. All inputs shall be transferable over the network to create any switching pattern.
- G. The lighting control system shall log all control events. Log reports shall be available through the integral touchscreen or enterprise software.

2.3 EQUIPMENT

A. Relay Panel

1. Enclosure: Shall be NEMA 1 rated, code gauge steel cabinet. Enclosure and contents shall be designed to operate in interior spaces with temperatures of 32°F - 104°F (0°-40°C) and 0-90% non-condensing humidity. Enclosure shall be available with optional recessed mounting hardware. See drawings for mounting requirements and refer to schedules on drawings for sizes.
2. Interior: Interiors shall be sized to accept relays and will provide true on/off indication of relay status through LED's. The system shall employ all modular connectors to avoid repeat wiring in case of component failure. The system CPU board shall be mounted on quick release hinge pins. All connections for the dry contact inputs shall incorporate modular connectors.
3. Power Supply: The control panel shall incorporate the use of a multi-tapped transformer. The panel shall not require specification of voltage for each control location. The voltage of 120 and 277 VAC shall be available with each control panel.
4. Cover: Provide surface cover with captive screws in hinged, lockable configuration. A wiring schedule directory card shall be affixed to the covers back to allow identification of circuits/relays/load controlled. Schedules must be typed and related to final room names and numbers (not bid document room names and numbers).
5. High Voltage Barrier: The controller shall provide the ability to provide for either voltage separation or emergency circuit separation.
6. Relays: The system shall utilize normally open control relays, that are rated to 20A at 120/277 VAC. The relays shall be mechanically latching, and shall permit individual override and LED configuration of relay status. The relays shall be rated for 10 million operations.
7. System Controller: The system controller shall consist of an integral touchscreen that provides access to the main programming features. The touchscreen shall permit the user to manually command any or all relays individually.
 - a. Provide master on/off control of a relay group while still allowing individual relays to be overridden by their local switch.
 - b. The control system shall permit up to 32 dry contact inputs for override purposes. Momentary 3 wire or 2 wire (toggle) inputs shall be supported. Any input shall be software linked to any number or relays.
 - c. The controller shall provide timers for each override. Each override timer shall be capable of 0-999 minutes. Software shall enable or disable overrides based on priorities, masks or time of day scheduling.
 - d. The controller shall accept either dry contact or analog ambient light sensors. The controller shall provide power for the sensor. Sensors shall provide for outdoor, indoor or skylight applications and issue a command to the controller once the threshold is reached.
 - e. Each control panel shall incorporate diagnostic aids for confirmation of

proper operation. The control panel shall employ both a backlit touchscreen and LED's to indicate:

- i. Power
 - ii. System OK
 - iii. Network communications
 - iv. System clock and date
 - v. Programming confirmation
 - vi. Control panel subnet network communications
8. Switches: The lighting controller shall support digitally addressable LED annunciated switches. Provide low voltage push-button switches in up to 6 button configurations. Provide factory engraved labeling for individual push-buttons. Provide in color to match wiring devices and coverplate to match devices and plates in Wiring Devices (Section 26 2726).
9. Wiring:
- a. Provide CAT5 cable between switches and controller to create a digital switch network.
 - b. Provide CAT5 cable between controller and other controllers via a RS-485 network. The RS-485 network shall support up to 250 controllers with a maximum distance of 4000 feet.
 - c. Programming: Provide a RS-232 (RJ-R Connection) to allow programming through either a local connection or remotely through a modem.
 - d. Provide wiring in conduit located within the walls and non-accessible ceilings. Provide wiring above accessible ceilings in (conduit to system enclosure) to system enclosure.
10. Ceiling Mounted Occupancy Sensors: Sensors shall utilize dual-technology (ultrasonic and infrared technologies) and have the following additional features:
- a. Sensor shall be class 2, low voltage; capable of mounting in the ceiling for maximum coverage.
 - b. Sensor shall have automatic self-adjustment algorithm that adjusts timer and sensitivity settings to maximize performance and minimize energy usage.
 - c. Sensor shall have 360 degree field of view.
 - d. Sensor shall incorporate non-volatile memory such that all settings and parameters are saved in protected memory.
 - e. Sensor shall have time delays from 10 to 30 minutes.
 - f. Sensor shall provide a visual means of indication that motion is being detected via an LED.
 - g. Sensors shall have readily accessible, user adjustable settings for time delay and sensitivity.

PART 3 EXECUTION:

3.1 INSTALLATION OF LIGHTING CONTROL EQUIPMENT:

- A. Install lighting control system components and ancillary equipment as indicated, in accordance with equipment manufacturers written instructions, and with recognized industry practices, to ensure that lighting control equipment complies with requirements.
- B. Comply with Requirements of NEC, and applicable portions of NECA's 'Standard of Installation' pertaining to general electrical installation practices.

- C. Coordinate with other electrical work, including raceways, electrical boxes and fittings, as necessary to interface installation of lighting control equipment work with other work.
- D. Electrical Identification: Refer to Section 26 0553 for requirements.

3.2 FIELD QUALITY CONTROL:

- A. Upon completion of installation and after circuitry has been energized, demonstrate capability and compliance of system with requirements.
- B. Where possible, correct malfunctioning units at site, then retest to demonstrate compliance; otherwise, remove and replace with new units, and proceed with retesting.

3.3 PRODUCT SUPPORT AND SERVICES:

- A. System Start-Up: Provide a factory authorized technician to verify the installation, test the system, and train the owner on proper operation and maintenance of the system. Before requesting start-up services, the installing contractor shall verify that:
 - 1. The control system has been fully installed in accordance with manufacturer's installation instructions.
 - 2. Low voltage wiring for overrides and sensors is completed.
 - 3. Accurate 'as-built' load schedules have been prepared for each lighting control panel.
 - 4. Proper notification of the impending start-up has been provided to the owner's representative.
 - 5. Programming of all switches, relays, groups of shall be completed by factory authorized technician, prior to final and training.
- B. Factory support: Factory telephone support shall be available at no cost to the owner during the warranty period. Factory assistance shall consist of assistance in solving programming or other application issues pertaining to the control equipment. The factory shall provide a toll free number for technical support.

3.4 WARRANTY:

- A. Manufacturer shall provide a one (1) year limited warranty on lighting control system. A ten (10) year limited warranty shall be provided on the lighting control relays.

3.5 RECORD DRAWINGS: Refer to Section 26 0502 for requirements.

3.6 TRAINING

- A. Provide four (4) hours of video taped training in two 2 hour sessions on the operation and use of the lighting control equipment, at job site, at no cost to the Owner.

END OF SECTION

SECTION 31 10 10
PAVEMENT REMOVAL

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Removal of roadway Pavement.
- B. Milling roadway Pavement.
- C. Removal of curb, gutter, sidewalk, Driveway Approach, waterway, or similar flatwork.
- D. Disposal of removed materials.

1.2 RELATED WORK

- A. Demolition of structures and utilities.

1.3 DEFINITIONS

- A. ADA: Americans with Disabilities Act.

PART 2 PRODUCTS Not Used

PART 3 EXECUTION

3.1 PREPARATION

- A. General
 - 1. Coordinate utility locations
 - 2. Preserve all active utilities.
 - 3. Notify neighborhood of day and time of operation.
 - 4. Make sure invert covers are properly installed in storm drain and sanitary sewer systems
 - 5. Mark existing utilities on redline drawings.
- B. Traffic Control: Provide worker and public safety measures
- C. Tree Roots:
 - 1. Avoid or minimize damage to tree roots. Roots provide anchorage, storage of energy, and absorption and conduction of water and mineral elements. Loss of root connection affects health and stability of tree and safety of people and property.
 - 2. Provide certified arborist observation of root cuts larger than 4 inches diameter. Notify owner's representative of such root cut.
- D. Existing Surfaces:
 - 1. Do not damage adjacent concrete surfaces that are not scheduled for removal.

2. Use rubber cleats or Pavement pads when operating backhoes, outriggers, track equipment, or any other equipment on or crossing paved surfaces.
3. Restore paved surfaces that are damaged by removal operations at no additional cost to the OWNER. Match the existing Pavement surface plus 1 inch.

3.2 SAW-CUT PEDESTRIAN TRIP HAZARDS

- A. Make saw cuts 1:8 slope measured to grade.
- B. Eliminate trip hazards across the full width of the hazard.

3.3 SAW-CUT CURB HORIZONTALLY

- A. Saw cut curbs for ADA ramps at 1:12 slope. No trip hazard at gutter flow line.
- B. Saw cut curbs for flares:
 1. 1:4 slope measured to grade, or
 2. 1:12 slope measured horizontally when complying with ADA.

3.4 REMOVE PORTLAND CEMENT CONCRETE

- A. Remove concrete to the nearest expansion joint or vertical saw cut.
- B. Make concrete cuts straight, vertical to the surface, true, full depth.
- C. DO NOT use machine mounted impact hammers.

3.5 REMOVE ASPHALT CONCRETE

- A. Saw cut full depth and remove Pavement.
- B. When asphalt concrete overlays Portland cement concrete Pavements do not use a machine mounted impact hammer.

3.6 MILLING

- A. Machine:
 1. Equipped to prevent air pollution.
 2. Equipped with a system to control slope of mill cut.
- B. Tolerances:
 1. Milling Depth: As indicated plus or minus 10 percent not uniformly high or uniformly low.
 2. Striation Texture: Uniform, discontinuous, longitudinal, 3/16 inch deep maximum, 3/4 inch center to center.
 3. Smoothness: Plus or minus 5/16 inch in 25 feet.
 4. Cross Slope: Plus or minus 1/4 inch in 10 feet.
- C. Performance:
 1. Lower utility frames, covers, and other Street Fixtures.
 2. Mill surfaces to the depth shown on the Drawings or indicated by OWNER'S REPRESENTATIVE. Do not disfigure adjacent work or existing surface

improvements.

3. If milling exposes smooth underlying Pavement surfaces, mill the smooth surfaces to make them rough.
4. Mill off material if it ponds water or if it has been damaged by water.
5. Where vehicles or pedestrians must pass over milled edges provide safe temporary ramps suitable to speed of user vehicles (or suitable for wheel chair user needs).
6. Remove excess material and clean milled surfaces.
7. If work equipment is removed from the milling site and milled surface awaits further work, provide appropriate traffic control and cleaning.

3.7 GRINDING

- A. Machine:
 1. Cutting head 36 inches wide minimum.
 2. 50 to 60 diamond blades per foot of head.
- B. Preparation:
 1. Control traffic.
 2. Provide water truck, waste truck, and other support machinery.
 3. Mark areas to be ground.

END OF SECTION

**SECTION 31 23 26
COMPACTION**

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Compaction of granular fill materials.

1.2 REFERENCES

- A. ASTM D 698: Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³ (600 kN- m/m³)).
- B. ASTM D 1557: Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³ (2,700 kN-m/m³))
- C. ASTM D 2216: Standard Test Method for Laboratory Determination of Water (Moisture) Content of Soil and Rock.
- D. ASTM D 2922: Standard Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).
- E. ASTM D 3017: Standard Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth).
- F. ASTM D 3282: Standard Practice for Classification of Soils and Soil- Aggregate Mixtures for Highway Construction Purposes.
- G. ASTM D 3740: Standard Practice for Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction.

1.3 DEFINITIONS

- A. A-1 Soil: Defined in ASTM D 3282.
- B. Modified Proctor Density: The maximum laboratory density, as defined in and determined by ASTM D 1557 using procedure A, B or C as applicable.
- C. Relative Density (or Relative Compaction): The ratio of field dry density to the maximum laboratory density expressed as a percentage.
- D. Standard Proctor Density: The maximum laboratory density, as defined in and determined by ASTM D 698 using procedure A, B or C as applicable.

1.4 QUALITY ASSURANCE

- A. Use a laboratory that follows and complies with ASTM D 3740.

PART 2 PRODUCTS Not Used

PART 3 EXECUTION

3.1 COMPACTION

- A. Moisten or dewater backfill material to obtain optimum moisture for compaction.

- B. Correct deficient compaction conditions. Replace or repair materials and damaged facilities.
- C. When no density compactive effort is specified, compact the entire area to eliminate unstable zones.

3.2 FIELD QUALITY CONTROL

- A. Testing: Perform control testing of materials. Perform additional testing at no additional cost to OWNER.
 - 1. Because of changes in source of materials or proportions requested by CONTRACTOR.
 - 2. Because of Failure of materials to meet specification requirements.
 - 3. For other testing services needed or required by CONTRACTOR.
- B. Report: For each material tested, record the following.
 - 1. Vertical and horizontal location of the test.
 - 2. Optimum laboratory moisture content.
 - 3. Field moisture content.
 - 4. Maximum laboratory dry density.
 - 5. Field density.
 - 6. Percent compaction results.
 - 7. Certification of test results by testing agency.
- C. Optimum Soil Density: Use ASTM D 2216 and the following industry standards.
 - 1. For A-1 Soils: Use test method C of ASTM D 1557 (Modified Proctor)
 - 2. For All Other Soils: Use test method C of ASTM D 698 (Standard Proctor).
- D. Field Density:
 - 1. Use ASTM D 3017 and test method C of ASTM D 2922 for shallow depth nuclear testing.
 - 2. No density determinations are required on any material containing more than 65 percent material retained on the number 10 sieve or more than 60 percent material retained on the number 4 sieve. In lieu of reporting densities in such cases, report the sieve analysis to document the material type.

END OF SECTION

SECTION 32 11 23
CRUSHED AGGREGATE BASE

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Treated or untreated base course requirements.

1.2 REFERENCES

- A. ASTM C 29: Standard Test Method for Unit Weight and Voids in Aggregate.
- B. ASTM C 131: Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.
- C. ASTM C 136: Standard Method for Sieve Analysis of Fine and Coarse Aggregates.
- D. ASTM D 75: Standard Practice for Sampling Aggregates.
- E. ASTM D 448: Standard Classification for Sizes of Aggregate for Road and Bridge Construction.
- F. ASTM D 1883: Standard Test Method for CBR (California Bearing Ratio) of Laboratory-Compacted Soils.
- G. ASTM D 2419: Standard Test Method for Sand Equivalent Value of Soils and Fine Aggregate.
- H. ASTM D 3665: Standard Practice for Random Sampling of Construction Materials.
- I. ASTM D 3740: Standard Recommended Practice for Evaluation of Agencies Engaged in Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction.
- J. ASTM D 4318: Standard Test Method for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.
- K. ASTM D 5821: Standard Test Method for Determining the percentage of Fractured Particles in Coarse Aggregate.

1.3 DEFINITIONS

- A. Aggregate Grading Band: Allowable deviation from Target Gradation Curve based upon the number of gradation tests in a Lot. It is possible that gradation for any sieve may lie outside of its respective Master Grading Band limits.
- B. Master Grading Band: Gradation limits allowed for various sieve sizes ranging from the maximum size sieve to the No. 200 sieve.
- C. Mean of Deviations: The sum of the absolute values of the variance between each screen target value and each measured value divided by the number of tests in the Lot.
- E. Target Gradation Curve: A smooth locus of points within the limits of the Master Grading Band.

1.4 SUBMITTALS

- A. Name of Supplier and aggregate source.
- B. Target Gradation Curve.

1.5 QUALITY ASSURANCE

- A. Use a laboratory that follows and complies with ASTM D 3740.

1.6 ACCEPTANCE

- A. Treated or Untreated Base Course: Lot size is one day’s production. Sub-lot size is 500 tons.
 - 1. OWNER’S REPRESENTATIVE is not obligated to accept changes in Target after any material is delivered to site.
 - 2. Lot is acceptable if gradation test deviations are within pay factor 1.00 limits. At OWNER’S REPRESENTATIVE’S discretion, a Lot with a sub-lot test deviation greater than pay factor 0.70 limits may stay in place at 50 percent cost.

Table 1- Pay Factors for Price Determination						
Criteria	Pay Factor	Mean of Deviations of Acceptance Tests From the Target Gradation Curve Expressed in Percentage Points				
		1 Sample	2 Samples	3 Sample	4 Sample	5 or More Samples
1/2" Sieve	1.00	0 – 15	0.0 – 12.1	0.0 – 10.8	0.0 – 10.0	0.0 – 9.5
	0.95	16 – 17	12.2 – 13.9	10.9 – 12.4	10.1 – 11.5	9.6 – 11.
	0.90	18 – 19	14.0 – 15.1	12.5 – 13.5	11.6 – 12.5	11.1 – 11.9
	0.80	20 – 21	15.2 – 17.2	13.6 – 15.3	12.6 – 14.2	12. – 13.5
	0.70	22 – 23	17.3 – 18.8	15.4 – 16.7	14.3 – 15.5	13.6 – 14.7
3/8" Sieve	1.00	0 – 15	0.0 – 11.5	0.0 – 9.8	0.0 – 8.8	0.0 – 8.0
	0.95	16 – 17	11.6 – 13.2	9.9 – 11.3	8.9 – 10.1	8.1 – 9.2
	0.90	18 – 19	13.3 – 14.4	11.4 – 12.3	10.2 – 11	9.3 – 10.0
	0.80	20 – 21	14.5 – 16.3	12.4 – 13.9	11.1 – 12.5	10.1 – 22.4
	0.70	22 – 23	16.4 – 17.9	14.0 – 15.2	12.6 – 13.6	11.5 – 12.4
No. 4 Sieve	1.00	0 – 14	0.0 – 10.5	0.0 – 8.8	0.0 – 7.8	0.0 – 7.0
	0.95	15 – 17	10.6 – 12.1	8.9 – 10.1	7.9 – 9.0	7.1 – 8.0
	0.90	18	12.2 – 13.1	10.2 – 11	9.1 – 9.8	8.1 – 8.7
	0.80	19 – 20	13.2 – 14.9	11.1 – 12.5	9.9 – 11.1	8.8 – 10.0
	0.70	21 – 22	15.0 – 16.3	12.6 – 13.6	11.2 – 12.1	10.1 – 10.8

Table 1- Pay Factors for Price Determination						
Criteria	Pay Factor	Mean of Deviations of Acceptance Tests From the Target Gradation Curve Expressed in Percentage Points				
		1 Sample	2 Samples	3 Sample	4 Sample	5 or More Samples
No. 16 Sieve	1.00	0 – 11	0.0 – 8.2	0.0 – 6.9	0.0 – 6.2	0.0 – 5.6
	0.95	12 – 13	8.3 – 9.4	7.0 – 7.9	6.3 – 7.1	5.7 – 6.4
	0.90	14	9.5 – 10.3	8.0 – 8.6	7.2 – 7.8	6.5 – 7.0
	0.80	15 – 16	10.4 – 11.6	8.7 – 9.8	7.9 – 8.8	7.1 – 8.0
	0.70	17	11.7 – 12.7	9.9 - 10.7	8.9 – 9.6	8.1 – 8.7
No. 50 Sieve	1.00	0 – 9	0.0 – 7.0	0.0 – 6.1	0.0 – 5.5	0.0 – 5.2
	0.95	10	7.1 – 8.0	6.2 – 7.0	5.6 – 6.3	5.3 – 6.0
	0.90	11	8.1 – 8.8	7.1 – 7.6	6.4 – 6.9	6.1 – 6.5
	0.80	12 – 13	8.9 – 10.0	7.7 – 8.7	7.0 – 7.8	6.6 – 7.4
	0.70	14	10.1 - 10.9	8.8 – 9.5	7.9 – 8.5	7.5 – 8.1
No. 200 Sieve	1.00	0 – 4.5	0.0 – 3.4	0.0 – 2.9	0.0 – 2.5	0.0 – 2.3
	0.95	4.6 – 5.2	3.5 – 3.9	3.0 – 3.3	2.6 – 2.9	2.4 – 2.6
	0.90	5.3 – 5.6	4.0 – 4.3	3.4 – 3.6	3.0 – 3.1	2.7 – 2.9
	0.80	5.7 – 6.4	4.4 – 4.9	3.7 – 4.1	3.2 – 3.6	3.0 – 3.3
	0.70	6.5 – 7.0	4.9 – 5.3	4.2 – 4.5	3.7 – 3.9	3.5 – 3.6

3. Suitability of Source: Meet Table 2 properties. A reduction in aggregate class will be accepted providing any costs for difference in excavation, backfill, and alternate design for CBR does not increase the Contract Price.

PART 2 PRODUCTS

2.1 UNTREATED BASE COURSE

- A. Material: Crushed rock, gravel, sand or other high quality mineral particle, or combination.

Table 2 – Properties					
Physical Property	Units	Aggregate Class			ASTM Test
		A	B	C	

Dry Rodded Unit Weight, min.	lb/ft ³	75			C 29
Liquid Limit, max.		25			D 4318
Plastic Index, max.		0	0	6	D 4318
Sand Equivalent, min.	percent	35			D 2419
Wear (hardness), max.	percent	50			C 131
Gradation		Table 3			C 136
Two Fractured Faces, min.	percent	90	50	50	D 5821
CBR, min.	percent	70	55	40	D 1883
NOTES					
(a) Liquid limit, plastic limit, sand equivalent: Passing No. 40 sieve.					
(b) Wear: Retained on No. 8 sieve.					
(c) CBR: Use a 10 lb surcharge measured at 0.20 inch penetration at 95 percent of modified Proctor.					
(d) Faces: Retained on No. 4 sieve.					

Table 3 – Gradation			
US Sieve Size	Master Grading Bands Limits		
	Grade 1-1/2	Grade 1	Grade 3/4
2"	–	–	–
1-1/2"	100	–	–
1"	–	100	–
3/4 "	81 – 91	–	100
1/2 "	67 – 77	79 – 91	–
3/8"	–	–	78 – 92
No. 4	43 – 53	49 – 61	55 – 67
No. 16	23 – 29	27 – 35	28 – 38
No. 200	6 – 10	7 – 11	7 – 11

2.2 ASPHALT TREATED BASE COURSE

- A. Meet requirements of this Section Article 2.1 and the following.
1. Sand equivalent and fractured face measured after asphalt residue is burned off.
 2. Plasticity and wear requirements apply to virgin aggregate portion only.
 3. Allowable asphalt content is controlled by CBR. B. If aggregate contains RAP.

4. Screen crushed RAP to remove debris.
5. Mechanically blend virgin and RAP aggregates. Do not use windrows for blending.

2.4 SOURCE QUALITY CONTROL

- A. Sample, ASTM D 75 on a random basis, ASTM D 3665.
- B. Reject crushed aggregate base products that do not meet requirements of this Section.

PART 3 EXECUTION

3.1 FIELD QUALITY CONTROL

- A. Remove any product found defective after installation and install acceptable product at no additional cost to the OWNER.

END OF SECTION

SECTION 32 13 13
CONCRETE PAVING

PART 1 GENERAL

1.1 SUMMARY

- A. The work to be performed under this section shall consist of furnishing all labor, materials, and equipment to form, pour, finish, and cure concrete walks, curbs and gutters, flat work, retaining walls, footings, mowstrips, and other concrete as per the plans and specifications. The work may include but not be limited to excavation, forming, pouring, finishing, jointing, curing, protecting, removing forms, restoring earth or sod around the edges, and guaranteeing the work.

PART 2 MATERIALS

2.1 CEMENT

- A. The cement shall be Portland Type II cement meeting current AASHTO Designation M-85 Specifications. The supplier and mix of concrete shall not be changed during the complete concrete phase of the project. All concrete shall be Class AA (AE) Type II. A 6.5 bag cement mix shall be used with a slump of 4-inch maximum. The concrete shall have a 6% air entrainment with a plus or minus variable of 1%. All air entraining agents shall conform to the requirements of AASHTO Designation ASTM260. The 28 day compressive strength shall be 4,000 P.S.I.

2.2 AGGREGATE

- A. The aggregate shall be well graded from fine to coarse. The fine aggregate shall be uniformly graded meeting the requirements of AASHTO Designation ASTM-C33. The coarse aggregate shall be 1" to #4 conforming to the requirements of AASHTO Designation M-92.

2.3 WATER

- A. The maximum water/cement ratio shall be 5 gallons per sack. All water used in mixing the concrete shall be clean and free of oil, alkali, organic matter, or other deleterious substances.

2.4 FILL AND BACK FILL

- A. The entire area beneath the concrete shall be excavated to the proper depth to allow for the specified thickness of untreated base course or the area shall be compacted to 95% as measured by a Procter test.
- B. All excavated material shall be either re-used on the site or hauled away as specified on the plans.
- C. Where untreated base course (free drainage material) is specified, the contractor shall import the required quantities from a local supplier. The contractor shall submit samples of the material to be used to the Inspector 3 days prior to use on the site. The untreated base course shall meet the requirements of Section 301 of the most recent edition of State of Utah Standard Specifications for Road and Bridge Construction. This refers to AASHTO Designations I-90, T-27, T-11, T-19 for mineral aggregate requirements. The gradation shall be for 3/4 or 1" maximum passing through the sieves in the percentages and with the tolerances shown on page 108, section 301.03 of the State Standard Specifications referred to above. (Base material shall be installed 12" wider than

concrete walk width, both sides.)

2.5 FORMS

- A. Forms shall be of suitable materials such as wood, plastic, metal, or combinations thereof. Forms shall be of the shape and dimensions shown on the plans and true to line and grades specified. All forms shall be free from knotholes, loose knots, cracks, splints, warps, or other defects affecting the strength or appearance of the finished product. All forms shall be free of bulges and warping. They shall be cleaned thoroughly before they are used on this project. There shall be no split holes, bolts, or nuts on the final concrete surface when the forms are removed.
- B. If at any stage of work, during or after placing the concrete, the forms sag or bulge the affected concrete shall be removed. Exceptions may be taken by the Inspector if the concrete is going to be covered with earth.

PART 3 EXECUTION

3.1 Supervisor/Foreman must have A.C.I. Training

3.2 All debris shall be removed from the inside of the forms prior to placement of any concrete. Placement operations may be postponed when in the opinion of the Inspector rainfall, excessive wind, low temperatures, wet spots, or the base is not sufficiently compacted. The Contractor shall take all necessary measures to protect the concrete after placement to prevent rain, graffiti, or other damage to the surface.

- A. Concrete mix trucks shall be routed to each pour over areas where the least possible damage will occur to the existing sprinkler irrigation system, utilities, lawn, or plant materials. The Contractor shall be responsible for repair of damage done by the concrete mix trucks and any other vehicles involved in these operations.
- B. The concrete shall be spread in horizontal layers insofar as practical and only of the thickness that can be satisfactorily hand worked or compacted with vibrators and other such equipment.
- C. The concrete shall be deposited as near the final resting place as possible so as to minimize working it and to prevent separating the ingredients.
- D. The concrete slope shall be 1" per 10' or 1% in the direction of the natural grade or as indicated on the plans. Flat work will have not more than a 1/8" difference in a 20' radius.

3.3 SAMPLING AND TESTING

- A. All concrete shall be sampled and tested in accordance with AASHTO Designation T-141 for air entrainment, slump, and strength. The Contractor shall have the test made at the appropriate times and places. All test results shall be sent to the project Landscape Architect or project Engineer by the testing laboratory at the Contractors expense.
 - 1. Slump Test: Slump tests shall be made in accordance with AASHTO Designation T-119. If a slump test does not meet the specifications, a second slump test shall be made immediately on the same load. The load will be accepted or rejected from the site by the inspector depending on the results of the second test.
 - 2. Air Entrainment: Air entrainment tests shall be made in accordance with AASHTO Designations T-152. If an air entrainment test does not meet the specification, a second test shall be taken immediately on the same load. The load will be accepted or rejected from the site by the Inspector depending on the results of the second test.
 - 3. Compression Tests: Making, curing, and determining compressive strength of

concrete cylinders shall be in accordance with AASHTO Designation T-22 and T23. Compressive strength shall be determined from "Strength Tests" in which the average of three standard cylinders shall constitute one strength test. Cylinders for strength tests shall be taken by the testing laboratory, which will also inspect the batching procedure to ascertain compliance with the mix design.

If any individual strength test is below 4,000 PSI, the concrete may be accepted by the project Landscape Architect or Engineer after reviewing the circumstances. The price the county shall pay for the concrete will be reduced in accordance with the following schedule:

PSI Below Specified	Pay Factor
<u>Strength Specification</u>	<u>(Percent)</u>
1-100	98
101-200	94
200-300	88
301-400	80

4. Proctor Tests: Compaction of the natural or imported base shall be tested in accordance with AASHTO Designation T-191. All testing procedures and any additional tests which may be required shall follow those specified in the most recent edition of State of Utah Standard Specifications for Road and Bridge Construction.

- B. All costs incurred in sampling and re-sampling, testing and retesting shall be paid by the Contractor.
- C. All batching and mixing procedures shall be followed based upon the Salt Lake County Public Works Specifications as administered by the Salt Lake County Public Works Department as related to the most recent edition of the State of Utah Standard Specifications for Road and Bridge Construction

3.4 FINISH

- A. Unless specified on the plans, the finish for all concrete flat work shall be a non-skid surface by medium brooming.

3.5 JOINTING

- A. Joints shall be placed in the concrete by the Contractor so as to control and minimize cracking. Normally the Contractor shall follow the jointing patterns shown on the plans or submit a drawing showing recommended changes for approval by the project Landscape Architect or Engineer.
 - 1. Control Joints: Shall be every 10 feet in curb and gutter. Sidewalk joints shall be in linear feet equal to the width of the walk (for example, a 6-foot wide walk shall be scored every 6 linear feet.) Slab work shall be jointed a maximum in feet of 2 -1/2 times the thickness of the concrete in inches (for example, the joints would be less than 15 feet apart for a slab 6 inches thick) and never more than 15 feet apart - for a 4" slab, between 8 - 10 feet.
 - a. The control joints shall be a depth of 1/4 the thickness of the slab. Control joints shall be made before shrinkage cracking occurs. All control joints shall be continuous across the concrete except where

interrupted by a post, wall, joint, or other obstacle.

- b. Control joints shall be saw cut (within 24 hours of pour), filled with an exterior weather sealant, and then a one part polyurethane sealant such as Chem-Calks 900. They may be hand formed with a deep cut wand tool with 1/4 radius round edges.
2. Construction Joints: Shall be created longitudinally by the edges of paving or transversely at the end of each day's work. A key way shall be formed by fastening a key of wood, plastic, or PVC to the form of the first slab. The thickness of the key way shall be 1/5 of the thickness of the slab. The edges shall be rounded 1/4" radius, never on slabs less than 6" thick. Use a release agent on wood formed key ways and 50' or less on walkways.
3. Isolation Joints: Shall be created at junctions of new and existing pavement, at buildings, or other abutting objects. A 1/2" expansion joint material (full depth) shall be placed against the existing object to prevent bonding.

3.6 WINTER CONCRETE

- A. When outside temperatures reach 35 degrees Fahrenheit, a 7-1/2 bag mix shall be used; heated water shall be used in the concrete mix. Heaters shall be used to heat the aggregate to a temperature of 70-150 degrees Fahrenheit. The aggregates shall be uniformly heated and the development of "hot spots" shall be avoided. The temperature of the mixed concrete shall be 60-90 degrees Fahrenheit. A straw blanket shall be used on all surfaces. Concrete shall not be poured on frozen ground and shall meet A.C.I. 305 and 306 requirements for hot and cold weather precautions. Concrete temperature must be maintained at 50 degrees Fahrenheit or greater but never more than 90 degrees Fahrenheit for 7 days.

3.7 CARE AND CURING

- A. All concrete shall be cured for a minimum of 7 days before heavy loads may be placed upon it. Care shall be taken by the supplier and the contractor to prevent too rapid curing and the improper aging of the concrete. Materials such as burlap mats, hay, straw, polyethylene, and water shall be used if necessary.
- B. After pouring and during the curing process, the contractor shall see that no initials or other unnecessary marks are made into the surface. The Contractor shall replace any section containing permanent marks at the completion of the project. Prior to that time, the Contractor may grind the surface or take measures to erase any permanent marks in a section if approved by the Inspector or project Landscape Architect (Engineer).

3.8 FORM REMOVAL

- A. After the concrete is cured, all forms, stakes, and fastening materials shall be removed from the concrete. Care shall be taken to protect the edges from chipping and to prevent damage to the concrete during removal.
- B. All forming materials shall be taken from the site as soon as possible after removal. The area taken up by the forms shall be filled with approved backfill, if needed, and compacted so that top soil shall be placed on top to meet finished grade. If the area is in existing lawn, the sod shall be removed back from the edges of the concrete the standard width of new commercial sod. Then new commercial sod shall be laid full width along the edges of the new concrete until all areas are repaired. The finish grade against the concrete shall be 1 to 1-1/2" below the top of the concrete for sod, 1" for seed.

3.9 CLEAN-UP

- A. Upon completion of the concrete work, the entire affected area shall be cleaned up by the

Contractor. All wood, forms, stakes, rocks, sod, and other extraneous material shall be removed from the premises.

3.10 GUARANTEE AND REPLACEMENT

- A. The Contractor shall guarantee all concrete materials, labor, and workmanship for 1 year following final approval of the contract as per the general County Specifications. Cracks in the concrete shall be routed out and filled with exterior weather sealant.

3.11 METHOD OF MEASUREMENT AND PAYMENT (LUMP SUM)

- A. The concrete work shall be measured either by the square foot or included as part of another item such as footings for a fence. The individual concrete work items shall be specified on the bidding schedule with the cost listed as lump sum or unit price. For example, a 6' sidewalk shall be measured as a walk 6' wide in units of 1' long. The unit price bid by the Contractor and used for payment shall include all equipment, labor, and materials to complete each square foot of sidewalk. Curb and gutter shall be measured and paid by the linear foot.
- B. Final payment shall be made by the actual units completed as described by the plans and specifications at the price shown on the bidding schedule.

END OF SECTION

SECTION 32 84 00

UNDERGROUND IRRIGATION SYSTEMS

PART 1 – GENERAL

1.1 SCOPE OF WORK

- A. The work to be performed under this Section shall consist of furnishing all labor and materials necessary to construct a complete working and tested automatic sprinkler irrigation system as per all drawings and specifications, providing full coverage of all planting areas on the site.
- B. All landscape and hardscape areas disturbed shall be restored to original or better condition.
- C. The Contractor shall operate, maintain until acceptance, and guarantee the new system until all lawn and plants planted on this project have become established and have been approved by the Owner's Authorized Representative (Hereafter listed as OAR).

1.2 SYSTEM DESCRIPTION

- A. Design of irrigation components: Locations of irrigation components on Construction Drawings may be approximate. Piping, sleeving and/or other components shown on Construction drawings may be shown schematically for graphic clarity and demonstration of component groupings and separations. All Irrigation components shall be placed in landscaped areas, with the exception of pipe and wire in sleeving under hardscapes.
- B. Construction requirements: Actual placement may vary as required to achieve a minimum of 100% coverage without overspray onto hardscape, buildings or other features.
- C. Layout of Irrigation Components: During layout and staking, consult with OAR to verify proper placement of irrigation components and to provide Contractor recommendations for changes, where revisions may be advisable. Small or minor adjustments to system layout are permissible to avoid existing field obstructions such as utility boxes or street light poles. Contractor shall place remote control valves in groups as practical to economize on quantity of valve clusters. Quick coupler valves shall be placed with valve groups as shown on plans.

1.3 DEFINITIONS

- A. Water Supply - Piping and components furnished and installed to provide irrigation water to the Project. Including but not limited to nipples, spools, shut off valves, corporation stop valves, water meters, pressure regulation valves, and piping upstream of (or prior to) the Point of Connection.
- B. Point of Connection: Location where the Contractor shall tie into the water supply. May require nipples, spools, isolation valves, meter, back flow device, flow sensor, or stop & waste valve for landscape irrigation needs and use.
- C. Main line piping: Pressurized piping downstream of the Point of Connection to provide water to remote control valves and quick couplers. Normally under constant pressure.
- D. Lateral line piping: Circuit piping downstream of remote control valves to provide water to sprinkler heads, drip systems or bubblers.
- E. OAR: Owner's Authorized Representative.

1.4 REFERENCES

- A. The following documents or standards will apply to the work of this Section:
 - 1. ASTM – American Society for Testing and Materials

2. IA – The Irrigation Association: Main BMP Document.
3. ASIC – American Society of Irrigation Consultants: ASIC Grounding Guideline.

1.5 CONTRACTOR QUALIFICATIONS:

- A. Contractor shall provide document or resume including at least the following items:
 1. That Contractor has been installing sprinklers on commercial projects for ten previous consecutive years.
 2. Contractor is licensed to perform landscape construction in the State of Utah.
 3. Contractor is bondable for the work to be performed.
 4. References of five projects of similar size and scope completed within the last ten years. Three of the projects listed shall be local.
 5. Project On-site Foreman or Supervisor has at least five consecutive years of commercial irrigation Installation experience.
 - a. Project Foreman shall be a current Certified Irrigation Contractor in good standing as set forth by the Irrigation Association.
 - b. Project Foreman shall be on Project site 75% of each working day.
 6. Provide evidence that Contractor currently employs workers in sufficient quantities to complete Project within time limits that are established by the Contract.
 7. Provide list of employees to be assigned to this Project and their irrigation installation experience.
 8. The contractor shall have successfully installed high density polyethylene pipe (HDPE) in irrigation projects.
- B. Certifications: All General laborers or workers on the Project shall be previously trained and familiar with sprinkler installation, and have a minimum of one-year experience. Those workers performing tasks related to PVC pipe and electrical components shall have certificates designated below:
 1. Certified Irrigation Contractor
 2. All workers engaged in handling, assembling and gluing of PVC pipe shall carry on Project site a Certificate of Training from the IPS factory representative authorizing said worker to prime and glue PVC pipe. (Contact Bill Godwin, G & S Sales, 801-972-0659).
 3. All workers engaged in the handling and installation of buried power wire, remote control valve wire, wire connectors, controllers and grounding equipment shall carry on Project site a Certificate of Training from Paige Wire factory representative authorizing said worker to install wire, wire connectors and grounding equipment. (Contact Vince Nolletti, Vice President Irrigation Operations, Paige Electric Co., LP, 559-431-2346).
 4. All Workers engaged in the installation of irrigation pipe which is assembled using joint restraint fittings, shall carry on project site; a Certificate of Training from authorized representative of Ductile Iron Fitting Manufacturer, (HARCO, Leemco, or approved equal) indicating:
 - a. Contractor firm has been adequately trained in installation of joint restraints to replace thrust blocking.
 - b. Authorizing said worker to install Ductile Iron fittings, joint restraints, isolation line valves, manifold isolation valves.
 5. **Documents verifying Certified Irrigation Contractor, PVC Pipe Certification, HDPE Pipe Certificatin, Electrical Component Certification, and Joint Restraint Systems shall be provided to OAR at least 30 days in advance of any irrigation installation on project site.**

1.6 SUBMITTALS

- A. Materials: At least thirty (30) days prior to ordering of any materials, the Contractor shall provide manufacturer catalog cut sheet and current printed specifications for each element or component of the irrigation system.
1. Submittals shall be in electronic format, on DVD or CD, as Adobe PDF documents.
 2. Provide three copies of submittals to OAR. No material shall be ordered, delivered or any work preceded in the field until the required submittals have been reviewed in its entirety and stamped approved.
 3. Delivered material shall match the approved samples.
 4. Substitutions: The Contractor shall use only materials and equipment that matches existing materials and equipment that are being replaced. No substitutions of materials will be approved on the sprinkler irrigation system!
- B. Operation and Maintenance Manual: At least thirty (30) days prior to final inspection, the Contractor shall provide Operation and Maintenance manual to OAR, in Adobe PDF format, containing:
1. Manufacturer catalog cut sheet and current printed specifications for each element or component of the irrigation system.
 2. Parts list for each operating element of the system.
 3. Manufacturer printed literature on operation and maintenance of operating elements of the system.
 4. Section listing instructions for overall system operation and maintenance. Include directions for Spring Start-up and Winterization.
- D. Owner's instruction: After system is installed, inspected and approved, instruct County in complete operation and maintenance procedures. Coordinate instruction with references to previously submitted Operation and Maintenance Manual.
1. Contractor shall provide adequate notice to Owner for scheduling.
- E. Materials to be furnished: The following items shall be supplied as part of this contract and shall be turned over to Owner at Final Inspection.
1. Two (2) special tools / wrenches for disassembly and adjustment of each type of irrigation equipment/heads installed that require such special tools/wrenches.
 2. Two keys for each type of automatic controller.
 3. One valve box cover key.
- F. Project Record Copy:
1. Maintain at project site one copy of all project documents clearly marked "Project Record Copy". Mark any deviation in material installation on Construction drawings. Maintain and update drawing at least weekly. Project Record Copy to be available to OAR on demand.
 2. Completed Project As-built Drawings:
 - a. Prior to final inspection, prepare and submit to OAR accurate as-built drawings.
 - b. Show detail and dimension changes made during installation. Show significant details and dimensions that were not shown in original Contract Documents.
 - c. Field dimension locations of sleeving, points of connection, main line piping, wiring runs not contained in main line pipe trenches, valves and valve boxes, quick coupler valves, color of hot and spare wires – splice boxes, and the size of all underground piping, valves, and drains.
 - 1). Dimensions are to be taken from permanent constructed surfaces, features or finished edges located at or above finished grade.
 3. The Contractor shall provide a GPS coordinate location for each of the following items: point of connection, water meter, backflow device, isolation valves, control valves, gate valves, filters, quick coupling valves, controller, flow meters, manual drain valves, and any other pertinent component of the irrigation system. Provide coordinates on as built drawings and recorded on a CD in WR format.

- G. Controller map: Upon completion of system, place in each controller, a color-coded copy of the area that controller services; indicating zone number, type of plant material and location on project that zone services. Laminate map with heat shrink clear plastic.

1.7 INSPECTIONS

- A. Inspections will be required for:
1. Hydrostatic test of irrigation main line.
 2. Continuity test of spare wires from controller to last valve with OAR.
 3. All piping system layout before backfilling.
 5. Coverage test.
 6. Final inspection / Start of Maintenance.
 7. Final inspection.
- B. Inspection Requests: Contractor shall notify the OAR a minimum of 48 hours (two working days) in advance for all inspection.
- C. Closing in Un-inspected Work: No work of this section shall be covered up or enclosed until it has been inspected, tested and approved by OAR.

1.8 WORKMANSHIP AND MATERIALS

- A. It is the intent of this specification that all material herein specified and shown on the construction documents shall be of the highest quality available and meeting the requirements specified.
- B. All work shall be performed in accordance with the best standards of practice relating to the trade.

1.9 DELIVERY—STORAGE—HANDLING

- A. During delivery, installation and storage of materials for Project, all materials shall be protected from contamination, damage, vandalism and prolonged exposure to sunlight. All material stored at Project site shall be neatly organized in a compact arrangement and storage shall not disrupt Project Owner or other trades on Project site. All material to be installed shall be handled by Contractor with care to avoid breakage or damage. Damaged materials attributed to Contractor shall be replaced with new at Contractor's expense.

1.10 WARRANTY

- A. Contractor shall provide one year Warranty. Warranty shall cover all materials, workmanship and labor. Warranty shall include filling and or repairing depressions or replacing turf or other plantings due to settlement of irrigation trenches or irrigation system elements. Valve boxes, sprinklers or other components settled from original finish grade shall be restored to proper grade. Irrigation system shall have been adjusted to provide proper, adequate coverage of irrigated areas.

1.11 MAINTENANCE

- A. Provide the following services:
1. Check coverage and adjust as necessary.

PART 2 - PRODUCTS

2.1 GENERAL

- A. Any discrepancies between existing site conditions and those indicated on the plans shall be called to the attention of the OAR, prior to continuance of the project.

- B. If there is an existing sprinkler irrigation system on the site, the Contractor shall remove any lines being abandoned, and cap or plug the ends of lines remaining in service with proper fittings and joint restraint systems. The Contractor shall remove or relocate existing heads and/or connect new lines to existing lines, as indicated on the plans. Any existing heads or other hardware so removed, which are not to be relocated, will be returned directly to the Salt Lake County Parks Department.
- C. Any existing head, valve, valve marker, valve box, or other existing equipment located where there will be a grade or surface material change, shall be adjusted up or down to its proper position in relation to the new finished grade, at no additional cost to the owner, unless the plans show it to be relocated.

2.2 PIPE AND FITTINGS

- A. General: Polyvinyl Chloride Schedule 40 Pipe and Fittings. This specification covers requirements for Schedule 40 PVC pipe and fittings made from Type 1 Polyvinyl Chloride.
 - 1. Materials: Pipe and fittings shall be manufactured from a PVC compound which meets the requirements of Type 1, Grade 1 Polyvinyl Chloride, as outlined in ASTM D-1684. A Type 1, Grade 1 compound is characterized as having the highest requirements for mechanical properties and chemical resistance.
 - a. PVC Type 1, Grade 1 pipe compound shall have a 2000 P.S.I. design stress at 74 degrees F., which is listed by the Plastic Pipe Institute (PPI). Materials, from which pipe and fittings are manufactured, shall have been tested and approved for conveying potable water by the National Sanitation Foundation Testing Laboratory (NSF).
- B. Pipe: All pipe used on the project for the sprinkler irrigation system shall conform to the requirements of ASTM D-1685. DWV PVC pipe shall not be allowed.
 - 1. All pipe, 3 inches diameter and smaller, shall be schedule 40 PVC.
 - 2. All pipe, 4 inches diameter and larger shall be PVC Class 200 0-ring pipe.
 - 3. 3 inch and larger pipe shall have gasketed ductile iron, HARCO, Leemco or approved equal (**hereafter referred to only as Ductile Iron**) type fittings with transition gaskets if needed, at all changes of direction tees, ells, caps, etc.
 - 4. Ductile Iron type fittings may have bolted end flanges and be wrapped in plastic. Bolts and nuts to be greased prior to assembly. Contractor exercising this option shall submit for approval to deviate from shown plan details.
 - 5. No bends other than very gradual in pipe shall be permitted. The Contractor shall use Ductile Iron elbow fittings of 90 and 45 degrees as the situations demand.
 - 6. HDPE Pipe shall be manufactured from a PE 3408/3608 resin listed with the Plastic Pipe Institute (PPI) as TR-4. The resin material will meet the specifications of ASTM D3350-05 with a cell classification of PE 345464C. The pipe shall contain no recycled compounds except that generated in the manufacturer's own plant from resin of the same specification from the same raw material.
 - a. The supplier of the HDPE pipe and fittings must be capable of supplying both the pipe and fittings.
- C. Fittings:
 - 1. Fittings: All fittings used on the project for the sprinkler irrigation system shall conform to the requirements of ASTM D-2466.
 - a. All solvent weld fittings on PVC lateral lines shall be schedule 40.
 - b. All solvent weld fittings on PVC main lines shall be schedule 80.
 - c. Ductile Iron tees with swivel type connections and integral fitting angle valves shall be used for transition from mainline pipe to manifold construction.
 - d. Any and all Ductile Iron fittings shall include Joint Restraints at each fitting.

- e. All Ductile Iron fittings shall come from a manufacturer offering a 10 year warranty on products and replacement labor costs. Prior to install, Contractor shall provide OAR documentation from the manufacturer shall provide documentation stating the above warranty information, including the labor reimbursement hourly rate.
- f. All Ductile Iron fittings and joint restraints shall have a fusion bonded epoxy coating on interior and exterior of the product surface, average of 10-12mm thickness. Epoxy coating shall conform to the requirements of CSA Z245.20-20 and NSF 61 for water services. Tar/bitumen coating will not be approved.
- g. All bolts used in fittings to be stainless steel.
- h. HDPE pipe fittings
 - 1) Thermal Butt Fusion Fittings - Fittings shall be PE3408/3608 HDPE, Cell Classification of PE 345464C as determined by ASTM D3350-05. Thermal Butt Fusion Fittings shall have a manufacturing standard of ASTM D3261. Molded & fabricated fittings shall have the same pressure rating as the pipe unless otherwise specified on the plans.
 - 2) Flanged and Mechanical Joint Adapters - Flanged and Mechanical Joint Adapters shall be PE 3408/3608 HDPE, Cell Classification of 345464C as determined by ASTM D3350-05. Flanged and Mechanical Joint Adapters shall have a manufacturing standard of ASTM D3261. Fittings shall have the same pressure rating as the pipe unless otherwise specified on the plans.

D. Pipe and Fittings Table:

Size	Mainline Piping	Mainline Fittings	Lateral Piping	Lateral Fittings
1"	SCH 40	SCH 40	SCH 40	SCH 40
1-1/4"	SCH 40	SCH 40	SCH 40	SCH 40
1-1/2"	SCH 40	SCH 40	SCH 40	SCH 40
2"	SCH 40	SCH 80	SCH 40	SCH 80
2-1/2"	SCH 40	SCH 80	SCH 40	SCH 80
3"	SCH 40	Mechanical Joint Restraint System Fittings	SCH 40	Mechanical Joint Restraint System Fittings
4"	PVC Class 200 Gasketed	Mechanical Joint Restraint System Fittings	PVC Class 200 Gasketed	Mechanical Joint Restraint System Fittings
6"	PVC Class 200 Gasketed	Mechanical Joint Restraint System Fittings	PVC Class 200 Gasketed	Mechanical Joint Restraint System Fittings

- E. Pipe Sleeves: Pipe sleeves shall be required under all new concrete or other new paving.
1. The size of the sleeve shall be at least 2 times (2X) (I.D.) larger than the pipes or wires, required for the sprinkler system.
 2. Wires shall be sleeved separately within their own sleeve.
 3. All pipe sleeves shall be PVC Schedule 40 pipe.

2.3 VALVES AND VALVE BOXES

- A. Valves:
1. The Contractor shall provide adequate material for the connection of valves to the system, i.e., adapters, flanges, nuts, bolts, gaskets, etc.
 2. Main line or Isolation Gate Valves: Shall be Gate Valves.
 - a. All mainline valves shall be resilient wedge and conform to AWWA C153 standards.
 - b. Material shall be ductile iron per ASTM A-536, Grade 65-45-12. Epoxy coating on all interior and exterior surfaces shall be fusion bonded epoxy, 12-14 mil thickness. The epoxy coating shall pass 90-Day immersion tests per CSA Z245.20-98. Tar/bitumen coating will not be approved.
 - c. Gate valves shall be available flange X flange models to mechanically connect to fittings or plastic pipe.
 - d. Gate valves shall have flange X push-on adapters with joint restraints, to connect to piping.
 - e. Valve bell end shall be deep bell, gasket and equipped with cast joint restraint clamps to securely fasten to plastic pipe. Restraints shall have blunt cast serrations. Machined threaded restraints will not be allowed.
 - f. Valves shall have a shroud around the 2" operating nut to accept IPS PVC sleeve which provides dirt-free access to actuate the valve.
 - g. All mainline valves shall be manufactured by Harco, Leemco, or approved equal.
 - h. All mainline isolation gate valves shall be of the same manufacturer, and shall provide a 10 year warranty on products and replacement labor costs. Prior to install, Contractor shall provide OAR documentation from the manufacturer shall provide documentation stating the above warranty information, including the labor reimbursement hourly rate.
 3. Manifold or RCV Isolation Valves: Shall be angle type.
 - a. Shall be epoxy coated cast iron.
 - b. Shall be same size as the largest lateral pipe they supply.
 - c. Shall connect to the main line pipe via a Ductile Iron Lateral Tee.
 - d. Lateral to mainline connection shall be made with ductile iron, resilient seated angle valve.
 - e. Valve body and restraint clamps shall be constructed of ductile iron per ASTM A-536, Grade 65-45-12.
 - f. Epoxy coating on all interior and exterior surfaces shall be fusion bonded epoxy, 10-12 mil thickness.
 - g. Valve mechanism and hardware shall be made of 100% 304 stainless steel. The valve stem shall be fine threaded stainless steel, O-Ring sealed for ease of operation.
 - h. Valve connection to the mainline fitting shall be spigot x bell, mechanically attached and swivel about the base 360 degrees to allow positioning of valve outlet to any desired direction.
 - i. Valve outlet shall be deep bell, gasket and equipped with integrally cast joint restraint clamps to securely fasten pipe to the valve. Restraint shall have blunt cast serrations. Machined threaded restraints will not be allowed.
 - j. Swivel style extensions shall be stackable.

- k. Valve shall have a shroud around the valve stem to accept IPS PVC sleeve.
 - l. All lateral to mainline transitions shall be as manufactured by Harco, Leemco or approved equal.
 - 4. Hydrometer/Master Valve (Owner-furnished Contractor-Installed)
 - 5. Quick Coupler Valves: Quick coupler valves shall be installed where specified on the plans. Each valve shall be a Rain Bird 44 LRC heavy duty brass, two-piece, single lug locking cap. Each valve shall also be teed off the supply line with at least 24 inches of galvanized iron pipe and all fittings from that point up shall be galvanized iron. A Ford B11444 heavy duty ball manual valve shall be installed upstream from each quick coupler or group of quick couplers on one supply line for water shut-off and maintenance. Access ball valve with a 2" PVC sleeve-capped by a Weathermatic 906L cap, within a 10" round Carson Box with tee lid.
 - a. Quick coupler valves shall be installed within a 10" round Brooks bolt down box with tee lid unless next to concrete pad, then install to grade.
 - b. The Contractor shall provide to the OAR at least 1 cap lock key and 1 quick coupling key with a swivel hose bib attached. These keys shall be delivered prior to final acceptance of the project.
 - 6. Control Valves: Control valves shall be installed as specified by the plans. Each valve shall be PEB/PESB plastic globe diaphragm and electrically activated as specified on the plans. No valve shall be installed more than 12 inches below finished grade. All pipe on the control valve manifolds shall be Schedule 80 PVC pipe.
 - 7. Manual Drain Valves: Manual drain valves shall be required at all low points in the main lines. See plans, notes, and details.
 - a. All manual drains shall be Ford B11333 heavy duty brass, ball valves.
 - b. The location of each manual drain shall be shown on the "as built" drawing with dimensions from the nearest permanent fixture, such as a building corner, etc.
 - 8. Automatic Drain Valves: Automatic drain valves shall not be allowed on this project.
- B. Valve Boxes:
 - 1. All main line buried gate valves shall be fitted with a 6" minimum diameter pipe sleeve and 10" round Carson valve box, tee lid with stainless steel bolt. Install a quick coupler just downstream of each gate isolation valve, for blow out purposes.
 - 2. Control Valve Boxes: All control valves shall be housed in a Carson 1419 standard or 1220 Jumbo series heavy duty plastic valve box, with a tee top, bolt-down lid, using stainless steel bolts.
- C. Valve Assembly Marking
 - 1. Each valve assembly and valve box must be permanently marked with the appropriate controller station number. Marking must be done in a manner which allows replacement of component parts without loss of marking.

2.4 BACKFLOW PREVENTION DEVICE

- A. Existing backflow prevention devices to be used.

2.5 IRRIGATION HEADS

- A. General
 - 1. All heads used on this project shall be as specified in the materials list on the plans.

2.6 CONTROL WIRE

- A. Standard Control Wire: All standard irrigation control wire shall bear approval as UF/UL PE type of underground feeder and each conductor shall be of electrical conductivity grade copper in accordance with ASTM-30. All control wire shall be specifically designed for direct burial use. Sizes shall be #14 ga for control wire and spare wire and #12 ga. For common wire. A minimum loop of 24 inches shall be left at each valve, at each splice, and at each controller for expansion and/or servicing of the wire. All splices shall be water-tight, as specified above. All wire, crossing water, attached to bridges, going under paving, or where conditions require protection, shall be housed in conduit or sleeves, all out of ground conduits shall be metal rigid conduit. All buried conduit can be P.V.C. conduit.
- B. All common or ground wires shall be White. Where more than one controller is required, a different color hot wire shall be used for each controller.
- C. The pigment or color of the wires shall be integrated into the covering, rather than painted on. No aluminum wire shall be used on this project!

2.7 TWO-WIRE CONTROLLER WIRE

- A. Shall be 14-2 Paige Electric Maxi Cable P7072D double jacketed, double insulated direct bury control wire and shall be run from the controller to each decoder.
- B. All Maxi-cable wire to be installed in 1" HDPE conduit. Where full roll of conduit length is insufficient to span between valves, contractor shall install standard size valve box as conduit pull box and install extra cable length as noted.
- C. For trouble shooting purposes, a star configuration is to be used as opposed to a looped configuration.
- D. An electric decoder cable fuse devise (DCFD) to be installed at all splits in the 2-wire path where more than two runs of Maxi Cable come together. Install DCFD and extra cable in standard size valve box.
- E. Each two-wire branch is to be either a different color of wire, or marked with colored tape at all splices for troubleshooting purposes and recorded on the Controller Wiring Map.
- F. An extra 36" of cable shall be installed on both the incoming and outgoing runs of two-wire cable at each control valve to allow maintenance personnel to lift control valves out of box for maintenance and servicing.
- G. 36" of extra cable length to be installed at all splices and conduit pull boxes, and valve boxes.
- H. Contractor shall clearly indicate on As-Builts and Controller Wiring Map the two wire path routing, with each color of wire, and record the amperage of each two-wire run from the farthest point on each run back to the controller on the As-Builts and Controller Wiring Map.

2.8 TWO WIRE DECODERS

- A. Two-Wire Decoders shall be Owner Provided, Contractor Installed. All two wire decoders shall be WT2W-SVD-11P. Only one decoder to one valve shall be used with no exceptions.
- B. Contractor to install decoders as per manufacturer's installation instructions. New decoder to be numbered in sequence with current system.
- C. Decoders are to be pre-addressed from the manufacturer.

2.9 LINE SURGE PROTECTION ALONG TWO-WIRE PATH

- A. Standalone surge protection along two-wire path is required: WT2W-LSP.
- B. Surge protection is to be installed per manufacturer's recommendations at a minimum of every 500' or every 5 decoders/valves, whichever is less. Additionally, surge protection is to be installed along the two-wire path, within close proximity to the irrigation controller, and at the end of each two-wire spur longer than 50'.

- C. Grounding is to be installed at each line surge protection installed as per decoder grounding details and shall meet manufacturer's minimum grounding requirements as necessary to maintain product warranty. All grounding shall allow for 10 OHMS of resistance or less.

2.10 TRACER WIRE

- A. Tracer Wire shall be installed with all irrigation mainlines.
- B. Detectable Tracer Tape shall be (for Open-Trench Installation): Presco 1776 Detectable Underground Warning Tape or approved equal with minimum 5 mil thickness, durable laminate construction and permanently imprinted with black ink.
- C. Splices along the continuous run of trace wire for repair of a wire break or replacement of failed segment of wire shall use 3M Brand DBR Direct Bury Splice Kit or approved equal. Approved alternatives must securely connect two or more wires, effectively moisture seal by means of a dielectric non-hardening silicone sealant, manufacturer approved for direct burial and rated for a minimum of 50V.
- D. Branch connections for laterals, turnouts, services and appurtenances shall use DryConn Direct Bury Lug Aqua, or approved equal. Approved alternatives must securely connect one or two wires to the main trace wire without cutting the main trace wire, effectively moisture seal by means of a dielectric non-hardening silicone sealant, manufacturer approved for direct burial and rated for a minimum of 50V.

2.11 CONTROLLER (Owner-furnished Contractor-Installed)

- A. Controller to be provided by Owner.
- B. The Contractor shall be required to provide conduit, wiring, and all materials along with the labor necessary to make the controller operational and in compliance with local electrical codes.

PART 3 – EXECUTION

3.1 GENERAL

- A. Irrigation System Design & Water Supply
 - 1. The sprinkler irrigation system is intended to convey full coverage of the lawn and planting areas affected. The system must provide the manufacturer's recommended minimum operating pressure or greater to every head while maintaining sufficient pressure to overcome the losses due to friction in the piping, fittings, and all other equipment.
 - 2. Adequate water supply:
 - a. Perform static pressure test prior to commencement of work.
 - b. Verify that proper connection is available, and is of adequate size. Verify that culinary connection components may be installed as necessary.
Notify OAR in writing of problems encountered prior to proceeding.
- B. Electrical Service
 - 1. If electrical service is not already in place, the Contractor will be required to make all necessary arrangements with Rocky Mountain Power Company including, but not limited to, making power connections, providing poles, weather head and meter, etc., as specified on the plans.
 - 2. All permits and compliance with electrical company requirements shall be the Contractor's responsibility. All electrical lines or conduit, entering onto the site or within the site, shall be buried a minimum of 24 inches or as required by applicable codes, whichever is greater.
- C. Construction Staking
 - 1. The Contractor shall provide the necessary staking to obtain the layout shown on the plans. The points of reference shall be the existing walks, buildings, curbs,

etc... The staking shall be approved by the OAR prior to commencing installation operations. Any changes in the system which appear necessary, due to field conditions, must be called to the attention of the OAR and approved at the time.

3.2 SEQUENCING

- A. Perform site survey, research utility records, contact utility location services. The Contractor shall familiarize himself with all hazards and utilities prior to work commencement. Install sleeving prior to installation of concrete, paving or other permanent site elements. Irrigation system Point of Connection components, backflow prevention and pressure regulation devices shall be installed and operational prior to all downstream components.
 - 1. All main lines shall be thoroughly flushed of all debris prior to installation of Remote Control Valves. All lateral lines shall be thoroughly flushed of all debris prior to installation of any sprinkler heads.
 - 2. Irrigation Contractor shall be required to submit detailed Construction Schedule to Owner prior to commencement. Schedule shall be updated weekly.
- B. Contractor shall schedule and organize work to minimize impact on project usage during public hours. Contractor shall confine work efforts to areas or zones which he can reasonably fence or protect, rather than spreading out trenching or other tasks across large areas of the site.
 - 1. Contractor shall schedule his work to reduce or eliminate open trenches at the end of each work day.
- C. Contractor is responsible to supply water to existing portions of the project during construction.
- D. Contractor is responsible to maintain existing turf and plant material in healthy condition. Any loss of turf or plant material due to Contractor neglect shall be replaced by Contractor at no cost to Owner. Water to existing turf or plant material shall not be turned off for more than 48 consecutive hours.

3.3 EXISTING FIELD CONDITIONS

- A. Preserve and protect all existing trees, plants, structures, hardscape, and architectural elements from damage due to work in this section. In the event that damage does occur to landscaping or structures, the contractor will repair or replace damage.
- B. Trenching or other work required in this section under limb spread of existing trees shall be done by hand or by other methods so as to prevent damage or harm to limbs, branches, and roots.
- C. Trenching in areas where root diameter exceeds 2 inches shall be done by hand. Exposed roots of this size shall be heavily wrapped with moistened burlap to avoid scarring or excessive drying. Where trenching machine is operated in proximity to roots that are less than 2 inches, the wall of the trench shall be hand trimmed, making clean cuts through roots.
- D. Trenches adjacent to or under existing trees shall be closed within 24 hours, and when this is not possible, the side of trench closest to tree or trees affected shall be covered with moistened burlap.
- E. Contractor to sequence the work in a way to minimize irrigation disruption to the existing landscape. Contractor is to ensure that the existing landscape receives sufficient irrigation to maintain the health of the existing landscape. Removal/Replacement of dead vegetation due to lack of water is the responsibility of the contractor at no additional cost to the owner.

3.4 TRENCHING AND BACKFILLING

- A. Excavation and Trenching:

1. Excavation work shall be as deep and as wide as will be required to safely perform the work, such as making mainline connections or forming vaults.
 2. Trenches shall be deep and wide enough to provide working space for placing 2 inches of mortar sand bedding underneath all new mainline pipe and fittings where the soil is rocky or gravelly.
 - a. 24 inches of cover shall be placed over the top of all pipe and fittings on main lines (lines which maintain a constant water pressure).
 - b. All trench bottoms shall be sloped so that the pipes will gravity drain back to the main connection point or the nearest manual drain.
 - c. If the existing main line is deeper than 30 inches, the Contractor shall install a riser to a depth of 18 to 30 inches and then install the new line at the required 18-30" depth. At no time will the mainline be installed deeper than 24" unless prior approval by OAR.
 3. Trenches for lines supplying large rotors shall be deep enough to maintain a minimum of 8 to 16 inches of cover over the top of all pipe and fittings. Trenches shall also be deep enough to guarantee that all swing joints drain back to the lateral and supply lines. Lateral lines may be pulled by a mechanical puller provided minimum uniform depth and all other applicable specifications are met.
 4. Trenches for lines supplying small heads shall be deep enough to maintain a minimum of 8 to 14 inches of cover over the top of all pipe and fittings. Trenches for these lines shall be a minimum of 6 inches away from any walks, curbs, and of sufficient width to accommodate tees coming out sideways (horizontally) from the laterals.
 5. Any rocks or other debris over one inch in diameter uncovered during excavation or trenching shall be removed from the area.
 6. If more than one line is required in a single trench, that trench shall be deep and wide enough to allow for at least 6 inches of separation horizontally between pipes.
 7. Any existing utility lines damaged during excavating or trenching shall be repaired immediately after notification of the utility owner and to his satisfaction. Should utility lines be encountered, which are not indicated on the plans, the OAR shall be notified. The repair of any damage shall be done as soon as possible by the Contractor or the utility owner, and proper compensation will be negotiated by the County. Such utility locations shall be noted on the "as built" drawings required before final payment of the sprinkler irrigation system contract.
- B. Backfill:
1. No backfilling of trenches shall be done until the system has been inspected for proper trench depths, installation of equipment, Ductile Iron fittings with joint restraints, control wire, and location of heads by the OAR.
 2. Before trenches are backfilled, the Contractor must show the OAR, the redlined "as built" drawing he has been keeping on the site, showing that changes and corresponding dimensions have been recorded where changes have been made.
 3. The system shall be tested under pressure for leaks, and general operation of the equipment. It must maintain a minimum pressure of 60 P.S.I. from the main connection to the farthest head. This may be tested and certified by the OAR. All defects disclosed by the pressurization and operation test shall be corrected before proceeding with further work.
 4. Backfill under and around the lines to the center line of the pipe shall be placed in maximum layers of 6 inches and thoroughly compacted.
 5. Special care shall be taken to assure complete compaction under the haunches of the pipe. Backfill compaction under the haunches of the pipe shall be compacted to the original density. Compaction requirements by mechanical compactor, i.e. jumping jack, above the pipe shall be the same as for surrounding areas.
 6. No rocks larger than 1 inch in diameter, nor any other debris, shall be backfilled into the trenches. All trenches shall be backfilled then saturated with water

sufficiently to insure no settling of the surface after lawn is planted or sod is replaced.

7. Where trenching is done in established lawn, care will be taken to keep the trenches only as wide as is necessary to accomplish the work. The trenches shall be backfilled as specified above and then 4 inches of topsoil will be placed to bring the trench up to existing grade so that sod can be laid. The new sod shall be first grade sod per specifications of standard width and shall be laid along the trenches so as to match the existing sod. No small pieces of sod shall be used and only standard lengths shall be accepted. No sod from the construction site shall be used unless otherwise specified

3.5 PIPE INSTALLATION

- A. General:
 1. Handling and unloading of pipe and fittings shall be in such a manner as to insure delivery at the job site in a sound, undamaged condition. Any pipe found to be damaged or defective in workmanship or materials shall be rejected or taken out if found installed.
- B. Plastic Pipe:
 1. Installation: The ends of all threaded pipe shall be reamed and free of all inside scale or burrs. Threads shall be cut clean and sharp, and to a length equal to 1-1/8 times the length of the female thread receiving the pipe. The threaded pipe shall be screwed into a full length of the female thread.
- C. Fittings:
 1. All tees coming out of main lines or valves and other fixtures, shall be horizontal so that no weight or pressure may be exerted through the fixture on the top or bottom of the main line.
 2. Maximum of two (2) auto valves per main line tee.
 3. All tees coming out of the lateral lines for heads and other fixtures shall be horizontal so that no direct weight or pressure may be exerted through the head to the top or bottom of the lateral line. Tees on lateral lines shall also be SXSXT to the head swing joints. See detailed drawings.
 4. All pipe joints shall be properly sealed with pipe dope applied to and well worked over the areas to be joined. The dope for galvanized pipe shall be a white lead and pure linseed oil mixed to be a consistency of thick paint or it may be Teflon tape.
 5. Every care shall be taken during installation to prevent dirt and debris (especially rocks) from getting into the pipes.
- D. HDPE Pipe Fusion:
 1. Sections of polyethylene pipe should be joined into continuous lengths on the jobsite above ground. The joining method shall be the thermal butt fusion method and shall be performed in strict accordance with the pipe supplier's recommendations. The butt fusion equipment used in the joining procedures should be capable of meeting all conditions recommended by the pipe supplier, including, but not limited to, temperature requirements of 400 degrees Fahrenheit, alignment, and an interfacial fusion pressure of 75 PSI. The fusion equipment used shall be manufactured by McElroy Manufacturing, or equal. The butt fusion joining will produce a joint weld strength equal to or greater than the tensile strength of the pipe itself.
 2. Electrofusion may be used where the thermal butt fusion method cannot be used. Electrofusion couplings and fittings shall be PE3408/3608 HDPE, Cell Classification of PE 345464C as determined by ASTM D3350-05. Electrofusion couplings or fittings shall have a manufacturing standard of ASTM F1055. Couplings and fittings shall have the same pressure rating as the pipe unless otherwise specified on the plans.
 3. Mechanical connection to other types of pipe shall be made by one of the Following methods:

1. Flange, using HDPE flange adapter with ductile iron back up ring, and zinc-plated bolts.
 2. Mechanical joint, using HDPE Mechanical Joint (MJ) adapter kit.
- E. Joint Restraint System
1. All ductile iron pipe fittings and mainline gate valves shall be restrained by the joint restraint system. Fittings shall require a 'fitting to pipe restraint' and mainline gate valves shall require a 'valve to pipe' restraint. When required by manufacturer, gasket bell ends of pipe shall require a 'pipe to pipe' restraint.
 2. **Concrete thrust blocks shall not be used.**
 3. Joint restraints are needed on pipe sized 3" and larger, wherever the main pipe line:
 - a. Changes any direction at tees, angles, and crosses vertical and horizontal.
 - b. Changes size at reducers.
 - c. Stops at a dead-end.
 - d. Valves at which thrust develops when closed.
 4. **The size and type of joint restraint system depends on a number of factors, including: pressure, pipe size, kind of soil, and type of fitting. Refer to detail table, as well as manufacturer's recommendations for proper sizing and types.**
 5. All pipes, lines, and risers shall be flushed thoroughly with water before installation of any heads. All debris and rocks found at that time shall be removed from the area as soon as possible.
- F. Sleeves:
1. Verify all sleeve locations below future hardscape. Flag all existing sleeves and conduits installed by other trades.

3.6 VALVE AND VALVE BOX INSTALLATION

- A. VALVES:
1. Manual Drain Valves: Manual drain valves shall be required at all low points in the main lines. See plans, notes, and details.
 - a. Each manual drain valve will be accessed by a 2 inch PVC Schedule 40 pipe sleeve, capped by a Weathermatic 906L locking valve cap with a RLK-1 key, no approved equals, enclosed within a 10" round Brooks Bolt down box top of drain sleeve to be 3" - 6" below lids of Brooks Box.
 - b. Each manual drain shall empty into a gravel sump, a minimum of 18 inches by 18 inches by 12 inches deep. The gravel shall be washed 3/4 inch rock. No pea gravel will be allowed.
- B. VALVE BOXES:
1. Control Valve Boxes: No valve box shall rest directly upon the valve or any fixture associated with it. Each valve box shall be centered on the valve it covers. Each valve box shall have 6 inches of clean 3/4" minus gravel placed in the bottom underneath the valve and lines to reduce the potential of mud and standing water therein.
 - a. All connections made inside the box to connect wires to the valve shall be made inside a 3M-DBR/Y-6 connector. Each connector shall be completely sealed and water proof with a minimum 24" wire loop in each box for each wire. Wires shall be twisted together first with pliers, soldered with lead free product, wire nut placed on soldered, twisted wire, then placed in waterproof tube. Wire nuts, tubes shall not be re-used or used more than once.
 - b. All splices in control wire shall also be housed in a valve box, as specified above.
 - c. All valve boxes of any type shall have at least 4 bricks, one per corner, for support.

3.7 IRRIGATION HEAD INSTALLATION:

- A. General:
 - 1. All heads shall be installed above grade so as to minimize washing of the topsoil and seed during the landscaping establishment period, except those which border paving or flat work of any kind. These heads shall be installed at the finished grade of the adjacent paving or flat work. Prior to final acceptance of the project, all heads shall be raised or lowered to final lawn or planting grade.
 - 2. Heads installed in existing sod shall be set at the grade of the soil.
 - 3. All rotary pop-up heads shall be installed at final grade on double swing joints. See detailed drawings in the section following this one. All swing joints must drain by gravity back to the supply lines.
 - 4. All pop-up, shrub spray, lawn spray, bubbler and strip spray heads shall be installed as shown in the details.

3.8 TWO-WIRE CONTROL WIRE INSTALLATION

- A. Two-Wire Control Wire - shall be installed in the same trench as the main line wherever possible. All conduit shall be installed in trenches 6 inches to either side of the pipes so that the conduit is protected from damage during backfilling and maintenance operations. See detailed drawing showing the wire located in those positions. Conduit not placed in the trenches by the sides or under the pipes, shall be buried 18 inches or deeper and marked on the "as built" drawings.
- B. All connections made inside the box to connect wires to the valve shall be made inside a 3M- DBR/Y connector. Each connector shall be completely sealed and water proof with a minimum 36" wire loop.
- C. Two-wire conduit is to terminate inside valve box. Install a standard size valve box as a 'Pull Box' at minimum of every 150'.
- D. Install all with a minimum 3 feet expansion loop for both incoming and outgoing wiring on two wire path for ease of maintenance.

3.9 TRACE WIRE INSTALLATION

- A. Trace tape shall be installed in the same trench, bored holes and casing with irrigation mainline pipe during pipe installation. It shall be placed 6" directly above the pipe.
- B. Except for approved spliced-in repair or replacement connections, tracer wire shall be continuous and without splices from each trace wire access point.
- C. At all irrigation main end caps, a minimum of 6 feet of tracer wire shall be extended beyond the end of the pipe, coiled and secured to the cap for future connections. The end of the tracer wire shall be spliced to the wire of a six pound zinc anode and is to be buried at the same elevations as the water main.
- D. Contractor shall perform a continuity test on all trace wire in the presence of the Engineer or the Engineers' representative. If the trace wire is found to be not continuous after testing, Contractor shall repair or replace the failed segment of the wire.

3.10 ELECTRICAL CONTROL WIRE INSTALLATION

- A. Standard Control wiring shall only be used for wiring of valve to decoder and wiring of master valve as specified. Wiring shall be installed in the same trench as the main line wherever possible.
- B. Wire type and method of installation shall be in accordance with local codes for NEC Class II circuits of 30-volt A.C. or less.
- C. All connections made inside the box to connect wires to the valve shall be made inside a 3M- DBR/Y connector. Each connector shall be completely sealed and water proof with a minimum 24" wire loop.

- D. All wires shall be direct runs with no splices. Wires cannot be spliced without approval of Owner's representative or Project Manager.
- E. Splices in electric control wires shall be fitted with a 3M DBR/Y Direct Bury Splice Kit. No exceptions. All splices shall be contained in a valve box with extra length equal to 24" above the top of the valve box.
- F. Wire shall be pulled into controller with 12" minimum tail, and properly labeled. Any wire that comes from the ground to the controller must be housed in PVC conduit or flex conduit.
- G. It is important that the splice is absolutely waterproof so that there is no chance for leakage of water and corrosion build-up on the connection. All wiring shall be accomplished with as few splices as possible. Splice locations shall be shown on the Record Drawings.
- H. An expansion curl shall be provided within 6 inches of each wire connection to a solenoid and at least every 100 feet of wire length on runs more than 100 feet in length. Expansion curls can be formed by wrapping five (5) turns of wire around a 1-inch diameter or larger pipe and then withdrawing the pipe.
- I. Contractor shall provide a complete wiring diagram showing wire routing for the connections between the controller and valves. See section one for the inclusion of wiring diagram in operation and maintenance manuals.

3.11 TWO-WIRE CONTROL WIRE INSTALLATION

- A. Two-Wire Control Wire - shall be installed in the same trench as the main line wherever possible. All conduit shall be installed in trenches 6 inches to either side of the pipes so that the conduit is protected from damage during backfilling and maintenance operations. See detailed drawing showing the wire located in those positions. Conduit not placed in the trenches by the sides or under the pipes, shall be buried 18 inches or deeper and marked on the "as built" drawings.
- B. All connections made inside the box to connect wires to the valve shall be made inside a 3M- DBR/Y connector. Each connector shall be completely sealed and water proof with a minimum 36" wire loop.
- C. Two-wire conduit is to terminate inside valve box. Install a standard size valve box as a 'Pull Box' at minimum of every 150'.
- D. Install all with a minimum 3 feet expansion loop for both incoming and outgoing wiring on two wire path for ease of maintenance.

3.12 COMMUNICATION CABLE INSTALLATION

- A. Not required for this contract.

3.13 TRACE WIRE INSTALLATION

- A. Trace tape shall be installed in the same trench, bored holes and casing with irrigation mainline pipe during pipe installation. It shall be placed 6" directly above the pipe.
- B. Except for approved spliced-in repair or replacement connections, tracer wire shall be continuous and without splices from each trace wire access point.
- C. At all irrigation main end caps, a minimum of 6 feet of tracer wire shall be extended beyond the end of the pipe, coiled and secured to the cap for future connections. The end of the tracer wire shall be spliced to the wire of a six pound zinc anode and is to be buried at the same elevations as the water main.
- D. Contractor shall perform a continuity test on all trace wire in the presence of the Engineer or the Engineers' representative. If the trace wire is found to be not continuous after testing, Contractor shall repair or replace the failed segment of the wire.

3.14 CONTROLLER INSTALLATION – OWNER PROVIDED CONTRACTOR INSTALLED

- A. Controllers are existing.
- B. Contractor shall wire valves into controller(s) and set proper program.
- C. All WeatherTrak equipment shall be inspected and approved by a WeatherTrak approved Specialist (Brady Pitcher, 801-592-6490). Contractor shall be responsible for obtaining inspection approval and shall have any rejected installation repaired and re-inspected at no cost to the Owner.

3.15 DECODERS

- A. Install the Owner provided decoders as per manufacturer's recommendations. Contractor to lay out decoders as required by system. No two valves are to share the same address. Decoders shall not be used for the flow sensor or master valve. Flow sensor is to be directly connected to the controller by communication wire and the master valve is to be connected with a #14 AWG Red Control wire and a #12 AWG Common White wire.
- B. All two wire decoders shall be installed inside valve box of control valve(s) in accordance with all manufacturers' installation recommendations.
- C. Grounding and line surge protection to be installed as per decoder grounding detail and per manufacturer's installation recommendations. Grounding wire shall be connected to grounding rods/plates with cadweld connection.

3.16 FINISHING AND TESTING

- A. When installation of all equipment is complete and backfilling, and grading operations are complete, and the irrigation system is full operable. The Owner shall hire a third party IA approved CLIA contractor. The audit contractor shall perform a uniformity and efficiency audit on representative portions (or the entire area) of the turf zones within the project, at the discretion of the Owner. The Contractor shall provide one or more irrigation technicians onsite prior to the audit to perform fine tuning of zones, and during the audit to tune again zones just prior to being audited. The Contractor shall be responsible to ensure his work is installed with all care and best practices taken, to maximize the efficiency and uniformity of the system. Any concerns the Contractor shall have with installing the system per plan, which will reduce uniformity and efficiency shall be brought to the OAR's attention in writing immediately.
- B. Following the Audit the Contractor shall call for an operational test and major inspection of the sprinkler irrigation system. Notice by the Contractor shall be given, in writing, 3 days in advance to the Project Manager so that proper scheduling can be done for those who are to attend.
- C. When installation of all equipment is complete and back filling, and grading operations are complete, the Contractor shall call for an operational test and major inspection of the sprinkler irrigation system. Notice by the Contractor shall be given, in writing, 3 days in advance to the OAR so that proper scheduling can be done for those who are to attend.
- D. At the appointed time, an inspection of all valve boxes, controllers, gate valves, and heads shall be made. The entire system will be tested to check for pressure, operation, water coverage, and head adjustment. A list of discrepancies (punch list), shall be written within 3 days and distributed as needed. Each item on the list shall be corrected before the system will be approved by the Inspector who will notify the OAR before payment will be made. The Contractor will be back charged for time spent by County offices and consultants who have been brought to the site for a final inspection when the project is not ready for a final inspection.
- E. Prior to acceptance of Project by Owner, Contractor shall engage a WeatherTRAK Factory Authorized Service Technician to commission, test, inspect, and certify the system is complete, and full operable and ready for use. Contact Brady Pitcher @ Sprinkler Supply Company, 801-592-6490. Contractor shall be responsible to make corrections, changes, and repairs to the system at no cost to the Owner to the control system until it is in operable condition ready for acceptance and use.

- H. HDPE Pipe Testing
 - 1. Prior to HDPE pipe being installed in the trench, at the beginning of the job, the contractor shall cut out the first butt fusion of each pipe size. The contractor shall prepare the sample for the test in accordance with ASTM D 2657. The samples shall be tested in the presence of the owner's representative. All samples shall be labeled and saved. Testing must be done at 73 degrees F plus or minus 5 degrees. Test temperature and sample size are critical to testing.

3.17 GUARANTEE AND MAINTENANCE

- A. Upon inspection and acceptance of the sprinkler irrigation system as being operational and properly installed, the Contractor shall guarantee the workmanship, materials, fixtures, and equipment to be free from defects for 1 year after Substantial Completion has been granted.
- B. In the fall of the year during the installation and guarantee period, the Contractor shall meet with the County maintenance personnel on the site. The Contractor shall winterize the system by draining all of the water and doing everything necessary to insure protection of the system until spring. Blowing out the lines by compressor shall be permitted during the 1 year guarantee. The individuals involved from both parties shall exchange all information necessary for the eventual take-over of the system by the County.
- C. The Contractor shall insure and guarantee complete drainage of the system. In working with or connecting to an existing system, he shall guarantee compatibility in operation and drainage between the two systems.
- D. The Contractor with the County maintenance personnel, inspector or OAR in attendance shall energize the sprinkler irrigation system again the following Spring and shall repair all defects found as a result of Winter damage, improper installation, improper maintenance, defective materials or inadequate sprinkler drainage.
- E. The Contractor shall coordinate with the landscaping sub-contractor during the entire landscaping and lawn establishment period on the use, scheduling, and maintenance of the sprinkler system.

3.18 FINAL INSPECTION

- A. At the end of the guarantee period, when the lawn and landscaping have been approved, the Contractor shall call for a final inspection of the sprinkler irrigation system. There shall be 5 days' notice given, in writing, to the OAR, prior so that the appropriate people may attend.
- B. Prior to that time, all heads shall have been adjusted to their proper pattern, radii, and height. The system shall have been flushed out, checked for operation, and any defects corrected. The entire system will be inspected and checked to determine if everything is in working order to be turned over to the County. A final list of items found in need or correction (if any), will be made and the Contractor shall correct them.
 - 1. The OAR will notify the Owner when they have verified that every item is acceptable.
 - 2. Upon final acceptance of the project by the OAR, the County shall assume all responsibility for the system.

3.19 MEASUREMENT AND PAYMENT

- A. Payment of the sprinkler irrigation system portion of the contract shall be the lump sum indicated at the time of bidding and any subsequent amendments to the contract price. Partial payments may be made to the General Contractor upon his request and based upon the percentage of approved work completed.
- B. Final payment of the sprinkler irrigation system work shall be made upon acceptance of the system, as specified above and upon the request of the General Contractor.

However, any problems arising at the end of the guarantee period will be corrected or subject to bonding action.

- C. Final payment for the contract will not be processed until:
1. "As Built" drawings or plans are received by the OAR
 2. Owner has receive copies of all Rain Bird product invoices.
 3. Control system is completely programmed for each zone, and is operable and running via web based access.

END OF SECTION

SECTION 32 9113
SOIL PREPARATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Furnish all material, labor, transportation, equipment and property to complete the soil preparation for all planting areas.

1.3 SUBMITTALS

- A. At least 30 days prior to ordering materials, the Contractor shall submit to the Project Manager representative samples, certifications, manufacturer's literature and certified test results for all materials as specified below. No materials shall be ordered or delivered until the required submittals have been reviewed and stamped approved by the Project Manager. Delivered materials shall match the approved samples.
- B. Approval shall not constitute final acceptance. The Project Manager reserves the right to reject, on or after delivery, any material that does not meet these Specifications.
- C. List of submittals required.
 - 1. Agricultural Soil Analysis Testing Results for Topsoil
 - 2. Literature on Fertilizers and additives
 - 3. Sample of topsoil and soil analysis testing results
 - 4. Sample of compost and testing results

1.4 QUALITY ASSURANCE

- A. The following standards apply to the work of this Section:
 - 1. AOAC: Association of Official Agricultural Chemists.
 - 2. ASA: Methods of Soils Analysis, American Society of Agronomy, Soil Science Society of America, Inc., Madison Wisconsin, latest edition.
 - 3. American Society for Testing and Materials (ASTM).
 - 4. All applicable local codes and regulations.
- B. It is the intent of this specification that all materials herein specified and shown on the drawings shall be of the highest quality available and meeting the requirements specified.
- C. The work of this Section shall be performed by a Contracting firm that has successfully installed work of a similar quality, schedule requirement, and construction detailing with a minimum of five (5) years' experience.

- D. All work shall be performed in accordance with the best standards of practice relating to the trade and under the continuous supervision of a competent foreman capable of interpreting the Drawing and Specifications.
- E. Soil shall not be worked when moisture content is so great that excessive compaction occurs, nor when it is so dry, that dust will form in air or that clods will not break readily. Water shall be applied, if necessary, to provide ideal moisture content for tilling and for planting.
- F. All accumulated debris and rubbish shall be cleaned up and removed from the site before commencing work. Clear and grub all dead vegetative matter. The site shall be weed free prior to proceeding with any work.
- G. Soil-Testing Laboratory Qualifications: An independent laboratory, recognized by the State Department of Agriculture, with the experience and capability to conduct the testing indicated and that specializes in types of tests to be performed.
- H. Topsoil Analysis: Furnish a soil analysis for each planting soil mix specified in this section by a qualified soil-testing laboratory stating percentages of organic matter; gradation of sand, silt, and clay content; cation exchange capacity; sodium absorption ratio; deleterious material; pH; and mineral and plant-nutrient content of topsoil.
 - 1. Report suitability of topsoil for lawn growth. State recommended quantities of nitrogen, phosphorus, and potash nutrients and soil amendments to be added to produce a satisfactory topsoil.

PART 2 - PRODUCTS

2.1 TOPSOIL

- A. Topsoil shall be of uniform quality, free from subsoil stiff or lumpy clay, hard clods, hardpan, rocks, disintegrated debris, plants, roots, seeds, and any other materials that would be toxic or harmful to plant growth. Topsoil shall contain no noxious weeds or noxious weed seeds.
- B. Topsoil shall meet all specifications below for the "Ideal" or "Acceptable" categories. Soil that falls within the "Not-Acceptable" range shall not be used.

TOPSOIL QUALITY*

Category	pH	Soluble Salts dS/m or mmho/cm	Sodium Ab- sorption Ratio (SAR)	Organic Mat- ter %	Sand %	Silt %	Clay %	Texture Class
Ideal	5.5- 7.5	<2	<3	≥2.0	<70	<70	<30	Loam (L), Silt Loam (SiL)
Acceptable	5.0- 8.2	<4	3 to 7 SiL, SiCL, CL 3 to 10 SCL, SL, L	≥1.0	<70	<70	<30	Sandy Clay Loam (SCL) Sandy Loam (SL) Clay Loam (CL) Silty Clay Loam (SiCL)
Not- Acceptable	<5.0 >8.2	>4	>10	<1.0	≥70	≥70	≥30	Loamy Sand (LS) Sandy Clay (SC) Silty Clay (SiC) Sand (S), Silt (S), Clay (C)

COARSE FRAGMENTS*

Category	%>2 mm (>5.0% exceeds guidelines)	Rocks Present >1.5" (>1.5" exceeds guidelines)
Ideal	□2.0	—
Acceptable	2.1-5.0	—
Not-Acceptable	>5.0	—

TOPSOIL NUTRIENT SPECIFICATION*

	Nitrate Ni- trogen ppm	Phosphorus ppm	Potassium ppm	Iron ppm
Ideal / Acceptable	>20	>15	>150	>10

*from "Topsoil Quality Guidelines for Landscaping", June 2002, AG/SO-02, prepared by Rich Koenig, Utah State University Cooperative Extension Soil Specialist, and Von Isaman, QA Consulting and Testing, LLC.

- C. **Mechanical Analysis** shall be performed and shall conform to ANSI/ASTM D 422. QUALITY ASSURANCE.

2.2 COMPOST

- A. Compost shall meet all specifications below for either “Ideal” or “Acceptable” categories. Compost that falls within the “Not-Acceptable” range shall not be used.

COMPOST QUALITY GUIDELINES FOR LANDSCAPING*

	pH	Soluble Salts dS/m	Sodium Ab- sorption Ra- tio (SAR)	Car- bon:Nitrogen Ratio (C:N)%	Moisture%	98% Coarse Ma- terial Passing (dry weight basis)
Ideal	6 to 8	≤5	<10	≤20:1	25 to 35	3/8”
Acceptable	5-6, 8-9	≤10	≤20	21:1 to 30:1	<25, >35	3/4”
Not- Acceptable	<5.0, >9.0	>10	>20	<10:1, >30:1	<20, >50	<98% 3/4”

*Von Isaman MS, Pres. Of QA Consulting and Testing, LLC., Dr. Rich Koenig, Utah State University Cooperative Extension Soils Specialist, and Dr. Teresa Cerny, USU Cooperative Extension Horticulturalist, 3 March 2003.

2.3 FERTILIZER AND ADDITIVES

- A. Required fertilizer and additives shall be determined by the Agricultural Soil Analysis.
- B. Fertilizer shall be furnished in bags or other standard containers with name, weight, and guaranteed analysis of contents clearly marked thereon.
- C. Chemical fertilizers shall be a mixed commercial fertilizer conforming to FS O-F-241 D, Type I, with percentages of nitrogen, phosphoric acid, and potash at 5-10-5 and 16-16-8. The combined N-P-K content shall be following percentages of total weight: 5 percent nitrogen 10 percent phosphoric acid and 5 percent potash. Fertilizers shall be uniform in composition, dry, and free flowing.

PART 3 - EXECUTION

3.1 TOPSOIL TESTING

- A. **PRIOR** to placement of topsoil, an Agricultural Soil Analysis shall be performed for the existing and/or proposed topsoil conditions.
- B. The landscape work shall not begin until all other trades have repaired all areas of settlement, erosion, rutting, etc., and the soils have been re-established, re-compacted, and refinished to finish grades. The L.A. shall be notified of all areas which prevent the landscape work from being executed.

- C. Areas requiring grading by the landscape contractor including adjacent transition areas shall be uniformly level or sloping between finish elevations to within 0.10-ft above or below required finish elevations.
- D. The landscape work shall not proceed until after walks, curbs, pavings, edging, and irrigation systems are in place. The contract operations shall be completed to a point where the landscape areas will not be disturbed. The subgrade shall be cleaned free of waste materials of all kinds.
- E. During grading, waste materials in the planting areas such as weeds, rocks (1 inches and larger) building materials, rubble, wires, cans, glass, lumber, sticks, hazardous materials etc., shall be removed from the site. Weeds shall be dug out by the roots.
- F. Fertilizers, additives, compost, etc. subject to moisture damage shall be kept in a weatherproof storage place in such a manner that they will be kept dry.
- G. Finish subgrade and topsoil placement and grading shall consist of:
 1. Prepare subgrade by rough grading and removing all irregularities and debris. Dig subgrade down as required in shrub beds and turf areas for the placement of topsoil. Provide laser leveling on large flat areas to create a uniform level subgrade.
 2. Planting areas shall have all road base and other debris removed prior to placement of topsoil. Subgrade soil shall be in a loosened and rough surface finish before topsoil is placed over subgrade. (Sub-grade surface shall not be smooth, but a rough surface shall exist for a transition zone of topsoil to subsoil.) If areas of subgrade become compacted before topsoil is placed, subgrade shall be tilled again before topsoil placement.
 3. Placing all amendments, soil additives and fertilizers for the areas as per the topsoil report and mixing amendments into topsoil.
 4. Adding amendments (compost, & fertilizers) and thoroughly mixing amendments by mechanical means to produce evenly mixed amended topsoil prior to placement topsoil.
 5. Till lawn and planting area subsoil's and topsoil's that are compacted.
 6. After tilling or placement of topsoil, bring areas to uniform grades by floating and/or hand raking. In large open level areas, perform laser leveling to create uniform level areas.
 7. Make minor adjustment of finish grades as directed by the project manager.
 8. Remove waste materials over 1" in size such as stones, roots, or other undesirable foreign materials and finish raking, dishing, dragging, and smoothing soil ready for planting.
 9. No grading or soil placement shall be undertaken when soils are wet or frozen
- H. Any unusual subsoil condition that will require special treatment shall be reported to the L.A.
- I. Topsoil shall be uniformly distributed over all areas where required. Subgrade and topsoil shall be damp and free from frost.
- J. Surface drainage shall be provided as shown by molding the surfaces to facilitate the natural run-off of water. Low spots and pockets shall be filled with topsoil and graded to drain properly.

- K. Finish grade for sodded areas shall be 2 inches below finish grade of adjacent pavement. Finish grade (top of bark mulch) shrub bed areas shall be 1 inches below finish grades of adjacent pavement.
- L. Topsoil shall be backfilled in lifts of no more than six inches (6"). Compact each lift by foot tamping to 95% prior to placing next layer of backfill. For irrigation trenches, settle trenches with water during backfill operations.

3.2 FINE GRADING

- A. When rough grading, weeding, soil preparation have been completed, and soil has been thoroughly water settled, all planting areas should be smoothly graded, ready for placement of plant materials.
- B. Fine grading shall be done when soil is at optimum moisture content.
- C. Finish grades shall be smooth, even and on a uniform plane with no abrupt changes of surface. The finish grade shall not vary more than one half inch (1/2") in ten feet (10') from the required line, and grade set forth in the Drawings. Adjustments of finish grades shall be made at direction of Project Manager as required.
- D. Finish grade of soil in all turf areas shall be one inch (1") below all paved surfaces before laying sod.

END OF SECTION

SECTION 32 91 19

LANDSCAPE GRADING

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Landscaping grading requirements.
- B. Backfill materials.

1.2 SUBMITTALS

- A. Submit maximum laboratory dry density and optimum laboratory moisture content for:
 - 1. Subgrade material, and
 - 2. Each type of fill to be used.
- B. Upon PROJECT MANAGER's request, submit a written quality control Inspections and testing report describing source and field quality control activities performed by CONTRACTOR and its Suppliers.

1.3 QUALITY ASSURANCE

- A. Do not change material sources, or aggregate without PROJECT MANAGER's knowledge.
- B. Reject backfill material that does not comply with requirements specified in this section.
- C. Landscape grading is aesthetic by nature and subject to continual monitoring and modification during the backfilling process. Work closely with PROJECT MANAGER particularly when grading and construction berms, channels, or other aesthetic considerations.

1.4 STORAGE

- A. Safely stockpile backfill materials.
- B. Separate differing materials, prevent mixing, and maintain optimum moisture content of backfill materials.
- C. Avoid displacement of and injury to Work while compacting or operating equipment.
- D. Movement of construction machinery over Work at any stage of construction is solely at CONTRACTOR's risk.

1.5 SITE CONDITIONS

- A. Do not place, spread, or roll any backfill material over material that is damaged by water. Remove and replace damaged material at no additional cost to OWNER.
- B. Control traffic and erosion. Keep area free of trash and debris. Repair settled, eroded, and rutted areas.
- C. Reshape and compact damaged structural section to required density.

1.6 ACCEPTANCE

- A. Native material may be wasted if there is no additional cost to substitute material acceptable to PROJECT MANAGER.

1.7 WARRANTY

- A. Any settlement noted in landscaped surfaces will be considered to be caused by improper compaction methods and shall be corrected at no cost to the OWNER.
- B. Restore incidentals damaged by settlement at no additional cost to OWNER.

PART 2 PRODUCTS

2.1 BACKFILL MATERIALS

- A. Common fill
- B. Crushed aggregate base
- C. Cement treated fill

2.2 MISCELLANEOUS

- A. Water: Make arrangements for sources of water during construction and make arrangements for delivery of water to site. Comply with local Laws and Regulations at no additional cost to OWNER when securing water from water utility company.

PART 3 EXECUTION

3.1 PREPARATION

- A. Identify required line, levels, contours, and datum.
- B. Stake and flag locations of underground utilities.
- C. Upon discovery of unknown utility or concealed conditions, notify PROJECT MANAGER.
- D. Verify stockpiled fill meets gradation requirements, areas to be backfilled are free of debris, snow, ice or water, and ground surface is not frozen.
- E. If subgrade is not readily compactable secure written authorization for extra excavation and backfill. Refer to Section 31 20 00.

3.2 PROTECTION

- A. Protect existing trees, shrubs, lawns, existing structures, fences, roads, sidewalks, paving, curb and gutter and other features.
- B. Protect above or below grade utilities. Contact utility companies to repair damage to utilities. Pay all cost of repairs.
- C. Protect Subgrade from desiccation, flooding and freezing.
- D. Do not fill adjacent to structures until Excavation is checked by PROJECT MANAGER.
- E. Do not use compaction equipment adjacent to walls or retaining walls that may cause wall to become over-stressed or moved from alignment.
- F. Do not disturb or damage foundation perimeter drainage, foundation, damp-proofing, foundation waterproofing and protective cover, or utilities in Trenches.
- G. Restore any damaged structure to its original strength and condition.

3.3 LAYOUT

- A. Maintain all benchmarks, control monuments and stakes, whether newly established by surveyor or previously existing. Protect from damage and dislocation.
- B. If discrepancy is found between Contract Documents and site, PROJECT MANAGER shall make such minor adjustments in the Work as necessary to accomplish the intent of Contract Documents without increasing the Cost of the Work to CONTRACTOR or OWNER.

3.4 GRADING

- A. Grading Intent: Spot elevations and contours indicated are based on the best available data. The intent is to maintain constant slopes between spot elevations. If a spot elevation is determined to be in error, or the difference in elevation between points change, then the minimum percentage of slope as a result of field adjustment of specific spot elevations is as follows:
 - 1. Pavement Areas: 1 percent.
 - 2. Concrete or Brick Areas: 0.30 percent.
 - 3. Lawn or Planted Area: 0.75 percent.
 - a. Implement laser leveling to produce consistent, uniformly, graded surfaces.
- B. Conduct Work in an orderly manner. Do not create a nuisance. Do not permit soil accumulation on streets or sidewalks. Do not allow soil to be washed into sewers and storm drains.
- C. Grade slopes to provide adequate drainage after compaction. Do not create water pockets or ridges. Use all means necessary to prevent erosion of freshly graded areas during construction until surfaces have been constructed and landscaping areas have taken hold.
- D. Remove surface stones greater than 1 inch from finished grading.
- E. In planting areas, provide a finished grade that conforms to Section 32 92 00.

3.7 COMPACTION

- A. Compact backfill per geotechnical report or as required to eliminate settling.

3.8 SURFACE RESTORATION

- A. Restore paved surfaces
- B. Finish landscaped surfaces with grass, Section 32 9200
 - 1. Backfill areas to contours and elevations indicated. Do not use frozen materials.
 - 2. Make smooth changes in grade. Blend slopes into level areas.
 - 3. Remove surplus backfill materials from site.
 - 4. Leave stockpile areas completely free of excess fill materials.
 - 5. Slope grade away from building at a minimum of 3 inches in 10 feet unless specified otherwise.

3.9 CLEANING

- A. Remove stockpiles from the site. Grade site surface to prevent free standing surface water.
- B. Leave borrow areas clean and neat.

END OF SECTION

SECTION 32 92 00

TURF AND GRASSES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Sodding.
 - 2. Turf renovation.
 - 3. Erosion-control material(s).

1.3 DEFINITIONS

- A. Finish Grade: Elevation of finished surface of planting soil.
- B. Pesticide: A substance or mixture intended for preventing, destroying, repelling, or mitigating a pest. Pesticides include insecticides, miticides, herbicides, fungicides, rodenticides, and molluscicides. They also include substances or mixtures intended for use as a plant regulator, defoliant, or desiccant.
- C. Pests: Living organisms that occur where they are not desired or that cause damage to plants, animals, or people. Pests include insects, mites, grubs, mollusks (snails and slugs), rodents (gophers, moles, and mice), unwanted plants (weeds), fungi, bacteria, and viruses.
- D. Planting Soil: Existing, on-site soil; imported soil; or manufactured soil that has been modified with soil amendments and perhaps fertilizers to produce a soil mixture best for plant growth. See Section 329113 "Soil Preparation and drawing designations for planting soils.
- E. Subgrade: The surface or elevation of subsoil remaining after excavation is complete, or the top surface of a fill or backfill before planting soil is placed.
- F. Substantial Completion: The point in time when the Work is sufficiently complete, in accordance with the Contract Documents, that the County can occupy or use the Work for its intended purpose.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For landscape Installer.
- B. Certification of Grass Seed: From seed vendor for each grass-seed monostand or mixture, stating the botanical and common name, percentage by weight of each species and variety, and percentage of purity, germination, and weed seed. Include the year of production and date of packaging.

1. Certification of each seed mixture for turfgrass sod. Include identification of source and name and telephone number of supplier.
- C. Product Certificates: For fertilizers, from manufacturer.
- D. Pesticides and Herbicides: Product label and manufacturer's application instructions specific to Project.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: Recommended procedures to be established by County for maintenance of turf during a calendar year. Submit before expiration of required maintenance periods.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified landscape installer whose work has resulted in successful turf establishment.
1. Professional Membership: Installer shall be a member in good standing of either the Professional Landcare Network or the American Nursery and Landscape Association.
 2. Experience: Three years' experience in turf installation.
 3. Installer's Field Supervision: Require Installer to maintain an experienced full-time supervisor on Project site when work is in progress.
 4. Personnel Certifications: Installer's field supervisor shall have certification in one of the following categories from the Professional Landcare Network:
 - a. Landscape Industry Certified Technician - Exterior.
 - b. Landscape Industry Certified Lawncare Manager.
 - c. Landscape Industry Certified Lawncare Technician.
 5. Pesticide Applicator: State licensed, commercial.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Sod: Harvest, deliver, store, and handle sod according to requirements in "Specifications for Turfgrass Sod Materials" and "Specifications for Turfgrass Sod Transplanting and Installation" sections in TPI's "Guideline Specifications to Turfgrass Sodding." Deliver sod within 24 hours of harvesting and in time for planting promptly. Protect sod from breakage and drying.
- B. Bulk Materials:
1. Do not dump or store bulk materials near structures, utilities, walkways and pavements, or on existing turf areas or plants.
 2. Provide erosion-control measures to prevent erosion or displacement of bulk materials; discharge of soil-bearing water runoff; and airborne dust reaching adjacent properties, water conveyance systems, or walkways.
 3. Accompany each delivery of bulk materials with appropriate certificates.

1.8 FIELD CONDITIONS

- A. Planting Restrictions: Plant during one of the following periods. Coordinate planting periods with initial establishment periods to provide required maintenance from date of planting completion.
1. Spring Planting: 15 March.
 2. Fall Planting: 15 October.

3. Days considered for the establishment period must be conducive to the growth and establishment of the sod and not non-growing seasonal months.
- B. Weather Limitations: Proceed with planting only when existing and forecasted weather conditions permit planting to be performed when beneficial and optimum results may be obtained. Apply products during favorable weather conditions according to manufacturer's written instructions.

PART 2 - PRODUCTS

2.1 TURFGRASS SOD

- A. Turfgrass Species: Bluegrass Sod
1. Sod specifications include but are not limited to:
 - a. Shall be grown from a 10 seed blend utilizing at least 6 highly-rhizomatous cultivars that exceed normally accepted industry criterion. Shall be rated highly wear-tolerant, have strong living color, be disease resistant, with strong leaf texture and early spring and late fall green color.
 - b. Shall contain no rye grass cultivars.
 - c. Shall have a maximum 50# per acre seeding rate.
 - d. Shall have a minimum one year root base with strong rhizome development.
 - e. Shall be certified noxious weed free.
 - f. Shall be Water Wise Turf™ as grown by a Water Wise Certified™ grower.
 - 1) Shall require no more than 30" annual supplemental water during establishment and no more than 20" annual supplemental water after establishment.
 - 2) Shall contain a strong root base capable of root penetration to a minimum depth of 8" into landscape soil.
 - g. Growing medium shall be a sandy soil (75% sand, 17% silt, 8% clay) with low clay content.
 - h. Shall be grown without netting.
 - i. Shipping mow height shall be 1-1/2".

2.2 TOP DRESSING:

- A. Top dressing: 1 part topsoil and 1 part clean sand, fertile, friable, and of fine texture, free of sub-soil, stones, lumps, clods, sticks, weeds, roots, or other extraneous materials.
1. Top dressing shall not be installed while site conditions are frozen or muddy.

2.3 FERTILIZERS

- A. Commercial Fertilizer: Commercial-grade complete fertilizer of neutral character, consisting of fast- and slow-release nitrogen, 50 percent derived from natural organic sources of urea formaldehyde, phosphorous, and potassium in the following composition:
1. Fertilizer shall be a complete mixture, analyzing sixteen (16)% Nitrogen; sixteen (16)% Phosphoric Acid; and eight (8)% Pot Ash, of commercial type and applied at a rate of six (6) pounds per thousand (1000) square feet of area.

- B. Slow-Release Fertilizer: Granular or pelleted fertilizer consisting of 50 percent water-insoluble nitrogen, phosphorus, and potassium in the following composition:
 - 1. Composition: 20 percent nitrogen, 10 percent phosphorous, and 10 percent potassium, by weight.
 - 2. Composition: Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified soil-testing laboratory.

2.4 PESTICIDES

- A. General: Pesticide, registered and approved by the EPA, acceptable to authorities having jurisdiction, and of type recommended by manufacturer for each specific problem and as required for Project conditions and application. Do not use restricted pesticides unless authorized in writing by authorities having jurisdiction.
- B. Pre-Emergent Herbicide (Selective and Nonselective): Effective for controlling the germination or growth of weeds within planted areas at the soil level directly below the mulch layer.
- C. Post-Emergent Herbicide (Selective and Nonselective): Effective for controlling weed growth that has already germinated.

2.5 EROSION-CONTROL MATERIALS

- A. Erosion-Control Blankets: Biodegradable wood excelsior, straw, or coconut-fiber mat enclosed in a photodegradable plastic mesh. Include manufacturer's recommended steel wire staples, 6 inches long.
- B. Erosion-Control Fiber Mesh: Biodegradable burlap or spun-coir mesh, a minimum of 0.92 lb/sq. yd., with 50 to 65 percent open area. Include manufacturer's recommended steel wire staples, 6 inches long.
- C. Erosion-Control Mats: Cellular, non-biodegradable slope-stabilization mats designed to isolate and contain small areas of soil over steeply sloped surface, of 4-inch nominal mat thickness. Include manufacturer's recommended anchorage system for slope conditions.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas to be planted for compliance with requirements and other conditions affecting installation and performance of the Work.
 - 1. Verify that no foreign or deleterious material or liquid such as paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, or acid has been deposited in soil within a planting area.
 - 2. Suspend planting operations during periods of excessive soil moisture until the moisture content reaches acceptable levels to attain the required results.
 - 3. Uniformly moisten excessively dry soil that is not workable or which is dusty.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

- C. If contamination by foreign or deleterious material or liquid is present in soil within a planting area, remove the soil and contamination as directed by Project Manager and replace with new planting soil.

3.2 PREPARATION

- A. Protect structures; utilities; sidewalks; pavements; and other facilities, trees, shrubs, and plantings from damage caused by planting operations.
 - 1. Protect adjacent and adjoining areas from hydroseeding and hydromulching overspray.
 - 2. Protect grade stakes set by others until directed to remove them.
- B. Install erosion-control measures to prevent erosion or displacement of soils and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways.

3.3 TURF AREA PREPARATION

- A. All areas of fill, i.e., trenches, mounds, etc., shall be compacted and settled as specified in the Grading and excavation of sprinkler irrigation sections of this project before any topsoil is placed on areas to be sodded.
- B. Remove weeds before sodding. Where weeds are extensive, apply selective herbicides as required. Do not use pre-emergence herbicides.
- C. Before topsoil is spread, the sub-grade shall be scarified to a depth of four (4) inches to ensure proper bonding with applied topsoil if it has been compacted due to weather or equipment. The area shall be leveled, weeded and raked free of stones larger than one half (1/2") inch in diameter and other debris.
- D. Topsoil shall be spread to a depth of four (4) inches or as directed by the Project Manager.
- E. Any existing topsoil used in sodded areas shall be loosened and pulverized to a depth of four (4) inches and all stones over one (1) inch in any dimension, sticks, roots, rubbish, or other extraneous matter, shall be removed from the premises. The surface will be fine graded so that when settled, the surface is free from depressions or ridges and will conform to the required grades indicated. The surface shall be smooth, loose, and of uniformly fine texture at the time of installation.
- F. Any areas containing new topsoil shall be rolled by a hand roller on small areas. After rolling at a weight of 150-200 pounds per linear foot of roller, the bed shall again be graded to the specified grade with a smooth surface. Large areas shall be final graded by passing a land plane in three different directions over the entire area to be planted.
- G. New turf shall be installed so that the finished grade shall be one-half (1/2) inch below the top of adjacent paving.
- H. The Contractor shall prepare no more ground than can be sodded in a twenty-four (24) hour period. Sod shall be placed within 24 hours of ground preparation. The ground shall be re-prepared if weather or traffic has compromised the friability of the prepared area.
- I. No sodding shall be done immediately after a rain storm or if a prepared surface has been compacted without first loosening the surface to a smooth, loose, uniformly fine texture just prior to sodding.

- J. Moisten prepared area before planting if soil is dry. Water thoroughly and allow surface to dry before planting. Do not create muddy soil.
- K. The specified fertilizer shall be applied and incorporated into the upper four (4) inches of topsoil at a rate of six (6) pounds per thousand (1000) square feet.
- L. Before planting, obtain Project Manger's acceptance of finish grading; restore planting areas if eroded or otherwise disturbed after finish grading.

3.4 PREPARATION FOR EROSION-CONTROL MATERIALS

- A. Prepare area as specified in "Turf Area Preparation" Article.
- B. For erosion-control mats, install planting soil in two lifts, with second lift equal to thickness of erosion-control mats. Install erosion-control mat and fasten as recommended by material manufacturer.
- C. Fill cells of erosion-control mat with planting soil and compact before planting.
- D. For erosion-control blanket or mesh, install from top of slope, working downward, and as recommended by material manufacturer for site conditions. Fasten as recommended by material manufacturer.
- E. Moisten prepared area before planting if surface is dry. Water thoroughly and allow surface to dry before planting. Do not create muddy soil.

3.5 SOD AVAILABILITY AND CONDITION

- A. The Contractor shall satisfy himself as to the existing conditions prior to any construction. The Contractor shall be fully responsible to furnish and lay all sod required on the plans. He shall furnish new sod as specified above and lay it so as to completely satisfy the intent and meaning of the plans and specifications at no extra cost to the County.
- B. In the case of any discrepancy in amount of sod to be removed or amount to be used, it shall be the contractor's responsibility to report such to the Project Manager prior to commencing the work.
- C. Any condition of the sod that shall prevent it from being lifted shall also be reported to the Project Managers. This shall not relieve the Contractor of the responsibility of removing the sod necessary to complete the project.

3.6 SODDING

- A. Lay sod within 24 hours of harvesting. Do not lay sod if dormant or if ground is frozen or muddy. No sod shall be stored on the site for longer than two (2) days. Sod that becomes yellow, dry, or broken, shall be removed from the site by the Contractor at his expense.
- B. Lay sod to form a solid mass with tightly fitted joints. Butt ends and sides of sod; do not stretch or overlap. Stagger sod strips or pads to offset joints in adjacent courses. No partial strip or pieces will be accepted. Avoid damage to soil or sod during installation. Tamp and roll lightly to ensure contact with soil, eliminate air pockets, and form a smooth surface. Work sifted soil or

fine sand into minor cracks between pieces of sod; remove excess to avoid smothering sod and adjacent grass.

1. All work shall be done from boards laid on top of the prepared surface or on already laid sod. Care shall be taken to prevent foot prints or other disturbances to the prepared bed, other than absolutely necessary. Any such disturbances shall be promptly repaired so that the sod will be laid on a proper bed to insure the necessary bonding between it and the sod.
2. Lay sod across slopes exceeding 1:3.
3. Anchor sod on slopes exceeding 1:6 with wood pegs spaced as recommended by sod manufacturer but not less than two anchors per sod strip to prevent slippage.

C. Saturate sod with fine water spray within two hours of planting. See table below for recommended watering amounts for the first month after installation:

Week	1 st	2 nd	3 rd	4 th
How often to water	Every Day	Every Other Day	Every Third Day	Every Fourth Day
April	*			
May	*	1/3	1/2	2/3
June	1/4	1/2	2/3	3/4
July	1/4	1/2	2/3	3/4
August	1/4	1/2	3/4	1
September	*	1/3	1/2	2/3
October	*			
	*Apply ¼ of an inch as needed			

3.7 SOD LIFTING

- A. All sod shall be removed from areas of construction (i.e., where walks, concrete slabs, buildings, etc., will be built) prior to excavation and other operations or when sod lifting is specified.
- B. Prior to beginning to lift any large quantities of sod, the Contractor shall notify the Project Manager in sufficient time for notification of the Park Maintenance Personnel, so that they can schedule the removal of the sod from the site to lay at another park site.
- C. When the sod is to be used by the Park Maintenance Personnel, as specified on the plans, the sod pieces shall be cut by a mechanical sod cutter into uniform pieces with square comers. Individual pieces shall not exceed sixteen (16) inches wide and forty-eight (48) inches long or the current standards size of the sodding industry. All sod shall be cut to a thickness of no more than one and one-quarter (1-1/4) inches, but no less than the sodding industry standards.

3.8 TOP DRESSING

- A. All areas which are sodded shall be top dressed with the top dressing specified above during or at the end of the establishment period to fill in noticeable gaps between seams. The top dressing shall be first applied by spreading it over the sod and then carefully working it into the joints with a stiff brush or mat.
- B. All sodded areas shall be thoroughly watered after the top dressing is applied. Watering must be done carefully so as to avoid puddling or washing. Further work shall be curtailed until the area is dried sufficiently to allow sodding continuance without damage to already laid sod or the prepared bed.

3.9 TURF RENOVATION

- A. Renovate existing turf where indicated.
- B. Renovate turf damaged by Contractor's operations, such as storage of materials or equipment and movement of vehicles.
 - 1. Reestablish turf where settlement or washouts occur or where minor regrading is required.
 - 2. Install new planting soil as required.
- C. Remove sod and vegetation from diseased or unsatisfactory turf areas; do not bury in soil.
- D. Remove topsoil containing foreign materials, such as oil drippings, fuel spills, stones, gravel, and other construction materials resulting from Contractor's operations, and replace with new planting soil.
- E. Mow, dethatch, core aerate, and rake existing turf.
- F. Remove weeds before seeding. Where weeds are extensive, apply selective herbicides as required. Do not use pre-emergence herbicides.
- G. Remove waste and foreign materials, including weeds, soil cores, grass, vegetation, and turf, and legally dispose of them off County's property.
- H. Till stripped, bare, and compacted areas thoroughly to a soil depth of 6 inches.
- I. Apply soil amendments and initial fertilizer required for establishing new turf and mix thoroughly into top 4 inches of existing soil. Install new planting soil to fill low spots and meet finish grades.
- J. Water newly planted areas and keep moist until new turf is established.

3.10 TURF ESTABLISHMENT

- A. General: Maintain and establish turf by watering, fertilizing, weeding, mowing, trimming, replanting, and performing other operations as required to establish healthy, viable turf. Roll, re-grade, and replant bare or eroded areas and re-mulch to produce a uniformly smooth turf. Provide materials and installation the same as those used in the original installation.
 - 1. Fill in as necessary soil subsidence that may occur because of settling or other processes. Replace materials and turf damaged or lost in areas of subsidence.
 - 2. In areas where mulch has been disturbed by wind or maintenance operations, add new mulch and anchor as required to prevent displacement.

3. Apply treatments as required to keep turf and soil free of pests and pathogens or disease. Use integrated pest management practices whenever possible to minimize the use of pesticides and reduce hazards.
- B. Watering: Install and maintain temporary piping, hoses, and turf-watering equipment to convey water from sources and to keep turf uniformly moist to a depth of 4 inches.
 1. Schedule watering to prevent wilting, puddling, erosion, and displacement of seed or mulch. Lay out temporary watering system to avoid walking over muddy or newly planted areas.
 2. Water turf with fine spray at a minimum rate of 1 inch per week unless rainfall precipitation is adequate.
 3. The Contractor shall submit a watering schedule to the Project Manager.
 - C. Mow turf as soon as top growth is tall enough to cut, no higher than 3 inches. Repeat mowing to maintain specified height without cutting more than one-third of grass height. Remove no more than one-third of grass-leaf growth in initial or subsequent mowings. Do not delay mowing until grass blades bend over and become matted. Do not mow when grass is wet. Schedule initial and subsequent mowings to maintain the following grass height:
 1. Mow Kentucky bluegrass to a height of to 2 inches.
 - D. Turf Post-fertilization: Apply commercial fertilizer after initial mowing and when grass is dry.
 1. Use fertilizer that provides actual nitrogen of at least 1 lb/1000 sq. ft. to turf area.
 - E. Turf Establishment Service: Provided by skilled employees of landscape Installer. Maintain as required in "Acceptable Turf Establishment," article 3.11. Begin establishment services immediately after each area is planted and continue until acceptable turf is established, but for not less than the following periods:
 1. Seeded Turf: 60 days from date of planting completion.
 - a. When initial establishment period has not elapsed before end of planting season, or if turf is not fully established, continue establishment during next planting season.
 2. Sodded Turf: 30 days from date of planting completion.

3.11 ACCEPTABLE TURF ESTABLISHMENT

- A. The Contractor shall be responsible for all sodded and seeded areas during the Turf Establishment period. The Establishment Period shall begin at the time sodding or seeding for the entire project is completed and continues until all turf meets establishment criteria.
- B. Turf installations shall meet the following criteria as determined by the Project Manager before Acceptance of Turf and Substantial Completion will be issued in writing:
 1. Acceptable Seeded Turf: Turf Establishment shall be achieved when the turf is a healthy, uniform, close stand of grass, free of weeds and surface irregularities, with coverage exceeding 95 percent over any 10 square foot area and bare spots not exceeding 4 by 4 inches.
 2. Acceptable Sodded Turf: Turf Establishment shall be achieved when the turf is healthy, well-rooted, even-colored, viable turf, free of weeds, open joints, bare areas, and surface irregularities.
- C. Use specified materials to reestablish turf that does not comply with requirements, and continue maintenance until turf is satisfactory.
- D. Written notice requesting establishment inspection shall be submitted to the Project Manager at least three (3) days prior to the anticipated inspection date.

3.12 PESTICIDE/HERBICIDE APPLICATION

- A. Apply pesticides and other chemical products and biological control agents according to requirements of authorities having jurisdiction and manufacturer's written recommendations. Coordinate applications with County's operations and others in proximity to the Work. Notify Project Manager before each application is performed.
- B. Post-Emergent Herbicides (Selective and Nonselective): Apply only as necessary to treat already-germinated weeds and according to manufacturer's written recommendations.

3.13 CLEANUP AND PROTECTION

- A. Promptly remove soil and debris created by turf work from paved areas. Clean wheels of vehicles before leaving site to avoid tracking soil onto roads, walks, or other paved areas.
- B. Remove surplus soil and waste material, including excess subsoil, unsuitable soil, trash, and debris, and legally dispose of them off County's property.
- C. Erect temporary fencing or barricades and warning signs as required to protect newly planted areas from traffic. Maintain fencing and barricades throughout initial maintenance period and remove after plantings are established.
- D. Remove non-degradable erosion-control measures after grass establishment period.

3.14 BASIS OF MEASUREMENT AND PAYMENT:

- A. Payment for this work shall be by lump sum price listed on the schedule of values as "turf installation."
 - 1. Payments for materials and labor will be made once the turf establishment period has ended and is determined by the County in writing to have met all the requirements of this specification.

END OF SECTION

SECTION 33 05 20
BACKFILLING TRENCHES

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Trench backfill materials.
- B. Trench backfilling requirements.
- C. Surface restoration requirements.

1.2 DEFINITIONS

- A. Bedding: That surface of the Excavation or portion of the Pipe Zone below the pipe.
- B. Pipe Zone: That zone in a backfilling operation which supports, and surrounds the pipe barrel, and extends to 1 foot above the top of the pipe barrel.

1.3 SUBMITTALS

- A. Submit maximum laboratory dry density and optimum laboratory moisture content for:
 - 1. Subgrade material, and
 - 2. Each type of fill to be used.
- B. Upon OWNER's request, submit a written quality control Inspections and testing report describing source and field quality control activities performed by CONTRACTOR and its Suppliers.

1.4 QUALITY ASSURANCE

- A. Do not change material sources or aggregate without OWNER's knowledge.
- B. Reject backfill material that does not comply with requirements specified in this section.

1.5 STORAGE AND PROTECTION

- A. Storage:
 - 1. Safely stockpile backfill materials.
 - 2. Separate differing materials, prevent mixing, and maintain optimum moisture content of backfill materials.
- B. Protection:
 - 1. During installation or repair, plug end of pipe or fitting except when installing next section of pipe or fitting.
 - 2. Avoid displacement of and injury to Work while compacting or operating

equipment.

3. Movement of construction machinery over Work at any stage of construction is solely at CONTRACTOR's risk.

1.6 SITE CONDITIONS

- A. Do not place, spread, or roll any backfill material over material that is damaged by water. Remove and replace damaged material at no additional cost to OWNER.
- B. Control traffic and erosion. Keep area free of trash and debris. Repair settled, eroded, and rutted areas.
- C. Reshape and compact damaged structural section to required density.
- D. Restore any damaged structure to its original strength and condition.
- E. Replace contaminated backfill at no additional cost to OWNER.

1.7 ACCEPTANCE

- A. General:
 1. Native material may be wasted if there is no additional cost to substitute material acceptable to OWNER.
- B. Trench Backfilling: One test per Lot.

Table 1: Lot Size for Trench Backfilling Operation		
Material	Test Criteria	Lot size
Subgrade	Standard (a)	200 lineal feet
Common Fill	Standard (a)	200 lineal feet per lift 25 square feet of footing area per lift
Crushed Aggregate Base	Modified (a)	200 lineal feet per lift 25 square feet of footing area per lift
Flowable Fill	Strength (b)	50 cubic yards
NOTES (a) Proctor density, Section 33 05 05 (b) Compressive strength, Section 31 05 15 (c) Lift thickness above the pipe zone before compaction, 8 inches.		

1.8 WARRANTY

- A. Any settlement noted in Trench backfill or in structures built over the Trench backfill will be considered to be caused by improper compaction methods and shall be corrected at no cost to the OWNER.

- B. Restore structures damaged by settlement at no additional cost to OWNER.

PART 2 PRODUCTS

2.1 BACKFILL MATERIALS

- A. Common fill
- B. Crushed aggregate base
- C. Cement treated fill
- D. Slag or asphalt bearing material not allowed.

2.2 ACCESSORIES

- A. Water: Make arrangements for sources of water during construction and make arrangements for delivery of water to site. Comply with local Laws and Regulations at no additional cost to OWNER when securing water from water utility company.
- B. Geotextile Fabric
- C. Identification Tape: Permanent, bright-colored, continuous-printed magnetic plastic tape, intended for direct-burial service; not less than 6 inches wide by 4 mils thick. The tape shall read "CAUTION: BURIED INSTALLATION BELOW". Color of tape as follows.
 - 1. Red: Electric power lines, cables, conduit and lighting cables
 - 2. Yellow: Gas, oil, steam, Petroleum or gaseous materials
 - 3. Orange: Communications, alarm, signal, cables or conduits.
 - 4. Blue: Potable water
 - 5. Purple: Reclaimed Water, irrigation and slurry lines
 - 6. Green: Sewer and storm drain lines

PART 3 EXECUTION

3.1 PREPARATION

- A. Verify backfill material meets gradation requirements, foundation walls are braced to support surcharge forces imposed by backfilling operations, areas to be backfilled are free of debris, snow, ice or water, and Trench bottom is not frozen.
- B. If Subgrade is not readily compactable secure written authorization for extra excavation and backfill
- C. Avoid injuring and displacement of pipe and structures while compacting soil or operating equipment next to pipeline.
- D. Place geotextile fabrics

3.2 GENERAL BACKFILLING REQUIREMENTS

- A. Protect Subgrade from desiccation, flooding and freezing.
- B. Do not damage corrosion protection on pipe.
- C. Repair or replace damaged pipe at no additional cost to OWNER.

- D. Withdraw sheathing, Shoring, piles, and similar supports as backfilling progresses. Backfill and compact all holes left by removals.
- E. Provide sufficient water quality facilities to protect downstream fish and wildlife, and to meet State water quality requirements.
- F. Water settling of Trench backfill is not permitted. "Jetting" of Trench backfill is prohibited.

3.3 PIPE ZONE

- A. Maintain uniform foundation along barrel of pipe with sufficient relief for joint connections.
- B. Use backfill materials meeting pipe manufacturer's recommendations.
- C. Maximum backfill particle size is 3/4 inch for plastic pipe.
- D. Do not permit free fall of backfill material which may damage pipe, pipe finish, or pipe alignment.
- E. Except where piping must remain exposed for tests, fill Pipe Zone as soon as possible.

3.4 TRENCH ABOVE PIPE ZONE.

- A. Maximum lift thickness before compaction is 8 inches.
- B. Fill unauthorized Excavations with material acceptable to OWNER at no additional cost to OWNER.
- C. Do not damage adjacent structures or service lines.
- D. Install continuous plastic line marker directly over buried lines 18 inches below finished grade.

3.5 MODIFIED BACKFILL LAYER METHOD

- A. At discretion of CONTRACTOR, backfill may be placed in thicker layers than indicated above subject to the following provisions.
 - 1. CONTRACTOR proves the ability of proposed method to achieve specified average compaction density.
 - 2. OWNER, on the basis of test results, approves the system in writing.
- B. Should CONTRACTOR find it necessary to change the method or any part of it, including the source of material, or the rate of placing the material, obtain approval of OWNER, who may require a further trial area.
- C. If testing shows a previously approved system is no longer producing the required degree of compaction, make changes to comply.
- D. Where vibration effects are creating environmental problems, make changes to eliminate problems.

3.6 COMPACTION

- A. Compact backfill
 - 1. A-1 soils: 95 percent or greater of a Modified Proctor Density.
 - 2. Other soils: 95 percent or greater of a Standard Proctor Density.

3.7 SURFACE RESTORATION

- A. Provide temporary paved surfaces where Trenches pass through roadways, Driveways or sidewalks.
- B. Restore paved surfaces
- C. Finish landscaped surfaces with grass, Section 32 92 00

3.8 CLEANING

- A. Remove stockpiles from the site. Grade site surface to prevent free standing surface water.
- B. Leave borrow areas clean and neat.

END OF SECTION

SECTION 33 11 00
WATER DISTRIBUTION AND TRANSMISSION

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Water distribution and transmission system identification, valves, boxes, service connections and accessories.
- B. This section is applicable to potable and non-potable water pressure systems.

1.2 REFERENCES

- A. ACPA: American Concrete Pipe Association.
- B. Applicable water company requirements.
- C. AWWA C600: AWWA Standard for Installation of Ductile-Iron Water Mains and Their Appurtenances.
- D. AWWA C605: AWWA Standard for Underground Installation of Polyvinyl Chloride (PVC) Pressure Pipe and Fittings for Water.
- E. AWWA C800: AWWA Standard for Underground Service Line Valves and Fittings.
- F. AWWA M11: AWWA Manual for Steel Pipe - Design and Installation.
- G. CDA: Copper Development Association.

1.3 PERFORMANCE REQUIREMENTS

- A. Depth of Cover:
 - 1. 48 inches minimum to top of pipe, service line, or as indicated in local building code. 72 inches maximum unless ENGINEER authorizes otherwise.
 - 2. If less cover, provide additional protection to withstand frost and external loads.
- B. Remove any section of pipe already placed that is found to be defective or damaged. Relay or replace without additional cost to OWNER.

1.4 SUBMITTALS

- A. Product Data: Submit manufacturer's technical product data and installation instructions.
- B. Commissioning: Submit testing data
- C. Record Documents: Include details of underground structures, connections, thrust blocks and anchors. Show interface and spatial relationship between piping and adjacent structures.
- D. Operating and Maintenance: Include maintenance data, parts lists, product data, and shop drawings.

1.5 SITE CONDITIONS

- A. Minimize neighborhood traffic interruptions. Barricade stockpiles.

- B. Secure acceptance of pipeline lateral tie-in work.
- C. Repair public and private facilities damaged by CONTRACTOR.
- D. Do not turn on or turn off any valve outside of the Work prior to securing ENGINEER's or water company's permission.

PART 2 PRODUCTS

2.1 PIPES AND FITTINGS

- A. Provide piping materials and factory fabricated piping products of sizes, types, pressure ratings, and capacities indicated. Use only NSF approved products in drinking water systems. All such products shall be appropriately stamped with the NSF logo.
- B. Where not indicated, provide proper selection as determined by installer and acceptable to ENGINEER to comply with installation requirements.
- C. Provide sizes and types of equipment connections for fittings of material that matches pipe material used in the piping system. Where more than one type of material or product Option is indicated, selection is installer's choice.
- D. Provide pipe fittings and accessories of same material and weight or class as pipe, with joining method indicated or recommended by manufacturer.

2.2 VALVE BOX

- A. Buried Valves In Traffic Areas: 2 piece, cast iron, screw adjustable sleeve, 5 - 1/4 inch shaft, with a drop lid.
- B. Buried Valves in Non-traffic Areas: Slip type of height required for the installation.
- C. Markings: On cover of valve box, cast the appropriate utility lettering.

2.3 VALVE CHAMBER

- A. General: Refer to applicable design criteria requirements explained in Laws and Regulations.
- B. Basin: Class 4000 concrete floor and walls.
- C. Steps: Plastic, cast into sidewalls greater than 4 feet deep.
- D. Top: Flat slab class 4000 concrete.
- E. Frame and Cover: Scoriated asphalt coated, heavy duty ductile iron with flat top design and appropriate utility lettering. Shape and size as indicated.

2.4 MORTAR, GROUT, AND CONCRETE

- A. Mortar
- B. Grout
- C. Concrete:
 - 1. Cast-in-place: Class 4000
 - 2. Precast: Class 5000

2.5 TAPPING SADDLES

- A. Provide bronze alloy, ductile iron, or stainless steel saddles with stainless steel double straps.
- B. Provide tapping saddles that have a minimum rated working pressure of 300 psi, neoprene gaskets, and bronze tapered threads.

2.6 SERVICE CONNECTION

- A. Type K copper pipe; with flare type 200 psi compression fittings in accordance with AWWA C800. If materials used in main line are non-copper, provide a plastic nipple to separate the metals.

2.7 ACCESSORIES

- A. Bolts, Nuts, Washers
- B. Anchorages: Provide anchorages for tees, wyes, crosses, plugs, caps, bends, valves, and hydrants. After installation, apply full coat of asphalt or other acceptable corrosion-retarding material to surfaces of ferrous anchorages.
- C. Corporation Stops: All bronze with tapered threads.
- D. Hydrant and Valve: Dry barrel
- E. Water Meter and Valve
- F. Grease: Non-oxide.
- G. Polyethylene Sheet: 8 mil thick.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify Trench Excavation is ready to receive work, and dimensions, and elevations are as indicated.
- B. Commencing installation means acceptance of existing conditions.

3.2 PREPARATION

- A. Hand trim to required elevations.
- B. Correct over excavations.
- C. Remove stones or other hard matter that could damage pipe embedment or impede backfilling or compaction.
- D. Examine areas and conditions under which materials and products are to be installed. Do not proceed with system installation until unsatisfactory conditions have been corrected in manner acceptable to system installer.
- E. Clearly identify and promptly set aside defective or damaged pipe. E. Use pipe cutting tool acceptable to pipe manufacturer.

3.3 LOCATING POTABLE WATER PIPE

- A. Comply with Utah Drinking Water Act. As a minimum locate potable water pipe at least 18 inches vertical and 10 feet horizontal edge to edge between water and sewer lines. Place water lines above sewer line.

- B. Where potable water pipe crosses under gravity-flow sewer lines, fully encase the sewer pipe in concrete for a distance at least 10 feet each side of the crossing.
 - 1. Do not locate any joint in the water line within 36 inches of the crossing.
 - 2. Encase water line if it is within 24 inches of a sewer force main or inverted syphon.
 - 3. Encase sewer main joints in concrete if joints are horizontally closer than 36 inches to the water line.
- C. Do not put potable water lines in the same Trench with sewer lines, storm drains or electric wires.

3.4 INSTALLATION - PIPE AND FITTING

- A. General:
 - 1. Seal each open end of pipeline at end of day's work.
 - 2. Grease all bolts and nuts then apply polyethylene sheet and tape wrap.
- B. Steel Pipe: AWWA M11.
- C. Ductile Iron Pipe: AWWA C600.
- D. Copper Tube: CDA "Copper Tube Handbook".
- E. Polyethylene Pipe: For 3 inches and smaller pipe follow AWWA C901. Install all other sizes per manufacturer's installation instructions.
- F. Polyvinyl Chloride Pipe: AWWA C605.
- G. Concrete Pipe: ACPA "Concrete Pipe Handbook".
- H. Wedges: Install metal wedges on all metal pipe systems.

3.5 INSTALLATION – CONCRETE THRUST BLOCKS

- A. Do not make hydrostatic tests until thrust block concrete has cured for at least 5 days.
- B. Provide thrust blocks on all plugs, caps, tees, hydrants and vertical or horizontal bends.
- C. Provide stainless steel or epoxy coated steel tie rods and clamps or shackles to restrain thrust.
- D. Unless otherwise indicated or directed by ENGINEER, place the base and bearing sides of thrust blocking directly against undisturbed earth.
- E. Sides of thrust blocking not subject to thrust may be placed against forms. Place thrust blocking so the fitting joints will be accessible for repair.

3.6 INSTALLATION - VALVES AND VALVE BOXES

- A. Valves:
 - 1. Ensure all parts are in working order.
 - 2. Set location of valves outside of sidewalk limits, Driveway Approaches and other pedestrian or vehicular interference.
 - 3. Install plumb with stems pointing up.
 - 4. Grease all exposed bolts and nuts then apply polyethylene sheet and tape wrap.
- B. Valve Boxes:

1. Set over valve nut so operator's key is plumb with clearance in valve box when opening and closing the valve.
2. Adjust box to finish grade.
3. Clean all dirt or foreign material out of box.

3.7 INSTALLATION – TAPS

- A. Apply for and pay for applicable permits from water company for the indicated size and location of tap to water main. Comply with all connection requirements of water company.
- B. Make all service taps with a tapping machine acceptable to the water company. Use teflon tape on all taps unless indicated otherwise.
- C. The minimum distance between taps is 24 inches, with a 5 degree stagger. Do not make service taps within 24 inches of the end of pipe. Install taps at 60 degrees from vertical, or authorized by ENGINEER.
- D. Service saddles are required on all taps except, 3/4 inch or 1" taps to new ductile iron pipe
- E. Grease all exposed bolts and nuts then apply polyethylene sheet and tape wrap.

3.8 INSTALLATION – SERVICE LINES

- A. Replacing Existing Water Service Line:
 1. Follow AWWA C800, Utah public drinking water regulations and Utah plumbing code requirements.
 2. When replacing water service lines, replace non-copper pipe with type K copper pipe.
- B. Looping Existing Water Service:
 1. Minimum pipe diameter 3/4 inch.
 2. Pinching tools used to close and open service lines may be used only if allowed by ENGINEER. When service line pinches cannot be returned to previous shape or flow, remove and replace damaged portion of pipe.
 3. Soldered joints or connections not allowed.
 4. For copper to iron connections use a brass pack joint compression coupling with joint locking device.
 5. For copper- to- copper connections use a brass flare coupling.
 6. Follow details shown in the Drawings.
- C. Meter Box: Install meter boxes back of the curb, outside of sidewalks and Driveway Approaches and outside of other pedestrian and vehicular interference.

3.9 INSTALLATION – WATER MAIN LOOP (SYPHON)

- A. Existing water mains may not match standard size. Excavate to obtain actual pipe diameter and match size.
- B. Do not shutdown pipeline until couplings and fittings are on site.
- C. Coordinate shutdown with water company.
- D. Connections to steel or transite pipe requires transition couplings or sleeves with

transition gaskets.

- E. Grease all exposed bolts and nuts then apply polyethylene sheet and tape wrap
- F. Provide thrust blocks except where joints are welded. Follow details shown on the Drawings.

3.10 DISINFECTION

- A. Disinfect per local governing requirements.
- B. After disinfection, legally dispose of disinfection water.

3.10 BACKFILLING

- A. Prior to Backfilling:
 - 1. Secure ENGINEER's acceptance of brass wedge installations and concrete thrust block installations.
- B. Trenches
- C. Landscapes

3.11 SURFACING RESTORATION

- A. Roadway Trenches and Patches
- B. Landscapes

END OF SECTION

SECTION 33 31 00
SANITARY SEWERAGE SYSTEMS

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Gravity sanitary sewerage systems.

1.2 REFERENCES

- A. ASTM C 478: Standard Specification for Precast Reinforced Concrete Manhole Section.
- B. ASTM C 891: Standard Practice for Installation of Underground Precast Concrete Utility Structures.
- C. ASTM C 923: Standard Specification for Resilient Connectors Between Reinforced Concrete Manhole Structures, Pipes and Laterals.

1.3 PERFORMANCE REQUIREMENTS

- A. Vertical Cover: Unless indicated otherwise, 2 feet minimum for laterals and 4 feet when subjected to light construction equipment loads.
- B. Remove any section of pipe already placed that is found to be out of alignment tolerance indicated, defective, or damaged. Relay or replace at no additional cost to OWNER.

1.4 PROJECT CONDITIONS

- A. Minimize neighborhood traffic interruptions. Barricade stockpiles.
- B. Provide access to adjacent properties for local traffic and pedestrians.
- C. Repair public and private facilities damaged by CONTRACTOR.

PART 2 PRODUCTS

2.1 PIPING AND FITTINGS

- A. Provide piping materials and factory fabricated piping products of sizes, types, and classes indicated.
- B. Where not indicated, provide proper selection acceptable to OWNER to comply with installation requirements.
- C. Provide pipe fittings and accessories of same material and weight or class as pipe, with joining method indicated or recommended by manufacturer.

2.2 CONCRETE

- A. Concrete:
 - 1. Cast-in-place: Class 4000

2. Precast: Class 5000

2.3 MANHOLES

- A. Basin: Precast concrete, ASTM C 478.
- B. Steps: None.
- C. Top: Concentric cone. Concentric flat slab concrete deck allowed only with OWNER's permission.
- D. Frame and Cover: Scoriated, asphalt coated, heavy duty, ductile iron; Section 05 56 00 with flat top design meeting load rating H-20 and appropriate utility lettering. Shape, size and lifting device as indicated.
- E. Pipe Connectors: Resilient, ASTM C 923. Sand mortar grout pipe connections.
- F. Joints in Sections: Bituminous mastic gasket-type sealant unless indicated otherwise.

PART 3 EXECUTION

3.1 PREPARATION

- A. Verify Trench Excavation is ready to receive work, and dimensions, and elevations are as indicated.
- B. Hand trim Excavations to required elevations. Backfill over excavations and compact.
- C. Examine areas and conditions under which materials and products are to be installed. Do not proceed with system installation until unsatisfactory conditions have been corrected in manner acceptable to system installer.
- D. Clearly identify and promptly set aside defective or damaged pipe.
- E. Use pipe cutting tool acceptable to pipe manufacturer.

3.2 INSTALLATION - PIPE AND FITTINGS

- A. Place bell or groove end facing upstream.
- B. Install gaskets per manufacturer's recommendations.
- C. Plug leakproof such pipeline branches, stubs or other open ends which are not to be immediately connected.
- D. Clean interior of pipe of dirt and debris as work progresses.

3.3 INSTALLATION – MANHOLES

- A. Form bottom of Excavation clean and smooth to correct elevation.
- B. Place structures in location indicated.
- C. Install precast units, ASTM C 891.
- D. Provide elevations and pipe inverts for inlets and outlets indicated.
- E. When structures occur in Pavements, mount frame and cover 1/2 inch below finished surface, elsewhere set 2 inches above finished grade. Provide a concrete Cover Collar between the frame and asphalt Pavement.

3.4 ABANDONED UTILITIES

- A. Plug and cap with concrete all open ends of abandoned underground utilities which are to remain in place.
- B. Provide closure to withstand hydrostatic or earth pressure which may result after ends of abandoned utilities have been closed.

3.5 TAP CONNECTIONS - 6 INCHES AND SMALLER

- A. Field cutting into new or existing piping will not be permitted unless written permission is obtained from Owner.
- B. Make connections to existing pipe and underground structures, so connections will conform as nearly as practicable to requirements specified for new work.
- C. Use commercially manufactured wyes for branch connections. Spring wyes into existing line and encase entire wye, plus 6 inches overlap, with not less than 6 inches of concrete.
- D. For taps into existing 24 inches or larger piping, or to underground structures, cut opening into unit sufficiently large to allow 3 inches of concrete to be packed around entering connection. Cut ends of connection passing through pipe or structure wall to conform to shape of and parallel with inside wall, unless otherwise indicated. Grout connection to provide smooth transition inlet into pipe.

3.6 TAP CONNECTIONS - LARGER THAN 6 INCHES

- A. Not allowed. Provide a Manhole structure.

3.7 JOINTS

- A. Join pipe per manufacturer's recommendation or as indicated.
- B. Joining Pipe of Different Sizes: At Manholes only.
- C. Use neoprene couplings with stainless steel bands to make connections between dissimilar pipe, or where standard pipeline joints are impractical.

3.8 BACKFILLING

- A. Prior to Backfilling: Commission pipeline, Section 33 08 00. Provide sizes and types of equipment connections and fittings which match pipe materials when pressure testing system.
- B. Trenches: Section 33 05 20.

3.9 CLEANING

- A. Remove debris, concrete, or other extraneous material which accumulates in existing pipes or structures.
- B. Clean all pipelines after testing. Do not flush sand, gravel, concrete, debris or other materials into existing piping system.

3.10 SURFACE RESTORATIONS

- A. Provide temporary paved surfaces where Trenches pass through roadways, Driveways, or sidewalks.
- B. Finish landscaped surfaces per Section
 - 1. With grass, Section 32 92 00

END OF SECTION

SECTION 02 41 19

SELECTIVE DEMOLITION AND REPAIR

PART 1 GENERAL

1.1 SUMMARY

- A. This Section includes:
 - 1. Complete demolition and removal of existing facility including footings and associated paving not indicated to remain. Remove utilities and cap outside the extents of the new construction. Identify location of capped utilities. Protect all existing features indicated to remain.
 - 2. Protect existing paving indicated to remain.
 - 3. Protect existing turf and irrigation systems indicated to remain and retain irrigation operation from April through October.
 - 4. It is the responsibility of the contractor to define the limits of demolition necessary and repair / patch to provide final construction required.
 - 5. Coordinate work to remain with Architect and Owner's representative.
 - 6. Investigate existing conditions to determine best routing for power and sanitary sewer lines.

1.2 DEFINITIONS

- A. Remove and Salvage: Detach items from existing construction and roll/palletize items to be returned to owner. Deliver items to owner.
- B. Remove: Detach items from existing construction and legally dispose of them off-site unless indicated to be removed and salvaged or removed and reinstalled.
- C. Remove and Reinstall: Detach items from existing construction, prepare for reuse, and reinstall where indicated.
- D. Existing to Remain: Existing items of construction that are not to be permanently removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.3 PRE-INSTALLATION MEETINGS

- A. Pre-demolition Conference: Conduct conference at Project site.

1.4 SUBMITTALS

- A. Pre-demolition photographs

1.5 FIELD CONDITIONS

- A. Owner will occupy portions of site immediately adjacent to selective demolition area for ongoing operations. Conduct selective demolition so Owner's use of adjacent site will not be disrupted.

- B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
- C. Notify Owner of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- D. Hazardous Materials: refer to "Asbestos Survey Report"
- E. Storage or sale of removed items or materials on-site is not permitted.
- F. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
 - 1. Maintain irrigation services from April through October.

PART 2 PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Contractor is responsible for obtaining approvals from applicable agencies for demolition and for service termination or temporary disconnect (e.g. SLCO Health Department, State of Utah Div. of Environmental Quality, Rocky Mountain Power, sewer district, water district).
- B. Regulatory Requirements: Comply with hauling and disposal regulations of authorities having jurisdiction.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped before starting selective demolition operations.
- B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- C. If unanticipated electrical, mechanical, fire sprinkler or structural elements conflict with intended design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Owner.
- D. Survey of Existing Conditions: Record existing conditions by use of preconstruction photographs.

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage. These systems may be modified as part of the work.
 - 1. Plumbing Systems
 - 2. Electrical Service and conduit.
 - 3. Irrigation Systems

3.3 PREPARATION

- A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with occupied adjacent areas of the ballfields, adjacent parking and other adjacent facilities.

3.4 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by closely examining all existing conditions. Use methods required to complete the Work within limitations of governing regulations and as follows:
 - 1. Neatly cut elements plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools minimize disturbance of adjacent surfaces.
 - 2. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 - 3. Do not use cutting torches.
 - 4. Dispose of demolished items and materials promptly.
- B. Removed and Reinstalled Items:
 - 1. Clean and repair items to functional condition adequate for intended reuse.
 - 2. Protect items from damage during transport and storage.
- C. Existing Items to Remain: Protect existing construction indicated to remain against damage and soiling during selective demolition. Temporarily support as necessary. Reconstruct permanent supports that are altered to comply with all code requirements.

3.5 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Except for items or materials indicated to be reused, salvaged or reinstalled, remove demolished materials from Project site and legally dispose of them in an EPA-approved landfill or recycling facility.
 - 1. Do not allow demolished materials to accumulate on-site.
 - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
- B. Burning: Do not burn demolished materials.

3.6 CLEANING

- A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION