

Intermountain Classic Air Medical / Bid Questions

Note: Responses are preliminary until issued by addendum. Questions must be submitted before 5:00 p.m., Tuesday, Nov. 8

Date	Question	Response
11/2/2022	Demo page ED205, between lines C & D, on both ends of the drawing, shows recessed cans with dotted lines which would indicate demolition. On page EL 105, those same conference rooms show the same dotted line recessed cans. It shows no new lighting for those rooms. Maybe the conference rooms keep the existing recessed cans?	Light fixtures will not be replaced in the existing conference rooms or in the soffits immediately outside of the conference rooms. The recessed cans in question are existing to remain, even though the outer line looks dashed.
11/3/2022	Is the AV system to be included in our scope, if so please provide specification for this and preferred vendor	Yes, it is included in the General Contract. Spec section 274113 (Audio Systems) is added by addendum #1; sections 274115 (Video Systems) and 274116 (Control Systems) are already included in the specifications. The owner's preferred AV vendors are Marshall Industries and CVE Multi-media
11/3/2022	Please clarify what is being requested on sheet ET601 with the photo of the penthouse	Provide conduit as required for the antenna system. Refer to updated sheet ET601.
11/3/2022	Please provide required rough in details for access control on drawings EY105	Provide 1" conduit to the card reader location and door frame stubbed to accessible ceiling. Coordinate any additional requirements with the security installers (Accent Automatics).
11/3/2022	Is access control included in our scope if so please provide specification and preferred vendor	All security installation will be completed by Accent Automatics.
11/3/2022	Are the panels UU5LB and L5 new or existing	Panel U5LB is new. Panel L5 is existing. Refer to the updated addendum drawings.
11/3/2022	What fixture type will be installed in storage room 515 not identified nor lighting control	Fixture types T24 have been added in this room.
11/3/2022	What is the current light control system manufacturer so we can match existing controls	Existing lighting controls are Acuity Sensor Switch.
11/3/2022	Is the sound system included our scope, please provide specs and preferred vendor.	Yes, it is included in the General Contract. Spec section 274113 (Audio Systems) is added by addendum #1; sections 274115 (Video Systems) and 274116 (Control Systems) are already included in the specifications. The owner's preferred AV vendors are Marshall Industries and CVE Multi-media

11/7/2022	Is there an addendum coming out?	Yes. There will be an addendum coming early this week.
11/7/2022	I don't see a one-line for the power. It shows two panel schedules. I don't know if they are new or existing. I think panel L5 is existing and panel U5LB is new. I don't see where they are being fed from?	Panel U5LB is new. Panel L5 is existing. Refer to the updated addendum drawings.
11/7/2022	are we to provide the UPS and the Maintenance bypass along with Panel U5lb?	The UPS and maintenance bypass are owner furnished, contractor installed.
11/7/2022	In the new data room if we are supplying U5LV panel and where to pull that feed from also the UPS and UPS by panel don't have enough info. It shows that on EP105 D1 upper left-hand corner.	Panel U5LB is new. Panel L5 is existing. Refer to the updated addendum drawings.
11/7/2022	We need sizes for the Fry Reglet L trim and F reveal mold. Sub is asking for more information.	Size for 3/4" thick millwork panels. See https://fryreglet.com/millwork-trims/ for additional dimensions for these trims.
11/8/2022	In the spec. it calls for double wall duct where there is no ceilings. Section 233113-11 / 3.10 B. That would make all the duct between grid lines 3 through 5 as double wall duct. Is this really what they want in this area? The cost will be triple the price. And if they do want double wall duct what would be the outside dimensions?	There are ceilings in all of the area of work. Refer to Reflected Ceiling Plans on sheets A151.2 and A151.3