

XERFLOW 3000-AL PRODUCT DATA SHEET

XERFLOW 3000-AL is a low-cement castable for service temperatures up to 3000°F, and up to 2200°F in non-wetting applications.

Recommended Service Temperature	3000°F (non-wetting 2200°F)		
Water Required for Mixing (as a % of weight)	7.5 – 8.5 %		
Material Required Per Cubic Foot	140 - 148 lbs.		
Packaging	64 - 55lb bags /pallet		
	1,000+lb Super Sacks		

TYPICAL CHEMICAL ANALYSIS

Al ₂ O ₃	SiO ₂	CaO	TiO ₂	Fe ₂ O ₃
50 - 54	37 - 41	3.0 - 3.4	1.7 - 2.1	0.7 - 1.0

TYPICAL PHYSICAL PROPERTIES

Test Temperature (°F)	Bulk Density (pcf)	C.C.S. (psi)	CMOR (psi)	Apparent Porosity (%)	Permanent Linear Change (%)
220	144 - 150	7000	1600	12 - 16	Nil
1500	143 - 149	7000	1600	14 - 17	-0.2 to 0.0
2000	141 - 147	7000	1600	17 - 20	-0.3 to 0.0
2732	135 - 142	9000	1800	15 - 18	+1.0 to +2.0

Xertech Specialties 1422 Hoelzer Ct. Dailey Industrial Park Pacific, MO 63069 Ph: (636)271-0586; Fax: (636)271-0587 www.xertechllc.com mail@xertechllc.com

Rel 12-14