

# THE ENSOLTIS CORPORATION SOLAR HEAT GAIN COEFFICIENT TEST REPORT

**SCOPE OF WORK**

NFRC 201-2020 TESTING ON ENSOLCOMP THERMAL PANEL

**REPORT NUMBER**

M6515.01-301-41 R0

**TEST DATE**

10/14/21

**ISSUE DATE**

11/02/21

**REVISED DATE**

11/15/21

**RECORD RETENTION END DATE**

10/14/26


**PAGES**

12

**DOCUMENT CONTROL NUMBER**

RTTDS-R-AMER-Test-2953 (06/26/18)

©2017 INTERTEK



**TEST REPORT FOR THE ENSOLTIS CORPORATION**

Report No.: M6515.01-301-41 R1

Date: 11/15/21

**REPORT ISSUED TO**

**THE ENSOLTIS CORPORATION**

15205 Road 28-1/2

Madera, CA 93638

**SECTION 1**

**SCOPE**

Architectural Testing, Inc. (an Intertek company) dba Intertek Building & Construction (B&C) was contracted by The ENSOLTIS Corporation to perform testing in accordance with NFRC 201-2020 on their Ensolcomp Thermal Panel, Ensolcomp Thermal Panel System. Results obtained are tested values and were secured by using the designated test method. Testing was conducted in full compliance to NFRC standards at the Intertek B&C test facility in Fresno, California.

Unless differently required, Intertek reports apply the "Simple Acceptance" rule also called "Shared Risk approach," of ILAC-G8:09/2019, Guidelines on Decision Rules and Statements of Conformity.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

For INTERTEK B&C:

**COMPLETED BY** Jerry Bontilao, BSME

**TITLE** Project Lead

**SIGNATURE**

**DATE** 11/15/21

**REVIEWED BY** Tyler Westerling, P.E.

**TITLE** Operations Manager, IIRC

**SIGNATURE**

**DATE** 11/15/21

JB:ss

---

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

**TEST REPORT FOR THE ENSOLTIS CORPORATION**

Report No.: M6515.01-301-41 R1

Date: 11/15/21

**SECTION 2**

**SUMMARY OF TEST RESULTS**

<b>Type:</b>	Ensolcomp Thermal Panel System
<b>Series/Model:</b>	Ensolcomp Thermal Panel
<b>Unit Size:</b>	84" x 84" (2133.6 mm x 2133.6 mm) (Model Size)
<b>Solar Heat Gain Coefficient (SHGC):</b>	0.04

**SECTION 3**

**TEST SPECIMEN SUMMARY**

<b>SERIES/MODEL</b>	Ensolcomp Thermal Panel
<b>TYPE</b>	Ensolcomp Thermal Panel System
<b>OVERALL SIZE</b>	84" x 84" (2133.6 mm x 2133.6 mm) (Model Size)
<b>NFRC STANDARD SIZE</b>	78.7" x 78.7" (2000 mm wide x 2000 mm high)
<b>GROUPING:</b>	N/A
<b>TEST SAMPLE SUBMITTED BY</b>	Client
<b>TEST SAMPLE SUBMITTED FOR</b>	Not Applicable

**SECTION 4**

**TEST METHOD**

The specimens were evaluated in accordance with the following:

*NFRC 201-2020, Interim Standard Test Method for Measuring the Solar Heat Gain Coefficient of Fenestration Systems Using Calorimetry Hot Box*

**SECTION 5**

**MATERIAL SOURCE/INSTALLATION**

Test samples were provided by The ENSOLTIS Corporation. Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by Intertek B&C for a minimum of five years from the test completion date.

The specimen was installed into an extruded polystyrene foam panel with an R-value of 18 using silicone caulking.

**TEST REPORT FOR THE ENSOLTIS CORPORATION**

Report No.: M6515.01-301-41 R1

Date: 11/15/21

**SECTION 6  
EQUIPMENT**

Testing was performed in the 84 inch Solar Calorimeter, ICN# 62061, located at 2524 East Jensen in Fresno, California, near the northeast corner of the lot and elevated approximately 15 feet from ground level. The foreground is desert and industrial buildings; the background is industrial buildings.

**Calibration Information for the 84 inch Calorimeter, ICN 62061:**

ICN/ASSET #	DESCRIPTION	LAST CALIBRATION DATE
4059	Moving Pyranometer	12/03/20
INT00175	Flowmeter	02/23/21

**SECTION 7  
LIST OF OFFICIAL OBSERVERS**

NAME	COMPANY
Jerry A. Bontilao	Intertek B&C

**TEST REPORT FOR THE ENSOLTIS CORPORATION**

Report No.: M6515.01-301-41 R1

Date: 11/15/21

**SECTION 8****TEST PROCEDURE**

Tracking system azimuth and altitude are read every minute and the calorimeter is moved to a position normal to the sun from chart stored in computer. The foreground is desert, the background is industrial buildings. Output was determined with flat characterization plate in place.

This test method does not include separate procedures to determine the heat flows due to either air movement or nighttime U-factor effects. As a consequence, the SHGC results obtained do not reflect the overall performance which may be found in field installations due to temperature differences, wind, shading, air leakage effects, and the thermal bridge effects specific to the design and construction of the fenestration system opening.

Since there is a wide variety of fenestration system openings in residential, commercial and industrial buildings, it is not feasible to select a "typical" surround panel construction in which to mount the fenestration test specimen. The selection of a relatively high thermal resistance surround panel places the focus of the test on the solar performance of the system. Therefore, it should be recognized that the solar heat gain coefficient results obtained from this test method, for ideal laboratory conditions in a highly insulating surround panel, should only be used for fenestration product comparisons or as input to performance analyses which also include thermal, air leakage and thermal bridge effects due to the surrounding building structure. To determine air leakage effects for windows and doors, refer to Test Method ASTM E283. For thermal transmittance refer to Test Method ASTM C 1199.

Ratings included in this report are for submittal to an NFRC-licensed IA for certification purposes and are not meant to be used for labeling purposes. Only those values identified on a valid Certificate of Authorization (CA) are to be used for labeling purposes.

**TEST REPORT FOR THE ENSOLTIS CORPORATION**

Report No.: M6515.01-301-41 R1

Date: 11/15/21

**SECTION 9**

**TEST SPECIMEN DESCRIPTION**

<b>MANUFACTURER</b>	The Ensoltis Corporation
<b>PRODUCT TYPE</b>	Ensolcomp Thermal Panel System
<b>SERIES/MODEL</b>	Ensolcomp Thermal Panel
<b>OVER-ALL UNIT SIZE</b>	84" x 84" (2133.6 mm x 2133.6 mm) (Model Size)

**CONSTRUCTION \***

The Ensolcomp Thermal Panel System consisted of one layer of 15/32" CDX Plywood, one layer of synthetic roofing underlayment meeting ICC-ES AC 188, one layer of 2 1/8" thick Ensolcomp Thermal Panel fastened to deck with 3" cap nails, two layers of 30 lb. ASTM roofing felt, one layer of 30-year dimensional shingles meeting ASTM D 3462 fastened to roof deck with 3 1/2" roofing nails.

**Heat Flow Summary**

	1	2	3	4	
<b>Roof Exterior Temperatures</b>	153.4	153.1	145.0	147.0	°F
<b>Roof Interior Temperatures</b>	84.0	83.8	80.9	78.8	°F
<b>Roof Underside Temperature</b>	77.0				°F
<b>Heat Flow Through Roof</b>	596.95				Btu/hr-ft
<b>Heat Flow Through Roof Per ft<sup>2</sup></b>	13.77				Btu/hr-ft <sup>2</sup>
<b>Solar Irradiance Per ft<sup>2</sup></b>	343.45				Btu/hr-ft <sup>2</sup>
<b>Solar Heat Gain Factor</b>					0.040
<b>Reduction of Heat Transfer*</b>	4.92				hr-ft <sup>2</sup> °F/Btu

\*Calculated using the average surface temperature difference, multiplied by the roof area (daylight opening of 79" x 79"), divided by the total energy flow.

**TEST REPORT FOR THE ENSOLTIS CORPORATION**

Report No.: M6515.01-301-41 R1

Date: 11/15/21

**SECTION 10**

**TEST RESULTS**

**Test Start Date:** 10/14/21

**Test Completion Date:** 10/14/21

**Time of Test:** 12:37 PM

**Test Duration**

The test parameters were considered stable for five consecutive time constants (minimum of 10 minutes each) from 12:37 to 13:27.

**Estimated Uncertainty:** 2.99%

This was determined using ANSI/NCSS Z540-2-1997 type B evaluation as described in section 4.3 of the specification. For assumptions used for this calculation or for a description of the procedure contact the "Individual-In-Responsible-Charge (IIRC)" that signed this report.

HEAT FLOWS	MEASUREMENT
1. Heat Extracted From System (Q fluid)	565.8 Btu/hr
2. Surround Panel Heat Flow (Qsp)	15.5 Btu/hr
3. Surround Panel Conductance	0.056 Btu/hr·ft <sup>2</sup> ·F
4. Heat Across Walls (Q walls)	-102.5 Btu/hr
5. Flanking Loss Heat Flow (Qfl)	42.828 Btu/hr
6. Auxiliary energy (Q aux)	45.1 Btu/hr
7. Maximum thermal transmittance (Q u-factor)	-32.1 Btu/hr
8. Net Specimen Heat Flow (Qs)	597.0 Btu/hr

**TEST REPORT FOR THE ENSOLTIS CORPORATION**

Report No.: M6515.01-301-41 R1

Date: 11/15/21

**SECTION 10 (Continued)**

**TEST RESULTS**

TEST CONDITIONS	MEASUREMENT
1. Average Interior Air Temperature	74.5 °F
2. Average Exterior Air Temperature	68.7 °F
3. Surround panel inside temperature (tsp1)	77.8 °F
4. Surround panel outside temperature (tsp2)	126.8 °F
5. Maximum Solar Irradiation Es	344.8 Btu/hr·ft <sup>2</sup>
6. Minimum Solar Irradiation Es	341.1 Btu/hr·ft <sup>2</sup>
7. Average Solar Irradiation Es	343.4 Btu/hr·ft <sup>2</sup>
8. Inlet Fluid Temperature	72.3 °F
9. Outlet Fluid Temperature	73.4 °F
10. Standardized Thermal Transmittance (Ust)*	0.13 Btu/hr·ft <sup>2</sup> ·F
11. Maximum Exterior Surface Coefficient (Hh-sun)	6.0 Btu/hr·ft <sup>2</sup> ·F
12. Minimum Exterior Surface Coefficient (Hh-sun)	3.2 Btu/hr·ft <sup>2</sup> ·F
13. Average Exterior Surface Coefficient (Hh-sun)	4.3 Btu/hr·ft <sup>2</sup> ·F
14. Standardized Weather Conductance (hstII)	5.1 Btu/hr·ft <sup>2</sup> ·F
15. Maximum Wind Velocity	4.6 MPH
16. Minimum Wind Velocity	1.6 MPH
17. Average Wind Velocity	2.9 MPH
18. Average Wind Direction (North equals 360 degrees)	353 Degrees
19. Starting Azimuth	177 Degrees
20. Ending Azimuth	193 Degrees
21. Minimum Altitude	44 Degrees
22. Maximum Altitude	45 Degrees
23. Water Flow Rate	2.24 gpm

\*Determined using NFRC 102. For details see Intertek B&C Report # M6516.01-301-46 R0.

**SECTION 11**

**CONCLUSION**

**Solar Heat Gain Coefficient (SHGC): 0.040**



**TEST REPORT FOR THE ENSOLTIS CORPORATION**

Report No.: M6515.01-301-41 R1

Date: 11/15/21

**SECTION 12**

**THERMOCOUPLES**

**Thermocouple Values**

Temperatures during maximum irradiation  
Air and heat exchanger temperatures

LOCATION	TEMPERATURE
Air Top 97	74.2 °F
Air Center 98	74.8 °F
Air Bottom 99	74.6 °F
Location 100	72.9 °F
Location 101	72.9 °F
Location 102	72.9 °F
Location 103	72.9 °F
Location 104	72.8 °F
Location 105	72.9 °F
Location 106	72.6 °F
Location 107	73.0 °F
Location 108	72.6 °F
Location 109	73.4 °F
Location 110	73.5 °F
Location 111	73.6 °F
Location 112	73.4 °F
Location 113	72.8 °F
Location 114	73.5 °F
Location 115	73.2 °F
Location 116	73.2 °F
Location 117	73.4 °F
Location 118	73.2 °F
Location 119	73.0 °F
Location 120	73.1 °F
Location 121	73.1 °F
Location 122	73.1 °F
Location 123	73.3 °F
Location 124	73.1 °F

LOCATION	TEMPERATURE
Location 125	73.0 °F
Location 126	72.8 °F
Location 127	72.9 °F
Location 128	73.0 °F
Location 129	73.0 °F
Location 130	72.9 °F
Location 131	72.9 °F
Location 132	72.7 °F
Location 133	72.8 °F
Location 134	73.1 °F
Location 135	73.0 °F
Location 136	72.8 °F
Location 137	73.3 °F
Location 138	72.8 °F
Location 139	72.9 °F
Location 140	73.1 °F
Location 141	72.9 °F
Location 142	73.0 °F
Location 143	72.8 °F
Location 144	73.0 °F
Location 145	72.9 °F
Location 146	73.4 °F
Location 147	72.7 °F
Location 148	73.0 °F
Location 149	72.9 °F
Location 150	72.8 °F
Location 151	72.8 °F
Location 152	72.8 °F

## TEST REPORT FOR THE ENSOLTIS CORPORATION

Report No.: M6515.01-301-41 R1

Date: 11/15/21

### SECTION 12 (Continued)

#### Thermocouple Locations

125	126	127
128	129	130

145	149
146	150
147	151
148	152

100	101	102	103	104
105	106	107	108	109
110	111	112	113	114
115	116	117	118	119
120	121	122	123	124

135	131
136	132
137	133
138	134

142	143	144
139	140	141

**84 INCH CALORIMETER**

**FACING CALORIMETER**

**TEST REPORT FOR THE ENSOLTIS CORPORATION**

Report No.: M6515.01-301-41 R1

Date: 11/15/21

**SECTION 13**

**PHOTOS**



Ensolcomp Thermal Panel



**TEST REPORT FOR THE ENSOLTIS CORPORATION**

Report No.: M6515.01-301-41 R1

Date: 11/15/21

**SECTION 14**

**REVISION LOG**

REVISION #	DATE	PAGES	REVISION
.01R0	11/02/21	N/A	Original Report Issue
.01R1	11/15/21	All	The description of the "Series/Model", the "Product Type", and the "Construction" of the assembly have been corrected as shown in the Cover Page and in Sections 2, 3 and 9. Changed "Ensoltis" to "Ensolcomp" and "CDX" to "CDX Plywood" of the construction of the assembly.