



# Precast Deck Footings

Why battle the weather and problems associated with pouring Deck Post Footings in the field? Conigliaro Block precasts footings and delivers them to jobsites ready to be lowered into place. No forming or bracing on site, no blowouts, no soggy Sonotubes and no weather delays. Our Precast Deck Post Footings are especially helpful when space is tight and concrete truck access is questionable. Our Precast Deck Post Footings are manufactured to order. We will meet your jobsite specifications and timeframe.



Filled with 4000 psi concrete and vertical rebar(s) for added tensile strength.

Vertical Sonotube available in several diameters:

6 in dia  
8 in dia  
10 in dia  
12 in dia  
14 in dia  
16 in dia  
18 in dia

Big Foot Base available in several sizes:

BF20 - accepts 6" or 8" sonotubes  
BF24 - accepts 8" or 10" sonotubes  
BF28 - accepts 10" or 12" sonotubes  
BF36 - accepts 12" or 14" or 16" or 18" sonotubes

Customer supplied anchor imbedding and custom pick points also available

