

Conigliaro Block – Delivery and Unloading Information

Conigliaro Blocks are delivered via flatbed truck. We offer both straight truck and tractor trailer options.



Our typical delivery is 40,000 pounds of product which equates to between 16 and 22 blocks per load depending on block type, size and finish.

The blocks are unloaded at the site by the onsite contractor using heavy equipment and a chain with a hook.



This pick point is centered on the top of each block, i.e. for full knob blocks the pick point is between the knobs and for a half knob block the pick point is within the knob.

Please note: Our 2', 3' and 4' long blocks have one pick point requiring you to have a chain with one hook. Our 6' long blocks have two pick points and require you to have a chain with two hooks.



Blocks weigh 1000 to 4000 pounds each, so it is imperative that the onsite contractor have the proper lifting gear to safely unload the blocks.



Conigliaro Block delivery rates include up to one hour of unload time, however typically unloading takes 30 to 45 minutes.



Call us at (888) CONIG – 25 if you have questions about the delivery and unloading of Conigliaro Blocks at your jobsite.

