

ABBREVIATIONS			
AB	ANCHOR BOLT	J-BOX	JUNCTIONBOX
ABV	ABOVE	JT	JOINT
AC	AIR CONDITIONING		
ACOUST	ACOUSTICAL	LAM	LAMINATE
AD	ACCESS DOOR, AREA DRAIN	LOC	LOCATE
ADDL	ADDITIONAL	LWTW	LIGHTWEIGHT
AFF	ABOVE FINISHED FLOOR		
AL	ALUMINUM	MAINT	MAINTENANCE
ALT	ALTERNATE	MAS	MASONRY
ALUM	ALUMINUM	MAT	MATERIAL
ANOD	ANODIZED	MATL	MATERIAL
APPD	APPROVED	MAX	MAXIMUM
APPROX	APPROXIMATE	MECH	MECHANICAL
ARCH	ARCHITECT	MET	METAL
AUTO	AUTOMATIC	MFG	MANUFACTURER
AVG	AVERAGE	MISC	MISCELLANEOUS
		MO	MASONRY OPENING
BDRM	BEDROOM		
BEL	BELOW	NAT	NATURAL
BTWN	BETWEEN	(N)	NEW
BLDG	BUILDING	NOM	NOMINAL
BLK	BLOCK		
BLKG	BLOCKING	OC	ON CENTER
		OD	OUTSIDE DIAMETER
CB	CATCH BASIN	OF	OUTSIDE FACE
CCW	COUNTER CLOCKWISE	OH	OVER HEAD
CEM	CEMENT	OPNG	OPENING
CER	CERAMIC	OPP	OPPOSITE HAND
CFT	CUBIC FOOT		
CIP	CAST-IN-PLACE	PLAM	PLASTICLAMINATE
CJ	CONTROL JOINT	PTTN	PARTITION
CL	CENTERLINE	PERP	PERPENDICULAR
CLG	CEILING	PLMBG	PLUMBING
CLR	CLEAR	PLTF	PLATFORM
CMU	CONCRETE MASONRY UNIT	PLWD	PLYWOOD
CONC	CONCRETE	PNT	PAINT
CONT	CONTINUOUS	PREFAB	PREFABRICATED
CPT	CARPET		
		QTY	QUANTITY
DBL	DOUBLE		
DEG	DEGREE	RA	RETURN AIR
DEM	DEMOLISH	RADIUS	
DEMO	DEMOLITION	REBAR	REINFORCING BAR
DEPT	DEPARTMENT	REF	REFERENCE
DET	DETAIL	RECD	REQUIRED
DIAG	DIAGONAL	REV	REVISION
DIA	DIAMETER	RO	ROUGH OPENING
DIM	DIMENSION	RWD	REDWOOD
DN	DOWN		
DTL	DETAIL	SCHED	SCHEDULE
DWG	DRAWING	SC	SOLID CORE
DS	DOWNSPOUT	SECT	SECTION
		SF	SQUAREFOOT
EA	EACH	SHT	SHEET
EJ	EXPANSION JOINT	SIM	SIMILAR
ELECT	ELECTRICAL	SPECS	SPECIFICATIONS
ENGR	ENGINEER	SQ	SQUARE
EQ	EQUAL	SSTL	STAINLESS STEEL
EQUIP	EQUIPMENT	STD	STANDARD
(E)	EXISTING	STL	STEEL
		STRUCT	STRUCTURAL
FDTN	FOUNDATION		
FE	FIRE EXTINGUISHER	T&B	TOP AND BOTTOM
FEC	FIRE EXTINGUISHER CABINET	T&G	TONGUE & GROOVE
FF	FINISHED FLOOR	T&D	TO BE DETERMINED
FHC	FIRE HOSE CABINET	TD	TRENCH DRAIN
FLR	FLOOR	TRD	TREAD
FOS	FACE OF STUDS	TSLAB	TOP OF SLAB
FP	FIREPROOF	TS	TOP OF STEEL
FT	FEET	TW	TOP OF WALL
FTG	FOOTING	(TYP)	TYPICAL
GA	GAUGE	UL	UNDERWRITERS LAB
GALV	GALVANIZED	UNO	UNLESS NOTED OTHERWISE
GB	GYP SUM BOARD	UON	UNLESS OTHERWISE NOTED
GC	GENERAL CONTRACTOR		
GL	GLASS	VERT	VERTICAL
GRND	GROUND	VIF	VERIFY IN FIELD
GWB	GYP SUM WALL BOARD		
		W/	WITH
H	HIGH	W/O	WITHOUT
HORIZ	HORIZONTAL	WC	WATER CLOSET
HR	HOUR	WD	WOOD
		WWM	WELDED WIRE MESH
ID	INSIDE DIAMETER	WP	WATERPROOF
IN	INCH		
INFO	INFORMATION		

SYMBOLS			
	DETAIL SYMBOL	ROOM #	ROOM IDENTIFICATION
	SECTION DETAIL	(A)	WINDOW NUMBER
	BUILDING SECTION	(01)	DOOR NUMBER
	BUILDING ELEVATION	A4	PARTITION TYPE
	REVISION SYMBOL	1	REVISION SYMBOL
	BREAK LINE		BREAK LINE
	HIDDEN OR OVERHEAD LINE		HIDDEN OR OVERHEAD LINE
	ELEVATION SYMBOL	2'-0"	DIMENSION LINE
	ALIGNMENT		ALIGNMENT
	ELEVATION MARKER		ELEVATION MARKER

GENERAL NOTES	
1.	THE CONTRACTOR SHALL THOROUGHLY EXAMINE THE PREMISES AND SHALL BASE HIS BID ON THE EXISTING CONDITIONS. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT IMMEDIATELY OF ANY DISCREPANCIES BETWEEN THE DRAWINGS AND THE ACTUAL FIELD CONDITIONS. THE CONTRACTOR SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND FIELD CONDITIONS.
2.	THE WORK INCLUDED UNDER THIS CONTRACT SHALL INCLUDE ALL LABOR, MATERIALS, TRANSPORTATION, TOOLS AND EQUIPMENT NECESSARY FOR THE CONSTRUCTION OF THE PROJECT, LEAVING ALL WORK READY FOR USE.
3.	PRIOR TO CONSTRUCTION, DISCREPANCIES BETWEEN THE ARCHITECTURAL AND ENGINEERING DRAWINGS SHALL BE REPORTED TO THE ARCHITECT.
4.	THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL MATERIALS AND WORKMANSHIP IN ACCORDANCE WITH THE APPLICABLE UNIFORM BUILDING CODE, HANDICAP ACCESS CODE AND ALL APPLICABLE ORDINANCES, INCLUDING STATE AND LOCAL BUILDING CODES AND REQUIREMENTS.
5.	THESE PLANS INDICATE THE GENERAL EXTENT OF DEMOLITION AND NEW CONSTRUCTION NECESSARY FOR THE WORK, BUT ARE NOT INTENDED TO BE ALL INCLUSIVE. ALL DEMOLITION AND ALL NEW WORK NECESSARY TO ALLOW FOR A FINISHED JOB IN ACCORDANCE WITH THE INTENTION OF THESE DOCUMENTS SHALL BE INCLUDED REGARDLESS OF WHETHER SHOWN ON THE DRAWINGS OR IN THE NOTES. DO NOT DEMOLISH ANY ITEMS THAT APPEAR STRUCTURAL, UNLESS SPECIFICALLY INDICATED TO BE DEMOLISHED IN THE CONSTRUCTION DOCUMENT, WITHOUT PRIOR REVIEW AND WRITTEN APPROVAL BY THE ARCHITECT.
6.	ANY ERRORS, OMISSIONS, AND CONFLICTS FOUND IN THESE CONSTRUCTION DOCUMENTS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT AND OWNER FOR CLARIFICATION BEFORE PROCEEDING WITH WORK.
7.	ALL DIMENSIONS ARE TO FACE OF FINISH UNLESS NOTED OTHERWISE. ALL DIMENSIONS SHALL BE VERIFIED.
8.	THE CONTRACTOR SHALL CONFIRM IN WRITING APPROXIMATE ON-SITE DELIVERY DATES FOR ALL CONSTRUCTION ITEMS AS REQUIRED BY THE CONSTRUCTION DOCUMENTS, AND SHALL NOTIFY THE ARCHITECT IN WRITING OF ANY POSSIBLE DELAYS AFFECTING OCCUPANCY.
9.	THE CONTRACTOR SHALL PROVIDE A SCHEDULE FOR CONSTRUCTION AS REQUIRED TO MEET THE OWNER'S PHASING REQUIREMENTS AND ULTIMATE COMPLETION DATE.
10.	THE CONTRACTOR SHALL VERIFY THAT NO CONFLICTS EXIST IN THE LOCATION OF ANY AND ALL MECHANICAL, ELECTRICAL, TELEPHONE, LIGHTING, PLUMBING AND FIRE SPRINKLER WORK (INCLUDING PIPING, DUCTWORK AND CONDUIT), AND THAT ALL CLEARANCES FOR INSTALLATION AND MAINTENANCE ARE PROVIDED.
11.	NO WORK DEFECTIVE IN CONSTRUCTION OR QUALITY OR DEFICIENT IN ANY REQUIREMENT OF THE CONTRACT DOCUMENTS WILL BE ACCEPTABLE IN CONSEQUENCE OF THE OWNER'S OR ARCHITECT'S FAILURE TO DISCOVER OR POINT OUT DEFICIENCIES OR DEFECTS DURING CONSTRUCTION. DEFECTIVE WORK REVEALED WITHIN THE TIME REQUIRED BY GUARANTEES SHALL BE REPLACED BY WORK CONFORMING TO THE INTENT OF THE CONTRACT. NO PAYMENT, EITHER PARTIAL OR FINAL, SHALL BE CONSTRUED AS ACCEPTANCE OF DEFECTIVE WORK OR IMPROPER MATERIALS.
12.	THE CONTRACTOR SHALL TAKE CARE NOT TO DAMAGE EXISTING CONSTRUCTION AND SHALL BE RESPONSIBLE FOR REPAIRING ALL DAMAGES CAUSED BY CONTRACTOR AND SUB-CONTRACTORS.
13.	THE CONTRACTOR SHALL REVIEW, APPROVE, STAMP AND SUBMIT WITH REASONABLE PROMPTNESS AND IN SUCH SEQUENCE AS TO CAUSE NO DELAY IN THE WORK, PRODUCT DATA, SHOP DRAWINGS AND SAMPLES FOR THE PROJECT.
14.	BY APPROVING, STAMPING AND SUBMITTING SHOP DRAWINGS, PRODUCT DATA AND SAMPLES, THE CONTRACTOR REPRESENTS THAT HE HAS DETERMINED AND VERIFIED MATERIALS, FIELD MEASUREMENTS, AND FIELD CONSTRUCTION CRITERIA RELATED THERETO AND THAT HE HAS CHECKED AND COORDINATED THE INFORMATION WITHIN SUCH SUBMITTALS WITH THE REQUIREMENTS OF THE WORK AND CONTRACT DOCUMENTS.
15.	THE CONTRACTOR SHALL NOT BE RELIEVED OF RESPONSIBILITY FOR ANY DEVIATION FROM THE REQUIREMENTS OF THE CONTRACT DOCUMENTS BY THE ARCHITECT'S REVIEW OF THE SHOP DRAWINGS, PRODUCT DATA OR SAMPLES. UNLESS THE CONTRACTOR HAS SPECIFICALLY INFORMED THE ARCHITECT IN WRITING OF SUCH DEVIATION AT THE TIME OF SUBMISSION AND THE ARCHITECT HAS GIVEN WRITTEN APPROVAL TO THE SPECIFIC DEVIATION.
16.	THE CONTRACTOR SHALL SUBMIT TO THE ARCHITECT THREE (3) PRINTS, TYPICALLY, OF EACH SHOP DRAWING SUBMITTAL PLUS THREE (3) COPIES OF EITHER PRODUCT DATA OR SAMPLES.
17.	THE ARCHITECT ASSUMES NO RESPONSIBILITY FOR DIMENSIONS OR QUANTITIES ON REVIEWED SUBMITTALS.
18.	SUBSTITUTIONS, REVISIONS AND/OR CHANGES MUST HAVE PRIOR WRITTEN APPROVAL BY THE ARCHITECT.
19.	THE CONTRACTOR SHALL MAINTAIN A CURRENT AND COMPLETE SET OF CONSTRUCTION DOCUMENTS ON THE JOB SITE DURING ALL PHASES OF CONSTRUCTION FOR USE BY ALL TRADES AND SHALL PROVIDE ALL SUBCONTRACTORS WITH CURRENT CONSTRUCTION DOCUMENTS AS REQUIRED.
20.	THE CONTRACTOR SHALL PROVIDE COMPLETE PRODUCT DATA AND RELATED INFORMATION APPROPRIATE FOR THE OWNER'S MAINTENANCE AND OPERATION OF PRODUCTS FURNISHED UNDER THE CONTRACT.
21.	WORK UNDER THIS CONTRACT SHALL BE WARRANTED BY THE CONTRACTOR AGAINST ALL DEFECTS FOR ONE (1) YEAR FROM THE DATE OF SUBSTANTIAL COMPLETION OF THE WORK OR DESIGNATED PORTIONS THEREOF OR FOR ONE (1) YEAR AFTER ACCEPTANCE BY THE OWNER OF DESIGNATED EQUIPMENT. IN THE CASE OF ITEMS REMAINING UNCOMPLETED AFTER THE DATE OF SUBSTANTIAL COMPLETION, THE ONE-YEAR WARRANTY PERIOD SHALL BE FROM DATE OF ACCEPTANCE OF SUCH ITEMS.
22.	EACH TRADE SHALL EXAMINE THE PREMISES TO INSURE THAT CONDITIONS ARE APPROPRIATE FOR HIS WORK TO COMMENCE, PRIOR TO COMMENCING HIS WORK. AREAS NOT APPROPRIATE SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT. COMMENCING WORK IMPLIES ACCEPTANCE OF EXISTING CONDITIONS.
23.	THE GENERAL CONTRACTOR SHALL ASSIST IN THE COORDINATION AND BE RESPONSIBLE FOR THE INSTALLATION OF N.I.C. ITEMS, INCLUDING BUT NOT LIMITED TO FURNITURE, EQUIPMENT, APPLIANCES, PLUMBING FIXTURES, DISHWASHERS, VOICE/ DATA CABLING, TELEPHONE WORK, ETC.
24.	THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETE INSTALLATION AS REQUIRED FOR ACCESSORY ITEMS INCLUDING SINK, DISHWASHER, REFRIGERATOR, LAUNDRY EQUIPMENT, ETC.
25.	ALL DRAWINGS AND NOTES ARE CONSIDERED COMPLEMENTARY, AND WHAT IS CALLED FOR BY EITHER WILL BE AS BINDING AS IF CALLED FOR BY ALL. ANY WORK SHOWN OR REFERRED TO ON ANY ONE SET OF DRAWINGS SHALL BE PROVIDED AS THOUGH SHOWN ON ALL RELATED DRAWINGS.
26.	VERIFY ALL ARCHITECTURAL DETAILS AND COORDINATE DRAWINGS WITH STRUCTURAL AND MEP DRAWINGS BEFORE INITIATION OF ANY RELATED WORK.
27.	ALL INSTALLATIONS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS, INDUSTRY AND BUILDING STANDARDS, AND CODE REQUIREMENTS. SEALANT, WEATHERSTRIPPING, AND FLASHING LOCATIONS IN DRAWINGS ARE NOT INTENDED TO BE INCLUSIVE.
28.	LARGER SCALE DETAILED DRAWINGS SUPERCEDES SMALLER SCALED ELEVATION AND PLAN DRAWINGS.

PROJECT TEAM	
PROPERTY OWNER: NEVADA COUNTY 950 MAIDU AVENUE NEVADA CITY CA 95959 T (530) 265-1218	PROJECT OWNER: AMI HOUSING, INC CONTACT: JENNIFER PRICE 3123 PROFESSIONAL DRIVE, SUITE 210 AUBURN, CA 95603 T (530) 878-5088
ARCHITECT RUSSELL DAVIDSON ARCHITECTURE + DESIGN CONTACT: RUSSELL DAVIDSON 644 ZION STREET, SUITE A NEVADA CITY, CA 95959 T (530) 264-5559	CIVIL ENGINEER MILLENIUM ENGINEERING CONTACT: MICHELLE LAYSHOT 159 SOUTH AUBURN STREET GRASS VALLEY, CA 95945 T (530) 446-6765
STRUCTURAL ENGINEER ASHLEY & VANCE ENGINEERING CONTACT: MIKE SIMMONS 1504 EUREKA ROAD, SUITE 370 ROSEVILLE, CA 95661 T (916) 790-3181	MECHANICAL, ELECTRICAL & PLUMBING ENGINEER OPTIMIZED ENERGY AND FACILITIES CONSULTING CONTACT: ETHAN FELLERSON 5734 ONE TREE BLVD ROCKLIN, CA 95765 T (916) 626-5518


APPLICABLE CODES	
ALL CODES REFERENCED ARE TO BE USED AS AMENDED BY THE STATE OF CALIFORNIA AND LOCAL JURISDICTION.	
2025 CALIFORNIA RESIDENTIAL BUILDING CODE 2025 CALIFORNIA MECHANICAL CODE 2025 CALIFORNIA ELECTRICAL CODE 2025 CALIFORNIA PLUMBING CODE 2025 CALIFORNIA GREEN BUILDING CODE 2025 CALIFORNIA FIRE CODE 2025 CALIFORNIA ENERGY CODE	


SCOPE OF WORK	
PROJECT CONSISTS OF THE FOLLOWING WORK: CONSTRUCT NEW ATTACHED ACCESSORY DWELLING UNIT (ADU) IN EXISTING GARAGE WITH SEPARATE ENTRANCE. THE ADU HAS TWO NEW SINGLE OCCUPANCY ACCESSIBLE BEDROOMS, AN ACCESSIBLE BATHROOM AND KITCHEN AREA. RENOVATE EXISTING FOUR BEDROOM RESIDENCE TO CREATE ONE NEW BEDROOM FOR A TOTAL OF FIVE SINGLE OCCUPANCY BEDROOMS. CONSTRUCT NEW LARGER LAUNDRY AREA TO SERVICE ALL SEVEN BEDROOMS.	

PROJECT DATA	
SITE DATA	
ADDRESS	12875 RATTLESNAKE ROAD GRASS VALLEY, CA 95945 022-020-026-000
A.P.N.:	
WIND EXPOSURE:	C
CLIMATE ZONE:	11
ZONING:	RA-3
SITE AREA:	1.54 ACRES (67,082 SF)
MAX. HEIGHT:	35'-0"
BUILDING ANALYSIS	
OCC. GROUP:	R-3
CONST. TYPE:	V-B
FIRE SPRINKLERS:	NONE
AREAS:	
CONDITION:	2,430 SF
GARAGE:	N/A
(N) ACCESSORY DWELLING:	576 SF


DEFERRED SUBMITTALS	
THE FOLLOWING SUBMITTALS WILL BE DEFERRED:	

SPECIAL INSPECTIONS	
THE FOLLOWING SPECIAL INSPECTIONS ARE REQUIRED: SUBJECT TO FIELD INSPECTION Plans shall reflect the scope of work of the project. Any changes or deviations must be submitted and reviewed by the Building Department prior to inspection.	

SHEET INDEX											
TITLE	T1.0 TITLE SHEET										
GENERAL NOTES	G1.0 GENERAL NOTES										
CGBSC	G2.0 CGBSC G2.1 CGBSC										
TYPICAL ACCESSIBILITY DETAILS	G3.0 TYPICAL ACCESSIBILITY DETAILS G3.1 TYPICAL ACCESSIBILITY DETAILS										
CIVIL	C1.0 COVER AND NOTES SHEET C2.0 GENERAL DETAILS C3.0 EXISTING TOPOGRAPHY & DEMOLITION PLAN C4.0 SITE, GRADING, DRAINAGE AND EROSION CONTROL PLAN										
FLOOR PLANS	A1.0 DEMOLITION FLOOR PLAN A1.1 NEW FLOOR PLAN A1.2 NEW REFLECTED CEILING PLAN A1.3 NEW ROOF PLAN A1.4 NEW FINISH FLOOR PLAN										
EXTERIOR ELEVATIONS	A2.0 BUILDING ELEVATIONS A2.1 BUILDING ELEVATIONS										
ENLARGED PLANS, INT ELEVATIONS, WALL SECTIONS	A4.0 ENLARGED PLAN & INTERIOR ELEVATIONS										
DETAILS	A5.0 DETAILS										
SCHEDULES & DIAGRAMS	A6.0 DOOR & WINDOW SCHEDULES										
STRUCTURAL	S-1.1 STRUCTURAL TITLE SHEET S-1.2 STRUCTURAL SPECIFICATIONS S-2.1 FOUNDATION PLAN S-2.2 ROOF FRAMING PLAN S-3.1 STRUCTURAL DETAILS										
PLUMBING	P0 PLUMBING SCHEDULES, CALCULATIONS & GENERAL NOTES P1 PLUMBING PLAN-WATER P2 PLUMBING PLAN-SEWER & VENT P3 PLUMBING FIRE PENETRATION DETAILS										
MECHANICAL	M0 MECHANICAL GENERAL NOTES, SCHEDULES & DETAILS M1 MECHANICAL PLAN M2 MECHANICAL FIRE PENETRATION DETAILS										
ENERGY CALCULATIONS	EN0 TITLE 24 ENERGY EN1 TITLE 24 ENERGY										
ELECTRICAL	E0 ELECTRICAL GENERAL NOTES, CALCS & SCHEDULES E1 ELECTRICAL PLAN										
REVIEWED FOR CODE COMPLIANCE with County of Nevada Building Regulation Ordinance & current California Codes. The stamping of this plan and specifications SHALL NOT be held to permit or to be an approval of violation of any County Ordinance or State Law County of Nevada Building Department											
 Monte Gillan Jun 01, 2026 1:35 pm Authorized Signature These plans shall be kept on the premises and accessible to the inspector at all times.											
<table border="1"> <thead> <tr> <th>ID</th> <th>NAME</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>REV 1</td> <td>5/1/26</td> </tr> </tbody> </table>		ID	NAME	DATE	1	REV 1	5/1/26				
ID	NAME	DATE									
1	REV 1	5/1/26									
<table border="1"> <thead> <tr> <th>SUBMITTED:</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td></td> <td>AS NOTED</td> </tr> <tr> <th>DRAWN BY:</th> <td>GTB</td> </tr> <tr> <th>CHECKED BY:</th> <td>RPD</td> </tr> <tr> <th>JOB:</th> <td>2025.33</td> </tr> </tbody> </table>		SUBMITTED:	DATE		AS NOTED	DRAWN BY:	GTB	CHECKED BY:	RPD	JOB:	2025.33
SUBMITTED:	DATE										
	AS NOTED										
DRAWN BY:	GTB										
CHECKED BY:	RPD										
JOB:	2025.33										
TITLE SHEET											
JOB SET											
T1.0											



RUSSELL DAVIDSON
ARCHITECTURE + DESIGN



RATTLESNAKE RESIDENCE

12875 RATTLESNAKE ROAD
GRASS VALLEY, CA 95945
APN: 022-020-026-000

ID	NAME	DATE
1	REV 1	5/1/26

SUBMITTED:	DATE
	AS NOTED
DRAWN BY:	GTB
CHECKED BY:	RPD
JOB:	2025.33

TITLE SHEET

JOB SET

T1.0

J:\uansjbrme\RDAD\Dropbox\RDAD\Projects\Current\2025-33 AMH\HomeskeyRattlesnake\Arch\CAO\Rattlesnake.rvt

AGING-IN-PLACE DESIGN AND FALL PROTECTION

At least one bathroom on the entry level shall be provided with grab bar reinforcement. Reinforcement shall be nominal 2x8 lumber and shall be located between 32 inches and 39.5 inches above the finished floor. Water closet reinforcement shall be installed on both side walls of the fixture, or on the side wall and the back wall. Shower reinforcement shall be continuous where wall framing is provided. Bathtub and combination bathtub/shower reinforcement shall be continuous on each end of the bathtub and the back wall. Back wall reinforcement for a lower grab bar shall be provided with the bottom edge located no more than 6 inches above the bathtub rim. Information identifying the location of the reinforcement shall be placed in the operations and maintenance manual. (CRC R328.1.1)

Electrical receptacles outlets, switches and controls shall be located not more than 48 inches measured from the top of the outlet box and not less than 15 inches measured from the bottom of the outlet box above the finished floor. (CRC R328.1.2)

At least one bathroom and one bedroom on the entry level shall provide a doorway with a net clear opening of not less than 32 inches measured with the door open at a 90-degree angle. (CRC R328.1.3)

Doorbell buttons shall be installed not more than 48" above the finished floor measured to the top of the button. (CRC R328.1.4)

GENERAL

Provide each bedroom, basement, and habitable attics with a minimum of one exterior window with a 44" maximum clear opening height, 5.7 sq. ft. minimum clear openable area (minimum 5.0 sq. ft. at grade floor openings), 24" minimum clear openable height and 20" minimum clear width, or an openable exterior exit door. Window wells, ladders, and steps shall comply with minimum code requirements. Bars, grilles, covers, and mesh screens shall be releasable or removable from the inside without the use of a key, tool, special knowledge, or force greater than 15lbs to operate the emergency escape and rescue openings. Photovoltaic panels & modules shall not be below an emergency escape and rescue opening within 36". (R319)

Each bathroom containing a bathtub, shower or tub/shower combination shall be mechanically ventilated with Energy Star approved equipment (minimum 50cfm) with an integral humidistat installed. (CRC R325.2.1)

Provide attic cross ventilation: 1/150 of attic area or 1/300 with at least 40% but not more than 50% of vents are a maximum 3 ft. below the ridge or highest space in the attic and the balance is provided in the lower third of the attic space (not limited to eaves or cornice vents). As an alternative in Climate Zone 16 (Truckee region), the net area may be reduced to 1/300 when a Class 1 or II vapor barrier is installed on the warm-in-winter side of the ceiling. baffles are required at vents for insulation. Provide minimum of 1" inch of air space between insulation and roof sheathing. (CRC R806)

Enclosed rafter spaces shall have a 1-inch clear cross ventilation. (Properly sized baffles for insulation) (CRC R806.3)

Under floor cross ventilation: minimum 1.0 sq. ft. for each 150 sq. ft. of under floor area. When a class 1 vapor retarder is installed on the ground surface the minimum area of ventilation may be limited to 1sq.ft for each 1,500 square feet of under-floor space. One ventilation opening shall be within three (3) feet of each corner of the building (CRC R408.1). Unvented crawl spaces shall comply with CRC R408.2. Unvented crawl space added option for dehumidification of 70 pints moisture per day per 1,000 sf to requirement for exemption. (R408.3)

Exterior balconies and elevated walking surfaces exposed to water, where structural framing is protected by an impervious moisture barrier require construction documents with manufacturer's installation instructions. (R106.1.5) Must be inspected and approved before concealing barrier. (R109.1.5.3)

Enclosed framing in exterior balconies and elevated walking surfaces exposed to rain, snow or drainage from irrigation shall be provided with cross-ventilation area of at least 1/150. (R304.1.3)

Provide landings and a porch light at all exterior doors. Landings are to be minimum 3 ft deep x width of door. Landings at required egress doors may step down a maximum of 7.75 inches when the door does not swing over the landing and 1.5 inches when door swings onto the landing. 20% or more than required exterior exit doors are required a threshold of 7.75 inches maximum; a landing is not required if a stair with two or fewer risers is located on the exterior side and the door does not swing over the stairway. (CRC R318.3)

At least one egress door shall be provided for each dwelling unit, the egress door shall be side hinged with a minimum openable width of 32 inches; the minimum clear openable height shall be 78 inches minimum (other doors shall not be required to comply with these dimensions). Egress doors shall be readily operable from the inside without the use of a key, special knowledge, or effort. (CRC R318.2)

Operable windows more than 72" above finish grade with a clear opening height less than 24" shall have openings not more than 4" apart or needs a compliant guard. (CRC R321.2.1)

FOUNDATIONS & CONCRETE SLABS

Slope drainage 6" within the first 10ft. from the foundation wall. If physical obstructions or lot lines prohibit the 10ft distance, a 2-5 percent slope shall be provided to an approved alternative method of diverting the water away from the foundation. Impervious surfaces shall also be sloped a minimum of 2 percent for 10ft away from structures to an approved drainage way. (CRC R401.3)

Footings shall extend at least 12 inches into the undisturbed ground surface. (CRC R403.1.4) Unless erected on solid rock, to protect against frost and freezing, the minimum foundation depth is 18 inches below grade if between 4,000-7,000 foot elevation and 24 inches below grade for 7,000 foot elevation and above. Exception: Interior footings shall be a minimum of 12 inches below grade. (Nevada County Code Section 14.03.190)

Stepped footings shall be used when slope of footing bottom is greater than 1 in 10 (V: H). Step footing detail shall be shown on building elevations and foundation plan. (CRC R403.1.5)

Concrete slabs: 3 1/2" minimum (CRC R506.1). Slabs under living areas and garages shall be reinforced with wire 6" x 6", 10 gauge x 10 gauge welded mesh or equivalent steel reinforcement and 4" thickness of 3/8" minimum gravel under the concrete slab. Separate from soil with a 6 mil polyethylene vapor retarder with joints lapped not less than 6 inches in living areas. A 4" rock capillary break shall be installed when a vapor retarder is required.

A minimum 18" x 24" under-floor access, unobstructed by pipes or ducts and within 5' of each under-floor plumbing cleanout and not located under a door to the residence, is required. Provide a solid cover or screen. (CRC 408.4 & CPC 707.9)

Minimum sill bolting: 3/4" anchor bolts or approved anchors at 6 ft. o.c. maximum for one-story; (CRC R403.1.6) Use anchor bolts at 4 ft. o.c. maximum for three story construction. Embedded bolts 7" minimum. The anchor bolts shall be placed in the middle third of the width of the plate. Locate end bolts not less than 7 bolt diameters, nor more than 12" from ends of sill members. In SDC DO and above: Provide 3"x3"x0.229 plate washers on each bolt at braced or shear wall locations. Standard washers shall be permitted for anchor bolts not located in braced/shear wall locations. The hole in the plate washer is permitted to be diagonally slotted with a width of up to 3/16" larger than the bolt diameter; the slot length shall not exceed 1 1/4", provided a standard cut washer is placed between the plate washer and the nut. (CRC R403.1.6.1 & R602.11.1)

WOOD FRAMING

Columns shall be restrained to prevent lateral displacement at the bottom end. Wood columns

shall be 4x material minimum and steel columns shall be schedule 40, 3" in diameter minimum. (CRC R407.3) Toenailing of posts to pier blocks no longer allowed under floor areas.

CLEARANCES AND TREATMENT FOR WOOD FRAMING

All joists, girders, ledgers, structural blocking and support posts/column shall be wood of natural resistance to decay or pressure-treated lumber when exposed to the weather. (CRC R304)

Columns in basements when in contact with basement slabs or metal pedestals shall be pressure treated or natural resistance to decay unless the pier/pedestals project 1" above concrete or 8" above earth. (CRC R304)

Columns in enclosed crawl spaces or unenclosed areas located within the periphery of the building shall be pressure treated or natural resistance to decay unless the column is supported by a concrete pier or metal pedestal of a height 8" or more. (CRC R304)

FLOORS

Under-floor areas with storage, fuel-fired equipment or electric-powered equipment with less than 2x10 solid joists or composite lumber of equal or greater cross-sectional area shall be protected on the underside by half-inch sheetrock or a sprinkler system. (R302.13)

Balconies and decks must be designed for a minimum live load of 60lbs per square foot. (CRC T-R301.5)

WALLS

Specify post to beam connections. Positive connection shall be provided to ensure against uplift and lateral displacement. (CRC R502.9 & CRC 2304.10.7)

All fasteners used for attachment of siding & into pressure treated lumber shall be of a corrosion resistant type. (CRC 304.3)

Provide approved building paper under the building siding and approved flashing at exterior openings. (CRC R703.2) Specify a minimum of 2 layers of Grade D paper under stucco and 2 layers of 15lb felt (or equivalent) under stone veneer.

Stucco shall have a minimum clearance to earth of 4 inches and 2 inches to paved surfaces with an approved weep screed. (CRC R703.7.2.1) Masonry stone veneer shall be flashed beneath the first course of masonry and provided with weep holes immediately above the flashing. (CRC R703.8.5 and R703.8.6)

ROOF

Show minimum 22" x 30" access opening to attic (CRC R807); may be required to be 30"x30" to remove the largest piece of mechanical equipment per the California Mechanical Code. Ceiling at attic access must be 30" measured from bottom of roof rafters to top of ceiling joists.

Provide adequate roof slope (minimum X inch per 12 inches) for roof drainage. Roof drains/gutters required to be installed per the California Plumbing Code with leaf/debris protection also installed.

Asphalt shingles with sloped roofs 2/12 to <4/12 shall have two layers of underlayment applied per CRC R905.2.2.

GARAGE AND CARPORT

Garage shall be separated from the dwelling unit & attic area by 1/2 inch gypsum board applied to the garage side. Garage beneath habitable rooms shall be separated by not less than 5/8" type X gypsum board. Structure supporting floor/ceiling assemblies used for required separations shall have 1/2" gypsum board installed minimum. Door openings from the garage to the dwelling shall be solid wood/steel doors or honeycomb steel doors not less than 1 3/8" thick or a 20-minute rated fire door. Doors shall be self-closing & self-latching. No openings directly into a sleeping room from the garage. When the dwelling and garage have fire sprinklers installed per R317.6 and R309, doors into the dwelling unit from the garage only need to be self-closing and self-latching. (CRC R302.5.1 & T-R302.6)

Ducts penetrating the garage to dwelling separation shall be a minimum of 26 gauge with no openings into the garage. (CRC R302.5.2)

Penetrations through the garage to dwelling separation wall (other than ducts as listed above) shall be fire-blocked per CRC Section R302.11, Item #4.

Garage and carport floor surfaces shall be non-combustible material and slope to drain towards the garage door opening. (CRC R317.1)

Appliances and receptacles installed in garage generating a glow, spark or flame shall be located 18" above floor unless it is listed as flammable vapor ignition resistant. (CMC 305.1) Provide protective post or other impact barrier from vehicles. (CMC 305.1.1)

Appliances in private garages and carports shall be installed with a minimum clearance of 6ft above the floor unless they are protected from vehicular impact. (CBC 406.2.9.3)

STAIRWAYS & RAMPS

Stair landings required every 127" of vertical rise. (CRC R318.7.3)

Exterior stair stringers must be naturally resistant to decay or pressure treated. (CRC R304.1)

Rise shall be maximum 7.75"; Run shall be 10" minimum; headroom 6'-8" minimum; width 36" minimum, 31.5" between a handrail on one side and 27" with handrails on two sides. Variation between riser heights 3/8" maximum. A nosing not less than .75 inches but not more than 1.25 inches shall be provided on stairways with solid risers where the tread depth is less than 11 inches. The leading edge of treads shall project not more than 1.25 inches beyond the tread below. Open risers are permitted, provided the opening between the treads does not permit the passage of a 4" sphere. (Openings are not limited when the stair has a rise of 30" or less). (CRC R318.7)

Stairways with 4 or more risers shall have a handrail on one side 34" to 38" above the tread nosing. Circular handrails shall have an outside diameter of 1.25"-2"; if not circular, it shall have a perimeter dimension of 4"-8.25" with a maximum cross-sectional dimension of 2.25". A minimum clearance of 1.5" shall be maintained from the wall or other surface. Handrails shall be returned and terminate in newel posts, or safety terminals. (CRC R320)

Guards shall be 42" minimum height (unless acting as a handrail/guard for a stairway; the guard height may be 34"-38" in height), with openings less than 4" inches clear between the open sides of stairs may have 4 3/8" openings). (CRC R321)

Provide landings at the top/bottom of the stairway the width of the stairway. The depth of the landing shall be 36" minimum. (CRC R318.7.6)

Usable spaces underneath enclosed/unenclosed stairways shall be protected by a minimum of 1/2" gypsum board. (CRC R302.7)

Ramps serving the egress door shall have a slope of not more than 1 unit vertical in 12 units horizontal (8.3-percent slope). All other ramps shall have a maximum slope of 1 unit vertical in 8 units horizontal (12.5-percent slope). Exception: Where it is technically infeasible to comply because of site constraints, ramps shall have a slope of not more than 1 unit vertical in 8 units horizontal (12.5-percent slope) (CRC R318.8.1). Provide 3'x3' landings at the top and bottom of ramps, where doors open onto ramps, and where ramps change directions. (CRC R318.8.2)

DECKS

Guards are required if deck or floor is over 30" above grade, minimum 42" high, with openings less than 4". (CRC R312) Guardrails shall be designed and detailed for lateral forces according to CRC Table 301.5.

Flashing must extend vertically 2" above the ledger and 4" horizontal beyond the ledger face. (CRC R507.9.1.3)

Provide deck lateral load connections at each end of the deck and at deck intersections per CRC R507.9.2. Specify connectors with a minimum allowable stress design capacity of 1,500lbs and install with 24" of the end of the deck. 750lb rated devices are allowed (DTT12 as example) if located at 4 points along the deck.

Posts/columns shall be restrained at the bottom end to prevent lateral displacement; clearly show approved post bases, straps, etc to achieve this per CRC R407.3

Joists, girders, structural blocking and support posts shall be wood of natural resistance to decay or pressure-treated lumber when exposed to the weather. (CRC R304.1(8))

Hardware and fasteners to be hot-dipped galvanized, stainless steel, silicon bronzed or copper. (CRC R304.3)

ELECTRICAL

Never install electrical panels in closets or bathrooms. Maintain a clearance of 36" inches in front of panels, 30" wide or width of equipment and 6'-6" high for headroom. (CEC 110.2.6)

All services supplying dwelling units shall be provided a surge protection device. The SPD shall be an integral part of the service equipment or shall be located immediately adjacent thereto. (CEC 230.67)

Provide a minimum 3 lug intersystem bonding busbar at the main electrical service. (CEC 250.94)

Provide a four-wire feed (two ungrounded conductors, one grounded conductor and an equipment grounding conductor) to all detached structures.

Provide electrical service load calculations for dwellings over 3,000 sq. ft. services 400 amperes or greater or as determined by the Plans Examiner.

All automatic garage door openers that are installed in a residence shall have a battery backup function that is designed to operate when activated because of an electrical outage. (CBC 406.2.1)

A concrete-encased electrode (ufer) consisting of 20' of rebar or #4 copper wire placed in the bottom of a footing is required for all new construction. (CEC 250.52(A)(3)) Bond all metal gas and water pipes to ground. All ground clamps shall be accessible and of an approved type. (CEC 250.104)

All 15/20 ampere receptacles installed per CEC 210.52 including attached and detached garages and accessory buildings shall be listed tamper-resistant receptacles. (CEC 406.12)

All branch circuits supplying 15/20 ampere outlets in family rooms, dining rooms, living rooms, parlors, libraries, dens, bedrooms, sunrooms, recreation rooms, closets, hallways, kitchens, laundry room or similar rooms/areas shall be protected by a listed combination type arc-fault circuit interrupter. (CEC 210.12)

Provide a minimum of one 20A circuit to be used for the laundry receptacle. (CEC 210.11(C)(2))

Provide a minimum of one 20A circuit for bathroom receptacle outlets. (CEC 210.11(C)(3))

GFCIs for Specific Appliances – 210.8(D) This change expands the requirement for GFCI-protected branch circuits or outlets to include those serving electric ranges, wall-mounted ovens, counter-mounted cooking units, clothes dryers and microwave ovens, no matter where they are located.

Provide at least 1 outlet in basements, garages, laundry rooms, decks, balconies, porches and within 3' of the outside of each bathroom basin. (CEC 210.52 (D), (F) & (G))

Furnaces installed in attics and crawl spaces shall have an access platform (catwalk in attics), light switch and receptacle in the space. Provide a service receptacle for the furnace. (CEC 210.63)

All dwellings must have one exterior outlet at the front and the back of the dwelling. (CEC 210.52(E))

Provide a minimum of one 20A circuit for attached and detached garage outlets. The circuit shall supply no other receptacle outlet. Exception: Garage circuit may serve readily accessible outdoor receptacle outlets. ((CEC 210.11 (C)(4))

A minimum of 1 receptacle shall be provided for each car space. (210.52(G)(1))

At least one wall switched lighting outlet or fixture shall be installed in every habitable room, bathroom, hallways, stairways, attached garages and detached garages with electrical power, equipment spaces (attics, basements, etc). (CEC 210.70).

Kitchens, dining rooms, pantries, breakfast nooks, and similar areas must have a minimum of two 20A circuits. Kitchen, pantry, breakfast nooks, dining rooms, work surfaces and similar areas counter outlets must be installed in every counter space 12" inches or wider, not greater than 4' o.c., within 24" inches of the end of any counter space and not higher than 20" above counter. (CEC 210.52 (C)) 1 receptacle is required for peninsula counter spaces. Receptacles shall be located behind kitchen sinks if the counter area depth behind the sink is more than 12" for straight counters and 18" for corner installations. (CEC Figure 210.52(C)(1))

Receptacles on Kitchen Islands and Peninsulas – 210.52(C)(2) This change removes the requirement for providing receptacles to serve countertops and work surfaces on kitchen islands and peninsulas but requires undefined provisions for a future receptacle if none are provided. This section previously required one or more receptacles to serve islands and peninsulas based on their countertop area.

Receptacles shall be installed at 12' o.c. maximum in walls starting at 6' maximum from the wall end. Walls longer than two feet shall have a receptacle. Halfway walls longer than 10 ft shall

have a receptacle in hallways. (CEC 210.52(A))

Receptacles installed Around Tub or Shower Spaces – 406.9(C) This change clarifies that the zone restricting the location of receptacles around a tub or shower space does not include those spaces separated by a floor, wall, ceiling, room door, window, or fixed barrier. The 2020 NEC extended the zone 3 feet beyond the bathtub rim or shower stall threshold.

Stairways with 6 or more risers shall have wall switch at each floor level at the stair landings. (CEC 210.70(A)(2))

Receptacles shall not be installed within or directly over a bathtub or shower stall. (CEC 406.9 (C)) Light pendants, ceiling fans, lighting tracks, etc shall not be located within 3ft horizontally and 8ft vertically above a shower and/or bathtub threshold. (CEC 410.10(D))

All lighting/fan fixtures located in wet or damp locations shall be rated for the application. (CEC 410.10)

GFCI outlets are required: for all kitchen receptacles that are designed to serve countertop surfaces, dishwashers, bathrooms, in under-floor spaces or below grade level, in unfinished basements, crawl space lighting outlets, in exterior outlets, within 5' of a laundry/utility/wet bar, sinks, indoor damp locations, mud rooms, finished basements, laundry areas, and in all garage outlets including outlets dedicated to a single device or garage door opener. (CEC 210.8).

Carbon-monoxide alarms shall be installed in dwelling units with fuel-burning appliances or with attached garages (CRC R311):

Outside of each separate sleeping area in the immediate vicinity of bedrooms

On every level of a dwelling unit including basements

Where a fuel-burning appliance is located within a bedroom, a carbon monoxide detector shall be installed in the bedroom.

Alterations, repairs, or additions exceeding 1,000 dollars (May be battery operated)

Smoke alarms shall be installed (CRC R310):

In each room used for sleeping purposes.

Outside of each separate sleeping area in the immediate vicinity of bedrooms.

In each story, including basements.

At the top of stairways between habitable floors where an intervening door or obstruction prevents smoke from reaching the smoke detector.

Shall not be installed within 20ft horizontally of cooking appliances and no closer than 3ft to mechanical registers, ceiling fans and bathroom doors with a bathtub or shower unless this would prevent placement of a smoke detector (R314.3(4)).

Within a room to which a sleeping loft is open, in the immediate vicinity of the sleeping loft.

Alterations, repairs, or additions exceeding 1,000 dollars. (May be battery operated.)

All smoke and carbon-monoxide alarms shall be hardwired with a battery backup (smoke alarms shall have a 10-year sealed battery). (CRC R314.4 & R315.1.2)

Smoke detectors within 10 feet to 20 feet of the stove shall be ionization type with alarm silencing switch. (CRC R314.3.3)

All 15/20 ampere receptacles in wet locations shall have in-use (bubble) covers installed. All receptacles in wet locations shall also be listed weather-resistant type. (CEC 406.9(B)(1))

ENERGY STORAGE SYSTEMS

Energy storage systems shall be installed per minimum code standards. (CRC R330) See the ESS handbook for more details.

PLUMBING

Underfloor cleanouts shall not be more than 5' from an underfloor access, access door or trap door. (CPC 707.9)

Kitchen sinks require a cleanout above the floor level of the lowest floor of the building.

ABS piping shall not be exposed to direct sunlight unless protected by water based synthetic latex paints. (CPC 906.1)

PVC piping shall not be exposed to direct sunlight unless protected by water based synthetic latex paint. .04" thick wrap or otherwise protected from UV degradation. (CPC 906.1)

Underground water supply lines shall have a 14 awg blue tracer wire. (CPC 604.10.1)

The entire floor space in a room containing a shower without thresholds shall be considered a "wet location" when using the CRC, CBC, and the CEC. (CPC 408.5)

Shower compartments, regardless of shape, shall have a minimum finished interior of 1024 square inches (32" by 32") and shall also be capable of encompassing a 30" circle. The required area and dimensions shall be measured at a height equal to the top of the threshold and shall be maintained to a point of not less than 70" above the shower drain outlet. (CPC 408.7) Provide curtain rod or door a minimum of 22" in width (CPC 408.5). Showers and tubs with showers require a non-absorbent surface up to 6" above the floor. (CRC R307.2) Minimum shower receptor slope is 1/8" per foot. (CPC 408.5)

ESS ready interconnection equipment with a minimum backed-up capacity of 60 amps and a minimum of four ESS-supplied branch circuits, or

A dedicated raceway from the main service panel to a panelboard (subpanel) that supplies the following branch circuits: refrigerator, lighting circuit near primary egress door, sleeping room receptacle and one additional.

The main panelboard shall have a minimum busbar rating of 225 amps. Space shall be reserved to allow future installation of a system isolation equipment/transfer switch within 3 feet of the main panelboard. Raceways shall be installed between the panelboard and the system isolation equipment to allow the connection of backup power source. (California Energy Code 150.0(s))

Heat pump space heater ready. Systems using a gas or propane furnace shall include a dedicated 240 volt branch circuit with 3 feet of the furnace. The branch circuit shall be rated at 30 amps minimum. The main electrical service shall have a reserved space to allow for the installation of a double pole circuit breaker. The reserved space shall be permanently marked as "For future 240V use". (California Energy Code 150.0(i))

Electric cooktop ready. Systems using a gas or propane cooktop shall include a dedicated 240 volt branch circuit with 3 feet of the cooktop. The branch circuit shall be rated at 30 amps minimum. The main electrical service shall have a reserved space to allow for the installation of a double pole circuit breaker. The reserved space shall be permanently marked as "For future 240V use". (California Energy Code 150.0(i))

Operable skylights shall be protected by a noncombustible mesh screen 1/8" max openings (CWCUC 504.8.2)

Exterior doors including garage doors shall be noncombustible, ignition resistant material, minimum 1 3/8 inch solid core, minimum 20 minute fire resistive rating or shall be tested to meet the performance requirements of SFM Standard 12-7A-1. (CWCUC 504.9)

Garage door perimeter gap maximum 1/8". Metal flashing, jamb and header overlap, and weather-stripping meeting section requirements are permitted. (CWCUC 504.9.2)

The walking surface material of decks, porches, balconies and stairs within 10ft of grade level shall be ignition resistant material, exterior fire-retardant treated wood or noncombustible material. (CWCUC 504.7.3)

All luminaires must be high efficiency. (California Energy Code 150.0(k)(1A))

Luminaries recessed in insulated ceilings must meet five requirements (California Energy Code

Indicate on the plans that the maximum hot water temperature discharging from a bathtub or whirlpool bathtub filler shall not exceed 120 degrees F. (CPC 408.4.2)

Provide anti-siphon valves on all hose bibs. (CPC 603.5.7)

Floor drains shall be provided with a trap primer. (CPC 1007)

Added new trap arm maximum lengths. (CPC Table 1002.2)

Gas piping on roofs shall be elevated minimum 3-1/2" above roof surface. (CPC 1210.3.5.3)

MECHANICAL

Wood burning appliances shall not be installed in a new or existing project that is not one of the following:

A pellet-fueled wood burning heater.

A U.S. EPA Phase II Certified wood burning heater.

An appliance or fireplace determined to meet the U.S. EPA particulate matter emission standard of less than 7.5 grams per hour for a non-catalytic wood fired appliance or 4.1 grams per hour for a catalytic wood fired appliance and is approved in writing by the APCO.

All newly installed gas fireplaces shall be direct vent and sealed-combustion type. (CMC 912.3)

Any installed wood stove or pellet stove shall meet the U.S. EPA New Source Performance Standard emission limits and shall have a permanent label certifying emission limits.

Pre-fab fireplaces require manufacturer specifications, model and UL Laboratories certification. Top chimney must extend a minimum of 2 ft. above any part of the building within 10 ft. (CMC 802.5.4)

Fireplaces shall have closable metal or glass doors, have combustion air intake drawn from the outside and have a readily accessible flue dampener control. Continuous burning pilot lights are prohibited. (California Energy Code 150.0(e))

Provide combustion air for all gas fired appliances per CMC Chapter 7.

Masonry chimneys and fireplaces shall be constructed per CRC Chapter 10. Provide details and notes on the plans for the construction, foundation, seismic reinforcement, seismic anchorage, firebox dimensions, etc.

Gas water heater and furnace are not allowed in areas opening into bathrooms, closets or bedrooms unless installed in a closet equipped with a listed gasketed door assembly and a listed self-closing device with all combustion air obtained from the outdoors. (CPC 504)

Roof top equipment on roofs with over 4/12 slope shall have a level 30"x30" working



2025 CALIFORNIA GREEN BUILDING STANDARDS CODE RESIDENTIAL MANDATORY MEASURES, SHEET 1

Y N/A RESPON. PARTY YES N/A RESPON. PARTY NOT APPLICABLE RESPONSIBLE PARTY (i.e. ARCHITECT, ENGINEER, OWNER, CONTRACTOR, INSPECTOR, ETC.)




Table with 2 columns: Y, N/A, RESPON. PARTY. Contains 'CHAPTER 3 GREEN BUILDING SECTION 301 GENERAL' and 'SECTION 302 MIXED OCCUPANCY BUILDINGS'.

Table with 2 columns: Y, N/A, RESPON. PARTY. Contains '4.106.4.2 New multifamily dwellings, hotels and motels and new residential parking facilities'.

Table with 2 columns: Y, N/A, RESPON. PARTY. Contains '4.106.4.3 Electric vehicle charging for additions and alterations of parking facilities serving existing multi-family buildings, hotels and motels'.

Table with 2 columns: Y, N/A, RESPON. PARTY. Contains 'DIVISION 4.4 MATERIAL CONSERVATION AND RESOURCE EFFICIENCY' and 'DIVISION 4.2 ENERGY EFFICIENCY'.

RATTLESNAKE RESIDENCE

12875 RATTLESNAKE ROAD GRASS VALLEY, CA 95945 APN: 022-020-026-000


Table with 3 columns: ID, NAME, DATE. Empty rows.

Table with 2 columns: SUBMITTED, DATE. SCALE AS NOTED. DRAWN BY: GTB. CHECKED BY: RPD. JOB: 2025.33

CGBCS


DIVISION 4.5 ENVIRONMENTAL QUALITY SECTION 4.501 GENERAL 4.501.1 Scope

JOB SET G2.0




ACCESSIBILITY NOTES:


- ALL DRINKING FOUNTAINS SHALL EITHER BE LOCATED COMPLETELY WITHIN ALCOVES, POSITIONED COMPLETELY BETWEEN WING WALLS, OR OTHERWISE POSITIONED SO AS NOT TO ENCRUCH INTO PEDESTRIAN WAYS. THE PROTECTED AREA WITHIN WHICH A DRINKING FOUNTAIN IS LOCATED SHALL BE 32 INCHES WIDE MINIMUM AND 18 INCHES DEEP MINIMUM, AND SHALL COMPLY WITH SECTION 11B-305.7. WHEN USED, WING WALLS OR BARRIERS SHALL PROJECT HORIZONTALLY AT LEAST AS FAR AS THE DRINKING FOUNTAIN AND TO WITHIN 6 INCHES VERTICALLY FROM THE FLOOR OR GROUND SURFACE. (11B-602.9)
- THE REQUIRED CLEARANCE AROUND THE WATER CLOSET SHALL BE PERMITTED TO OVERLAP THE WATER CLOSET. ASSOCIATED GRAB BARS, DISPENSERS, SANITARY NAPKIN DISPOSAL UNITS, COAT HOOKS, SHELVES, ACCESSIBLE ROUTES, CLEAR FLOOR SPACE AND CLEARANCES REQUIRED AT OTHER FIXTURES, AND THE TURNING SPACE. NO OTHER FIXTURES OR OBSTRUCTIONS SHALL BE LOCATED WITHIN THE REQUIRED WATER CLOSET CLEARANCE. (11B-604.3.2)
- FLUSH CONTROLS SHALL BE HAND OPERATED OR AUTOMATIC. HAND OPERATED FLUSH CONTROLS SHALL COMPLY WITH SECTION 11B-309 EXCEPT THEY SHALL BE LOCATED 44 INCHES MAXIMUM ABOVE THE FLOOR. FLUSH CONTROLS SHALL BE LOCATED ON THE OPEN SIDE OF THE WATER CLOSET EXCEPT IN AMBULATORY ACCESSIBLE COMPARTMENTS COMPLYING WITH SECTION 11B-604.8.2. (11B-604.6)
- TOILET PAPER DISPENSERS SHALL COMPLY WITH SECTION 11B-309.4 AND SHALL BE 7 INCHES MINIMUM AND 9 INCHES MAXIMUM IN FRONT OF THE WATER CLOSET MEASURED TO THE CENTERLINE OF THE DISPENSER. THE OUTLET OF THE DISPENSER SHALL BE BELOW THE GRAB BAR, 19 INCHES MINIMUM ABOVE THE FINISH FLOOR AND SHALL NOT BE LOCATED BEHIND GRAB BARS. DISPENSERS SHALL NOT BE OF A TYPE THAT CONTROLS DELIVERY OR THAT DOES NOT ALLOW CONTINUOUS PAPER FLOW. (11B-604.7)
- TOILET COMPARTMENT DOORS, INCLUDING DOOR HARDWARE, SHALL COMPLY WITH SECTION 11B-404 EXCEPT THAT IF THE APPROACH IS FROM THE PUSH SIDE OF THE COMPARTMENT DOOR, CLEARANCE BETWEEN THE DOOR SIDE OF THE COMPARTMENT AND ANY OBSTRUCTION SHALL BE 48 INCHES MINIMUM MEASURED PERPENDICULAR TO THE COMPARTMENT DOOR IN ITS CLOSED POSITION. DOORS SHALL BE LOCATED IN THE FRONT PARTITION OR IN THE SIDE WALL OR PARTITION FARTHEST FROM THE WATER CLOSET. WHERE LOCATED IN THE FRONT PARTITION, THE DOOR OPENING SHALL BE 4 INCHES MAXIMUM FROM THE SIDE WALL OR PARTITION FARTHEST FROM THE WATER CLOSET. WHERE LOCATED IN THE SIDE WALL OR PARTITION, THE DOOR OPENING SHALL BE 4 INCHES MAXIMUM FROM THE FRONT PARTITION. THE DOOR SHALL BE SELF-CLOSING. A DOOR PULL COMPLYING WITH SECTION 11B-404.2.7 SHALL BE PLACED ON BOTH SIDES OF THE DOOR NEAR THE LATCH. DOORS SHALL NOT SWING INTO THE CLEAR FLOOR SPACE OR CLEARANCE REQUIRED FOR ANY FIXTURE. DOORS MAY SWING INTO THAT PORTION OF MANEUVERING SPACE WHICH DOES NOT OVERLAP THE CLEARANCE REQUIRED AT A WATER CLOSET. (11B-604.8.1.2)
- A SHOWER SPRAY UNIT WITH A HOSE 59 INCHES LONG MINIMUM THAT CAN BE USED BOTH AS A FIXED-POSITION SHOWER HEAD AND AS A HANDHELD SHOWER SHALL BE PROVIDED. THE SHOWER SPRAY UNIT SHALL HAVE AN ON/OFF CONTROL WITH A NON-POSITIVE SHUT-OFF IF AN ADJUSTABLE-HEIGHT SHOWER HEAD ON A VERTICAL BAR IS USED. THE BAR SHALL BE INSTALLED SO AS NOT TO OBSTRUCT THE USE OF GRAB BARS. SHOWER SPRAY UNITS SHALL DELIVER WATER THAT IS 120 F (49°C) MAXIMUM. (11B-605.6)
- THRESHOLDS IN ROLL-IN TYPE SHOWER COMPARTMENTS SHALL BE 1/2 INCH HIGH MAXIMUM IN ACCORDANCE WITH SECTION 11B-303. (11B-605.7)
- SHOWER FLOOR OR GROUND SURFACE, FLOOR OR OTHER SURFACES OF SHOWERS SHALL COMPLY WITH SECTION 11B-302.1 AND SHALL BE SLOPED 1/4" MAXIMUM IN ANY DIRECTION. WHERE DRAINS ARE PROVIDED, GRATE OPENINGS SHALL BE 1/4 INCH MAXIMUM AND FLUSH WITH THE FLOOR SURFACE. (11B-605.9)
- A SEAT IN A STANDARD ROLL-IN SHOWER COMPARTMENT SHALL BE A FOLDING TYPE. SHALL BE INSTALLED ON THE SIDE WALL ADJACENT TO THE CONTROLS, AND SHALL EXTEND FROM THE BACK WALL TO A POINT WITHIN 3 INCHES OF THE COMPARTMENT ENTRY. A SEAT IN AN ALTERNATE ROLL-IN TYPE SHOWER COMPARTMENT SHALL BE A FOLDING TYPE. SHALL BE INSTALLED ON THE FRONT WALL OPPOSITE THE BACK WALL, AND SHALL EXTEND FROM THE ADJACENT SIDE WALL TO A POINT WITHIN 3 INCHES OF THE COMPARTMENT ENTRY. THE TOP OF THE SEAT SHALL BE 17 INCHES MINIMUM AND 19 INCHES MAXIMUM ABOVE THE BATHROOM FINISH FLOOR. WHEN FOLDED, THE SEAT SHALL EXTEND 6 INCHES MAXIMUM FROM THE MOUNTING WALL. SEATS SHALL COMPLY WITH SECTION 11B-810.3.1 OR 11B-810.3.2. (11B-810.3)
- ALL DIMENSIONS ARE TO FINISHED INTERIOR OR EXTERIOR WALL FINISH. VERIFY IN FIELD.




15 TOILET COMPARTMENT TOE CLEARANCE
SCALE: 1/2" = 1'-0"




14 SHOWER COMPARTMENT SEAT
SCALE: 1/2" = 1'-0"




13 RESTROOM SIGNAGE
SCALE: 1" = 1'-0"




12 ADA SIGNAGE
SCALE: 1" = 1'-0"




10 (TYP) MULTI-OCCUPANCY RESTROOM
SCALE: 1/2" = 1'-0"




9 ROLL-IN TYPE SHOWER COMPARTMENT
SCALE: 1/2" = 1'-0"




7 ALTERNATE ROLL-IN TYPE SHOWER COMPARTMENT
SCALE: 1/2" = 1'-0"



5 (TYP) ACCESSIBLE RESTROOM
SCALE: 1/2" = 1'-0"



4 FIXTURE MOUNTING HEIGHT
SCALE: 1/2" = 1'-0"



11 TYPICAL ACCESSIBILITY DETAILS

ID	NAME	DATE

SUBMITTED: DATE
SCALE: AS NOTED
DRAWN BY: GTB
CHECKED BY: RPD
JOB: 2025.33

TYPICAL ACCESSIBILITY DETAILS

JOB SET

G3.1

J:\users\jrd\RD+D Dropbox\RD+D Projects\Current\2025.33 AMH HomeKey\Rattlesnake\Arch\CAD\Rattlesnake.pn1\Rattlesnake.pn1

GENERAL NOTES

- ALL MATERIALS AND CONSTRUCTION SHALL MEET THE REQUIREMENTS OF THE SPECIAL PROVISIONS, TECHNICAL SPECIFICATIONS AND THE FOLLOWING SPECIFICATIONS, CODES AND NOTES SHALL MEET THE REQUIREMENTS OF THE ADOPTED STANDARDS OF THE GOVERNING AGENCY, WHICH SHALL GOVERN IN CASE OF CONFLICT.
 - STATE OF CALIFORNIA, DEPARTMENT OF TRANSPORTATION, STANDARD SPECIFICATIONS CURRENT EDITIONS OF THE FOLLOWING:
 - CALIFORNIA BUILDING CODE: 2025
 - CALIFORNIA ENERGY CODE: 2025
 - NATIONAL FIRE PROTECTION ASSOCIATION: 2025
 - CALIFORNIA GREEN BUILDING STANDARDS CODE - "CALGREEN": 2025
- MILLENNIUM PLANNING AND ENGINEERING, EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED, OR COPIED IN ANY MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO A THIRD PARTY WITHOUT THE EXPRESS WRITTEN CONSENT OF MILLENNIUM PLANNING AND ENGINEERING. IN THE EVENT OF UNAUTHORIZED REUSE OF THESE PLANS BY A THIRD PARTY, THE THIRD PARTY SHALL HOLD MILLENNIUM PLANNING AND ENGINEERING HARMLESS.
- MILLENNIUM PLANNING AND ENGINEERING, RESERVES THE RIGHT TO PERFORM OBSERVATION VISITS TO THE SITE AT ANY TIME. OBSERVATIONS ARE PERFORMED SOLELY FOR THE PURPOSE OF DETERMINING IF THE CONTRACTOR UNDERSTANDS DESIGN INTENT CONVEYED IN THE PLANS. OBSERVATIONS DO NOT GUARANTEE CONTRACTOR'S PERFORMANCE AND ARE NOT TO BE CONSTRUED AS SUPERVISION OF THE PROJECT.
- ALL INSPECTIONS REQUIRED BY THE BUILDING CODES, LOCAL BUILDING DEPARTMENTS, OR BY THESE PLANS SHALL BE PROVIDED BY AN INDEPENDENT INSPECTION COMPANY OR THE BUILDING DEPARTMENT. SITE VISITS BY THE ENGINEER OF RECORD DO NOT CONSTITUTE AN INSPECTION, UNLESS SPECIFICALLY CONTRACTED.
- IN THE EVENT THAT CERTAIN EXISTING DIMENSIONS AND/OR CONDITIONS ARE FOUND TO BE DIFFERENT FROM THOSE SHOWN ON THE PLANS AND DETAILS, THE ENGINEER SHALL BE IMMEDIATELY NOTIFIED SO THAT THE PROPER REVISIONS CAN BE MADE IF NECESSARY. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR THE RESULTS OF ANY ERRORS, DISCREPANCIES, OR OMISSIONS WHICH THE CONTRACTOR FAILED TO NOTIFY MILLENNIUM PLANNING AND ENGINEERING, OF BEFORE CONSTRUCTION AND/OR FABRICATION OF THE WORK.
- THE DETAILS SHOWN ON THE DRAWINGS ARE TYPICAL. SIMILAR DETAILS APPLY TO SIMILAR CONDITIONS. NO DEVIATIONS FROM DETAILS SHALL BE MADE WITHOUT THE PRIOR WRITTEN APPROVAL OF MILLENNIUM PLANNING AND ENGINEERING.
- THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DESIGN AND PROVIDE ADEQUATE SHORING, BRACING, FORM-WORK, ETC. AS REQUIRED FOR THE PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION.
- THESE PLANS HAVE BEEN PREPARED USING STANDARDS OF CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. THEY NECESSARILY ASSUME THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKMEN WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, IT IS UNDERSTOOD THAT THE CONTRACTOR WILL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR ALL MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
- ALL WORK OR CONSTRUCTION SHALL COMPLY WITH ALL APPLICABLE BUILDING CODES, REGULATIONS AND SAFETY REQUIREMENTS.
- PARKING SHALL BE MAINTAINED FREE OF FLAMMABLE VEGETATION AND CONSIST OF SURFACING CAPABLE OF SUPPORTING A 75,000 LB VEHICLE.

SITE WORK

- MILLENNIUM PLANNING AND ENGINEERING HAS NOT MADE A GEOTECHNICAL REVIEW OF THE BUILDING SITE AND IS NOT RESPONSIBLE FOR GENERAL SITE STABILITY OR SOIL SUITABILITY FOR THE PROPOSED PROJECT.
- BUILDING SITES ARE ASSUMED TO BE DRAINED AND FREE OF CLAY OR EXPANSIVE SOIL.
- ALL FINISH GRADES SHALL SLOPE A MIN. OF 5% AWAY FROM FOUNDATION, 2% MIN. AWAY FOR PAVED SURFACES FOR A MIN. OF 10 FEET AND DRAIN AWAY FROM BUILDING FOOTINGS. ADEQUATE DRAINAGE AWAY FROM THE STRUCTURE SHALL BE PROVIDED BY CONTRACTOR OR OTHERS, AS REQUIRED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EXCAVATION PROCEDURES INCLUDING SHORING AND PROTECTION OF ADJACENT PROPERTY, STRUCTURES, STREETS AND UTILITIES IN ACCORDANCE WITH THE LOCAL BUILDING DEPARTMENT. ANY DAMAGE TO AN EXISTING STRUCTURE AS A RESULT OF ANY ACTION OF THE CONTRACTOR SHALL BE REPAIRED AND/OR REPLACED AT THE CONTRACTOR'S EXPENSE. CONTRACTOR SHALL PROVIDE BARRICADES, WARNING SIGN, ETC. AS REQUIRED BY LOCAL CODES.
- CONTRACTOR SHALL LOCATE AND CLEARLY MARK THE LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL RELOCATE UTILITY LINES AS REQUIRED.
- NO CUTS OR FILLS ARE ALLOWED WITHIN 2' OF THE PROPERTY LINE.
- THIS OFFICE AND ENGINEER CAN NOT BE HELD RESPONSIBLE FOR CONSTRUCTION THAT TAKES PLACE ON THIS PROPERTY UNLESS THE CONSTRUCTION IS STAKED AND MONITORED BY THIS OFFICE.
- IF ANY SUSPECTED TRIBAL CULTURAL RESOURCES ARE DISCOVERED DURING GROUND DISTURBING CONSTRUCTION ACTIVITIES, ALL WORK SHALL CEASE WITHIN 100 FEET OF THE FIND, OR AN AGREED UPON DISTANCE BASED ON THE PROJECT AREA AND NATURE OF THE FIND. A TRIBAL REPRESENTATIVE FROM A CALIFORNIA NATIVE AMERICAN TRIBE THAT IS TRADITIONALLY AND CULTURALLY AFFILIATED WITH A GEOGRAPHIC AREA SHALL BE IMMEDIATELY NOTIFIED AND SHALL DETERMINE IF THE FIND IS A TCR (PRC §21074).

THE TRIBAL REPRESENTATIVE WILL MAKE RECOMMENDATIONS FOR FURTHER EVALUATION AND TREATMENT AS NECESSARY. TRIBAL REPRESENTATIVES ACT AS A REPRESENTATIVE OF THEIR TRIBAL GOVERNMENT AND ARE QUALIFIED PROFESSIONALS THAT HAVE THE AUTHORITY AND EXPERTISE TO IDENTIFY SITES OR OBJECTS OF CULTURAL VALUE TO NATIVE AMERICAN TRIBES AND RECOMMEND APPROPRIATE TREATMENT OF SUCH SITES OR OBJECTS. IF HUMAN REMAINS, OR SUSPECTED HUMAN REMAINS, ARE DISCOVERED THE APPROPRIATE STATE AND FEDERAL LAWS SHALL BE FOLLOWED. PRESERVATION IN PLACE IS THE PREFERRED OPTION FOR MITIGATION OF TORS UNDER CEQA AND UAC PROTOCOLS, AND EVERY EFFORT SHALL BE MADE TO PRESERVE THE RESOURCES IN PLACE, INCLUDING THROUGH PROJECT REDESIGN, IF FEASIBLE. WHEN AVOIDANCE IS INFEASIBLE, THE PREFERRED TREATMENT BY UAC IS TO RECORD THE RESOURCE, MINIMIZE HANDLING OF CULTURAL OBJECTS, LEAVING OBJECTS IN PLACE WITHIN THE LANDSCAPE, OR RETURNING OBJECTS TO A LOCATION NEARBY WHERE THEY WILL NOT BE SUBJECT TO FUTURE IMPACTS.

WORK AT THE DISCOVERY LOCATION CANNOT RESUME UNTIL ALL NECESSARY INVESTIGATION AND EVALUATION OF THE DISCOVERY UNDER THE REQUIREMENTS OF CEQA HAVE BEEN SATISFIED. PRIOR TO BUILDING PERMIT FINAL APPROVAL, THE PROPERTY SHALL BE IN COMPLIANCE WITH THE VEGETATION MANAGEMENT REQUIREMENTS PRESCRIBED IN CALIFORNIA FIRE CODE SECTION 4906 AND LOCAL ENFORCING AGENCY.

NORTHERN SIERRA AIR QUALITY NOTES


- THE APPLICANT SHALL BE RESPONSIBLE FOR ENSURING THAT ALL ADEQUATE DUST CONTROL MEASURES ARE IMPLEMENTED IN A TIMELY MANNER DURING ALL PHASES OF PROJECT DEVELOPMENT AND CONSTRUCTION.
- ALL MATERIAL EXCAVATED, STOCKPILED, OR GRADED SHALL BE SUFFICIENTLY WATERED, TREATED, OR COVERED TO PREVENT FUGITIVE DUST FROM LEAVING THE PROPERTY BOUNDARIES AND CAUSING A PUBLIC NUISANCE OR A VIOLATION OF AN AMBIENT AIR STANDARD. WATERING SHOULD OCCUR AT LEAST TWICE DAILY, WITH COMPLETE SITE COVERAGE.
- ALL AREAS WITH VEHICLE TRAFFIC SHALL BE WATERED OR HAVE DUST PALLIATIVE APPLIED AS NECESSARY FOR REGULAR STABILIZATION OF DUST EMISSIONS.
- ALL ON-SITE VEHICLE TRAFFIC SHALL BE LIMITED TO A SPEED OF 15 MPH ON UNPAVED ROADS.
- ALL LAND CLEARING, GRADING, EARTH MOVING, OR EXCAVATION ACTIVITIES ON A PROJECT SHALL BE SUSPENDED AS NECESSARY TO PREVENT EXCESSIVE WINDBLOWN DUST WHEN WINDS ARE EXPECTED TO EXCEED 20 MPH.
- ALL INACTIVE PORTIONS OF THE DEVELOPMENT SITE SHALL BE COVERED, SEEDED, OR WATERED UNTIL A SUITABLE COVER IS ESTABLISHED. ALTERNATIVELY, THE APPLICANT MAY APPLY APPROVED NONTOXIC SOIL STABILIZERS (ACCORDING TO MANUFACTURERS SPECIFICATIONS) TO ALL INACTIVE CONSTRUCTION AREAS (PREVIOUSLY GRADED AREAS WHICH REMAIN INACTIVE FOR 96 HOURS) IN ACCORDANCE WITH THE LOCAL GRADING ORDINANCE.
- ALL MATERIAL TRANSPORTED OFF-SITE SHALL BE EITHER SUFFICIENTLY WATERED OR SECURELY COVERED TO PREVENT PUBLIC NUISANCE, AND THERE MUST BE A MINIMUM OF SIX (6) INCHES OF FREEBOARD IN THE BED OF THE TRANSPORT VEHICLE.
- PAVED STREETS ADJACENT TO THE PROJECT SHALL BE SWEEPED AT THE END OF EACH DAY, OR MORE FREQUENTLY IF NECESSARY, TO REMOVE EXCESSIVE OR VISIBLY RAISED ACCUMULATIONS OF DIRT AND/OR MUD WHICH MAY HAVE RESULTED FROM ACTIVITIES AT THE PROJECT SITE.

FUEL MODIFICATION NOTE

- CONTRACTOR SHALL CREATE, AND OWNER SHALL MAINTAIN DEFENSIBLE SPACE OF 100 FEET FROM EACH SIDE AND FROM THE FRONT AND REAR OF THE STRUCTURE. THE INTENSITY OF FUELS MANAGEMENT MAY VARY WITHIN THE 100-FOOT PERIMETER OF THE STRUCTURE, THE MOST INTENSE BEING WITHIN THE FIRST 30' AROUND THE STRUCTURE IF POSSIBLE WITHIN THE PROPERTY BOUNDARY.
- ROADSIDE VEGETATION; A FUEL MODIFICATION AREA SHALL BE PROVIDED FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE DRIVEWAY.
- VERTICAL CLEARANCE; VERTICAL CLEARANCE SHALL BE 15 FEET MINIMUM, MEASURED FROM THE OUTSIDE EDGE OF THE SHOULDER.


THIS PARAGRAPH DOES NOT APPLY TO SINGLE SPECIMENS OF TREES OR OTHER VEGETATION THAT ARE WELL-PRUNED AND MAINTAINED SO AS TO EFFECTIVELY MANAGE FUELS AND NOT FORM A MEANS OF RAPIDLY TRANSMITTING FIRE FROM OTHER NEARBY VEGETATION TO A STRUCTURE OR FROM A STRUCTURE TO OTHER NEARBY VEGETATION. THE INTENSITY OF THE VEGETATION MANAGEMENT MAY VARY WITHIN THE 100-FOOT PERIMETER OF THE STRUCTURE, WITH THE MOST INTENSE BEING WITHIN THE FIRST 50 FEET AROUND THE STRUCTURE.

IMPROVEMENT PLANS FOR:
12875 RATTLESNAKE RESIDENCE
GRASS VALLEY, CALIFORNIA
APRIL, 2026



Susan McLendon
May 15, 2026
8:09 am

Approved, see Table 12.02.210.B



VICINITY MAP
NTS

PROJECT INFORMATION

APPLICANT

RUSSELL DAVIDSON
149 CROWN POINT CT, SUITE C
GRASS VALLEY, CA 95945
EMAIL: RUSSELL@DAVIDSONARCH.COM

CIVIL ENGINEERING

MILLENNIUM PLANNING & ENGINEERING
159 S. AUBURN STREET
GRASS VALLEY, CALIFORNIA 95945
(530) 446-6765
CONTACT: MICHELLE LAYSHOT, P.E.

SITE ADDRESS

12875 RATTLESNAKE ROAD
GRASS VALLEY, CA 95945

SITE AREA

1.54 ACRES

APN

022-020-026

ZONING

RA-3

FIRE

OPHIR HILL FIRE PROTECTION DISTRICT
125 E. MAIN STREET
GRASS VALLEY, CALIFORNIA 95945
CONTACT: ROBB ROTHENBERGER
(530) 273-8351

ELECTRICAL

PACIFIC GAS AND ELECTRIC COMPANY
12840 BILL CLARK WAY
AUBURN, CA 95602
CONTACT: LEE WELLS
(925) 519-6212

BASIS OF BEARINGS

THE MERIDIAN OF THIS SURVEY IS BASED ON NAD 83 CALIFORNIA STATE PLANE COORDINATE SYSTEM ZONE 2. DISTANCES SHOWN HEREON ARE GROUND DISTANCES IN U.S. SURVEY FEET AND DECIMALS THEREOF.

BENCHMARK

THE VERTICAL DATUM IS BASED ON NAVD 88 DETERMINED BY A MINIMUM 2 HOUR STATIC GPS OBSERVATION POST PROCESSED USING OPUS.

ABBREVIATIONS

AC	ASPHALT CONCRETE	INV	INVERT
AB	AGGREGATE BASE	IRR	IRRIGATION
B.S.L.	BUILDING SETBACK LINE	HDPE	HIGH DENSITY POLYETHYLENE
C	CONCRETE	LF	LINEAR FEET
CATV	CABLE TV	MAX	MAXIMUM
C.A.V.	CLEAN AIR VEHICLE	MIN	MINIMUM
CMP	CORRUGATED METAL PIPE	MH	MAN HOLE
COMM.	COMMUNICATION BOX	P	PAVEMENT
CF	CUBIC FEET	P.E.	POLYETHYLENE
DET.	DETAIL	SD	STORM DRAIN
DI	DRAIN INLET	SDCB	STORM DRAIN CATCH BASIN
D.I.P.	DUCTILE IRON PIPE	SDMH	STORM DRAIN MANHOLE
EG	EXISTING GROUND	SSMH	SANITARY SEWER MANHOLE
ELEC.	ELECTRICAL	STD.	STANDARD
E.V.	ELECTRIC VEHICLE	TC	TOP OF CURB
EX., (E)	EXISTING	TDPUJ	TRUCKEE DONNER PUBLIC UTILITY DISTRICT
FF	FINISH FLOOR	TSD	TRUCKEE SANITARY DISTRICT
FG	FINISH GRADE	TYP.	TYPICAL
FH	FIRE HYDRANT	W	WATER
FL	FLOW LINE	WV	WATER VALVE
I.E.	INVERT ELEVATION		

SITE STATISTICS


LAND AREA	AREA (SF)	% OF SITE
ASPHALT	116	~0.2%
CONCRETE AND SIDEWALKS	3,513	~5.2%
BUILDING (FOOTPRINT)	3,600	~5.4%
LANDSCAPE/OPEN SPACE	56,931	~89.2%
TOTAL	67,082 (1.54 AC)	100%
TOTAL PERCENT IMPERVIOUS		~10.8%

SHEET INDEX

C1.0	COVER AND NOTES SHEET
C2.0	DETAILS
C3.0	DEMOLITION PLAN
C4.0	SITE, GRADING, DRAINAGE AND EROSION CONTROL PLAN



SITE PLAN
SCALE: 1" = 30'



REV.	DESCRIPTION	DATE
1	PLAN CHECK COMMENTS	5/1/26
2	PLAN CHECK COMMENTS	6/10/26

RATTLESNAKE RESIDENCE
12875 RATTLESNAKE ROAD
GRASS VALLEY, CA 95945



DATE SIGNED: 04-24-26

DESIGNED BY: MCL

DRAWN BY: DEC


PROJECT NO.: 25-0908

DATE: APRIL 2026



SHEET NUMBER:

C1.0


- NOTES:
- CURB RAMP SHALL HAVE A DETECTABLE WARNING SURFACE THAT EXTENDS THE FULL WIDTH AND 3'-0" DEPTH OF THE RAMP. DETECTABLE WARNING SURFACES SHALL CONFORM TO THE DETAILS ON THIS PLAN AND THE REQUIREMENTS IN THE STANDARD SPECIFICATIONS.
 - THE EDGE OF THE DETECTABLE WARNING SURFACE NEAREST THE STREET SHALL BE BETWEEN 6" AND 8" FROM THE GUTTER FLOWLINE.
 - DOMES SHALL BE ARMOR TILE, FEDERAL YELLOW IN COLOR.
 - TRUNCATED DOMES SHALL BE WET-SET.




1 TRUNCATED DOME DETAIL
NTS





2 TYPICAL CONCRETE SECTION
NTS




3 ACCESSIBLE PARKING IDENTIFICATION SIGN
NTS





4 ACCESSIBLE PARKING SPACE
NTS



5 FIBER ROLL DETAIL
NTS




6 FRENCH DRAIN DETAIL
NTS




INLET PROTECTION MINIMUM DIMENSIONS

ROCK CLASS	PIPE Ø IN.	X FEET	Y FEET	Z FEET
NO. 1 BACKING	12	3	4	5
NO. 1 BACKING	18	4.5	6	7.5
NO. 1 BACKING	24	6	8	10
NO. 1 BACKING	30	7.5	10	12.5
NO. 1 BACKING	36	9	12	15
NO. 1 BACKING	42	10.5	14	17.5
NO. 1 BACKING	48	12	16	20


7 OUTLET PROTECTION DETAIL
NTS




8 V-DITCH
NTS




9 WHEEL STOP DETAIL
NTS



10 AREA DRAIN DETAIL
NTS



11 SANITARY SEWER CLEANOUT
NTS




12 TYPICAL HAMMERHEAD DETAIL
NTS


DATE	DESCRIPTION
5/7/26 <td>REV 1</td>	REV 1



DATE SIGNED: 04-24-26
DESIGNED BY: MCL
DRAWN BY: DEC
PROJECT NO: 25-0908
DATE: APRIL 2026



NOTES:
 1. Surface capable of supporting a 40,000 lb. vehicle with a minimum of 4" A.B., compacted to 95%, placed on a subgrade compacted to 90%.



COUNTY OF NEVADA
 DEPARTMENT OF PUBLIC WORKS
 LOCAL RURAL ROAD SYSTEM
FIRE STANDARD DRIVEWAY
 Approved by: *Patrick G. Perkins*
 Principal Civil Engineer Date 12-17-19
 STANDARD DRAWING C-2


DEMOLITION NOTES

- (D1) REMOVE EXISTING GRAVEL.
- (D2) REMOVE EXISTING CONCRETE.
- (D3) ABANDON EXISTING WELL.

UTILITY NOTE

EXISTING UTILITIES ARE SHOWN WHERE THEY ARE BELIEVED TO EXIST. ACTUAL LOCATION AND ELEVATION MAY VARY. CONTRACTOR SHALL CALL U.S.A. (UNDERGROUND SERVICE ALERT- 1-800-642-2444) TO LOCATE ALL UTILITIES PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION AND SHALL TAKE EXTRA CAUTION TO AVOID DAMAGE TO EXISTING UTILITIES.

LEGEND	
	PROPERTY LINE
	ADJACENT PROPERTY LINE
	BUILDING SETBACK LINE (B.S.L.)
	EXISTING CONCRETE
	EXISTING GRAVEL DRIVEWAY
	EXISTING ASPHALT
	DEMO EXISTING CONCRETE
	REMOVE EXISTING GRAVEL DRIVEWAY
	OVERHEAD ELECTRICAL LINE
	EXISTING WOOD FENCE
	EXISTING STORM DRAIN PIPE
	EXISTING SEWER PIPE
	UTILITY POLE
	ELECTRICAL BOX/PANEL
	GAS METER
	WELL
	IRRIGATION CONTROL VALVE
	HOSE BIB
	SEWER CLEANOUT
	SEPTIC TANK
	TREE TYPE & SIZE




REV.	DESCRIPTION	DATE
REV 1		5/1/26


RATTLESNAKE RESIDENCE
 12875 RATTLESNAKE ROAD
 GRASS VALLEY, CA 95945
EXISTING TOPOGRAPHY & DEMOLITION PLAN



DATE SIGNED: 04-24-26
 DESIGNED BY: MCL
 DRAWN BY: DEC
 PROJECT NO: 25-0908
 DATE: APRIL 2026

C3.0





LEGEND	
	PROPERTY LINE
	PROPOSED CURB
	EXISTING CONCRETE SIDEWALK
	PROPOSED CONCRETE SIDEWALK (C.O.G.V. DETAIL ST-3)
	PROPOSED GRAVEL DRIVEWAY
	EXISTING GRAVEL DRIVEWAY
	VELOCITY DISSIPATER
	MATCH EX. GRADE
	CONCRETE ELEVATION
	FLOWLINE ELEVATION
	SE-5-FIBER ROLLS (DETAIL 5, SHEET C2.0)
	WM-8 CONCRETE WASH-OUT AREA
	EXISTING SANITARY SEWER CLEANOUT
	PROPOSED HDPE STORM PIPE
	PROPOSED DRAINAGE INLET

CONSTRUCTION NOTES

- CONSTRUCT 4" PCC OVER 6" CLASS II A.B. COMPACTED TO 95% R.C. OVER 12" NATIVE SOIL COMPACTED TO 90% R.C. W/ #3 REBAR @ 18" O.C., EACH WAY (SEE DETAIL 2, SHEET C3.0).
- INSTALL 6" CLASS II A.B. COMPACTED TO 95% R.C. OVER 12" NATIVE SOIL COMPACTED TO 90% R.C.
- INSTALL V-DITCH @ 1% MIN. SLOPE (DETAIL 8, SHEET C2.0)
- INSTALL ACCESSIBLE PARKING IDENTIFICATION SIGN (SEE DETAIL 3, SHEET C2.0).
- INSTALL ACCESSIBLE PARKING STALLS AND "NO PARKING" ACCESS AISLE (SEE DETAIL 4, SHEET C2.0).
- INSTALL VELOCITY DISSIPATER/ROCK OUTLET PROTECTION (DETAIL 7, SHEET C2.0).
- INSTALL FIBER ROLLS (DETAIL 5, SHEET C2.0). SEE BMP SE-5 IN THE CALIFORNIA STORM WATER QUALITY ASSOCIATION (CASQA) CONSTRUCTION BMP HANDBOOK FOR ADDITIONAL REQUIREMENTS. INSTALL CHECK DAMS AT 30' INTERVALS ALONG FLOWLINE OF GUTTER OR SWALE (TYPICAL) (SEE BMP SE-4 IN CASQA BMP HANDBOOK)
- CONCRETE CLEANOUT AREA SHALL BE LOCATED BY THE CONTRACTOR SUBJECT TO BMP REQUIREMENTS OR SHALL BE CONDUCTED OFFSITE AT THE CONCRETE PLANT. SEE BMP WM-8 FOR ADDITIONAL INFORMATION IN THE CALIFORNIA STORM WATER QUALITY ASSOCIATION (CASQA).
- INSTALL HDPE STORM PIPE @ 6" MIN. COVER AND 1% MIN. SLOPE.
- INSTALL 12" NYLOPLAST LANDSCAPE DRAIN (OR EQUAL) (DETAIL 10, SHEET C3.0).
- INSTALL 24" MIN. WIDTH FRENCH DRAIN BEHIND CURB WITH 4" PERFORATE PIPE WRAPPED IN NON-WOVEN FILTER FABRIC @ 0.5% MIN. SLOPE (DETAIL 6, SHEET C3.0)
- CLEAN DEBRIS OUT OF CULVERT AND REGRADE FLOWLINE TO DRAIN TO NORTH.
- CONNECT PROPOSED PERFORATED PIPE TO EXISTING DRAIN INLET. CLEAN OUT EX. DRAIN INLET. REPLACE INLET, IF NECESSARY.
- INSTALL SANITARY SEWER CLEANOUT (DETAIL 11, SHEET C2.0)


EARTHWORK QUANTITIES:

GRADING EXCAVATION QUANTITIES:
 CUT: 20 CUBIC YARDS
 FILL: 0 CUBIC YARDS
 NET: 7 CUBIC YARDS EXPORT
 *EXCESS SOIL SHALL BE PLACED ONSITE IN HEIGHT NOT TO EXCEED 6".

- THE TOPOGRAPHY FROM WHICH THE ABOVE QUANTITIES WERE COMPUTED WAS OBTAINED FROM A FIELD TOPOGRAPHIC SURVEY, RESULTING IN A 1" CONTOUR INTERVAL MAP THAT WAS PROVIDED BY MILLENNIUM PLANNING & ENGINEERING, DATED JANUARY 2026.
- THE CONTRACTOR IS ADVISED TO MAKE AN INDEPENDENT EVALUATION OF THE EARTHWORK QUANTITIES INVOLVED. THE OWNER AND MILLENNIUM PLANNING AND ENGINEERING DO NOT, EXPRESSLY OR BY IMPLICATION, AGREE THAT THE ACTUAL EARTHWORK QUANTITIES WILL CORRESPOND TO THOSE GIVEN ABOVE. EARTHWORK QUANTITIES MAY FLUCTUATE DEPENDING UPON SIZE AND AMOUNT OF ROCK ENCOUNTERED. ANY EXCESS OR UNSUITABLE MATERIAL SHALL BE REMOVED FROM THE OWNER'S PROPERTY AND DISPOSED OF AT THE CONTRACTOR'S EXPENSE.

UTILITY NOTES

- CONTRACTOR TO POTHOLE ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION AND NOTIFY ENGINEER IF ACTUAL LOCATION AND DEPTH DIFFERS SIGNIFICANTLY FROM LOCATION AND DEPTH SHOWN ON PLANS.
- CONTRACTOR SHALL COORDINATE WITH UTILITY COMPANIES TO OBTAIN FINAL CONSTRUCTION DRAWINGS AND STANDARD SPECIFICATIONS. ALL UNDERGROUND CONDUIT AND PIPING TO BE INSTALLED IN ACCORDANCE WITH THE LATEST ADOPTED VERSION OF THE CALIFORNIA PLUMBING CODE AS WELL AS PLANS/STANDARDS AND DETAILS OF THE LOCAL UTILITY COMPANY HAVING JURISDICTION.
- CONTRACTOR SHALL ADJUST ALL (E) UTILITY BOXES, VAULTS AND MANHOLES WHICH OCCUR WITHIN NEW PAVEMENT TO 1/2" TO 1/4" BELOW FINISH GRADE. CONTRACTOR SHALL UPGRADE ALL BOXES, VAULTS AND LIDS TO H-20 TRAFFIC RATED WHERE BOXES VAULTS AND LIDS OCCUR WITHIN VEHICLE TRAFFIC AREAS.
- EXISTING UTILITIES ARE SHOWN WHERE THEY ARE BELIEVED TO EXIST. ACTUAL LOCATION AND ELEVATION MAY VARY. CONTRACTOR SHALL CALL U.S.A. (UNDERGROUND SERVICE ALERT- 1-800-642-2444) TO LOCATE ALL UTILITIES PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION AND SHALL TAKE EXTRA CAUTION TO AVOID DAMAGE TO EXISTING UTILITIES.



REV.	DESCRIPTION	DATE
REV 1		5/7/26

RATTLESNAKE RESIDENCE
 12875 RATTLESNAKE ROAD
 GRASS VALLEY, CA 95945


SITE, GRADING, DRAINAGE AND EROSION CONTROL PLAN




DATE SIGNED: 04-24-26
 DESIGNED BY: MCL
 DRAWN BY: DEC
 PROJECT NO: 25-0908

DATE: APRIL 2026
 SHEET NUMBER: C4.0

U:\enrg\mfr\RD+A\Dropbox\RD+A\Projects\Curren\2025-33-AMH\HomeKey\Rattlesnake\Arch\CAD\Rattlesnake.pjn\Rattlesnake.pjn



1 NEW FLOOR PLAN
SCALE: 1/4" = 1'-0"



LEGEND

- (E) WALL TO REMAIN
- (N) WALL
- 1 HR. FIRE WALL
- ROOM NAME ### ROOM IDENTIFICATION
- A WINDOW NUMBER
- 01 DOOR NUMBER
- 6.01 KEYNOTE

GENERAL NOTES



- REFERENCES
- REFER TO SHEET A5.0 FOR PARTITION ASSEMBLIES. ALL EXTERIOR WALLS K6 U.N.O. ALL INTERIOR WALLS A4 U.N.O.
 - REFER TO SHEET A6.0 FOR WINDOW & DOOR SCHEDULES.
 - REFER TO ENLARGED PLANS ON SHEET A4.0 FOR ADDITIONAL NOTATION AND DIMENSIONS.
 - REFER TO REFLECTED CEILING PLAN FOR CEILING HEIGHTS.
 - REFER TO MECHANICAL, ELECTRICAL AND PLUMBING GENERAL NOTES ON SHEET G1.0
 - INSTALL FINISHES PER FINISH PLAN ON SHEET A1.4
 - INSTALL WINDOWS & DOORS PER SCHEDULE ON SHEET A6.0
- NOTES
- WRITTEN DIMENSIONS TO PREVAIL OVER SCALING OF DRAWINGS. SUBCONTRACTOR TO VERIFY ALL DIM. PRIOR TO CONSTRUCTION
 - EXTERIOR DIMENSIONS ARE MEASURED TO FACE OF STRUCTURAL STUD / CMU / SLAB EDGE OR CENTERLINE OF STRUCTURE U.N.O.
 - INTERIOR DIMENSIONS ARE MEASURED TO FACE OF STUD, U.N.O.
 - DOORS AND WINDOWS ARE MEASURED TO CENTERLINE OF OPENINGS.
 - ALL ANGLED WALLS ARE AT 45 DEGREES U.N.O.
 - SET JAMB AT HINGE SIDE OF:
EXTERIOR DOORS @ 4.5" U.N.O.
INTERIOR DOORS @ 4.5" U.N.O.
 - PROVIDE MIN. 36"x36" LEVEL LANDINGS OUTSIDE AT ALL EXTERIOR DOORS PER CRC SECTION R311.3, WITH LANDINGS NOT MORE THAN 7.75" BELOW INSIDE FINISHED FLOORS AT INWARD SWINGING (OR SLIDING) DOORS AND 1.5" AT OUTWARD SWINGING PER CRC SECTION R311.3.1. ALL LANDINGS SHALL SLOPE 1/4" FT AWAY FROM DOORS MIN. TYP. PROVIDE MIN. 12" CLASS 2 AGGREGATE BASEROCK UNDER SLABS AT ALL DOORWAY LANDINGS, TYP.
 - GLASS DOORS & PANELS OF SHOWER & BATHTUB ENCLOSURES & ADJACENT WALL OPENINGS WITHIN 60" ABOVE A STANDING SURFACE OR DRAIN INLET SHALL BE TEMPERED SAFETY GLASS, AS PER CRC SECTION R308.4.5.
 - BATHROOM FLOORS TO HAVE SKID-RESISTANT SURFACE.
 - BASE LINING MATERIAL BENEATH SHOWER PAN SLOPED TO DRAIN AS PER CPC SECTION 408.7.
 - OPEN GUARDRAILS SHALL HAVE INTERMEDIATE RAILS OR AN ORNAMENTAL PATTERN SUCH THAT A SPHERE 4 INCHES IN DIAMETER CANNOT PASS THROUGH.
 - PROVIDE FIREBLOCKING IN CONCEALED SPACES PER CRC R302.11.

WILDLAND URBAN INTERFACE

- PROPOSED CONSTRUCTION MATERIALS ARE NON-COMBUSTIBLE / IGNITION RESISTANT PER CRC SECTION R337.4
- PROPOSED ROOFING SHALL COMPLY WITH CRC SECTION R337.5
- VENTING FOR SOFFITS AND EAVES SHALL HAVE MESH SCREENING PER CRC SECTION R337.6
- EXTERIOR WINDOWS AND DOORS SHALL BE MULTI-PANED, TEMPERED GLASS PER CRC SECTION R337.8
- EXTERIOR DECKING AND WALKWAYS SHALL BE NON-COMBUSTIBLE, IGNITION RESISTANT PER CRC SECTION R327.9

KEYNOTES

- INSTALL EXTERIOR CONCRETE FLATWORK WITH SPECIFIED FINISH AND JOINT PATTERN
- PROVIDE 15 MIL VAPOR BARRIER ON EXISTING CONCRETE SLAB AND WOOD FURRING WITH SUBFLOOR AT ADU PER STRUCTURAL DETAILS ON S-3.1. ADU FLOORING TO BE LEVEL WITH THE EXISTING RESIDENCE FLOORING.
- INSTALL WOOD FRAMING WITH REQUIRED SEISMIC BLOCKING AND CONNECTIONS, TYPICAL
- INSTALL HAMPTON BAY OR APPROVED EQUAL CABINETS AND BUILT-INS PER DRAWINGS. PROVIDE HARDWARE PULLS ON ALL DOORS AND DRAWERS.
- INSTALL NEW SHELF AND HANGER ROD AT 5'-0" HEIGHT
- INSTALL ENERGY-EFFICIENT WINDOWS WITH LOW-EMISSION GLASS
- INSTALL INTERIOR DOORS WITH CASINGS, HARDWARE, AND PROPER OPERATION, TYPICAL
- INSTALL INSULATED EXTERIOR DOORS WITH WEATHERSTRIPPING AND THRESHOLDS
- PATCH, REPAIR AND PAINT WITH NEW GYPSUM BOARD FINISH AT DEMO AREA TO MATCH EXISTING ADJACENT WALLS. PROVIDE NEW CHAIR RAIL TO MATCH EXISTING
- NEW FURNITURE, SHOWN DASHED, TYPICAL
- INSTALL NEW HVAC UNIT. SEE MECHANICAL DRAWINGS.
- INSTALL NEW ELECTRICAL SUB-PANEL PER ELECTRICAL DRAWINGS.



RATTLESNAKE RESIDENCE

12875 RATTLESNAKE ROAD
GRASS VALLEY, CA 95945
APN: 022-020-026-000

ID	NAME	DATE
1	REV 1	5/1/26


SUBMITTED:	DATE
SCALE:	AS NOTED
DRAWN BY:	GTB
CHECKED BY:	RPD
JOB:	2025-33

NEW FLOOR PLAN

JOB SET
A1.1

GENERAL NOTES


- REFER TO SHEET A6.0 FOR WINDOW & DOOR SCHEDULES.
- INSTALL ALL FINISHES PER MANUFACTURER SPECIFICATIONS



2 SOUTH ELEVATION
 SCALE: 1/4" = 1'-0"

KEYNOTES

- 2.12 EXISTING ROOF TO REMAIN
- 2.13 EXISTING GUTTER TO REMAIN
- 2.14 EXISTING DOWNSPOUT TO REMAIN
- 2.19 REMOVE EXISTING STONE FINISH AND WOOD TRIM. PREPARE SUBSTRATE FOR NEW EXTERIOR CEMENT PLASTER FINISH TO MATCH EXISTING
- 6.05 REPAIR AND REPLACE EXISTING WOOD TRIM AT ALL EXTERIOR OPENINGS AND SIDING. APPLY NEW PAINT.
- 7.01 INSTALL INFILL FRAMING AT DEMOLISHED OPENING WITH EXTERIOR CEMENT PLASTER FINISH TO MATCH EXISTING ADJACENT.
- 7.02 REPAIR EXISTING EXTERIOR CEMENT PLASTER FINISH TO MATCH EXISTING AS REQUIRED.
- 9.11 APPLY PAINT AT ENTIRE EXTERIOR CEMENT PLASTER FINISH TO MATCH EXISTING.



1 WEST ELEVATION
 SCALE: 1/4" = 1'-0"

RATTLESNAKE RESIDENCE

12875 RATTLESNAKE ROAD
 GRASS VALLEY, CA 95945
 APN: 022-020-026-000

ID	NAME	DATE


SUBMITTED:	DATE
SCALE:	AS NOTED
DRAWN BY:	GTB
CHECKED BY:	RPD
JOB:	2025.33

BUILDING ELEVATIONS


JOB SET

A2.1


J:\users\jrd\A-D Dropbox\RDA-D\Projects\Current\2025-33 AMH HomeKey\Rattlesnake\Arch\CAD\Rattlesnake.pln\Rattlesnake.pln




6 KITCHEN 2
SCALE: 1/2" = 1'-0"




7 KITCHEN 2
SCALE: 1/2" = 1'-0"




2 BATH 3 (ADA)
SCALE: 1/2" = 1'-0"




3 BATH 3 (ADA)
SCALE: 1/2" = 1'-0"




4 BATH 3 (ADA)
SCALE: 1/2" = 1'-0"



5 BATH 3 (ADA)
SCALE: 1/2" = 1'-0"




1 ENLARGED KITCHEN 2 / BATH 3 (ADA)
SCALE: 1/2" = 1'-0"



KEYNOTES

- 6.08 INSTALL HAMPTON BAY OR APPROVED EQUAL CABINETS AND BUILT-INS PER DRAWINGS. PROVIDE HARDWARE PULLS ON ALL DOORS AND DRAWERS.
- 9.09 INSTALL ENGINEERED QUARTZ COUNTERTOP QC-1 WITH PROPER SUPPORT AND SEAMS
- 10.05 INSTALL BATHROOM MIRRORS AND MEDICINE CABINETS WITH PROPER ANCHORING
- 10.07 PROVIDE RECESSED FLOOR FOR PREFABRICATED ROLL-IN ACCESSIBLE SHOWER
- 10.08 INSTALL ADA ACCESSIBLE UNISEX RESTROOM SIGNAGE PER DETAIL 13/G3.1
- 12.06 NEW FURNITURE, SHOWN DASHED, TYPICAL



RUSSELL DAVIDSON
ARCHITECTURE + DESIGN



RATTLESNAKE RESIDENCE

12875 RATTLESNAKE ROAD
GRASS VALLEY, CA 95945
APN: 022-020-026-000

ID	NAME	DATE
1	REV 1	5/1/26


SUBMITTED:	DATE
SCALE:	AS NOTED
DRAWN BY:	GTB
CHECKED BY:	RPD
JOB:	2025.33

ENLARGED PLAN
& INTERIOR
ELEVATIONS


JOB SET

A4.0


J:\uansj\p\mfrda\Dropbox\RDA-D\Projects\Current\2025-33 AMH Homekey\Rattlesnake\Arch\CAD\Rattlesnake.pjn\Rattlesnake.pjn




19 PARTITION 'A.1' (1-HOUR FIRE RATED)
SCALE: 1 1/2" = 1'-0"




14 PARTITION 'A'
SCALE: 1 1/2" = 1'-0"




18 UPPER CABINET WALL ATTACHMENT
SCALE: 3" = 1'-0"




17 UPPER CABINET WALL ATTACHMENT
SCALE: 3" = 1'-0"




16 UPPER CABINET CEILING ATTACHMENT
SCALE: 3" = 1'-0"




13 COUNTER WALL ATTACHMENT
SCALE: 3" = 1'-0"




12 LOWER CABINET TOE KICK
SCALE: 3" = 1'-0"




11 LOWER CABINET WALL ATTACHMENT
SCALE: 3" = 1'-0"




9 INTERIOR DOOR HEAD
SCALE: 3" = 1'-0"




8 UPPER CABINET W/DOOR
SCALE: 1" = 1'-0"




7 LOWER CABINET W/ DRAWER & DOOR
SCALE: 1" = 1'-0"




6 COUNTER, OPEN BELOW
SCALE: 1" = 1'-0"




4 INTERIOR DOOR JAMB
SCALE: 3" = 1'-0"




3 LOWER CABINET WITH DOOR
SCALE: 1" = 1'-0"



2 LOWER CABINET W/FOUR DRAWERS
SCALE: 1" = 1'-0"



1 LOWER CABINET W/ SINK
SCALE: 1" = 1'-0"



RATTLESNAKE RESIDENCE

12875 RATTLESNAKE ROAD
GRASS VALLEY, CA 95945
APN: 022-020-026-000

ID	NAME	DATE
1	REV 1	5/1/26

SUBMITTED: DATE
SCALE: AS NOTED
DRAWN BY: GTB
CHECKED BY: RPD
JOB: 2025-33

DETAILS

JOB SET


A5.0

DOOR SCHEDULE												U-VALUE	USHGC	FIRE RATING	HARDWARE SET	CLOSER	REMARKS
DOOR #	ROOM NAME	TYPE	STATUS	W	H	MFG	FRAME		LEAF								
							MATERIAL	FINISH	MATERIAL	FINISH							
EXTERIOR																	
01	KITCHEN 2	B	New	3'-0"	6'-8"	TBD	WOOD	PAINTED	SCWD	PAINTED				PRIVACY, LEVER TYPE	N	ADA ACCESSIBLE THRESHOLD. SEE DETAIL 1/G3.0	
02	MECH	B	New	2'-8"	6'-8"	TBD	WOOD	PAINTED	SCWD	PAINTED				STORAGE	N		
03	DINING	A	New	8'-0"	6'-8"	ANDERSEN 100 OR EQUAL	WOOD	PAINTED	COMP.	WHITE	0.32	0.22		PRIVACY	N		
INTERIOR																	
04	(N) BEDRM 6 (ADA)	B	New	3'-0"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED				PRIVACY, LEVER TYPE	N		
05	(N) BEDRM 6 (ADA)	C	New	6'-0"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED				PASSAGE, PULL TYPE	N		
06	(N) BEDRM 5 (ADA)	C	New	6'-0"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED				PASSAGE, PULL TYPE	N		
07	(N) BEDRM 5 (ADA)	B	New	3'-0"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED				PRIVACY, LEVER TYPE	N		
08	KITCHEN 2	B	New	2'-6"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED				PASSAGE, LEVER TYPE	N		
09	BATH 3 (ADA)	B	New	3'-0"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED				PRIVACY, LEVER TYPE	N		
10	LAUNDRY	B	New	3'-0"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED			20 MIN	PRIVACY, LEVER TYPE	Y	ADA ACCESSIBLE THRESHOLD. SEE DETAIL 1/G3.0	
11	BEDRM 4	B	New	2'-6"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED				PRIVACY	N		
12	(N) BEDRM 7	B	New	2'-6"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED				PRIVACY	N		
13	(N) BEDRM 7	C	New	5'-0"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED				PASSAGE	N		
14	OFFICE	B	New	2'-6"	6'-8"	MASONITE OR EQUAL	WOOD	PAINTED	HCWD	PAINTED				PRIVACY	N		

- ### DOOR NOTES
- ALL GLASS IN DOORS SHALL BE TEMPERED. TEMPERED GLASS SHALL BE PERMANENTLY IDENTIFIED AND VISIBLE WHEN THE UNIT IS GLAZED.
 - ALL GLAZING WILL BE INSTALLED WITH A CERTIFYING LABEL ATTACHED, SHOWING THE "U" VALUE.
 - REFER TO FLOOR PLANS FOR DIRECTION OF DOOR SWING.
 - DOORS SHALL MEET THE MINIMUM INFILTRATION REQUIREMENTS PER SECTION 116 E.E.S.
 - VENTILATION SHALL COMPLY WITH C.B.C. 1203.4 AND R303.
 - ALL EXTERIOR WINDOW AND EXTERIOR DOOR ASSEMBLIES TO HAVE AN STC RATING OF 36 OR GREATER.
 - DOORS MAY OPEN TO THE EXTERIOR ONLY IF THE FLOOR OR LANDING IS NOT MORE THAN 1/2 INCH LOWER THAN THE DOOR THRESHOLD. SECTION R311.3.1 CRC
 - GLAZED OPENINGS WITHIN EXTERIOR DOORS SHALL BE INSULATING-GLASS UNITS WITH A MINIMUM OF ONE TEMPERED PANE.




RUSSELL DAVIDSON
ARCHITECTURE + DESIGN

2 DOOR TYPES
SCALE: 1" = 1'-0"

WINDOW SCHEDULE													REMARKS
ID	LOCATION	TYPE	STATUS	W	H	MFG	TEMPERING	GLAZING	U-VALUE	SHGC	FRAME		
											MATERIAL	FINISH	
02	BEDRM 4	F	NEW	6'-0"	4'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
03	BEDRM 3	F	NEW	6'-0"	4'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
04	BEDRM 2	G	NEW	8'-0"	4'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
05	BATH 1	A	NEW	4'-0"	1'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
06	(N) BEDRM 7	E	NEW	5'-0"	4'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
07	DINING	E	NEW	5'-0"	4'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
08	NOOK	E	NEW	5'-0"	4'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
09	KITCHEN 1	B	NEW	4'-0"	3'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
10	OFFICE	E	NEW	5'-0"	4'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
11	DEN	H	NEW	8'-0"	5'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
12	BEDRM 1	D	NEW	4'-0"	5'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
20	(N) BEDRM 5 (ADA)	E	NEW	5'-0"	4'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
21	(N) BEDRM 6 (ADA)	E	NEW	5'-0"	4'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	
22	KITCHEN 2	C	NEW	4'-0"	4'-0"	ANDERSEN 100 OR EQUAL	TEMPERED (SGL)	PASSIVESUN	0.28	0.45	COMP.	WHITE	

- ### WINDOW NOTES
- SEE EXTERIOR ELEVATION FOR DIRECTION OF OPERATION OF WINDOWS (ALL OPERABLE WINDOWS TO HAVE SCREENS).
 - ALL WINDOW DIMENSIONS PERTAIN TO ROUGH OPENINGS (R.O.), CONTRACTOR TO FIELD VERIFY ACTUAL DIMENSIONS FOR WINDOWS.
 - ALL GLAZING WILL BE INSTALLED WITH A CERTIFYING LABEL ATTACHED, SHOWING THE NFRC LABEL.
 - ALL GLAZING SHALL BE SPECTRALLY SELECTIVE LOW E COATED TO MEET TITLE 24 ENERGY REQUIREMENTS.
 - WINDOWS SHALL MEET THE MINIMUM INFILTRATION REQUIREMENTS PER SECTION 116 E.E.S.D
 - VENTILATION SHALL COMPLY WITH C.B.C. 1203.4 AND R303
 - EVERY SLEEPING ROOM SHALL HAVE ONE OPERABLE WINDOW FOR EMERGENCY ESCAPE OR RESCUE WITH A MIN. NET CLEAR OPENABLE AREA OF 5.7 SQ. FT. MIN. NET CLEAR OPENABLE HEIGHT OF 24" MIN., NET CLEAR WIDTH OF 20" AND A FIN. SILL HEIGHT OF NOT MORE THAN 44" A.F.F. PER CRC SECTION 3101
 - ALL EXTERIOR WINDOW AND EXTERIOR DOOR ASSEMBLIES TO HAVE AN STC RATING OF 30 OR GREATER.
 - TEMPERED GLASS SHALL BE PERMANENTLY IDENTIFIED AND VISIBLE WHEN THE UNIT IS GLAZED.
 - EVERY SPACE INTENDED FOR HUMAN OCCUPANCY SHALL BE PROVIDED WITH NATURAL VENTILATION AND NATURAL LIGHT BY MEANS OF VENTILATION / ARTIFICIAL LIGHT. CBC SECTIONS 1203.4 AND 1205.1 AND R303
 - THE MINIMUM NET GLAZED AREA FOR NATURAL LIGHT SHALL NOT BE LESS THAN 8% OF THE FLOOR AREA OF THE ROOM SERVED. CBC SECTION 1205.2
 - THE MINIMUM OPENABLE AREA TO THE OUTDOORS FOR NATURAL VENTILATION SHALL BE 4% OF THE FLOOR AREA BEING VENTILATED. SECTION 1203.4
 - EXTERIOR WINDOWS AND EXTERIOR GLAZED DOOR ASSEMBLIES SHALL BE CONSTRUCTED OF MULTIPANE GLAZING WITH ONE TEMPERED PANE. HAVE A FIRE RESISTANCE RATING OF 20 MINUTES OR MEET THE REQUIREMENTS OF SFM 12-7A-2.



1 WINDOW TYPES
SCALE: 1" = 1'-0"

RATTLESNAKE RESIDENCE

12875 RATTLESNAKE ROAD
GRASS VALLEY, CA 95945
APN: 022-020-026-000

ID	NAME	DATE
1	REV 1	5/1/26

SUBMITTED: DATE
SCALE: AS NOTED
DRAWN BY: GTB
CHECKED BY: RPD
JOB: 2025.33

DOOR & WINDOW SCHEDULES


JOB SET

A6.0

U:\enrg\mfr\RD\A-D Dropbox\RD\A-D Projects\Current\2025-33 AMH HomeKey\Rattlesnake\Acht\CA\DR\enrg\mfr\Rattlesnake.pht

Nevada County Homekey + Rattlesnake Residence

12875 Rattlesnake Rd.
Grass Valley, CA 95945




1504 Eureka Road #370
Roseville, CA 95661
(916) 790-3181

WWW.ASHLEYVANCE.COM

CIVIL • STRUCTURAL


ENGINEER OF RECORD:




STANDARD DETAILS

9 TYPICAL NOTCHING & BORING


PENETRATIONS IN TOP PLATES & SILL PLATES




NOTCHING LIMITS FOR WOOD STUDS




BORING LIMITS FOR WOOD STUDS




6 TYPICAL FLOOR / ROOF NAILING



4 TYPICAL CONCRETE SLAB JOINTS



1 TYPICAL REINFORCING BAR BENDS



ABBREVIATIONS

AB	Anchor Bolt	MB	Maximum
A&B	Above and Below	MB	Machine Bolt
Abv.	Above	MF	Moment Frame
Add'l.	Additional	Mfr.	Manufacturer(s)
Adj.	Adjacent	Min.	Minimum
Alt.	Alternate(s)	Mod.	Modular, Module
Appd.	Approved	(N)	New
Arch.	Architectural	N/A	Not Applicable
Avg.	Average	NTS	Not to Scale
AYC	Alaskan Yellow Cedar	OC	On Center
Bldg.	Building	OD	Outside Diameter
Bkg.	Blocking	OPNG	Opening
Bw.	Below	Opp.	Opposite
Bm.	Beam	Opt.	Option, (al)
BN	Boundary Nailing	Para.	Parallel
Bot.	Bottom	Pen.	Penetrate, (ion)
Brp.	Bearing	Perf.	Perforated
Btwn.	Between	Perim.	Perimeter
Cant.	Cantilevered	Perp.	Perpendicular
CIP	Cast in Place	PI	Plywood Index
CJP	Ceiling Joist Complete Joint Penetration	PJP	Partial Joint Pen.
CL	Center Line	PL	Plywood
Clg.	Ceiling	Prep.	Prepare, (ation)
Clr.	Clear	Press.	Pressure
CMU	Conc. Masonry Unit	Proj.	Project
Col.	Column	Prop.	Property
Conc.	Concrete	PSF	Pounds per Sq. Ft.
Conn.	Connection	PT	Pressure-Treated
Const.	Construction	PV	Photovoltaic (Solar Panels)
Cont.	Continue, (ous)	R	Radius
Cr.	Center	Rec(s)	Recommendation(s)
d	Double	Ref.	Reference
Defl.	Deflection	Reinf.	Reinforce, (ed), (ement), (ing)
Demo.	Demolish, (ion)	Req'd	Require, (d)
Dep.	Depress, (ed)	Reqs.	Requirements
DF	Douglas Fir	Ret.	Retaining
Dia.	Diameter	RJ	Roof Joist
Diaph.	Diaphragm	RR	Roof Rafter
Dim.	Dimension	RW	Redwood
Dist.	Distance	Sched.	Schedule
DJ	Deck Joist	Shg.	Sheathing
Dwg.	Drawing	Sim.	Similar
(E)	Existing	SIP	Struct. Insulated Panel
EA	Each	SMS	Sheet Metal Screw
EF	Each Face	SOG	Slab on Grade
Elev.	Elevation	Spec.	Specify, (ed), (cation)
Embed	Embed, (ded), (ment)	Spec.	Specify, (ed), (cation)
Engr.	Engineer	SS	Stainless Steel
EOR	Engineer of Record	SS	Select Struct. Grade
Eq.	Equal, Equivalent	Std.	Standard
ES	Each Side	Std.	Standard
EW	Each Way	Stl.	Steel
Exp.	Expansion	Struct.	Structure, (al)
Ext.	Exterior	SW	Shear Wall
Fdn.	Foundation	T&B	Top and Bottom
FF	Finished Floor	T&G	Tongue and Groove
FJ	Floor Joist	Temp.	Temporary
Fr.	Framing	Thk.	Thickness
Frmg.	Framing	TN	Toe-Nail
Ft.	Feet	TP	Top Plate
Fig.	Footing	T&B	Top of Beam
Gal.	Gauge	TOC	Top of Concrete
Galv.	Galvanized	TOG	Top of Grade
GB	Grade Beam	TOS	Top of Steel
GC	General Contractor	TOW	Top of Wall
GLB	Glulam Beam	Trmr.	Trimmer Stud
Gyp.	Gypsum	Typ.	Typical
HD	Holddown	UNO	Unless Noted
Hdr.	Header	Vert.	Vertical
Hdw.	Hardware	VIF	Verify in Field
Hng.	Hanger	W	With
Horiz.	Horizontal	w/in	Within
HT	Height	w/o	Without
ID	Inside Diameter	Wt.	Weight
In.	Inches	WWF	Welded Wire Fabric
Insp.	Inspect, (ion)	WWM	Welded Wire Mesh
Int.	Interior		
Invt.	Invert, Inverted		
KS	King Stud	@	At
KP	King Post	&	And
Loc.	Location	°	Degrees
LW	Light Weight	>	Greater Than
		<	Less Than
		#	Number, Pound(s)
		%	Percent, (age)
		±	Plus or Minus

PROJECT INFORMATION

ARCHITECT:
Russell Davidson Architecture + Design
149 Crown Point Court, Suite C
Grass Valley, CA 95945


DESIGN PARAMETERS

GENERAL PARAMETERS	
Building Code	2025 CBC*
Roof Loads	
Dead Loads** (DL)	15 psf
**Includes 3 psf PV Loads	
Live Loads (LL)	20 psf
Snow Loads (SL) Pg/Ps	103/87 psf
SOILS VALUES	
(Table 1806.2)	
Bearing Pressure	1500 psf
WIND DESIGN BASIS	
Ultimate Wind Speed, V_{ULT}	95 mph
Risk Category	II
Exposure	C
Int. Press. Coefficient, GC_{pi}	±0.18
SEISMIC DESIGN BASIS	
Seismic Design Category	D
Site Class	D
Seismic Factors	
S_s / S_1	0.780 / 0.240
S_{DS} / S_{D1}	0.690 / 0.420
Risk Category	II
Importance Factor, I_p	1.00
Resisting System:	Wood Shear Walls
Response Mod. Coefficient, R	6.5
Design Base Shear	$V = 0.106W$
Analysis Procedure:	Eqv. Lateral Force (ASCE 7, T. 12.6-1)


TYPICAL SHEAR WALL FRAMING NOTES:

- Single sided shear walls may be placed on EITHER side of the framed wall.
- Sill plates on masonry or concrete to be pressure treated per Timber / Lumber specifications. Sill plate thickness per SW Sched.
- Wall studs and blkg. are required at all adjoining panel edges. Thickness of wall studs and blkg. at panel edges per SW Sched.
- Where plywood is applied on both faces of a wall, edge nails shall be staggered on adjacent panel edges OR panel joints shall be offset to fall on different framing members. Plywood joint and sill plate nailing shall be staggered in all cases.
- Plywood panels shall butt along centerlines of framing members. Minimum plywood dimension for shearwall shall be 12".
- Nails shall be located at least 3/8" from all panel edges.
- The use of pneumatic nail guns for shear wall nailing is subject to continued satisfactory jobsite performance and subject to the review and approval by the Engineer of Record and/or Building Inspector. If the nail heads penetrate the outer ply more than would be normal for a hand held hammer, or if the minimum edge distances are not maintained, the performance will be deemed as unsatisfactory and the continued use of pneumatic nail for shear wall nailing will not be permitted.
- At all bearing walls (both exterior and interior walls) not noted as shear walls, continuous full depth blocking shall be provided between joists and rafters with LTP4 or A35 to top plates @ 32" oc at floors and 48" oc at roofs, unless noted otherwise per plan.
- Refer to material specifications for additional framing requirements.



SHEAR WALL LEGEND



8 TYPICAL SHEAR WALL FRAMING



3 TYPICAL WOOD FRAMED OPENING



REVISION:	
03.16.2026	Issued for Permit
05.01.2026	Plan Revision #1

SHEET INDEX

S-1.1	Structural Title Sheet
S-1.2	Structural Specifications
S-2.1	Foundation Plan
S-2.2	Roof Framing Plan
S-3.1	Structural Details

PROJECT ENGINEER:
Ariene Castillo
(916) 790-3181 x217
ariene@ashleyvance.com

DATE: 2/24/26 SCALE: NTS
AV JOB: 251477 SHEET SIZE: 24"x36"

STRUCTURAL TITLE
JOB SET
S-1.1

THESE PLANS AND SPECIFICATIONS ARE THE PROPERTY OF ASHLEY & VANCE ENGINEERING INC. AND ARE RESTRICTED FOR USE ON THE ORIGINAL SITE FOR WHICH THEY WERE PREPARED. REPRODUCTION OR PUBLICATION IN ANY FORM, WHOLE OR IN PART, IS PROHIBITED. VISUAL CONTACT WITH THESE DOCUMENTS CONSTITUTES ACCEPTANCE OF THESE RESTRICTIONS.

GENERAL NOTES

- 1. The following notes, details, schedules & specifications shall apply to all phases of this project unless specifically noted otherwise. Notes and details on the structural plans shall take precedence over general notes and typical details. Where no details are given, construction shall be as shown for similar work.
2. All drawings are considered to be part of the contract documents. The Contractor shall be responsible for the review and coordination of all drawings and specifications prior to the start of construction. Any discrepancies shall be brought to the attention of the Engineer prior to the start of construction so that a clarification can be issued. Any work performed in conflict with the contract documents or any applicable code requirements shall be corrected by the Contractor at no expense to the Owner or Engineer.
3. All information on existing conditions shown on the structural plans are based on best present knowledge available, but without guarantee of accuracy. The Contractor shall be responsible for the verifications of all dimension and conditions at the site. Any discrepancies between actual site conditions and information shown on the drawings or in the specifications shall be brought to the attention of the EOR prior to the start of construction.
4. Refer to the Architectural plans for the following:
(a) Dimensions
(b) Size and location of all interior and exterior wall locations.
(c) Size and location of all floor, roof and wall openings
(d) Size and location of all drains, slopes, depressions, steps, etc.
(e) Specification of all finishes & waterproofing
(f) All other non-structural elements
5. Refer to the mechanical, electrical and plumbing plans for the following:
(a) Size and location of all equipment
(b) Pipe runs, sleeves, hangers and trenches
(c) All other mechanical, electrical or plumbing related elements
6. DO NOT scale structural plans. Contractor shall use all written dimensions on Architectural plans.
7. Construction materials shall be uniformly spread out if placed on floor or roof so as to not overload the framing. Load shall not exceed the design live load per square foot. It is the Contractor's responsibility to provide adequate shoring and/or bracing as required.
8. Specifications and detailing of all waterproofing and drainage items, while sometimes shown on the structural plans for general information purposes only, are solely the design responsibility of others.
9. The Engineer will not be responsible for and will not have control or charge of construction means, methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the construction delineated by these plans. It should be understood that the Contractor or his/her agent(s) shall supervise and direct all work and shall be solely and completely responsible for all construction means, methods, techniques, sequences, procedures and conditions on the job site, including safety of all persons and property during the entire period of construction. Periodic observations by the Engineer, his staff or representatives are not intended to include verification of dimensions or review the adequacy of the Contractor's safety measures on or near the construction site.
10. Modifications of the plans, notes, details and specifications shall not be permitted without prior approval from the Engineer.
11. All workmanship shall conform to the best practice prevailing in the various trades performing the work. The Contractor shall be responsible for coordinating the work of all trades.
12. It is the Contractor's responsibility to ensure that only approved structural plans are used during the course of construction. The use of unapproved documents shall be at the contractor's own risk. Corrections of all work based on such documents shall be performed at the Contractor's expense.
13. These plans and specifications represent the structural design only. No information nor warranty is provided for the work of any other Consultant (Architect, Mechanical, Electrical, etc.). This includes, but is not limited to, waterproofing, drainage, ventilation, accessibility, or dimensions.

FOUNDATIONS

- 1. Refer to Structural Design Parameters section on sheet S-1.1 for all soil design values used in calculations.
2. Soils values per Table 1806.2 of the latest edition of the Governing Building Code.
3. Unexpected Soil Conditions: At the discretion of the engineer of record, or the local building department, a soils report may be required in the event that substandard material is discovered on site. If this occurs, contact Engineer of Record for further guidance.
4. All compaction, fill, backfilling and site preparation shall be performed in accordance with project soils report or the Governing Building Code Chapter 18 & Appendix J. All such work shall be performed under the supervision of the building official.
5. Excavate to required depths and dimensions (as indicated in the drawings), cut square and smooth with firm level bottoms. Care shall be taken not to over-excavate foundation at lower elevation and prevent disturbance of soils around high elevation.
6. Foundations forms and excavations shall be clean and free of debris, achieving all minimum dimensions noted. Encroachment of soil at corners and reduced reinforcement clearances are not permitted.
7. Excavate all foundations to required depths into compacted fill or natural soil (as per plans and details) and as verified by the building official.
8. All foundations shall be inspected and approved by the appropriate building official prior to forming and placement of reinforcing or concrete.
9. Foundations shall not be poured until all required reinforcing steel, framing hardware, sleeves, inserts, conduits, pipes, etc. and formwork is properly placed and inspected by the appropriate building official/inspector(s).
10. It is the responsibility of the contractor in charge of framing to properly position all holdown bolts, anchor bolts, column bases, and all other cast-in-place hardware. Refer to typical details. All hardware to be secured prior to foundation inspections.
11. The sides and bottoms of dry excavations must be moistened to optimum moisture content or just above, just prior to placing concrete. Conversely, de-water footings as required to remove standing water and to maintain optimum working conditions.
12. The Contractor shall be solely responsible for all excavation procedures including lagging, shoring, and the protection of adjacent property, structures, streets, and utilities in accordance with all federal, state and local safety ordinances. The Contractor shall provide for the design and installation of all cribbing, bracing and shoring required.

EXISTING CONDITIONS

- 1. Work shown is new unless noted as Existing: (E).
2. Existing construction shown on these drawings was obtained from existing drawings and/or site investigation. Field verify all conditions & dimensions prior to shop drawing production and fabrication of structural elements.
3. Where existing conditions vary significantly from those shown on these drawings, the Engineer shall be notified prior to continued construction related to subject conditions.
4. Shore all existing construction as required, including where welding to existing steel framing. Shoring design by others.
5. Do not core or cut new openings in existing concrete or masonry without specific approval of the Engineer. All existing concrete surfaces to be in contact with new concrete shall be cleaned and roughened to 1/4" minimum amplitude. Use ICC approved bonding agent on existing concrete prior to placing new concrete.
6. Verify location of existing rebar before fabrication using non-destructive testing. Existing reinforcing shall be avoided where drilling for post-installed anchors or concrete dowels.
7. All existing (E) wood elements to remain shall be field inspected during construction and treated for dryrot removal / control. Where existing GLB's to remain are found to have extensive dryrot deeper than the top two laminations (3"), the structural engineer shall be notified prior to continued construction related to subject GLB's.
8. All existing connections at elements to be replaced shall be replaced or re-attached to match existing conditions.

ROUGH CARPENTRY

- 1. Refer to latest edition of the Governing Building Code, Table 2304.10.2, for all minimum nailing requirements.
2. Refer to individual sections for applicable material specifications.
3. Fabricate, size, install, connect, fasten, bore, notch, and cut wood and plywood with joints true, tight, and well-nailed, screwed or bolted as required, all members to have solid bearing without being shimmed, unless noted otherwise. Set horizontal members subject to bending with the crown up. Install framing plumb, square, true and cut for full bearing. Splices are not permitted between bearings. Use full lengths unless otherwise specified.
4. Metal framing angles, anchor, clips, straps, ties, holdowns, etc. shall be manufactured by Simpson Strong-Tie Co. No substitutions shall be permitted without prior approval of the Engineer.
5. All walls are to have continuous double 2x top plates spliced per Detail 7/S-1.1 unless specifically noted otherwise on the plans and details.
6. Wall Studs:
(a) Unless specifically noted on the plan and details, use the following guidelines for wall framing:
i. Use 2x4 studs at 16" oc for walls less than 9'-0" tall.
ii. Walls 9'-0" to 16'-0" tall shall be constructed of 2x6 studs at 16" oc
iii. Request specifically engineered wall details for walls greater than 16'-0" tall.
7. Blocking:
(a) Provide min. one row of nominal 2" thick blocking of same width as stud, fitted snugly and spiked into studs at mid-height of partitions or walls over 8' high.
(b) All foundation cripple walls (or "pony walls") less than 14" in height shall be solid blocking.
(c) Rim blocking/rim board to be 1-1/4" minimum width x full depth at bearing walls, UNO per plans and details. Refer to shearwall section for additional rim/blocking requirements.
8. Notching:
(a) Is not permitted of any structural member without prior approval
(b) In exterior and bearing walls, notches shall not exceed 25% of the stud depth.
(c) Non-bearing partition walls, notches shall not exceed 40% of the stud depth.
(d) Successive notches in the same member shall be spaced a min of 18" apart.
9. Boring:
(a) Is not permitted of any structural member without prior approval
(b) In exterior and bearing walls, holes shall not exceed 40% of the stud depth.
(c) Non-bearing partition walls, may be drilled not greater than 60% of stud depth.
(d) Successive holes in the same member shall be spaced a minimum of 18" apart.
10. Bearing:
(a) Provide a min. of 1-1/2" of bearing for all 2x joists and hdsr 4x10 / 6x8 & smaller.
(b) Provide a min. of 3" of bearing for all beams and hdsr 4x12 / 6x10 & larger, UNO on plans.
(c) Members bearing on prefabricated hangers are to have full bearing and nailing per manufacturer's specifications.
11. Posts:
(a) Posts inside walls shall bear on sill plates and shall be continuous between top and bottom plates, unless specifically noted otherwise.
(b) Provide posts under all beams, girders or double joists equal to the width of the supported member.
(c) Posts on upper levels are to be stacked on posts of equal size at levels below, unless a larger post is specified on the plans.
(d) Vertically oriented blocking ("squash blocking") shall be used to fully transfer the post area through floors to foundation. Vertical blocking shall be equal to floor thickness plus 1/16".
(e) Headers framing into continuous posts without trimmer studs shall be supported in Simpson HUC hangers unless noted otherwise on the plans.
(f) Isolated posts shall be seated in Simpson post or column bases, unless noted otherwise on the plans.
12. Roof Framing:
(a) Provide wood joists, as specified, laid with the crown up and spaced as indicated.
(b) Provide a minimum of 1-1/2" end bearing unless otherwise shown.
(c) Provide full depth solid 2x blkgr or cross-bridging between the joists at 8' oc max.
(d) Provide all cricket framing required to achieve positive drainage per Arch.
(e) Install plywood panels with the face grain across the framing and close joints and nail at each support. Fully nail with common nails per the plans.
(f) Plywood panels shall not be less than 4" x 8' except at boundaries and changes in framing direction, where the minimum panel dimension shall be no less than 24", unless all edges of undersized panels are supported by and fastened to framing members or blocking.
(g) Provide Simpson "PSCL" clips at all plywood joints perpendicular to framing. Provide clips midway between framing members at the unsupported edges of plywood when members are spaced at 24" or greater. If clips are not used, provide solid blocking for joints perpendicular to framing.
13. Floor Framing:
(a) Provide wood joists, as specified, laid with the crown up and spaced as indicated.
(b) Provide a minimum of 1-1/2" end bearing unless otherwise shown.
(c) Provide full depth solid 2x blkgr or cross-bridging between the joists at 8' oc max. For floors framed with I joists, refer to the mfg's spec's for blkgr requirements.
(d) Provide full depth solid 2x blocking between the joists under all walls and partitions where the wall or partition is perpendicular to the floor framing (including floors framed with I joists)
(e) Install plywood sheathing with the face grain across supports, end supports staggered, and the edges of sheets centered over supports. If T&G plywood is used, blocking need not be provided at all plywood edges (UNO per plan). If T&G plywood is not used, blocking shall be provided at all plywood edges. Glue plywood to joists and fully nail with common nails per the plans.
(f) Plywood panels shall not be less than 4" x 8' except at boundaries and changes in framing direction, where the minimum panel dimension shall be no less than 24", unless all edges of undersized panels are supported by and fastened to framing members or blocking.
14. Shear Walls:
(a) Refer to plans for all shearwall locations, length type and nailing.
(b) Refer to Shearwall Schedule on title sheet for additional information.
(c) Shear wall lengths specified on plans are minimum required.
(d) Shear walls to be nailed with common nails. All nails to have minimum 3/8" edge distance to panel or framing member.
(e) Where 3x framing is required per the shear wall schedule, stagger edge nailing.
(f) Oriented Strand Board (OSB) may be used in lieu of plywood.
(g) Typical Rim Board/Blocking at Shearwalls shall be 1-3/4" Min. LSL (refer to Engineered Lumber Section for Material Specifications). Refer to Shearwall Schedule per Plan for Min. Rim/Blkg Width Requirements per Transfer Fasteners.

TIMBER / LUMBER

- 1. All structural lumber shall be Douglas Fir-Larch, S4S and shall conform to the Governing Building Code, section 2303.1.1.
2. The minimum lumber grade of each member shall be as follows (unless specifically noted otherwise on plans and details):
(a) 2x studs, blocking, plates: Stud
(b) 2x joists #2 or better
(c) 4x4, 4x6, or 6x6 beams or posts #2 or better
(d) 4x8, 6x8, or larger beams or posts #1 or better
It is recommended (but not required) that all exposed members be Select Structural or better and free of heart center due to visual characteristics.
3. All lumber in contact with concrete or masonry shall be pressure treated Douglas Fir. Whenever it is necessary to cut, notch, bore or splice pressure treated material, all newly cut surfaces shall be thoroughly painted with the same preservative.
4. Maximum moisture content for all structural members shall not exceed 19%.
5. All plywood sheathing shall be CDX grade (or better) Douglas Fir with exterior glue. All sheathing shall conform to the Governing Building Code and grade-marked by the American Plywood Association (APA). Panel index to be 40/20 for floors and 24/0 for roofs unless specifically noted otherwise on the plans and details.

ENGINEERED LUMBER

- 1. Glu-laminated Beams (GLB):
(a) shall have the following properties:

Use	EWS Combination Symbol	Species / Grade	Flexural Stress, Fb (ksi)	Modulus of Elasticity, E (ksi)	Horiz. Shear Stress, Fv (psi)	Compression Fc para. (psi)	Compression Fc perp. (psi)
Simple Span Bm	24F-V4	DF	+2,400/-1,850	1,800	265	1,650	650
Continuous or Cantilever Bm	24F-V8	DF	+/- 2,400	1,800	265	1,650	650
Columns	2	DF / L2	+/- 1,800	1,300	265	1,600	560

(b) shall not be notched, cut or drilled without prior approval from the Engineer
(c) shall have exterior glue and weather-treatment prior to installation
(d) shall be fabricated by an approved manufacturer & in accordance with ANSI A 190.1
(e) shall have factory standard camber of 3,500-5,000 ft on beams UNO per Plan
2. Laminated Veneer Lumber (LVL):
(a) shall be 1-3/4" minimum thickness with the following minimum properties:
i. E = 2000 ksi
ii. Fb = 2600 psi
iii. Fv = 285 psi
iv. Fc (parallel) = 2500 psi
v. Fc (perp.) = 750 psi
vi. Ft (parallel) = 1500 psi
vii. Specific Gravity = 0.50
(b) shall be fabricated by an approved manufacturer
(c) shall bear a minimum of 3-1/2" on specified supports. Provide full depth solid blocking at all bearing points
(d) shall be nailed in accordance with mfg's specifications. Unless otherwise approved, nailing into the top edge shall not be spaced any closer than:
i. 16d @ 8" oc, 10d @ 5" oc, and 8d @ 4" oc
ii. When nailing must be reduced, stagger rows a minimum of 1/2" apart while maintaining proper edge distances.
(e) shall be, when comprised of multiple members, connected with 16d nail, 1/2" bolts or 1/4" lag screws in accordance with manufacturer's specifications.
(f) shall not be cut, notched or drilled without specific written approval of the EOR.
3. Laminated Strand Lumber (LSL):
(a) shall be 1-3/4" minimum thickness with the following minimum properties:
i. E = 1550 ksi
ii. Fb = 2325 psi
iii. Fv = 310 psi
iv. Fc (parallel) = 2170 psi
v. Fc (perp.) = 900 psi
vi. Ft (parallel) = 1070 psi
vii. Specific Gravity = 0.50
(b) shall be fabricated by an approved manufacturer
(c) shall bear a minimum of 3-1/2" on specified supports. Provide full depth solid blocking at all bearing points
(d) shall be nailed in accordance with mfg's specifications. Unless otherwise approved, nailing into the top edge shall not be spaced any closer than:
i. 16d @ 8" oc, 10d @ 4" oc, and 8d @ 4" oc
ii. When nailing must be reduced, stagger rows a minimum of 1/2" apart while maintaining proper edge distances.
(e) shall be, when comprised of multiple members, connected with 16d nail, 1/2" bolts or 1/4" lag screws in accordance with manufacturer's specifications.
(f) shall not be cut, notched or drilled without specific written approval of the EOR.
4. Parallel Strand Lumber (PSL):
(a) shall be 2-1/2" minimum thickness with the following minimum properties:
i. E = 2200 ksi
ii. Fb = 2900 psi
iii. Fv = 290 psi
iv. Fc (parallel) = 2900 psi
v. Fc (perp.) = 625 psi
vi. Ft (parallel) = 2300 psi
vii. Specific Gravity = 0.50
(b) shall be fabricated by an approved manufacturer
(c) shall bear a minimum of 3-1/2" on specified supports. Provide full depth solid blocking at all bearing points
(d) shall be nailed in accordance with manufacturer's specifications. Unless otherwise approved, nailing shall not be spaced any closer than:
i. Narrow face: 16d @ 6" oc, 10d @ 4" oc, and 8d @ 4" oc
ii. Wide Face: 16d @ 8" oc, and 10d & 8d @ 6" oc
iii. When nailing must be reduced, stagger rows a minimum of 1/2" apart while maintaining proper edge distances
(e) shall not be cut, notched or drilled without specific written approval of the EOR.
5. Plywood I Joists:
(a) type and manufacturer shall be clearly noted on the plans. Substitutions shall not be permitted without prior approval of the Engineer.
(b) shall be installed in accordance with applicable code approvals and mfg's spec's.
(c) shall bear a minimum of 1-3/4" at all end supports, and 3-1/2" at intermediate supports. Provide full depth solid blocking at all bearing points.
(d) shall be installed with intermediate blocking or bridging as specified by the Mfr. Only omit intermediate blocking when specifically allowed by the Mfr.
(e) shall not be cut, notched or drilled without specific written approval of the EOR.

WOOD FASTENERS

- 1. All Fasteners:
(a) shall be hot-dipped zinc-coated galvanized steel, stainless steel, silicon bronze, or copper when in contact with preservative-treated wood
i. When used in exterior applications, fasteners shall have coating types and weights in accordance with the treated wood or bolt manufacturer's requirements. A min. of ASTM A153, type G185 zinc-coated galvanized steel (or equiv.) shall be used.
ii. When used in an interior, dry environment in SBX/DOT or zinc borate preservative-treated wood, plain carbon nails shall be permitted.
2. Nails:
(a) shall be with "common" nails unless noted otherwise.
(b) shall not be driven closer than 1/2 their length nor closer than 1/4 of their length to the edge or end of a member, except for sheathing.
(c) shall be installed in pre-drilled lead holes if necessary to avoid splitting.
(d) All nailing shall conform to the Governing Building Code, Table 2304.10.2.
3. Lag screws:
(a) shall be installed into pre-drilled lead holes. Lubricant (or soap) shall be used to facilitate installation and prevent damage to the screws.
4. Bolts to Wood Framing:
(a) shall conform to ASTM A307, UNO specifically on plans and details.
(b) shall be installed in pre-drilled holes a max of 1/16" larger than the specified bolt dia.
(c) when installed against wood surfaces, shall have standard washers (ASTM F436) under the heads and nuts.
5. Anchor Bolts:
(a) shall be installed at all exterior walls and all interior shear and/or bearing walls.
(b) shall be 5/8" diameter with 3x3x0.229" steel plate washers at shearwalls.
(c) shall be 5/8" diameter with 2x2x3/16" steel plate washers at non-shearwalls.
(d) shall have 7" minimum embedment. (Contractor to coordinate length of bolts with sill plate thicknesses).
(e) shall conform to ASTM F1554, Grade 36, UNO.
(f) shall not be spaced greater than 72" oc Refer to shearwall schedule for specific anchor bolt spacing requirements.
(g) shall be placed a maximum of 12" from wall corners, wall ends, and sill plate splices (but not less than 7 dia.), and a min. of two bolts per piece of sill plate is required.
(h) shall be secured in place prior to foundation inspection.
(i) shall have a minimum edge distance of 1-3/4", UNO per plans and details.
6. Anchor Rods:
(a) shall be fully threaded, UNO.
(b) shall have 12" minimum embedment, UNO. (Contractor to coordinate length of bolts with min. projection above connected parts).
(c) shall be heavy hex headed or terminate w/ double nut and washer per details, UNO.
(d) shall conform to ASTM F1554, Grade 36, UNO.
(e) shall be secured in place prior to foundation inspection.
(f) shall have a minimum edge distance of 1-3/4", UNO per plans and details.
7. Powder Actuated Shot Pins:
(a) shall be installed at all interior non-bearing, non-shearwalls.
(b) shall conform to ICC ESR-2138, or equivalent.
(c) shall be 0.157x3" with 1.5" diameter steel washers, UNO.
(d) shall mechanically galvanized when installed in preservative-treated or fire-retardant-treated wood.
(e) shall not be spaced greater than 32" o.c.



1504 Eureka Road #370
Roseville, CA 95661
(916) 790-3181

WWW.ASHLEYVANCE.COM

CIVIL • STRUCTURAL

ENGINEER OF RECORD:



Nevada County Homekey +
Rattlesnake Residence
12875 Rattlesnake Rd.
Grass Valley, CA 95945

REVISION table with columns for date and description. Includes entries for 03.16.2026 (Issued for Permit) and 05.01.2026 (Plan Revision #1).

PROJECT ENGINEER:
Arlene Castillo
(916) 790-3181 x217
arlene@ashleyvance.com
DATE: 2/24/26 SHEET: NTS
AV JOB: 251477 SHEET SIZE: 24"x36"

STRUCTURAL
SPECIALISTS
JOB SHEETS

S-1.2




**Nevada County Homekey +
Rattlesnake Residence**
12875 Rattlesnake Rd.
Grass Valley, CA 95945

REVISION:	
03.16.2026	Issued for Permit
05.01.2026	Plan Revision #1

PROJECT ENGINEER:
Ariene Castillo
(916) 790-3181 x217
ariene@ashleyvance.com

DATE: 2/24/26 SCALE: 1/4"=1'-0"
AV JOB: 251477 SHEET SIZE: 24"x36"

FOUNDATION PLAN
JOB SET
S-2.1




NOTE:
Contractor to Investigate to Identify if an Existing Continuous Foundation Occurs along Gridline 4 Prior to Cutting for New Footings.

GENERAL FOUNDATION NOTES

Foundations per Governing Building Code, Table 1806.2
At the request of the client (or client's agent), Ashley & Vance Engineering has designed the foundations in conformance with Table 1806.2. If the building official determines that expansive soils are present, or other geologic issues of concern, then they may require that special provisions be made to the foundation design to safeguard against damage due to the expansiveness or due to other geologic issues. If this becomes the situation, all foundation construction must be halted and the client, at their own expense, shall: (a) obtain a soils report prepared by a Soils Engineer licensed in the state of the project; (b) commission Ashley & Vance Engineering to revise the foundation plans and details, and framing plans if necessary, to reflect the recommendations of the soils report; (c) submit the revised plans to the Building Department for approval.

See General Notes & Specifications for additional requirements and material specifications.
All dimensions per Architectural plans
Contractor to VERIFY all dimensions w/ Architectural plans PRIOR to commencement of construction.





**Nevada County Homekey +
Rattlesnake Residence**
12875 Rattlesnake Rd.
Grass Valley, CA 95945

REVISION:	
03.16.2026	Issued for Permit
05.01.2026	Plan Revision #1


PROJECT ENGINEER:
Ariene Castillo
(916) 790-3181 x217
ariene@ashleyvance.com

DATE: 2/24/26 SCALE: 1/4"=1'-0"
AV JOB: 251477 SHEET SIZE: 24"x36"

**ROOF FRAMING
JOB SET**

S-2.2

DO NOT SCALE THESE DRAWINGS. REFER TO ARCHITECTURAL PLANS FOR ALL DIMENSIONS.



WALL SCHEDULE	
Stud wall locations per Architecturals.	
(E) Wood-Framed Wall to be Removed (See Arch.)	—
(E) Wood-Framed Wall to Remain	—
(N) Wood-Framed Wall, Thk. per Arch. 2x4 Min. DF Stud @ 16" oc	—
All Walls to have Continuous Double Top Plates, All Splices to be per Detail 7/S-1.1	
Walls above	---
(shown for clarity)	---

GENERAL FRAMING NOTES

(N) Beams (per Call-out)
(E) Beams (to Remain)

All Lumber 4x6, 6x6 and Smaller to be DF #2 UNO
All Lumber 4x8, 6x8 and Larger to be DF #1 UNO
All Beams to Bear on Plates w/ Indicated Post or Doubler Below UNO
All Hangers Shall be Installed w/ Max. Nailing per Mfr. & Sized for Full Width & Depth of Supported Members, UNO

(E) Framing (to Remain)

Waterproofing, flashing, & finish details per Architecturals.

See General Notes & Specifications for additional requirements and material specifications.

All dimensions per Architectural plans
Contractor to VERIFY all dimensions w/ Architectural plans PRIOR to commencement of construction.
Contractor shall verify all existing conditions prior to construction & contact Engineer and Architect regarding any discrepancies.

THESE PLANS AND SPECIFICATIONS ARE THE PROPERTY OF ASHLEY & VANCE ENGINEERING INC. AND ARE RESTRICTED FOR USE ON THE ORIGINAL SITE FOR WHICH THEY WERE PREPARED. REPRODUCTION OR PUBLICATION IN ANY FORM, WHOLE OR IN PART, IS PROHIBITED. VISUAL CONTACT WITH THESE DOCUMENTS CONSTITUTES ACCEPTANCE OF THESE RESTRICTIONS.


17 NOT USED

13

9 NOT USED

5 NOT USED

1 RAISED FLOOR ON (E) SLAB ON GRADE



18 NOT USED

14


10 NOT USED

6 NOT USED

2 RAISED FLOOR AT SLAB STEP

For Items Not Shown or Noted, See Detail 1/S-3.1

Shim with P.T. Members @ 16" o.c. Max., As Req'd



Note: Special Inspection is not required

PBS to Fit


#4x12" Dowels @ 18" o.c. Max. Typ. Around. Drill & Epoxy, Typ. 2-Min. per Side

(E) Slab

(3) #4 Ea. Way, Eq. Spaced

Per Plan Ctr'd on Post

3 TYPICAL PAD IN EXISTING SLAB




19 NOT USED

15

11 NOT USED

7 NOT USED



Simpson Titen HD Bolt w/ 4/2" Min. Embed. Spaced per Wood Fastener Specifications on S-1.2 Install per Mfr. Specs (Refer to Spec's for Add'l Reqs)

Sill PL per Specs

Stud Wall per Plan

Existing Foundation

1-3/4" Edge Distance Min.

SECTION

20 NOT USED

16

12 NOT USED

8 NOT USED

4 INFILL WALL TO EXISTING SLAB EDGE



1504 Eureka Road #370
Roseville, CA 95661
(916) 790-3181

WWW.ASHLEYVANCE.COM

CIVIL • STRUCTURAL

ENGINEER OF RECORD:



Nevada County Homekey +
Rattlesnake Residence
12875 Rattlesnake Rd.
Grass Valley, CA 95945

REVISION:

03.16.2026 Issued for Permit

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

05.01.2026 Plan Revision #1

PROJECT ENGINEER:

Ariene Castillo

(916) 790-3181 x217

ariene@ashleyvance.com

DATE: 2/24/26

SCALE: NTS

AV JOB: 251477

SHEET SIZE: 24"x36"

STRUCTURAL
JOB SET

S-3.1

RESIDENTIAL CALGREEN PLUMBING NOTES

- ENHANCED DURABILITY AND REDUCED MAINTENANCE:
4.406.1 ANNULAR SPACES AROUND PIPES, ELECTRIC CABLES, CONDUITS OR OTHER OPENINGS IN PLATES AT EXTERIOR WALLS SHALL BE PROTECTED AGAINST THE PASSAGE OF RODENTS BY CLOSING SUCH OPENINGS WITH CEMENT MORTAR, CONCRETE MASONRY OR SIMILAR METHOD ACCEPTABLE TO THE ENFORCING AGENCY.
- BUILDING MAINTENANCE AND OPERATION:
4.410.1 AN OPERATION AND MAINTENANCE MANUAL SHALL BE PROVIDED TO THE BUILDING OCCUPANT OR OWNER
- INDOOR WATER USE
A) PLUMBING FIXTURES (WATER CLOSETS AND URINALS) AND FITTINGS (FAUCETS AND SHOWERHEADS) INSTALLED IN RESIDENTIAL BUILDINGS SHALL COMPLY WITH THE PRESCRIPTIVE REQUIREMENTS OF SECTIONS 4.303.1.1 THROUGH 4.303.1.4.4
B) PLUMBING FIXTURES AND FITTINGS REQUIRED IN SECTION 4.303.1 SHALL BE INSTALLED IN ACCORDANCE WITH THE CALIFORNIA PLUMBING CODE, AND SHALL MEET THE APPLICABLE REFERENCED STANDARDS.

PIPING SCHEDULE

TYPE	SIZE	JOINING METHOD	NOTES
SANITARY WASTE BELOW GRADE	ALL	SOLVENT	ABS
SANITARY WASTE ABOVE GRADE	ALL	SOLVENT	ABS
SANITARY VENT	ALL	SOLVENT	ABS
CONDENSATE PIPING	ALL	SOLVENT	PVC/CPVC
CONDENSATE PIPING EXPOSED	ALL	SOLVENT	PVC/CPVC (PROTECTED WITH WATER-BASED LATEX PAINT)
DOMESTIC WATER	ALL	95/5 SOLDER	TYPE "L" OR "K" COPPER W/SEISMIC BRACING
SANITARY WASTE/VENT	BELOW GRADE	SERVICE WEIGHT CAST IRON	NO-HUB COUPLING
	ABOVE GRADE	SERVICE WEIGHT CAST IRON	NO-HUB COUPLING

PIPE INSULATION SCHEDULE

TYPE	DIAMETER SIZE (INCHES)	FLUID TEMP RANGE (°F)	INSULATION CONDUCTIVITY (BTU*INCH/HR*FT*°F)	INSULATION THICKNESS (INCHES)
DOMESTIC HOT WATER	<1	105-140	0.22-0.28	1
DOMESTIC HOT WATER	1 OR LARGER	105-140	0.22-0.28	1-1/2

VALUE OPTION: (E) TANK WATER HEATER SCHEDULE

SYMBOL	MANU.	MODEL	LOCATION	RECOVERY AT 90°F ΔT	ENERGY FACTOR	CAPACITY (GAL)	VOLTAGE	REMARKS
WH-1	RHEEM	PROE50 T2 RH95	INTERIOR	21.0	0.95	50	240-1φ-60Hz	4.5KW, VALUE OPTION: EXISTING WH TO REMAIN

STANDARD OPTION: (N) HEAT PUMP TANK WATER HEATER SCHEDULE

SYMBOL	MANU.	MODEL NO.	LOCATION	SERVES	CAPACITY (GAL)	FIRST HOUR RATING (GPH)	INPUT MBH (KW)	HP	ELECTRICAL VOLTAGE	AMPS	WEIGHT (LBS)	REMARKS
HPWH-1	RHEEM	XE80T10HS45U1	INTERIOR CLOSET	RESIDENCE	80	87	(4.5)	-	230-1φ-60Hz	-	244	INSTALL TMV-1 TO ENSURE 120°F SETPOINT, REPLACE (E) WH LIKE-FOR-LIKE

PLUMBING FIXTURE SCHEDULE - SEE FLOOR PLAN FOR APPLICABLE FIXTURES

TAG	FIXTURE	TYPE	MOUNTING	MANU.	MODEL NO.	WATER SUPPLY			DRAIN		PIPE SIZES				REMARKS
						MANU.	MODEL NO.	MAX GPM/GPF	TYPE	SIZE	WASTE	VENT	CW	HW	
BT-1	BATHTUB/SHOWER	-	FLOOR	-	COORDINATE MODEL SELECTION WITH OWNER	-	-	-	P-TRAP	1-1/2"	1-1/2"	1-1/4"	1/2"	1/2"	
CW-1	CLOTHES WASHER	-	FLOOR	-	COORDINATE MODEL SELECTION WITH OWNER	-	-	-	P-TRAP	2"	2"	1-1/2"	1/2"	1/2"	
DW-1	DISHWASHER	RESIDENTIAL	UNDER COUNTER	-	COORDINATE MODEL SELECTION WITH OWNER	-	-	-	INDIRECT	1-1/2"	2"	1-1/2"	-	1/2"	SHALL COMPLY WITH UL 749
HB-1	HOSE BIBB	-	WALL	WOODFORD	26	-	-	-	-	-	-	1/2"	-	-	BACKFLOW PROTECTED, ASSE STANDARD 1052
LAV-1	LAVATORY (1X FAUCET MOUNTING HOLES)	METERED	UNDER COUNTER	MOEN	WSL84733	1.2	-	-	P-TRAP	1-1/4"	1-1/2"	1-1/4"	1/2"	1/2"	OR EQUIVALENT, ADA COMPLIANT, BATTERY POWERED SENSOR ACTIVATED
	LAVATORY (3X FAUCET MOUNTING HOLES-CENTERSET)	METERED	UNDER COUNTER	MOEN	WS84633SRN	1.2	-	-	P-TRAP	1-1/4"	1-1/2"	1-1/4"	1/2"	1/2"	OR EQUIVALENT, ADA COMPLIANT, BATTERY POWERED SENSOR ACTIVATED, PROVIDE 4" CENTERSET HOLES
SH-1	SHOWER	-	-	DELTA ARVO	142840-SP-1	1.8	-	-	P-TRAP	2"	2"	1-1/2"	1/2"	1/2"	OR EQUIVALENT, ADA COMPLIANT
SK-1	SINK (1X FAUCET MOUNTING HOLES)	SINGLE COMPARTMENT	DROP-IN	MOEN	7423	2.0	-	-	P-TRAP	1-1/2"	2"	1-1/2"	1/2"	1/2"	OR EQUIVALENT, INSTALL 3/4 HP COMPACT GARBAGE DISPOSAL
	SINK (3X FAUCET MOUNTING HOLES-WIDESPREAD)	SINGLE COMPARTMENT	DROP-IN	MOEN	7425	2.0	-	-	P-TRAP	1-1/2"	2"	1-1/2"	1/2"	1/2"	OR EQUIVALENT, INSTALL 3/4 HP COMPACT GARBAGE DISPOSAL
SK-2	BAR SINK	METERED	UNDER COUNTER	MOEN	7423	2.0	-	-	P-TRAP	1-1/2"	2"	1-1/2"	1/2"	1/2"	OR EQUIVALENT
TMV-1	THERMOSTATIC MIXING VALVE	-	-	WATTS	LFMMV-M1	-	-	-	-	-	-	1/2"	1/2"	-	ASSE STANDARD 1017, 1069, AND 1070 LISTED, 0.5-12 GPM FLOW RATING
WC-1	WATER CLOSET	GRAVITY	FLOOR	AMERICAN STANDARD	3378AB.128	-	-	-	INTEGRAL P-TRAP	-	3"	2"	1/2"	-	OR EQUIVALENT, ADA COMPLIANT, ELONGATED OPEN FRONT SEAT

NOTES: COORDINATE ALL TRIM AND ACCESSORY OPTIONS WITH OWNER EQUIVALENT FIXTURES ACCEPTABLE CONTINGENT ON OWNER APPROVAL

WATER AND SEWER SERVICE CALCULATION

FIXTURE TYPE	NO.	SEWER		COLD WATER		HOT WATER		TOTAL WATER
		FU	TOTAL	FU	TOTAL	FU	TOTAL	FU
BATH TUB/SHOWER	1	2	2	4	4	3	3	4
CLOTHES WASHER	1	3	3	4	4	3	3	4
KITCHEN SINK (DOMESTIC)	1	2	2	1.5	1.5	1.125	1.125	1.5
LAVATORY	1	1	1	1	1	0.75	0.75	1
WATER CLOSET - GRAVITY	1	3	3	2.5	2.5	0	0	2.5
MISC EQUIP (ICE, SODA COFFEE)	1	1	1	0.5	0.5	0	0	0.5
EXISTING DEMAND	1	23	23	24.5	24.5	12.375	12.375	26
TOTAL FU			35.0		38.0		20.3	39.5

EQUIVALENT COLD WATER FLOWRATE (GPM):	24
PRESSURE AVAILABLE AT MAIN (PSI):	50
MINIMUM REQUIRED FIXTURE PRESSURE (PSI):	8
ELEVATION LOSS (PSI):	1.3
METER LOSS (PSI):	4.2
BACKFLOW PREVENTER LOSS (PSI):	10
EQUIVALENT PIPE LENGTH FROM METER TO MOST REMOTE FIXTURE (FT):	150
FRICITION LOSS PRESSURE AVAILABLE (PSI):	26.50
MAXIMUM ALLOWABLE FRICTION LOSS (PSI/100 FT):	14.13
MINIMUM REQUIRED "WATER" PIPE SIZE (INCHES):	1.25
MINIMUM REQUIRED "SEWER" PIPE SIZE (INCHES):	3

SIZE: TYPE L COPPER	CW MAX FLOW		CW FIXTURE UNIT		HW MAX FLOW		HW FIXTURE UNIT
NOMINAL DIAMETER (INCHES)	INTERNAL DIAMETER	GPM	FPS	FLUSH TANK	GPM	FPS	
0.5	0.545	4.0	5.6	4	3.6	5.0	4
0.75	0.785	10.6	7.0	15	7.5	5.0	10
1	1.025	20.6	8.0	32	12.9	5.0	18
1.25	1.265	31.3	8.0	56	19.6	5.0	30

(CALCULATIONS PER CPC APPENDIX A)

PLUMBING SHEET INDEX


- P0 PLUMBING SCHEDULES, CALCULATIONS, & GENERAL NOTES
- P1 PLUMBING PLAN - WATER
- P2 PLUMBING PLAN - SEWER & VENT
- P3 PLUMBING FIRE PENETRATION DETAILS

PLUMBING SCOPE OF WORK

- (E) WATER AND SEWER SERVICE TO SERVE (N) GARAGE CONVERSION
- INSTALLATION OF ALL COLD AND HOT WATER PIPING AND FITTINGS FOR NEW FIXTURES IN (N) GARAGE CONVERSION
- INSTALLATION OF ALL SEWER AND VENT PIPING AND FITTINGS FOR NEW FIXTURES IN (N) GARAGE CONVERSION
- (E) PLUMBING FIXTURES TO REMAIN IN (E) MAIN RESIDENCE
- (E) WATER HEATER TO REMAIN AND TO BE RELOCATED TO WH CLOSET
- INSTALLATION OF NEW PIPING AND FITTINGS FOR NEW CLOTHES WASHER IN (E) MAIN RESIDENCE
- REPLACE ALL PLUMBING FIXTURE FAUCETS AND WATER CLOSETS. (E) LAVATORY/SINK BOWLS TO REMAIN.

PLUMBING LEGEND

- CW- COLD WATER
- HW- HOT WATER
- NG- NATURAL GAS
- SS SANITARY SEWER
- SSV SANITARY SEWER VENT
- VTR VENT THRU ROOF
- AFF ABOVE FINISHED FLOOR
- BF BELOW FLOOR
- FA, TB FROM ABOVE, TO BELOW
- FB, TA FROM BELOW, TO ABOVE
- FU FIXTURE UNITS
- GPM GALLONS PER MINUTE
- TMV THERMOSTATIC MIXING VALVE
- POC - POINT OF CONNECTION
- GAS POC
- COLD WATER POC
- CONDENSATE POC
- CLEANOUT
- HOSE BIBB
- SHUT-OFF VALVE
- PUMP



DATE SIGNED 05-01-26


RATTLESLAKE RESIDENCE
12875 RATTLESLAKE ROAD
GRASS VALLEY, CA. 95945

ISSUED FOR	DATE
PERMIT	04-02-26
PLAN CHECK #1	05-01-26

PROJECT NUMBER 25341

SHEET TITLE
PLUMBING SCHEDULES, CALCULATIONS, & GENERAL NOTES

SHEET NO.
P0



A PLUMBING PLAN - SEWER & VENT
SCALE: 1/4"=1'-0"



SHEET NOTES:

1. (E) EXISTING
(N) NEW
(D) DEMO
2. ALL EQUIPMENT, FITTINGS, FIXTURES, AND PIPING ARE (E) TO REMAIN U.O.N.
3. ENSURE 1/4" PER 1 FT. SLOPE FOR SANITARY SEWER PIPING
4. ENSURE MINIMUM 1/8" PER FOOT SLOPE FOR ALL CONDENSATE PIPING AND INSTALL PER CPC 814. ALL CONDENSATE PIPING SHALL BE 3/4" U.O.N. OR LARGER IF RECOMMENDED BY THE MANUFACTURER
5. ENSURE CLEANOUT TO GRADE EXISTS
6. PROVIDE WALL CLEANOUTS AT ALL LAVATORIES AND HAND SINKS
7. NO UNDER-FLOOR CLEANOUT SHALL BE LOCATED MORE THAN 5 FEET FROM AN ACCESS DOOR, TRAP DOOR, OR CRAWL HOLE. CPC 707.9

KEY NOTES:

- ① PVC CONDENSATE TO DRAIN TO APPROVED RECEPTOR
- ② SECONDARY CONDENSATE FROM SECONDARY CONTAINMENT PAN, DRAIN TO VISIBLE LOCATION PER CMC 310.2(2)




DATE SIGNED: 05-01-26

RATTLESNAKE RESIDENCE
12875 RATTLESNAKE ROAD
GRASS VALLEY, CA. 95945

ISSUED FOR	DATE
PERMIT	04-02-26
PLAN CHECK #1	05-01-26

PROJECT NUMBER 25341
SHEET TITLE
PLUMBING PLAN - SEWER & VENT JOB SET
SHEET NO.
P2




System No. F-C-2030
F Ratings — 1 and 2 Hr (See Item 1)
T Ratings — 0, 3/4, 1, 1-1/2 and 2 Hr (See Item 3)

FC 2030

- Floor-Ceiling Assembly** — The 1 or 2 hr fire-rated solid or trussed lumber joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in the individual L500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The F Rating of the freestop system is equal to the rating of the floor-ceiling and wall assemblies. The general construction features of the floor-ceiling assembly are summarized below:
 - Flooring System** — Lumber or plywood subfloor with finish floor of lumber, plywood or Floor Topping Mixture* as specified in the individual Floor-Ceiling Design. Diam of opening shall be 1 in. (25 mm) larger than the nom diam of through-penetrant (Item 3).
 - Joists** — Nom 10 in. (254 mm) deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or Structural Wood Members* with bridging as required and with ends firestopped.
 - Gypsum Board*** — Thickness, type, number of layers and fasteners shall be as specified in the individual Floor-Ceiling Design. Diam of opening shall be 1 in. (25 mm) larger than the nom diam of through-penetrant (Item 3).
 - Furring Channels** — (Not Shown) (As required) — Resilient galvanized steel furring installed in accordance with the manner specified in the individual L500 Series Designs in the Fire Resistance Directory.

Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. May 23, 2008

Page: 1 of 2




ANSI/UL1479 (ASTM E814)	CANULC S115
F Rating — 1 and 2 Hr (See Item 1)	F Rating — 1 and 2 Hr (See Item 1)
T Rating — 1/4 Hr	FT Rating — 1/4 Hr
L Rating At Ambient — Less Than 1 CFM/sq ft	FH Rating — 1 and 2 Hr (See Item 1)
L Rating At 400 F — 4 CFM/sq ft	FTH Rating — 1/4 Hr
	L Rating At Ambient — Less Than 1 CFM/sq ft
	L Rating At 400 F — 4 CFM/sq ft

FC 1009

- Floor-Ceiling Assembly** — The 1 or 2 hr fire-rated solid or trussed lumber joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in the individual L500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The F Rating of the freestop system is equal to the rating of the floor-ceiling assembly. The general construction features of the floor-ceiling assembly are summarized below:
 - Flooring System** — Lumber or plywood subfloor with finish floor of lumber, plywood or Floor Topping Mixture* as specified in the individual Floor-Ceiling Design. Diam of opening to be max 1 in. (25 mm) larger than diam of pipe. As an alternate, the opening may be square-cut with a max dimension 1 in. (25 mm) greater than the diam of the pipe.
 - Wood Joists** — Nom 10 in. (254 mm) deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or Structural Wood Members* with bridging as required and with ends firestopped.
 - Furring Channels** — (Not Shown) (As required) — Resilient galvanized steel furring installed in accordance with the manner specified in the individual L500 Series Designs in the Fire Resistance Directory.
 - Gypsum Board*** — Thickness, type, number of layers and fasteners shall be as specified in the individual Floor-Ceiling Design. Diam of opening to be max 1 in. (25 mm) larger than diam of pipe.

Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. January 15, 2015

Page: 1 of 2




System No. F-C-2030
F Ratings — 1 and 2 Hr (See Item 1)
T Ratings — 0, 3/4, 1, 1-1/2 and 2 Hr (See Item 3)

FC 2030

- Chase Wall** — (Optional) - The through penetrant (Item 3) may be routed through a 1 or 2 hr fire-rated single, double or staggered wood stud/gypsum wallboard chase wall having a fire rating consistent with that of the floor-ceiling assembly. The chase wall shall be constructed of the materials and in the manner specified in the individual U300 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:
 - Studs** — Nom 2 by 4 in. (51 by 102 mm) or double nom 2 by 4 in. (51 by 102 mm) lumber studs.
 - Sole Plate** — Nom 2 by 6 in. (51 by 152 mm) (or larger) or parallel 2 by 4 in. (51 by 102 mm) lumber plates, tightly butted. Diam of opening shall be 1 in. (25 mm) larger than the nom diam of through-penetrant (Item 3).
 - Top Plate** — The double top plate shall consist of two nom 2 by 6 in. (51 by 152 mm) (or larger) or parallel 2 by 4 in. (51 by 102 mm) lumber plates, tightly butted. Diam of opening shall be 1 in. (25 mm) larger than the nom diam of through-penetrant (Item 3).
 - Gypsum Board*** — Thickness, type, number of layers and fasteners shall be as specified in individual Wall and Partition Design.
- Through-Penetrants** — One nom 1-1/2 in. (38 mm), 2 in. (51 mm), 3 in. (76 mm) or 4 in. (102 mm) diam nonmetallic pipe to be installed within the freestop system. Diam of opening through flooring system and through sole and top plates of chase wall to be max 2-1/8 in. (54 mm), 2-5/8 in. (67 mm), 4 in. (102 mm) or 5 in. (127 mm) for nom 1-1/2 in. (38 mm), 2 in. (51 mm), 3 in. (76 mm) or 4 in. (102 mm) diam nonmetallic pipe sizes, respectively. Pipe to be rigidly supported on both sides of the floor-ceiling assembly. The T Rating is dependent on the size of the through-penetrant. For 2 hr rated assemblies, the T Rating is 2 hr for 1-1/2 in. (38 mm) diam (and smaller) pipes and 1-1/2 hr for pipes greater than 1-1/2 in. (38 mm) diam. For 1 hr rated assemblies, the T Rating is 1 hr for 1-1/2 in. (38 mm) diam (and smaller) pipes, 3/4 hr for 2 in. (51 mm) diam pipes and 0 hr for pipes greater than 2 in. (51 mm) diam. The following types of nonmetallic pipes may be used:
 - Polyvinyl Chloride (PVC) Pipe — Schedule 40 solid-core or cellular core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.
 - Chlorinated Polyvinyl Chloride (CPVC) Pipe — SDR17 CPVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.
 - Acrylonitrile Butadiene Styrene (ABS) Pipe — Schedule 40 solid-core or cellular core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.
 - Flame Retardant Polypropylene (FRPP) Pipe — Schedule 40 FRPP pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.
- Freestop System** — The details of the freestop system shall be as follows:
 - Fill, Void or Cavity Material*** — Sealant — Min 3/4 in. (19 mm) thickness of fill material to be installed within the annular space between the pipe and the flooring (Item 1A) or sole plate. Min 5/8 in. (16 mm) thickness applied within the annular space, flush with the bottom surface of ceiling or lower top plate.
 HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant
 - Firestop Device*** — Firestop Collar — Firestop collar shall be installed in accordance with the accompanying installation instructions. Collar to be installed and latched around the pipe and secured to underside of ceiling or chase wall top plate (Item 2C) using the anchor hooks provided with the collar. (Minimum 2 anchor hooks for 1-1/2 (38 mm) and 2 in. (51 mm) diam pipes and 3 anchor hooks for 3 in. (76 mm) diam pipes). The anchor hooks are to be secured to the ceiling with min 3/16 in. (5 mm) diam steel toggle bolts or to the chase wall top plate with min No. 12 by min 1 in. (25 mm) long steel wood screws in conjunction with steel washers.
 HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 643 501/57N, CP643 63/2N, CP 643 903/3N or CP643 1104/4N Firestop Collar

Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. January 15, 2015

Page: 2 of 2




ANSI/UL1479 (ASTM E814)	CANULC S115
F Rating — 1 and 2 Hr (See Item 1)	F Rating — 1 and 2 Hr (See Item 1)
T Rating — 1/4 Hr	FT Rating — 1/4 Hr
L Rating At Ambient — Less Than 1 CFM/sq ft	FH Rating — 1 and 2 Hr (See Item 1)
L Rating At 400 F — 4 CFM/sq ft	FTH Rating — 1/4 Hr
	L Rating At Ambient — Less Than 1 CFM/sq ft
	L Rating At 400 F — 4 CFM/sq ft

FC 1009

- Chase Wall** — (Optional) - The through penetrant (Item 3) may be routed through a 1 or 2 hr fire-rated single, double or staggered wood stud/gypsum wallboard chase wall having a fire rating consistent with that of the floor-ceiling assembly. The chase wall shall be constructed of the materials and in the manner specified in the individual U300 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:
 - Studs** — Nom 2 by 4 in. (51 by 102 mm), 2 by 6 in. (51 by 152 mm) or double nom 2 by 4 in. (51 by 102 mm) lumber studs. Nom 2 by 4 in. (51 by 102 mm) studs are allowed for through-penetrants (Item 3) not exceeding nom 2 in. (51 mm) diam.
 - Sole Plate** — Nom 2 by 4 in. (51 by 102 mm), 2 by 6 in. (51 by 152 mm) or parallel 2 by 4 in. (51 by 102 mm) lumber plates, tightly butted. Diam of opening is to be max 1 in. (25 mm) larger than diam of pipe. As an alternate, the opening may be square-cut with a max dimension 1 in. (25 mm) greater than the diam of the pipe. Plates may be discontinuous over opening, terminating at two opposing edges of opening. Max length of discontinuity to be 1 in. (25 mm) greater than diam of through penetrant.
 - Top Plate** — The double top plate shall consist of two nom 2 by 4 in. (51 by 102 mm), 2 by 6 in. (51 by 152 mm) or two sets of parallel 2 by 4 in. (51 by 102 mm) lumber plates, tightly butted. Diam of opening is to be max 1 in. (25 mm) larger than diam of pipe. As an alternate, the opening may be square-cut with a max dimension 1 in. (25 mm) greater than the diam of the pipe. Plates may be discontinuous over opening, terminating at two opposing edges of opening. Max length of discontinuity to be 1 in. (25 mm) greater than diam of through penetrant.
 - Steel Plate** — When lumber plates are discontinuous, nom 1-1/2 in. (38 mm) wide, No. 20 gauge (or heavier) galv steel plates shall be installed to connect each discontinuous lumber plate and to provide a form for the fill material. Steel plates sized to lap 2 in. (51 mm) onto each discontinuous lumber plate and secured to lumber plates with steel screws or nails.
 - Gypsum Board*** — Thickness, type, number of layers and fasteners shall be as specified in individual Wall and Partition Design.
- Through Penetrants** — One metallic pipe, conduit or tubing to be installed within the freestop system. Pipe, conduit or tubing to be rigidly supported on both sides of floor assembly. The annular space within the freestop system shall be min 0 in. (point contact) to max 1 in. (25 mm). The following types and sizes of metallic pipes or conduits may be used:
 - Steel Pipe** — Nom 4 in. (102 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe.
 - Iron Pipe** — Nom 4 in. (102 mm) diam (or smaller) cast or ductile iron pipe.
 - Conduit** — Nom 4 in. (102 mm) diam (or smaller) steel electrical metallic tubing or steel conduit.
 - Copper Tubing** — Nom (102 mm) 4 in. diam (or smaller) Type L (or heavier) copper tubing.
 - Copper Pipe** — Nom (102 mm) 4 in. diam (or smaller) Regular (or heavier) copper pipe.
- Fill, Void or Cavity Material*** — Sealant — Min 3/4 in. (19 mm) thickness of fill material applied within the annulus, flush with the top surface of the floor or sole plate. Min 5/8 in. (16 mm) thickness of fill material applied within the annulus, flush with bottom surface of ceiling or lower top plate.
 HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP601S, CFS-S SIL CG, CP606, FS-ONE Sealant or FS-ONE MAX Intumescent Sealant (Note: L Ratings apply only when FS-ONE Sealant is used.)

Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. January 15, 2015

Page: 2 of 2




System No. W-L-2078
F Ratings — 1 and 2 Hr (See Item 1)
T Ratings — 0, 1 and 2 Hr (See Items 2 and 3)
L Rating At Ambient — 3 CFM/sq ft
L Rating At 400 F — Less Than 1 CFM/sq ft

FC 2078

- Wall Assembly** — The fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300, U400, U400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the construction features noted below:
 - Studs** — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide and spaced max 24 in. (610 mm) OC.
 - Gypsum Board*** — Nom 5/8 in. (16 mm) thick gypsum board, as specified in the individual Wall and Partition Design. Max diam of opening is 1-1/2 in. (38 mm).
- The hourly F Rating of the freestop system is equal to the hourly fire rating of the wall assembly in which it is installed.
- Through-Penetrants** — One nonmetallic pipe, conduit or tubing to be installed within the freestop system. The annular space between pipe and periphery of opening shall be min 0 in. (point contact) to max 1/2 in. (13 mm). Pipe or conduit to be rigidly supported on both sides of the wall assembly. The following types and sizes of nonmetallic pipes may be used:
 - Polyvinyl Chloride (PVC) Pipe — Nom 10 in. (254 mm) diam (or smaller) Schedule 40 solid-core or cellular core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.
 - Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 10 in. (254 mm) diam (or smaller) SDR13.5 CPVC pipe for use in closed (process or supply) piping systems.
 - Acrylonitrile Butadiene Styrene (ABS) Pipe — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 solid-core or cellular core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.
 - Flame Retardant Polypropylene (FRPP) Pipe — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 FRPP pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.
 - Polyethylene Fluoride (PVDF) Pipe — Nom 4 in. (102 mm) diam (or smaller) PVDF pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.
- When max in. diam pipe is used, T Rating is equal to the hourly fire rating of the wall. When nom 8 in. or 10 in. (203 or 254 mm) diam pipe is used, T Rating is 1 hr.
- Firestop Device*** — Firestop Collar — Firestop collar shall be installed in accordance with the accompanying installation instructions. Collar to be installed and latched around the pipe and secured to both sides of the wall using the anchor hooks provided with the collar. (Minimum two anchor hooks for 1-1/2 and 2 in. (38 and 51 mm) diam pipes, three anchor hooks for 3 and 4 in. (76 and 102 mm) diam pipes, four anchor hooks for 6 in. (152 mm) diam pipes, ten anchor hooks for 8 in. (203 mm) diam pipes and twelve anchor hooks for 10 in. (254 mm) diam pipes). The anchor hooks are to be secured to the surface of wall with 3/16 in. (4.8 mm) long steel toggle bolts along with washers. As an alternate for pipe sizes of 8 in. diam or less, min No. 10 by 1-1/2 in. (25.4 by 38 mm) long drywall or laminate screws with min 3/4 in. (19 mm) steel washers may be used. When the drywall or laminate screw is used, T Rating shall not exceed 1 hr.
 HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 643 501/57N, CP 643 63/2N, CP 643 903/3N, CP 643 1104/4N, CP 643 180/4N, CP 644 200/4N and CP 644 250/10 Firestop Collars
- Fill, Void or Cavity Material*** — Sealant — (Not Shown) — Min 1/2 in. (13 mm) thickness of sealant applied within the annular space for nom 8 in. and 10 in. (203 and 254 mm) diam pipes, flush with each side of wall. Sealant in annular space is optional for max 6 in. (152 mm) diam pipes. A min 1/4 in. (6 mm) thickness of sealant is required within the annular space, flush with each side of wall, to obtain the L Ratings for max 6 in. (152 mm) diam pipes.
 HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant or FS-ONE MAX Intumescent Sealant

Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. January 08, 2015



System No. W-L-5029
F Ratings — 1, 2 and 3 Hr (See Items 1, 3 and 4)
T Ratings — 0, 1/2, 1 and 1-1/4 Hr (See Item 3)
L Rating At Ambient — 4 CFM/sq ft
L Rating At 400 F — Less Than 1 CFM/sq ft

FC 5029

- Wall Assembly** — The 1, 2 or 3 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300, U400, U400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:
 - Studs** — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide for 1 and 2 hr and FH Rating and 3-1/2 in. (89 mm) wide for 3 hr F and FH rating and spaced max 24 in. (610 mm) OC.
 - Gypsum Board*** — Min 5/8 in. (16 mm) thick with square or tapered edges. The gypsum board type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual Wall and Partition Design. Max diam of opening is 18-5/8 in. (473 mm). The hourly F and FH Ratings of the freestop system are equal to the hourly fire rating of the wall assembly in which it is installed.
 - Through Penetrants** — One metallic pipe or tubing to be installed within the freestop system. Pipe or tubing to be rigidly supported on both sides of wall assembly. The following types and sizes of metallic pipes or tubing may be used:
 - Steel Pipe** — Nom 12 in. (305 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe.
 - Iron Pipe** — Nom 12 in. (305 mm) diam (or smaller) cast or ductile iron pipe.
 - Copper Tubing** — Nom 6 in. (152 mm) diam (or smaller) Type L (or heavier) copper tubing. When the hourly F or FH Rating of the freestop system is 3 hr, the nom diam of copper pipe shall not exceed 4 in. (102 mm).
 - Copper Pipe** — Nom 6 in. (152 mm) diam (or smaller) Regular (or heavier) copper pipe. When the hourly F or FH Rating of the freestop system is 3 hr, the nom diam of copper pipe shall not exceed 4 in. (102 mm).
 - Pipe Covering*** — Nom 1, 1-1/2 or 2 in. (25, 38 or 51 mm) thick hollow cylindrical heavy density (min 3.5 pcf or 56 kg/m³) glass fiber units jacketed on the outside with an all service jacket. Longitudinal joints sealed with metal fasteners or factory-applied self-sealing tape. Transverse joints secured with metal fasteners or with tape supplied with the product. For 1 and 2 hr F and FH Ratings, the annular space between insulated penetrant and periphery of opening shall be min 0 in. (point contact) to max 1-1/8 in. (48 mm). For 3 hr F and FH Ratings, the annular space shall be min 0 in. (point contact) to max 1-1/4 in. (32 mm).
 - See Pipe and Equipment Covering** — Materials (BRG) category in the Building Materials Directory for the names of manufacturers. Any pipe covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a Smoke Developed Index of 50 or less may be used.
- The hourly T, FT, FTH Ratings of the freestop system are 1/2 hr for 1 hr rated walls and 1 hr for 2 hr rated walls. For 3 hr rated walls, the hourly T, FT and FTH Ratings when steel and iron pipes are used are 1 hr. For 3 hr rated walls, the hourly T, FT and FTH Ratings when copper penetrants are used are 1-1/4 hr for 2 in. (51 mm) thick pipe covering and 0 hr for pipe covering thickness less than 2 in. (51 mm).
- Pipe Covering*** — (Not Shown) — As an alternate to Item 3, max 2 in. (51 mm) thick cylindrical calcium silicate (min 14 pcf) units sized to the outside diam of the pipe or tube may be used. Pipe insulation secured with stainless steel bands or min 15 AWG stainless steel wire spaced max 12 in. (305 mm) OC. When the alternate pipe covering is used, the T and FT Rating shall be as specified in Item 3 above.
- See Pipe and Equipment Covering** — Materials (BRG) category in the Building Materials Directory for names of manufacturers. Any pipe covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a Smoke Developed Index of 50 or less may be used.
- Fill, Void or Cavity Material*** — Sealant — For 1 and 2 hr F and FH Rating, min 5/8 in. (16 mm) thickness of fill material applied within the annulus, flush with both surfaces of wall. For 3 hr F and FH Rating, min 1 in. (25 mm) thickness of fill material applied within the annulus, flush with both surfaces of wall. At the point contact location between pipe covering and gypsum board, a min 1/2 in. (13 mm) diam bead of fill material shall be applied at the pipe covering/gypsum board interface on both surfaces of wall.
 HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant or FS-ONE MAX Intumescent Sealant

Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. March 19, 2015

OPTIMIZED ENERGY & FACILITIES CONSULTING, INC.
 5734 Lonepine Boulevard, Rocklin, CA 95765
 Office: (916) 626-5518 www.oefcinc.com

REGISTERED PROFESSIONAL ENGINEER
 No. M36994
 EXP. 09-30-2026
 M. B. BAYLOR
 STATE OF CALIFORNIA
 DATE SIGNED: 05-01-26

RATTLESNAKE RESIDENCE
 12875 RATTLESNAKE ROAD
 GRASS VALLEY, CA. 95945

ISSUED FOR	DATE
PERMIT	04-02-26
PLAN CHECK #1	05-01-26

PROJECT NUMBER 25341

SHEET TITLE

PLUMBING FIRE PENETRATION DETAILS
JOB SET

SHEET NO.

P3

GENERAL NOTES

- CONTRACTOR TO EXAMINE THE PROPOSED WORK SITE AND BECOME FAMILIAR WITH ALL JOB CONDITIONS AFFECTING THE WORK SHOWN. CONTRACTOR(S) SHALL FIELD-VERIFY SITE CONDITIONS INCLUDING LOCATIONS AND SIZES OF EXISTING PIPING, VALVES, CLEANOUTS, WASTE MAINS, GAS METERS, ETC., AND BIDS SHALL BE BASED ON ACTUAL FIELD CONDITIONS. NO ADDITIONAL ALLOWANCE WILL BE GRANTED DUE TO LACK OF KNOWLEDGE OF SITE CONDITIONS. ACCEPT SOLE AND COMPLETE RESPONSIBILITY FOR CONDITIONS OF THE JOBSITE, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK.
- DRAWINGS INDICATE DIAGRAMMATICALLY THE ARRANGEMENT OF PRINCIPAL APPARATUS, PIPING, DUCTWORK, AND OTHER MATERIAL. FOLLOW DRAWING AS CLOSELY AS POSSIBLE IN ORDER TO ACHIEVE A NEAT INSTALLATION WHILE STILL WORKING AROUND ANY OBSTRUCTIONS. INSPECT SITE CONDITIONS AFFECTING THE WORK AND PROVIDE FITTINGS AND ACCESSORIES AS REQUIRED TO MEET CONDITIONS WHETHER SHOWN OR NOT.
- IT IS NOT THE INTENTION OF THE PLANS AND SPECIFICATIONS TO COVER ALL INCIDENTALS REQUIRED TO PROVIDE COMPLETE AND FULLY-OPERATIONAL SYSTEMS. THE CONTRACTOR IS TO FURNISH ALL LABOR, MATERIALS, TRANSPORTATION, EQUIPMENT, MISCELLANEOUS SERVICES, ETC., REQUIRED TO ACCOMPLISH THIS RESULT. ANYTHING WHICH MAY BE REASONABLY CONSTRUED AS A NECESSARY PART OF THE INSTALLATION SHALL BE INCLUDED, WHETHER SPECIFICALLY SHOWN OR MENTIONED OR NOT. ENGINEER WILL PROVIDE INTERPRETATIONS UPON REQUEST.
- ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN COMPLIANCE WITH THE FOLLOWING CODES AS AMENDED AND ADOPTED BY THE AUTHORITY(ES) HAVING JURISDICTION: 2025 CALIFORNIA BUILDING CODE, 2025 CALIFORNIA MECHANICAL CODE, 2025 CALIFORNIA PLUMBING CODE, 2025 CALIFORNIA ELECTRICAL CODE, 2025 CALIFORNIA ENERGY CODE (TITLE 24), NATIONAL FIRE PROTECTION ASSOCIATION (NFPA), OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA), AND ANY OTHER LOCAL CODES, ORDINANCES, REGULATIONS, OR AUTHORITIES HAVING JURISDICTION. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES OR OTHER CODES AND REGULATIONS APPLICABLE TO THIS PROJECT. THESE CODES SHALL DETERMINE MINIMUM REQUIREMENTS FOR MATERIALS, METHODS, AND LABOR PRACTICES NOT OTHERWISE DEFINED IN THESE SPECIFICATIONS.
- DEFINITIONS:
 - WORK: LABOR AND MATERIALS OF THE CONTRACTOR AND/OR SUBCONTRACTOR.
 - FURNISH: OBTAIN, COORDINATE, SUBMIT THE NECESSARY DRAWINGS, DELIVER TO THE JOBSITE IN NEW CONDITION AND GUARANTEE.
 - PROVIDE: FURNISH AND INSTALL.
 - CONNECT: BRING SERVICE TO THE EQUIPMENT AND MAKE FINAL ATTACHMENTS INCLUDING NECESSARY PIPE FITTINGS, DUCTWORK, TRANSITIONS, ETC.
 - CONCEALED: HIDDEN FROM SIGHT IN CHASES, FURRED SPACES, SHAFTS, ABOVE CEILING, EMBEDDED IN CONSTRUCTION, IN CRAWL SPACES, OR BURIED.
 - EXPOSED: NOT INSTALLED UNDERGROUND OR CONCEALED AS DEFINED ABOVE.
 - PERFORMANCE: CONTRACTOR SHALL PERFORM ALL WORK SPECIFIED, INDICATED, AND REQUIRED UNLESS OTHERWISE NOTED, INCLUDING FINAL CONNECTIONS, IN A WORKMANLIKE MANNER USING WORKERS SKILLED AND EXPERIENCED IN THE TRADE. PIPES, FIXTURES, EQUIPMENT, GRILLES, REGISTERS, ETC. TO BE INSTALLED LEVEL, SQUARE, OR CENTERED, ETC. TO GIVE A NEAT APPEARANCE.
 - FULL FUNCTION: PROVIDE ALL MINOR ITEMS NECESSARY FOR A COMPLETE AND FULLY FUNCTIONAL INSTALLATION.
- CONTRACTOR SHALL CONFIRM ALL SITE VOLTAGES BEFORE BIDDING AND ORDERING EQUIPMENT. REIMBURSE ELECTRICAL CONTRACTOR, AT NO CHARGE TO CLIENT, FOR ELECTRICAL CONTRACTOR'S COST INCURRED DUE TO SUBSTITUTION OF MECHANICAL EQUIPMENT HAVING ELECTRICAL REQUIREMENTS DIFFERING FROM SITE CONDITIONS.
- CONTRACTOR SHALL PROVIDE THE OWNER WITH COPIES OF OPERATION, MAINTENANCE, AND PREVENTATIVE MAINTENANCE MANUALS FOR EACH MODEL AND TYPE OF PLUMBING AND MECHANICAL EQUIPMENT.
- CONTRACTOR SHALL PROVIDE EVIDENCE OF LICENSING, BONDING, AND INSURANCE, AND PROVIDE OTHER NECESSARY ADMINISTRATIVE FUNCTIONS FOR CONTRACTOR'S WORK.
- CONTRACTOR SHALL PROCURE AND PAY FOR ALL REQUIRED PERMITS AND SERVICE CHARGES.
- COORDINATION: CONFORM TO GENERAL CONSTRUCTION CONTRACT DOCUMENTS EXCEPT AS MODIFIED HEREIN. REFER ALSO TO STRUCTURAL AND ELECTRICAL CONTRACT DOCUMENTS. COORDINATE ALL WORK WITH OTHER TRADES.
- CUTTING AND PATCHING: CUT AND PATCH AS REQUIRED. CUT OR WELD STRUCTURAL MEMBERS ONLY WITH APPROVAL OF A STRUCTURAL ENGINEER. PATCHING SUBJECT TO ACCEPTANCE BY OWNER.
- SAW CUT TRENCHES IN SLAB SHALL BE FULLY RESTORED AND REINFORCED TO PREVENT SAGGING. ROUGHEN SAW CUT EDGES PRIOR TO RE-POURING CONCRETE.
- COORDINATE ALL WORK WITH OTHER TRADES TO PROVIDE A COMPLETE INSTALLATION. CONNECT ALL EQUIPMENT FURNISHED BY OTHERS AS REQUIRED. INSTALL ALL WORK TO CLEAR ARCHITECTURAL AND STRUCTURAL MEMBERS. INSTALL ALL ABOVE GRADE (OVERHEAD) PIPING AS HIGH AS PRACTICAL.
- RESTORE ALL DAMAGE RESULTING FROM YOUR WORK AND LEAVE PREMISES IN CLEAN CONDITION WHEN FINISHED WITH WORK. ADJUST, CLEAN, REPAIR, OR REPLACE PRODUCTS, WHICH HAVE BEEN DAMAGED.
- GUARANTEE ALL WORK AND MATERIALS FOR ONE YEAR MINIMUM FROM DATE OF FILING NOTICE OF COMPLETION.
- PROVIDE FLASHING AND COUNTER FLASHING FOR ALL WALL AND ROOF PENETRATIONS.
- ADJUSTMENTS: MAKE MINOR ADJUSTMENTS TO WORK WHERE REQUESTED BY OWNER, WHEN SUCH ADJUSTMENTS ARE NECESSARY TO PROPER OPERATION AND WITHIN THE INTENT OF THE CONTRACT.
- MATERIALS AND EQUIPMENT: PROVIDE NEW, UL-LISTED, COMMERCIAL-GRADE MATERIALS, DEVICES, EQUIPMENT, AND FIXTURES SUITABLE FOR THE ENVIRONMENT WHERE INSTALLED. REUSE EXISTING ONLY WHEN COMPLIANT WITH THE CONTRACT DOCUMENTS, IN GOOD CONDITION, AND APPROVED BY THE ENGINEER.
- INSTALLATION: INSTALL ALL MATERIALS, EQUIPMENT, AND SYSTEMS IN FULL ACCORD WITH MANUFACTURER'S INSTRUCTIONS.
- LAYOUT: INSTALL ALL PIPING AND DUCTWORK TO PRESENT A NEAT AND ORDERLY APPEARANCE. RUN ALL LINES PARALLEL WITH BUILDING CONSTRUCTION AS MUCH AS POSSIBLE. MAINTAIN HEADROOM, EQUIPMENT CLEARANCE, AND GRADIENT WHERE REQUIRED. ALLOW FOR EXPANSION & CONTRACTION.
- ACCESS DOORS: PROVIDE ACCESS DOORS OR PANELS FOR ALL VALVES, CLEANOUTS, DAMPERS, CONTROLS, DEVICES, AND OTHER ITEMS REQUIRING INSPECTION OR MAINTENANCE.
- START-UP: THOROUGHLY TEST AND DEMONSTRATE PROPER OPERATION OF ALL SYSTEMS AND EQUIPMENT MODIFIED, FURNISHED OR INSTALLED UNDER THIS CONTRACT.
- WARRANTY: ALL MATERIALS AND EQUIPMENT INSTALLED UNDER THIS CONTRACT SHALL BE GUARANTEED FREE FROM ALL MECHANICAL, ELECTRICAL, AND WORKMANSHIP DEFECTS FOR A MINIMUM OF ONE YEAR FROM DATE OF FINAL ACCEPTANCE. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGES TO THE PREMISES CAUSED BY LEAKS AND/OR BREAKS IN PIPES AND FIXTURES INSTALLED UNDER THIS CONTRACT, AS WELL AS ANY DAMAGE FROM LEAKS VIA ROOF PENETRATIONS MADE AND SEALED UNDER CONTRACTOR'S SCOPE.
- PATCHING & PAINTING: RESTORE ANY DAMAGE RESULTING FROM THE WORK AND LEAVE PREMISES CLEAN, ADJUST, CLEAN, REPAIR, AND/OR REPLACE ANY ITEMS DAMAGED BY THE WORK. RESTORE WALL AND ROOF PENETRATIONS TO MATCH SURROUNDING WALL OR ROOF, RESPECTIVELY.
- AIR BALANCE: PROVIDE SERVICES NECESSARY TO VERIFY AIR QUANTITIES AND BALANCE FOR ESTABLISHED QUANTITIES AND UNIFORM TEMPERATURE IN THE SPACES SERVED. ADJUST ALL DAMPERS AND ELEMENTS IN GRILLES AND DIFFUSERS FOR PROPER AIR DISTRIBUTION AND TO MINIMIZE DRAFTS. COMPLY WITH SMACNA MANUAL FOR THE BALANCING AND ADJUSTMENT OF AIR DISTRIBUTION SYSTEMS.
- DUCTWORK SHALL BE FABRICATED AND INSTALLED IN ACCORDANCE WITH THE LATEST EDITION OF THE SMACNA LOW PRESSURE DUCT CONSTRUCTION STANDARD.
- ALL BRANCH DUCTS SHALL HAVE BALANCING DAMPERS WITH ACCESSIBLE LOCKING TYPE QUADRANT.
- HVAC EQUIPMENT SHALL BE CERTIFIED BY THE MANUFACTURER FOR COMPLIANCE WITH CALIFORNIA ENERGY COMMISSION STANDARDS.
- DUCT SHALL MEET UL 181, CLASS I AND NFPA 90A AND 90B. DUCT SHALL BE INSTALLED STRAIGHT AND SUPPORT SPACING SHALL BE IN STRICT ACCORDANCE WITH "SMACNA HVAC DUCT CONSTRUCTION STANDARDS, METAL AND FLEXIBLE". FLEXIBLE DUCTWORK SHALL BE EXTENDED TO THE FULLEST POSSIBLE LENGTH, IN ORDER TO MINIMIZE PRESSURE DROP IN THE DUCT. EXCESS DUCT LENGTHS SHALL BE SHORTENED TO PREVENT UNNECESSARY CHANGES IN DIRECTIONS. WHERE ABRUPT CHANGES IN DIRECTION ARE UNAVOIDABLE USE ADJUSTABLE SHORT RADIUS SHEET METAL ELBOWS TO MAKE DIRECTION CHANGES. CONNECTIONS AT METAL DUCTS OR COLLARS SHALL BE MADE BY DRAW BANDS AND PRESSURE-SENSITIVE TAPE WITH THE DRAW BANDS TIGHTENED AS RECOMMENDED BY THE MANUFACTURER WITH AN ADJUSTABLE TENSIONING TOOL. USING PRESSURE-SENSITIVE TAPE ALONE WITHOUT DRAW BANDS IS NOT ACCEPTABLE. ALL PRESSURE-SENSITIVE TAPES AND MASTICS USED SHALL COMPLY WITH UL 181.
- HVAC EQUIPMENT SHALL NOT BE OPERATED DURING CONSTRUCTION WITHOUT A FILTER INSTALLED TO PROTECT THE EVAPORATOR COIL. AFTER ALL CONSTRUCTION IS COMPLETED, ALL CONSTRUCTION FILTERS SHALL BE REMOVED AND NEW FILTERS SHALL BE INSTALLED.

RESIDENTIAL CALGREEN MECHANICAL NOTES

- ENHANCED DURABILITY AND REDUCED MAINTENANCE:
 - 4.406.1 ANNULAR SPACES AROUND PIPES, ELECTRIC CABLES, CONDUITS OR OTHER OPENINGS IN PLATES AT EXTERIOR WALLS SHALL BE PROTECTED AGAINST THE PASSAGE OF RODENTS BY CLOSING SUCH OPENINGS WITH CEMENT MORTAR, CONCRETE MASONRY OR SIMILAR METHOD ACCEPTABLE TO THE ENFORCING AGENCY.
- BUILDING MAINTENANCE AND OPERATION:
 - 4.410.1 AN OPERATION AND MAINTENANCE MANUAL SHALL BE PROVIDED TO THE BUILDING OCCUPANT OR OWNER.
- ENVIRONMENTAL QUALITY:
 - 4.503.1 ANY INSTALLED GAS FIREPLACE SHALL BE A DIRECT-VENT SEALED-COMBUSTION TYPE. ANY INSTALLED WOODSTOVE OR PELLET STOVE SHALL COMPLY WITH U.S. EPA NEW SOURCE PERFORMANCE STANDARDS (NSPS) EMISSION LIMITS AS APPLICABLE, AND SHALL HAVE A PERMANENT LABEL INDICATING THEY ARE CERTIFIED TO MEET THE EMISSION LIMITS. WOODSTOVES, PELLET STOVES, AND FIREPLACES SHALL ALSO COMPLY WITH APPLICABLE LOCAL ORDINANCES.
 - 4.504.1 DUCT OPENINGS AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS SHALL BE COVERED DURING CONSTRUCTION.
 - 4.504.2.1 ADHESIVES, SEALANTS AND CAULKS SHALL BE COMPLIANT WITH VOC AND OTHER TOXIC COMPOUND LIMITS.
- INSTALLER AND SPECIAL INSPECTOR QUALIFICATIONS:
 - 702.1 HVAC SYSTEM INSTALLERS ARE TRAINED AND CERTIFIED IN THE PROPER INSTALLATION OF HVAC SYSTEMS.
 - 702.2 SPECIAL INSPECTORS EMPLOYED BY THE ENFORCING AGENCY MUST BE QUALIFIED AND ABLE TO DEMONSTRATE COMPETENCE IN THE DISCIPLINE THEY ARE INSPECTING.
 - VERIFICATION OF COMPLIANCE WITH THIS CODE MAY INCLUDE CONSTRUCTION DOCUMENTS, PLANS, SPECIFICATIONS BUILDER OR INSTALLER CERTIFICATION, INSPECTION REPORTS, OR OTHER METHODS ACCEPTABLE TO THE ENFORCING AGENCY WHICH SHOW SUBSTANTIAL CONFORMANCE.

MECHANICAL SHEET INDEX

M0	MECHANICAL SCHEDULES & GENERAL NOTES
M1	MECHANICAL PLAN – FLOOR
M2	MECHANICAL FIRE PENETRATION DETAILS
ENO	TITLE 24 ENERGY
EN1	TITLE 24 ENERGY

MECHANICAL SCOPE OF WORK

- (E) PACKAGED HVAC UNIT TO BE REPLACED LIKE FOR LIKE
 - INSTALLATION OF (N) DUCTWORK AND GRILLES FOR (N) GARAGE CONVERSION. CONNECT (N) DUCTWORK TO (E) HVAC DUCTWORK MAINS IN ATTIC. INSTALL WITH (N) COMBO FIRE/SMOKE DAMPERS FOR 1-HOUR RATED GARAGE WALL.
 - INSTALLATION OF NEW KITCHEN EXHAUST SYSTEM AND ALL ASSOCIATED DUCTWORK, DAMPERS, AND GRILLES FOR (N) GARAGE CONVERSION.
 - INSTALLATION OF NEW BATHROOM EXHAUST SYSTEM AND ALL ASSOCIATED DUCTWORK, DAMPERS, AND GRILLES FOR (N) GARAGE CONVERSION.
 - (E) EXHAUST SYSTEM AND ALL ASSOCIATED DUCTWORK, DAMPERS, AND GRILLES TO REMAIN IN (E) MAIN RESIDENCE.
 - INSTALLATION OF NEW CLOTHES DRYER SYSTEM AND ALL ASSOCIATED DUCTWORK, DAMPERS, AND GRILLES IN (E) MAIN RESIDENCE.
- INSTALLATION OF NEW DUCTED MINI-SPLIT AND ALL ASSOCIATED DUCTWORK, DAMPERS, AND GRILLES FOR (N) GARAGE CONVERSION.

MECHANICAL LEGEND

	AC-1 THERMOSTAT
	CONDENSATE POC
	ELECTRICAL POC
	GAS POC
	WATER POC
	CEILING DIFFUSER (HARDID)
	CEILING RETURN (HARDID)
	SIDEWALL SUPPLY/RETURN
	POC - POINT OF CONNECTION
	TRANSITION
	DAMPER
	FIRE-SMOKE DAMPER
	50 CFM (4\"/>
	100 CFM (6\"/>
	DIAMETER
	CFM CUBIC FEET PER MINUTE
	FROM ABOVE, TO BELOW
	FROM BELOW, TO ABOVE
	RETURN AIR
	SUPPLY AIR
	FIRE SMOKE DAMPER



DATE SIGNED 05-01-26

(E) PACKAGED GAS/ELECTRIC SCHEDULE

TAG	MANU	MODEL	LOCATION	SERVES	TONS	REF	SUPPLY FAN			COOLING			HEATING			CONDENSER			COMPRESSOR			CMB FAN			ELECTRICAL			SEER (EER)	AFUE	WEIGHT (LBS)	REMARKS
							CFM	ESP	FLA	TOTAL MBH	SENSIBLE MBH	EDB	EWB	AMB	INPUT MBH	OUTPUT MBH	QTY	FLA (EA)	QTY	RLA (EA)	FLA	V-φ-Hz	MCA	MOCP	FLA	V-φ-Hz	MCA				
AC-1	LENNOX	GCS16R-651-125-2P	OUTSIDE	HOUSE	5.0	R-22	2000	0.8"	4.6	60.0	48.0	80°F	67°F	105°F	125.0	100.0	1	2.0	1	27.6	0.6	230-1-60	42.0	60.0	10.0 (8.9)	78.3%	560.0	TO BE REPLACED			

(N) PACKAGED GAS/ELECTRIC SCHEDULE

TAG	MANU	MODEL	LOCATION	SERVES	TONS	REF	SUPPLY FAN			COOLING			HEATING			CONDENSER			COMPRESSOR			CMB FAN			ELECTRICAL			SEER2 (EER2)	AFUE	WEIGHT (LBS)	REMARKS
							CFM	ESP	FLA	TOTAL MBH	SENSIBLE MBH	EDB	EWB	AMB	INPUT MBH	OUTPUT MBH	QTY	FLA (EA)	QTY	RLA (EA)	FLA	V-φ-Hz	MCA	MOCP	FLA	V-φ-Hz	MCA				
AC-1	LENNOX	LRP13GEK60-126-EP-1-A	OUTSIDE	HOUSE	5.0	R-454B	2000	0.8"	4.2	60.0	48.0	80°F	67°F	105°F	126.0	102.1	1	1.7	1	24.3	-	230-1-60	36.3	60.0	13.4 (10.6)	81.0%	557.0	OR APPROVED EQUIVALENT, INSTALL UNIT WITH HORIZONTAL DISCHARGE CONFIGURATION TO MATCH EXISTING DUCTWORK. PROVIDE UNIT WITH R-454B REFRIGERANT (SAFETY GROUP A2L, HIGH PROBABILITY SYSTEM) AND FACTORY INTEGRAL REFRIGERANT LEAK DETECTION SENSOR & CONTROLS			

MINI-SPLIT HEAT PUMP SCHEDULE

OUTDOOR UNIT														INDOOR UNIT														SEER2 (EER2)	HSPF2	REMARKS		
TAG	MANU	MODEL	LOCATION	TONS	REF	COOLING			HEATING			ELECTRICAL					WEIGHT (LBS)	TAG	TYPE	MANU	MODEL	LOCATION	SERVES	TONS	CFM	ESP	FAN FLA				WEIGHT (LBS)	
						TOTAL MBH	SENSIBLE MBH	EDB	EWB	AMB	MBH @47°F	MBH @17°F	V-φ-Hz	COND FLA	COMP RLA	MCA												MOCP				
HP-1	DAIKIN	PUZ-A18NKA7	OUTSIDE	1.5	R-454B	18.0	13.9	80°F	67°F	95°F	19.0	11.0	230-1-60	0.5	7	11.0	28	100	FC-1	DUCTED	DAIKIN	FEAD-A18AA8	ATTIC	ADU	1.5	600	0.6"	1.95	60	18.7 (10.3)	8.6	OR APPROVED EQUIVALENT, PROVIDE UNIT WITH R-454B REFRIGERANT (SAFETY GROUP A2L, HIGH PROBABILITY SYSTEM) AND FACTORY INTEGRAL REFRIGERANT LEAK DETECTION SENSOR & CONTROLS

FIRE/SMOKE DAMPER SCHEDULE


TAG	TYPE	MANU.	MODEL	REMARKS
FSD-1	FIRE/SMOKE DAMPER	POTTORFF	FSD-151-0P	OUT-OF-PARTITION COMBINATION FIRE SMOKE DAMPER, 1.5 HOUR RATING, UL LISTED, WITH 120V/1A MOTOR ACTUATOR, INNOVARFLEX MODEL D4120 SMOKE DETECTOR WITH 120 VOLT 1 PHASE ACTUATOR, TEST SWITCH, AND REMOTE CONTROL SWITCH. SMOKE DETECTOR FURNISHED BY THE DAMPER MANUFACTURER, INSTALLED BY MECHANICAL CONTRACTOR 1, 2, 3
<ol style="list-style-type: none"> ACCESS TO FIRE/SMOKE DAMPERS AND FIRE DAMPERS ARE REQUIRED FOR INSPECTION AND MAINTENANCE. PROVIDE A MINIMUM SIZE 12"x12" OR LARGER ENOUGH TO PERFORM INSPECTION AND MAINTENANCE. ACCESS TO FIRE/SMOKE DAMPERS AND FIRE DAMPERS SHALL BE LABELED AT ALL ACCESS POINTS. ANY DUCT DETECTORS UTILIZED FOR OPERATION OF THE FIRE/SMOKE DAMPERS MUST BE MONITORED BY THE FIRE ALARM PANEL FOR INTEGRITY. 				

RATTLESNAKE RESIDENCE
 12875 RATTLESNAKE ROAD
 GRASS VALLEY, CA. 95945

ISSUED FOR	DATE
PERMIT	04-02-26
PLAN CHECK #1	05-01-26
PROJECT NUMBER	25341

SHEET TITLE
MECHANICAL GENERAL NOTES, SCHEDULES, & DETAILS
JOB SET

SHEET NO.
M0



A MECHANICAL PLAN
SCALE: 1/4"=1'-0"




SHEET NOTES:

- (E) EXISTING
(N) NEW
(D) DEMO
- ALL EQUIPMENT/CONTROLS AND DUCTWORK/FITTINGS SHOWN ARE (E) TO REMAIN U.O.N.
- HVAC EQUIPMENT SHALL BE PERMANENTLY IDENTIFIED AS TO THE AREA OR SPACE SERVED BY THE EQUIPMENT PER CMC 303.6
- CONTRACTOR SHALL VERIFY ALL A2L REFRIGERANT-CONTAINING SYSTEMS MEET THE REQUIREMENTS OF ASHRAE 15, INCLUDING ALL REFRIGERANT LEAK DETECTION SENSORS, SAFETY SHUT-OFF VALVES, AND VENTILATION, AS REQUIRED
- PROVIDE NAMEPLATE FOR EACH SELF-CONTAINED REFRIGERATION SYSTEM PER CMC 1115.5, WHICH INCLUDES A SYMBOL INDICATING THAT A FLAMMABLE REFRIGERANT IS BEING USED PER CMC 1104.6.2.1. PROVIDE LABEL ADJACENT TO SERVICE PORTS AND OTHER LOCATIONS WHERE SERVICE INVOLVING COMPONENTS CONTAINING REFRIGERANT IS PERFORMED PER CMC 1104.6.2.2
- THERMOSTATS TO BE INSTALLED AT 48" A.F.F. (TOP OF THERMOSTAT). DO NOT INSTALL THERMOSTATS OVER CASEWORK OR SHELVING OVER 24" IN DEPTH AND 34" IN HEIGHT. COORDINATE EXACT LOCATION WITH OWNER.
- ALL DUCTWORK PENETRATIONS TO THE EXTERIOR OF BUILDING SHALL BE CORROSION-RESISTANT AND PROTECTED FROM INTRUSION BY WATER, INSECTS, ETC.
- PROVIDE FIRE STOPPING ASSEMBLY PROTECTION FOR DUCT PENETRATIONS OF RATED ASSEMBLIES. FIRE STOP RATING SHALL MATCH RATED ASSEMBLY BEING PENETRATED
- EQUIPMENT IN ATTICS AND UNDER-FLOOR SPACES SHALL BE PROVIDED WITH AN ACCESS OPENING LARGE ENOUGH TO REMOVE THE LARGEST PIECE OF EQUIPMENT BUT NO LESS THAN 22"x30" PER CMC 304.4
- PROVIDE FIRE STOPPING ASSEMBLY PROTECTION FOR DUCT PENETRATIONS OF RATED ASSEMBLIES. FIRE STOP RATING SHALL MATCH RATED ASSEMBLY BEING PENETRATED
- ALL NEW CONCEALED DUCTWORK TO BE INSULATED WITH MINIMUM R-8, AND PERMITTED TO BE FLEX DUCT
- COORDINATE FINAL GRILLE LOCATIONS WITH OWNER
- ENSURE MIN. 3" CLEARANCE FROM EXHAUST OUTLETS TO OPERABLE WINDOW PER CMC 407.2.2
- SUPPLY REGISTERS WILL BE SIZED IN THE FOLLOWING MANNER:

<65 CFM	=	8x4
65-130 CFM	=	10x6
130-200 CFM	=	12x8
200-250 CFM	=	14x8
- ALL CLOTHES DRYER MOISTURE EXHAUST DUCTS SHALL COMPLY WITH CMC 504.3. DUCTS SHALL TERMINATE ON THE OUTSIDE OF THE BUILDING, NOT LESS THAN 3 FEET FROM OPENINGS INTO THE BUILDING.
 -DUCTS SHALL BE EQUIPPED WITH A BACKDRAFT DAMPER
 -SCREENS SHALL NOT BE INSTALLED AT THE DUCT TERMINATION
 -DUCTS SHALL NOT BE CONNECTED OR INSTALLED WITH SHEET METAL SCREWS OR OTHER FASTENERS THAT WILL OBSTRUCT THE FLOW
 -DUCTS SHALL BE OF METAL AND HAVE SMOOTH INTERIOR SURFACE
 -VERIFY WITH OWNER IF ACCESSIBLE LINT TRAP IS DESIRED

KEY NOTES:

- UNDERCUT DOOR FOR EXHAUST MAKEUP AIR
- KITCHEN HOOD TO PROVIDE MINIMUM 160 CFM OF EXHAUST AIR PER CENC TABLE 160.2-G. HOOD TO BE INSTALLED PER CENC 160.2(B)(2)(A)(V) AND MANUFACTURER'S RECOMMENDATIONS. MAX 3.0 SONES
- EXHAUST FAN TO RUN CONTINUOUSLY AT 59 CFM PER CENC 160.2(B)(2)(V) AND ASHRAE 62.2 REQUIREMENTS FOR WHOLE HOUSE VENTILATION, PROVIDE WITH SIGN NEXT TO FAN SWITCH INFORMING OWNER FAN IS TO RUN CONTINUOUSLY. MAX 1.0 SONE.
- RETURN AIR GRILLE WITH FILTER FRAME
- 4" DRYER VENT TO ROOF. VENT PER MANUFACTURER INSTRUCTIONS PER CMC 504.4.2.1. VENT LENGTH DOES NOT EXCEED 14'. PROVIDE ACCESSIBLE BOOSTER FAN AS REQUIRED
- 4" EXHAUST VENT TO ROOF



RATTLESNAKE RESIDENCE
12875 RATTLESNAKE ROAD
GRASS VALLEY, CA. 95945

ISSUED FOR	DATE
PERMIT	04-02-26
PLAN CHECK #1	05-01-26

PROJECT NUMBER 25341

SHEET TITLE

**MECHANICAL PLAN
JOB SET**

SHEET NO.

M1

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

GENERAL INFORMATION

01	Project Name	12875 Rattlesnake Road
02	Run Title	Title 24 Analysis
03	Project Location	12875 Rattlesnake Road
04	City	Grass Valley
05	Zip	95945
06	County	NEVADA
07	Climate Zone	1
08	Front Orientation (Mag/Cards)	135
09	Building Type	Single Family
10	Number of Dwelling Units	1
11	Project Scope	Addition and/or Alteration
12	Number of Bedrooms	3
13	Addition Cond. Floor Area (SF)	539
14	Number of Stories	1
15	Existing Cond. Floor Area (SF)	1756
16	Penetration Average U-Factor	0.23
17	Total Cond. Floor Area (SF)	2295
18	Slating Percentage (%)	13.62%
19	ADU Bedroom Count	0
20	ADU Conditioned Floor Area	539
21	Fuel Type	Natural Gas
22	No. Dwelling Units	1

COMPLIANCE RESULTS

Building Complies with Computer Requirement
 This building incorporates features that require field testing and/or verification by a certified ECC rater under the supervision of a CE-approved ECC provider.
 This building incorporates one or more special features shown below:

REQUIRED SPECIAL FEATURES

The following are features that must be installed as required for meeting the modeled energy performance for this computer analysis:

- Ceiling high level of insulation
- Insulation below roof deck
- Window coverings and/or film
- Northward Energy Efficiency Allowance (NEEA) rated heat pump water heater; specific brand/model, or equivalent, must be installed
- One or more heat pump water heaters have been modeled as demand response compatible

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained in this document.
 CA Building Energy Efficiency Standards - 2025 Single-Family Compliance
 Report Version: 2025.0.000
 Report Generated: 2026-04-29 11:33:05
 Schema Version: rev 20250101

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

ECC RATING SUMMARY

The following is a summary of the features that must be field-verified by a certified ECC Rater as a condition for meeting the modeled energy performance for this computer analysis. Additional detail is provided in the building tables below. Registered CF2Us and CF3Us are required to be completed in the ECC Registry.

Compliance Summary

Standard Design	Long Term System Cost (LSC)*		Source Energy Use		Peak Cooling**	
	Efficiency* (kBtu/yr)	Total* (kBtu/yr)	Total* (kBtu/yr)	n/a	Electricity (kWh)	n/a
Standard Design	29.76	n/a	n/a	n/a	n/a	n/a
Proposed Design	27.08	n/a	n/a	n/a	n/a	n/a
Compliance Margins	2.68	n/a	n/a	n/a	n/a	n/a

RESULTS: Complies

* Long term System Cost (LSC) is a 95 year present value cost to California's energy system. LSC is not a predicted utility bill.
 Efficiency measures include energy efficient improvements such as better building envelope and more efficient mechanical equipment.
 ** Peak cooling target represents 100% of the standard design building peak cooling energy use.

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained in this document.
 CA Building Energy Efficiency Standards - 2025 Single-Family Compliance
 Report Version: 2025.0.000
 Report Generated: 2026-04-29 11:33:05
 Schema Version: rev 20250101

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

A/C AND SOURCE ENERGY COMPLIANCE RESULTS FOR PERFORMANCE COMPONENTS

Energy Use	Standard Design Source Energy (kBtu/yr)*	Standard Design LSC* (kBtu/yr)	Proposed Design Source Energy (kBtu/yr)*	Proposed Design LSC* (kBtu/yr)	Compliance Margin Source (kBtu/yr)	Compliance Margin LSC* (kBtu/yr)
Space Heating	0	13.4	0	17.01	0	-1.63
Space Cooling	0	0.27	0	6.79	0	0.41
IAQ Ventilation	0	7.2	0	0.29	0	0
Water Heating	0	6.89	0	2.99	0	3.9
Life Utility/Off-Grid Battery	n/a	n/a	n/a	0	n/a	0
Photovoltaics and Battery	n/a	n/a	n/a	0	n/a	0
Flexibility	n/a	n/a	n/a	n/a	n/a	n/a
Indoor Lighting	0	1.54	0	1.54	n/a	0
Appl. & Cooling	0	6.14	0	6.14	n/a	0
Plug Loads	0	8.11	0	8.11	n/a	0
Outdoor Lighting	0	0.42	0	0.42	n/a	0
TOTAL COMPLIANCE	0	45.97	0	43.29	2.68	2.68

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained in this document.
 CA Building Energy Efficiency Standards - 2025 Single-Family Compliance
 Report Version: 2025.0.000
 Report Generated: 2026-04-29 11:33:05
 Schema Version: rev 20250101

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

ENERGY USE INTENSITY

	Standard Design (kBtu/ft² · yr)	Proposed Design (kBtu/ft² · yr)	Margin (kBtu/ft² · yr)	Margin Percentage
Gross EU*	27.77	27.26	0.51	1.84
Net EU**	27.77	27.26	0.51	1.84

BUILDING - FEATURES INFORMATION

Q1	Q2	Q3	Q4	Q5	Q6	Q7
01	02	03	04	05	06	07

ZONE INFORMATION

Q1	Q2	Q3	Q4	Q5	Q6	Q7
01	02	03	04	05	06	07

OPaque SURFACE SUMMARY

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11
01	02	03	04	05	06	07	08	09	10	11

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained in this document.
 CA Building Energy Efficiency Standards - 2025 Single-Family Compliance
 Report Version: 2025.0.000
 Report Generated: 2026-04-29 11:33:05
 Schema Version: rev 20250101

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

OPaque SURFACE SUMMARY

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

FINESTRATION / GLAZING

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained in this document.
 CA Building Energy Efficiency Standards - 2025 Single-Family Compliance
 Report Version: 2025.0.000
 Report Generated: 2026-04-29 11:33:05
 Schema Version: rev 20250101

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

FINESTRATION / GLAZING

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

OPaque SURFACE CONSTRUCTIONS

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained in this document.
 CA Building Energy Efficiency Standards - 2025 Single-Family Compliance
 Report Version: 2025.0.000
 Report Generated: 2026-04-29 11:33:05
 Schema Version: rev 20250101

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

OPaque SURFACE CONSTRUCTIONS

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained in this document.
 CA Building Energy Efficiency Standards - 2025 Single-Family Compliance
 Report Version: 2025.0.000
 Report Generated: 2026-04-29 11:33:05
 Schema Version: rev 20250101

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

OPaque SURFACE CONSTRUCTIONS

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained in this document.
 CA Building Energy Efficiency Standards - 2025 Single-Family Compliance
 Report Version: 2025.0.000
 Report Generated: 2026-04-29 11:33:05
 Schema Version: rev 20250101

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

OPaque SURFACE CONSTRUCTIONS

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

WATER HEATING SYSTEMS

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained in this document.
 CA Building Energy Efficiency Standards - 2025 Single-Family Compliance
 Report Version: 2025.0.000
 Report Generated: 2026-04-29 11:33:05
 Schema Version: rev 20250101

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

WATER HEATING SYSTEMS

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

WATER HEATERS - HEAT PUMP

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained in this document.
 CA Building Energy Efficiency Standards - 2025 Single-Family Compliance
 Report Version: 2025.0.000
 Report Generated: 2026-04-29 11:33:05
 Schema Version: rev 20250101

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
 Project Name: 12875 Rattlesnake Road
 Calculation Date/Time: 2026-04-29T11:32:45-07:00
 Input File Name: 25341 Russell Davidson Arch Nevada County Homekeyr Rattlesnake - EA_A.rbd25x
 Calculation Description: Title 24 Analysis

HVAC - HEAT PUMPS

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

HVAC - DISTRIBUTION SYSTEMS

Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18	Q19	Q20
01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20

Registration Number: 426-P0101273424-000-000-0000000-0000
 Registration Date/Time: 04/30/2026 10:59
 ECC Provider: CHEERS
 80722: This document has been generated by California Home Energy Efficiency Rating Services (CHEERS) using information submitted by third parties not affiliated with or related to CHEERS. Therefore, CHEERS is not responsible for, and does not warrant, the accuracy or completeness of the information contained


ELECTRICAL GENERAL NOTES

- ENTIRE INSTALLATION SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE 2025 CALIFORNIA ELECTRICAL CODE, NATIONAL ELECTRICAL CODE, AND ALL STATE AND LOCAL CODES, RULES AND ORDINANCES HAVING JURISDICTION.
- ALL CONDUCTORS SHALL BE PER DESIGN SHEETS, ELECTRICAL CODE AND MAXIMUM VOLTAGE DROP OF 3% WILL DEFINE CONDUCTOR SIZING.
- CONDUITS SHALL BE USED IN THE FOLLOWING METHODS:
 - POLY VINYL CHLORIDE (PVC) CONDUITS MAY BE USED IN CONCRETE SLABS AND UNDERGROUND PROVIDED ELBOWS AND RISERS ARE RIGID;
 - ALL EXPOSED CONDUIT SUBJECT TO WEAR OR COLLISION SHALL BE RIGID GALVANIZED STEEL (RGS) OR INTERMEDIATE METALLIC TUBING (MT). APPLY BITUMASTIC COATING TO ALL METALLIC CONDUITS IN SLABS OR UNDERGROUND.
 - PROVIDE FIRE RETARDANT U.L. APPROVED SEALANT ON ALL RACEWAY PENETRATIONS OF FIRE RATED CEILINGS, PARTITIONS, WALLS AND STRUCTURAL SLABS.
- FOR TELEPHONE SYSTEM: PROVIDE GROUNDING FOR ALL TELEPHONE BACKBOARDS, TERMINAL CABINETS AND EQUIPMENT PER REQUIREMENTS OF NEC 800 AND TELEPHONE COMPANY.
- ALL DISCONNECT SWITCHES SHALL BE SIZED PER NEC TO ACCOMMODATE EQUIPMENT SERVED, INCLUDING REQUIRED FUSES, U.N.O. SWITCHES SHALL BE HORSE POWER RATED, OF HEAVY DUTY TYPE. PROVIDE MEANS FOR PAD LOCKING IN THE OPEN POSITION.
- ALL CIRCUIT BREAKERS SHALL BE INVERSE TIME (THERMAL MAGNETIC) "PERMANENT TRIP" TYPE. TWO AND THREE POLE CIRCUIT BREAKERS SHALL BE COMMON TRIP.
- ALL CONNECTIONS TO GROUND RODS AND GRID, ETC., SHALL BE MADE WITH U.L. APPROVED WELDED CONNECTIONS, UNLESS NOTED OTHERWISE.
- LIGHTING SYSTEMS SHALL COMPLY WITH TITLE 24. ALL LIGHTING FIXTURES, LAMPS, BALLASTS, DIMMER SWITCHES, AND CONTROLS SHALL BE CERTIFIED WITH THE CALIFORNIA ENERGY COMMISSION ("CEC") AS MEETING ALL TITLE 24 REQUIREMENTS AND BE LISTED IN THE APPLICABLE CEC DIRECTORY. ALL SUCH DEVICES AND EQUIPMENT SHALL BE INSTALLED PER THE MANUFACTURER'S INSTRUCTIONS. LIGHT FIXTURES IN SUSPENDED CEILINGS SHALL BE SUPPORTED IN STRICT ACCORDANCE WITH CALIFORNIA BUILDING CODE (LATEST EDITION) SEISMIC REQUIREMENTS.
- ALL ELECTRICAL EQUIPMENT, DEVICES, WIRE, ETC., SHALL BE LISTED, FOR THE INTENDED USE, WITH UNDERWRITER'S LABORATORIES, INC. (UL), WHERE STANDARDS HAVE BEEN ESTABLISHED. BY UL. ALL EQUIPMENT SHALL BE RAIN TIGHT WHERE EXPOSED TO THE WEATHER. ALL FLEX CONDUITS CONNECTED TO SUCH EQUIPMENT SHALL BE METALLIC LIQUID TIGHT. ALL EQUIPMENT IN HAZARDOUS LOCATIONS, PER NEC, CHAPTER 5, SHALL BE IN ACCORDANCE WITH THE NEC. ALL EQUIPMENT IN CORROSIVE ENVIRONMENTS SHALL BE IN ENCLOSURES (SUCH AS NEMA 4X) RATED FOR THE ENVIRONMENT.
- UTILITY SERVICE AND REQUIREMENTS SHALL BE COORDINATED WITH POWER SERVICE WITH POWER COMPANY; PROVIDE FOR ALL STANDARD POWER COMPANY REQUIREMENTS. FAULT CURRENT RATINGS SHALL BE PROVIDED BY UTILITY.
- THE LAYOUTS OF THE CONTRACT DRAWINGS ARE DIAGRAMMATIC. IT IS NOT INTENDED TO SHOW EVERY OFFSET AND FITTING, NOR EVERY STRUCTURAL DIFFICULTY THAT WILL BE ENCOUNTERED DURING THE INSTALLATION OF THE WORK. ALIGNMENT OF EQUIPMENT AND ROUTING OF RACEWAYS MAY BE VARIED SLIGHTLY TO ACCOMMODATE ARCHITECTURAL CONDITIONS OR TO AVOID THE WORK OF OTHER TRADES. IF ANY CONFLICTS OCCUR NECESSITATING DEPARTURES FROM CONTRACT DRAWINGS, DETAILS OF DEPARTURES AND REASONS THEREFORE SHALL BE SUBMITTED AS SOON AS PRACTICABLE FOR WRITTEN APPROVAL OF THE ENGINEER.
- THE WORD "CONTRACTOR", AS USED IN THE ELECTRICAL CONTRACT DOCUMENTS, SHALL MEAN THE PRIME (I.E. GENERAL) CONTRACTOR AND HIS/HER SUBCONTRACTORS FOR THE APPROPRIATE TRADE. WHERE THE OWNER ACTS AS HIS OWN CONTRACTOR, THE WORD CONTRACTOR APPLIES TO THE OWNER.
- CONTRACTOR SHALL PROVIDE EVIDENCE OF LICENSING, BONDING, AND INSURANCE, AND PROVIDE OTHER NECESSARY ADMINISTRATIVE FUNCTIONS FOR CONTRACTOR'S WORK.
- CONTRACTOR SHALL PROCURE AND PAY FOR ALL REQUIRED PERMITS AND SERVICE CHARGES.
- COORDINATION: CONFORM TO GENERAL CONSTRUCTION CONTRACT DOCUMENTS EXCEPT AS MODIFIED HEREIN. REFER ALSO TO STRUCTURAL AND MECHANICAL CONTRACT DOCUMENTS. COORDINATE ALL WORK WITH OTHER TRADES.
- CUTTING AND PATCHING: ANY CUTTING, ATTACHING, OR WELDING TO BUILDING STRUCTURE SHOULD BE COORDINATED AND APPROVED BY A CALIFORNIA LICENSED STRUCTURAL ENGINEER. PATCHING SUBJECT TO ACCEPTANCE BY OWNER.
- SAW CUT TRENCHES IN SLAB SHALL BE FULLY RESTORED AND REINFORCED TO PREVENT SAGGING. ROUGHEN SAW CUT EDGES PRIOR TO RE-POURING CONCRETE.
- COORDINATE ALL WORK WITH OTHER TRADES TO PROVIDE A COMPLETE INSTALLATION. CONNECT ALL EQUIPMENT FURNISHED BY OTHERS AS REQUIRED. INSTALL ALL WORK TO CLEAR ARCHITECTURAL AND STRUCTURAL MEMBERS. INSTALL ALL ABOVE GRADE (OVERHEAD) PIPING AS HIGH AS PRACTICAL.
- RESTORE ALL DAMAGE RESULTING FROM THE WORK AND LEAVE PREMISES IN CLEAN CONDITION WHEN FINISHED WITH WORK. ADJUST, CLEAN, REPAIR, OR REPLACE PRODUCTS, WHICH HAVE BEEN DAMAGED.
- PROVIDE FLASHING AND COUNTER FLASHING FOR ALL WALL AND ROOF PENETRATIONS.
- WARRANTY: ALL MATERIALS AND EQUIPMENT INSTALLED UNDER THIS CONTRACT SHALL BE GUARANTEED FREE FROM ALL MECHANICAL, ELECTRICAL, AND WORKMANSHIP DEFECTS FOR A MINIMUM OF ONE YEAR FROM DATE OF FINAL ACCEPTANCE. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGES TO THE PREMISES CAUSED BY WORK UNDER THIS CONTRACT, AS WELL AS ANY DAMAGE FROM LEAKS VIA ROOF PENETRATIONS MADE AND SEALED UNDER CONTRACTOR'S SCOPE.

RESIDENTIAL CALGREEN ELECTRICAL NOTES

- ENHANCED DURABILITY AND REDUCED MAINTENANCE:
 - 4.406.1 ANNULAR SPACES AROUND PIPES, ELECTRIC CABLES, CONDUITS OR OTHER OPENINGS IN PLATES AT EXTERIOR WALLS SHALL BE PROTECTED AGAINST THE PASSAGE OF INTRUDERS BY CLOSING SUCH OPENINGS WITH CEMENT MORTAR, CONCRETE MASONRY OR SIMILAR METHOD ACCEPTABLE TO THE ENFORCING AGENCY
- BUILDING MAINTENANCE AND OPERATION:
 - 4.410.1 AN OPERATION AND MAINTENANCE MANUAL SHALL BE PROVIDED TO THE BUILDING OCCUPANT OR OWNER
- SITE DEVELOPMENT:
 - 4.106.4 PROVIDE CAPABILITY FOR ELECTRIC VEHICLE CHARGING IN ONE- AND TWO-FAMILY DWELLINGS AND IN TOWNHOUSES WITH ATTACHED PRIVATE GARAGES; AND 10 PERCENT OF TOTAL PARKING SPACES, AS SPECIFIED, FOR MULTIFAMILY DWELLINGS.

ONE-LINE DIAGRAM



FEEDER SCHEDULE - 1 PHASE

TAG	# OF CU SETS	COPPER CONDUIT (PER SET)	COPPER CONDUCTORS (PER SET)		# OF AL SETS	ALUMINUM CONDUIT (PER SET)	ALUMINUM CONDUCTORS (PER SET)	
			PHASE/NEUTRAL	GROUND			PHASE/NEUTRAL	GROUND
E-01	1	1"	(3) #4 AWG CU	(1) #8 AWG CU	1	1-1/4"	(3) #3 AWG AL	(1) #6 AWG AL

Residential Electrical Load Calculation in accordance with CEC 220.82

[12875 RATTLESNAKE ROAD] - Garage Conversion Subpanel			
General Load			Source
Total square footage of Unit	540 SF x 3 VA/SF =	1,620 VA	CEC
20A small appliance @ 1500VA =	2 x 1500 VA =	3,000 VA	CEC
Laundry circuit @ 1500VA =	1 x 1500 VA =	1,500 VA	CEC
General Subtotal		6,120 VA	
Appliance Load			Source
Disposal	1 x 800 VA x 1.00 =	800 VA	CEC
Refrigerator	1 x 800 VA x 1.00 =	800 VA	CEC
Range/Oven	1 x 8000 VA x 1.00 =	8,000 VA	CEC
Clothes Dryer	1 x 5000 VA x 1.00 =	5,000 VA	CEC
Appliance Subtotal		14,600 VA	
First 10kVA @ 100%	10,000 VA x 1.0 =	10,000 VA	CEC 220.82
Remainder @ 40%	10,720 VA x 0.40 =	4,288 VA	CEC 220.82
General & Appliance Subtotal		14,288 VA	
HVAC Load @ 100%			Source
Condenser Unit #1	1 x 2173.5 VA x =	2,174 VA	Cutsheet
Fan Coil Unit #1	1 x 0 VA x =	0 VA	Cutsheet
HVAC Subtotal @ 100%		2,174 VA	
Total Load (General + Appliance + HVAC Subtotals)		16,462 VA	
		240 Volts	
		1 Phase	
		68.6 Amps	
		70 AMP Service/Panel	
		4 AWG CU Feeder sizes	
		3 AWG AL Feeder sizes	

Residential Electrical Load Calculation in accordance with CEC 220.83

[12875 RATTLESNAKE ROAD] - Main Panel - Existing Loads Only			
General Load			Source
Total square footage of Unit	2430 SF x 3 VA/SF =	7,290 VA	NEC
20A small appliance @ 1500VA =	2 x 1500 VA =	3,000 VA	NEC
Laundry circuit @ 1500VA =	1 x 1500 VA =	1,500 VA	NEC
General Subtotal		11,790 VA	
Appliance Load			Source
Electric Tank Water Heater	1 x 4500 VA x 1.00 =	4,500 VA	Cutsheet
Disposal	1 x 800 VA x 1.00 =	800 VA	NEC
Dishwasher	1 x 1300 VA x 1.00 =	1,300 VA	NEC
Range/Oven	1 x 8000 VA x 1.00 =	8,000 VA	NEC
Clothes Dryer	1 x 5000 VA x 1.00 =	5,000 VA	NEC
Stand-Alone Oven	1 x 8000 VA x 1.00 =	8,000 VA	Cutsheet
Appliance Subtotal		27,600 VA	
First 8kVA @ 100%	8,000 VA x 1.0 =	8,000 VA	NEC 220.83
Remainder @ 40%	31,390 VA x 0.40 =	12,556 VA	NEC 220.83
General & Appliance Subtotal		20,556 VA	
HVAC Load @ 100%			Source
Package HVAC Unit	1 x 6946 VA x =	6,946 VA	Cutsheet
HVAC Subtotal @ 100%		6,946 VA	
Total Load (General + Appliance + HVAC Subtotals)		27,502 VA	
		240 Volts	
		1 Phase	
		114.6 Amps	
		200 AMP Service/Panel	
		2/0 AWG CU Feeder sizes per Table 310.12	
		4/0 AWG AL Feeder sizes per Table 310.12	

TOTAL LOAD:
 114.6 AMPS + 68.6 AMPS =
 183.2 AMPS < 200 AMP (E) SERVICE

ELECTRICAL SHEET INDEX

- E0 ELECTRICAL SCHEDULES, ONE-LINE, & GENERAL NOTES
- E1 ELECTRICAL PANEL SCHEDULES
- E2 ELECTRICAL PLAN

ELECTRICAL SCOPE OF WORK

- INSTALLATION OF (N) SUBPANEL FROM (E) SERVICE TO FEED (N) GARAGE CONVERSION
- INSTALLATION OF NEW LIGHTING SYSTEMS AND ASSOCIATED POWER AND CONTROLS IN (N) GARAGE CONVERSION
- (E) LIGHTING SYSTEMS AND ASSOCIATED POWER AND CONTROLS TO REMAIN IN MAIN (E) HOUSE
- (E) WATER HEATER TO REMAIN AND TO BE RELOCATED TO WH CLOSET
- INSTALLATION OF NEW CLOTHES DRYER & CLOTHES WASHER AND ASSOCIATED POWER AND CONTROLS IN (E) MAIN RESIDENCE
- RELOCATION AND ADDITION OF LIGHTING FIXTURES PER PLANS. CONNECT TO EXISTING LIGHTING SYSTEMS AND ASSOCIATED POWER AND CONTROLS

Panel Name:	A - ADU Subpanel				Bus Rating:	70A	
Voltage & Phase:	120/240V - 1Ø - 3W				AIC Rating:	10kAIC	
Mounting:	Surface				Main Type:	Circuit Breaker	
Enclosure Rating:	NEMA 3R				MCB Rating:	70A	
	Description	BRK	Ckt	PHASE	Ckt	BRK	Description
	Clothes Washer	20/1	1	A	2	20/1	Bedroom - Receptacles
	Clothes Dryer	30/2	3	B	4	20/1	Bathroom - Receptacles
	-	-	5	A	6	20/1	Living - Receptacles
	Refrigerator	20/1	7	B	8	20/1	Small Kitchen Appliance #1
	Range	30/2	9	A	10	20/1	Small Kitchen Appliance #2
	-	-	11	B	12	20/1	Unit Lighting
	Disposal	20/1	13	A	14	30/2	HP-1
	-	-	15	B	16	-	-

LIGHTING LEGEND


- ⊙ DOWNLIGHT
- ⊙ PENDANT LIGHT
- ⊕ SURFACE MOUNT
- TRACK LIGHT
- WALL MOUNT FIXTURE
- S_XX WALL MOUNTED SWITCH (D- DIMMER, V- VACANCY SENSOR, 3- 3-WAY)

POWER LEGEND

- ⊕ DUPLEX OUTLET - WALL, FLOOR, CEILING MOUNTED
- ⊕ GFI - GROUND FAULT INTERRUPT WP - WEATHERPROOF +44" - 44" AFF
- ⊕ FLOOR-MOUNTED DUPLEX OUTLET
- ⊕ QUADRUPLEX OUTLET 16IN A.F.F. U.O.N.
- ⊕ FLOOR-MOUNTED QUADRUPLEX OUTLET
- ⊕ DEDICATED OUTLET
- ⊕ 20A, 208/240V OUTLET (NEMA 6-20R)
- ⊕ 30A, 208/240V OUTLET (NEMA 6-30R)
- ▶ PHONE-DATA PORT
- ⊙ SMOKE DETECTOR
- ⊙ CARBON MONOXIDE DETECTOR
- ⊙ JUNCTION BOX
- ⊕ TELEVISION
- ⊕ DISCONNECT - POLES (CAPACITY/FUSE)
- LP-1,3,5 HOME RUN - PANEL-POLE(S)
- POWER PANEL
- T-1 TRANSFORMER

ELECTRICAL LEGEND

- A.F.F. ABOVE FINISHED FLOOR
- +48" HEIGHT (INCHES) AFF
- D DIMMER
- TX TRANSFORMER



DATE SIGNED 05-01-26

RATTLESNAKE RESIDENCE
 12875 RATTLESNAKE ROAD
 GRASS VALLEY, CA. 95945

ISSUED FOR	DATE
PERMIT	04-02-26
PLAN CHECK #1	05-01-26


PROJECT NUMBER 25341

SHEET TITLE

ELECTRICAL GENERAL NOTES, CALCS, & SCHEDULES
JOB SET

SHEET NO.

E0



A ELECTRICAL PLAN
SCALE: 1/4"=1'-0"



SHEET NOTES:

1. (E) EXISTING
(N) NEW
(R) RELOCATED
2. ALL RECEPTACLES/EQUIPMENT ARE (E) TO REMAIN U.O.N.
3. ALL WIRING TO BE #12 AWG U.O.N.
4. ALL INTERIOR WIRING TO BE 2-CONDUCTOR, NON-METALLIC SHEATHED. ALL EXTERIOR WIRING TO BE INSULATED WITH THWN-2. ALL EXTERIOR CONDUIT SHALL BE FLEX CONDUIT ABOVE GROUND, OR PVC IF BELOW GROUND
5. BOND METALLIC GAS PIPE AND WATER PIPES TO SERVICE GROUND
6. SMOKE DETECTORS AND CARBON MONOXIDE DETECTORS ARE TO BE HARDWIRED AND INTERCONNECTED AND HAVE A BATTERY BACKUP. SMOKE DETECTORS AND CARBON MONOXIDE DETECTORS SHALL SOUND AN ALARM AND BE AUDIBLE IN ALL SLEEPING AREAS
7. ALL CEILING FAN BOXES TO BE LISTED AS "FAN RATED"
8. ALL 120-VOLT, SINGLE PHASE, 15- & 20-AMP BRANCH CIRCUITS SUPPLYING OUTLETS INSTALLED IN DWELLING UNIT KITCHENS, DINING ROOMS, FAMILY ROOMS, LIVING ROOMS, PARLORS, LIBRARIES, BENS, BEDROOMS, SUNROOMS, REC ROOMS, CLOSETS, LAUNDRY AREAS, HALLWAYS AND SIMILAR ROOMS SHALL BE PROTECTED BY A LISTED ARC-FAULT CIRCUIT INTERRUPTER, COMBINATION TYPE, INSTALLED TO PROVIDE PROTECTION OF THE BRANCH CIRCUIT PER CEC 210.12
9. NON-METALLIC SHEATHED CABLE SHALL BE SECURED BY STAPLES. CABLE TIES, STRAPS, HANGERS OR SIMILAR AT INTERVALS NOT EXCEEDING 4'-1/2" WITHIN 12" OF EACH CABINET, BOX OR FITTING. FLAT CABLES SHALL NOT BE STAPLED ON EDGE
10. ALL NEW 125-VOLT, 15 AND 20 AMP RECEPTACLES IN THE DWELLING ARE LISTED TAMPER-RESISTANT. CEC 406.12
11. CONTRACTOR TO COORDINATE WITH OWNER TO CONFIRM FINAL LOCATIONS OF CONVENIENCE RECEPTACLES
12. ALL RECEPTACLES LOCATED IN BATHROOMS, GARAGES, OUTDOORS, CRAWLSPACES, UNFINISHED AREAS OF BASEMENTS, KITCHENS, BATHHOUSES, LAUNDRY AREAS, OR WITHIN 6FT OF SINKS, TUBS, OR SHOWERS TO HAVE GFI PROTECTION PER CEC 210.8(A)
13. PROVIDE AT LEAST TWO 20-AMPERE BRANCH CIRCUITS TO SERVE COUNTER TOP RECEPTACLES FOR SMALL KITCHEN APPLIANCES PER CEC 210.52(B)
14. PROVIDE ONE DEDICATED 20-AMPERE BRANCH CIRCUIT FOR THE BATHROOM RECEPTACLE OUTLETS PER CEC 210.11(C)(3).
15. ALL EXTERIOR DISCONNECT SWITCHES SHALL BE NEMA 3R PER CEC TABLE 110.26. PROVIDE LIQUID-TIGHT CONDUIT
16. ALL RECEPTACLES LOCATED OUTSIDE SHALL BE TYPE WEATHER RESISTANT, GFI WITH EXTRA DUTY IN-USE COVER, PER CEC 210.8 AND 406.9(B)
17. RECEPTACLES IN DWELLINGS TO BE LOCATED PER CEC 210.52
18. PROVIDE FIRE STOPPING ASSEMBLY PROTECTION FOR DUCT PENETRATIONS OF RATED ASSEMBLIES. FIRE STOP RATING SHALL MATCH RATED ASSEMBLY BEING PENETRATED
19. GARAGE CONVERSION LIGHTING TO BE ON CIRCUIT A-12

KEY NOTES:

- ① DISCONNECT FOR WATER HEATER
- ② PROVIDE NEMA 14-30R RECEPTACLE WITH #10 AWG, 2-CONDUCTOR, NON-METALLIC WIRE
- ③ INDOOR FAN COIL POWERED VIA OUTDOOR CONDENSER UNIT, PROVIDE WIRING BETWEEN INDOOR AND OUTDOOR UNITS PER MANUFACTURER REQUIREMENTS AND COORDINATE WITH MECHANICAL CONTRACTOR



DATE SIGNED 05-01-26

RATTLESNAKE RESIDENCE
12875 RATTLESNAKE ROAD
GRASS VALLEY, CA. 95945

ISSUED FOR	DATE
PERMIT	04-02-26
PLAN CHECK #1	05-01-26

PROJECT NUMBER	25341
SHEET TITLE	ELECTRICAL PLAN JOB SET
SHEET NO.	E1