



## SYNTHETIC ROOF UNDERLAYMENT

<b>-Felt (85)</b>	<b>-Felt (85)</b>
<b>Roll Width</b>	<b>48"</b>
<b>Roll Weight</b>	<b>19 lb</b>
<b>Roll Length</b>	<b>250 ft</b>
<b>Rolls per Pallet (44x44)</b>	<b>72</b>
<b>Rolls per Truckload -36 Skids</b>	<b>2592</b>
<b>Rolls Required per 1,000 sq feet</b>	<b>1</b>
<b>Material Composition</b>	<b>PP/PE</b>
<b>UV Resistance</b>	<b>4 Months</b>
<b>Dimensional Stability</b>	<b>MD 0.10-PASS CD -0.27- PASS</b>
<b>Unroll-Ability D266</b>	<b>No Cracking or Sticking - PASS</b>
<b>Tear Strength ASTM D4533 MD</b>	<b>50 lb</b>
<b>Tear Strength ASTM D4533 CD</b>	<b>53 lb</b>
<b>Water shower Exposure ASTM D1777</b>	<b>Pass</b>
<b>Permeability ASTM D1777</b>	<b>&lt;0.05 Perms</b>
<b>Mullen Burst</b>	<b>113 psi</b>
<b>Nominal Thickness ASTM D1777</b>	<b>85 GSM/ Woven</b>
<b>Temperature Range</b>	<b>-40° F to 270° F</b>
<b>Enhanced Slip Resistance Surface</b>	<b>Excellent</b>
<b>Liquid Water Transmission</b>	<b>No Sign of Any Water Penetration</b>
<b>Loss on Heating % D266</b>	<b>0.4-PASS</b>
<b>Pliability</b>	<b>No Cracking or Delamination</b>
<b>Warranty</b>	<b>15 Years</b>
<b>MD = Machine Direction</b>	<b>CD = Cross Direction</b>