

CUSTOMS BROKERS—INTERNATIONAL FREIGHT FORWARDERS—SHIP'S AGENTS

Volume 1 First Quarter



Supply Chain Security Advisement

CONTAINER AND TRAILER SECURITY

As a certified C-TPAT company, we are committed to educating all our customers on critical supply chain security issues. Container and trailer security programs and procedures are crucial elements of a secure supply chain. We recommend that you instruct your foreign vendors, highway carriers, freight forwarders and third party logistic providers to carefully inspect all trailers and containers bound for the United States.

Container and trailer integrity must be maintained to protect against the introduction of unauthorized material and/or persons. At the point of stuffing, procedures must be in place to ensure that containers are properly inspected prior to release.

The 17 point tractor and trailer inspection is an integral part of cargo security for all tractors and trailers/containers arriving from a foreign destination. Both the tractor and trailer/container need be scrutinized if arriving from a foreign destination

We highly recommend the following inspection process for containers/trailers and that you forward this information to all of your foreign vendors and any entity involved in the supply chain of your cargo.







ATTENTION



Report any abnormalities including overages and shortages to U.S. Customs and Border Protection at:

1-800-BE-ALERT

Please visit their website for more information and current security alerts at:

WWW.CBP.GOV

For further questions or comment regarding this advisement, please contact our offices at:

San Diego

Tel. (619) 232-8941

www.pshinc.net

L.A./Long Beach

Tel. (562) 985-3456

E-mail: tom-jenkins@pshinc.net

17 Point Tractor & Trailer Inspection

Bumper

Check the void space behind the bumper

2 Engine

Inspect the engine compartment

? Tires

Check rims and areas around wheels

4 Flant

Check for false compartments

5 Fuel Tanks

Look for evidence of modifications

6 Cab/Storage Compartment

Check the driver's area and sleeper

7 Air Tanks

Evidence of repairs should be scrutinized

B Drive Shafts

Shafts should be clear of obstructions

9 Fifth Wheel

Skid plate and natural compartment

10 Outside/Undercarriage

Support beams should be visible

1 Floor

Should be flush from front wall to end

12 Inside/Outside Daors

Door spaces should not be filled in

13 Side Wells

Tap with mallet. It should sound hollow

14 Ceiling/Roof

Check blocks and vent holes.

15 Front Wall

Measure the inside length of the trailer

6 Refrigerated Unit

Unit should be functional

17 Exhaust

Observe while engine is running