

ELEVATOR CABS AND SURFACES



Standard Manufacturing Lead Time

Standard Sizes 10-12 Days
All Other Power Unit Sizes = 4-8 Weeks
Expedited Manufacturing Available

Advantages

- Fabricated In Durham NC
- Cost Effective
- Compact Design
- All Components are Located in the Tank
- ShortLead Times

Standard Equipment

- Pump: IMO, Settima or Seim
- Motor: Imperial or US
- Valve: Maxton
- 80 Starts Per Hour Motor
- Compact “MEI Silencer” with Pneumatic Noise Suppression
- Oil Level Dipstick
- Isolation Between the Pump/Motor Assembly and the Tank
- Oil Temperature Sensor (ASME 2010 Code Only)

Optional Features

- Loadweigh Sensor
- Tank Heater
- Thermostat
- Oil Level Sight Gauge with Thermometer (on tank)
- Pressure Gauge (mounted on valve)
- Low Oil Level Switch (in tank)
- Low Pressure Switch (required if jack head is above power unit)
- Hot Oil Sensor
- Oil Cooler
- Vent/Fill Strainer
- Down Speed Regulated Valve
- 120 Starts Per Hour Available (up to 40 HP)
- Junction box
- Installation kit
- Overflow Connection
- B-Port
- Top Mount Valve
- **Extended 3 Year Warranty Available**