



- CONSTRUCTION NOTES:**
- ① INSTALL 6" J-DRAIN SWD MODULAR FOUNDATION DRAIN LAID FLAT ON SUB-GRADE
 - ② INSTALL 6" SMOOTH INTERIOR PERFORATED HDPE STORM DRAIN PIPE
 - ③ INSTALL J-DRAIN SWD DRAIN END CAP WITH MAGNETIC LOCATOR TAPE
 - ④ INSTALL HDPE HORIZONTAL BEND (16 IN TOTAL)
 - ⑤ INSTALL STORM DRAIN TEE
 - ⑥ INSTALL J-DRAIN LP CONNECTOR AND RISER TO 6" STORM DRAIN PIPE (39 IN TOTAL)
 - ⑦ CONNECT FIELD STORM DRAINS TO EXISTING STORM DRAIN OUTFALLS. CONTRACTOR TO VERIFY SIZE, LOCATION, INVERT OF EXISTING STORM DRAIN OUTFALL PRIOR TO CONSTRUCTION

4MOST
SPORT GROUP



149 South Broad Street | Grove City | Pennsylvania | 16127

OUTDOOR ATHLETIC FACILITY
DESIGNERS & CONSULTANTS

724.870.4249
office@4mostsport.com
www.4mostsport.com

ALL RIGHTS RESERVED

OWNERSHIP OF DOCUMENTS

This document, and the ideas and designs incorporated herein, as an instrument of professional service, is the sole property of 4Most Sport Group LLC, and is not to be used in whole or in part for any other project or purpose without the expressed written authorization of 4Most Sport Group LLC.

CONTRACTOR

City of Milbank, South Dakota

Birthplace of American Legion Baseball
New Full-Size Baseball Field

Lake Farley Camp Site
Milbank, SD 57252

Drainage Plan

| No. | Description | Date |
|-----|-------------|------|
| | | |
| | | |
| | | |

FOR REVIEW ONLY
NOT FOR CONSTRUCTION

| | |
|----------------|------------|
| Project Number | 4M-026-AE |
| Date | 06/16/2022 |
| Drawn by | WRC |
| Checked by | GJD |

PF-2.3



1" = 20'