



CEI 0-21:2022-03 Annex Nbis.

EXPOFIN SOLID POWER

HV 261 KWH

EXPOFIN srl - E.S.Co (Energy Service Company)

Viale dell'Industria, 19 - 35129 Padova (PD)

P.IVA e C.F: 05419570287

Tel. +39 045 2457 812

Mail. info@expofin.it - segreteria@expofin.it

PEC: expofin@legalmail.it

Sito: www.expofin.eu

DICHIARAZIONE SOSTITUTIVA DI ATTO NOTORIO AI SENSI DEL D.P.R. 28 DICEMBRE 2000 N. 445

Dichiarazione di conformità alle prescrizioni della norma CEI 0-21:2022-03 e successive varianti applicabili (V1, V2, EC, EC2)

Declaration of compliance with the requirements of CEI standard 0-21:2022-03 and subsequent applicable variants (V1, V2, EC, EC2)

Regola tecnica di riferimento per la connessione di utenti attivi e passivi alle reti BT delle imprese distributrici di energia elettrica.

Technical reference rule for connecting active and passive users to the LV networks of electricity distribution providers.

Con la presente si attesta che il prodotto:

We hereby declare that the product

Famiglia di generatori – sistemi di accumulo

Family of generators – storage systems

Definiti da:


Defined by:

Expofin Solid Power HV 261

È CONFORME AGLI STANDARD

Is compliant to the standards

CEI 0-21:2022-03 Annex Bbis



1) Expofin Solid Power HV 261

Informazioni tecniche e descrizione del prodotto:

Il sistema trova applicazione principalmente in scenari industriali e commerciali.

1. Il sistema di accumulo di energia comprende un rack per batterie, un armadio PCS, un armadio di distribuzione dell'energia, un sistema di distribuzione ausiliario, un sistema di aria condizionata, una scatola di controllo BMS e un sistema antincendio.

- La scatola di distribuzione ausiliaria serve a fornire l'alimentazione ausiliaria per l'intero sistema di controllo BMS e per il sistema di aria condizionata.
- L'armadio della batteria si collega al PCS tramite la convergenza della barra collettiva e il PCS converte la corrente continua generata dalle batterie di accumulo di energia in corrente alternata, necessaria per il collegamento alla rete tramite trasformatori e altri componenti o richiesta dal cliente.
- L'ESS è dotato di un controller locale nell'armadio di distribuzione dell'alimentazione e raccoglie informazioni sul funzionamento del PCS, della batteria e di altri dispositivi nel sistema. Inoltre carica le informazioni nel sistema di gestione dell'energia tramite lo sfondo e facilita la gestione del sistema di accumulo dell'energia.
- La funzione di controllo principale integrata nella scatola di controllo BMS.

Technical Information and product description:

The system is mainly applied in industrial and commercial scenarios.

1. The Energy Storage System which include one battery rack, one PCS cabinet, one power distribution cabinet, auxiliary distribution system, Air-condition system, BMS control box and fire suppression system.

- The auxiliary distribution box is for providing the auxiliary power for whole BMS control system, air-condition system.
- Battery cabinet connects to PCS through the busbar convergence, and the PCS converts the DC power generated by the energy storage batteries into AC power which required for connecting to the grid through transformers and other components or required by client.
- The ESS is equipped with the local controller in Power distribution cabinet, it collects running information of the PCS, battery, and other devices in the system. And it uploads the information to the energy management system via the background and facilitate the management of energy storage system.
- The master control function integrated in BMS control box.



Test Report - Products

DICHIARA

che il sistema di accumulo energetico EXPOFIN SOLID POWER HV 261 è stato sottoposto a verifiche di conformità secondo la norma CEI 0-21:2022-03 e successive varianti applicabili, presso laboratorio TÜV Rheinland, con esito positivo;
 che i relativi rapporti di prova originali e la documentazione tecnica di supporto sono conservati presso EXPOFIN S.r.l.;
 che la documentazione potrà essere resa disponibile, su richiesta motivata, ai soggetti aventi titolo per verifiche tecniche/autorizzative/di connessione, nel rispetto degli obblighi di riservatezza e delle condizioni d'uso dei documenti del laboratorio;
 che la presente dichiarazione non sostituisce i rapporti di prova originali emessi dal laboratorio, ma attesta quanto sopra sotto la responsabilità del dichiarante.


Cliente: Client:	EXPOFIN S.R.L. VIALE DELL'INDUSTRIA, N.19 – 35129 PADOVA (PD) – ITALY
Elemento di prova: Test item:	Energy Storage System (Integrated Battery Energy Storage System)
Identificazione / Numero di tipo: Identification / Type no.:	SOLID POWER HV 261
Specifiche del test: Test specification:	CEI 0-21:2022-03 CEI 0-21;V1:2022-11 CEI 0-21;V2:2024-01 CEI 0-21;V2/EC:2024-03 CEI 0-21;V2/EC2:2025-02
Laboratorio di prova: Testing laboratory:	TÜV Rheinland (Shanghai) Co., Ltd.
Risultato del test*: Test result*:	Pass/Approvato

TEST REPORT

CEI 0-21:2022-03+V1+V2:2024-01+V2/EC2:2024-03+V2/EC2:2025-02

Regola tecnica di riferimento per la connessione di Utenti attivi e passivi alle reti BT delle imprese distributrici di energia elettrica

/Reference technical rules for the connection of active and passive users to the LV electrical Utilities

<p>Nome e indirizzo del richiedente: Applicant's name and Address:</p>	<p>EXPOFIN S.R.L. VIALE DELL'INDUSTRIA, N.19 – 35129 PADOVA (PD) – ITALY</p>
<p>Descrizione dell'elemento di prova: Test item description:</p>	<p>Energy Storage System (Integrated Battery Energy Storage System)</p>
<p>Marchio: Trade Mark:</p>	
<p>Produttore: Manufacturer:</p>	<p>EXPOFIN S.R.L. VIALE DELL'INDUSTRIA, N.19 – 35129 PADOVA (PD) – ITALY</p>

NORME DI RIFERIMENTO:

Reference Standard:

CEI 0-21:2022-03+V1+V2:2024-01+V2/EC2:2024-03+V2/EC2:2025-02

Regola tecnica di riferimento per la connessione di Utenti attivi e passivi alle reti BT delle imprese distributrici di energia elettrica

/Reference technical rules for the connection of active and passive users to the LV electrical Utilities.

The standard refers to the following standards:

Allienamento al Regolamento UE 2016/631, UE 2016/1388 e UE 2016/1447 (RfG)

/ Alignment with the Regulation UE 2016/631, UE 2016/1388 e UE 2016/1447 (Requirements for Generators - RfG)

CEI EN 60068-2-2:2008-11

Prove ambientali - Parte 2-2: Prove - Prova B: Caldo secco

/Environmental testing - Part 2-2: Tests - Test B: Dry heat

CEI EN 60068-2-78:2002:03

Prove ambientali - Parte 2-78: Prove - Prova Cab: Caldo umido, regime stazionario

/Environmental testing - Part 2-78: Tests - Test Cab: Damp heat, steady state

CEI EN 60068-2-1:2007:11

Prove ambientali - Parte 2-1: Prove - Prova A: Freddo

/Environmental testing - Part 2-1: Tests - Test A: Cold

CEI EN 60068-2-14:2010

Prove ambientali - Parte 2-14: Prove - Prova N: Cambio di temperatura

/Environmental testing - Part 2-14: Tests - Test N: Change of temperature

CEI EN 60255-27:2023

Parte 27: requisiti di sicurezza dei prodotti

/Electrical Relays - Part 27: Product safety requirements

CEI EN 61000-3-2:2007-04 + CEI EN 61000-3-2/A1/A2:2011-09

Compatibilità elettromagnetica (EMC) Parte 3-2: Limiti - Limiti per le emissioni di corrente armonica (apparecchiature con corrente di ingresso ≤ 16 A per fase)

/Electromagnetic compatibility (EMC) - Part 3-2: Limits - Limits for harmonic current emissions (equipment input current ≤ 16 A per phase)

CEI EN 61000-3-3:2009-09

Compatibilità elettromagnetica (EMC) Parte 3-3: Limiti - Limitazione delle variazioni di tensioni, fluttuazioni di tensione e del flicker in sistemi di alimentazione in bassa tensione per apparecchiature con corrente nominale ≤ 16 A per fase e non soggette ad allacciamento su condizione

/Electromagnetic compatibility (EMC) - Part 3-3: Limits - Limitation of voltage changes, voltage fluctuations and flicker in public low-voltage supply systems, for equipment with rated current ≤ 16 A per phase and not subject to conditional connection.

CEI EN 61000-3-12:2012

Compatibilità elettromagnetica (EMC) Limiti per le correnti armoniche prodotte da apparecchiature collegate alla rete pubblica a bassa tensione aventi correnti di ingresso > 16 A e ≤ 75 A per fase

/ Electromagnetic compatibility (EMC) - Part 3-2: Limits - Limits for harmonic current emissions (equipment input current ≤ 16 A per phase)

IEC 61400-21 & IEC 61000-3-6 (Rate d > 75 A single-phase)

Parte 21: Misurazione e valutazione delle caratteristiche di qualità dell'energia delle turbine eoliche collegate alla rete IEC/TR 61000-3-6, Compatibilità elettromagnetica (EMC) – Parte 3-6: Limiti – Valutazione dei limiti di emissione per il collegamento di impianti di distorsione a sistemi di alimentazione MV, HV ed EHV

Part 21: Measurement and assessment of power quality characteristics of grid connected wind turbines IEC/TR 61000-3-6, Electromagnetic compatibility (EMC) – Part 3-6: Limits – Assessment of emission limits for the connection of distorting installations to MV, HV and EHV power systems

CEI EN 61000-3-11:2011

Compatibilità elettromagnetica (EMC) Limitazione delle variazioni di tensione, delle fluttuazioni di tensione e del flicker in sistemi di alimentazione pubblici a bassa tensione - Apparecchiature con correnti nominali < 75 A e soggetti ad allacciamento su condizione

/ Electromagnetic compatibility (EMC) - Part 3- 3: Limits - Limitation of voltage changes, voltage fluctuations and flicker in public low voltage supply systems, for equipment with rated current ≤ 16 A per phase and not subject to conditional connection

IEC 61400-21 & IEC 61000-3-6(I rated > 75A single-phase)

Parte 21: Misurazione e valutazione delle caratteristiche di qualità dell'energia delle turbine eoliche collegate alla rete IEC 61000-4-15, Compatibilità elettromagnetica (EMC) – Parte 4: Tecniche di prova e misurazione – Sezione 15: Flickermeter – Specifiche funzionali e di progettazione

Part 21: Measurement and assessment of power quality characteristics of grid connected wind turbines IEC 61000-4-15, Electromagnetic compatibility (EMC) – Part 4: Testing and measurement techniques – Section 15: Flickermeter – Functional and design specifications

CEI EN 60146-1-1:1997 + A1:1998

Convertitori a semiconduttori - Prescrizioni generali e convertitori commutati dalla linea Prove di isolamento (§ 4.2.1).

/ Semiconductor converters - General requirements and line commutated converters - Part 1-1: Specification of basic requirements Insulation tests (§. 4.2.1).



- Test item particulars..... :
- Equipment mobility : Stationary fixed
- Connection to the mains : Permanent connection
- Environmental category : outdoor
- Over voltage category Mains : OVC III
- Over voltage category PV : N/A
- Mains supply tolerance (%) : According to the specified supply range.
see model list on the following pages for details.
- Tested for power systems : TN, TT
- IT testing, phase-phase voltage (V) : N/A
- Class of equipment : Class I
- Pollution degree : PD 1 PD 2 (Inside) PD 3(Outside)

General product information:

DISPOSITIVO DI INTERFACCIA	PROTEZIONE DI INTERFACCIA	DISPOSITIVO DI CONVERSIONE STATICA	DISPOSITIVO DI GENERAZIONE ROTANTE
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Description of tested item:

Verified Sample:

Descrizione /Description:	Energy Storage System
Costruttore / Manufacturer:	EXPOFIN S.R.L. VIALE DELL'INDUSTRIA, N.19 – 35129 PADOVA (PD) – ITALY
Modello/ Model	SOLID POWER HV 261
Number of phases	3

Test Setup:






Figura 20 – Simulatore di rete BT

Block Diagram:



BESS



PCS

Test conditions:

Temperature: 25°C Relative humidity: 65%

Firmware version: DSP: 1.2.0.5

ARM: 1.9.1.7

EMU: V1.2



Copy of marking plate:

	
Product Name	Semi-Solid State Battery Energy Storage System Rechargeable Li-ion Battery System
Battery Designation	IFpP73r175/208j[(52S)5S]M/-30+50/95
Product Model	SOLID POWER HV 261
Nominal Voltage	832Vd.c
Rated Energy	261KWh
Rated Capacity	314Ah
Max. Charge Voltage	949Vd.c
Max. Charge Current	157A
Cut-off Discharge Voltage	650Vd.c
Max. Discharge Current	157A
Available SOC Range	10%~100%
Rate AC Voltage	400Va.c(3L+N)
Frequency	50/60Hz
Max. AC Current	180A
Aux Voltage	220Va.c 50/60Hz
Aux Rate Power	2.6KW
Ambient Temperature	-30℃ to +55℃
Dimensions (W*D*H)	1100*1400*2350mm
Weight	2440kg
Protection Class	I
Enclosure	IP55
Cooling Mode	Liquid-cooled
Working Altitude	≤3000m
Production Date	22-Sep.-2025
Series Number	 EB250055-00001
manufacturer	EXPOFIN S.R.L.

⚠ CAUTION

Please read user manual before operating the system

- * Prohibit to open the box unless authorized.
- * Do not over charge & over discharge.
- * One full charge needed per two months.
- * Recharge at derated current by the first time.
- * Recharge at derated current when system under voltage.
- * Do not disassemble the battery pack.
- * Do not short-circuit or reverse polarity.
- * Do not step on it, drop it and avoid the strong shock.
- * Do not use battery if it is damaged or deformed.
- * Do not expose to temperatures above 60℃.
- * Do not transport or store the battery with metallic items.

Emergency Situations

- * If leaking, fire, wet or damaged, switch off the breaker, go away from the battery.
- * Do not touch the leaking liquid, do not use water, but sand or drypowder extinguisher is usable.

Do not dispose of battery in trash, dispose of according to local regulations.






Made in China  

DATASHEET:




Note: The information of importer provided on product prior marketing.

The main features of the product are shown as below:

	Cell	Module
Product	Solid State Battery Cell	Solid State Battery
Type/model	EFS314	GTEFS-166V52.25K-M05P
Cell Capacity [Ah]	314	314
Cell Quantity	1	52
Battery structure	-	1P52S
Nominal voltage [V]	3.2	166.4
Rated capacity [Wh]	1004.8	52249.6
Upper limit charging voltage [V]	3.8	197.6
Recommend charging current [A]	157	157
Maximum charging current [A]	314	195
Recommend discharging current [A]	157	157
Maximum discharging current [A]	314	195
Discharge cut-off voltage [V]	2.5	130
Lower limit discharging voltage [V]	2.0	104
Temperature range for charging [°C]	0 to 55	-30 to 50
Temperature range for discharging [°C]	-30 to 60	-30 to 50
Temperature threshold for protection	-	53
Overcharge protected voltage supply by battery system	-	≥197.6V
Recommend charging method by manufacturer	Charging the cell with 157A constant current until to 3.65V, then constant voltage 3.65V until charging current reduces to 15A	At constant Power 26100W till cell voltage reaches 3.65 V.
Dimension [mm]	TxWxH: (71.95±0.5) x (174.8±0.5) x (207.1±0.5)	1152±3*800±3*238±3
Weight [kg]	5.63±0.2	340±5
Ingress Protection (IP)	-	IP67
Protective Class	-	I
Cooling type	-	Liquid cooling
Altitude [m]	-	≤3000
Notes:		



	Battery system
Product	Integrated Battery Energy Storage System
Type/model	SOLID POWER HV 261
Cell Capacity [Ah]	314
Cell Quantity	260
Battery structure	(1P52S)5S
Nominal voltage [V]	832
Rated capacity [Wh]	261248
Upper limit charging voltage [V]	936
Recommend charging current [A]	157
Maximum charging current [A]	195
Recommend discharging current [A]	157
Maximum discharging current [A]	195
End-of-charge voltage [V]	936
Discharge cut-off voltage [V]	728
Temperature range for charging [°C]	-30 to 50*
Temperature range for discharging [°C]	-30 to 50
Operating ambient temperature [°C]	-30 to 50
Temperature threshold for protection	53
Overcharge protected voltage supply by battery system	≥3.7V/cell
Recommend charging method by manufacturer	At constant Power 125kW till cell voltage reaches 3.65 V
Dimension [mm]	1100*1400*2350
Weight [kg]	2440
Ingress Protection (IP)	IP55
Protective Class	I
Cooling type	Liquid-cooled
Altitude[m]	≤3000
*Notes: When the cell temperature is less than 0°C, the battery system will stop working and the liquid cooling unit will start heating. It will start derating when ambient temperature is 0°C to 10°C and more than 45°C.	



MODELS LIST		INPPCS-125/0L4-W-14-A2-0S
DC Side	VMAX DC [Vdc]	1000
	Voltage Range V[Vdc]	600-1000
	Max. DC current [Ad.c.]	198
	Rated DC power [kW]	125
	Max. DC power [kW]	137.5
	Overtoltage Category (OVC)	II
AC Side	Rated Output Voltage Ur [Vac]	3L / N / PE, 230 / 400
	AC rated Input /Output active Power PE [kW]	125
	Rated Output Frequency FNETZ [Hz]	50/60±2.5
	Harmonic (THDi)	≤5% (at nominal Power)
	Max. AC Input/Output current [Aa.c.]	180
	AC voltage tolerance	-15%~+15%
	Adjustable reactive Power range	-100%~100%
	Power Factor cosφ [λ]	-0.99~+0.99, At nominal Power
	Overtoltage Category (OVC)	III
System	Max. efficiency	99%
	Protective Class	I
	Ingress Protection (IP)	IP20
	Operating Temperature Range [°C]	-30 to 50(>45 derating)
	Cooling Type	Air Cooling
	Pollution degree (PD)	3
	Altitude [m]	3000(>2,000 derating)
	Weight [kg]	70
Size [mm]	W520×H240×D680	



3. Energy Storage System

MODELS LIST		Integrated Battery Energy Storage System
DC side	VMAX DC[Vdc]	936
	Battery Nominal Voltage [Vd.c.]	832
	Rated capacity[Wh]	261248
	Max. Current I _{max} [A]	195
	Voltage Range [Vd.c.]	728 to 936
AC side	PCS Cabinet Model	INPPCS-125/0.4-W-14-A2-OS
	Rated H.V. voltage [kVa.c.]	400
	Rated H.V. current [A a.c.]	180
	Rated grid frequency [Hz]	50/60
	Max. Current [A a.c.]	198
	Rated AC power [kVA]	125
	Overvoltage Category (OVC)	III
Battery Energy Storage System	IP rating/ Enclosure index / type	IP55
	Protective Class	I
	Operating Temperature Range [°C]	-30 to 50 (>45 derating)
	Pollution degree (PD)	PD3(PD2 inside)
	Altitude [m]	≤3000 (>2000 derating)
	Weight [kg]	2440
	Size (W x D x H) [mm]	1100*1400*2350

Tests performed (name of test and test clause):
Allegato A: Caratteristiche e prove per il Sistema di Protezione di Interfaccia (SPI) Annex A: Requirements and test for Interface Protection System (SPI)

Sample 1: Hybrid inverter and battery are housed in a single cabinet, model name:
- Expofin Solid Power HV 261

A.4 Verifiche e prove sul SPI ¹ /test and inspection on SPI				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Prove funzionali sull'SPI <i>/Functional test on SPI</i>	A.4.3	Condizioni di riferimento / Reference conditions (20 °C) – Tab.9	N/A	N/A
	A.4.3.1	Caldo secco / Dry heat test	N/A	N/A
	A.4.3.2	CEI EN 60068-2-2 (Test B) - Tab.12	N/A	N/A
	A.4.7 (limit conditions)	Umidità / Humidity test CEI EN 60068-2-78 (Test Cab) - Tab.12	N/A	N/A
		Freddo / Cold test CEI EN 60068-2-1 (Test A) - Tab.12	N/A	N/A

A.4.3.3 Prescrizioni aggiuntive per le prove funzionali <i>/Additional requirements of the functional test</i>				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Insensibilità delle armoniche del relè di frequenza	A.4.3.3.1	CEI 0-21:2022-03	N/A	N/A
Segnale di telescatto	A.4.3.3.2	CEI 0-21:2022-03	N/A	N/A
Segnale di telecomunicazione	A.4.3.3.3	CEI 0-21:2022-03	N/A	N/A
Verifica di insensibilità alla derivata di frequenza (ROCOF)	A.4.3.4	CEI 0-21:2022-03	PASS	1
Autotest	A.4.4	CEI 0-21:2022-03	N/A	N/A
Single Fault tolerance	A.4.5	CEI 0-21:2022-03	PASS	1

A.4.6: Prove di compatibilità EMC				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample

¹ Interface protection System (SPI) can be integrated to inverter with output power up to 11.08KW.



Compatibilità elettromagnetica /Electromagnetic compatibility	A.4.6	CEI EN 60255-26 CEI EN 50263 (Severità classe 2 – Livello industriale) – Tab.11	PASS	1
---	--------------	---	------	---

Note 1) Please refer to EMC report no. CN25UYGT 001, issued by TÜV Rheinland (Shanghai) Co., Ltd.

(Remarks: This report is the original EMC report for model GTEFS-832V261KWh/125KW.)

A.4.7 Compatibilità Climatica / Climatic compatibility				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Compatibilità Climatica /Climatic compatibility Storage conditions	A.4.7 (limit conditions)	Caldo secco / Dry heat test CEI EN 60068-2-2 (Test B) - Tab.12	PASS	1
		Umidità / Humidity test CEI EN 60068-2-78 (Test Cab) - Tab.12	PASS	1
		Freddo / Cold test CEI EN 60068-2-1 (Test A) - Tab.12	PASS	1
		Ciclo termico /changing temperature CEI EN 60068-2-14 - Tab.12	PASS	1
Compatibilità Climatica /Climatic compatibility Inverter in working conditions	A.4.7 (limit conditions)	Caldo secco / Dry heat test CEI EN 60068-2-2 (Test B) - Tab.12	PASS	1
		Umidità / Humidity test CEI EN 60068-2-78 (Test Cab) - Tab.12	PASS	1
		Freddo / Cold test CEI EN 60068-2-1 (Test A) - Tab.12	PASS	1
		Ciclo termico /changing temperature CEI EN 60068-2-14 - Tab.12	PASS	1

A.4.8 Prove di isolamento /Insulating test				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Tenuta ad impulso /Pulse test	A.4.8	CEI EN 60255-27 Note ²	PASS	1
Rigidità Dielettrica /Dielectric Strength		CEI EN 60255-27 Note ¹	PASS	1
Resistenza di Isolamento /insulation resistance		CEI EN 60255-27 Note ¹	PASS	1

A.4.9 Prove di sovraccaricabilità dei circuiti di misura / Measurement circuits Overload				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample

² In case of integrated SPI, reference standard for insulating test is the CEI 60146-1-1.

Prove di sovraccaricabilità dei circuiti di misura <i>/ Measurement circuits Overload</i>	A.4.9	CEI 0-21:2022-03	N/A	N/A
			N/A	N/A
			N/A	N/A

Allegato B: Prove sugli inverter per impianti indirettamente connessi
Allegato B: Inverter tests for PV plants not directly connected to the grid

Note: The tested product has no PV ports, so this section (Allegato B) is not applicable.

B.1 Prove sull'inverter / inverter tests				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Armoniche di corrente <i>/ Harmonics measurement</i> (full power, 66% and 33% of max. power) <input type="checkbox"/> CEI EN 61000-3-2 <input type="checkbox"/> CEI EN 61000-3-12 <input checked="" type="checkbox"/> IEC 61400-21 & IEC 61000-3-6	B.1 Tab. 14 Tab. 15	Condizioni di riferimento / Reference conditions (20 °C) – Tab.14	N/A	N/A
		Caldo secco / Dry heat test CEI EN 60068-2-2 (Test B) - Tab.15	N/A	N/A
		Umidità / Humidity test CEI EN 60068-2-78 (Test Cab) - Tab.15	N/A	N/A
		Freddo / Cold test CEI EN 60068-2-1 (Test A) - Tab.15	N/A	N/A
Fluttuazioni di tensione <i>/ Flicker measurement</i> (full power, 66% and 33% of max. power) <input type="checkbox"/> CEI EN 61000-3-3 <input type="checkbox"/> CEI EN 61000-3-11 <input checked="" type="checkbox"/> IEC 61400-21 & IEC 61000-4-15	B.1 Tab. 14 Tab. 15	Condizioni di riferimento / Reference conditions (20 °C) – Tab.14	N/A	N/A
		Caldo secco / Dry heat test CEI EN 60068-2-2 (Test B) - Tab.15	N/A	N/A
		Umidità / Humidity test CEI EN 60068-2-78 (Test Cab) - Tab.15	N/A	N/A
		Freddo / Cold test CEI EN 60068-2-1 (Test A) - Tab.15	N/A	N/A

B.1.1 Condizioni di connessione, riconnessione ed erogazione graduale della potenza				
<i>Connection, re-connection conditions, and gradual increase of the power production</i>				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Verifica delle condizioni di connessione e riconnessione <i>/ Check of the connection and re-connection conditions</i>	8.4.1.3 B.1.1.1	CEI 0-21:2022-03	N/A	N/A
Verifica della erogazione graduale della potenza attiva <i>/ Check of the gradual increase of the power production</i>	8.4.1.3 B.1.1.2	CEI 0-21:2022-03	N/A	N/A

B.1.2 Erogazione della potenza reattiva /Reactive power production (or adsorbtion)				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Verifica dei requisiti costruttivi: capability erogazione della potenza reattiva <i>/ Check of the constructive requirements: reactive power production capability</i> <i>Not Applicable for plant with power <800W.</i>	8.4.4.2 B.1.2.1	CEI 0-21:2022-03	N/A	N/A
Erogazione di potenza reattiva secondo un livello assegnato <i>/ Reactive power production according to an assigned level</i> <i>Applicable for plant with power >11.08KW.</i>	B.1.2.3	CEI 0-21:2022-03	N/A	N/A
Tempo di risposta ad una variazione a gradino del livello assegnato <i>/Reaction time after a step variation of the assigned level.</i> <i>Applicable for plant with power >11.08KW.</i>	B.1.2.4	CEI 0-21:2022-03	N/A	N/A
Erogazione automatica di potenza reattiva secondo una curva caratteristica $\cos\phi=f(P)$ <i>/ Automatic reactive power production according to a characteristic curve $\cos(\phi)$</i>	B.1.2.5 <i>Annex E E.2</i>	CEI 0-21;V2:2024-01 CEI 0-21:2022-03	N/A	N/A
Erogazione automatica di potenza reattiva secondo una curva caratteristica $Q=f(V)$ <i>/ Automatic reactive power production according to a characteristic curve $Q=f(V)$</i> <i>Applicable for plant with power >11.08KW.</i>	B.1.2.6 <i>Annex E E.2.1</i>	CEI 0-21:2022-03	N/A	N/A

B.1.3 Limitazione della potenza attiva <i>/ Active power limitation</i>				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Limitazione della potenza attiva per valori di tensione prossimi al 110 % di Un <i>/ Active power limitation for voltage values near to 100 % di Un</i>	8.5.3.1 B.1.3.1 Annex F.3	CEI 0-21:2022-03	N/A	N/A
Regolazione della potenza attiva in presenza di transitori sulla rete di trasmissione <i>/ Active power regulation in coincidence with transitory on the transmission grid</i>	8.5.3.4 B.1.3.2 Annex F.3	CEI 0-21:2022-03	N/A	N/A
Verifica del campo di funzionamento in tensione e frequenza <i>/ Check the voltage and frequency operating range</i>	8.4.4 B.1.3.3	CEI 0-21:2022-03	N/A	N/A
Riduzione della potenza attiva in presenza di transitori di sottofrequenza sulla rete di trasmissione. <i>/ Active power reduction in coincidence with transitory on the transmission grid</i> <i>Not mandatory on static generator</i>	8.5.3.4 B.1.3.3.1	CEI 0-21:2022-03	N/A	N/A
Limitazione della potenza attiva su comando esterno proveniente dal Distributore <i>/ Active power limitation in coincidence with external command coming from the Electricity Distributor</i> <i>Not Applicable for plant with power <800W.</i>	8.5.3.3 B.1.3.4 Annex F.4	CEI 0-21:2022-03	N/A	N/A

B.1.4 Emissione di componente continua nella corrente di uscita <i>/ DC current injection on the output</i>				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Verifica della emissione di componente continua <i>/Check of DC current injection</i>	8.4.4.1 B.1.4.1	Condizioni di riferimento / Reference conditions (20 °C)	N/A	N/A
		Caldo secco / Dry heat test CEI EN 60068-2-2 (Test B)	N/A	N/A
		Umidità / Humidity test CEI EN 60068-2-78 (Test Cab)	N/A	N/A
		Freddo / Cold test CEI EN 60068-2-1 (Test A)	N/A	N/A
Verifica delle protezioni contro l'immissione di componente continua <i>/ Check of protections against the DC current injection.</i>	8.4.4.1 B.1.4.2	Condizioni di riferimento / Reference conditions (20 °C)	N/A	N/A
		Caldo secco / Dry heat test CEI EN 60068-2-2 (Test B)	N/A	N/A
		Umidità / Humidity test CEI EN 60068-2-78 (Test Cab)	N/A	N/A
		Freddo / Cold test CEI EN 60068-2-1 (Test A)	N/A	N/A

B.1.5 Verifica della insensibilità agli abbassamenti di tensione (LVFRT capability) <i>/ Check of the LVFRT capability</i>				
Test non accreditato Accredia / Test not Accredia accredited				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
LVFRT Capability <i>Applicable for plant with power >11.08KW.</i>	8.5.1 B.1.5	CEI 0-21:2022-03	N/A	N/A

B.1.6 Verifica della insensibilità alle richiuse automatiche in discordanza di fase <i>/ Check of the insensibility to the re-closures when phases are in discordance</i>				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Verifica della insensibilità alle richiuse automatiche in discordanza di fase <i>/ Check of the insensibility to the re-closures when phases are in discordance</i>	B.1.6 <input checked="" type="checkbox"/> B.1.6.1 <input type="checkbox"/> B.1.6.2 <input type="checkbox"/> B.1.6.3	CEI 0-21:2022-03	N/A	N/A

Allegato B: Prove di compatibilità EMC				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Compatibilità elettromagnetica <i>/Electromagnetic compatibility</i>	Annex B	CEI EN 61000-6-3 CEI EN 61000-6-2	N/A	N/A

Allegato L: Sistema di Limitazione dell'Immissione (SLI) <i>/ Annex L: System power limitation</i>				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Sistema di Limitazione dell'Immissione (SLI) <i>/System power limitation (<11.08kW)</i>	L.3	CEI 0-21;V2/EC2:2025-02	N/A	N/A

Allegato B bis: Prove sui sistemi di accumulo
/ Annex Bbis: Tests on Energy storage systems

Bbis.3 Prove sull'inverter / inverter tests

Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Scalarità e modularità: /Scalability and modularity <input type="checkbox"/> Case A <input checked="" type="checkbox"/> Case B <input type="checkbox"/> Case C <input type="checkbox"/> Case D Not Applicable for plant with power <800W.	Bbis.2.2	CEI 0-21:2022-03	PASS	1
Armoniche di corrente /Harmonics measurement (full power, 66% and 33% of $P_{S_{max}}$) (full power, 66% and 33% of $P_{C_{max}}$ only for bidirectional converters) <input type="checkbox"/> CEI EN 61000-3-2 <input type="checkbox"/> CEI EN 61000-3-12 <input checked="" type="checkbox"/> IEC 61400-21 & IEC 61000-3-6	Bbis.3 Tab. 2Bbis Tab. 3Bbis	Condizioni di riferimento / Reference conditions (20 °C) – Tab.2Bbis	PASS	1
		Caldo secco / Dry heat test CEI EN 60068-2-2 (Test B) - Tab.3Bbis	PASS	1
		Umidità / Humidity test CEI EN 60068-2-78 (Test Cab) - Tab.3Bbis	PASS	1
		Freddo / Cold test CEI EN 60068-2-1 (Test A) - Tab.3Bbis	PASS	1
Fluttuazioni di tensione /Flicker measurement (full power, 66% and 33% of $P_{S_{max}}$) (full power, 66% and 33% of $P_{C_{max}}$ only for bidirectional converters) <input type="checkbox"/> CEI EN 61000-3-3 <input type="checkbox"/> CEI EN 61000-3-11 <input checked="" type="checkbox"/> IEC 61400-21 & IEC 61000-4-15	Bbis.3 Tab. 2Bbis Tab. 3Bbis	Condizioni di riferimento / Reference conditions (20 °C) – Tab.2Bbis	PASS	1
		Caldo secco / Dry heat test CEI EN 60068-2-2 (Test B) - Tab.3Bbis	PASS	1
		Umidità / Humidity test CEI EN 60068-2-78 (Test Cab) - Tab.3Bbis	PASS	1
		Freddo / Cold test CEI EN 60068-2-1 (Test A) - Tab.3Bbis	PASS	1

Bbis.4 Verifica del campo di funzionamento in tensione e frequenza
Check the operating range in voltage and frequency

Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Verifica del campo di funzionamento /Check the operating range	Bbis.4	CEI 0-21:2022-03	PASS	1

Bbis.5 Condizioni di connessione, riconnessione ed erogazione graduale della potenza <i>Connection, re-connection conditions, and gradual increase of the power production</i>				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Verifica delle condizioni di connessione e riconnessione <i>/Check of the connection and re-connection conditions</i>	8.4.1.3 Bbis.5.1	CEI 0-21:2022-03	PASS	1
Verifica della erogazione graduale della potenza attiva <i>/Check of the gradual increase of the power production</i>	8.4.1.3 Bbis.5.2	CEI 0-21:2022-03	PASS	1

Bbis.6 Erogazione della potenza reattiva / Reactive power production (or adsorbtion)				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Verifica dei requisiti costruttivi: capability erogazione della potenza reattiva <i>/ Check of the constructive requirements: reactive power production capability</i>	Bbis.6.1	CEI 0-21:2022-03	PASS	1
Erogazione di potenza reattiva secondo un livello assegnato <i>/ Reactive power production according to an assigned level</i> <i>Applicable for plant with power >11.08KW.</i>	Bbis.6.3	CEI 0-21:2022-03	PASS	1
Tempo di risposta ad una variazione a gradino del livello assegnato <i>/Reaction time after a step variation of the assigned level.</i> <i>Applicable for plant with power >11.08KW.</i>	Bbis.6.5	CEI 0-21:2022-03	PASS	1
Erogazione automatica di potenza reattiva secondo una curva caratteristica $\cos\phi=f(P)$ <i>/ Automatic reactive power production according to a characteristic curve $\cos(\phi)$</i>	Bbis.6.6 Annex E E.2	CEI 0-21;V2:2024-01 CEI 0-21:2022-03	PASS	1
Erogazione automatica di potenza reattiva secondo una curva caratteristica $Q=f(V)$ <i>/ Automatic reactive power production according to a characteristic curve $Q=f(V)$</i> <i>Applicable for plant with power >11.08KW.</i>	Bbis.6.8 Annex E E.2.1	CEI 0-21:2022-03	PASS	1

Bbis.7 Limitazione della potenza attiva <i>/ Active power limitation</i>				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Limitazione della potenza attiva per valori di tensione prossimi al 110 % di Un <i>/ Active power limitation for voltage values near to 100 % di Un</i>	8.5.3.1 Bbis.7.1 Annex F.3	CEI 0-21:2022-03	PASS	1
Regolazione della potenza attiva in presenza di transitori di sovrافrequenza sulla rete di trasmissione <i>/ Active power regulation in coincidence with transitory on the transmission grid</i>	8.5.3.4 Bbis.7.2 Annex F.3	CEI 0-21:2022-03	PASS	1
Riduzione della potenza attiva in presenza di transitori di sottofrequenza sulla rete di trasmissione. <i>/ Active power regulation in coincidence with transitory on the transmission grid</i>	8.5.3.4 Bbis.7.3	CEI 0-21;V2/EC:2024-03; CEI 0-21:2022-03	PASS	1
Limitazione della potenza attiva su comando esterno proveniente dal Distributore <i>/ Active power limitation in coincidence with external command coming from the Electricity Distributor</i>	Bbis7.4	CEI 0-21:2022-03	PASS	1
Verifica del tempo di assestamento ad un comando di incremento/riduzione di potenza <i>/ Check settling time with command to increase/decrease of power</i>	Bbis7.4.1	CEI 0-21:2022-03	PASS	1

Bbis.8 Emissione di componente continua nella corrente di uscita <i>/ DC current injection on the output</i>				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Verifica della emissione di componente continua <i>/Check of DC current injection</i>	Bbis.8.1	Condizioni di riferimento / Reference conditions (20 °C)	PASS	1
		Caldo secco / Dry heat test CEI EN 60068-2-2 (Test B)	PASS	1
		Umidità / Humidity test CEI EN 60068-2-78 (Test Cab)	PASS	1
		Freddo / Cold test CEI EN 60068-2-1 (Test A)	PASS	1
Verifica delle protezioni contro l'immissione di componente continua <i>/ Check of protections against the DC current injection.</i>	Bbis.8.2	Condizioni di riferimento / Reference conditions (20 °C)	PASS	1
		Caldo secco / Dry heat test CEI EN 60068-2-2 (Test B)	PASS	1
		Umidità / Humidity test CEI EN 60068-2-78 (Test Cab)	PASS	1
		Freddo / Cold test CEI EN 60068-2-1 (Test A)	PASS	1

Bbis.9 Verifica della insensibilità agli abbassamenti di tensione (LVFRT capability) <i>/ Check of the LVFRT capability</i>				
Test non accreditato Accredia/Test not Accredia accredited				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
LVFRT Capability <i>Applicable for plant with power >11.08KW.</i>	8.5.1 Bbis.9	CEI 0-21:2022-03	PASS	1

Bbis.10 Verifica della insensibilità alle richiuse automatiche in discordanza di fase <i>/ Check of the insensibility to the re-closures when phases are in discordanza</i>				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Verifica della insensibilità alle richiuse automatiche in discordanza di fase <i>/ Check of the insensibility to the re-closures when phases are in discordanza</i>	Bbis.10 <input checked="" type="checkbox"/> Bbis.10.1 <input type="checkbox"/> Bbis.10.2 <input type="checkbox"/> Bbis.10.3	CEI 0-21:2022-03	PASS	1



Bbis.5.2.2 Funzionamento di porzioni di rete BT di distribuzione in isola intenzionale / Operation of portions of the LV distribution network in intentional islanding				
Test	Ref. CEI 0-21	Ref. standard	Result	Sample
Funzionamento di porzioni di rete BT di distribuzione in isola intenzionale <i>/ Operation of portions of the LV distribution network in intentional islanding</i>	Bbis.5.2.2	CEI 0-21; V1:2022-11	N/A	N/A


TESTING RESULTS

A.4.3.4	TABLE: Verifica di insensibilità alla derivata di frequenza (ROCOF) <i>/ Check of immunity at the frequency derived (ROCOF)</i>	P
Ambient temperature (°C)	20°C ± 2°C	
Humidity (RH %)	35% - 75% RH	
Instrumentation list	See table "Measurement equipment and instrumentation"	
Uncertainty	See table	

Grafico: Test verifica di insensibilità alla derivata di frequenza (ROCOF)

/ Graph: Check of immunity test at the frequency derived (ROCOF)

[81>S2] ROCOF – 51.50 Hz-47.5HZ



RESULT: The Inverter doesn't disconnects from the grid after ROCOF test



A.4.5	TABLE: Single Fault tolerance	P
Ambient temperature (°C)	20°C ± 2°C	
Humidity (RH %)	35% - 75% RH	
Instrumentation list.....	See table "Measurement equipment and instrumentation"	
Uncertainty	See table	

No.	component No.	fault	test voltage (V.d.c.)	test time	fuse No.	Input current (A)	Result
Cell voltage sampling of BMU							
1.	R118	O-C	832.0	10min	-	-	Cut off the main circuit contactor
2.	C110	S-C	832.0	10min	-	-	Cut off the main circuit contactor
3.	C122	S-C	832.0	10min	-	-	Cut off the main circuit contactor
Temperature voltage sampling of BMU							
4.	R123	O-C	832.0	10min	-	-	Cut off the main circuit contactor
5.	R100	O-C	832.0	10min	-	-	Cut off the main circuit contactor
6.	C165	S-C	832.0	10min	-	-	Cut off the main circuit contactor
Communication on BMU							
7.	UC1 PIN6&PIN7	S-C	832.0	10min	-	-	Cut off the main circuit contactor
8.	C25	S-C	832.0	10min	-	-	Cut off the main circuit contactor
Power Supply							
9.	C50	S-C	832.0	10min	-	-	Cut off the main circuit contactor
10.	C37	S-C	832.0	10min	-	-	Cut off the main circuit contactor
11.	C60	S-C	832.0	10min	-	-	Cut off the main circuit contactor

No.	component No.	fault	test voltage (Vd.c.)	test time	fuse No.	Input current (A)	Result
12.	C20	S-C	832.0	10min	-	-	Cut off the main circuit contactor
13.	R156	O-C	832.0	10min	-	-	Cut off the main circuit contactor
MCU							
14.	Y1	S-C	832.0	10min	-	-	Cut off the main circuit contactor
Power Supply of BCU							
15.	R192	O-C	832.0	10min	-	-	The main control MCU power supply is open circuit, unable to provide relay pull-in current, the main circuit relays are disconnected
16.	C14	S-C	832.0	10min	-	-	The main control MCU power supply short circuit, unable to provide relay pull-in current, the main circuit relays are disconnected
Communication of BCU							
17.	UN3 PIN6&PIN7	S-C	832.0	10min	-	-	The communication between the main control and EMS is interrupted, and main circuit relays are disconnected
18.	U2 PIN33&PIN34	S-C	832.0	10min	-	-	The total voltage is detected to be 0 compared with the monomer accumulation sum, and the difference is too large to disconnect the main circuit relays
Current sampling of BCU							
19.	RA5	O-C	832.0	10min	-	-	The charging current acquisition is abnormal, which triggers the high charging current protection and disconnects the main circuit relays
20.	R164	O-C	832.0	10min	-	-	HALL_5V power supply mining is abnormal, affecting the current sampling calculation value is too large, triggering the charging current too high protection, the main circuit relays is disconnected
MOS of BCU							

No.	component No.	fault	test voltage (Vd.c.)	test time	fuse No.	Input current (A)	Result
21.	QHL1	S-C, then simulate V/I/T fault	832.0	10min	-	-	QHL1 is short-circuited and the main positive relay remains closed to simulate the high voltage fault of the monomer, trigger the high voltage fault protection of the monomer and disconnect the main negative relay
22.	QHL2	S-C, then simulate V/I/T fault	832.0	10min	-	-	QHL2 is short-circuited and the main negative relay remains closed to simulate the charging current too high fault, triggering the charging current too high protection and the main positive relay disconnects
RELAY Ctrl of BCU							
23.	D20	O-C	832.0	10min	-	-	The relay pull-in current is interrupted, and main circuit relays is disconnected and cannot be closed
LOCK FUNCTION of BCU							
24.	V/I/T	simulate V/I/T fault	832.0	10min	-	-	The high voltage box is locked in the energy storage cabinet. When voltage, current and temperature faults occur, the fault alarm is locked and the user cannot open the energy storage cabinet and restart the high voltage box without permission
Liquid Cooling System							
25.	Liquid cooling unit water supply pump communication	O-C	832.0	10min	-	-	Liquid-cooled unit pump, compressor stop running, reported circulating water pump frequency converter communication failure
26.	Liquid-cooled unit outlet water pressure sensor	O-C	832.0	10min	-	-	Liquid-cooled unit pump can run normally, the compressor works, reported the outlet water pressure sensor, the equipment alarm

No.	component No.	fault	test voltage (Vd.c.)	test time	fuse No.	Input current (A)	Result
27.	Liquid-cooled unit outlet water temperature sensor	O-C	832.0	10min	-	-	Liquid-cooled unit pump can run normally, the compressor works, reported the water temperature sensor failure, equipment alarms
28.	Evaporative fan	O-C	832.0	10min	-	-	The pump of liquid cooling unit can run normally, the compressor is working, and the evaporator fan is reported to be faulty, and the equipment alarms.
Main circuits and Aux power							
29.	Exchange breaker	O-C	832.0	10min	-	-	Node alarm, system stops running
30.	System emergency	O-C	832.0	10min	-	-	Emergency stop disconnect, system failure shutdown.
31.	Direct-current breaker	O-C	832.0	10min	-	-	System failure shutdown, battery disconnected, liquid cooled unit running normally, report node failure
32.	AC Lightning Protector	S-C	832.0	10min	-	-	Node alarm, system stops running
33.	BMS Sampling Fault	S-C	832.0	10min	-	-	BMS communication failure and controls system failure shutdown, uploads rack BMS communication failure
34.	BMS and EMU communication	O-C	832.0	10min	-	-	EMU detects BMS communication failure and control system failure shutdown and reports BMS communication failure
35.	EMU and PCS communication	O-C	832.0	10min	-	-	EMU detects PCS unit failure and control system failure shutdown
Fire Protection							
36.	Fire system primary alarm (smoke alarm)	O-C	832.0	10min	-	-	EMU alarm, fire fighting fan starts, control system stops running, report node fault.

No.	component No.	fault	test voltage (Vd.c.)	test time	fuse No.	Input current (A)	Result
37.	Fire system secondary alarm (smoke sensor alarm, temperature sensor alarm)	O-C	832.0	10min	-	-	EMU alarm, fire fighting fan starts, control system stops running, report node fault.
38.	Combustible gas concentration over limit	O-C	832.0	10min	-	-	EMU alarm, fire fighting fan starts, control system stops running, report node fault.
39.	Fire fighting gas release	O-C	832.0	10min	-	-	EMU alarm, control system stops running, report node fault.
40.	Fire-fighting fan communication	O-C	832.0	10min	-	-	EMU alarm, control system stops running, report fire fan fault signal.

Note(s):

1: Failures or faults may be short-circuits in the PCS, or to exposed conductive parts, earth faults, or short-circuit in the output circuits, failure in the control circuits, or blocking of a motor fed by power EE.

There shall be no emission of molten metal, burning insulation, or flaming or glowing particles from the fire enclosure, and there shall be no charring, glowing, or flaming of the tissue paper or cheesecloth, or glowing or flaming of surgical cotton.

Faults protected by "UL certified current fuse only" shall be performed and repeated 3 times.

In case of components damaged other than fuse, the evaluation should be repeated 3 times.

Report in result section:


- Measure transformer temperature at all times
- Fuse opened Yes / No?
- Components damaged?
- Emit Flames?
- Emit molten metal?
- Did it pass the electric strength test?

What happened to the SPS? Shutdown / cycle protection / normal operation

Compatibilità Climatica / Climatic compatibility


A.4.7	TABLE : Dry heat (Test B) – storage conditions.	P
CEI EN 60068-2-2:2008-11		
Prove ambientali - Parte 2-2: Prove - Prova B: Caldo secco		
/Environmental testing - Part 2-2: Tests - Test B: Dry heat		
Condizioni di test /Test conditions	dissipa calore /heat -dissipating	
Tipo di campione /Specimen type	Bb: graduale / gradual	
Tipo di ventilazione /Air circulation	forzata / forced air	
Temperatura misurata /Measured temperature:	70 °C	
Duration:	16 h	
Precondizionamento /Preconditioning		
--		
Verifiche iniziali /Initial measurement		
Verifica della corretta funzionalità del dispositivo / verification of correct device functionality		
Verifica del corretto funzionamento della protezione di interfaccia / verification of correct interface protection		
Verifiche finali /Final measurement		
Dopo il ciclo termico / after thermal cycle		
Verifica della corretta funzionalità del dispositivo / verification of correct device functionality		
Verifica del corretto funzionamento della protezione di interfaccia / verification of correct interface protection		
Condizioni particolari di prova /Particular test condition		
Apparato non operativo (non alimentato) / device not operative (not powered)		

Image: Dry heat (Test B) – storage conditions.




A.4.7	TABLE : Humidity test (Test Cab) - storage conditions.	P
CEI EN 60068-2-78:2002:03 Prove ambientali - Parte 2-78: Prove - Prova Cab: Caldo umido, regime stazionario /Environmental testing - Part 2-78: Tests - Test Cab: Damp heat, steady state		
Temperatura misurata /Measured temperature:	40 °C	
Umidità misurata /measured humidity:	93 RH%	
Duration:	96 h	
Instrumentation list	See table "Measurement equipment and instrumentation"	
Uncertainty	See table	
Precondizionamento /Preconditioning		
-		
Verifiche iniziali /Initial measurement		
Verifica della corretta funzionalità del dispositivo / verification of correct device functionality		
Verifica del corretto funzionamento della protezione di interfaccia / verification of correct interface protection		
Verifiche finali /Final measurement		
Dopo il ciclo termico / after thermal cycle		
Verifica della corretta funzionalità del dispositivo / verification of correct device functionality		
Verifica del corretto funzionamento della protezione di interfaccia / verification of correct interface protection		
Condizioni particolari di prova /Particular test condition		
Apparato non operativo (non alimentato) / device not operative (not powered)		
Supplementary information:		
After the conditions, the inverter still work without any problem.		

Image: Humidity test (Test Cab) - storage conditions.




A.4.7	TABLE : Cold test (Test A) – storage conditions.	P
CEI EN 60068-2-1:2007:11 Prove ambientali - Parte 2-1: Prove - Prova A: Freddo <i>/Environmental testing - Part 2-1: Tests - Test A: Cold</i>		
Condizioni di test <i>/Test conditions</i>	dissipa calore <i>/heat -dissipating</i>	
Tipo di campione <i>/Specimen type</i>	Bb: graduale <i>/ gradual</i>	
Tipo di raffreddamento del campione <i>/Specimen cooling type</i>	senza raffreddamento artificiale <i>/without artificial cooling</i>	
Tipo di ventilazione <i>/Air circulation</i>	forzata <i>/ forced air</i>	
Temperatura misurata <i>/Measured temperature:</i>	-10 °C	
Duration:	16 h	
Instrumentation list:	See table "Measurement equipment and instrumentation"	
Uncertainty:	See table	
Precondizionamento <i>/Preconditioning</i> -		
Verifiche iniziali <i>/Initial measurement</i> Verifica della corretta funzionalità del dispositivo <i>/ verification of correct device functionality</i> Verifica del corretto funzionamento della protezione di interfaccia <i>/ verification of correct interface protection</i>		
Verifiche finali <i>/Final measurement</i> Dopo il ciclo termico <i>/ after thermal cycle</i> Verifica della corretta funzionalità del dispositivo <i>/ verification of correct device functionality</i> Verifica del corretto funzionamento della protezione di interfaccia <i>/ verification of correct interface protection</i>		
Condizioni particolari di prova <i>/Particular test condition</i> Apparato non operativo (non alimentato) <i>/ device not operative (not powered)</i>		
Supplementary information: After the conditions, the inverter still work without any problem.		

Image: Cold test (Test A) – storage conditions




A.4.7	TABLE : Change of temperature (Test N) – storage conditions.	P
CEI EN 60068-2-14:2010 Prove ambientali - Parte 2-14: Prove - Prova N: Cambio di temperatura <i>/Environmental testing - Part 2-14: Tests - Test N: Change of temperature</i>		
Prova/Test	NB: Cambio a velocità controllata <i>/NB Change with specified rate of change</i>	
Tipo di ventilazione <i>/Air circulation</i>	forzata / forced air	
N° cicli <i>/Number of cycle:</i>	1	
Temperatura minima T_A <i>/Minimum temperature T_A:</i>	$- 10 \pm 2^\circ\text{C}$	
Temperatura massima T_B <i>/Maximum temperature T_B :</i>	$+70 \pm 2^\circ\text{C}$	
Durata di esposizione t_1 <i>/Exposure time t_1:</i>	3 h	
Tempo di trasferimento t_2 <i>/Transition time t_2:</i>	3 h	
Instrumentation list:	See table "Measurement equipment and instrumentation"	
Uncertainty:	See table	
Precondizionamento <i>/Preconditioning</i> -		
Verifiche iniziali <i>/Initial measurement</i> Verifica della corretta funzionalità del dispositivo <i>/ verification of correct device functionality</i> Verifica del corretto funzionamento della protezione di interfaccia <i>/ verification of correct interface protection</i>		
Verifiche finali <i>/Final measurement</i> Dopo il ciclo termico <i>/ after thermal cycle</i> Verifica della corretta funzionalità del dispositivo <i>/ verification of correct device functionality</i> Verifica del corretto funzionamento della protezione di interfaccia <i>/ verification of correct interface protection</i>		
Condizioni particolari di prova <i>/Particular test condition</i> Apparato non operativo (non alimentato) <i>/ device not operative (not powered)</i>		
Supplementary information: After the conditions, the inverter still work without any problem.		

Image: Change of temperature (Test N) – storage conditions.




A.4.7	TABLE : Dry heat (Test B) – working conditions.	P
CEI EN 60068-2-2:2008-11 Prove ambientali - Parte 2-2: Prove - Prova B: Caldo secco <i>/Environmental testing - Part 2-2: Tests - Test B: Dry heat</i>		
Condizioni di test <i>/Test conditions</i>	dissipa calore <i>/heat -dissipating</i>	
Tipo di campione <i>/Specimen type</i>	Bb: graduale <i>/ gradual</i>	
Tipo di ventilazione <i>/Air circulation</i>	forzata <i>/ forced air</i>	
Temperatura misurata <i>/Measured temperature:</i>	55 °C	
Duration:	16 h	
Precondizionamento <i>/Preconditioning</i> --		
Verifiche iniziali <i>/Initial measurement</i> Verifica della corretta funzionalità del dispositivo <i>/ verification of correct device functionality</i> Verifica del corretto funzionamento della protezione di interfaccia <i>/ verification of correct interface protection</i>		
Verifiche finali <i>/Final measurement</i> Dopo il ciclo termico <i>/ after thermal cycle</i> Verifica della corretta funzionalità del dispositivo <i>/ verification of correct device functionality</i> Verifica del corretto funzionamento della protezione di interfaccia <i>/ verification of correct interface protection</i>		
Condizioni particolari di prova <i>/Particular test condition</i> Apparato non operativo (non alimentato) <i>/ device not operative (not powered)</i>		
Supplementary information: After the conditions, the inverter still work without any problem.		

Image: Dry heat (Test B) – working conditions.




A.4.7	TABLE : Humidity test (Test Cab) - working conditions.	P
<p>CEI EN 60068-2-78:2002:03 Prove ambientali - Parte 2-78: Prove - Prova Cab: Caldo umido, regime stazionario /Environmental testing - Part 2-78: Tests - Test Cab: Damp heat, steady state</p>		
Temperatura misurata /Measured temperature:		40 °C
Umidità misurata /measured humidity:		93 RH%
Duration:		96 h
Instrumentation list		See table "Measurement equipment and instrumentation"
Uncertainty		See table
Precondizionamento /Preconditioning -		
<p>Verifiche iniziali /Initial measurement Verifica della corretta funzionalità del dispositivo / verification of correct device functionality Verifica del corretto funzionamento della protezione di interfaccia / verification of correct interface protection</p>		
<p>Verifiche finali /Final measurement Dopo il ciclo termico / after thermal cycle Verifica della corretta funzionalità del dispositivo / verification of correct device functionality Verifica del corretto funzionamento della protezione di interfaccia / verification of correct interface protection</p>		
<p>Condizioni particolari di prova /Particular test condition Apparato non operativo (non alimentato) / device not operative (not powered)</p>		
<p>Supplementary information: After the conditions, the inverter still work without any problem.</p>		

Image: Humidity test (Test Cab) - working conditions.




A.4.7	TABLE : Cold test (Test A) – working conditions.	P
<p>CEI EN 60068-2-1:2007:11 Prove ambientali - Parte 2-1: Prove - Prova A: Freddo <i>/Environmental testing - Part 2-1: Tests - Test A: Cold</i></p>		
Condizioni di test <i>/Test conditions</i>		dissipa calore <i>/heat -dissipating</i>
Tipo di campione <i>/Specimen type</i>		Bb: graduale <i>/ gradual</i>
Tipo di raffreddamento del campione <i>/Specimen cooling type</i>		senza raffreddamento artificiale <i>/without artificial cooling</i>
Tipo di ventilazione <i>/Air circulation</i>		forzata <i>/ forced air</i>
Temperatura misurata <i>/Measured temperature:</i>		-10 °C
Duration:		16 h
Instrumentation list:		See table "Measurement equipment and instrumentation"
Uncertainty:		See table
Precondizionamento <i>/Preconditioning</i> -		
<p>Verifiche iniziali <i>/Initial measurement</i> Verifica della corretta funzionalità del dispositivo <i>/ verification of correct device functionality</i> Verifica del corretto funzionamento della protezione di interfaccia <i>/ verification of correct interface protection</i></p>		
<p>Verifiche finali <i>/Final measurement</i> Dopo il ciclo termico <i>/ after thermal cycle</i> Verifica della corretta funzionalità del dispositivo <i>/ verification of correct device functionality</i> Verifica del corretto funzionamento della protezione di interfaccia <i>/ verification of correct interface protection</i></p>		
<p>Condizioni particolari di prova <i>/Particular test condition</i> Apparato non operativo (non alimentato) <i>/ device not operative (not powered)</i></p>		
<p>Supplementary information: After the conditions, the inverter still work without any problem.</p>		

Image: Cold test (Test A) – working conditions



A.4.7	TABLE : Change of temperature (Test N) – working conditions.	P
CEI EN 60068-2-14:2010 Prove ambientali - Parte 2-14: Prove - Prova N: Cambio di temperatura <i>/Environmental testing - Part 2-14: Tests - Test N: Change of temperature</i>		
Prova/Test	NB: Cambio a velocità controllata <i>/NB Change with specified rate of change</i>	
Tipo di ventilazione <i>/Air circulation</i>	forzata / forced air	
N° cicli <i>/Number of cycle:</i>	1	
Temperatura minima T_A <i>/Minimum temperature T_A:</i>	$- 10 \pm 2 \text{ }^\circ\text{C}$	
Temperatura massima T_B <i>/Maximum temperature T_B :</i>	$+55 \pm 2 \text{ }^\circ\text{C}$	
Durata di esposizione t_1 <i>/Exposure time t_1:</i>	3 h	
Tempo di trasferimento t_2 <i>/Transition time t_2:</i>	3 h	
Instrumentation list:	See table "Measurement equipment and instrumentation"	
Uncertainty:	See table	
Precondizionamento <i>/Preconditioning</i> -		
Verifiche iniziali <i>/Initial measurement</i> Verifica della corretta funzionalità del dispositivo <i>/ verification of correct device functionality</i> Verifica del corretto funzionamento della protezione di interfaccia <i>/ verification of correct interface protection</i>		
Verifiche finali <i>/Final measurement</i> Dopo il ciclo termico <i>/ after thermal cycle</i> Verifica della corretta funzionalità del dispositivo <i>/ verification of correct device functionality</i> Verifica del corretto funzionamento della protezione di interfaccia <i>/ verification of correct interface protection</i>		
Condizioni particolari di prova <i>/Particular test condition</i> Apparato non operativo (non alimentato) <i>/ device not operative (not powered)</i>		
Supplementary information: After the conditions, the inverter still work without any problem.		

Image: Change of temperature (Test N) – working conditions.





A.4.8 TABLE: Insulation tests		P	
<input type="checkbox"/> CEI EN 60255-27:2023 Parte 27: requisiti di sicurezza dei prodotti <i>/Electrical Relays - Part 27: Product safety requirements</i>			
<input checked="" type="checkbox"/> CEI EN 60146-1-1:1997 + A1:1998 Convertitori a semiconduttori - Prescrizioni generali e convertitori commutati dalla linea Prove di isolamento (§ 4.2.1). <i>/ Semiconductor converters - General requirements and line commutated converters - Part 1-1: Specification of basic requirements</i> <i>Insulation tests (§. 4.2.1).</i>			
Ambient temperature (°C)		20°C ± 2°C	
Humidity (RH %)		35% - 75% RH	
Instrumentation list.....		See table "Measurement equipment and instrumentation"	
Uncertainty		See table	
Resistenza di isolamento /Insulation Resistance			
Test	Test Voltage (V)	R measured	Limit
Between PE and AC output shorted	500 Vdc	>50G	≥1MΩ
Between PE and DC input shorted	500 Vdc	>50G	≥1MΩ
Between PE and DC + AC shorted	500 Vdc	>50G	≥1MΩ
Prova di rigidità dielettrica/ Dielectric strenght test			
Test	Test Voltage (V)	R Measured after test MΩ @ 500Vdc	Comments
Between PE and AC output shorted	2120 Vdc	>50G	No discharge.
Between PE and DC + AC shorted	2120 Vdc	>50G	No discharge.
Supplementary information: Tested on 2025030005-001(model : GTEFS-832V261KWh/125KW).			



TESTING RESULTS

Allegato B bis: Prove sui sistemi di accumulo
/ Annex B bis: Tests on Energy Storage Systems

Terminologia e definizioni degli EESS in accordo al par. 8.5.3.4
/ Terminology and definitions for EESS systems in according to clause 8.5.3.4 :

CUS:	Capacity of the storage system	125000W
PSN:	Power from Battery to the Grid	125000W
PCN:	Power from the Grid to the Battery	125000W
PS_{MAX}:	Power from Battery to the Grid within the CUS – (range of 10% - 90%)	125000W
PC_{MAX}:	Power from Grid to the Battery within the CUS – (range of 10% - 90%)	125000W
PN_{INV}:	Rated Power from the Inverter	125000W

Operation Condition
$PS_{MAX} \geq PSN$
$PC_{MAX} \geq PCN$
$PS_{MAX} \leq PN_{INV}$
$PC_{MAX} \leq PN_{INV}$

Bbis.2.2: TABLE: Scalarità e modularità <i>/Table: Scalarity and modularity</i>	
Ambient temperature (°C)	N/A
Humidity (RH %)	N/A
Instrumentation list.....	N/A
Uncertainty	N/A
<input type="checkbox"/> Caso A	<p>SOTTOSISTEMA DI CONVERSIONE: P₁, P₂, ..., P_N SOTTOSISTEMA DI ACCUMULO: C₁, C₂, ..., C_M</p>
<input checked="" type="checkbox"/> Caso B	<p>SOTTOSISTEMA DI CONVERSIONE: P₁, P₂, ..., P_N SOTTOSISTEMA DI ACCUMULO: 1 x C, 2 x C, ..., M x C</p>
<input type="checkbox"/> Caso C	<p>SOTTOSISTEMA DI CONVERSIONE: 1 x P, 2 x P, ..., N x P SOTTOSISTEMA DI ACCUMULO: C₁, C₂, ..., C_M</p>
<input type="checkbox"/> Caso D	<p>SOTTOSISTEMA DI CONVERSIONE: 1 x P, 2 x P, ..., N x P SOTTOSISTEMA DI ACCUMULO: 1 x C, 2 x C, ..., M x C</p>

Configurazione di Energy Storage System / Energy Storage system configuration

Inverter:

P_{MIN}		P_{MAX}	
P_1 :	125kW	P_N :	125kW
$N_{module\ min}$:	--	$N_{module\ max}$:	--

Storage:

E_{MIN}		E_{MAX}	
C_1 :	261kWh	C_M :	261kWh
$M_{module\ min}$:	--	$M_{module\ max}$:	--

Tabella di prove per EESS: / Table of tests for EESS

Caso A	Potenza sottosistema di conversione (W)		
	$P_1 (P_{MIN})$...	$P_N (P_{MAX})$
Capacità sottosistema di accumulo (Wh) $C_1 (E_{MIN})$	Prove parziali Allegato Bbis	non sono richieste ulteriori prove	Prove parziali Allegato Bbis
...	non sono richieste ulteriori prove	non sono richieste ulteriori prove	non sono richieste ulteriori prove
$C_M (E_{MAX})$	non sono richieste ulteriori prove	non sono richieste ulteriori prove	Prove complete Allegato Bbis

Caso C	Potenza sottosistema di conversione (W)			
	modulo base P (P_{MIN})	2 moduli	≥ 3 moduli	N moduli (P_{MAX})
Capacità sottosistema di accumulo (Wh) $C_1 (E_{MIN})$	Prove parziali Allegato Bbis	non sono richieste ulteriori prove	Prove parziali Allegato Bbis in una qualunque delle configurazioni con (almeno) 3 moduli del sottosistema di conversione	non sono richieste ulteriori prove
...	non sono richieste ulteriori prove	non sono richieste ulteriori prove		non sono richieste ulteriori prove
$C_M (E_{MAX})$	Prove complete Allegato Bbis	non sono richieste ulteriori prove		non sono richieste ulteriori prove

Caso B	Potenza sottosistema di conversione (W)		
	$P_1 (P_{MIN})$...	$P_N (P_{MAX})$
Capacità sottosistema di accumulo (Wh) modulo base C (E_{MIN})	Prove parziali Allegato Bbis	non sono richieste ulteriori prove	Prove parziali Allegato Bbis
...	non sono richieste ulteriori prove	non sono richieste ulteriori prove	non sono richieste ulteriori prove
M moduli (E_{MAX})	non sono richieste ulteriori prove	non sono richieste ulteriori prove	Prove complete Allegato Bbis

Caso D	Potenza sottosistema di conversione (W)			
	modulo base P (P_{MIN})	2 moduli	≥ 3 moduli	N moduli (P_{MAX})
Capacità sottosistema di accumulo (Wh) modulo base C (E_{MIN})	Prove parziali Allegato Bbis	non sono richieste ulteriori prove	Prove parziali Allegato Bbis in una qualunque delle configurazioni con 3 moduli del sottosistema di conversione	non sono richieste ulteriori prove
...	non sono richieste ulteriori prove	non sono richieste ulteriori prove		non sono richieste ulteriori prove
M moduli (E_{MAX})	Prove complete Allegato Bbis	non sono richieste ulteriori prove		non sono richieste ulteriori prove



Bbis.3: TABLE: Armoniche di corrente /Harmonics measurement

(full power, 66% and 33% of $P_{s_{max}}$)

- CEI EN 61000-3-2 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-12 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-3-6 ($I_{rated} > 75A$ single-phase)

Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 10% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Supplementary information:	
Operator	See cover page
Supervisor	See cover page
Test Date.....	See cover page

Harmonics current measured on L1 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	60.865	33.590	121.277	66.930	181.746	100.301	--	P
2	0.399	0.220	0.390	0.215	0.473	0.261	--	P
3	0.606	0.335	1.212	0.669	1.628	0.898	--	P
4	0.136	0.075	0.153	0.084	0.222	0.122	--	P
5	1.360	0.751	1.360	0.750	1.300	0.717	--	P
6	0.205	0.113	0.345	0.190	0.448	0.247	--	P
7	0.271	0.150	0.584	0.322	0.887	0.489	--	P
8	0.038	0.021	0.069	0.038	0.089	0.049	--	P
9	0.382	0.211	0.248	0.137	0.089	0.049	--	P
10	0.027	0.015	0.072	0.040	0.059	0.032	--	P
11	0.264	0.146	0.597	0.329	0.611	0.337	--	P
12	0.087	0.048	0.036	0.020	0.077	0.043	--	P
13	0.139	0.077	0.292	0.161	0.433	0.239	--	P
14	0.024	0.013	0.068	0.037	0.069	0.038	--	P
15	0.044	0.024	0.322	0.177	0.276	0.152	--	P
16	0.029	0.016	0.038	0.021	0.051	0.028	--	P
17	0.262	0.144	0.329	0.181	0.311	0.172	--	P
18	0.105	0.058	0.088	0.048	0.064	0.035	--	P
19	0.124	0.068	0.568	0.314	0.402	0.222	--	P
20	0.065	0.036	0.061	0.034	0.050	0.027	--	P
21	0.030	0.016	0.100	0.055	0.152	0.084	--	P
22	0.030	0.017	0.039	0.022	0.045	0.025	--	P
23	0.170	0.094	0.274	0.151	0.398	0.220	--	P
24	0.030	0.017	0.044	0.024	0.063	0.035	--	P
25	0.167	0.092	0.424	0.234	0.679	0.375	--	P
26	0.092	0.051	0.014	0.008	0.016	0.009	--	P
27	0.083	0.046	0.122	0.067	0.160	0.088	--	P
28	0.086	0.048	0.030	0.016	0.054	0.030	--	P
29	0.246	0.136	0.160	0.088	0.381	0.210	--	P
30	0.026	0.014	0.053	0.029	0.049	0.027	--	P
31	0.171	0.095	0.189	0.104	0.498	0.275	--	P
32	0.041	0.023	0.073	0.040	0.023	0.013	--	P
33	0.053	0.029	0.029	0.016	0.185	0.102	--	P
34	0.049	0.027	0.042	0.023	0.059	0.033	--	P
35	0.261	0.144	0.076	0.042	0.408	0.225	--	P
36	0.086	0.047	0.095	0.053	0.044	0.025	--	P
37	0.166	0.092	0.400	0.221	0.330	0.182	--	P
38	0.074	0.041	0.093	0.051	0.017	0.009	--	P
39	0.015	0.008	0.072	0.040	0.064	0.035	--	P
40	0.043	0.024	0.079	0.044	0.031	0.017	--	P

Harmonics current measured on L2 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	58.620	32.351	116.305	64.186	177.201	97.793	--	P
2	0.421	0.232	0.421	0.232	0.356	0.196	--	P
3	0.538	0.297	1.057	0.583	1.231	0.680	--	P
4	0.266	0.147	0.317	0.175	0.446	0.246	--	P
5	0.918	0.507	1.078	0.595	1.291	0.712	--	P
6	0.071	0.039	0.069	0.038	0.041	0.023	--	P
7	0.308	0.170	0.413	0.228	0.584	0.322	--	P
8	0.058	0.032	0.088	0.048	0.083	0.046	--	P
9	0.173	0.096	0.126	0.070	0.118	0.065	--	P
10	0.070	0.039	0.096	0.053	0.153	0.084	--	P
11	0.237	0.131	0.309	0.170	0.281	0.155	--	P
12	0.064	0.036	0.015	0.008	0.047	0.026	--	P
13	0.086	0.047	0.161	0.089	0.308	0.170	--	P
14	0.021	0.012	0.038	0.021	0.047	0.026	--	P
15	0.094	0.052	0.223	0.123	0.225	0.124	--	P
16	0.034	0.019	0.051	0.028	0.028	0.015	--	P
17	0.250	0.138	0.207	0.114	0.164	0.091	--	P
18	0.097	0.053	0.038	0.021	0.029	0.016	--	P
19	0.105	0.058	0.395	0.218	0.283	0.156	--	P
20	0.030	0.016	0.070	0.039	0.045	0.025	--	P
21	0.027	0.015	0.047	0.026	0.140	0.077	--	P
22	0.030	0.017	0.048	0.027	0.022	0.012	--	P
23	0.170	0.094	0.253	0.139	0.267	0.148	--	P
24	0.063	0.035	0.042	0.023	0.038	0.021	--	P
25	0.117	0.064	0.351	0.194	0.538	0.297	--	P
26	0.061	0.034	0.015	0.008	0.042	0.023	--	P
27	0.078	0.043	0.078	0.043	0.078	0.043	--	P
28	0.062	0.034	0.018	0.010	0.057	0.031	--	P
29	0.253	0.140	0.205	0.113	0.443	0.244	--	P
30	0.058	0.032	0.019	0.011	0.042	0.023	--	P
31	0.194	0.107	0.194	0.107	0.400	0.221	--	P
32	0.034	0.019	0.058	0.032	0.023	0.013	--	P
33	0.119	0.066	0.038	0.021	0.068	0.038	--	P
34	0.067	0.037	0.067	0.037	0.078	0.043	--	P
35	0.269	0.149	0.123	0.068	0.504	0.278	--	P
36	0.104	0.057	0.058	0.032	0.035	0.019	--	P
37	0.180	0.099	0.353	0.195	0.276	0.152	--	P
38	0.059	0.033	0.089	0.049	0.017	0.009	--	P
39	0.054	0.030	0.056	0.031	0.072	0.040	--	P
40	0.025	0.014	0.086	0.048	0.030	0.017	--	P

Harmonics current measured on L3 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	61.129	33.735	121.572	67.093	182.104	100.499	--	P
2	0.933	0.515	1.108	0.611	1.266	0.699	--	P
3	1.095	0.605	1.641	0.905	1.913	1.056	--	P
4	0.290	0.160	0.475	0.262	0.659	0.364	--	P
5	1.225	0.676	1.328	0.733	1.386	0.765	--	P
6	0.023	0.013	0.058	0.032	0.070	0.039	--	P
7	0.252	0.139	0.414	0.228	0.549	0.303	--	P
8	0.182	0.100	0.094	0.052	0.055	0.031	--	P
9	0.341	0.188	0.223	0.123	0.202	0.111	--	P
10	0.098	0.054	0.105	0.058	0.136	0.075	--	P
11	0.195	0.107	0.435	0.240	0.419	0.231	--	P
12	0.057	0.032	0.027	0.015	0.065	0.036	--	P
13	0.142	0.078	0.243	0.134	0.402	0.222	--	P
14	0.048	0.026	0.139	0.077	0.095	0.052	--	P
15	0.039	0.022	0.389	0.215	0.350	0.193	--	P
16	0.085	0.047	0.052	0.029	0.077	0.043	--	P
17	0.352	0.194	0.247	0.136	0.157	0.087	--	P
18	0.041	0.023	0.025	0.014	0.023	0.013	--	P
19	0.128	0.070	0.468	0.258	0.353	0.195	--	P
20	0.070	0.038	0.061	0.034	0.053	0.029	--	P
21	0.073	0.040	0.090	0.050	0.155	0.085	--	P
22	0.062	0.034	0.035	0.019	0.027	0.015	--	P
23	0.193	0.107	0.261	0.144	0.336	0.185	--	P
24	0.040	0.022	0.054	0.030	0.069	0.038	--	P
25	0.161	0.089	0.370	0.204	0.613	0.339	--	P
26	0.045	0.025	0.043	0.024	0.067	0.037	--	P
27	0.032	0.018	0.101	0.056	0.027	0.015	--	P
28	0.060	0.033	0.018	0.010	0.041	0.023	--	P
29	0.229	0.126	0.174	0.096	0.429	0.237	--	P
30	0.050	0.027	0.032	0.018	0.060	0.033	--	P
31	0.185	0.102	0.190	0.105	0.415	0.229	--	P
32	0.038	0.021	0.076	0.042	0.051	0.028	--	P
33	0.059	0.033	0.102	0.056	0.050	0.028	--	P
34	0.044	0.024	0.026	0.015	0.067	0.037	--	P
35	0.273	0.151	0.117	0.065	0.455	0.251	--	P
36	0.141	0.078	0.105	0.058	0.043	0.024	--	P
37	0.211	0.117	0.392	0.216	0.236	0.130	--	P
38	0.021	0.011	0.081	0.045	0.021	0.012	--	P
39	0.084	0.046	0.091	0.050	0.065	0.036	--	P
40	0.096	0.053	0.035	0.019	0.054	0.030	--	P



Bbis.3: TABLE: Armoniche di corrente /Harmonics measurement (full power, 66% and 33% of PC_{max})	
<input type="checkbox"/> CEI EN 61000-3-2 ($I_{rated} \leq 16$ A single-phase) <input type="checkbox"/> CEI EN 61000-3-12 ($16A < I_{rated} \leq 75A$ single-phase) <input checked="" type="checkbox"/> IEC 61400-21 & IEC 61000-3-6	
Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 10% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Supplementary information: - <i>Test not applicable to unidirectional generators</i>	

Harmonics current measured on L1 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	59.326	32.740	119.823	66.127	180.987	99.882	--	P
2	0.379	0.209	0.319	0.176	0.271	0.150	--	P
3	0.377	0.208	0.223	0.123	0.121	0.067	--	P
4	0.033	0.018	0.131	0.073	0.193	0.107	--	P
5	1.032	0.570	1.228	0.678	1.585	0.875	--	P
6	0.106	0.058	0.132	0.073	0.298	0.165	--	P
7	0.451	0.249	0.426	0.235	0.442	0.244	--	P
8	0.025	0.014	0.035	0.019	0.070	0.039	--	P
9	0.087	0.048	0.130	0.072	0.177	0.098	--	P
10	0.105	0.058	0.051	0.028	0.061	0.034	--	P
11	0.219	0.121	0.112	0.062	0.288	0.159	--	P
12	0.045	0.025	0.117	0.064	0.127	0.070	--	P
13	0.242	0.134	0.429	0.237	0.445	0.246	--	P
14	0.093	0.051	0.020	0.011	0.079	0.044	--	P
15	0.126	0.070	0.023	0.013	0.125	0.069	--	P
16	0.015	0.008	0.117	0.064	0.097	0.054	--	P
17	0.101	0.056	0.496	0.274	0.573	0.316	--	P
18	0.087	0.048	0.035	0.020	0.100	0.055	--	P
19	0.053	0.029	0.180	0.099	0.097	0.054	--	P
20	0.032	0.017	0.063	0.035	0.054	0.030	--	P
21	0.059	0.033	0.204	0.113	0.271	0.149	--	P
22	0.044	0.024	0.035	0.019	0.080	0.044	--	P
23	0.301	0.166	0.148	0.082	0.263	0.145	--	P
24	0.100	0.055	0.070	0.039	0.106	0.058	--	P
25	0.157	0.086	0.301	0.166	0.619	0.341	--	P
26	0.124	0.068	0.041	0.022	0.078	0.043	--	P
27	0.056	0.031	0.028	0.015	0.144	0.080	--	P
28	0.122	0.067	0.043	0.024	0.088	0.049	--	P
29	0.081	0.044	0.058	0.032	0.388	0.214	--	P
30	0.123	0.068	0.080	0.044	0.069	0.038	--	P
31	0.136	0.075	0.066	0.037	0.409	0.225	--	P
32	0.179	0.099	0.125	0.069	0.057	0.031	--	P
33	0.043	0.024	0.058	0.032	0.096	0.053	--	P
34	0.089	0.049	0.075	0.041	0.046	0.025	--	P
35	0.120	0.066	0.101	0.056	0.376	0.208	--	P
36	0.052	0.029	0.076	0.042	0.071	0.039	--	P
37	0.119	0.066	0.155	0.085	0.076	0.042	--	P
38	0.093	0.052	0.092	0.051	0.015	0.008	--	P
39	0.083	0.046	0.062	0.034	0.099	0.055	--	P
40	0.079	0.044	0.013	0.007	0.042	0.023	--	P

Harmonics current measured on L2 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	60.723	33.511	119.924	66.183	179.804	99.230	--	P
2	0.571	0.315	0.657	0.363	0.748	0.413	--	P
3	0.488	0.269	0.525	0.290	0.410	0.226	--	P
4	0.341	0.188	0.284	0.157	0.421	0.232	--	P
5	0.687	0.379	0.924	0.510	1.287	0.710	--	P
6	0.067	0.037	0.042	0.023	0.085	0.047	--	P
7	0.350	0.193	0.350	0.193	0.475	0.262	--	P
8	0.044	0.025	0.040	0.022	0.069	0.038	--	P
9	0.363	0.200	0.343	0.189	0.254	0.140	--	P
10	0.036	0.020	0.021	0.012	0.059	0.033	--	P
11	0.162	0.089	0.084	0.046	0.171	0.095	--	P
12	0.056	0.031	0.017	0.009	0.057	0.031	--	P
13	0.229	0.126	0.458	0.253	0.426	0.235	--	P
14	0.028	0.016	0.084	0.046	0.063	0.035	--	P
15	0.052	0.029	0.172	0.095	0.077	0.042	--	P
16	0.067	0.037	0.046	0.025	0.075	0.041	--	P
17	0.084	0.047	0.498	0.275	0.517	0.285	--	P
18	0.090	0.050	0.051	0.028	0.045	0.025	--	P
19	0.098	0.054	0.209	0.115	0.157	0.086	--	P
20	0.041	0.023	0.102	0.056	0.057	0.032	--	P
21	0.065	0.036	0.135	0.074	0.185	0.102	--	P
22	0.060	0.033	0.030	0.017	0.081	0.044	--	P
23	0.299	0.165	0.142	0.079	0.264	0.146	--	P
24	0.066	0.036	0.084	0.047	0.109	0.060	--	P
25	0.143	0.079	0.263	0.145	0.505	0.279	--	P
26	0.110	0.061	0.025	0.014	0.056	0.031	--	P
27	0.104	0.057	0.046	0.025	0.109	0.060	--	P
28	0.032	0.017	0.063	0.035	0.057	0.031	--	P
29	0.129	0.071	0.096	0.053	0.424	0.234	--	P
30	0.070	0.038	0.067	0.037	0.050	0.028	--	P
31	0.122	0.067	0.120	0.066	0.350	0.193	--	P
32	0.097	0.054	0.066	0.036	0.080	0.044	--	P
33	0.023	0.013	0.025	0.014	0.076	0.042	--	P
34	0.070	0.039	0.083	0.046	0.020	0.011	--	P
35	0.074	0.041	0.161	0.089	0.408	0.225	--	P
36	0.038	0.021	0.078	0.043	0.042	0.023	--	P
37	0.196	0.108	0.144	0.079	0.038	0.021	--	P
38	0.065	0.036	0.070	0.039	0.035	0.019	--	P
39	0.018	0.010	0.044	0.024	0.104	0.057	--	P
40	0.066	0.036	0.030	0.016	0.030	0.016	--	P

Harmonics current measured on L3 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	59.316	32.735	119.825	66.129	180.972	99.874	--	P
2	0.806	0.445	0.682	0.376	0.666	0.368	--	P
3	0.906	0.500	0.712	0.393	0.631	0.348	--	P
4	0.409	0.226	0.528	0.291	0.736	0.406	--	P
5	0.976	0.539	1.131	0.624	1.445	0.797	--	P
6	0.135	0.075	0.158	0.087	0.217	0.120	--	P
7	0.430	0.237	0.386	0.213	0.463	0.255	--	P
8	0.115	0.064	0.125	0.069	0.094	0.052	--	P
9	0.222	0.122	0.072	0.040	0.143	0.079	--	P
10	0.114	0.063	0.070	0.039	0.080	0.044	--	P
11	0.089	0.049	0.127	0.070	0.116	0.064	--	P
12	0.093	0.051	0.046	0.026	0.056	0.031	--	P
13	0.224	0.124	0.377	0.208	0.367	0.203	--	P
14	0.038	0.021	0.020	0.011	0.040	0.022	--	P
15	0.050	0.028	0.094	0.052	0.051	0.028	--	P
16	0.048	0.026	0.055	0.030	0.027	0.015	--	P
17	0.042	0.023	0.471	0.260	0.556	0.307	--	P
18	0.096	0.053	0.069	0.038	0.046	0.026	--	P
19	0.083	0.046	0.156	0.086	0.105	0.058	--	P
20	0.035	0.019	0.086	0.047	0.051	0.028	--	P
21	0.020	0.011	0.176	0.097	0.196	0.108	--	P
22	0.046	0.025	0.021	0.011	0.053	0.029	--	P
23	0.285	0.157	0.062	0.034	0.265	0.146	--	P
24	0.113	0.062	0.073	0.040	0.089	0.049	--	P
25	0.157	0.087	0.259	0.143	0.569	0.314	--	P
26	0.061	0.034	0.011	0.006	0.039	0.022	--	P
27	0.120	0.066	0.034	0.019	0.097	0.054	--	P
28	0.096	0.053	0.039	0.021	0.041	0.023	--	P
29	0.078	0.043	0.080	0.044	0.356	0.197	--	P
30	0.056	0.031	0.072	0.040	0.092	0.051	--	P
31	0.141	0.078	0.129	0.071	0.399	0.220	--	P
32	0.124	0.068	0.063	0.035	0.059	0.032	--	P
33	0.067	0.037	0.048	0.026	0.097	0.053	--	P
34	0.029	0.016	0.036	0.020	0.024	0.013	--	P
35	0.100	0.055	0.209	0.115	0.355	0.196	--	P
36	0.083	0.046	0.099	0.055	0.111	0.061	--	P
37	0.196	0.108	0.171	0.094	0.079	0.043	--	P
38	0.092	0.051	0.052	0.028	0.048	0.027	--	P
39	0.039	0.021	0.119	0.066	0.100	0.055	--	P
40	0.054	0.030	0.017	0.010	0.065	0.036	--	P



Bbis.3: TABLE: Armoniche di corrente /Harmonics measurement
(full power, 66% and 33% of $P_{s_{max}}$)

- CEI EN 61000-3-2 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-12 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-3-6

Ambient temperature (°C)	+55 °C ± 2 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Supplementary information:	

Harmonics current measured on L1 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	59.326	32.740	119.823	66.127	180.987	99.882	--	P
2	0.379	0.209	0.319	0.176	0.271	0.150	--	P
3	0.377	0.208	0.223	0.123	0.121	0.067	--	P
4	0.033	0.018	0.131	0.073	0.193	0.107	--	P
5	1.032	0.570	1.228	0.678	1.585	0.875	--	P
6	0.106	0.058	0.132	0.073	0.298	0.165	--	P
7	0.451	0.249	0.426	0.235	0.442	0.244	--	P
8	0.025	0.014	0.035	0.019	0.070	0.039	--	P
9	0.087	0.048	0.130	0.072	0.177	0.098	--	P
10	0.105	0.058	0.051	0.028	0.061	0.034	--	P
11	0.219	0.121	0.112	0.062	0.288	0.159	--	P
12	0.045	0.025	0.117	0.064	0.127	0.070	--	P
13	0.242	0.134	0.429	0.237	0.445	0.246	--	P
14	0.093	0.051	0.020	0.011	0.079	0.044	--	P
15	0.126	0.070	0.023	0.013	0.125	0.069	--	P
16	0.015	0.008	0.117	0.064	0.097	0.054	--	P
17	0.101	0.056	0.496	0.274	0.573	0.316	--	P
18	0.087	0.048	0.035	0.020	0.100	0.055	--	P
19	0.053	0.029	0.180	0.099	0.097	0.054	--	P
20	0.032	0.017	0.063	0.035	0.054	0.030	--	P
21	0.059	0.033	0.204	0.113	0.271	0.149	--	P
22	0.044	0.024	0.035	0.019	0.080	0.044	--	P
23	0.301	0.166	0.148	0.082	0.263	0.145	--	P
24	0.100	0.055	0.070	0.039	0.106	0.058	--	P
25	0.157	0.086	0.301	0.166	0.619	0.341	--	P
26	0.124	0.068	0.041	0.022	0.078	0.043	--	P
27	0.056	0.031	0.028	0.015	0.144	0.080	--	P
28	0.122	0.067	0.043	0.024	0.088	0.049	--	P
29	0.081	0.044	0.058	0.032	0.388	0.214	--	P
30	0.123	0.068	0.080	0.044	0.069	0.038	--	P
31	0.136	0.075	0.066	0.037	0.409	0.225	--	P
32	0.179	0.099	0.125	0.069	0.057	0.031	--	P
33	0.043	0.024	0.058	0.032	0.096	0.053	--	P
34	0.089	0.049	0.075	0.041	0.046	0.025	--	P
35	0.120	0.066	0.101	0.056	0.376	0.208	--	P
36	0.052	0.029	0.076	0.042	0.071	0.039	--	P
37	0.119	0.066	0.155	0.085	0.076	0.042	--	P
38	0.093	0.052	0.092	0.051	0.015	0.008	--	P
39	0.083	0.046	0.062	0.034	0.099	0.055	--	P
40	0.079	0.044	0.013	0.007	0.042	0.023	--	P

Harmonics current measured on L2 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	60.723	33.511	119.924	66.183	179.804	99.230	--	P
2	0.571	0.315	0.657	0.363	0.748	0.413	--	P
3	0.488	0.269	0.525	0.290	0.410	0.226	--	P
4	0.341	0.188	0.284	0.157	0.421	0.232	--	P
5	0.687	0.379	0.924	0.510	1.287	0.710	--	P
6	0.067	0.037	0.042	0.023	0.085	0.047	--	P
7	0.350	0.193	0.350	0.193	0.475	0.262	--	P
8	0.044	0.025	0.040	0.022	0.069	0.038	--	P
9	0.363	0.200	0.343	0.189	0.254	0.140	--	P
10	0.036	0.020	0.021	0.012	0.059	0.033	--	P
11	0.162	0.089	0.084	0.046	0.171	0.095	--	P
12	0.056	0.031	0.017	0.009	0.057	0.031	--	P
13	0.229	0.126	0.458	0.253	0.426	0.235	--	P
14	0.028	0.016	0.084	0.046	0.063	0.035	--	P
15	0.052	0.029	0.172	0.095	0.077	0.042	--	P
16	0.067	0.037	0.046	0.025	0.075	0.041	--	P
17	0.084	0.047	0.498	0.275	0.517	0.285	--	P
18	0.090	0.050	0.051	0.028	0.045	0.025	--	P
19	0.098	0.054	0.209	0.115	0.157	0.086	--	P
20	0.041	0.023	0.102	0.056	0.057	0.032	--	P
21	0.065	0.036	0.135	0.074	0.185	0.102	--	P
22	0.060	0.033	0.030	0.017	0.081	0.044	--	P
23	0.299	0.165	0.142	0.079	0.264	0.146	--	P
24	0.066	0.036	0.084	0.047	0.109	0.060	--	P
25	0.143	0.079	0.263	0.145	0.505	0.279	--	P
26	0.110	0.061	0.025	0.014	0.056	0.031	--	P
27	0.104	0.057	0.046	0.025	0.109	0.060	--	P
28	0.032	0.017	0.063	0.035	0.057	0.031	--	P
29	0.129	0.071	0.096	0.053	0.424	0.234	--	P
30	0.070	0.038	0.067	0.037	0.050	0.028	--	P
31	0.122	0.067	0.120	0.066	0.350	0.193	--	P
32	0.097	0.054	0.066	0.036	0.080	0.044	--	P
33	0.023	0.013	0.025	0.014	0.076	0.042	--	P
34	0.070	0.039	0.083	0.046	0.020	0.011	--	P
35	0.074	0.041	0.161	0.089	0.408	0.225	--	P
36	0.038	0.021	0.078	0.043	0.042	0.023	--	P
37	0.196	0.108	0.144	0.079	0.038	0.021	--	P
38	0.065	0.036	0.070	0.039	0.035	0.019	--	P
39	0.018	0.010	0.044	0.024	0.104	0.057	--	P
40	0.066	0.036	0.030	0.016	0.030	0.016	--	P

Harmonics current measured on L3 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	59.316	32.735	119.825	66.129	180.972	99.874	--	P
2	0.806	0.445	0.682	0.376	0.666	0.368	--	P
3	0.906	0.500	0.712	0.393	0.631	0.348	--	P
4	0.409	0.226	0.528	0.291	0.736	0.406	--	P
5	0.976	0.539	1.131	0.624	1.445	0.797	--	P
6	0.135	0.075	0.158	0.087	0.217	0.120	--	P
7	0.430	0.237	0.386	0.213	0.463	0.255	--	P
8	0.115	0.064	0.125	0.069	0.094	0.052	--	P
9	0.222	0.122	0.072	0.040	0.143	0.079	--	P
10	0.114	0.063	0.070	0.039	0.080	0.044	--	P
11	0.089	0.049	0.127	0.070	0.116	0.064	--	P
12	0.093	0.051	0.046	0.026	0.056	0.031	--	P
13	0.224	0.124	0.377	0.208	0.367	0.203	--	P
14	0.038	0.021	0.020	0.011	0.040	0.022	--	P
15	0.050	0.028	0.094	0.052	0.051	0.028	--	P
16	0.048	0.026	0.055	0.030	0.027	0.015	--	P
17	0.042	0.023	0.471	0.260	0.556	0.307	--	P
18	0.096	0.053	0.069	0.038	0.046	0.026	--	P
19	0.083	0.046	0.156	0.086	0.105	0.058	--	P
20	0.035	0.019	0.086	0.047	0.051	0.028	--	P
21	0.020	0.011	0.176	0.097	0.196	0.108	--	P
22	0.046	0.025	0.021	0.011	0.053	0.029	--	P
23	0.285	0.157	0.062	0.034	0.265	0.146	--	P
24	0.113	0.062	0.073	0.040	0.089	0.049	--	P
25	0.157	0.087	0.259	0.143	0.569	0.314	--	P
26	0.061	0.034	0.011	0.006	0.039	0.022	--	P
27	0.120	0.066	0.034	0.019	0.097	0.054	--	P
28	0.096	0.053	0.039	0.021	0.041	0.023	--	P
29	0.078	0.043	0.080	0.044	0.356	0.197	--	P
30	0.056	0.031	0.072	0.040	0.092	0.051	--	P
31	0.141	0.078	0.129	0.071	0.399	0.220	--	P
32	0.124	0.068	0.063	0.035	0.059	0.032	--	P
33	0.067	0.037	0.048	0.026	0.097	0.053	--	P
34	0.029	0.016	0.036	0.020	0.024	0.013	--	P
35	0.100	0.055	0.209	0.115	0.355	0.196	--	P
36	0.083	0.046	0.099	0.055	0.111	0.061	--	P
37	0.196	0.108	0.171	0.094	0.079	0.043	--	P
38	0.092	0.051	0.052	0.028	0.048	0.027	--	P
39	0.039	0.021	0.119	0.066	0.100	0.055	--	P
40	0.054	0.030	0.017	0.010	0.065	0.036	--	P



Bbis.3: TABLE: Armoniche di corrente /Harmonics measurement
(full power, 66% and 33% of $P_{s_{max}}$)

- CEI EN 61000-3-2 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-12 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-3-6

Ambient temperature (°C)	+55 °C ± 2 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Supplementary information:	

Harmonics current measured on L1 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	60.768	33.536	121.108	66.837	181.692	100.271	--	P
2	0.406	0.224	0.384	0.212	0.466	0.257	--	P
3	0.608	0.336	1.206	0.665	1.604	0.885	--	P
4	0.139	0.077	0.151	0.083	0.226	0.125	--	P
5	1.367	0.754	1.338	0.738	1.189	0.656	--	P
6	0.205	0.113	0.346	0.191	0.432	0.238	--	P
7	0.277	0.153	0.567	0.313	0.767	0.423	--	P
8	0.034	0.019	0.065	0.036	0.064	0.035	--	P
9	0.380	0.210	0.239	0.132	0.028	0.015	--	P
10	0.026	0.014	0.075	0.042	0.051	0.028	--	P
11	0.259	0.143	0.604	0.334	0.635	0.351	--	P
12	0.085	0.047	0.033	0.018	0.088	0.048	--	P
13	0.142	0.078	0.290	0.160	0.431	0.238	--	P
14	0.025	0.014	0.063	0.034	0.051	0.028	--	P
15	0.045	0.025	0.324	0.179	0.246	0.136	--	P
16	0.030	0.017	0.042	0.023	0.040	0.022	--	P
17	0.260	0.144	0.328	0.181	0.302	0.167	--	P
18	0.108	0.060	0.090	0.050	0.048	0.027	--	P
19	0.121	0.067	0.557	0.307	0.338	0.187	--	P
20	0.068	0.038	0.055	0.031	0.051	0.028	--	P
21	0.031	0.017	0.104	0.057	0.182	0.100	--	P
22	0.029	0.016	0.040	0.022	0.042	0.023	--	P
23	0.177	0.098	0.269	0.149	0.375	0.207	--	P
24	0.035	0.019	0.045	0.025	0.060	0.033	--	P
25	0.165	0.091	0.435	0.240	0.608	0.336	--	P
26	0.095	0.052	0.016	0.009	0.029	0.016	--	P
27	0.085	0.047	0.119	0.066	0.118	0.065	--	P
28	0.087	0.048	0.028	0.015	0.032	0.018	--	P
29	0.234	0.129	0.153	0.085	0.365	0.201	--	P
30	0.023	0.013	0.052	0.029	0.054	0.030	--	P
31	0.175	0.097	0.172	0.095	0.552	0.304	--	P
32	0.044	0.024	0.070	0.039	0.027	0.015	--	P
33	0.052	0.028	0.041	0.023	0.176	0.097	--	P
34	0.058	0.032	0.038	0.021	0.042	0.023	--	P
35	0.260	0.144	0.078	0.043	0.380	0.210	--	P
36	0.087	0.048	0.091	0.050	0.037	0.020	--	P
37	0.167	0.092	0.407	0.225	0.317	0.175	--	P
38	0.072	0.040	0.088	0.048	0.018	0.010	--	P
39	0.016	0.009	0.069	0.038	0.112	0.062	--	P
40	0.037	0.020	0.077	0.043	0.032	0.018	--	P

Harmonics current measured on L2 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	58.217	32.129	116.899	64.514	176.324	97.309	--	P
2	0.426	0.235	0.423	0.234	0.358	0.198	--	P
3	0.580	0.320	0.997	0.550	1.171	0.646	--	P
4	0.263	0.145	0.318	0.176	0.417	0.230	--	P
5	0.928	0.512	1.056	0.583	1.212	0.669	--	P
6	0.067	0.037	0.067	0.037	0.037	0.020	--	P
7	0.305	0.168	0.399	0.220	0.495	0.273	--	P
8	0.063	0.035	0.082	0.045	0.080	0.044	--	P
9	0.171	0.094	0.103	0.057	0.121	0.067	--	P
10	0.064	0.035	0.104	0.057	0.162	0.089	--	P
11	0.230	0.127	0.330	0.182	0.292	0.161	--	P
12	0.064	0.035	0.013	0.007	0.046	0.026	--	P
13	0.094	0.052	0.139	0.077	0.310	0.171	--	P
14	0.021	0.011	0.040	0.022	0.062	0.034	--	P
15	0.095	0.053	0.222	0.123	0.204	0.113	--	P
16	0.038	0.021	0.051	0.028	0.024	0.013	--	P
17	0.245	0.135	0.215	0.119	0.143	0.079	--	P
18	0.094	0.052	0.034	0.019	0.035	0.020	--	P
19	0.110	0.061	0.383	0.211	0.238	0.131	--	P
20	0.032	0.018	0.068	0.037	0.034	0.019	--	P
21	0.023	0.013	0.055	0.030	0.160	0.088	--	P
22	0.027	0.015	0.047	0.026	0.028	0.015	--	P
23	0.179	0.099	0.249	0.137	0.239	0.132	--	P
24	0.070	0.039	0.039	0.022	0.029	0.016	--	P
25	0.112	0.062	0.363	0.200	0.494	0.273	--	P
26	0.065	0.036	0.014	0.008	0.048	0.026	--	P
27	0.081	0.045	0.077	0.042	0.075	0.041	--	P
28	0.062	0.034	0.024	0.013	0.034	0.019	--	P
29	0.245	0.135	0.200	0.110	0.349	0.193	--	P
30	0.053	0.029	0.017	0.009	0.034	0.019	--	P
31	0.196	0.108	0.174	0.096	0.468	0.258	--	P
32	0.038	0.021	0.060	0.033	0.030	0.017	--	P
33	0.118	0.065	0.042	0.023	0.076	0.042	--	P
34	0.074	0.041	0.060	0.033	0.069	0.038	--	P
35	0.267	0.147	0.118	0.065	0.465	0.256	--	P
36	0.106	0.058	0.054	0.030	0.034	0.019	--	P
37	0.178	0.098	0.367	0.202	0.259	0.143	--	P
38	0.055	0.030	0.090	0.050	0.013	0.007	--	P
39	0.056	0.031	0.060	0.033	0.058	0.032	--	P
40	0.033	0.018	0.088	0.048	0.042	0.023	--	P

Harmonics current measured on L3 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	61.029	33.680	121.400	66.998	182.031	100.459	--	P
2	0.942	0.520	1.099	0.606	1.244	0.687	--	P
3	1.089	0.601	1.626	0.897	1.863	1.028	--	P
4	0.288	0.159	0.469	0.259	0.657	0.363	--	P
5	1.231	0.680	1.307	0.721	1.314	0.725	--	P
6	0.020	0.011	0.052	0.029	0.042	0.023	--	P
7	0.257	0.142	0.390	0.215	0.407	0.225	--	P
8	0.181	0.100	0.094	0.052	0.055	0.031	--	P
9	0.345	0.190	0.214	0.118	0.217	0.120	--	P
10	0.099	0.055	0.098	0.054	0.113	0.062	--	P
11	0.189	0.104	0.445	0.245	0.457	0.252	--	P
12	0.057	0.031	0.024	0.013	0.070	0.038	--	P
13	0.141	0.078	0.242	0.133	0.380	0.210	--	P
14	0.047	0.026	0.141	0.078	0.080	0.044	--	P
15	0.038	0.021	0.382	0.211	0.317	0.175	--	P
16	0.085	0.047	0.053	0.029	0.085	0.047	--	P
17	0.353	0.195	0.247	0.136	0.118	0.065	--	P
18	0.041	0.023	0.023	0.013	0.021	0.012	--	P
19	0.131	0.072	0.456	0.251	0.301	0.166	--	P
20	0.067	0.037	0.060	0.033	0.051	0.028	--	P
21	0.073	0.040	0.102	0.056	0.198	0.109	--	P
22	0.067	0.037	0.032	0.018	0.019	0.010	--	P
23	0.199	0.110	0.252	0.139	0.298	0.165	--	P
24	0.041	0.023	0.054	0.030	0.057	0.032	--	P
25	0.151	0.083	0.378	0.208	0.545	0.301	--	P
26	0.044	0.024	0.042	0.023	0.051	0.028	--	P
27	0.031	0.017	0.093	0.051	0.063	0.035	--	P
28	0.060	0.033	0.020	0.011	0.037	0.021	--	P
29	0.219	0.121	0.172	0.095	0.351	0.193	--	P
30	0.049	0.027	0.034	0.019	0.056	0.031	--	P
31	0.187	0.103	0.162	0.089	0.483	0.266	--	P
32	0.039	0.022	0.075	0.041	0.059	0.033	--	P
33	0.061	0.034	0.107	0.059	0.041	0.022	--	P
34	0.043	0.024	0.024	0.013	0.060	0.033	--	P
35	0.272	0.150	0.111	0.061	0.422	0.233	--	P
36	0.139	0.076	0.099	0.054	0.030	0.016	--	P
37	0.215	0.119	0.395	0.218	0.233	0.128	--	P
38	0.020	0.011	0.085	0.047	0.022	0.012	--	P
39	0.079	0.044	0.090	0.050	0.047	0.026	--	P
40	0.098	0.054	0.025	0.014	0.050	0.027	--	P



Bbis.3: TABLE: Armoniche di corrente /Harmonics measurement
(full power, 66% and 33% of PC_{max})

- CEI EN 61000-3-2 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-12 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-3-6

Ambient temperature (°C)	+55 °C ± 2 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table

Supplementary information:

- *Test not applicable to unidirectional generators*

Harmonics current measured on L1 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	59.235	32.690	119.560	65.982	181.360	100.088	--	P
2	0.372	0.206	0.315	0.174	0.266	0.147	--	P
3	0.366	0.202	0.223	0.123	0.128	0.070	--	P
4	0.028	0.015	0.135	0.075	0.218	0.120	--	P
5	1.035	0.571	1.213	0.669	1.537	0.848	--	P
6	0.100	0.055	0.132	0.073	0.317	0.175	--	P
7	0.456	0.252	0.409	0.225	0.322	0.178	--	P
8	0.026	0.014	0.035	0.019	0.074	0.041	--	P
9	0.083	0.046	0.132	0.073	0.185	0.102	--	P
10	0.104	0.057	0.047	0.026	0.075	0.041	--	P
11	0.216	0.119	0.113	0.062	0.319	0.176	--	P
12	0.044	0.024	0.118	0.065	0.130	0.072	--	P
13	0.240	0.132	0.436	0.241	0.466	0.257	--	P
14	0.095	0.052	0.023	0.013	0.077	0.043	--	P
15	0.126	0.070	0.027	0.015	0.105	0.058	--	P
16	0.017	0.009	0.121	0.067	0.102	0.056	--	P
17	0.095	0.052	0.495	0.273	0.511	0.282	--	P
18	0.086	0.047	0.031	0.017	0.096	0.053	--	P
19	0.053	0.029	0.184	0.102	0.165	0.091	--	P
20	0.029	0.016	0.062	0.034	0.052	0.028	--	P
21	0.065	0.036	0.197	0.109	0.200	0.111	--	P
22	0.041	0.023	0.034	0.019	0.070	0.039	--	P
23	0.301	0.166	0.157	0.087	0.385	0.212	--	P
24	0.099	0.054	0.070	0.039	0.075	0.041	--	P
25	0.160	0.088	0.285	0.157	0.455	0.251	--	P
26	0.117	0.065	0.038	0.021	0.091	0.050	--	P
27	0.053	0.029	0.038	0.021	0.208	0.115	--	P
28	0.123	0.068	0.048	0.026	0.080	0.044	--	P
29	0.078	0.043	0.050	0.028	0.247	0.136	--	P
30	0.125	0.069	0.079	0.044	0.082	0.045	--	P
31	0.134	0.074	0.070	0.039	0.558	0.308	--	P
32	0.181	0.100	0.128	0.070	0.065	0.036	--	P
33	0.044	0.024	0.061	0.034	0.073	0.040	--	P
34	0.095	0.052	0.074	0.041	0.049	0.027	--	P
35	0.133	0.073	0.113	0.062	0.465	0.256	--	P
36	0.052	0.029	0.081	0.044	0.060	0.033	--	P
37	0.117	0.064	0.166	0.092	0.065	0.036	--	P
38	0.107	0.059	0.093	0.051	0.019	0.010	--	P
39	0.086	0.048	0.065	0.036	0.093	0.052	--	P
40	0.075	0.041	0.014	0.007	0.020	0.011	--	P

Harmonics current measured on L2 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	60.647	33.470	119.810	66.121	180.967	99.871	--	P
2	0.568	0.314	0.657	0.362	0.729	0.403	--	P
3	0.514	0.283	0.482	0.266	0.470	0.259	--	P
4	0.343	0.189	0.278	0.154	0.394	0.218	--	P
5	0.687	0.379	0.910	0.502	1.250	0.690	--	P
6	0.064	0.035	0.040	0.022	0.066	0.036	--	P
7	0.346	0.191	0.331	0.183	0.373	0.206	--	P
8	0.044	0.024	0.037	0.021	0.065	0.036	--	P
9	0.365	0.201	0.332	0.183	0.251	0.139	--	P
10	0.033	0.018	0.021	0.011	0.059	0.033	--	P
11	0.162	0.089	0.075	0.041	0.223	0.123	--	P
12	0.055	0.030	0.019	0.010	0.037	0.021	--	P
13	0.235	0.130	0.478	0.264	0.452	0.249	--	P
14	0.026	0.014	0.080	0.044	0.071	0.039	--	P
15	0.050	0.027	0.173	0.095	0.093	0.051	--	P
16	0.066	0.037	0.047	0.026	0.063	0.035	--	P
17	0.078	0.043	0.493	0.272	0.487	0.269	--	P
18	0.089	0.049	0.045	0.025	0.030	0.017	--	P
19	0.103	0.057	0.218	0.120	0.226	0.125	--	P
20	0.039	0.022	0.105	0.058	0.075	0.041	--	P
21	0.065	0.036	0.131	0.072	0.169	0.093	--	P
22	0.060	0.033	0.030	0.017	0.070	0.039	--	P
23	0.298	0.164	0.152	0.084	0.375	0.207	--	P
24	0.066	0.036	0.086	0.047	0.111	0.061	--	P
25	0.148	0.081	0.248	0.137	0.366	0.202	--	P
26	0.107	0.059	0.024	0.013	0.064	0.036	--	P
27	0.102	0.057	0.046	0.026	0.152	0.084	--	P
28	0.027	0.015	0.064	0.036	0.057	0.032	--	P
29	0.127	0.070	0.090	0.049	0.297	0.164	--	P
30	0.072	0.040	0.065	0.036	0.067	0.037	--	P
31	0.121	0.067	0.127	0.070	0.488	0.269	--	P
32	0.098	0.054	0.070	0.038	0.059	0.032	--	P
33	0.021	0.012	0.029	0.016	0.061	0.033	--	P
34	0.067	0.037	0.083	0.046	0.031	0.017	--	P
35	0.089	0.049	0.168	0.093	0.498	0.275	--	P
36	0.041	0.023	0.081	0.045	0.031	0.017	--	P
37	0.194	0.107	0.154	0.085	0.060	0.033	--	P
38	0.068	0.038	0.071	0.039	0.042	0.023	--	P
39	0.014	0.008	0.044	0.025	0.101	0.056	--	P
40	0.065	0.036	0.032	0.018	0.031	0.017	--	P

Harmonics current measured on L3 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	59.234	32.690	119.567	65.986	181.352	100.084	--	P
2	0.801	0.442	0.679	0.375	0.678	0.374	--	P
3	0.921	0.508	0.705	0.389	0.568	0.314	--	P
4	0.412	0.227	0.526	0.290	0.708	0.391	--	P
5	0.977	0.539	1.121	0.619	1.398	0.772	--	P
6	0.133	0.073	0.156	0.086	0.216	0.119	--	P
7	0.438	0.242	0.374	0.206	0.359	0.198	--	P
8	0.114	0.063	0.131	0.072	0.130	0.071	--	P
9	0.222	0.122	0.076	0.042	0.139	0.077	--	P
10	0.113	0.062	0.069	0.038	0.083	0.046	--	P
11	0.087	0.048	0.121	0.067	0.173	0.096	--	P
12	0.092	0.051	0.049	0.027	0.055	0.031	--	P
13	0.222	0.123	0.389	0.215	0.407	0.225	--	P
14	0.036	0.020	0.022	0.012	0.037	0.020	--	P
15	0.051	0.028	0.089	0.049	0.066	0.037	--	P
16	0.047	0.026	0.056	0.031	0.037	0.020	--	P
17	0.039	0.022	0.471	0.260	0.510	0.281	--	P
18	0.096	0.053	0.067	0.037	0.053	0.029	--	P
19	0.087	0.048	0.157	0.086	0.158	0.087	--	P
20	0.038	0.021	0.087	0.048	0.054	0.030	--	P
21	0.021	0.012	0.174	0.096	0.158	0.087	--	P
22	0.044	0.024	0.021	0.011	0.051	0.028	--	P
23	0.283	0.156	0.074	0.041	0.343	0.190	--	P
24	0.111	0.061	0.071	0.039	0.089	0.049	--	P
25	0.159	0.088	0.253	0.140	0.415	0.229	--	P
26	0.056	0.031	0.013	0.007	0.042	0.023	--	P
27	0.119	0.066	0.036	0.020	0.129	0.071	--	P
28	0.099	0.055	0.038	0.021	0.040	0.022	--	P
29	0.079	0.043	0.072	0.040	0.247	0.136	--	P
30	0.056	0.031	0.072	0.040	0.091	0.050	--	P
31	0.141	0.078	0.132	0.073	0.528	0.291	--	P
32	0.125	0.069	0.060	0.033	0.036	0.020	--	P
33	0.071	0.039	0.050	0.027	0.098	0.054	--	P
34	0.034	0.019	0.033	0.018	0.033	0.018	--	P
35	0.107	0.059	0.218	0.121	0.437	0.241	--	P
36	0.076	0.042	0.100	0.055	0.089	0.049	--	P
37	0.195	0.108	0.179	0.099	0.103	0.057	--	P
38	0.099	0.054	0.049	0.027	0.063	0.035	--	P
39	0.030	0.017	0.121	0.067	0.092	0.051	--	P
40	0.050	0.028	0.021	0.011	0.028	0.015	--	P



Bbis.3: TABLE: Armoniche di corrente /Harmonics measurement
(full power, 66% and 33% of $P_{s_{max}}$)

- CEI EN 61000-3-2 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-12 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-3-6

Ambient temperature (°C)	-10 °C ± 2 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table

Supplementary information:

Harmonics current measured on L1 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	60.963	33.644	121.073	66.818	181.743	100.299	--	P
2	0.403	0.222	0.386	0.213	0.457	0.252	--	P
3	0.610	0.337	1.208	0.667	1.619	0.894	--	P
4	0.135	0.075	0.151	0.083	0.216	0.119	--	P
5	1.361	0.751	1.344	0.742	1.262	0.697	--	P
6	0.204	0.113	0.348	0.192	0.428	0.236	--	P
7	0.276	0.152	0.571	0.315	0.841	0.464	--	P
8	0.036	0.020	0.065	0.036	0.072	0.039	--	P
9	0.382	0.211	0.243	0.134	0.061	0.033	--	P
10	0.026	0.015	0.073	0.040	0.046	0.025	--	P
11	0.261	0.144	0.603	0.333	0.614	0.339	--	P
12	0.087	0.048	0.034	0.019	0.087	0.048	--	P
13	0.139	0.077	0.290	0.160	0.432	0.238	--	P
14	0.024	0.013	0.063	0.035	0.059	0.032	--	P
15	0.045	0.025	0.323	0.178	0.267	0.147	--	P
16	0.030	0.016	0.041	0.023	0.046	0.025	--	P
17	0.260	0.144	0.330	0.182	0.309	0.170	--	P
18	0.105	0.058	0.089	0.049	0.048	0.026	--	P
19	0.121	0.067	0.561	0.310	0.369	0.204	--	P
20	0.066	0.037	0.058	0.032	0.058	0.032	--	P
21	0.030	0.017	0.104	0.057	0.165	0.091	--	P
22	0.029	0.016	0.040	0.022	0.041	0.022	--	P
23	0.172	0.095	0.270	0.149	0.388	0.214	--	P
24	0.033	0.018	0.046	0.025	0.058	0.032	--	P
25	0.166	0.092	0.430	0.237	0.644	0.356	--	P
26	0.091	0.050	0.016	0.009	0.030	0.016	--	P
27	0.085	0.047	0.119	0.066	0.147	0.081	--	P
28	0.087	0.048	0.028	0.015	0.039	0.021	--	P
29	0.242	0.133	0.154	0.085	0.365	0.201	--	P
30	0.025	0.014	0.052	0.028	0.051	0.028	--	P
31	0.171	0.094	0.177	0.098	0.522	0.288	--	P
32	0.042	0.023	0.072	0.040	0.030	0.017	--	P
33	0.053	0.029	0.038	0.021	0.178	0.098	--	P
34	0.052	0.029	0.038	0.021	0.054	0.030	--	P
35	0.261	0.144	0.080	0.044	0.392	0.216	--	P
36	0.086	0.048	0.094	0.052	0.043	0.024	--	P
37	0.167	0.092	0.407	0.224	0.313	0.173	--	P
38	0.074	0.041	0.090	0.050	0.014	0.008	--	P
39	0.015	0.008	0.068	0.038	0.077	0.042	--	P
40	0.041	0.023	0.079	0.044	0.033	0.018	--	P

Harmonics current measured on L2 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	58.377	32.217	116.896	64.512	176.558	97.438	--	P
2	0.423	0.233	0.423	0.234	0.361	0.199	--	P
3	0.591	0.326	1.046	0.578	1.246	0.688	--	P
4	0.267	0.147	0.320	0.176	0.431	0.238	--	P
5	0.927	0.512	1.087	0.600	1.283	0.708	--	P
6	0.070	0.039	0.066	0.036	0.032	0.018	--	P
7	0.306	0.169	0.415	0.229	0.557	0.307	--	P
8	0.059	0.033	0.086	0.048	0.093	0.052	--	P
9	0.174	0.096	0.099	0.055	0.114	0.063	--	P
10	0.067	0.037	0.101	0.056	0.152	0.084	--	P
11	0.231	0.128	0.332	0.183	0.294	0.163	--	P
12	0.064	0.035	0.014	0.008	0.042	0.023	--	P
13	0.092	0.051	0.141	0.078	0.320	0.176	--	P
14	0.020	0.011	0.039	0.022	0.057	0.031	--	P
15	0.095	0.052	0.217	0.120	0.219	0.121	--	P
16	0.034	0.019	0.052	0.028	0.019	0.011	--	P
17	0.248	0.137	0.215	0.119	0.156	0.086	--	P
18	0.094	0.052	0.035	0.019	0.036	0.020	--	P
19	0.108	0.060	0.386	0.213	0.261	0.144	--	P
20	0.031	0.017	0.070	0.039	0.045	0.025	--	P
21	0.027	0.015	0.053	0.029	0.149	0.082	--	P
22	0.029	0.016	0.048	0.027	0.016	0.009	--	P
23	0.169	0.093	0.244	0.135	0.252	0.139	--	P
24	0.066	0.037	0.040	0.022	0.030	0.017	--	P
25	0.111	0.061	0.360	0.198	0.520	0.287	--	P
26	0.062	0.034	0.015	0.008	0.043	0.024	--	P
27	0.080	0.044	0.080	0.044	0.068	0.038	--	P
28	0.062	0.034	0.022	0.012	0.045	0.025	--	P
29	0.249	0.138	0.201	0.111	0.398	0.220	--	P
30	0.057	0.032	0.017	0.009	0.044	0.024	--	P
31	0.193	0.106	0.180	0.099	0.427	0.235	--	P
32	0.033	0.018	0.061	0.034	0.019	0.010	--	P
33	0.118	0.065	0.040	0.022	0.075	0.041	--	P
34	0.069	0.038	0.062	0.034	0.075	0.041	--	P
35	0.268	0.148	0.118	0.065	0.490	0.270	--	P
36	0.107	0.059	0.056	0.031	0.038	0.021	--	P
37	0.179	0.099	0.366	0.202	0.251	0.138	--	P
38	0.059	0.033	0.090	0.050	0.022	0.012	--	P
39	0.056	0.031	0.060	0.033	0.064	0.036	--	P
40	0.027	0.015	0.087	0.048	0.036	0.020	--	P

Harmonics current measured on L3 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	61.226	33.789	121.368	66.980	182.093	100.493	--	P
2	0.936	0.517	1.099	0.607	1.262	0.696	--	P
3	1.095	0.604	1.629	0.899	1.902	1.050	--	P
4	0.290	0.160	0.470	0.260	0.666	0.367	--	P
5	1.226	0.677	1.312	0.724	1.358	0.749	--	P
6	0.022	0.012	0.051	0.028	0.074	0.041	--	P
7	0.255	0.141	0.397	0.219	0.503	0.278	--	P
8	0.181	0.100	0.093	0.051	0.054	0.030	--	P
9	0.344	0.190	0.216	0.119	0.207	0.114	--	P
10	0.100	0.055	0.101	0.056	0.117	0.065	--	P
11	0.192	0.106	0.446	0.246	0.436	0.241	--	P
12	0.057	0.031	0.026	0.014	0.074	0.041	--	P
13	0.140	0.078	0.243	0.134	0.398	0.220	--	P
14	0.049	0.027	0.141	0.078	0.087	0.048	--	P
15	0.039	0.022	0.386	0.213	0.338	0.187	--	P
16	0.084	0.046	0.052	0.028	0.075	0.042	--	P
17	0.352	0.194	0.245	0.135	0.136	0.075	--	P
18	0.041	0.022	0.023	0.013	0.015	0.008	--	P
19	0.128	0.071	0.459	0.253	0.324	0.179	--	P
20	0.068	0.038	0.061	0.034	0.046	0.025	--	P
21	0.074	0.041	0.100	0.055	0.175	0.097	--	P
22	0.063	0.035	0.033	0.018	0.024	0.013	--	P
23	0.194	0.107	0.256	0.141	0.321	0.177	--	P
24	0.040	0.022	0.055	0.031	0.048	0.027	--	P
25	0.156	0.086	0.378	0.209	0.594	0.328	--	P
26	0.043	0.024	0.041	0.023	0.062	0.034	--	P
27	0.032	0.018	0.096	0.053	0.033	0.018	--	P
28	0.060	0.033	0.019	0.010	0.041	0.023	--	P
29	0.225	0.124	0.172	0.095	0.400	0.221	--	P
30	0.050	0.028	0.032	0.018	0.057	0.031	--	P
31	0.184	0.101	0.168	0.092	0.452	0.249	--	P
32	0.038	0.021	0.077	0.042	0.059	0.033	--	P
33	0.059	0.032	0.107	0.059	0.054	0.030	--	P
34	0.044	0.024	0.024	0.013	0.060	0.033	--	P
35	0.273	0.151	0.111	0.061	0.457	0.252	--	P
36	0.140	0.077	0.101	0.056	0.034	0.019	--	P
37	0.214	0.118	0.396	0.218	0.215	0.119	--	P
38	0.020	0.011	0.084	0.047	0.018	0.010	--	P
39	0.083	0.046	0.091	0.050	0.056	0.031	--	P
40	0.096	0.053	0.028	0.016	0.049	0.027	--	P



Bbis.3: TABLE: Armoniche di corrente /Harmonics measurement
(full power, 66% and 33% of PC_{max})

- CEI EN 61000-3-2 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-12 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-3-6

Ambient temperature (°C)	-10 °C ± 2 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table

Supplementary information:

- *Test not applicable to unidirectional generators*

Harmonics current measured on L1 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	59.373	32.766	119.553	65.979	181.380	100.099	--	P
2	0.377	0.208	0.318	0.175	0.281	0.155	--	P
3	0.372	0.205	0.224	0.124	0.124	0.069	--	P
4	0.026	0.015	0.136	0.075	0.200	0.110	--	P
5	1.031	0.569	1.218	0.672	1.571	0.867	--	P
6	0.098	0.054	0.132	0.073	0.297	0.164	--	P
7	0.459	0.253	0.413	0.228	0.393	0.217	--	P
8	0.028	0.016	0.033	0.018	0.082	0.045	--	P
9	0.084	0.046	0.132	0.073	0.188	0.104	--	P
10	0.103	0.057	0.048	0.026	0.070	0.039	--	P
11	0.213	0.118	0.114	0.063	0.294	0.162	--	P
12	0.048	0.026	0.118	0.065	0.122	0.068	--	P
13	0.244	0.135	0.436	0.241	0.455	0.251	--	P
14	0.092	0.051	0.022	0.012	0.075	0.042	--	P
15	0.127	0.070	0.025	0.014	0.127	0.070	--	P
16	0.018	0.010	0.120	0.066	0.098	0.054	--	P
17	0.095	0.053	0.496	0.274	0.552	0.305	--	P
18	0.087	0.048	0.032	0.018	0.096	0.053	--	P
19	0.056	0.031	0.180	0.099	0.118	0.065	--	P
20	0.030	0.017	0.062	0.034	0.054	0.030	--	P
21	0.064	0.035	0.200	0.111	0.245	0.135	--	P
22	0.040	0.022	0.034	0.019	0.076	0.042	--	P
23	0.302	0.167	0.152	0.084	0.312	0.172	--	P
24	0.099	0.055	0.070	0.039	0.091	0.050	--	P
25	0.166	0.092	0.289	0.160	0.552	0.305	--	P
26	0.117	0.065	0.041	0.023	0.083	0.046	--	P
27	0.054	0.030	0.034	0.019	0.173	0.096	--	P
28	0.124	0.068	0.047	0.026	0.087	0.048	--	P
29	0.075	0.042	0.052	0.029	0.321	0.177	--	P
30	0.125	0.069	0.082	0.045	0.076	0.042	--	P
31	0.134	0.074	0.067	0.037	0.485	0.267	--	P
32	0.180	0.099	0.127	0.070	0.060	0.033	--	P
33	0.044	0.024	0.059	0.033	0.080	0.044	--	P
34	0.095	0.052	0.075	0.041	0.047	0.026	--	P
35	0.126	0.070	0.109	0.060	0.437	0.241	--	P
36	0.054	0.030	0.080	0.044	0.067	0.037	--	P
37	0.114	0.063	0.161	0.089	0.053	0.029	--	P
38	0.104	0.058	0.092	0.051	0.021	0.011	--	P
39	0.086	0.047	0.064	0.035	0.106	0.058	--	P
40	0.073	0.040	0.012	0.007	0.037	0.020	--	P

Harmonics current measured on L2 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	60.477	33.376	120.192	66.331	180.457	99.590	--	P
2	0.565	0.312	0.662	0.365	0.727	0.401	--	P
3	0.485	0.268	0.529	0.292	0.429	0.237	--	P
4	0.336	0.186	0.282	0.156	0.408	0.225	--	P
5	0.687	0.379	0.920	0.508	1.282	0.708	--	P
6	0.062	0.034	0.042	0.023	0.072	0.040	--	P
7	0.350	0.193	0.339	0.187	0.439	0.242	--	P
8	0.043	0.024	0.036	0.020	0.065	0.036	--	P
9	0.366	0.202	0.332	0.183	0.253	0.140	--	P
10	0.032	0.017	0.021	0.012	0.063	0.035	--	P
11	0.157	0.087	0.077	0.043	0.187	0.103	--	P
12	0.052	0.029	0.019	0.010	0.039	0.021	--	P
13	0.236	0.130	0.478	0.264	0.425	0.235	--	P
14	0.026	0.015	0.081	0.045	0.066	0.036	--	P
15	0.051	0.028	0.175	0.097	0.082	0.045	--	P
16	0.068	0.037	0.047	0.026	0.067	0.037	--	P
17	0.080	0.044	0.499	0.276	0.511	0.282	--	P
18	0.087	0.048	0.047	0.026	0.036	0.020	--	P
19	0.101	0.056	0.215	0.119	0.183	0.101	--	P
20	0.038	0.021	0.104	0.057	0.062	0.034	--	P
21	0.061	0.034	0.134	0.074	0.169	0.093	--	P
22	0.060	0.033	0.030	0.017	0.080	0.044	--	P
23	0.297	0.164	0.144	0.079	0.309	0.170	--	P
24	0.068	0.037	0.086	0.047	0.108	0.060	--	P
25	0.143	0.079	0.251	0.139	0.444	0.245	--	P
26	0.107	0.059	0.025	0.014	0.059	0.033	--	P
27	0.101	0.055	0.049	0.027	0.126	0.070	--	P
28	0.032	0.018	0.064	0.035	0.057	0.032	--	P
29	0.128	0.071	0.090	0.050	0.366	0.202	--	P
30	0.070	0.039	0.066	0.036	0.057	0.032	--	P
31	0.122	0.068	0.122	0.068	0.420	0.232	--	P
32	0.097	0.053	0.069	0.038	0.068	0.037	--	P
33	0.022	0.012	0.026	0.015	0.065	0.036	--	P
34	0.071	0.039	0.083	0.046	0.025	0.014	--	P
35	0.086	0.047	0.164	0.090	0.469	0.259	--	P
36	0.040	0.022	0.080	0.044	0.034	0.019	--	P
37	0.194	0.107	0.148	0.082	0.051	0.028	--	P
38	0.066	0.037	0.070	0.039	0.039	0.021	--	P
39	0.014	0.008	0.044	0.024	0.111	0.061	--	P
40	0.067	0.037	0.030	0.017	0.027	0.015	--	P

Harmonics current measured on L3 phase								
Order [h]	33%		66%		100%		Limits [A]	Results
	I [A]	I/In [%]	I [A]	I/In [%]	I [A]	I/In [%]		
1	59.372	32.766	119.552	65.978	181.372	100.095	--	P
2	0.805	0.444	0.683	0.377	0.665	0.367	--	P
3	0.918	0.507	0.705	0.389	0.608	0.335	--	P
4	0.412	0.227	0.528	0.292	0.721	0.398	--	P
5	0.972	0.537	1.124	0.621	1.436	0.793	--	P
6	0.135	0.074	0.156	0.086	0.210	0.116	--	P
7	0.443	0.245	0.376	0.208	0.413	0.228	--	P
8	0.114	0.063	0.131	0.073	0.109	0.060	--	P
9	0.227	0.125	0.074	0.041	0.138	0.076	--	P
10	0.115	0.063	0.071	0.039	0.084	0.046	--	P
11	0.086	0.047	0.124	0.068	0.132	0.073	--	P
12	0.092	0.051	0.048	0.027	0.058	0.032	--	P
13	0.225	0.124	0.385	0.212	0.393	0.217	--	P
14	0.033	0.018	0.022	0.012	0.037	0.020	--	P
15	0.050	0.028	0.090	0.050	0.058	0.032	--	P
16	0.047	0.026	0.055	0.030	0.031	0.017	--	P
17	0.042	0.023	0.470	0.259	0.544	0.300	--	P
18	0.096	0.053	0.069	0.038	0.051	0.028	--	P
19	0.088	0.049	0.155	0.086	0.120	0.066	--	P
20	0.037	0.021	0.087	0.048	0.054	0.030	--	P
21	0.018	0.010	0.176	0.097	0.190	0.105	--	P
22	0.048	0.027	0.020	0.011	0.050	0.028	--	P
23	0.284	0.157	0.068	0.038	0.292	0.161	--	P
24	0.112	0.062	0.072	0.040	0.084	0.046	--	P
25	0.164	0.090	0.255	0.141	0.507	0.280	--	P
26	0.057	0.031	0.014	0.008	0.043	0.024	--	P
27	0.121	0.067	0.035	0.019	0.109	0.060	--	P
28	0.100	0.055	0.038	0.021	0.039	0.022	--	P
29	0.076	0.042	0.075	0.041	0.304	0.168	--	P
30	0.059	0.033	0.073	0.040	0.093	0.051	--	P
31	0.143	0.079	0.132	0.073	0.462	0.255	--	P
32	0.124	0.069	0.062	0.034	0.041	0.023	--	P
33	0.069	0.038	0.048	0.026	0.103	0.057	--	P
34	0.029	0.016	0.033	0.018	0.028	0.015	--	P
35	0.103	0.057	0.215	0.119	0.413	0.228	--	P
36	0.084	0.046	0.101	0.055	0.100	0.055	--	P
37	0.193	0.107	0.174	0.096	0.094	0.052	--	P
38	0.097	0.053	0.051	0.028	0.057	0.031	--	P
39	0.035	0.019	0.120	0.066	0.107	0.059	--	P
40	0.054	0.030	0.021	0.011	0.052	0.029	--	P



Bbis.3: TABLE: Fluttuazioni di tensione /Flicker measurement

(full power, 66% and 33% of $P_{s_{max}}$)

- CEI EN 61000-3-3 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-11 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-4-15

Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 10% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Supplementary information:	



100% PS _{max}	L1	L2	L3	Limit
Pst	0.112	0.092	0.097	1.00
Plt	0.111	0.094	0.099	0.65
dc [%]	0.000	0.206	0.195	3.30
dmax [%]	0.000	0.821	0.769	6.00
dt [s]	0.000	0.000	0.000	0.50

66% PS _{max}	L1	L2	L3	Limit
Pst	0.102	0.110	0.115	1.00
Plt	0.098	0.102	0.113	0.65
dc [%]	0.000	0.172	0.238	3.30
dmax [%]	0.000	0.731	0.503	6.00
dt [s]	0.000	0.000	0.000	0.50

33% PS _{max}	L1	L2	L3	Limit
Pst	0.098	0.104	0.116	1.00
Plt	0.097	0.108	0.114	0.65
dc [%]	0.000	0.154	0.193	3.30
dmax [%]	0.000	0.813	0.725	6.00
dt [s]	0.000	0.000	0.000	0.50



Bbis.3: TABLE: Fluttuazioni di tensione /Flicker measurement

(full power, 66% and 33% of PC_{max})

- CEI EN 61000-3-3 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-11 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-4-15

Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 10% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table

Supplementary information:

- *Test not applicable to unidirectional generators*

100% PC _{max}	L1	L2	L3	Limit
Pst	0.109	0.099	0.105	1.00
Plt	0.107	0.097	0.106	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50

66% PC _{max}	L1	L2	L3	Limit
Pst	0.106	0.095	0.109	1.00
Plt	0.106	0.096	0.111	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50

33% PC _{max}	L1	L2	L3	Limit
Pst	0.117	0.101	0.110	1.00
Plt	0.119	0.166	0.108	0.65
dc [%]	0.152	0.223	0.095	3.30
dmax [%]	0.693	0.724	0.726	6.00
dt [s]	0.000	0.000	0.000	0.50



Bbis.3: TABLE: Fluttuazioni di tensione /Flicker measurement
(full power, 66% and 33% of $P_{s_{max}}$)

- CEI EN 61000-3-3 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-11 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-4-15

Ambient temperature (°C)	+55 °C ± 2 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Supplementary information:	



100% PS _{max}	L1	L2	L3	Limit
Pst	0.112	0.096	0.099	1.00
Plt	0.111	0.096	0.105	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50

66% PS _{max}	L1	L2	L3	Limit
Pst	0.105	0.104	0.117	1.00
Plt	0.100	0.104	0.115	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50

33% PS _{max}	L1	L2	L3	Limit
Pst	0.100	0.110	0.118	1.00
Plt	0.099	0.113	0.117	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50



Bbis.3: TABLE: Fluttuazioni di tensione /Flicker measurement

(full power, 66% and 33% of PC_{max})

- CEI EN 61000-3-3 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-11 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-4-15

Ambient temperature (°C)	+55 °C ± 2 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Supplementary information:	
Operator	See cover page
Supervisor	See cover page
Test Date.....	See cover page



100% PC _{max}	L1	L2	L3	Limit
Pst	0.111	0.099	0.106	1.00
Plt	0.108	0.098	0.107	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50

66% PC _{max}	L1	L2	L3	Limit
Pst	0.111	0.101	0.114	1.00
Plt	0.106	0.099	0.113	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50

33% PC _{max}	L1	L2	L3	Limit
Pst	0.119	0.105	0.115	1.00
Plt	0.121	0.102	0.113	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50



Bbis.3: TABLE: Fluttuazioni di tensione /Flicker measurement

(full power, 66% and 33% of $P_{s_{max}}$)

- CEI EN 61000-3-3 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-11 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-4-15

Ambient temperature (°C)	-10 °C ± 2 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table

Supplementary information:

100% PS _{max}	L1	L2	L3	Limit
Pst	0.112	0.100	0.107	1.00
Plt	0.109	0.099	0.108	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50

66% PS _{max}	L1	L2	L3	Limit
Pst	0.103	0.102	0.116	1.00
Plt	0.103	0.101	0.118	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50

33% PS _{max}	L1	L2	L3	Limit
Pst	0.098	0.115	0.116	1.00
Plt	0.100	0.116	0.119	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50



Bbis.3: TABLE: Fluttuazioni di tensione /Flicker measurement

(full power, 66% and 33% of PC_{max})

- CEI EN 61000-3-3 ($I_{rated} \leq 16$ A single-phase)
- CEI EN 61000-3-11 ($16A < I_{rated} \leq 75A$ single-phase)
- IEC 61400-21 & IEC 61000-4-15

Ambient temperature (°C)	-10 °C ± 2 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Supplementary information:	



100% PC _{max}	L1	L2	L3	Limit
Pst	0.110	0.100	0.109	1.00
Plt	0.111	0.100	0.106	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50

66% PC _{max}	L1	L2	L3	Limit
Pst	0.104	0.103	0.115	1.00
Plt	0.107	0.100	0.114	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50

33% PC _{max}	L1	L2	L3	Limit
Pst	0.116	0.105	0.104	1.00
Plt	0.122	0.107	0.108	0.65
dc [%]	0.000	0.000	0.000	3.30
dmax [%]	0.000	0.000	0.000	6.00
dt [s]	0.000	0.000	0.000	0.50



Bbis.4	TABLE: Verifica del campo di funzionamento in tensione e frequenza <i>/ Check the operating range in voltage and frequency</i>	
Ambient temperature (°C)	:	25 °C ± 5 °C
Humidity (RH %)	:	65% ± 5% RH
Instrumentation list.....	:	See table "Measurement equipment and instrumentation"
Uncertainty	:	See table
Supplementary information:		
Operator	:	See cover page
Supervisor	:	See cover page
Test Date.....	:	See cover page

Test Point	Range of operation	Pout [W]	Cosφ	Test time [s]	Limit [%]	Result
Test 1	85% U _n – 47.5Hz	100% P _{Smax} (o P _{NINV})	1.00	at least 300	±5% S _n	No Disconnection
Test 2	110% U _n - 51.5Hz	100% P _{Smax} (o P _{NINV})	1.00	at least 300	±5% S _n	No Disconnection
Test 3	85% U _n – 47.5Hz	100% P _{Cmax}	1.00	at least 300	±5% S _n	No Disconnection
Test 4	110% U _n - 51.5Hz	100% P _{Cmax}	1.00	at least 300	±5% S _n	No Disconnection

Grafico Test 1: 110% U_n - 51.5Hz / 100% $P_{s_{max}}$

/ Graph Test 1: 110% U_n - 51.5Hz




Grafico Test 2: 85% U_n - 47.5Hz / 100% $P_{s_{max}}$

/ Graph Test 2: 85% U_n - 47.5Hz




Grafico Test 3: 110% U_n - 51.5Hz / 100% P_{cmax}

/ Graph Test 1: 110% U_n - 51.5Hz





Grafico Test 4: 85% U_n - 47.5Hz / 100% P_{cmax}

/ Graph Test 4: 85% U_n - 47.5Hz






8.4.1.3 Par. a) & b) Bbis.5.1 Bbis.5.2	TABLE: Verifica delle condizioni di connessione e riconnessione <i>/ Check of the connection and re-connection conditions</i> TABLE: Verifica della erogazione graduale della potenza attiva <i>/ Check of the gradual increase of the power production</i>
Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Supplementary information:	


Voltage [Vac]	Voltage Condition [Vac]	Frequency [Hz]	Frequency condition [Hz]	Output Power [W]	Rec. Time [sec]	Ramp Time [sec]	Ramp gradient [%Pn/s]	Acceptability criteria	Note
1.12Un	V < 85% or V > 110%	50	49.9Hz < f < 50.1Hz	---	---	---	---	no connection after 30s	First connection
1.08Un	85% < V < 110%	50	49.9Hz < f < 50.1Hz	12460 7	142	330	0.30	Connection Delay for Reconnection ≥ 30 s Ramp ratio P < 0.333 % Pn/s	Connection to grid (no after fault of the grid- ex. First connection) Ref. a) 8.4.1.3
0.83Un	V < 85%	50	49.9Hz < f < 50.1Hz	---	---	---	---	no connection after 300 s	UV Ref. b) 8.4.1.3
0.87Un	85% < V < 110%	50	49.9Hz < f < 50.1Hz	10570 6	310	300	0.28	Connection Delay for Reconnection ≥ 300 s Ramp ratio P < 0.333 % Pn/s	Reconnecti on after fault recovery Ref. b) 8.4.1.3
1.12Un	V > 110%	50	49.9Hz < f < 50.1Hz	---	---	---	---	no connection after 300 s	OV Ref. b) 8.4.1.3
1.08Un	85% < V < 110%	50	49.9Hz < f < 50.1Hz	12489 0	330	329	0.30	Connection Delay for Reconnection ≥ 300 s Ramp ratio P < 0.333 % Pn/s	Reconnecti on after fault recovery Ref. b) 8.4.1.3
Un	85% < V < 110%	48.85	f < 47.5Hz	---	---	---	---	no connection after 300 s	UF Ref. b) 8.4.1.3
Un	85% < V < 110%	49.95	49.9Hz < f < 50.1Hz	12520 0	318	326	0.30	Connection Delay for Reconnection ≥ 300 s Ramp ratio P < 0.333 % Pn/s	Reconnecti on after fault recovery Ref. b) 8.4.1.3
Un	85% < V < 110%	50.15	f > 51.1Hz	---	---	---	---	no connection after 300 s	OF Ref. b) 8.4.1.3
Un	85% < V < 110%	50.05	49.9Hz < f < 50.1Hz	12460 0	313	332	0.30	Connection Delay for Reconnection ≥ 300 s Ramp ratio P < 0.333 % Pn/s	Reconnecti on after fault recovery Ref. b) 8.4.1.3

Grafico Bbis.5.2: Verifica della erogazione graduale della Potenza attiva
/ Graph Bbis.5.2: Check of the gradual increase of the power production

Test in discharging mode ($P_{s_{max}}$)



Test in charging mode ($P_{c_{max}}$)




8.4.4.2 Bbis.6.1	TABLE: check of the constructive requirements: reactive power production capability
Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Max. cosφ declared	<input type="checkbox"/> cosφ: 0.9 → Pout ≤ 11.08 KW (triangular) <input checked="" type="checkbox"/> Q/Pn% = 48.43% → Pout > 11.08 KW (rectangular)
<div style="text-align: center;">  <p> ■ Capability "rettangolare" Per ogni P = P_n; Q = 0,4843 P_n </p> <p> ▴ Capability "triangolare" Per ogni P = P_n; Q = 0,4843 P </p> </div> <p>Figura 3Bbis – Capability per un sistema di accumulo con inverter bidirezionale.</p>	
<p>Supplementary information:</p> <p><i>For each of the 10 levels of active power, 1 value of inductive reactive power and 1 value of conductive reactive power shall be registered as average values in 1 min, based on the measurements at the fundamental in a window of 200ms.</i></p>	

TABLE: Reactive power production with set point Q = 0

Power Step	Active Power		Reactive Power		Power Factor	Deviation	Target value	Limit
	[W]	[%Sn]	[VAR]	[%Sn]	Cosφ	ΔQ/Sn[%]	Q/Sn[%]	ΔQ/Sn
90% - 100% $P_{S_{max}}$	124317	99.5	246.0912	0.002	1.00	0.002	0	<±5%
70% - 80% $P_{S_{max}}$	99807	79.8	55.98046	0.000	1.00	0.000	0	<±5%
50% - 60% $P_{S_{max}}$	75952	60.8	43.0424	0.000	1.00	0.000	0	<±5%
30% - 40% $P_{S_{max}}$	50479	40.4	15.8946	0.000	1.00	0.000	0	<±5%
10% - 20% $P_{S_{max}}$	25879	20.7	-98.5046	-0.001	1.00	-0.001	0	<±10%
10% - 20% $P_{C_{max}}$	-25583	-20.5	-54.2855	0.000	1.00	0.000	0	<±10%
30% - 40% $P_{C_{max}}$	-50240	-40.2	-158.48	-0.009	1.00	-0.009	0	<±5%
50% - 60% $P_{C_{max}}$	-75572	-60.5	61.38192	0.000	1.00	0.000	0	<±5%
70% - 80% $P_{C_{max}}$	-100233	-80.2	-143.762	-0.001	1.00	-0.001	0	<±5%
90% - 100% $P_{C_{max}}$	-124922	-99.9	-449.185	-0.004	1.00	-0.004	0	<±5%

TABLE: Reactive power adsorbed with set point Q = Qmin

Power Step	Active Power		Reactive Power		Power Factor	Deviation	Target value	Limit
	[W]	[%Sn]	[VAr]	[%Sn]	Cosφ	ΔQ/Sn	Q/Sn[%]	ΔQ/Sn
90% - 100% $P_{S_{max}}$	4797	3.8	-125171	-100.1	-0.034	0.1	-100	<±5%
70% - 80% $P_{S_{max}}$	3783	3.0	-125201	-100.2	-0.034	0.2	-100	<±5%
50% - 60% $P_{S_{max}}$	2878	2.3	-125262	-100.2	-0.032	0.2	-100	<±5%
30% - 40% $P_{S_{max}}$	3779	3.0	-125223	-100.2	-0.034	0.2	-100	<±5%
10% - 20% $P_{S_{max}}$	3783	3.0	-125020	-100.0	-0.034	0	-100	<±5%
10% - 20% $P_{C_{max}}$	-4270	-3.4	-125151	-100.1	-0.034	0.1	-100	<±5%
30% - 40% $P_{C_{max}}$	-4365	-3.5	-125173	-100.1	-0.034	0.1	-100	<±5%
50% - 60% $P_{C_{max}}$	-5112	-4.1	-125199	-100.2	-0.033	0.2	-100	<±5%
70% - 80% $P_{C_{max}}$	-4276	-3.4	-125150	-100.1	-0.034	0.1	-100	<±5%
90% - 100% $P_{C_{max}}$	-4273	-3.4	-125149	-100.1	-0.034	0.1	-100	<±5%

TABLE: Reactive power produced with set point Q = Qmax

Power Step	Active Power		Reactive Power		Power Factor	Deviation	Target value	Limit
	[W]	[%Sn]	[VAr]	[%Sn]	Cosφ	ΔQ/Sn[%]	Q/Sn[%]	ΔQ/Sn
90% - 100% $P_{S_{max}}$	3185	2.5	125350	100.3	0.025	0.3	100	<±5%
70% - 80% $P_{S_{max}}$	2320	1.9	125315	100.3	0.017	0.3	100	<±5%
50% - 60% $P_{S_{max}}$	3186	2.5	125350	100.3	0.025	0.3	100	<±5%
30% - 40% $P_{S_{max}}$	3184	2.5	125357	100.3	0.025	0.3	100	<±5%
10% - 20% $P_{S_{max}}$	3182	2.5	125360	100.3	0.025	0.3	100	<±5%
10% - 20% $P_{C_{max}}$	-5861	-4.7	125343	100.3	-0.047	0.3	100	<±5%
30% - 40% $P_{C_{max}}$	-5858	-4.7	125339	100.3	-0.047	0.3	100	<±5%
50% - 60% $P_{C_{max}}$	-5859	-4.7	125349	100.3	-0.047	0.3	100	<±5%
70% - 80% $P_{C_{max}}$	-6711	-5.4	125309	100.2	-0.0	0.2	100	<±5%
90% - 100% $P_{C_{max}}$	-5959	-4.8	125306	100.2	-0.047	0.2	100	<±5%



Bbis.6.3	TABLE: reactive power production according to an assigned level Required for inverter used in plant > 11.08KW (applicable for inverter with Pnom < 11.08 KW as well)
Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Max. cosφ declared	<input type="checkbox"/> cosφ: 0.9 → Pout ≤ 11.08 KW <input checked="" type="checkbox"/> Q/Pn% = 48.43% → Pout > 11.08 KW
SET-POINT	
Supplementary information: <ul style="list-style-type: none"> - Output power during test set at 50%Pn (power level set by DC simulator). - Maintain each set point at least 60 s. - Calculate the average values in 1 min, based on measurements at the fundamental frequency in a window of 200ms. 	
Operator	See cover page
Supervisor	See cover page
Test Date	See cover page

Tabella Bbis.6.3: Misura dell' accuratezza della regolazione della potenza reattiva in base ad un comando esterno

/ Tabella Bbis.6.3 : reactive power production according to an assigned level

Output Power [%]	Set point Q/Sn [%]	Output Power measured [W]	Reactive Power measured [Var]	Deviation ΔQ/Sn [%]	ΔQ Limit [%]	RESULT
50% PS _{MAX}	40.0 %	62590	50850	0.68	≤ 5% Sn	PASS
50% PC _{MAX}	40.0 %	-61894	50727	0.58	≤ 5% Sn	PASS

Bbis.6.5	TABLE: Tempo di risposta ad una variazione a gradino del livello assegnato <i>/ Reaction time after a step variation of the assigned level.</i>
	Required for inverter used in plant > 11.08KW (applicable for inverter with Pnom < 11.08 KW as well)

Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Max. cosφ declared	<input type="checkbox"/> cosφ: 0.9 → Pout ≤ 11.08 KW <input checked="" type="checkbox"/> Q/Pn% = 48.43% → Pout > 11.08 KW




Figura 6Bbis – Misura del tempo di risposta a variazioni a gradino del set-point assegnato per la potenza reattiva

Supplementary information:

- Measurements performed with output power set at 50%Pnom and 100%Pnom
- Sample rate: at least 200ms.

Tabella Bbis.6.5 : Misura del tempo di risposta a variazioni a gradino del set-point assegnato per la potenza reattiva

/ Table: Reaction time after a step variation of the assigned level

Test 1 : 100% output power						
Step	Output Power [W]	transient	Output Voltage [V]	Reactive Power [Var]	Tr [s]	Limit [s]
1	99266	0 → -Qmin	229.98	-74046	7.4	10
2	98807	-Qmin → +Qmax	231.04	75264	8.4	10
3	123517	+Qmax → 0	230.57	115	8.0	10
Test 2 : 50% output power						
Step	Output Power [W]	transient	Output Voltage [V]	Reactive Power [Var]	Tr [s]	Limit [s]
1	62982	0 → -Qmin	228.58	-74875	9.2	10
2	61371	-Qmin → +Qmax	231.71	74920	9.6	10
3	62244	+Qmax → 0	230.18	1281	9.4	10
Descrizione del metodo di controllo adottato / description of control method used:						

Grafico: Tempo di risposta ad una variazione a gradino del livello assegnato (Test 1 – 100% Pn).

/ Graph of the reaction time after a step variation of the assigned level (Test 1 - 100%).






Grafico: Tempo di risposta ad una variazione a gradino del livello assegnato (Test 2 – 50% Pn).

/ Graph of the reaction time after a step variation of the assigned level (Test 2 - 50%).



Bbis.6.6 **TABLE: Erogazione automatica di potenza reattiva secondo una curva caratteristica $\cos\phi = f(P)$**
Annex E
E.2 / Automatic production of reactive power according to a characteristic curve $\cos\phi = f(P)$

Ambient temperature (°C)	: 25 °C ± 5 °C
Humidity (RH %)	: 65% ± 5% RH
Instrumentation list.....	: See table "Measurement equipment and instrumentation"
Uncertainty	: See table
Max. $\cos\phi$ declared	: <input type="checkbox"/> $\cos\phi$: 0.9 → $P_{out} \leq 11.08$ KW <input checked="" type="checkbox"/> $Q/P_n\%$ = 48.43% → $P_{out} > 11.08$ KW
Set value.....	: Lock-in: 1.05 Vn (Induttivo) (Vn and 1.1 Vn with steps of 0.01) Lock-out: 230 V or 50%PS _{max} (0.9 Vn and Vn with steps of 0.01) Lock-in: 0.95 Vn (Capacitivo) (0.9 Vn and Vn with steps of 0.01) Lock-out: 230 V or 50%PS _{max} (Vn and 1.1 Vn with steps of 0.01)



Supplementary information:

- Function must be enable by a local command of the converter.
- Each value must be reach in < 10s.
- Describe the Lock-in value defined by the manufacturer

Tabella Bbis.7: Erogazione automatica di potenza reattiva secondo una curva caratteristica $\cos\phi = f(P)$

/ Table Bbis.7: $\cos\phi = f(P)$

Induttivo								
P/Pn [%]	P [W]	Vout [V]	Q [Var]	Cos ϕ measured	Cos ϕ Set-point	$\Delta Q/P_n$	Limit $\Delta Q/P_n$	RESULT
20	25263	239.24	1116	0.9999	1.00	0.89%	$\pm 2.5\% P_n$	P
30	37961	239.29	958	0.9999	1.00	0.77%	$\pm 2.5\% P_n$	P
40	50625	239.34	804	1.0000	1.00	0.64%	$\pm 2.5\% P_n$	P
50	63336	239.40	675	1.0000	1.00	0.54%	$\pm 2.5\% P_n$	P
60	75992	239.45	533	1.0000	1.00	0.43%	$\pm 2.5\% P_n$	P
60	76213	244.04	-14852	0.9802	0.98	0.50%	$\pm 2.5\% P_n$	P
70	89082	244.08	-25463	0.9601	0.96	0.42%	$\pm 2.5\% P_n$	P
80	99334	244.13	-34311	0.9400	0.94	1.39%	$\pm 2.5\% P_n$	P
90	113399	244.17	-47288	0.9209	0.92	0.82%	$\pm 2.5\% P_n$	P
100	116810	244.19	-50650	0.9154	0.90*	4.74%	$\pm 2.5\% P_n$	P
100	116990	232.72	-50771	0.9153	0.90*	4.71%	$\pm 2.5\% P_n$	P
100	123455	225.89	-267	1.0000	1.00	-0.21%	$\pm 2.5\% P_n$	P

Note*: Reduced reactive power output is permitted for the reason that the apparent power is limited.


Capacitivo								
P/Pn [%]	P [W]	Vout [V]	Q [Var]	Cos ϕ measured	Cos ϕ Set-point	$\Delta Q/P_n$	Limit $\Delta Q/P_n$	RESULT
20	25588	220.86	-979	0.9998	1.00	-0.78%	$\pm 2.5\% P_n$	P
30	38298	220.91	-1183	0.9999	1.00	-0.95%	$\pm 2.5\% P_n$	P
40	51121	220.97	-1346	0.9999	1.00	-1.08%	$\pm 2.5\% P_n$	P
50	63694	221.02	-1466	1.0000	1.00	-1.17%	$\pm 2.5\% P_n$	P
60	75171	221.07	-1600	1.0000	1.00	-1.28%	$\pm 2.5\% P_n$	P
60	74976	216.49	12856	0.9817	0.98	-1.89%	$\pm 2.5\% P_n$	P
70	87528	216.55	23209	0.9617	0.96	-1.86%	$\pm 2.5\% P_n$	P
80	100021	216.60	33965	0.9424	0.94	-1.87%	$\pm 2.5\% P_n$	P
90	115382	216.66	48613	0.9225	0.92	-0.43%	$\pm 2.5\% P_n$	P
100	115411	216.68	48638	0.9184	0.90*	-5.81%	$\pm 2.5\% P_n$	P
100	115365	228.14	48759	0.9183	0.90*	-5.69%	$\pm 2.5\% P_n$	P
100	123626	235.06	-2133	1.0000	1	-1.71%	$\pm 2.5\% P_n$	P

Note*: Reduced reactive power output is permitted for the reason that the apparent power is limited.


Grafico: Erogazione automatica di potenza reattiva secondo una curva caratteristica $\cos\phi = f(P)$

/ Graph: Reactive power production according to a characteristic curve $\cos(\phi) = f(P)$

Induttivo



Capacitivo



Bbis.6.8 <i>Annex E</i> E.2.1	TABLE: Erogazione automatica di potenza reattiva secondo una curva caratteristica $Q=f(V)$ <i>/ Automatic reactive power production according to a characteristic curve $Q=f(V)$</i> Required for inverter used in plant > 11.08KW
---	---

Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Set value.....	Lock-in: 0.2*PS _{max} (or 0.2*P _{NINV}) and 0.2*PC _{max} Lock-out: 0.05*PS _{max}
Activation settings.....	Activation of the protection with a delay from 0 to 30 s with step of 1 s (Default setting: 3 s)




Figura 39 – Curve caratteristiche standard $Q = f(V)$ (a27)

Default settings:	V/Vn	Q/Pn%
V2i	0.90	Q _{MAX}
V1i	0.92	0.00%
V1s	1.08	0.00%
V2s	1.10	Q _{MIN}

Supplementary information:

The setting of $k = 0 + 1$ with steps of 0.01

The setting of $Q(V)$ function is enabled by a local command of the inverter.

Parametri definiti dal costruttore:
/ Parameters defined by the customer

Discharge mode: $P_{S_{max}}$	k=0.1	$V_{1s} = 1.08\%V_n$	$V_{2s} = 1.1\%V_n$	Table A.1
		$V_{1i} = 0.92\%V_n$	$V_{2i} = 0.9\%V_n$	Table A.2
Discharge mode: $P_{S_{max}}$	k= - 0.1	$V_{1s} = 1.08\%V_n$	$V_{2s} = 1.1\%V_n$	Table A.3
		$V_{1i} = 0.92\%V_n$	$V_{2i} = 0.9\%V_n$	Table A.4
Charge mode: $P_{C_{max}}$	k=0.1	$V_{1s} = 1.08\%V_n$	$V_{2s} = 1.1\%V_n$	Table B.1
		$V_{1i} = 0.92\%V_n$	$V_{2i} = 0.9\%V_n$	Table B.2
Charge mode: $P_{C_{max}}$	k= - 0.1	$V_{1s} = 1.08\%V_n$	$V_{2s} = 1.1\%V_n$	Table B.3
		$V_{1i} = 0.92\%V_n$	$V_{2i} = 0.9\%V_n$	Table B.4


Table A.1: Discharge mode with k=0.1

Set Point		Measure			Q/Sn[%] expected	$\Delta Q \%$	LIMITS	RESULT
P/P _{S_{max}} [%]	V/V _n	P/P _{S_{max}} [%]	V _{out} [V]	Q [Var]				
<20%	1.07	14.30	246.35	7739	$\approx k Q_{max}$ ($< \pm 5 \% S_n$)	0.2	$\leq \pm 5\% S_n$	P
<20%	1.09	14.49	250.83	7788	$\approx k Q_{max}$ ($< \pm 5 \% S_n$)	0.2	$\leq \pm 5\% S_n$	P
<20 % → 30 %	1.09	29.72	250.86	-29565	-0.4 Q_{max} ($< 10 \text{ sec}$)	0.3	$\leq \pm 5\% S_n$	P
40%	1.09	40.39	250.89	-29598	-0.4 Q_{max}	0.3	$\leq \pm 5\% S_n$	P
50%	1.09	50.73	250.80	-30610	-0.4 Q_{max}	-0.5	$\leq \pm 5\% S_n$	P
60%	1.09	60.35	250.84	-30810	-0.4 Q_{max}	-0.6	$\leq \pm 5\% S_n$	P
70%	1.09	69.99	250.83	-30573	-0.4 Q_{max}	-0.5	$\leq \pm 5\% S_n$	P
80%	1.09	79.80	250.86	-30991	-0.4 Q_{max}	-0.8	$\leq \pm 5\% S_n$	P
90%	1.09	90.12	250.86	-31128	-0.4 Q_{max}	-0.9	$\leq \pm 5\% S_n$	P
100%	1.09	96.01	250.82	-30462	-0.4 Q_{max}	-0.4	$\leq \pm 5\% S_n$	P
100%	1.10	83.83	253.23	-67524	-0.9 Q_{max}	0.1	$\leq \pm 5\% S_n$	P
100 % → 10%	1.10	9.84	253.00	-67687	-0.9 Q_{max}	0.1	$\leq \pm 5\% S_n$	P
10 % → $\leq 5\%$	1.10	3.84	253.14	7558	$\approx k Q_{max}$ ($< \pm 5 \% S_n$)	0.2	$\leq \pm 5\% S_n$	P

Table A.2: Discharge mode with k= 0.1

Set Point		Measure			Q/Qn[%] expected	$\Delta Q \%$	LIMIT	RESULT
P/Ps _{max} [%]	V/Vn	P/Ps _{max} [%]	Vout [V]	Q [Var]				
<20%	0.93	15.15	214.18	7673	$\approx k Q_{max}$ ($< \pm 5 \% S_n$)	0.14	$\leq \pm 5 \% S_n$	P
<20%	0.91	15.07	209.25	7621	$\approx k Q_{max}$ ($< \pm 5 \% S_n$)	0.10	$\leq \pm 5 \% S_n$	P
<20 % → 30 %	0.91	29.89	209.35	44789	0.6 Q _{max} ($< 10 \text{ sec}$)	-0.17	$\leq \pm 5 \% S_n$	P
40%	0.91	40.34	209.28	45492	0.6 Q _{max}	0.39	$\leq \pm 5 \% S_n$	P
50%	0.91	50.53	209.27	44972	0.6 Q _{max}	-0.02	$\leq \pm 5 \% S_n$	P
60%	0.91	59.93	209.22	45182	0.6 Q _{max}	0.15	$\leq \pm 5 \% S_n$	P
70%	0.91	69.91	209.15	46160	0.6 Q _{max}	0.93	$\leq \pm 5 \% S_n$	P
80%	0.91	79.80	209.25	44487	0.6 Q _{max}	-0.41	$\leq \pm 5 \% S_n$	P
90%	0.91	82.21	209.26	44486	0.6 Q _{max}	-0.41	$\leq \pm 5 \% S_n$	P
100%	0.91	83.63	209.06	43944	0.6 Q _{max}	-0.84	$\leq \pm 5 \% S_n$	P
100%	0.90	67.42	207.16	74299	Q _{max}	-0.56	$\leq \pm 5 \% S_n$	P
100 % → 10%	0.90	9.05	206.96	75618	Q _{max}	0.49	$\leq \pm 5 \% S_n$	P
10 % → $\leq 5\%$	0.90	3.34	206.36	7307	$\approx k Q_{max}$ ($< \pm 5 \% S_n$)	-0.15	$\leq \pm 5 \% S_n$	P

Graph curve Q=f(V)
Curve A.1



Graph curve Q=f(V)
Curve A.2





Table A.3: Discharge mode with k= -0.1

Set Point		Measure			Q/Qn[%] expected	ΔQ %	LIMIT	RESULT
P/Ps _{max} [%]	V/Vn	P/Ps _{max} [%]	Vout [V]	Q [Var]				
<20%	1.07	15.01	246.30	-7421	$\approx -k Q_{max}$ ($< \pm 5\% S_n$)	0.06	$\leq \pm 5\% S_n$	P
<20%	1.09	15.24	251.10	-7340	$\approx -k Q_{max}$ ($< \pm 5\% S_n$)	0.13	$\leq \pm 5\% S_n$	P
<20 % → 30 %	1.09	31.10	250.91	-45489	-0.6 Q _{max} (< 10 sec)	-0.39	$\leq \pm 5\% S_n$	P
40%	1.09	40.95	250.94	-45926	-0.6 Q _{max}	-0.74	$\leq \pm 5\% S_n$	P
50%	1.09	49.97	250.90	-45461	-0.6 Q _{max}	-0.37	$\leq \pm 5\% S_n$	P
60%	1.09	59.62	250.89	-45395	-0.6 Q _{max}	-0.32	$\leq \pm 5\% S_n$	P
70%	1.09	70.77	250.92	-46385	-0.6 Q _{max}	-1.11	$\leq \pm 5\% S_n$	P
80%	1.09	79.57	250.79	-44926	-0.6 Q _{max}	0.06	$\leq \pm 5\% S_n$	P
90%	1.09	89.85	250.81	-45543	-0.6 Q _{max}	-0.43	$\leq \pm 5\% S_n$	P
100%	1.09	92.62	250.81	-45930	-0.6 Q _{max}	-0.74	$\leq \pm 5\% S_n$	P
100%	1.10	78.86	253.09	-75211	-Q _{max}	-0.17	$\leq \pm 5\% S_n$	P
100 % → 10%	1.10	9.64	252.83	-75774	-Q _{max}	-0.62	$\leq \pm 5\% S_n$	P
10 % → $\leq 5\%$	1.10	3.74	253.30	-7239	$\approx -k Q_{max}$ ($< \pm 5\% S_n$)	0.21	$\leq \pm 5\% S_n$	P

Table A.4: Discharge mode with k= -0.1

Set Point		Measure			Q/Qn[%] expected	$\Delta Q \%$	LIMIT	RESULT
P/Ps _{max} [%]	V/Vn	P/Ps _{max} [%]	Vout [V]	Q [Var]				
<20%	0.93	14.77	214.25	-7690	$\approx -k Q_{max}$ ($< \pm 5 \% S_n$)	-0.15	$\leq \pm 5 \% S_n$	P
<20%	0.91	15.27	208.93	-7735	$\approx -k Q_{max}$ ($< \pm 5 \% S_n$)	-0.19	$\leq \pm 5 \% S_n$	P
<20 % → 30 %	0.91	30.79	209.32	30606	0.4 Q _{max} ($< 10 \text{ sec}$)	0.48	$\leq \pm 5 \% S_n$	P
40%	0.91	39.72	209.35	29440	0.4 Q _{max}	-0.45	$\leq \pm 5 \% S_n$	P
50%	0.91	50.02	209.36	28471	0.4 Q _{max}	-1.22	$\leq \pm 5 \% S_n$	P
60%	0.91	60.66	209.15	31592	0.4 Q _{max}	1.27	$\leq \pm 5 \% S_n$	P
70%	0.91	69.48	209.17	30327	0.4 Q _{max}	0.26	$\leq \pm 5 \% S_n$	P
80%	0.91	79.75	209.11	29751	0.4 Q _{max}	-0.20	$\leq \pm 5 \% S_n$	P
90%	0.91	86.95	209.18	29312	0.4 Q _{max}	-0.55	$\leq \pm 5 \% S_n$	P
100%	0.91	87.25	209.12	29853	0.4 Q _{max}	-0.12	$\leq \pm 5 \% S_n$	P
100%	0.90	71.13	206.85	67093	0.9 Q _{max}	-0.33	$\leq \pm 5 \% S_n$	P
100 % → 10%	0.90	10.17	206.62	68233	0.9 Q _{max}	0.59	$\leq \pm 5 \% S_n$	P
10 % → $\leq 5\%$	0.90	3.88	206.22	-7586	$\approx -k Q_{max}$ ($< \pm 5 \% S_n$)	-0.07	$\leq \pm 5 \% S_n$	P

Graph curve Q=f(V)
Curve A.3



Graph curve Q=f(V)
Curve A.4





Table B.1: Charge mode with k=0.1

Set Point		Measure			Q/Qn[%] expected	ΔQ %	LIMIT	RESULT
P/Pc _{max} [%]	V/Vn	P/Pc _{max} [%]	Vout [V]	Q [Var]				
<20%	1.07	-15.20	245.95	7422	$\approx -k Q_{max}$ ($< \pm 5\% S_n$)	-0.06	$\leq \pm 5\% S_n$	P
<20%	1.09	-15.46	251.53	7189	$\approx -k Q_{max}$ ($< \pm 5\% S_n$)	-0.25	$\leq \pm 5\% S_n$	P
<20 % → 30 %	1.09	-29.75	250.47	-30997	$-0.4 Q_{max}$ (< 10 sec)	-0.80	$\leq \pm 5\% S_n$	P
40%	1.09	-39.33	250.65	-31118	$-0.4 Q_{max}$	-0.89	$\leq \pm 5\% S_n$	P
50%	1.09	-49.53	250.67	-30554	$-0.4 Q_{max}$	-0.44	$\leq \pm 5\% S_n$	P
60%	1.09	-59.74	250.74	-31006	$-0.4 Q_{max}$	-0.80	$\leq \pm 5\% S_n$	P
70%	1.09	-70.74	250.75	-30682	$-0.4 Q_{max}$	-0.55	$\leq \pm 5\% S_n$	P
80%	1.09	-80.77	250.88	-31132	$-0.4 Q_{max}$	-0.91	$\leq \pm 5\% S_n$	P
90%	1.09	-90.00	250.85	-30462	$-0.4 Q_{max}$	-0.37	$\leq \pm 5\% S_n$	P
100%	1.09	-96.11	250.83	-29953	$-0.4 Q_{max}$	0.04	$\leq \pm 5\% S_n$	P
100%	1.10	-83.44	253.28	-66155	$-0.9 Q_{max}$	1.08	$\leq \pm 5\% S_n$	P
100 % → 10%	1.10	-10.29	253.67	-65793	$-0.9 Q_{max}$	1.37	$\leq \pm 5\% S_n$	P
10 % → $\leq 5\%$	1.10	-3.71	254.27	7590	$\approx -k Q_{max}$ ($< \pm 5\% S_n$)	0.07	$\leq \pm 5\% S_n$	P

Table B.2: Charge mode with k=0.1

Set Point		Measure			Q/Qn[%] expected	$\Delta Q \%$	LIMIT	RESULT
P/Pc _{max} [%]	V/Vn	P/Pc _{max} [%]	Vout [V]	Q [Var]				
<20%	0.93	-15.12	214.39	7688	$\approx k Q_{max}$ ($< \pm 5 \% S_n$)	0.15	$\leq \pm 5 \% S_n$	P
<20%	0.91	-15.04	209.46	7636	$\approx k Q_{max}$ ($< \pm 5 \% S_n$)	0.11	$\leq \pm 5 \% S_n$	P
<20 % → 30 %	0.91	-29.83	209.56	44879	0.6 Q _{max} ($< 10 \text{ sec}$)	-0.10	$\leq \pm 5 \% S_n$	P
40%	0.91	-40.26	209.49	45583	0.6 Q _{max}	0.47	$\leq \pm 5 \% S_n$	P
50%	0.91	-50.43	209.48	45062	0.6 Q _{max}	0.05	$\leq \pm 5 \% S_n$	P
60%	0.91	-59.81	209.43	45272	0.6 Q _{max}	0.22	$\leq \pm 5 \% S_n$	P
70%	0.91	-69.77	209.36	46252	0.6 Q _{max}	1.00	$\leq \pm 5 \% S_n$	P
80%	0.91	-79.64	209.46	44576	0.6 Q _{max}	-0.34	$\leq \pm 5 \% S_n$	P
90%	0.91	-82.05	209.47	44575	0.6 Q _{max}	-0.34	$\leq \pm 5 \% S_n$	P
100%	0.91	-83.46	209.27	44032	0.6 Q _{max}	-0.77	$\leq \pm 5 \% S_n$	P
100%	0.90	-68.29	207.37	74448	Q _{max}	-0.44	$\leq \pm 5 \% S_n$	P
100 % → 10%	0.90	-9.03	207.17	75769	Q _{max}	0.62	$\leq \pm 5 \% S_n$	P
10 % → $\leq 5\%$	0.90	-3.33	206.57	7322	$\approx k Q_{max}$ ($< \pm 5 \% S_n$)	-0.14	$\leq \pm 5 \% S_n$	P

Graph curve Q=f(V)
Curve B.1



Graph curve Q=f(V)
Curve B.2





Table B.3: Charge mode with k= -0.1

Set Point		Measure			Q/Qn[%] expected	$\Delta Q \%$	LIMIT	RESULT
P/Pc _{max} [%]	V/Vn	P/Pc _{max} [%]	Vout [V]	Q [Var]				
<20%	1.07	-15.04	246.79	-7436	$\approx -k Q_{max}$ ($< \pm 5 \% S_n$)	0.05	$\leq \pm 5 \% S_n$	P
<20%	1.09	-15.27	251.60	-7355	$\approx -k Q_{max}$ ($< \pm 5 \% S_n$)	0.12	$\leq \pm 5 \% S_n$	P
<20 % → 30 %	1.09	-31.16	251.41	-45580	$-0.6 Q_{max}$ ($< 10 \text{ sec}$)	-0.46	$\leq \pm 5 \% S_n$	P
40%	1.09	-41.03	251.44	-46018	$-0.6 Q_{max}$	-0.81	$\leq \pm 5 \% S_n$	P
50%	1.09	-50.07	251.40	-45552	$-0.6 Q_{max}$	-0.44	$\leq \pm 5 \% S_n$	P
60%	1.09	-59.74	251.39	-45486	$-0.6 Q_{max}$	-0.39	$\leq \pm 5 \% S_n$	P
70%	1.09	-70.91	251.42	-46478	$-0.6 Q_{max}$	-1.18	$\leq \pm 5 \% S_n$	P
80%	1.09	-79.73	251.29	-45016	$-0.6 Q_{max}$	-0.01	$\leq \pm 5 \% S_n$	P
90%	1.09	-90.03	251.31	-45634	$-0.6 Q_{max}$	-0.51	$\leq \pm 5 \% S_n$	P
100%	1.09	-92.81	251.31	-46022	$-0.6 Q_{max}$	-0.82	$\leq \pm 5 \% S_n$	P
100%	1.10	-79.02	253.60	-75361	$-Q_{max}$	-0.29	$\leq \pm 5 \% S_n$	P
100 % → 10%	1.10	-9.66	253.34	-75926	$-Q_{max}$	-0.74	$\leq \pm 5 \% S_n$	P
10 % → $\leq 5\%$	1.10	-3.75	253.81	-7253	$\approx -k Q_{max}$ ($< \pm 5 \% S_n$)	0.20	$\leq \pm 5 \% S_n$	P


Table B.4: Charge mode with k= -0.1

Set Point		Measure			Q/Qn[%] expected	Δ Q %	LIMIT	RESULT
P/PC _{max} [%]	V/Vn	P/PC _{max} [%]	Vout [V]	Q [Var]				
<20%	0.93	-14.81	214.68	-7713.07	≈-k Q _{max} (< ± 5 % S _n)	-0.17	≤ ± 5% S _n	P
<20%	0.91	-15.32	209.35	-7758.21	≈-k Q _{max} (< ± 5 % S _n)	-0.21	≤ ± 5% S _n	P
<20 % → 30 %	0.91	-30.88	209.74	30697.82	0.4 Q _{max} (< 10 sec)	0.56	≤ ± 5% S _n	P
40%	0.91	-39.84	209.77	29528.32	0.4 Q _{max}	-0.38	≤ ± 5% S _n	P
50%	0.91	-50.17	209.78	28556.41	0.4 Q _{max}	-1.15	≤ ± 5% S _n	P
60%	0.91	-60.84	209.57	31686.78	0.4 Q _{max}	1.35	≤ ± 5% S _n	P
70%	0.91	-69.69	209.59	30417.98	0.4 Q _{max}	0.33	≤ ± 5% S _n	P
80%	0.91	-79.99	209.53	29840.25	0.4 Q _{max}	-0.13	≤ ± 5% S _n	P
90%	0.91	-87.21	209.60	29399.94	0.4 Q _{max}	-0.48	≤ ± 5% S _n	P
100%	0.91	-87.51	209.54	29942.56	0.4 Q _{max}	-0.05	≤ ± 5% S _n	P
100%	0.90	-71.34	207.26	67294.28	0.9 Q _{max}	-0.16	≤ ± 5% S _n	P
100 % → 10%	0.90	-10.20	207.03	68437.70	0.9 Q _{max}	0.75	≤ ± 5% S _n	P
10 % → ≤ 5%	0.90	-3.93	206.63	-7601.17	≈-k Q _{max} (< ± 5 % S _n)	-0.08	≤ ± 5% S _n	P

Graph curve Q=f(V)
Curve B.3




Graph curve Q=f(V)
Curve B.4







8.5.3.1	TABLE: Limitazione della potenza attiva per valori di tensione prossimi al 110 % di Un
Bbis.7.1	<i>/ Active power limitation for voltage values near to 100 % di Un</i>
Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table
Supplementary information: Active power was been measured with an average of 1 second.	
Operator	See cover page
Supervisor	See cover page
Test Date.....	See cover page

Set Point	Measure		Limits	Result
	P _{out} [W]	V _{out} [V]		
V/V _{110%} [%]				
-2%	121917	248.6	-	P
+2%	-125026	257.5	≤ 20% P _{Smax} (for unidirectional) ≥ 80% P _{Cmax} (for bidirectional)	P
-2%	123501	248.6	-	P



<p>8.5.3.4 8.5.3.5 Bbis.7.2</p>	<p>TABLE: Verifica della riduzione automatica della potenza attiva in presenza di transitori di sovrافrequenza sulla rete <i>/ Active power regulation in coincidence with transitory on the transmission grid</i></p>
<p>Ambient temperature (°C)</p>	<p>25 °C ± 5 °C</p>
<p>Humidity (RH %)</p>	<p>65% ± 5% RH</p>
<p>Instrumentation list.....</p>	<p>See table "Measurement equipment and instrumentation"</p>
<p>Uncertainty</p>	<p>See table</p>
 <p>Figura 9Bbis – Curve di limitazione della potenza attiva per convertitori bidirezionali</p>	 <p>Figura 10Bbis – Curve di limitazione della potenza attiva per convertitori unidirezionali</p>
<p><i>Sequence test for Bi-directional EESS</i></p>	<p><i>Sequence test for Uni-directional EESS</i></p>
<p>Supplementary information: Test was performed with a sampling time of 200ms Sn is an active nominal power of the inverter</p>	

Sequence A						
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	Limits	Graph point
1	100% P _{Smax}	47.50	125000	123373	± 2.5% S _n	t1
2	100% P _{Smax}	50.15	125000	123325	± 2.5% S _n	t2
3	100% P _{Smax}	50.40	84275	84825	± 2.5% S _n	t3
4	100% P _{Smax}	50.60	46225	46659	± 2.5% S _n	t4
5	100% P _{Smax}	51.49	-123097	-125631	± 2.5% S _n	t5
6	100% P _{Smax}	50.11	-123097	-125614	± 2.5% S _n	t6
Step #	Set output power [%]	frequency [Hz]	Wait time [s]	Power Gradient [% P _{ref} /min]	Limits	
					Wait time [s]	Power Gradient [% P _{ref} /min]
6→7	100% P _{Smax}	50.00	601	9.03	≥ 300	≤ 20%
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	Limits	Graph point
7	100% P _{Smax}	50.00	125000	122355	± 2.5% S _n	t7
Sequence B						
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	limits	Graph point
1	50% P _{Smax}	47.50	62500	62030	± 2.5% S _n	t1'
2	50% P _{Smax}	50.15	62500	62001	± 2.5% S _n	t2'
3	50% P _{Smax}	50.40	33832	34070	± 2.5% S _n	t3'
4	50% P _{Smax}	50.60	4958	5141	± 2.5% S _n	t4'
5	50% P _{Smax}	51.49	-123534	-125899	± 2.5% S _n	t5'

6	50% P _{Smax}	50.11	-123534	-125853	± 2.5% S _n	t6'
Step #	Set output power [%]	frequency [Hz]	Wait time [s]	Power Gradient [% P _{ref} /min]	Limits	
					Wait time [s]	Power Gradient [% P _{ref} /min]
6→7	100% P _{Smax}	50.00	602	9.02	≥ 300	≤20%
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	Limits	Graph point
7	50% P _{Smax}	50.00	62500	62931	± 2.5% S _n	t7'
Sequence C*						
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	limits	Graph point
1	0% P _{Smax}	47.50	0	-841	± 2.5% S _n	t1''
2	0% P _{Smax}	50.15	0	-909	± 2.5% S _n	t2''
3	0% P _{Smax}	50.40	-19995	-20963	± 2.5% S _n	t3''
4	0% P _{Smax}	50.60	-39082	-40463	± 2.5% S _n	t4''
5	0% P _{Smax}	51.49	-123550	-126476	± 2.5% S _n	t5''
6	0% P _{Smax}	50.11	-123550	-126419	± 2.5% S _n	t6''
Step #	Set output power [%]	frequency [Hz]	Wait time [s]	Power Gradient [% P _{ref} /min]	Limits	
					Wait time [s]	Power Gradient [% P _{ref} /min]
6→7	100% P _{Smax}	50.00	601	9.02	≥ 300	≤20%
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	Limits	Graph point
7	0% P _{Smax}	50.00	0	-686	± 2.5% S _n	t7'

*Sequence C applicable only for bidirectional converters.

Grafico Sequenza A: Curva di limitazione della potenza attiva rispetto alla frequenza

/ Graph Sequence A: Active power regulation in coincidence with transitory on the transmission grid

Sequence A line graph:




Grafico Sequenza B: Curva di limitazione della potenza attiva rispetto alla frequenza

/ Graph Sequence B: Active power regulation in coincidence with transitory on the transmission grid

Sequence B line graph:





Grafico Sequenza C*: Curva di limitazione della potenza attiva rispetto alla frequenza

/ Graph Sequence C*: Active power regulation in coincidence with transitory on the transmission grid

Sequence C line graph:



<p>8.5.3.4</p> <p>8.5.3.5</p> <p>Bbis.7.3</p>	<p>TABLE: Regolazione della potenza attiva in presenza di transitori sulla rete di trasmissione</p> <p><i>/Active power regulation in coincidence with transitory on the transmission grid</i></p>
---	---

Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table




Figura 70 – Curve di limitazione della potenza attiva

Supplementary information:
 The storage needs an energy capacity of 20% of CUS
 Test was performed with a sampling time of 200ms
 Sn is an active nominal power of the inverter



Sequence A						
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	limits	Graph point
1	50% PS _{max}	51.50	62500	62590	± 2.5% S _n	t1
2	50% PS _{max}	49.85	62500	62532	± 2.5% S _n	t2
3	50% PS _{max}	49.60	80452	80599	± 2.5% S _n	t3
4	50% PS _{max}	49.40	98271	97633	± 2.5% S _n	t4
5	50% PS _{max}	49.11	124109	123275	± 2.5% S _n	t5
6	50% PS _{max}	49.89	124109	123256	± 2.5% S _n	t6
Step #	Set output power [%]	frequency [Hz]	Wait time [s]	Power Gradient [% P _{ref} /min]	Limits	
					Wait time [s]	Power Gradient [% P _{ref} /min]
6→7	50% PS _{max}	50.00	603	9.04	≥ 300	20%
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	Limits	Graph point
7	50% PS _{max}	50.00	62500	62648	± 2.5% S _n	t7

Sequence B						
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	limits	Graph point
1	0% PS _{max}	51.50	0	-140	± 2.5% S _n	t1'
2	0% PS _{max}	49.85	0	-137	± 2.5% S _n	t2'
3	0% PS _{max}	49.60	34804	35074	± 2.5% S _n	t3'
4	0% PS _{max}	49.40	70882	70796	± 2.5% S _n	t4'
5	0% PS _{max}	49.11	123196	122264	± 2.5% S _n	t5'



6	0% P _{Smax}	49.89	123196	122224	± 2.5% S _n	t6'
Step #	Set output power [%]	frequency [Hz]	Wait time [s]	Power Gradient [% P _{ref} /min]	Limits	
					Wait time [s]	Power Gradient [% P _{ref} /min]
6→7	0% P _{Smax}	50.00	604	9.02	≥ 300	20%
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	Limits	Graph point
7	0% P _{Smax}	50.00	0	-475	± 2.5% S _n	t7'

Sequence C'						
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	limits	Graph point
1	100% P _{Cmax}	51.50	-125000	-125742	± 2.5% S _n	t1''
2	100% P _{Cmax}	49.85	-125000	-125732	± 2.5% S _n	t2''
3	100% P _{Cmax}	49.60	-54094	-52231	± 2.5% S _n	t3''
4	100% P _{Cmax}	49.40	17544	19009	± 2.5% S _n	t4''
5	100% P _{Cmax}	49.11	121418	121688	± 2.5% S _n	t5''
6	100% P _{Cmax}	49.89	121418	121971	± 2.5% S _n	t6''
Step #	Set output power [%]	frequency [Hz]	Wait time [s]	Power Gradient [% P _{ref} /min]	Limits	
					Wait time [s]	Power Gradient [% P _{ref} /min]
6→7	100% P _{Cmax}	50.00	605	9.04	≥ 300	20%
Step #	Set output power [%]	frequency [Hz]	Expected power value [W]	Actual power values [W]	Limits	Graph point
7	100% P _{Cmax}	50.00	-125000	-125624	± 2.5% S _n	t7''

***Sequence C applicable only for bidirectional converters.**

Grafico Sequenza A: Curva di limitazione della potenza attiva rispetto alla frequenza

/ Graph Sequence A: Active power regulation in coincidence with transitory on the transmission grid

Sequence A line graph:




Grafico Sequenza B: Curva di limitazione della potenza attiva rispetto alla frequenza

/ Graph Sequence B: Active power regulation in coincidence with transitory on the transmission grid

Sequence B line graph:





Grafico Sequenza C*: Curva di limitazione della potenza attiva rispetto alla frequenza

/ Graph Sequence C*: Active power regulation in coincidence with transitory on the transmission grid

Sequence C line graph:





Bbis.7.4	TABLE: Limitazione della potenza attiva su comando esterno proveniente dal Distributore <i>/ Active power limitation in coincidence with external command coming from the Electricity Distributor</i>	
Ambient temperature (°C)	:	25 °C ± 5 °C
Humidity (RH %)	:	65% ± 5% RH
Instrumentation list.....	:	See table "Measurement equipment and instrumentation"
Uncertainty	:	See table
Supplementary information:		
The setting point time's of active power command is 60 seconds.		
The active power was been measured with average value of 1 minute and its measure is checked at least after 30 seconds from the set-point of active power command.		

Test	Set Point	Output Power expected [W]	Output Power measured [W]	Δ P/Pn [%]	Limit [%]	RESULT
1	50%PS _{max} → 30%PS _{max}	37500	37614	0.09	± 2.5% PS _{max}	P
2	50%PS _{max} → 30% P _{Cmax} *	-37500	-37681	0.09	± 2.5% PS _{max}	P

***Test applicable only for bidirectional converters.**

Grafico Test 1: Limitazione della potenza attiva in risposta a comando esterno

/ Graph Test 1: Active power limitation in coincidence with external command coming from the Electricity Distributor





Grafico Test 2: Limitazione della potenza attiva in risposta a comando esterno

/ Graph Test 2: Active power limitation in coincidence with external command coming from the Electricity Distributor





Bbis.7.4.1	TABLE: Verifica del tempo di assestamento ad un comando di incremento/riduzione di potenza <i>/ Check the settling time with external command to increase/decrease the power</i>	
Ambient temperature (°C)	:	25 °C ± 5 °C
Humidity (RH %)	:	65% ± 5% RH
Instrumentation list.....	:	See table "Measurement equipment and instrumentation"
Uncertainty	:	See table
Supplementary information		

Tabella A: Tempo di assestamento ad un comando di riduzione della potenza attiva

/ Table A: Time of alignment after an active power reduction command

Test	Set Point	Output Power expected [W]	Output Power measured [W]	Output Power limit [%]	Settling Time [s]	Settling Time limit [s]	RESULT
A.1*	100% P _{Smax} → 30% P _{Cmax}	-37500	-38423	± 2.5% S _n	1.4	< 50	P
A.2	100% P _{Smax} → 30% P _{Smax}	37500	36491	± 2.5% S _n	1.2	< 50	P

Table B: Tempo di assestamento ad un comando di incremento della potenza attiva

/ Table B: Time of alignment after an active power increasing command

Test	Set Point	Output Power expected [W]	Output Power measured [W]	Output Power limit [%]	Settling Time [s]	Settling Time limit [s]	RESULT
B.1*	100% P _{Cmax} → 50% P _{Smax}	62500	63204	± 2.5% S _n	1.0	< 50	P
B.2	0% P _{Smax} → 50% P _{Smax}	62500	62062	± 2.5% S _n	1.0	< 50	P

*Test applicable only for bidirectional converters.

Grafico Test A.1: Limitazione della potenza attiva in risposta a comando esterno

/ Graph Test A.1: Active power limitation in coincidence with external command coming from the Electricity Distributor




Grafico Test A.2: Limitazione della potenza attiva in risposta a comando esterno

/ Graph Test A.2: Active power limitation in coincidence with external command coming from the Electricity Distributor




Grafico Test B.1: Limitazione della potenza attiva in risposta a comando esterno

/ Graph Test B.1: Active power limitation in coincidence with external command coming from the Electricity Distributor





Grafico Test B.2: Limitazione della potenza attiva in risposta a comando esterno

/ Graph Test B.2: Active power limitation in coincidence with external command coming from the Electricity Distributor





Bbis.8		TABLE: Emissione di componente continua nella corrente di uscita <i>/Check of DC current injection</i>											
Ambient temperature (°C)		25 °C ± 5 °C											
Humidity (RH %)		65% ± 5% RH											
Instrumentation list.....		See table "Measurement equipment and instrumentation"											
Uncertainty		See table											
Temperature test:		Reference Conditions											
Bbis.8.1		TABLE: Verifica della emissione di componente continua <i>/ Check of DC current injection.</i>											
Power [%]	Power [W]	Rated Voltage [Vrms]	Cospφ	Rated Current [A]			Injected value D.C. [mA]			Injected value D.C. [%In]			Limit [%In]
				R	S	T	R	S	T	R	S	T	
33± 5	41663	230.1	1.00	59.6	60.4	62.1	275.0	212.5	233.3	0.15	0.12	0.13	0.5
66± 5	83325	230.3	1.00	118.7	119.6	117.1	245.8	237.5	262.5	0.14	0.13	0.14	0.5
100 ± 5	126250	230.5	1.00	180.8	182.5	182.1	320.8	295.8	354.1	0.18	0.16	0.20	0.5
Bbis.8.2		TABLE: Verifica delle protezioni contro l'immissione di componente continua <i>/ Check of protections against the DC current injection.</i>											
Power [%]	Power [W]	Rated Voltage [Vrms]	Cospφ	Rated Current [A]			Intervention value D.C.			Trip Time [ms]	Limit [s]		
				R	S	T	[mA]	[%In]	I _{dc} >				
33± 5	42488	229.9	1.00	58.7	59.6	60.4	2670	1.47	0.5% In	891	1		
66± 5	84975	230.2	1.00	116.6	117.9	117.9	2730	1.51	0.5% In	878	1		
100 ± 5	123750	230.3	1.00	181.2	181.6	180.4	2700	1.49	0.5% In	890	1		
Power [%]	Power [W]	Rated Voltage [Vrms]	Cospφ	Rated Current [A]			Intervention value D.C.			Trip Time [ms]	Limit [s]		
				R	S	T	[A]	[%In]	I _{dc} >>				
33± 5	41126	229.6	1.00	60.4	59.6	61.7	11.4	6.29	1A	167	0.2		
66± 5	82253	230.2	1.00	118.3	117.9	119.1	12.3	6.79	1A	178	0.2		
100 ± 5	125025	230.5	1.00	181.2	181.8	181.0	11.7	6.46	1A	181	0.2		



Bbis.8		TABLE: Emissione di componente continua nella corrente di uscita <i>/Check of DC current injection</i>											
Ambient temperature (°C)		25 °C ± 5 °C											
Humidity (RH %)		65% ± 5% RH											
Instrumentation list.....		See table "Measurement equipment and instrumentation"											
Uncertainty		See table											
Temperature test:		+55°C ± 2°C											
Bbis.8.1		TABLE: Verifica della emissione di componente continua <i>/ Check of DC current injection.</i>											
Power [%]	Power [W]	Rated Voltage [Vrms]	Cosφ	Rated Current [Arms]			Injected value D.C. [mA]			Injected value D.C. [%In]			Limit [%In]
				R	S	T	R	S	T	R	S	T	
33± 5	41656	230.1	1.00	60.3	60.2	62.1	265.0	212.5	243.3	0.15	0.12	0.13	0.5
66± 5	83706	230.7	1.00	118.3	119.1	117.3	255.8	237.5	262.5	0.14	0.13	0.14	0.5
100 ± 5	125257	230.2	1.00	180.1	182.3	182.1	321.8	295.8	284.1	0.18	0.16	0.16	0.5
Bbis.8.2		TABLE: Verifica delle protezioni contro l'immissione di componente continua <i>/ Check of protections against the DC current injection.</i>											
Power [%]	Power [W]	Rated Voltage [Vrms]	Cosφ	Rated Current [Arms]			Intervention value D.C.			Trip Time [ms]	Limit [s]		
				R	S	T	[mA]	[%In]	I _{dc} >				
33± 5	42445	229.5	1.00	58.2	59.3	60.3	2676	1.48	0.5% In	837	1		
66± 5	85007	230.2	1.00	115.9	118.3	118.0	2735	1.51	0.5% In	859	1		
100 ± 5	124750	230.5	1.00	181.1	181.1	180.5	2715	1.50	0.5% In	889	1		
Power [%nominal VA]	Power [W]	Rated Voltage [Vrms]	Cosφ	Rated Current [Arms]			Intervention value D.C.			Trip Time [ms]	Limit [s]		
				R	S	T	[A]	[%In]	I _{dc} >>				
33± 5	42134	229.5	1.00	60.5	59.9	61.2	11.4	6.29	1A	167	0.2		
66± 5	84250	230.3	1.00	118.7	117.4	119.5	12.2	6.73	1A	178	0.2		
100 ± 5	124024	230.1	1.00	181.8	181.0	181.7	11.3	6.24	1A	181	0.2		



Bbis.8		TABLE: Emissione di componente continua nella corrente di uscita <i>/Check of DC current injection</i>											
Ambient temperature (°C)		25 °C ± 5 °C											
Humidity (RH %)		65% ± 5% RH											
Instrumentation list.....		See table "Measurement equipment and instrumentation"											
Uncertainty		See table											
Temperature test:		-10 °C ± 2 °C											
Bbis.8.1		TABLE: Verifica della emissione di componente continua <i>/ Check of DC current injection.</i>											
Power [%]	Power [W]	Rated Voltage [Vrms]	Cosφ	Rated Current [Arms]			Injected value D.C. [mA]			Injected value D.C. [%In]			Limit [%In]
				R	S	T	R	S	T	R	S	T	
33± 5	42400	230.1	1.00	60.7	61.9	62.1	265.6	212.2	243.2	0.15	0.12	0.13	0.5
66± 5	84806	230.7	1.00	118.3	119.1	117.3	256.0	237.5	262.7	0.14	0.13	0.14	0.5
100 ± 5	125350	230.2	1.00	180.1	182.3	182.1	321.8	295.2	284.3	0.18	0.16	0.16	0.5
Bbis.8.2		TABLE: Verifica delle protezioni contro l'immissione di componente continua <i>/ Check of protections against the DC current injection.</i>											
Power [%]	Power [W]	Rated Voltage [Vrms]	Cosφ	Rated Current [Arms]			Intervention value D.C.			Trip Time [ms]	Limit [s]		
				R	S	T	[mA]	[%In]	I _{dc} >				
33± 5	42436	229.5	1.00	58.2	59.3	60.3	2678	1.48	0.5% In	785	1		
66± 5	84046	230.2	1.00	116.9	118.4	118.7	2766	1.53	0.5% In	893	1		
100 ± 5	124768	230.5	1.00	182.1	181.3	180.6	2785	1.54	0.5% In	773	1		
Power [%]	Power [W]	Rated Voltage [Vrms]	Cosφ	Rated Current [Arms]			Intervention value D.C.			Trip Time [ms]	Limit [s]		
				R	S	T	[A]	[%In]	I _{dc} >>				
33± 5	42167	229.5	1.00	61.8	62.0	61.9	11.3	6.24	1A	156	0.2		
66± 5	84290	230.3	1.00	118.3	118.4	119.1	12.0	6.62	1A	180	0.2		
100 ± 5	124469	230.1	1.00	181.2	181.5	181.7	11.9	6.57	1A	167	0.2		

Bbis.9 **TABLE: Verifica della insensibilità agli abbassamenti di tensione (LVFRT capability)**
/ Check of the LVFRT capability

Ambient temperature (°C)	25 °C ± 5 °C
Humidity (RH %)	65% ± 5% RH
Instrumentation list.....	See table "Measurement equipment and instrumentation"
Uncertainty	See table

Tabella 8ter – Parametri relativi alla Figura 14b per la fault-ride-through capability dei parchi di generazione oltre 11,08 kW

Uret	0,05 [p.u.]	Tclear	0,2 s
Uclear	0,15 [p.u.]	Trec1	0,2 s
Urec1	0,15 [p.u.]	Trec2	0,2 s
Urec2	0,85 [p.u.]	Trec3	1,5 s




Figura 30 – Caratteristica (V - t): UVRT e OVRT per i parchi di generazione oltre 11,08 kW

Supplementary information:


Output power: 25000W				Limit: from 10 % to 30% P _{Smax} .					
Test	Residual magnitude [V/Vn]			phase angle [°]			Duration [ms]	Recovery time [ms]	Recovery time limit [ms]
	R	S	T	φ ₁	φ ₂	φ ₃			
1s – guasto simmetrico trifase / three phases symmetric failure	0.10 ± 0.05	0.10 ± 0.05	0.10 ± 0.05	0°	-120°	120°	200 ± 20	100	400
1a – guasto asimmetrico bifase / two phases asymmetric failure	0.87 ± 0.05	0.87 ± 0.05	0.10 ± 0.05	27°	-147°	120°	200 ± 20	102	400
2s – guasto simmetrico trifase / three phases symmetric failure	0.25 ± 0.05	0.25 ± 0.05	0.25 ± 0.05	0°	-120°	120°	400 ± 20	110	400
2a – guasto asimmetrico bifase / two phases asymmetric failure	0.88 ± 0.05	0.88 ± 0.05	0.25 ± 0.05	22°	-142°	120°	400 ± 20	102	400
3s – guasto simmetrico trifase / three phases symmetric failure	0.50 ± 0.05	0.50 ± 0.05	0.50 ± 0.05	0°	-120°	120°	850 ± 20	104	400
3a – guasto asimmetrico bifase / two phases asymmetric failure	0.90 ± 0.05	0.90 ± 0.05	0.50 ± 0.05	14°	-134°	120°	850 ± 20	107	400
4s – guasto simmetrico trifase / three phases symmetric failure	0.75 ± 0.05	0.75 ± 0.05	0.75 ± 0.05	0°	-120°	120°	1300 ± 20	134	400
4a – guasto simmetrico bifase / two phases asymmetric failure	0.94 ± 0.05	0.94 ± 0.05	0.75 ± 0.05	7°	-127°	120°	1300 ± 20	107	400
5 guasto asimmetrico bifase in BT / two phases asymmetric failure	0.10 ± 0.05	1.0 ± 0.05	0.10 ± 0.05	0°	-120°	120°	200 ± 20	95	400
6 guasto asimmetrico bifase in BT / three phases symmetric failure	0.50 ± 0.05	1.0 ± 0.05	0.50 ± 0.05	0°	-120°	120°	850 ± 20	222	400
7 OV1 - three-phase symmetrical overvoltage	1.25± 0.05	1.25± 0.05	1.25± 0.05	0°	-120°	120	100± 20	114	400
8 OV2 - three-phase symmetrical overvoltage	1.20± 0.05	1.20± 0.05	1.20± 0.05	0°	-120°	120	500± 20	142	400

Grafici: LVFRT


/ Graphs: LVFRT

Test 1s -- guasto simmetrico trifase

/ three phases symmetric failure




Nome	A	B	Eff
AC-U1 [A]	5.202498	1.928411	-3.274083
AC-U2 [A]	-52.13443	3.438798	85.57323
AC-U3 [A]	47.98838	-2.881246	36.30206
AC-U1 [V]	29.30304	3.838963	-26.18406
AC-U2 [V]	-288.8720	-30.13339	208.7428
AC-U3 [V]	257.3251	25.19107	-231.9141
U1_IRMS_r@POWER-AC [V]	229.5417	23.18389	-206.3478
U2_IRMS_r@POWER-AC [V]	229.3763	23.20930	-206.1870
U3_IRMS_r@POWER-AC [V]	229.5385	23.23028	-206.3282
I1_IRMS_r@POWER-AC [A]	37.34783	1.197488	-34.55562
I2_IRMS_r@POWER-AC [A]	36.42035	1.232037	-33.88341
I3_IRMS_r@POWER-AC [A]	37.57404	1.140019	-34.42582
P_t_r@POWER-AC [W]	25462.87	-25.78523	-25488.85
S_t_r@POWER-AC [VA]	20550.18	205.9614	-25344.23
Q_t_r@POWER-AC [var]	840.0813	33.09547	-816.9039
PF_t_r@POWER-AC []	0.999456	-0.782822	-1.787748




Nome	A	B	Eff
AC-U1 [A]	8.070318	16.40974	2.426432
AC-U2 [A]	2.443119	-44.64320	-47.88072
AC-U3 [A]	-4.436991	35.64277	40.07936
AC-U1 [V]	0.305176	36.81377	36.00060
AC-U2 [V]	-28.36094	-294.9629	-248.0320
AC-U3 [V]	36.88372	257.7365	239.8707
U1_IRMS_r@POWER-AC [V]	23.19388	328.0673	205.7134
U2_IRMS_r@POWER-AC [V]	23.20930	228.9429	205.4038
U3_IRMS_r@POWER-AC [V]	23.23028	228.8247	205.5044
I1_IRMS_r@POWER-AC [A]	1.197408	39.00852	35.81113
I2_IRMS_r@POWER-AC [A]	2.526937	37.76307	35.23703
I3_IRMS_r@POWER-AC [A]	3.140019	37.83548	34.89046
P_t_r@POWER-AC [W]	-25.78523	2570.29	-2996.08
S_t_r@POWER-AC [VA]	205.9614	3623.18	20517.20
Q_t_r@POWER-AC [var]	23.09547	-121.2342	-144.5297
PF_t_r@POWER-AC []	-0.768232	0.999988	1.768281

Test 1a -- guasto asimmetrico bifase


/ two phases asymmetric failure




Test 2s -- guasto simmetrico trifase
/ three phases symmetric failure




Test 2a -- guasto asimmetrico bifase
/ two phases asymmetric failure




Test 3s -- guasto simmetrico trifase
/ three phases symmetric failure




Test 3a -- guasto asimmetrico bifase
/ two phases asymmetric failure






Test 4a -- guasto simmetrico bifase
/ two phases asymmetric failure




时间 [s]	A	B	网幅
0:12.6065877	0:12.8243285	0:21.77409	
AC-I1 [A]	127.5327	1.555405	-125.9773
AC-I2 [A]	-67.48132	5.485860	72.96718
AC-I3 [A]	19.10641	-3.394821	-22.50123
AC-U1 [V]	-25.70319	-1.281023	-26.98422
AC-U2 [V]	-318.2602	-274.5578	43.70237
AC-U3 [V]	6.589863	27.54736	20.97750
U1_IRMS_rc@POWER-AC [V]	226.7764	23.26076	-203.5156
U2_IRMS_rc@POWER-AC [V]	229.5421	229.0401	-0.502060
U3_IRMS_rc@POWER-AC [V]	222.7968	23.22038	-199.5764
I1_IRMS_rc@POWER-AC [A]	40.43102	2.864600	-37.56732
I2_IRMS_rc@POWER-AC [A]	41.21754	3.393416	-37.82413
I3_IRMS_rc@POWER-AC [A]	47.70745	2.894477	-44.81297
P_l_rc@POWER-AC [W]	25938.88	-495.2473	-26434.13
S_l_rc@POWER-AC [VA]	29259.23	911.0718	-28348.16



时间 [s]	A	B	网幅
0:12.8241770	0:12.9187002	0:0945232	
AC-I1 [A]	0.923477	-47.53689	-48.46037
AC-I2 [A]	4.749862	33.22598	28.47632
AC-I3 [A]	-3.608324	12.63478	16.24310
AC-U1 [V]	-4.265785	-315.0096	-310.7438
AC-U2 [V]	-264.4425	223.3763	487.8187
AC-U3 [V]	28.62477	92.88383	64.25906
U1_IRMS_rc@POWER-AC [V]	23.26076	230.2467	206.9860
U2_IRMS_rc@POWER-AC [V]	229.0401	229.8332	0.793106
U3_IRMS_rc@POWER-AC [V]	23.22038	230.2459	207.0256
I1_IRMS_rc@POWER-AC [A]	2.864600	38.97208	36.10748
I2_IRMS_rc@POWER-AC [A]	3.393416	35.91195	32.51853
I3_IRMS_rc@POWER-AC [A]	2.894477	37.41764	34.52317
P_l_rc@POWER-AC [W]	-495.2473	25580.16	26075.41
S_l_rc@POWER-AC [VA]	911.0718	25842.21	24931.14


6 guasto asimmetrico bifase in BT
/ three phases symmetric failure



7 OV1 - three-phase symmetrical overvoltage



8 OV2 - three-phase symmetrical overvoltage




Output power: 125000W				Limit: from > 90% P _{Smax} .					
Test	Residual magnitude [V/Vn]			phase angle [°]			Duration [ms]	Recovery time [ms]	Recovery time limit [ms]
	R	S	T	φ ₁	φ ₂	φ ₃			
1s – guasto simmetrico trifase / three phases symmetric failure	0.10 ± 0.05	0.10 ± 0.05	0.10 ± 0.05	0°	-120°	120°	200 ± 20	121	400
1a – guasto asimmetrico bifase / two phases asymmetric failure	0.87 ± 0.05	0.87 ± 0.05	0.10 ± 0.05	27°	-147°	120°	200 ± 20	181	400
2s – guasto simmetrico trifase / three phases symmetric failure	0.25 ± 0.05	0.25 ± 0.05	0.25 ± 0.05	0°	-120°	120°	400 ± 20	174	400
2a – guasto asimmetrico bifase / two phases asymmetric failure	0.88 ± 0.05	0.88 ± 0.05	0.25 ± 0.05	22°	-142°	120°	400 ± 20	152	400
3s – guasto simmetrico trifase / three phases symmetric failure	0.50 ± 0.05	0.50 ± 0.05	0.50 ± 0.05	0°	-120°	120°	850 ± 20	188	400
3a – guasto asimmetrico bifase / two phases asymmetric failure	0.90 ± 0.05	0.90 ± 0.05	0.50 ± 0.05	14°	-134°	120°	850 ± 20	245	400
4s – guasto simmetrico trifase / three phases symmetric failure	0.75 ± 0.05	0.75 ± 0.05	0.75 ± 0.05	0°	-120°	120°	1300 ± 20	250	400
4a – guasto simmetrico bifase / two phases asymmetric failure	0.94 ± 0.05	0.94 ± 0.05	0.75 ± 0.05	7°	-127°	120°	1300 ± 20	245	400
9 guasto asimmetrico bifase in BT / two phases asymmetric failure	0.10 ± 0.05	1.0 ± 0.05	0.10 ± 0.05	0°	-120°	120°	200 ± 20	174	400
10 guasto asimmetrico bifase in BT / three phases symmetric failure	0.50 ± 0.05	1.0 ± 0.05	0.50 ± 0.05	0°	-120°	120°	850 ± 20	205	400
11 OV1 - three-phase symmetrical overvoltage	1.25± 0.05	1.25± 0.05	1.25± 0.05	0°	-120°	120	100± 20	257	400
12 OV2 - three-phase symmetrical overvoltage	1.20± 0.05	1.20± 0.05	1.20± 0.05	0°	-120°	120	500± 20	284	400

Grafici: LVFRT


/ Graphs: LVFRT

Test 1s -- guasto simmetrico trifase

/ three phases symmetric failure




Id	A	B	Valore
时间 [s]	0:12.223480	0:12.440581	0.217102
AC-I1 [A]	23.10177	3.602110	-15.49966
AC-I2 [A]	-227.0803	3.231374	230.3116
AC-I3 [A]	207.8206	-4.066088	-211.8867
AC-U1 [V]	26.83044	-25.03753	-51.86796
AC-U2 [V]	-295.5585	-6.595135	288.9633
AC-U3 [V]	265.7447	29.49000	-236.2547
U1_IRMS_rc@POWER-AC [V]	229.8868	23.17846	-206.7083
U2_IRMS_rc@POWER-AC [V]	229.5594	23.21684	-206.3425
U3_IRMS_rc@POWER-AC [V]	229.7999	23.22457	-206.5754
I1_IRMS_rc@POWER-AC [A]	181.8154	3.133007	-178.6824
I2_IRMS_rc@POWER-AC [A]	178.3326	2.413887	-175.0188
I3_IRMS_rc@POWER-AC [A]	182.1777	3.282357	-178.8953
P_t_rc@POWER-AC [W]	124541.6	-23.16486	-124564.8
S_t_rc@POWER-AC [VA]	124599.3	204.8924	-124394.4




Id	A	B	Valore
时间 [s]	0:12.441736	0:12.562374	0.120638
AC-I1 [A]	2.879701	-65.14148	-68.02118
AC-I2 [A]	2.589210	-179.0365	-181.7258
AC-I3 [A]	-3.653028	253.2715	256.9245
AC-U1 [V]	-15.28788	-83.52352	-68.23564
AC-U2 [V]	-17.72642	-232.7624	-215.0359
AC-U3 [V]	29.91820	306.0100	276.0918
U1_IRMS_rc@POWER-AC [V]	23.17775	229.4470	206.2692
U2_IRMS_rc@POWER-AC [V]	23.21656	229.0068	205.7902
U3_IRMS_rc@POWER-AC [V]	23.22437	229.3152	206.0908
I1_IRMS_rc@POWER-AC [A]	3.142461	181.5171	178.3747
I2_IRMS_rc@POWER-AC [A]	2.427385	179.5239	177.0965
I3_IRMS_rc@POWER-AC [A]	3.288189	181.9820	178.6938
P_t_rc@POWER-AC [W]	-23.71183	124426.0	124449.7
S_t_rc@POWER-AC [VA]	205.5568	124492.0	124286.4

Test 1a -- guasto asimmetrico bifase

/ two phases asymmetric failure




Test 2s -- guasto simmetrico trifase
/ three phases symmetric failure



Test 2a -- guasto asimmetrico bifase
/ two phases asymmetric failure




Tempo	A	B	Valore
时间 [s]	0:13.130619	0:13.546523	0.415904
AC-I1 [A]	-10.40188	1.634441	12.03632
AC-I2 [A]	-74.19149	4.659739	78.85123
AC-I3 [A]	63.92756	-4.183390	-68.11095
AC-U1 [V]	247.7443	-65.44543	-313.1898
AC-U2 [V]	-292.6758	-18.08977	274.5860
AC-U3 [V]	30.58291	79.42510	48.84219
U1_IRMS_rc@POWER-AC [V]	233.5079	201.4564	-32.05150
U2_IRMS_rc@POWER-AC [V]	224.7452	201.3524	-23.39272
U3_IRMS_rc@POWER-AC [V]	227.0005	57.02613	-169.9744
I1_IRMS_rc@POWER-AC [A]	180.8740	4.671188	-176.2029
I2_IRMS_rc@POWER-AC [A]	172.7093	4.341579	-168.3678
I3_IRMS_rc@POWER-AC [A]	181.8419	3.123329	-178.7186
P_t_rc@POWER-AC [W]	117083.2	-1384.093	-118467.2
S_t_rc@POWER-AC [VA]	122329.3	1993.340	-120336.0




Tempo	A	B	Valore
时间 [s]	0:13.543729	0:13.695973	0.182244
AC-I1 [A]	4.408561	185.1791	180.7705
AC-I2 [A]	-0.200424	67.26858	67.46900
AC-I3 [A]	-5.317070	-256.0446	-250.7275
AC-U1 [V]	-253.4547	224.2327	477.6874
AC-U2 [V]	208.3912	94.87630	-113.5149
AC-U3 [V]	44.54208	-319.7491	-364.2912
U1_IRMS_rc@POWER-AC [V]	201.4455	232.9748	31.52927
U2_IRMS_rc@POWER-AC [V]	201.3458	232.3086	30.96286
U3_IRMS_rc@POWER-AC [V]	57.01724	232.5533	175.5361
I1_IRMS_rc@POWER-AC [A]	4.665024	179.6920	175.0269
I2_IRMS_rc@POWER-AC [A]	4.344277	176.3954	172.0511
I3_IRMS_rc@POWER-AC [A]	3.111824	179.2552	176.1434
P_t_rc@POWER-AC [W]	-1382.594	124468.3	125850.8
S_t_rc@POWER-AC [VA]	1991.878	124528.3	122536.4


Test 3s -- guasto simmetrico trifase
/ three phases symmetric failure




Test 3a -- guasto asimmetrico bifase
/ two phases asymmetric failure




Test 4s -- guasto simmetrico trifase
/ three phases symmetric failure







5 guasto asimmetrico bifase in BT
/ two phases asymmetric failure




6 guasto asimmetrico bifase in BT
/ three phases symmetric failure



7 OV1 - three-phase symmetrical overvoltage




8 OV2 - three-phase symmetrical overvoltage



Bbis.10	TABLE: Verifica della insensibilità alle richiuse automatiche in discordanza di fase <i>/ Check of the insensibility to the re-closures when phases are in discordance</i>	
<input checked="" type="checkbox"/>	Bbis.10.1 Test su rete simulata <i>/ Test on simulated grid</i>	
<input type="checkbox"/>	Bbis.10.2 Test su rete di distribuzione tramite trasformatore di accoppiamento <i>/ Test on distribution grid through coupler transformer</i>	
<input type="checkbox"/>	Bbis.10.3 Test su rete di distribuzione, simulazione della deriva di frequenza <i>/ Test on distribution grid, simulation of frequency deviation</i>	
	Ambient temperature (°C)	25 °C ± 2 °C
	Humidity (RH %)	35 %
	Instrumentation list	See table "Measurement equipment and instrumentation"
	Uncertainty	See table


Supplementary information:
Test made with grid simulator as follow:






Test	Output Power [W]	Output Current [A]	Phase displacement [°]	Phase displacement [°]	Result
1	124508	180.9	+90°	+90°	No damage inverter connected
2	125230	181.4	-90°	-90°	No damage Inverter connected
3	124303	180.6	+180°	+180°	No damage Inverter connected
4	124490	180.7	180°	180°	No damage inverter connected


TEST#1: +90° phase displacement




TEST#2: -90° phase displacement.



TEST#3: +180° phase displacement



TEST#4: -180° phase displacement



-TEST REPORT END-

PHOTO DOCUMENTATION

Energy Storage System (Integrated Battery Energy Storage System)

SOLID POWER HV 261

Model: SOLID POWER HV 261



Energy Storage System (Front view)



Energy Storage System (Back view)

Model: SOLID POWER HV 261



Energy Storage System (Left view)



Energy Storage System (Right view)

Model: SOLID POWER HV 261



Energy Storage System (Open view)




Battery Pack

Model: SOLID POWER HV 261



Battery control box



Battery Pack (Top view)

Model: SOLID POWER HV 261



Battery Pack (Right view)



Battery Pack (Left view)

Model: SOLID POWER HV 261



Battery pack (inside view)