

### **TEST REPORT**

Report No.: E1117.02-109-44

## Rendered to:

FAIRFIELD METAL, LLC Fairfield, New Jersey

**PRODUCT TYPE**: ACM Panel System (Wet Seal) **SERIES/MODEL**: ECONNECT-Z

Title	Summary of Results	
Dagign Proggues	+3840 Pa (+80.20 psf)	
Design Pressure	-1920 Pa (-40.10 psf)	
Air Infiltration	$<0.1 \text{ L/s/m}^2 (<0.01 \text{ cfm/ft}^2)$	
Water Penetration Resistance Test Pressure	720 Pa (15.04 psf)	

Reference must be made to Report No. E1117.02-109-44, dated 12/04/14 for complete test specimen description and detailed test results.

Test Report No.: E1117.02-109-44

Report Date: 12/04/14

Page 1 of 5

1.0 Report Issued To: Fairfield Metal, LLC

9 Audrey Place

Fairfield, New Jersey 07004

2.0 Test Laboratory: Architectural Testing, Inc.

130 Derry Court

York, Pennsylvania 17406-8405

717-764-7700

## **3.0 Project Summary:**

**Architectural Testing** 

**3.1 Product Type**: ACM Panel System (Wet Seal)

3.2 Series/Model: ECONNECT-Z

**3.3 Compliance Statement**: Results obtained are tested values and were secured by using the designated test method(s). Test specimen description and results are reported herein.

**3.4 Test Dates**: 11/12/2014 - 11/14/2014


- **3.5 Test Record Retention End Date**: All test records for this report will be retained until November 14, 2018.
- **3.6 Test Location**: Architectural Testing, Inc. test facility in York, Pennsylvania.
- 3.7 Test Sample Source: The test specimen was provided by the client. Representative samples of the test specimen(s) will be retained by Architectural Testing for a minimum of four years from the test completion date.
- **3.8 Drawing Reference**: The test specimen drawings have been reviewed by Architectural Testing and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Architectural Testing per the drawings located in Appendix B. Any deviations are documented herein or on the drawings.

#### 3.9 List of Official Observers:

**Company** Name

Fairfield Metal, LLC Ryan Hunt

Michael D. Stremmel, P.E. Architectural Testing, Inc. Scott Gill Architectural Testing, Inc.





4.0 Test Method(s):

ASTM E 283-04, Test Method for Determining Rate of Airflow Through Exterior Windows, Curtain Walls and Doors Under Specified Pressure Differences Across the Specimen.

ASTM E 330-02, Test Method for Structural Performance of Exterior Windows, Curtain Walls and Doors by Uniform Static Air Pressure Difference.

ASTM E 331-00, Test Method for Water Penetration of Exterior Windows, Curtain Walls and Doors by Uniform Static Air Pressure Difference.

AAMA 501-1-05, Standard Test Method for Water Penetration of Windows, Curtin Walls and Doors using Dynamic Pressure.

## **5.0 Test Specimen Description:**

### **5.1 Product Sizes:**

Overall Area:	Width		Height	
5.9 m <sup>2</sup> (64.0 ft <sup>2</sup> )	millimeters	inches	millimeters	inches
Overall size	2438	96	2438	96
Top panel	2426	95-1/2	1207	47-1/2
Bottom panels (2)	1207	47-1/2	1207	47-1/2

**5.2 Base Wall Construction**: The test wall was fabricated with 16 gauge, 6" galvanized steel studs spaced 16" on center. The steel studs were secured at each end to the top and bottom 16 gauge steel track using #6 x 3/4" long hex head self-tapping screws. The stud wall was sheathed with 5/8" thick DensGlass™ which was secured to the studs with #6 x 1-1/4" long flat head self-tapping screws. The DensGlass™ was covered with a rubberized peel-and-stick air-water barrier. The wall utilized a nominal 2x8 Spruce-Pine-Fir wood wrap around the perimeter, secured to the steel studs with #10 x 3" long flat head self-tapping screws.



Test Report No.: E1117.02-109-44


Report Date: 12/04/14

Page 3 of 5

## **5.0 Test Specimen Description**: (Continued)

**5.3 Panel Construction**: The test specimen was constructed of three aluminum composite panels that were 4 mm (0.157") thick. The panels were constructed with a 0.120" thick plastic core and two 0.020" thick aluminum interior and exterior skins, adhered to the plastic core. A  $90^\circ$  bend was utilized on all four sides of the panels, resulting in a 1" long return leg. The corners utilized a 3/4" wide, 1-1/4" by 1-1/4" aluminum angle, secured to each panel leg with one  $\#6 \times 3/4"$  pan head screw. All panel edges utilized aluminum extrusions which were secured to the panels with  $\#6 \times 3/4"$  pan head screws, spaced \$12" on center.

**5.4 Panel Installation:** The panels were installed in a bottom to top and left to right order. The panels were attached to the stud wall using the aluminum extrusions on the panels. The extrusions were secured to the steel stud wall with #10 x 2" hex head self-tapping screws, spaced 16" on center into each stud. The panel joints utilized an aluminum extrusion that was slid into the adjacent panel extrusion. The joint extrusion was secured to the stud wall with #10 x 2" hex head self-tapping screws, spaced 16" on center into each stud. All panel joints were sealed with backer rod and butyl sealant. The perimeter of the wall system was sealed to the wood buck with backer rod and butyl sealant.





**6.0 Test Results**: The temperature during testing was 19°C (66°F). The results are tabulated as follows:

Title of Test	Results	Allowed	Note
Air Leakage,			
per ASTM E 283	<0.1 L/s/m <sup>2</sup>		
at 75 Pa (1.6 psf)	(<0.01 cfm/ft <sup>2</sup> )	N/A	
Air Leakage,			
per ASTM E 283	<0.1 L/s/m <sup>2</sup>		
at 300 Pa (6.27 psf)	(<0.01 cfm/ft <sup>2</sup> )	N/A	
Water Penetration,			
per ASTM E 547 and ASTM E 331			
at 720 Pa (15.04 psf)	Pass	No leakage	
Dynamic Water Penetration			
per AAMA 501.1			
at 720 Pa (15.04 psf)	Pass	No leakage	
Uniform Load Deflection,			
per ASTM E 330			
Deflections taken at horizontal			
joint between studs			
+3840 Pa (+80.20 psf)	0.5 mm (0.02")		
-1920 Pa (-40.10 psf)	0.5 mm (0.02")	N/A	1, 2
Uniform Load Structural,			
per ASTM E 330			
Permanent sets taken at horizontal			
joint between studs			
+5760 Pa (+120.30 psf)	0.3 mm (0.01")		
-2880 Pa (-60.15 psf)	<0.3 mm (<0.01")	N/A	1, 2

*General Note*: All testing was performed in accordance with the referenced standard(s).

Note 1: Loads were held for 10 seconds.

Note 2: Tape and film were not used to seal against air leakage during structural testing.



Test Report No.: E1117.02-109-44

Report Date: 12/04/14

Page 5 of 5

Architectural Testing will service this report for the entire test record retention period. Test records that are retained such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be retained by Architectural Testing, Inc. for the entire test record retention period.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen(s) tested. This report may not be reproduced, except in full, without the written approval of Architectural Testing, Inc.

For ARCHITECTURAL TESTING, Inc.

Coatt Cill Michael D. Ctrommel D.E.

Scott Gill Senior Technician Michael D. Stremmel, P.E. Senior Project Engineer

SG:asm

Attachments (pages): This report is complete only when all attachments listed are included.

Appendix-A: Photograph (1) Appendix-B: Drawings (4)

Test Report No.: E1117.02-109-44 Report Date: 12/04/14



Appendix A Photograph




Photo No. 1 View of Tested Wall Assembly




Appendix B


**Drawings** 








# VERTICAL JOINT DETAIL







9 Audrey Place Fairfield, NJ 07004 973-276-8440 fairfieldmetal.com







# HORIZONTAL JOINT DETAIL







9 Audrey Place Fairfield, NJ 07004

973-276-8440


fairfieldmetal.com








# BASE TERMINATION DETAIL






9 Audrey Place Fairfield, NJ 07004 973-276-8440 fairfieldmetal.com

# **SUBSTRATE**







Fairfield Metal 9 Audrey Place, Fairfield, NJ 07004 Phone: 973-276-8440 www.fairfieldmetal.com Project Name:

Drawn By: BJ

ECONECT-Z SYSTEM STIFFENERS

Scale:

1:1 Date: 11.21.2014

Drawing No.