

Material Test Report

Report Number: 7555/1-15
Issue Number: 2 - This version supersedes all previous issues
Reissue Reason: update
Date Issued: 13/01/2026
Client: DIXON SAND (PENRITH) PTY LTD
, PENRITH NSW 2751
Contact: Michael Munnoch
Project Number: 7555/1
Project Name: MATERIAL ANALYSIS MATERIAL TESTING - 4610 OLD NORTHERN ROAD, MAROOTA
Work Request: 1985
Sample Number: S-1985C
Date Sampled: 07/01/2026
Dates Tested: 07/01/2026 - 13/01/2026
Sampling Method: Sampled by Client
The results apply to the sample as received
Preparation Method: AS 1289.1.1 - Sampling and Preparation of Soils
Site Selection: Selected by Client
Sample Location: White

Particle Size Distribution (AS1141.11.1)				
Sample Washing	Sample was Washed			
Sieve	Passed %	Passing Limits	Retained %	Retained Limits
75 mm	100		0	
63 mm	100		0	
53 mm	100		0	
37.5 mm	100		0	
26.5 mm	100		0	
19 mm	100		0	
13.2 mm	100		0	
9.5 mm	100		0	
6.7 mm	100		0	
4.75 mm	100		0	
2.36 mm	95		5	
1.18 mm	87		8	
0.6 mm	54		33	
0.425 mm	30		24	
0.3 mm	13		16	
0.15 mm	2		11	
0.075 mm	0		2	

Clay and Fine Silt (AS 1141.33)		Min	Max
Volume of Clay and Silt (%)	10		

GEOTECH

TESTING PTY LTD

ABN 71 076 676 321

Geotech Testing Pty Ltd

Penrith Laboratory

34 Borec Road Penrith NSW 2750

Phone: (02) 4722 2744

Email: matthew@geotech.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Mathew Morley
Laboratory Manager
Laboratory Number: 2734

