


STOCKTON UNIVERSITY

Building Renovation: New Mail/Package Section & Sub Tenant Space Atlantic City, NJ

Technical Specifications



INDEX OF SPECIFICATIONS

<u>SECTION #</u>	<u>SECTION IDENTIFICATION</u>
01 00 00	GENERAL REQUIREMENTS
01 10 00	SUMMARY
01 20 00	PRICE AND PAYMENT PROCEDURES
01 21 00	ALLOWANCES
01 30 00	ADMINISTRATIVE REQUIREMENTS
01 32 16	CONSTRUCTION SCHEDULE
01 33 00	SUBMITTAL PROCEDURES
01 33 23	SHOP DRAWINGS, PRODUCT DATA, SAMPLES & PHOTOGRAPHS
01 40 00	QUALITY REQUIREMENTS
01 60 00	PRODUCT REQUIREMENTS
01 70 00	EXECUTION AND CLOSEOUT REQUIREMENTS
01 71 00	CLEANING
01 73 29	CUTTING AND PATCHING
02 41 19	SELECTIVE DEMOLITION
02 41 26	SELECTIVE ELECTRICAL DEMOLITION
06 10 00	ROUGH CARPENTRY
06 20 00	FINISH CARPENTRY
08 11 13	STEEL DOOR FRAMES
08 14 00	WOOD DOORS
08 71 00	DOOR HARDWARE
09 21 16	GYPSUM BOARD ASSEMBLIES
09 22 16	NON-LOAD BEARING METAL FRAMING SYSTEM
09 30 00	CERAMIC TILE
09 51 13	ACOUSTICAL CEILING
09 90 00	PAINTS AND COATINGS
10 00 00	MISCELLANEOUS SPECIALTIES
10 14 00	INTERIOR SIGNAGE
10 28 00	TOILET ACCESSORIES
12 35 30	CASEWORK
21 05 29	HANGERS AND SUPPORTS FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT
21 13 13	WET-PIPE SPRINKLER SYSTEMS
22 05 23	GENERAL-DUTY VALVES FOR PLUMBING PIPING
22 05 29	HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT
22 05 53	IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT
22 07 00	PLUMBING INSULATION
22 11 16	DOMESTIC WATER PIPING
22 13 16	SANITARY WASTE AND VENT PIPING
22 40 00	PLUMBING FIXTURES AND TRIM
23 05 29	HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT
23 05 53	IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT
23 05 93	TESTING, ADJUSTING, AND BALANCING FOR HVAC
23 33 00	AIR DUCT ACCESSORIES
23 33 46	FLEXIBLE DUCTS
23 37 00	AIR OUTLETS AND INLETS
26 05 00	COMMON WORK RESULTS FOR ELECTRICAL
26 05 19	LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES
26 05 26	GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS
26 25 29	HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

26 05 33
26 27 26
26 51 00

RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS
WIRING DEVICES
INTERIOR LIGHTING

INDEX OF DRAWINGS

SECTION 01 00 00
GENERAL REQUIREMENTS

- 1.0 **DESCRIPTION:** Work included in this project shall be for the
New Mail/Package Section & Sub Tenant Space
- 1.1 **LOCATION:** South Albany Ave, Atlantic City, NJ
- 1.2 **If there are any conflicts in the specifications the University's General Conditions would take precedence.**
- 2.0 **CONTRACTOR'S RESPONSIBILITY:**
- 2.1 **Once the project has been awarded, the General Contractor, his employees including subcontractors and their employees will each be required to coordinate with the Facility of Planning and Construction of Stockton University to gain access to the site and before the start of any work.**
- 2.2 Verify all measurements and conditions in the field.
- 2.3 Before starting work, examine all adjoining work on which the work of these specifications depend. Perform corrective work to all existing conditions necessary to make these specifications perform in all respects.
- 2.4 **APPLICABLE DOCUMENTS:** Publications, specifications and standards listed in this Specification form a part of the Specification to the extent indicated by the reference thereto. Unless otherwise indicated, the issue of effect on the date of issuing the Invitation for bids shall apply.
- 2.5 **PROGRESS CHART:** Within ten (10) days of the receipt of Notice to Proceed and prior to commencement of work, the Contractor shall submit and receive approval for a Progress Chart indicating the planned starting and completion dates for all work items.
- 2.6 **PRICE SCHEDULE:** Along with the Progress Chart, the Contractor shall submit a price schedule for each work item, indicating his breakdown for labor, material and equipment. Definitions applying are as follows:
- 2.6.1 **LABOR COST:** Direct labor wages and benefits, labor insurance, supervisory labor, small hand tools chargeable to labor, prorated cost of job expenses such as field office and telephone, prorated percentage of general (main office) overhead and percentage of profit.
- 2.6.2 **MATERIAL COST:** Direct material costs delivered to the site, prorated percentage of job expenses, general overhead and profit.
- 2.6.3 **EQUIPMENT COST:** Plant and equipment charges, prorated percentage of job expenses, general overhead and profit.
- 2.7 **INTENT OF DRAWINGS AND SPECIFICATIONS:** The intent of the drawings and specifications is to provide for the completion of the work in every detail that is described therein. The Contractor shall furnish all labor; materials, equipment, tools, transportation and necessary supplies such as may be reasonably required to complete the work in accordance with the drawings.
- 2.8 **REPAIR OF EXISTING WORK:** The work shall be carefully laid out in advance. Where cutting or patching surfaces is necessary for proper installation, the work shall be carefully done by skilled mechanics. Any damage to the building or equipment caused by the Contractor shall be repaired by skilled mechanics of the trades involved, at no additional costs to the Owner. The Contractor shall patch and refinish all damaged surfaces caused by this work so as to match adjacent surfaces in material, texture and color to the satisfaction of the Architect.
- 2.9 **MATERIALS APPROVED:**

- 2.9.1 Catalog cuts and other information shall be submitted by the Contractor as required herein and as necessary to secure approval of the material and methods to be incorporated into the work.
- 2.9.2 Four (4) copies of catalogs and other printed information shall be submitted. One (1) copy of printed matter will be returned to the Contractor for his use.
- 2.9.3 All submittals shall be made using the "Shop Drawing/Material Approval Request" form. Submittals shall be numbered sequentially and shall include the information required.
- 2.9.4 Within ten (10) days after receipt of Notice to Proceed, the Contractor shall submit a submittals log indicating all required submittals and dates to be submitted.

3.0 **METHODS OF MATERIAL QUALIFICATION:**

- 3.0.1 Each material and product can be incorporated into the work and shall conform to the specifications. The Contractor may use any of the following methods to demonstrate compliance with the specifications except as otherwise required.
- 3.0.2 Certificates of Compliance with specification requirements signed by an authorized officer of the manufacturer, processor or approved trade association involved. Such certificates shall show the name and address of the Contractor and the name and location of the project.
- 3.0.3 All materials shall be installed as per manufacturer guide specifications.
- 3.0.4 Labeling by the manufacturer on unbroken and unopened containers.
- 3.0.5 Official marking or labeling by recognized grading organization or national code association indicating compliance.

3.1 **DELIVERY, STORAGE, AND HANDLINGS:**

- 3.1.1 Deliver materials to the job site in the manufacturer's sealed and undamaged containers or wrappings.
- 3.1.2 Each product delivered shall be identified with the manufacture's name, date of manufacture, lot name and trade name.
- 3.1.3 Store materials up off the ground under cover, protected from weather and construction activities.
- 3.1.4 The Contractor shall store all material on the job site at his own risk. The Owner will not be responsible for any lost material.

3.2 **PRECONSTRUCTION MEETING:** A preconstruction meeting is required and will be arranged for some convenient date after contract award, but before the start of site work.

4.0 **INSPECTION:** The Contractor shall keep the Architect fully informed of contract operations and plans so that he may arrange to be present at various times when work is being performed.

5.0 **HOURS OF WORK:** All construction operations shall be performed between the hours of 8 a.m. and 4:30 p.m. local time, Monday through Friday inclusive, pending approved schedule by owner. If the Contractor desires to carry on work outside of these hours, he shall submit an application to the Owner for approval at least seventy-two (72) hours in advance. No such work outside the regular hours established above shall be undertaken without approval of the Owner and at no additional cost to the Owner.

6.0 **UTILITIES:** Electricity and water, as available, will be furnished by the Owner for construction purposes at no cost, provided that these utilities are not overloaded.

7.0 **TOILET FACILITIES:** Shall be provided by the Owner, but used on a limited bases and as approved by the Owner.

8.0 **REMOVAL:** All material and debris removed shall become the property of the Contractor and shall be removed from the site during and after the work. Debris and waste material shall not be discharged into surrounding area. None of the materials being removed may be reused, except as noted on the drawings. All debris removed shall be properly disposed of in approved sites.

- 9.0 **SAFETY BARRICADE:** Provide steel tubular scaffold system with 3” thick wood boards to allow a protected route of travel from all exits. Protective scaffolding shall extend a minimum of 8’ from face of building.
- 10.0 **MANUFACTURER’S REPRESENTATIVE’S RESPONSIBILITIES:**
- 10.0.1 Keeping the Architect informed on a periodic basis as to the progress and quality of the work.
 - 10.0.2 Calling to the attention of the Contractor those matters which he considers to be in violation of the contract requirements.
 - 10.0.3 Reporting to the Architect any failure or refusal of the Contractor to correct unacceptable practices.
 - 10.0.4 Conducting preliminary and subsequent job site meetings with the Contractor’s official job representative.
 - 10.0.5 Rendering any other inspection services which the Architect may designate.
 - 10.0.6 Inspecting, after completion of work, the extent to which the Contractor has complied with these specifications.
 - 10.0.7 The presence and activities of the manufacturers and the Architect shall in no way relieve the Contractor of his contractual responsibilities.
- 11.0 **TEMPORARY TRAILERS** Not Required
- 12.0 **ENCLOSURES AND FENCING**
- 12.0.1 At staging area.
 - 12.0.2 Interior Enclosures:
 - 1. Provide temporary partitions to separate work areas from Owner occupied areas, to prevent penetration of dust and moisture into Owner occupied areas, and to prevent damage to existing materials and equipment.
 - 2. Construction: Framing, plywood & gypsum board sheet materials with closed joints and sealed edges at intersections with existing surfaces:
 - a. Insulated to R 13 min.
 - b. STC rating of 35 in accordance with ASTM E90.
 - c. Surface Burning Characteristics: Maximum 25/450 flame spread/smoke developed index when tested in accordance with ASTM E84, NFPA 255, UL 723.
 - d. Fire Rated Construction: To match existing rating.
 - e. Tested Rating: Determined in accordance with ASTM E119.
 - 3. Paint surfaces exposed to view from Owner occupied areas.
- 13.0 **WORK PERFORMED:** The General Contractor shall certify that a minimum of 25% of the work shall be performed by his direct staff, not sub-contractors.
- 14.0 **COVID DATA:** The Contractor shall comply with ALL states rules and regulations as it relates to New Jersey State Guidelines.

END OF SECTION

SECTION 01 10 00

SUMMARY

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Contract description.
- B. Work by Owner.
- C. Contractor's use of site and premises.
- D. Work sequence.
- E. Owner occupancy.
- F. Specification Conventions.

1.2 CONTRACT DESCRIPTION

- A. Work of the Project includes:
Proposed interior renovation as indicated on the construction drawings.
- B. This project will be phased as noted below:
 - 1. **Mailroom:** Office and related items should be completed "First".
 - 2. **New Restroom:** Related items should be completed "Second".
 - 3. **New Tenant Space:** Related items should be completed "Third".
- C. Perform Work of Contract under fixed cost contract with Owner in accordance with Conditions of Contract.

1.3 WORK BY OWNER

- A. Work under this contract includes:
 - 1. No work in this project scope is anticipated to be by Owner.

1.4 CONTRACTOR'S USE OF SITE AND PREMISES

- A. Limit use of site and premises to allow:
 - 1. Owner occupancy.
 - 2. Refer to 01 00 00 "General Requirements" for Hours of Work.
 - 3. Use of site and premises by the public.
- B. Emergency Building Exits during Construction.
 - 1. All emergency building exists to be kept clear at all times.

1.5 WORK SEQUENCE

- A. Construct Work in phases to accommodate Owner's occupancy requirements during construction period. Coordinate construction schedule and operations with Owner.
- B. Refer to Notice to Bidders and Bid Proposal Form for anticipated project start date.

1.6 OWNER OCCUPANCY

- A. The Owner will occupy the premises during the entire period of the construction phase of construction.
- B. Cooperate with Owner to minimize conflict, and to facilitate Owner's operations.
- C. Schedule the Work to accommodate Owner occupancy.

1.7 SPECIFICATION CONVENTIONS

- A. These specifications are written in imperative mood and streamlined form. This imperative language is directed to the Contractor, unless specifically noted otherwise. The words “shall be” are included by inference where a colon (:) is used within sentences or phrases.

END OF SECTION

SECTION 01 20 00

PRICE AND PAYMENT PROCEDURES

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Cash allowances.
- B. Contingency allowances.
- C. Testing and inspection allowances.
- D. Schedule of values.
- E. Applications for payment.
- F. Change procedures.
- G. Defect assessment.
- H. Unit prices.
- I. Alternates.

1.2 CASH ALLOWANCES – FOR PERMITS

- A. All Permit fees are by owner
- B. All monies not used for permits shall be credited to the Owner as part of the last application for payment.
- C. Differences in costs will be adjusted by Change Order.
- D. Allowances Schedule: check bid schedule and other sections of the specification.

1.3 CONTINGENCY ALLOWANCES

- A. Include in the Base Bid Contract, a stipulated sum/price, as indicated on the bid proposal form for use upon Owner's instruction for unforeseen items. Any unused funds are to be credited back to the owner.
- B. Contractor's costs for products, delivery, installation, labor, insurance, payroll, taxes, bonding, equipment rental, overhead and profit will be included in Change Orders authorizing expenditure of funds from this Contingency Allowance.
- C. Funds will be drawn from Contingency Allowance only by Change Order.

- D. At closeout of Contract, funds remaining in Contingency Allowance will be credited to Owner by Change Order.

1.4 TESTING AND INSPECTION ALLOWANCES

- A. Provided by owner except as noted in other sections of the specification.
- B. Differences in cost will be adjusted by Change Order.

1.5 SCHEDULE OF VALUES

- A. Submit printed schedule on AIA Form G703 - Continuation Sheet for G702 standard form.
- B. Submit Schedule of Values in duplicate within 15 days after date of Owner-Contractor Agreement established in Notice to Proceed.
- C. Format: Utilize Table of Contents of this Project Manual. Identify each line item with number and title of major specification Section. Identify site mobilization, bonds and insurance, close out, and separate lines for material and labor where applicable.
- D. Include in each line item, amount of Allowances specified in this section. For unit cost Allowances, identify quantities taken from Contract Documents multiplied by unit cost to achieve total for each item.
- E. Include separately from each line item, direct proportional amount of Contractor's overhead and profit.
- F. Revise schedule to list approved Change Orders, with each Application for Payment.

1.6 APPLICATIONS FOR PAYMENT

- A. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
 - 1. List of subcontractors.
 - 2. Schedule of Values.
 - 3. Contractor's Construction Schedule.
 - 4. Products list.
 - 5. Schedule of unit prices.
 - 6. Submittals Schedule.
 - 7. List of Contractor's staff assignments.
 - 8. List of Contractor's principal consultants.
 - 9. Copies of building permits.
 - 10. Initial progress report.
 - 11. Certificate of insurance and insurance policies.
 - 12. Performance and payment bonds.

- B. Final Payment Application: Submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
1. Evidence of completion of Project closeout requirements.
 2. Completion of punchlist items.
 3. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 4. Updated final statement, accounting for final changes to the Contract Sum.
 5. Transmittal of required Project Construction records to the Owner.
 6. Removal of temporary facilities, services, surplus materials, debris, etc.
 7. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
 8. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
 9. AIA Document G707, "Consent of Surety to Final Payment."
 10. Evidence that claims have been settled.
 11. Original County Voucher form marked "Final Payment".
 12. Final, liquidated damages settlement statement.
 13. Prevailing Wage Rate Statement.
 14. One (1) year 100% Maintenance Bond.
 15. All Operation and Maintenance Manuals, Warrantees and Guarantees.
- C. Content and Format: Utilize Schedule of Values for listing items in Application for Payment.
- D. Submit updated monthly construction schedule with each Application for Payment.
- E. Payment Period: Submit at intervals stipulated in the Agreement.
- F. Submit with transmittal letter as specified for Submittals in Section 01 33 00 - Submittal Procedures.
- G. Substantiating Data: When Architect/Engineer requires substantiating information, submit data justifying dollar amounts in question. Include the following with Application for Payment:
1. Current construction photographs.
 2. Partial release of liens from major subcontractors and vendors.
 3. Record documents for review by Owner which will be returned to Contractor.
 4. Affidavits attesting to off-site stored products.
 5. Construction progress schedules revised and current as specified.
- H. The application for payment shall be used by the Owner as a guide for payments based on work completed, with no deviations once payments have started.

1.7 CHANGE PROCEDURES

- A. Submittals: Submit name of individual authorized to receive change documents, and be responsible for informing others in Contractor's employ or Subcontractors of changes to the Work.

- B. The Architect/Engineer will advise of minor changes in the Work not involving adjustment to Contract Sum/Price or Contract Time by issuing supplemental instructions on AIA Form G710.
- C. The Architect/Engineer may issue a Notice of Change including a detailed description of proposed change with supplementary or revised Drawings and specifications, a change in Contract Time for executing the change with stipulation of overtime work required and the period of time during which the requested price will be considered valid]. Contractor will prepare and submit estimate within ten days.
- D. Contractor may propose changes by submitting a request for change to Architect/Engineer, describing proposed change and its full effect on the Work. Include a statement describing reason for the change, and effect on Contract Sum/Price and Contract Time with full documentation [and a statement describing effect on Work by separate or other Contractors]. Document requested substitutions in accordance with specification.
- E. Stipulated Sum/Price Change Order: Based on Notice of Change and Contractor's fixed price quotation or Contractor's request for Change Order as approved by Architect/Engineer.
- F. Unit Price Change Order: For contract unit prices and quantities, the Change Order will be executed on fixed unit price basis. For unit costs or quantities of units of work, which are not pre-determined, execute Work under Construction Change Directive. Work Directive Change. Changes in Contract Sum/Price or Contract Time will be computed as specified for Time and Material Change Order.
- G. Construction Change Directive Work Directive Change: Architect/Engineer may issue directive, on AIA Form G713 Construction Change Directive signed by Owner, instructing Contractor to proceed with change in the Work, for subsequent inclusion in a Change Order. Document will describe changes in the Work, and designate method of determining any change in Contract Sum/Price or Contract Time. Promptly execute change.
- H. Time and Material Change Order: Submit itemized account and supporting data after completion of change, within time limits indicated in Conditions of the Contract. Architect/Engineer will determine change allowable in Contract Sum/Price and Contract Time as provided in Contract Documents.
- I. Maintain detailed records of work done on Time and Material basis. Provide full information required for evaluation of proposed changes, and to substantiate costs for changes in the Work.
- J. Document each quotation for change in cost or time with sufficient data to allow evaluation of quotation.
- K. Change Order Forms: AIA G701 Change Order.
- L. Execution of Change Orders: Architect/Engineer will issue Change Orders for signatures of parties as provided in Conditions of the Contract.
- M. Correlation Of Contractor Submittals:

1. Promptly revise Schedule of Values and Application for Payment forms to record each authorized Change Order as separate line item and adjust Contract Sum/Price.
2. Promptly revise progress schedules to reflect change in Contract Time, revise sub-schedules to adjust times for other items of work affected by the change, and resubmit.
3. Promptly enter changes in Project Record Documents.
4. See General Conditions and Supplementary General Conditions of the Contract for Construction for further information on 1%-line item for Close Out Documentation, and Overhead, Profit and Bonding

1.8 DEFECT ASSESSMENT

- A. Replace the Work, or portions of the Work, not conforming to specified requirements.
- B. If, in the opinion of the Architect/Engineer it is not practical to remove and replace the Work, the Architect/Engineer will direct appropriate remedy or adjust payment.
- C. The defective Work may remain, but unit sum/price will be 50 percent at discretion of Architect/Engineer.
- D. Defective Work will be partially repaired to instructions of Architect/Engineer and unit sum/price will be reduced 50 percent at discretion of Architect/Engineer.
- E. Individual specification sections may modify these options or may identify specific formula or percentage sum/price reduction.
- F. Authority of Architect/Engineer to assess defects and identify payment adjustments, is final.
- G. Non-Payment For Rejected Products: Payment will not be made for rejected products for any of the following:
 1. Products wasted or disposed of in a manner that is not acceptable.
 2. Products determined as unacceptable before or after placement.
 3. Products not completely unloaded from transporting vehicle.
 4. Products placed beyond lines and levels of required Work.
 5. Products remaining on hand after completion of the Work.
 6. Loading, hauling, and disposing of rejected products.

1.9 UNIT PRICES:

1. Not Applicable

1.10 ALTERNATES

1. NONE

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

Not Used.

END OF SECTION

SECTION 01 21 00

ALLOWANCES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements governing allowances.
 - 1. Certain items are specified in the Contract Documents by allowances. Allowances have been established in lieu of additional requirements and to defer selection of actual materials and equipment to a later date when additional information is available for evaluation. If necessary, additional requirements will be issued by Change Order.
- B. Types of allowances include the following:
 - 1. Lump-sum allowances.

1.3 SELECTION AND PURCHASE

- A. At the earliest practical date after award of the Contract, advise Architect of the date when final selection and purchase of each product or system described by an allowance must be completed to avoid delaying the Work.
- B. At Architect's request, obtain proposals for each allowance for use in making final selections. Include recommendations that are relevant to performing the Work.
- C. Purchase products and systems selected by Architect from the designated supplier.

1.4 SUBMITTALS

- A. Submit proposals for purchase of products or systems included in allowances, in the form specified for Change Orders.
- B. Submit invoices or delivery slips to show actual quantities of materials delivered to the site for use in fulfillment of each allowance.
- C. Coordinate and process submittals for allowance items in same manner as for other portions of the Work.

1.5 COORDINATION

- A. Coordinate allowance items with other portions of the Work. Furnish templates as required to coordinate installation.

1.6 LUMP-SUM, UNIT-COST AND QUANTITY ALLOWANCES

- A. Allowance shall include cost to Contractor of specific products and materials ordered by Owner under allowance and shall include freight, and delivery to Project site. Do not include taxes.
- B. Contractor's costs for receiving and handling at Project site, labor, installation, overhead and profit, and similar costs related to products and materials ordered by Owner under allowance shall be included as part of the Contract Sum and not part of the allowance.

1.7 UNUSED MATERIALS

- A. Return unused materials purchased under an allowance to manufacturer or supplier for credit to Owner, after installation has been completed and accepted. Re-stocking charges will be credited to the Contractor only upon submission to the Architect of written documentation on material supplier's invoice or letterhead evidencing amount charged.
 - 1. If requested by Architect, prepare unused material for storage by Owner when it is not economically practical to return the material for credit. If directed by Architect, deliver unused material to Owner's storage space. Otherwise, disposal of unused material is Contractor's responsibility.

PART 2 - PRODUCTS

- A. Refer to drawings and specifications for all product information and requirements.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine products covered by an allowance promptly on delivery for damage or defects. Return damaged or defective products to manufacturer for replacement.

3.2 PREPARATION

- A. Coordinate materials and their installation for each allowance with related materials and installations to ensure that each allowance item is completely integrated and interfaced with related work.

3.3 SCHEDULE OF ALLOWANCES

- A. Allowance for unforeseen site conditions: \$10,000.00
- B. Refer to the Bid Proposal Form for a complete list of all Allowances.

END OF SECTION

SECTION 01 30 00
ADMINISTRATIVE REQUIREMENTS

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Coordination and project conditions.
- B. Preconstruction meeting.
- C. Site mobilization meeting.
- D. Progress meetings.
- E. Pre-installation meetings.
- F. Cutting and patching.
- G. Special procedures.

1.2 COORDINATION AND PROJECT CONDITIONS

- A. Coordinate scheduling, submittals, and Work of various sections of Project Manual to ensure efficient and orderly sequence of installation of interdependent construction elements.
- B. Verify utility requirements and characteristics of operating equipment are compatible with building utilities. Coordinate work of various sections having interdependent responsibilities for installing, connecting to, and placing in service, operating equipment.
- C. Coordinate space requirements, supports, and installation of mechanical and electrical Work indicated diagrammatically on Drawings. Follow routing shown for pipes, ducts, and conduit, as closely as practicable; place runs parallel with lines of building. Utilize spaces efficiently to maximize accessibility for other installations, for maintenance, and for repairs.
- D. In finished areas except as otherwise indicated, conceal pipes, ducts, and wiring within construction. Coordinate locations of fixtures and outlets with finish elements.
- E. Coordinate completion and clean-up of Work of separate sections in preparation for Substantial Completion.
- F. After Owner occupancy of premises, coordinate access to site for correction of defective Work and Work not in accordance with Contract Documents, to minimize disruption of Owner's activities.

1.3 PRECONSTRUCTION MEETING

- A. Owner will schedule meeting after Notice of Award.
- B. Attendance Required: Owner, Architect and Contractor.
- C. Agenda:
 - 1. Execution of Owner-Contractor Agreement.
 - 2. Submission of executed bonds and insurance certificates.
 - 3. Distribution of Contract Documents.
 - 4. Submission of list of Subcontractors, list of products, schedule of values, and progress schedule.
 - 5. Designation of personnel representing parties in Contract and Architect.
 - 6. Procedures and processing of field decisions, submittals, and substitutions, applications for payments, proposal request, Change Orders, and Contract closeout procedures.
 - 7. Scheduling.

- D. Record minutes and distribute copies within two days after meeting to participants, with one copy to Architect, Owner and those affected by decisions made.

1.4 SITE MOBILIZATION MEETING

- A. Architect will schedule meeting at Project site prior to Contractor occupancy.
- B. Attendance Required: Owner, Architect, Construction Manager, Special Consultants, and Contractor, Contractor's Superintendent and major Subcontractors.
- C. Agenda:
 - 1. Use of premises by Owner and Contractor.
 - 2. Owner's requirements.
 - 3. Construction facilities and controls provided by Owner.
 - 4. Temporary utilities provided by Owner.
 - 5. Schedules.
 - 6. Application for payment procedures.
 - 7. Procedures for testing.
 - 8. Procedures for maintaining record documents.
 - 9. Requirements for start-up of equipment.
 - 10. Inspection and acceptance of equipment put into service during construction period.
- D. Record minutes and distribute copies within two days after meeting to participants, with one copy to Architect, Owner and those affected by decisions made.

1.5 PROGRESS MEETINGS

- A. Schedule and administer meetings throughout progress of the Work at maximum bi-monthly intervals.
- B. Make arrangements for meetings, prepare agenda with copies for participants, and preside at meetings.
- C. Attendance Required: Job superintendent, major subcontractors and suppliers, Owner and Architect, as appropriate to agenda topics for each meeting.
- D. Agenda:
 - 1. Review minutes of previous meetings.
 - 2. Review of Work progress.
 - 3. Field observations, problems, and decisions.
 - 4. Identification of problems impeding planned progress.
 - 5. Review of submittals schedule and status of submittals.
 - 6. Review of off-site fabrication and delivery schedules.
 - 7. Maintenance of progress schedule.
 - 8. Corrective measures to regain projected schedules.
 - 9. Planned progress during succeeding work period.
 - 10. Coordination of projected progress.
 - 11. Maintenance of quality and work standards.
 - 12. Effect of proposed changes on progress schedule and coordination.
 - 13. Other business relating to Work.
- E. Record minutes and distribute copies within two days after meeting to participants, with one copy to Architect, Owner and those affected by decisions made.

1.6 PRE-INSTALLATION MEETINGS

- A. When required in individual specification sections, convene pre-installation meetings at Project site prior to commencing work of specific section.
- B. Require attendance of parties directly affecting, or affected by, Work of specific section.

- C. Notify Architect/Engineer four days in advance of meeting date.
- D. Prepare agenda and preside at meeting:
 - 1. Review conditions of installation, preparation and installation procedures.
 - 2. Review coordination with related work.
- E. Record minutes and distribute copies within two days after meeting to participants, with one copy to Architect, Owner and those affected by decisions made.

PART 2 EXECUTION

2.1 CUTTING AND PATCHING

- A. RELATED DOCUMENTS
 - 1. Drawings and General Provisions of Contract, including but not limited to, General and Supplementary Conditions and other Division 1, Specification Sections, apply to work of this Section.
- B. DESCRIPTION OF WORK
 - 1. Definitions: “Cutting and Patching” includes cutting into existing construction to provide for the installation or performance of other Work and subsequent fitting and patching required to restore surfaces to their original conditions.
 - 2. “Cutting and Patching” is performed for coordination of the Work, to uncover work for access or inspection, to obtain samples for testing, to permit alternations to be performed, or for other similar purposes.
 - 3. Cutting and Patching performed during the manufacture of products, or during the initial fabrication, erection or installation processes is not considered to the “Cutting and Patching” under this definition. Drilling of holes to install fasteners and similar operations are also not considered to be “Cutting and Patching”.
- C. QUALITY ASSURANCE
 - 1. Requirements for Structural Work: Do not cut and patch structural work without prior approval of a structural engineer.
 - 2. Operational and Safety Limitations: Do not cut and patch operational elements or safety related components in a manner that would result in a reduction of their capacity to perform in the manner intended, including energy performance, or that would result in increased maintenance, or decreased operational life or decreased safety.
- D. SUBMITTALS
 - 1. Procedural Proposal for Cutting and Patching: Where prior approval of cutting and patching is required, submit proposed procedures for this work well in advance of the time work will be performed and request approval to proceed. Include the following information, as applicable, in the submittal.
 - 2. List products to be used and firms that will perform work.
 - 3. Give dates when work is expected to be performed.
 - 4. List utilities that will be disturbed or otherwise be affected by work, including those that will be relocated and those that will be out-of-service temporarily. Indicate how long utility service will be disrupted.
 - 5. Approval by the Design Consultant or Project Management Firm to proceed with cutting and patching work does not waive the Design Consultant’s or Project Management Firm’s right to later require complete removal and replacement of work found to be cut and patched in an unsatisfactory manner.
- E. MATERIALS
 - 1. General: Except as otherwise indicated, or as directed by the Design Consultant or Project Management Firm, use materials for cutting and patching that are identical to existing materials. If identical materials are not available, or cannot be used, use

materials that fully match existing adjacent surfaces possible with regard to visual effect. Use materials for cutting and patching that will result in equal-or-better performance characteristics.

F. INSPECTION

1. Before cutting, examine the surface to be cut and patched and the conditions under which the work is to be performed. If unsafe or otherwise unsatisfactory conditions are encountered notify Project Management Firm immediately. Execute cutting (including excavation) fitting or patching of work required to: make several parts fit properly; uncover work to provide for installation or ill-timed work; remove and replace defective work; remove and replace work not conforming to requirements of Contract Documents.

G. PREPARATION

1. Temporary Support: To prevent failure provide temporary support of work to be cut.
2. Protection: Protect other work during cutting and patching to prevent damage. Provide protection from adverse weather conditions for that part of the project that may be exposed during cutting and patching operations.

H. PERFORMANCE

1. General: Except as otherwise indicated or as approved by the Design Consultant or Project Management Firm, proceed with cutting and patching at the earliest feasible time and complete work without delay.
2. Cutting: Cut the work using methods that are least likely to damage work to be retained or adjoining work. Where possible review proposed procedures with the original installer; comply with original installer's recommendations.
3. In general, where cutting is required use hand or small power tools designed for sawing or grinding, not hammering and chopping. Cut through concrete and masonry using a cutting machine such as a carborundum saw or core drill to insure a neat hole. Cut holes and slots neatly to size required with minimum disturbance of adjacent work. To avoid marring existing finished surfaces, cut or drill from exposed or finished side into concealed surfaces. Temporarily cover openings when not in use.
4. Comply with requirements of applicable Sections of Division 2 where cutting and patching require excavating and backfilling.
5. Patching: Patch with seams which are durable and as invisible as possible. Comply with specified tolerances for the work.
6. Where feasible, inspect and test patched areas to demonstrate integrity of work.
7. Restore exposed finishes of patched areas and where necessary extend finish restoration into retained adjoining work in a manner which will eliminate evidence of patching and refinishing.
8. Where removal of walls or partitions extends one finished area into another finished area, patch and repair floor and wall surfaces in the new space to provide an even surface of uniform color and appearance, remove existing floor and wall coverings and replace with new materials.
9. Where patch occurs in a smooth painted surface, extend final paint coat over entire unbroken surface containing patch, after patched area has received prime and base coat.

I. CLEANING

1. Thoroughly clean areas and spaces where work is performed or used as access to work. Remove completely, point mortar, oils, putty, and items of similar nature. Thoroughly clean piping, conduit, and similar features before painting or other finishing is applied. Restore damaged pipe covering to its original condition

2.2 SPECIAL PROCEDURES

- A. Materials: As specified in product sections; match existing with new products for patching and extending work.
- B. Employ skilled and experienced installer to perform alteration work.
- C. Cut, move, or remove items as necessary for access to alterations and renovation Work. Replace and restore at completion.
- D. Remove unsuitable material not marked for salvage, including rotted wood, corroded metals, and deteriorated masonry and concrete. Replace materials as specified for finished Work.
- E. Remove debris and abandoned items from area and from concealed spaces.
- F. Prepare surface and remove surface finishes to permit installation of new work and finishes.
- G. Close openings in exterior surfaces to protect existing work from weather and extremes of temperature and humidity.
- H. Remove, cut, and patch Work in manner to minimize damage and to permit restoring products and finishes to original condition.
- I. Refinish existing visible surfaces to remain in renovated rooms and spaces, to renewed condition for each material, with neat transition to adjacent finishes. Coordinate with construction documents.
- J. Where new Work abuts or aligns with existing, provide smooth and even transition. Patch Work to match existing adjacent Work in texture and appearance.
- K. When finished surfaces are cut so that smooth transition with new Work is not possible, terminate existing surface along straight line at natural line of division and submit recommendation to Architect/Engineer for review.
- L. Where change of plane of 1/4 inch or more occurs, request instructions from Architect/Engineer.
- M. Trim existing doors to clear new floor finish. Refinish trim to original condition. Coordinate with construction documents.
- N. Patch or replace portions of existing surfaces which are damaged, lifted, discolored, or showing other imperfections.
- O. Finish surfaces as specified in individual product sections.

END OF SECTION

SECTION 01 32 16

CONSTRUCTION SCHEDULE

PART 1 GENERAL

1.1 DESCRIPTION:

- 1.1.1 Work Included: To assure adequate planning and execution of the work so that the work is completed within the number of calendar days allowed in the contract, and to assist the Owner in appraising the reasonableness of the proposed schedule and in evaluating progress of the work, prepare and maintain the schedules and reports described in this section.
- 1.1.2 Definitions: "Day" used throughout the contract, unless otherwise stated, means "Calendar Day".

1.2 QUALITY ASSURANCE:

- 1.2.1 Qualifications of Scheduling Personnel: Employ a scheduler who is thoroughly trained and experienced in compiling construction schedule data, in analyzing by use of Critical Path Method or PERT, and in preparation and issue of periodic reports as required below.
- 1.2.2 Reference Standards: Perform all data preparation, analysis, charting and updating in accordance with all recommendations contained in the current edition of "CPM in Construction" Manual of Associate General Contractors, or in accordance with other standards approved by the State.
- 1.2.3 Reliance Upon Approved Schedule:
- 1.2.4 The construction schedule as approved by the Owner will be an integral part of the Contract and will establish interim Contract Completion dates for the various activities.
- 1.2.5 Should any activity not be completed within fifteen (15) days after the stated scheduled date, the Owner shall have the right to order the Contractor to expedite completion of the activity by whatever means the Owner deems appropriate and necessary, without additional compensation to the Contractor.
- 1.2.6 Should any activity be thirty (30) or more days behind schedule, the Owner shall have the right to perform the activity or have activity performed by whatever method the Owner deems appropriate.
- 1.2.7 Costs incurred by the Owner in connection with expediting construction activity under this Article shall be reimbursed to the Owner by the Contractor.
- 1.2.8 It is expressly understood and agreed that failure by the Owner to exercise the option to either order the Contractor to expedite an activity or to expedite the activity by other means shall not be considered precedent setting for any other activities.

1.3 SUBMITTALS:

- 1.3.1 General: Comply with the provisions of Section 013000.
- 1.3.2 Preliminary Analysis: Within ten (10) days after receipt of Notice to Proceed, submit one (1) reproducible copy and four (4) prints of a preliminary construction schedule, plus four (4) prints of proposed format or Materials Status Reports, prepared in accordance with Part Three of this Section.
- 1.3.3 Construction Schedule: Within twenty (20) days after receipt of Notice to Proceed, submit one (1) reproducible and four (4) prints of construction schedule prepared in accordance with Part Three of this Section. Update the construction schedule on a monthly basis.
- 1.3.4 Periodic Report:
- 1.3.5 On the first working day of each month following submittal described in Paragraph 1.3 above, submit four (4) prints of the construction schedule updated as described in Part Three of this Section.
- 1.3.6 Accompanying each periodic submittal of construction schedule, submit four (4) prints of the Materials Status Reports updated as described in Part Three of this Section.

PART 2 PRODUCTS

2.1 CONSTRUCTION ANALYSIS:

- 2.1.1 Diagram: Graphically show the order and interdependence of all activities necessary to complete the work, and the sequence in which each activity is to be accomplished, as planned by the Contractor and his project field superintendent in coordination with all subcontractors whose work is shown on the diagram. Activities shown on the diagram shall include, but are not necessarily limited to:
 - a. Project mobilization;
 - b. Submittals and approvals of Shop Drawings and Samples;
 - c. Procurement of equipment and critical materials;
 - d. Fabrication of special material and equipment, and their installation and testing;
 - e. Final cleanup;
 - f. Final inspection and testing;
 - g. All activities by the governing agencies that affect progress, required dates for completion, or both, for all and for each part of the work.
- 2.1.2 The detail of information shall be such that duration times of activities shall normally range from one (1) to fifteen (15) days. The selection and number of activities shall be subject to the Owner's approval.
- 2.1.3 Show on the diagram, as a minimum for each activity, preceding and following event numbers, description of each activity, and cost and activity duration in calendar days. Submit diagram on a sheet 75 cm (30") high by the width required.

- 2.2 Mathematical Analysis: Furnish a mathematical analysis of the diagram by manual or computer-aided means, including a tabulation of each activity. Show the following information as a minimum for each activity:
- a. Preceding and following event number;
 - b. Activity descriptions;
 - c. Earliest start date (by calendar date);
 - d. Latest start date (by calendar date);
 - e. Earliest finish date (by calendar date);
 - f. Latest finish date (by calendar date);
 - g. Slack or float (by calendar days);
 - h. Monetary value of the activity;
 - i. Percentage of activity completed;
 - j. Contractor's earnings based on portion of activity completed.
- 2.2.1 The means used in making the mathematical analysis shall be capable of compiling the total value of completed and partially completed activities, and be capable of accepting modifications approved for time and logic adjustments.
- 2.3 Periodic Reports: If computer-aided means are used, list the activities in computer printout sorts as follows:
- a. By the preceding event number from lowest to highest, and then in order of the following event numbers;
 - b. By the amount of float, then in order of preceding event numbers, and then in order of succeeding event numbers.
 - c. In order of preceding event numbers, and then in order of succeeding event numbers (show the dollar amount and dollars spent to date for each activity);
 - d. Other sorts requested by the Owner, for which the Contractor will be reimbursed in accordance with the General Conditions provisions for "Changes."
- 2.4 MATERIAL STATUS REPORTS:
- 2.4.1 Format: The Contractor's standard materials status report form will be acceptable if, in Architect's judgment, it provides sufficient pertinent data to determine that materials procurement flow is adequate for all needs of the work.
- 2.4.2 Content: Show at least the following information:
- 2.4.3 Item Description, listed in accordance with Specifications Section Number in which the item is called for:
- 2.4.4 Purchase Order Number and Date of Issue:
- 2.4.5 Vendor Name:
- 2.4.6 Date Shipped and Shipping Means Utilized:
- 2.4.7 Estimated Date of Arrival at Job Site.

- 2.4.8 Actual Date of Arrival at Job Site, and Receiving Report Number.
- 2.5 Data Processing: Process the data by manual or computer-aided methods, but to a degree of promptness and accuracy assuring complete display of all pertinent current information at date of each periodic report.

PART 3 EXECUTION

3.1 PRELIMINARY ANALYSIS:

3.1.1 Contents:

- a. Show all activities of the Contractor under this work for the period between receipt of Notice to Proceed and Submittal of Construction Schedule required as noted above.
- b. Show the Contractor's general approach to remainder of the work.
- c. Show cost of all activities scheduled for performance before submittal and approval of the construction schedule.

3.1.2 Submittals shall be in accordance with Paragraphs.

- 3.2 CONSTRUCTION SCHEDULE: As soon as practicable after receipt of Notice to Proceed, complete the Construction Analysis described in Article 2.1 above, in preliminary form. Meet with the Architect and construction manager to review contents of proposed construction schedule, and make all revisions agreed upon. Submit in accordance with Paragraph 1.3 above.

- 3.3 MATERIAL STATUS REPORT: As soon as practicable after receipt of Notice to Proceed, meet with the State, review contents of proposed Materials Status Reports, and make all revisions to format agreed upon.

3.4 PERIODIC REPORTS:

3.4.1 Construction Schedule, Contents:

- a. Report actual progress by updating the mathematical analysis.
- b. Note on the summary report, or clearly show on a revised issue of affected portions of the detailed diagram, all revisions causing changes in the detailed program.
- c. Revise the summary report as necessary for clarity.
- d. Show activities or portions of activities completed during the reporting period and their actual value.
- e. State the percentage of work actually completed and schedule as the report date, and the progress along the critical path in terms of days ahead of or behind the allowable dates.
- f. If the work is behind schedule, also report progress along other paths with negative slack.
- g. Include a narrative report which shows, but is not necessarily limited to:
 - i. A description of the problem areas, current and anticipated;
 - ii. Delaying factors, and their impact;
 - iii. An explanation of corrective actions taken or proposed.

- 3.4.2 Show the date of latest revision. Submit in accordance with the provisions above.
- 3.5 Materials Status Reports:
 - 3.5.1 On the letter of transmittal accompanying periodic reports, on an accompanying summary sheet, or by other means acceptable to the Architect, clearly indicate those items the delivery of which are critically overdue or otherwise hazardous to maintenance of the approved schedule.
 - 3.5.2 Submit in accordance with the provisions above.
- 3.6 REVISIONS: Make only those revisions to approved Construction Schedule and approved Materials Status Reports as are approved in advance by the Architect.

PART 4 SUBMISSION

- 4.1 SUBMISSION: A progress schedule shall be updated monthly by the General Contractor, with coordination of the other prime contractors (as required). This updated schedule shall be submitted to the Architect at the first job meeting and each meeting thereafter. If schedule is not submitted, request for payment may be withheld.

END OF SECTION

SECTION 01 33 00
SUBMITTAL PROCEDURES

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Submittal procedures.
- B. Construction progress schedules.
- C. Proposed products list.
- D. Product data.
- E. Shop drawings.
- F. Samples.
- G. Design data.
- H. Test reports.
- I. Certificates.
- J. Manufacturer's instructions.
- K. Manufacturer's field reports.
- L. Erection drawings.

1.2 SUBMITTAL PROCEDURES

- A. Transmit each submittal with AIA Form G810.
- B. Sequentially number transmittal forms. Mark revised submittals with original number and sequential alphabetic suffix.
- C. Identify Project, Contractor, subcontractor and supplier, pertinent drawing and detail number, and specification section number, appropriate to submittal.
- D. Apply Contractor's stamp, signed or initialed certifying that review, approval, verification of products required, field dimensions, adjacent construction Work, and coordination of information is in accordance with requirements of the Work and Contract Documents.
- E. Schedule submittals to expedite Project, and deliver to Architect at business address. Coordinate submission of related items.
- F. For each submittal for review, allow 15 days excluding delivery time to and from Contractor.
- G. Identify variations from Contract Documents and product or system limitations which may be detrimental to successful performance of completed Work.
- H. Allow space on submittals for Contractor and Architect review stamps.
- I. When revised for resubmission, identify changes made since previous submission.
- J. Distribute copies of reviewed submittals as appropriate. Instruct parties to promptly report inability to comply with requirements.
- K. Submittals not requested will not be recognized or processed.

1.3 CONSTRUCTION PROGRESS SCHEDULES

- A. Submit initial schedules within 20 days after date of Owner-Contractor Agreement. After review, resubmit required revised data within ten days.
- B. Submit revised Progress Schedules with each Application for Payment.
- C. Distribute copies of reviewed schedules to Project site file, subcontractors, suppliers and other concerned parties.
- D. Instruct recipients to promptly report, in writing, problems anticipated by projections indicated in schedules.
- E. Submit computer generated horizontal bar chart with separate line for each section of Work, identifying first workday of each week.
- F. Show complete sequence of construction by activity, identifying Work of separate stages and other logically grouped activities. Indicate early and late start, early and late finish, float dates, and duration.
- G. Indicate estimated percentage of completion for each item of Work at each submission.
- H. Submit separate schedule of submittal dates for shop drawings, product data and samples, including dates reviewed submittals will be required from Architect. Indicate decision dates for selection of finishes.
- I. Revisions To Schedules:
 - 1. Indicate progress of each activity to date of submittal, and projected completion date of each activity.
 - 2. Identify activities modified since previous submittal, major changes in scope, and other identifiable changes.
 - 3. Prepare narrative report to define problem areas, anticipated delays, and impact on Schedule. Report corrective action taken, or proposed, and its effect.

1.4 PROPOSED PRODUCTS LIST

- A. Within 20 days after date of Owner-Contractor Agreement, submit list of major products proposed for use as indicated on drawings and specifications, with name of manufacturer, trade name, model number of each product and specification section.
- B. For products specified only by reference standards, give manufacturer, trade name, model or catalog designation and reference standards.

1.5 PRODUCT DATA

- A. Product Data: Submit to Architect for review for limited purpose of checking for conformance with information given and design concept expressed in Contract Documents.
- B. All submittals shall be submitted electronically to the Architect & Construction Manager (as applicable). An electronic copy will be returned to the Contractor for his use.
- C. Mark each submittal to identify applicable products, models, options, and other data. Supplement manufacturers' standard data to provide information specific to this Project.
- D. Indicate product utility and electrical characteristics, utility connection requirements and location of utility outlets for service for functional equipment and appliances.
- E. After review, produce copies and distribute in accordance with SUBMITTAL PROCEDURES article and for record documents described in Section 017000.

1.6 SHOP DRAWINGS

- A. Shop Drawings: Submit to Architect for review for limited purpose of checking for conformance with information given and design concept expressed in Contract Documents.
- B. Indicate special utility and electrical characteristics, utility connection requirements and location of utility outlets for service for functional equipment and appliances.
- C. When required by individual specification sections, provide shop drawings signed and sealed by professional engineer responsible for designing components shown on shop drawings.
 - 1. Include signed and sealed calculations to support design.
 - 2. Submit drawings and calculations in form suitable for submission to and approval by authorities having jurisdiction.
 - 3. Make revisions and provide additional information when required by authorities having jurisdiction.
 - 4. All submittals shall be submitted electronically to the Architect & Construction Manager (as applicable). An electronic copy will be returned to the Contractor for his use.
 - 5. Shop drawing review is based on submission of specified items as indicated in the construction documents and specifications. Product substitutions are allowed and must be substantiated and verified by filling out Yezzi Associates "Proposed Substitution Certification" form included in the bid submission package. Architects shop drawing review is limited to one submission per product - subsequent submission and review time for some product or substitution review time incurred by the architect will be billed to the general contractor at a rate of \$100/hr. Additional review time due to resubmissions specifically requested by the architect in order to finalize product submission and conformance with construction documents and design intent will not incur any additional charges.
- D. After review, produce copies and distribute in accordance with SUBMITTAL PROCEDURES article and for record documents described in Section 017000.

1.7 SAMPLES

- A. Samples: Submit to Architect for review for limited purpose of checking for conformance with information given and design concept expressed in Contract Documents.
- B. Samples For Selection as Specified in Product Sections:
 - 1. Submit to Architect for aesthetic, color or finish selection.
 - 2. Submit samples of finishes from full range of manufacturers' standard colors, textures and patterns for Architect selection.
- C. Submit samples to illustrate functional and aesthetic characteristics of Products, with integral parts and attachment devices. Coordinate sample submittals for interfacing work.
- D. Include identification on each sample, with full Project information.
- E. Submit number of samples specified in individual specification sections; Architect will retain one sample.
- F. Reviewed samples which may be used in the Work are indicated in individual specification sections.

- G. Samples will not be used for testing purposes unless specifically stated in specification section.
 - H. After review, produce duplicates and distribute in accordance with SUBMITTAL PROCEDURES article and for record documents purposes described in Section 017000.
- 1.8 DESIGN DATA
- A. Submit for Architect's knowledge as contract administrator or for Owner.
 - B. Submit for information for limited purpose of assessing conformance with information given and design concept expressed in Contract Documents.
- 1.9 TEST REPORTS
- A. Submit for Architect's knowledge as contract administrator or for Owner.
 - B. Submit test reports for information for limited purpose of assessing conformance with information given and design concept expressed in Contract Documents.
- 1.10 CERTIFICATES
- A. When specified in individual specification sections, submit certification by manufacturer, installation/application subcontractor, or Contractor to Architect, in quantities specified for Product Data.
 - B. Indicate material or product conforms to or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.
 - C. Certificates may be recent or previous test results on material or Product, but must be acceptable to Architect/Engineer.
- 1.11 MANUFACTURER'S INSTRUCTIONS
- A. When specified in individual specification sections, submit printed instructions for delivery, storage, assembly, installation, adjusting and finishing, to Architect for delivery to Owner in quantities specified for Product Data.
 - B. Indicate special procedures, perimeter conditions requiring special attention, and special environmental criteria required for application or installation.
- 1.12 MANUFACTURER'S FIELD REPORTS
- A. Submit reports for Architect's benefit as contract administrator or for Owner.
 - B. Submit report in duplicate within 5 days of observation to Architect for information.
 - C. Submit for information for limited purpose of assessing conformance with information given and design concept expressed in Contract Documents.
- 1.13 ERECTION DRAWINGS
- A. Submit drawings for Architect's benefit as contract administrator or for Owner.
 - B. Submit for information for limited purpose of assessing conformance with information given and design concept expressed in Contract Documents.
 - C. Data indicating inappropriate or unacceptable Work may be subject to action by Architect or Owner.

1.14 PERMIT APPLICATION

- A. The Contractor shall apply for all required permits. The Owner shall be copied all permit applications.
- B. The Owner will pay for all permits. The Contractor shall pay for all permits and be reimbursed by the Owner.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

Not Used.

END OF SECTION

SECTION 01 33 23

SHOP DRAWINGS, PRODUCT DATA, SAMPLES & PHOTOGRAPHS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary conditions and other Division-1 Specification sections, apply to work of this section.

1.2 DESCRIPTION OF REQUIREMENTS

- A. General: This section specifies procedural requirements for non-administrative submittals including shop drawings, product data, samples and other miscellaneous work-related submittals. Shop drawings, product data, samples and other work-related submittals are required to amplify, expand and coordinate the information contained in the Contract Documents.
- B. Refer to other Division-1 Sections and other contract documents for specifications on administrative, non-work-related submittals. Such submittals include, but are not limited to the following items:
 - 1. Permits
 - 2. Payment applications
 - 3. Performance and payment bonds.
 - 4. Insurance certificates
 - 5. Inspection and test reports
 - 6. Schedule of values
 - 7. Progress reports
 - 8. Listing of subcontractors.
- C. Shop drawings are technical drawings and data that have been specially prepared for this project, including but not limited to the following items:
 - 1. Fabrication and installation drawings
 - 2. Setting diagrams
 - 3. Shopwork manufacturing instructions
 - 4. Templates
 - 5. Patterns
 - 6. Coordination drawings (for use on-site)
 - 7. Schedules
 - 8. Design mix formulas
 - 9. Contractor's engineering calculations
- D. Standard information prepared without specified reference to a project is not considered to be shop drawings.
- E. Product data includes standard printed information on manufactured products that has not been specially-prepared for this project, including but not limited to the following items:
 - 1. Manufacturer's product specifications and installation instructions.
 - 2. Standard color charts.
 - 3. Catalog cuts
 - 4. Roughing-in diagram and templates
 - 5. Standard wiring diagrams

6. Printed performance curves
 7. Operational range diagrams
 8. Mill reports
 9. Standard product operating and maintenance manuals
- F. Samples are physical examples of work, including but not limited to the following items.
1. Partial sections of manufactured or fabricated work
 2. Small cuts or containers of materials
 3. Complete units of repetitively-used materials
 4. Swatches showing color, texture and pattern
 5. Color range sets
 6. Units of work to be used for independent inspection and testing
- G. Mock-ups are special forms of samples, which are too large or otherwise inconvenient for handling in the manner specified for transmittal of sample submittals.
- H. Miscellaneous submittals are work-related, non-administrative submittals that do not fit in the three previous categories, including, but not limited to the following:
1. Specially-prepared and standard printed warranties
 2. Maintenance agreements
 3. Workmanship bonds
 4. Survey data and reports
 5. Project photographs
 6. Testing and certification reports
 7. Record drawings
 8. Field measurement data
 9. Operating and maintenance manuals
 10. Keys and other security protection devices
 11. Overrun stock

1.3 SUBMITTAL PROCEDURES:

- A. General: Refer to the General Conditions for basic procedures for submittal handling.
1. Coordination: Coordinate the preparation and processing of submittals with the performance of the work. Coordinate each separate submittal with other submittals and related activities such as testing, purchasing fabrication, delivery and similar activities that require sequential activity.

Coordinate the submittal of different units of interrelated work so that one submittal will not be delayed by the Architect/Engineer's need to review a related submittal requiring coordination with other submittals until related submittals are forthcoming.
 2. Coordination of Submittal Times: Prepare and transmit all submittals to the architect/Engineer within seven (7) days of Notice of Award Notice to Proceed period. Transmit different kinds of submittals for the same unit of work so that processing will not be delayed by the Architect/Engineer's need to review submittals concurrently for coordination.
 3. Review Time: Allow sufficient time within the fourteen (14) days period so that the installation will not be delayed as a result of the time required to properly process submittals, including time for re-submittal, if necessary. Advise the Architect/Engineer on each submittal, as to whether processing time is critical to the progress of the work, and if the work would be expedited if processing time could be shortened.

Allow two weeks for the Architect/Engineer's initial processing of each submittal. Allow a longer time period where processing must be delayed for coordination with subsequent submittals. The architect/Engineer will advise the contractor promptly when it is determined that a submittal being processed must be delayed for coordination.

No extension of time will be authorized because of the contractor's failure to transmit submittals to the Architect/Engineer sufficiently in advance of the work.

4. Submittal Preparation: Mark each submittal with a permanent label for identification. Provide the following information on the label for proper processing and recording of action taken.
 - a. Project name
 - b. Date
 - c. Name and address of Contractor
 - d. Name and address of sub-contractor
 - e. Name and address of supplier
 - f. Name of manufacturer
 - g. Number and title of appropriate specification section
 - h. Drawing number and detail references, as appropriate
 - i. Similar definitive information as necessaryProvide a space on the label for the Contractor review and approval markings, and a space for the Architect/Engineer's "Action" marking.
5. Submittal Transmittal: Package each submittal appropriately for transmittal and handling. Transmit each submittal from the Contractor to the architect/Engineer, and to other destinations as indicated, by use of a transmittal form. Submittals received from sources other than the Contractor will be returned to the sender "without action".
6. Transmittal Form: Provide on the form places for the following information:
 - a. Project name
 - b. Date
 - c. To
 - d. From
 - e. Category and type of submittal
 - f. Submittal purpose and description
 - g. Submittal and transmittal distribution records
 - h. Signature of transmitter

Contractor's certification stating that the information submitted complies with the requirements of the Contract Documents, with a place for the Contractor's signature.

Record relevant information and requests for data on the transmittal form. On the transmittal form, or on a separate sheet attached to the form, record deviations from the requirements of the Contract Documents, if any, including minor variations and limitations.

1.4 SPECIFIC SUBMITTAL REQUIREMENTS:

- A. General: Specific submittal requirements for individual units of work are specified in the applicable specification section. Except as otherwise indicated in the individual specification sections, comply with the requirements specified herein for each type of submittal.

Where it is necessary to provide intermediate submittals between the initial and final submittals, provide and process intermediate submittals in the same manner as for initial submittals.

- B. Shop Drawings: Information required on shop drawings includes, dimensions, identification of specific products and materials, which are included in the work, compliance with specified standards and notations of coordination requirements with other work. Provide special notation of dimensions that have been established by field measurement. Deviations, modifications, additions or deletions from the contract documents must be specifically called out on the shop drawings by way of a cloud, note or request for review or clarification.

Do not permit shop drawings copies without an appropriate final "Action" marking by the Architect/Engineer to be used in connection with the work.

Preparation: Submit newly prepared information, drawn to accurate scale on sheets not less than 8 – 1/2" x 11"; except for actual pattern or template type drawings, the maximum sheet size shall not exceed 36" x 48". Indicate the name of the firm that prepared each shop drawing and provide appropriate project identification in the title block. Provide a space not less than 20 sq. in. beside the title block for marking the record of the review process and the Architect/Engineer's "Action" marking.

Do not reproduce contract documents or copy standard printed information as the basis of shop drawings.

- C. Initial Submittal: Provide one correctable translucent reproducible print and one blue-line or black-line print; the reproducible print will be returned.
- D. Product Data: General information required specifically as product data includes manufacturer's standard printed recommendations for application and use, compliance with recognized standards of trade associates and testing agencies, and the application of their labels and seals (if any), special notation of dimensions which have been verified by way of field measurement, and special coordination requirements for interfacing the material, product or system with other work.
- E. Samples: Submit samples for the Architect/Engineer's visual review of general generic kind, color, pattern, and texture, and for a final check of the coordination of these characteristics with other related elements of the work. Samples are also submitted for quality control comparison of these characteristics between the final sample submittal and the actual work as it is delivered and installed.

Refer to individual work sections of these specifications for additional sample requirements, which may be intended for examination or testing of additional characteristics. Compliance with other required characteristics is the exclusive responsibility of the Contractor; such as, compliance is not considered in the Architect/Engineer's review and "Action" indication of sample submittals.

Documentation required specifically for sample submittals, includes a generic description of the sample, the sample source or the product name or manufacturer, compliance with governing regulations and recognized standards. In addition, indicate limitations in terms of availability, sizes, delivery time, and similar limiting characteristics.

Refer to individual sections of these specifications for samples, which, because of their relatively high cost or other special considerations, are intended to be returned to the Contractor for incorporation in the work. Such samples must be in an undamaged condition at the time of use. On

the transmittal form to the Architect/Engineer, indicate such special requests regarding the disposition of sample submittals.

- F. Submittal: At the Contractor's option, and depending upon the nature of the anticipated response from the Architect/engineer, the initial submittal of samples may be either a preliminary submittal or a final submittal.
- G. Preliminary submittal, of a single set of samples, is required where requirements indicate the Architect/Engineer's selection of color, pattern, texture or similar characteristics from a manufacturer's range of standard choices is necessary. Preliminary submittals will be reviewed and returned with the Architect/Engineer's "Action" marking.
- H. Final Submittals: Submit 3 sets of samples in the final submittal, one set will be returned.

1.5 MISCELLANEOUS SUBMITTALS:

- A. Inspection and Test Reports: Classify each inspection and test report as being either "shop drawings" or "product data" depending on whether the report is specially prepared for the project, or a standard publication of workmanship control testing at the point of production. Process inspection and test reports accordingly.
- B. Warranties: Refer to section "Products and Substitutions" for specific general requirements on warranties, product bonds, workmanship bonds and maintenance agreement. In addition to copies desired for the Contractor's use, furnish 2 executed copies of such warranties, bonds or agreements. Provide 2 additional copies where required for maintenance manuals.
- C. Project Photographs: The lead Contractor shall furnish 2 prints each of 3 project photographs at monthly intervals and at completion of project 2 prints each of 4 interior and 4 exterior photographs. Comply with Architect/Engineer's direction concerning desired vantage points for shots.

Photographs shall be 8" x 10" glossy color prints on single-weight commercial grade stock, with extra 3/4" wide margin punched for standard 3-ring binder and a copy of negatives. Identify each print on the backside with name and address of photographer, name of project, date of shot and description of vantage point. Also provide final photographs on compact disks, digital video disks, USB thumb drives or SD cards using JPEG file format.
- D. Survey Data: Refer to Section 010000 "General Requirements" for specific general requirements on property surveys, field measurements, quantitative records of actual work, damage surveys and similar data required by the individual sections of these specifications. None of the specified copies will be returned.
- E. Survey Copies: Furnish 2 copies of general survey data. Provide 10 copies of the final property survey.
- F. Records of Actual Work: Furnish 4 copies of records of actual work, one of which will be returned for inclusion in the record documents as specified in Section 017000.
- G. Closeout Submittals: Refer to Section 017000 and to individual sections of these specifications for specific submittal requirements of project closeout information, materials, tools, and similar items.

1.6 ARCHITECT/ENGINEER'S ACTION:

Action stamp: The Architect/Engineer will stamp each submittal to be returned with a uniform, self explanatory action stamp, approximately marked and executed to indicate whether the submittal returned is for a) unrestricted use, b) final-but-restricted use or c) must be revised and resubmitted; or d) without action (as explained on the transmittal form).

- A. Final Unrestricted Release: Where the submittals are marked as follows, the work covered by the submittal may proceed provided it complies with the requirements of the contract documents; acceptance of the work will depend upon that compliance.
Marking: “NO EXCEPTIONS TAKEN”
- B. Final-But-Restricted-Release: When the submittals are marked as follows, the work covered by the submittal may proceed provided it complies with both the Architect/Engineer’s notations or corrections on the submittals and with the requirements of the contract documents; acceptance of the work will depend on that compliance.
Marking: “EXCEPTION TAKEN AS NOTED”
- C. Returned for re-submittal: when the submittal is marked as follows, do not proceed with the work covered by the submittal, including purchasing, fabrication, delivery or other activity. Revise the submittal or prepare a new submittal in accordance with the Architect/Engineer’s notations stating the reasons for returning the submittal; resubmit the submittal without delay. Repeat if necessary to obtain a different action marking. Do not permit submittals with the following marking to be used at the project site, or else where work is in progress.
Marking “REVISE AND RESUBMIT”
- D. Other Action: Where the submittal is returned, marked with the Architect/Engineer’s explanation, for special processing or other Contractor activity, or is primarily for information or record purposes, the submittal will be marked.

PART 2 – PRODUCTS (Not Applicable)

PART 3 – EXECUTION (Not Applicable)

END OF SECTION.

SECTION 01 40 00
QUALITY REQUIREMENTS

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Quality control and control of installation.
- B. Tolerances
- C. References.
- D. Mock-up requirements.
- E. Testing and inspection services.
- F. Manufacturers' field services.
- G. Examination.
- H. Preparation.

1.2 QUALITY CONTROL AND CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce Work of specified quality.
- B. Comply with manufacturers' instructions, including each step-in sequence.
- C. When manufacturers' instructions conflict with Contract Documents, request clarification from Architect/Engineer before proceeding.
- D. Comply with specified standards as minimum quality for the Work except where more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
- E. Perform Work by persons qualified to produce required and specified quality.
- F. Verify field measurements are as indicated on Shop Drawings or as instructed by manufacturer.
- G. Secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion, or disfigurement.

1.3 TOLERANCES

- A. Monitor fabrication and installation tolerance control of products to produce acceptable Work. Do not permit tolerances to accumulate.
- B. Comply with manufacturers' tolerances. When manufacturers' tolerances conflict with Contract Documents, request clarification from Architect/Engineer before proceeding.
- C. Adjust products to appropriate dimensions; position before securing products in place.

1.4 REFERENCES

- A. For products or workmanship specified by association, trades, or other consensus standards, comply with requirements of standard, except when more rigid requirements are specified or are required by applicable codes.
- B. Conform to reference standard by date of issue current on date of Contract Documents, except where specific date is established by code.
- C. Obtain copies of standards where required by product specification sections.

- D. When specified reference standards conflict with Contract Documents, request clarification from Architect/Engineer before proceeding.
- E. Neither contractual relationships, duties, nor responsibilities of parties in Contract nor those of Architect/Engineer shall be altered from Contract Documents by mention or inference otherwise in reference documents.

1.5 MOCK-UP REQUIREMENTS

- A. Tests will be performed under provisions identified in this section and identified in respective product specification sections.
- B. Assemble and erect specified items with specified attachment and anchorage devices, flashings, seals, and finishes.
- C. Accepted mock-ups shall be comparison standard for remaining Work.
- D. Where mock-up has been accepted by Architect/Engineer and is specified in product specification sections to be removed; remove mock-up and clear area when directed to do so by Architect/Engineer.

1.6 TESTING AND INSPECTION SERVICES

- A. Employ and pay for services of an independent testing agency or laboratory acceptable to Owner to perform specified testing.
 - 1. Prior to start of Work, submit testing laboratory name, address, and telephone number, and names of full-time registered Engineer and responsible officer.
 - 2. Submit copy of report of laboratory facilities inspection made by Materials Reference Laboratory of National Bureau of Standards during most recent inspection, with memorandum of remedies of deficiencies reported by inspection.
- B. The independent firm will perform tests, inspections and other services specified in individual specification sections and as required by Architect/Engineer and authority having jurisdiction.
 - 1. Laboratory: Authorized to operate at Project location.
 - 2. Laboratory Staff: Maintain full time registered Engineer specialist on staff to review services.
 - 3. Testing Equipment: Calibrated at reasonable intervals with devices of accuracy traceable to National Bureau of Standards or accepted values of natural physical constants.
- C. Testing, inspections and source quality control may occur on or off project site. Perform off-site testing as required by Architect/Engineer or Owner.
- D. Reports will be submitted by independent firm to Architect/Engineer and Contractor, in duplicate, indicating observations and results of tests and indicating compliance or non-compliance with Contract Documents.
- E. Cooperate with independent firm; furnish samples of materials, design mix, equipment, tools, storage, safe access, and assistance by incidental labor as requested.
 - 1. Notify Architect/Engineer and independent firm 36 hours prior to expected time for operations requiring services.
 - 2. Make arrangements with independent firm and pay for additional samples and tests required for Contractor's use.
- F. Testing and employment of testing agency or laboratory shall not relieve Contractor of obligation to perform Work in accordance with requirements of Contract Documents.
- G. Re-testing or re-inspection required because of non-conformance to specified requirements shall be performed by same independent firm on instructions by Architect/Engineer. Payment for re-

testing or re-inspection will be charged to Contractor by deducting testing charges from Contract Sum/Price.

- H. Agency Responsibilities:
 - 1. Test samples of mixes submitted by Contractor.
 - 2. Provide qualified personnel at site. Cooperate with Architect/Engineer and Contractor in performance of services.
 - 3. Perform specified sampling and testing of products in accordance with specified standards.
 - 4. Ascertain compliance of materials and mixes with requirements of Contract Documents.
 - 5. Promptly notify Architect/Engineer and Contractor of observed irregularities or non-conformance of Work or products.
 - 6. Perform additional tests required by Architect/Engineer.
 - 7. Attend preconstruction meetings and progress meetings.
- I. Agency Reports: After each test, promptly submit 3 copies of report to Architect/Engineer and to Contractor. When requested by Architect/Engineer, provide interpretation of test results. Include the following:
 - 1. Date issued.
 - 2. Project title and number.
 - 3. Name of inspector.
 - 4. Date and time of sampling or inspection.
 - 5. Identification of product and specifications section.
 - 6. Location in Project.
 - 7. Type of inspection or test.
 - 8. Date of test.
 - 9. Results of tests.
 - 10. Conformance with Contract Documents.
- J. Limits On Testing Authority:
 - 1. Agency or laboratory may not release, revoke, alter, or enlarge on requirements of Contract Documents.
 - 2. Agency or laboratory may not approve or accept any portion of the Work.
 - 3. Agency or laboratory may not assume duties of Contractor.
 - 4. Agency or laboratory has no authority to stop the Work.

1.7 MANUFACTURERS' FIELD SERVICES

- A. When specified in individual specification sections, require material or product suppliers or manufacturers to provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, quality of workmanship, start-up of equipment, test, adjust and balance of equipment as applicable, and to initiate instructions when necessary.
- B. Submit qualifications of observer to Architect/Engineer 30 days in advance of required observations. Observer subject to approval of Architect/Engineer.
- C. Report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions.
- D. Refer to Section 01 33 00 - Submittal Procedures, MANUFACTURERS' FIELD REPORTS article.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify existing site conditions and substrate surfaces are acceptable for subsequent Work. Beginning new Work means acceptance of existing conditions.
- B. Verify existing substrate is capable of structural support or attachment of new Work being applied or attached.
- C. Examine and verify specific conditions described in individual specification sections.
- D. Verify utility services are available, of correct characteristics, and in correct locations.

3.2 PREPARATION

- A. Clean substrate surfaces prior to applying next material or substance.
- B. Seal cracks or openings of substrate prior to applying next material or substance.
- C. Apply manufacturer required or recommended substrate primer, sealer, or conditioner prior to applying new material or substance in contact or bond.

END OF SECTION

SECTION 01 60 00
PRODUCT REQUIREMENTS

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Products.
- B. Product delivery requirements.
- C. Product storage and handling requirements.
- D. Product options.
- E. Product substitution procedures.
- F. Equipment electrical characteristics and components.

1.2 PRODUCTS

- A. Furnish products of qualified manufacturers suitable for intended use. Furnish products of each type by single manufacturer unless specified otherwise.
- B. Do not use materials and equipment removed from existing premises, except as specifically permitted by Contract Documents.
- C. Furnish interchangeable components from same manufacturer for components being replaced.

1.3 PRODUCT DELIVERY REQUIREMENTS

- A. Transport and handle products in accordance with manufacturer's instructions.
- B. Promptly inspect shipments to ensure products comply with requirements, quantities are correct, and products are undamaged.
- C. Provide equipment and personnel to handle products by methods to prevent soiling, disfigurement, or damage.

1.4 PRODUCT STORAGE AND HANDLING REQUIREMENTS

- A. Store and protect products in accordance with manufacturers' instructions.
- B. Store with seals and labels intact and legible.
- C. Store sensitive products in weather tight, climate controlled, enclosures in an environment favorable to product.
- D. For exterior storage of fabricated products, place on sloped supports above ground.
- E. Provide bonded off-site storage and protection when site does not permit on-site storage or protection.
- F. Cover products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of products.
- G. Store loose granular materials on solid flat surfaces in well-drained area. Prevent mixing with foreign matter.
- H. Provide equipment and personnel to store products by methods to prevent soiling, disfigurement, or damage.
- I. Arrange storage of products to permit access for inspection. Periodically inspect to verify products are undamaged and are maintained in acceptable condition.

1.5 PRODUCT OPTIONS

- A. Products Specified by Reference Standards or by Description Only: Any product meeting those standards or description.
- B. Products Specified by Naming One or More Manufacturers: Products of one or manufacturers named and meeting specifications, substitutions are allowed in accordance with General Conditions Section 4.15 and Section 1.6 – Product Substitution Procedures under Section 01 60 00.
- C. Products Specified by Naming One or More Manufacturers with Provision for Substitutions: Submit request for substitution for any manufacturer not named in accordance with General Conditions Section 4.15, the following article and filling out the “Substitution Certification” form.

1.6 PRODUCT SUBSTITUTION PROCEDURES

- A. Architect/Engineer will consider requests for Substitutions only within 10 days after date of Owner-Contractor Agreement.
- B. Substitutions may be considered when a product becomes unavailable through no fault of Contractor.
- C. Document each request with complete data substantiating compliance of proposed Substitution with Contract Documents and fill out the “Substitution Certification” form and submit with all backup data.
- D. A request constitutes a representation that Bidder/Contractor:
 - 1. Has investigated proposed product and determined that it meets or exceeds quality level of specified product.
 - 2. Will provide same warranty for Substitution as for specified product.
 - 3. Will coordinate installation and make changes to other Work which may be required for the Work to be complete with no additional cost to Owner.
 - 4. Waives claims for additional costs or time extension which may subsequently become apparent.
 - 5. Will reimburse Owner and Architect/Engineer for review or redesign services associated with re-approval by authorities having jurisdiction.
- E. Substitutions will not be considered when they are indicated or implied on Shop Drawing or Product Data submittals, without separate written request, or when acceptance will require revision to Contract Documents.
- F. Substitution Submittal Procedure:
 - 1. Submit three copies of request for Substitution for consideration. Limit each request to one proposed Substitution, along with “Substitution Certification” form.
 - 2. Submit Shop Drawings, Product Data, and certified test results attesting to proposed product equivalence. Burden of proof is on proposer.
 - 3. Architect/Engineer will notify Contractor in writing of decision to accept or reject request.

PART 2 PRODUCTS

2.1 EQUIPMENT ELECTRICAL CHARACTERISTICS AND COMPONENTS

- A. Wiring Terminations: Furnish terminal lugs to match branch circuit conductor quantities, sizes, and materials indicated. Include lugs for terminal box.

- B. Cord and Plug: Furnish minimum 6-foot (2 m) cord and plug including grounding connector for connection to electric wiring system. Cord of longer length is specified in individual specification sections.

PART 3 EXECUTION

Not Used.

END OF SECTION

SECTION 01 70 00
EXECUTION AND CLOSEOUT REQUIREMENTS

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Closeout procedures.
- B. Final cleaning.
- C. Starting of systems.
- D. Demonstration and instructions.
- E. Testing, adjusting and balancing.
- F. Protecting installed construction.
- G. Project record documents.
- H. Operation and maintenance data.
- I. Manual for materials and finishes.
- J. Manual for equipment and systems.
- K. Spare parts and maintenance products.
- L. Product warranties and product bonds.
- M. Maintenance service.

1.2 CLOSEOUT PROCEDURES

- A. Submit written certification that Contract Documents have been reviewed, Work has been inspected, and that Work is complete in accordance with Contract Documents and ready for Architect/Engineer's review.
- B. Provide submittals to Architect/Engineer required by authorities having jurisdiction.
- C. Submit final Application for Payment identifying total adjusted Contract Sum, previous payments, and sum remaining due.
- D. Owner will occupy all portions of building as specified in Section 01 10 00 - Summary.
- E. See General Conditions and Supplementary General Conditions of the Contract for Construction for further information on 5% line item for Close Out Documentation, and Overhead, Profit and Bonding

1.3 FINAL CLEANING

- A. Execute final cleaning prior to final project assessment.
- B. Clean interior and exterior glass, surfaces exposed to view; remove temporary labels, stains and foreign substances, polish transparent and glossy surfaces, vacuum carpeted and soft surfaces.
- C. Clean equipment and fixtures to sanitary condition with cleaning materials appropriate to surface and material being cleaned.
- D. Replace filters of operating equipment.
- E. Clean debris from roofs, gutters, downspouts, and drainage systems.
- F. Clean site; sweep paved areas, rake clean landscaped surfaces.
- G. Remove waste and surplus materials, rubbish, and construction facilities from site.

1.4 STARTING OF SYSTEMS

- A. Coordinate schedule for start-up of various equipment and systems.
- B. Notify Architect/Engineer and Owner seven days prior to start-up of each item.
- C. Verify each piece of equipment or system has been checked for proper lubrication, drive rotation, belt tension, control sequence, and for conditions which may cause damage.
- D. Verify tests, meter readings, and specified electrical characteristics agree with those required by equipment or system manufacturer.
- E. Verify wiring and support components for equipment are complete and tested.
- F. Execute start-up under supervision of applicable manufacturer's representative or Contractors' personnel in accordance with manufacturers' instructions.
- G. When specified in individual specification Sections, require manufacturer to provide authorized representative to be present at site to inspect, check, and approve equipment or system installation prior to start-up, and to supervise placing equipment or system in operation.
- H. Submit a written report in accordance with Section 01 33 00 - Submittal Procedures that equipment or system has been properly installed and is functioning correctly.

1.5 DEMONSTRATION AND INSTRUCTIONS

- A. Demonstrate operation and maintenance of products to Owner's personnel two weeks prior to date of Substantial Completion and final inspection.
- B. Demonstrate Project equipment instructed by qualified manufacturer's representative who is knowledgeable about the Project.
- C. For equipment or systems requiring seasonal operation, perform demonstration for other season within 4 months.
- D. Utilize operation and maintenance manuals as basis for instruction. Review contents of manual with Owner's personnel in detail to explain all aspects of operation and maintenance.
- E. Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, maintenance, and shutdown of each item of equipment at agreed time, at equipment location.
- F. Prepare and insert additional data in operations and maintenance manuals when need for additional data becomes apparent during instruction.
- G. Required instruction time for each item of equipment and system is specified in individual sections.

1.6 TESTING, ADJUSTING AND BALANCING

- A. Reports will be submitted by independent firm to Architect/Engineer indicating observations and results of tests and indicating compliance or non-compliance with requirements of Contract Documents. General contractor is to cover costs for all testing and reports.

1.7 PROTECTING INSTALLED CONSTRUCTION

- A. Protect installed Work and provide special protection where specified in individual specification sections.
- B. Provide temporary and removable protection for installed products. Control activity in immediate work area to prevent damage.
- C. Provide protective coverings at walls, projections, jambs, sills, and soffits of openings.

- D. Protect finished floors, stairs, and other surfaces from traffic, dirt, wear, damage, or movement of heavy objects, by protecting with durable sheet materials.
- E. Prohibit traffic or storage upon waterproofed or roofed surfaces. When traffic or activity is necessary, obtain recommendations for protection from waterproofing or roofing material manufacturer.
- F. Prohibit traffic from landscaped areas.

1.8 PROJECT RECORD DOCUMENTS

- A. Maintain on site one set of the following record documents; record actual revisions to the Work:
 - 1. Drawings.
 - 2. Specifications.
 - 3. Addenda.
 - 4. Change Orders and other modifications to the Contract.
 - 5. Reviewed Shop Drawings, Product Data, and Samples.
 - 6. Manufacturer's instruction for assembly, installation, and adjusting.
- B. Ensure entries are complete and accurate, enabling future reference by Owner.
- C. Store record documents separate from documents used for construction.
- D. Record information concurrent with construction progress, not less than weekly.
- E. Specifications: Legibly mark and record at each product section description of actual products installed, including the following:
 - 1. Manufacturer's name and product model and number.
 - 2. Product substitutions or alternates utilized.
 - 3. Changes made by Addenda and modifications.
- F. Record Drawings and Shop Drawings: Legibly mark each item to record actual construction including:
 - 1. Measured depths of foundations in relation to finish first floor datum.
 - 2. Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 - 3. Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.
 - 4. Field changes of dimension and detail.
 - 5. Details not on original Contract drawings.
- G. Submit three (3) electronic copies of all record drawings and approved shop drawings on thumb drives to Architect/Engineer.

1.9 OPERATION AND MAINTENANCE DATA

- A. Submit three (3) electronic copies of all operation and maintenance data on thumb drives to Architect/Engineer.
- B. Prepare cover with title "OPERATION AND MAINTENANCE INSTRUCTIONS", title of project, and subject matter of binder when multiple binders are required.
- C. Subdivide content with permanent divider pages, logically organized as described below; with tab titling clearly identified.
- D. Drawings: Submit electronically with O&M documentation.
- E. Contents: Prepare Table of Contents for each volume, with each product or system description identified, in three parts as follows:
 - 1. Part 1: Directory, listing names, addresses, and telephone numbers of Architect/Engineer, Contractor, Subcontractors, and major equipment suppliers.

2. Part 2: Operation and maintenance instructions arranged by system and subdivided by specification section. For each category, identify names, addresses, and telephone numbers of Subcontractors and suppliers. Identify the following:
 - a. Significant design criteria.
 - b. List of equipment.
 - c. Parts list for each component.
 - d. Operating instructions.
 - e. Maintenance instructions for equipment and systems.
 - f. Maintenance instructions for all finishes, including recommended cleaning methods and materials, and special precautions identifying detrimental agents.
3. Part 3: Project documents and certificates, including the following:
 - a. Approved shop drawings and product data.
 - b. Air and water balance reports.
 - c. Certificates.
 - d. Originals and 2 Photocopies of warranties and bonds.

1.10 MANUAL FOR MATERIALS AND FINISHES

- A. Submit two copies of preliminary draft or proposed formats and outlines of contents before start of Work. Architect/Engineer will review draft and return one copy with comments.
- B. For equipment, or component parts of equipment put into service during construction and operated by Owner, submit documents within ten days after acceptance.
- C. Submit one copy of completed volumes 15 days prior to final inspection. Draft copy be reviewed and returned with Architect/Engineer comments. Revise content of document sets as required prior to final submission.
- D. Submit three sets of revised final volumes in final form within 10 days after final inspection.
- E. Building Products, Applied Materials, and Finishes: Include product data, with catalog number, size, composition, and color and texture designations. Include information for re-ordering custom manufactured products.
- F. Instructions for Care and Maintenance: Include manufacturer's recommendations for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- G. Moisture Protection and Weather Exposed Products: Include product data listing applicable reference standards, chemical composition, and details of installation. Include recommendations for inspections, maintenance, and repair.
- H. Additional Requirements: As specified in individual product specification sections.
- I. Include listing in Table of Contents for design data, with tabbed fly sheet and space for insertion of data.

1.11 MANUAL FOR EQUIPMENT AND SYSTEMS

- A. Submit two copies of preliminary draft or proposed formats and outlines of contents before start of Work. Architect/Engineer will review draft and return one copy with comments.
- B. For equipment, or component parts of equipment put into service during construction and operated by Owner, submit documents within ten days after acceptance.
- C. Submit one copy of completed volumes 15 days prior to final inspection. Draft copy be reviewed and returned after final inspection, with Architect/Engineer comments. Revise content of document sets as required prior to final submission.
- D. Submit three sets of revised final volumes in final form within 10 days after final inspection.

- E. Each Item of Equipment and Each System: Include description of unit or system, and component parts. Identify function, normal operating characteristics, and limiting conditions. Include performance curves, with engineering data and tests, and complete nomenclature and model number of replaceable parts.
- F. Panelboard Circuit Directories: Provide electrical service characteristics, controls, and communications; typed, by label machine.
- G. Include color coded wiring diagrams as installed.
- H. Operating Procedures: Include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and special operating instructions.
- I. Maintenance Requirements: Include routine procedures and guide for preventative maintenance and trouble shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- J. Include servicing and lubrication schedule, and list of lubricants required.
- K. Include manufacturer's printed operation and maintenance instructions.
- L. Include sequence of operation by controls manufacturer.
- M. Include original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- N. Include control diagrams by controls manufacturer as installed.
- O. Include Contractor's coordination drawings, with color coded piping diagrams as installed.
- P. Include charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
- Q. Include list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
- R. Include test and balancing reports as specified in Section 01 40 00 - Quality Requirements.
- S. Additional Requirements: As specified in individual product specification sections.
- T. Include listing in Table of Contents for design data, with tabbed dividers and space for insertion of data.

1.12 SPARE PARTS AND MAINTENANCE PRODUCTS

- A. Furnish spare parts, maintenance, and extra products in quantities specified in individual specification sections.
- B. Deliver to Project site and place in location as directed by Owner; obtain receipt prior to final payment.

1.13 PRODUCT WARRANTIES AND PRODUCT BONDS

- A. Obtain warranties and bonds executed in duplicate by responsible subcontractors, suppliers, and manufacturers, within ten days after completion of applicable item of work.
- B. Execute and assemble transferable warranty documents and bonds from subcontractors, suppliers, and manufacturers.
- C. Verify documents are in proper form, contain full information, and are notarized.
- D. Co-execute submittals when required.
- E. Include Table of Contents and assemble in three D side ring binder with durable plastic cover.

- F. Submit prior to final Application for Payment.
- G. Time Of Submittals:
 - 1. For equipment or component parts of equipment put into service during construction with Owner's permission, submit documents within ten days after acceptance.
 - 2. Make other submittals within ten days after Date of Substantial Completion, prior to final Application for Payment.
 - 3. For items of Work for which acceptance is delayed beyond Date of Substantial Completion, submit within ten days after acceptance, listing date of acceptance as beginning of warranty or bond period.

1.14 MAINTENANCE SERVICE

- A. Furnish service and maintenance of components indicated in specification sections for two years minimum from date of Substantial Completion.
- B. Examine system components at frequency consistent with reliable operation. Clean, adjust, and lubricate as required.
- C. Include systematic examination, adjustment, and lubrication of components. Repair or replace parts whenever required. Use parts produced by manufacturer of original component.
- D. Do not assign or transfer maintenance service to agent or Subcontractor without prior written consent of Owner.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

Not Used.

END OF SECTION

SECTION 01 71 00

CLEANING

PART 1 - GENERAL

1.01 WORK INCLUDED

Contractor shall maintain the project site and adjacent areas affected by the work as specified below.

1.02 DESCRIPTION

- A. During its progress, i.e. on a daily basis and at its completion, and as required by the General Conditions, the work and the adjacent areas affected thereby shall be kept cleaned up and all rubbish, surplus materials, and unneeded construction equipment shall be removed and all damage repaired so that the Owner, the public and property owners will be inconvenienced as little as possible.
- B. Requirements of Regulatory Agencies:
1. In addition to the requirements herein, maintain the cleanliness of the Work and surrounding premises within the Work limits so as to comply with federal, state, and local fire and safety laws, ordinances, codes and regulations.
 2. Comply with all federal, state and local anti-pollution laws, ordinances, codes and regulations when disposing of waste materials, debris and rubbish.
- C. Scheduling of Cleaning and Disposal Operations:
1. So that dust, wash water or other contaminants generated during such operations do not damage or mar painted or finished surfaces.
 2. To prevent accumulation of dust, dirt, debris, rubbish and waste materials on or within the Work or on the premises surrounding the Work.
- D. Waste Disposal:
1. The Contractor shall not delegate waste disposal or dumpster services to a subcontractor, but shall take charge of all cleanup disposal needs.
 2. Dispose of all waste materials, debris and rubbish off the plant site at an approved disposal site.
 3. Do not burn or bury rubbish or waste materials on the work site.
 4. Do not dispose of volatile or hazardous wastes such as mineral spirits, oil, or paint thinner improperly.
 5. Do not discharge wastes into streams or waterways.
- E. Cleaning Materials:
1. Use only cleaning materials recommended by manufacturer of surface to be cleaned.
 2. Use each type of cleaning material on only those surfaces recommended by the cleaning material manufacturer.
 3. Use only materials which will not create hazards to health or property.

- F. During Construction:
1. Keep the Work and surrounding premises within work limits free of accumulations of dirt, dust, waste materials, debris and rubbish.
 2. Keep dust generating areas wetted down so as to prevent the entry of dust into surrounding equipment.
 3. Provide suitable containers for storage of waste materials, debris and rubbish until time of disposal.
 4. Dispose of waste, debris and rubbish off site at legal disposal areas.
- G. When Project is Completed:
1. Remove and dispose of all excess or waste materials, debris, rubbish, and temporary facilities from the site structures and all facilities.
 2. Repair pavement, roads, sod, and all other areas affected by construction operations and restore them to original condition or to condition specified.
 3. Remove spatter, grease, stains, fingerprints, dirt, dust, labels, tags, packing materials and other foreign items or substances from interior and exterior surfaces, equipment, signs and lettering.
 4. Repair, patch and touch up chipped, scratched, dented or otherwise marred surfaces to match specified finish.
 5. Remove paint, clean and restore all equipment and material nameplates, labels and other identification markings.
 6. Wash and shine mirrors, glazing and polished surfaces.
 7. Clean all floors, slabs, pavements, and ground surfaces.
 8. Maintain cleaning until acceptance and occupation by Owner.

END OF SECTION

SECTION 01 73 29

CUTTING AND PATCHING

PART 1 – GENERAL

1.1 Related Documents

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Provide cutting and patching work, comply with project requirements for:
 - 1. Demolition of existing construction as shown on plans and as required for new work. Note demolition plans illustrate generally work to be removed. **The contractor shall inspect site prior to Bid and include all demolition work required to perform new work. All demolition and patching work shall be considered in the contract scope.**

PART 2 – PRODUCTS

2.1 MATERIALS

- A. Match existing materials for cutting and patching work with new materials conforming to project requirements or existing conditions if not herein specified.

PART 3 – EXECUTION:

- A. Inspect conditions prior to work to identify scope and type of work required. Notify Owner of work requiring interruption to building services or Owner's operations. Conform to project requirements listed above.
- B. Clean work area and areas affected by cutting and patching operations.
- C. The Building will be occupied during construction, the Contractor shall conform to all OSHA Standard, protect all openings, doorways and walkways during construction.

END OF SECTION

SECTION 02 41 19

SELECTIVE DEMOLITION

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes all demolition work required to perform new work.

1.2 SUBMITTALS

- A. Shop Drawings and Schedule: Describe demolition, removal procedures, sequence and schedule.

PART 2 EXECUTION

2.1 PREPARATION

- A. Provide, erect, and maintain temporary barriers and security devices.
- B. Notify owner of work, which may affect their property, potential noise, utility outage, or disruption. Coordinate all work with Owner.
- C. Prevent movement or settlement of adjacent structures. Provide bracing and shoring as required.
- D. Protect existing landscaping materials and structures to remain.
- E. Erect and maintain weatherproof airtight closures for exterior openings.
- F. Erect and maintain temporary partitions to prevent spread of dust, odors and noise to permit continued Owner occupancy.
- G. Protect existing items indicated to remain.

2.2 DEMOLITION REQUIREMENTS

- A. Conduct demolition to minimize interference with adjacent building areas.
- B. Conduct operations with minimum interference to public or private accesses.
- C. Maintain protected egress and access at all times. Do not close or obstruct roadways or sidewalks without permits.
- D. Cease operations immediately when adjacent structural components appear to be in danger. Notify authority having jurisdiction and Architect/Engineer.

2.3 SELECTIVE DEMOLITION

- A. Demolish and remove components in orderly and careful manner, in sequence outlined in submitted and approved schedule.
- B. Protect existing supporting structural members.

2.4 CLEAN UP

- A. Remove demolished materials from site as work progresses.
- B. Leave areas of work in clean condition.
- C. Dispose of all debris in accordance with all State and Municipal requirements. Provide load tickets where applicable.

END OF SECTION

SECTION 02 41 26

SELECTIVE ELECTRICAL DEMOLITION

PART 1 GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Removal of existing electrical equipment, wiring, and conduit in areas to be remodeled; removal of designated construction; dismantling, cutting and alterations for completion of the Work.
 - 2. Disposal of materials.
 - 3. Storage of removed materials.
 - 4. Identification of utilities.
 - 5. Salvaged items.
 - 6. Protection of items to remain as indicated on Drawings.
 - 7. Relocate existing equipment to accommodate construction.
- B. Related Sections:
 - 1. Section 02 41 19 - Selective Demolition.

1.2 SUBMITTALS

- A. Section 01 33 00 - Submittal Procedures: Requirements for submittals.
- B. Shop Drawings: Indicate demolition and removal sequence and location of salvageable items; location and construction of temporary work. Describe demolition removal procedures and schedule.

1.3 CLOSEOUT SUBMITTALS

- A. Section 01 70 00 - Execution and Closeout Requirements: Requirements for submittals.
- B. Project Record Documents: Record actual locations of capped utilities, conduits and equipment abandoned in place.

1.4 QUALITY ASSURANCE

- A. Perform Work in accordance with local Municipality and state regulation standard.

1.5 PRE-INSTALLATION MEETINGS

- A. Section 01 30 00 - Administrative Requirements: Pre-installation meeting.
- B. Convene minimum one week prior to commencing work of this section.

1.6 SEQUENCING

- A. Section 01 10 00 - Summary: Requirements for sequencing.

1.7 SCHEDULING

- A. Section 01 30 00 - Administrative Requirements, 01 32 16 - Construction Progress Schedule: Requirements for scheduling.
- B. Schedule work to coincide with new construction.
- C. Perform noisy, malodorous, and/or dusty work:
 - 1. During work.
- D. Cease operations immediately when structure appears to be in danger and notify Architect/Engineer. Do not resume operations until directed.

1.8 COORDINATION

- A. Section 01 30 00 - Administrative Requirements: Requirements for coordination.
- B. Conduct demolition to minimize interference with adjacent and occupied building areas.
- C. Coordinate demolition work with Owner.
- D. Coordinate and sequence demolition so as not to cause shutdown of operation of surrounding areas.
- E. Shut-down Periods:
 - 1. Arrange timing of shut-down periods of in-service panels with Owner. Do not shut down any utility without prior written approval.
 - 2. Keep shut-down period to minimum or use intermittent period as directed by Owner.
 - 3. Maintain life-safety systems in full operation in occupied facilities.
- F. Identify salvage items in cooperation with Owner.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 EXAMINATION

- A. Section 01 30 00 - Administrative Requirements: Verification of existing conditions before starting work.
- B. Verify wiring and equipment indicated to be demolished serve only abandoned facilities.
- C. Verify termination points for demolished services.

3.2 PREPARATION

- A. Erect, and maintain temporary safeguards, including warning signs and lights, barricades, and similar measures, for protection of the public, Owner, Contractor's employees, and existing improvements to remain.
- B. Temporary egress signage and emergency lighting

3.3 DEMOLITION

- A. Demolition Drawings are based on casual field observation and existing record documents. Report discrepancies to Architect/Engineer before disturbing existing installation.
- B. Remove exposed abandoned conduit, including abandoned conduit above accessible ceiling finishes. Cut conduit flush with walls and floors, and patch surfaces.
- C. Remove conduit, wire, boxes, and fastening devices to avoid any interference with new installation.
- D. Disconnect electrical systems in walls, floors, and ceilings scheduled for removal.
- E. Reconnect equipment being disturbed by renovation work and required for continue service to nearest available panel.
- F. Disconnect or shut off service to areas where electrical work is to be removed. Remove electrical fixtures, equipment, and related switches, outlets, conduit and wiring which are not part of final project.
- G. Install temporary wiring and connections to maintain existing systems in service during construction.

- H. Perform work on energized equipment or circuits with experienced and trained personnel.
- I. Remove, relocate, and extend existing installations to accommodate new construction.
- J. Repair adjacent construction and finishes damaged during demolition and extension work.
- K. Remove exposed abandoned grounding and bonding components, fasteners and supports, and electrical identification components, including abandoned components above accessible ceiling finishes. Cut embedded support elements flush with walls and floors.
- L. Clean and repair existing equipment to remain or to be reinstalled.
- M. Protect and retain power to existing active equipment remaining.
- N. Cap abandoned empty conduit at both ends.
- O. Perform Work in accordance with applicable code standards.

3.4 EXISTING PANELBOARDS

- A. Ring out circuits in existing panel affected by the Work. Where additional circuits are needed, reuse circuits available for reuse. Install new breakers.
- B. Tag unused circuits as spare.
- C. Where existing circuits are indicated to be reused, use sensing measuring devices to verify circuits feeding Project area or are not in use.
- D. Remove existing wire no longer in use from panel to equipment.
- E. Provide new updated directories where more than three circuits have been modified or rewired.

3.5 SALVAGE ITEMS

- A. Remove and protect items indicated on Drawings to be salvaged and turn over to Owner.
- B. Items of salvageable value may be removed as work progresses. Transport salvaged items from site as they are removed.

3.6 REUSABLE ELECTRICAL EQUIPMENT

- A. Carefully remove equipment, materials, or fixtures which are to be reused.
- B. Disconnect, remove, or relocate existing electrical material and equipment interfering with new installation.
- C. Relocate existing lighting fixtures as indicated on Drawings. Clean fixtures and re-lamp. Test fixture to see if it is in good working condition before installation at new location.

3.7 CLEANING

- A. Section 01 70 00 - Execution and Closeout Requirements & 01 71 00 - Cleaning: Requirements for cleaning.
- B. Remove demolished materials as work progresses. Legally dispose.
- C. Keep workplace neat.

3.8 PROTECTION OF FINISHED WORK

- A. Section 01 70 00 - Execution and Closeout Requirements: Requirements for protecting finished Work.
- B. Do not permit traffic over unprotected floor surface.

END OF SECTION

SECTION 06 10 00

ROUGH CARPENTRY

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes blocking in wall openings; wood furring and grounds; back boards, and concealed wood blocking.

1.2 SUBMITTALS

- A. Shop Drawings: Indicate framing system, loads and cambers, bearing details, framed openings.

1.3 QUALITY ASSURANCE

- A. Perform Work in accordance with the following agencies:
 - 1. Lumber Grading Agency: Certified by NIST PS 20.
 - 2. Plywood Grading Agency: Certified by APA/The Engineered Wood Association.
- B. Surface Burning Characteristics:
 - 1. Fire Retardant Treated Materials: Maximum 25/450 flame spread/smoke developed index when tested in accordance with ASTM E84.
- C. Apply label from agency approved by authority having jurisdiction to identify each fire retardant treated material.
- D. Perform Work in accordance with authorities having jurisdiction.

PART 2 PRODUCTS

2.1 LUMBER MATERIALS

- A. Lumber Grading Rules: WWPA G-5.
- B. Sill Plate: Pressure treated .40 cca / syp.

2.2 SHEATHING MATERIALS

- A. Plywood Roof Sheathing: Plywood; Exposure Durability 1; sanded.
- B. Plywood Wall Sheathing: Structural I; Exposure Durability 1; sanded.

2.3 ACCESSORIES

- A. Fasteners: Plain finish elsewhere.
- B. Die Stamped Connectors:

- C. Structural Framing Connectors: Galvanized steel, sized to suit framing conditions.
- D. Anchors: Toggle bolt type for anchorage to hollow masonry. Expansion shield and lag bolt type for anchorage to solid masonry or concrete. Bolt or ballistic fastener for anchorages to steel.
- E. Sill Gasket: Plate width, closed cell foam strip.
- F. Sill Flashing (Under Sill Gasket): Polyethylene sheet or Galvanized steel.

PART 3 EXECUTION

3.1 FRAMING

- A. Erect wood framing members in accordance with the International Building Code, latest edition. Place members level and plumb. Place horizontal members crown side up.
- B. Place sill gasket directly on sill flashing.
- C. Bridging to be provided and installed as per manufacturer specifications.

3.2 SHEATHING

- A. Secure sheathing with ends staggered, over firm bearing.

3.3 SITE APPLIED WOOD TREATMENT

- A. Treat site-sawn cuts. Brush apply two coats of preservative treatment on untreated wood in contact with cementitious materials, roofing, and related metal flashings.
- B. Allow preservative to cure prior to erecting members.

END OF SECTION

SECTION 06 20 00

FINISH CARPENTRY

1.0 GENERAL:

1.1 DESCRIPTION:

1.1.1 Work Included: Install wood, nails, screws, and other items as needed, and perform finish carpentry for the construction shown on the drawings, as specified herein, and as needed for a complete and proper installation.

1.1.2 Related Work: Documents affecting work of this Section include, but are not necessarily limited to General Conditions, Supplementary Conditions, and other sections of these specifications.

1.2 QUALITY ASSURANCE: Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this section.

2.0 PRODUCTS:

2.1 GRADE STAMPS:

2.1.1 Identify lumber by the grade stamp of the West Coast Lumber Inspection Bureau, or such grade stamp as is approved in advance by the Architect.

2.1.2 Identify plywood as to species, grade, and glue type by the stamp of the American Plywood Association.

2.2 MATERIALS: Provide materials in the quantities needed for the work as shown on the drawings, and as described in this section.

2.3 OTHER MATERIALS: Provide other materials, not specifically described but required for a complete and proper installation, as selected by the Contractor subject to the approval of the Architect.

3.0 EXECUTION:

3.1 SURFACE CONDITIONS: Examine the areas and conditions under which work of this section will be performed. Correct conditions detrimental to timely and proper completion of the work. Do not proceed until unsatisfactory conditions are corrected.

3.2 WORKMANSHIP:

3.2.1 Produce joints which are true, tight, and well nailed with all members assembled in accordance with the drawings.

- 3.2.2 Jointing:
- a. Make joints to conceal shrinkage, miter exterior joints, cope interior joints, miter or scarf end-to-end joints.
 - b. Install trim in pieces as long as possible, jointing only where solid support is obtained.
- 3.2.3 Fastening:
- a. Install items straight, true, level, plumb, and firmly anchored in place.
 - b. Where blocking or backing is required, coordinate as necessary with other trades to ensure placement of required backing and blocking in a timely manner.
- 3.3 INSTALLATION OF OTHER ITEMS: Install items in strict accordance with the drawings and the recommended methods of the manufacturer as approved by the Architect, anchoring firmly into position at the prescribed locations, straight, plumb, and level.
- 3.4 FINISHING:
- 3.4.1 Sandpaper finished wood surfaces thoroughly as required to produce a uniformly smooth surface, always sanding in the direction of the grain; except do not sand wood which is designed to be left rough.
- 3.4.2 No coarse grained sandpaper mark, hammer mark, or other imperfection will be accepted.
- 3.5 CLEANING UP:
- 3.5.1 Keep the premises in a neat, safe, and orderly condition at all times during execution of this portion of the work, free from accumulation of sawdust, cut-ends, and debris.
- 3.5.2 Sweeping:
- a. At the end of each working day, and more often if necessary, thoroughly sweep surfaces where refuse from this portion of the work has settled.
 - b. Remove the refuse to the area of the job site set aside for its storage.
 - c. Upon completion of this portion of the work, thoroughly broom clean all surfaces.

END OF SECTION

SECTION 08 11 13

STEEL DOOR FRAMES

PART 1 GENERAL

1.0 SUMMARY

- A. Section includes non-rated and fire rated steel door frames.

1.2 SUBMITTALS

- A. Shop Drawings: Indicate frame elevations, fastening method, internal reinforcements, and cutouts for hardware and finishes.
- B. Product Data: Submit frame configurations, location of cutouts for hardware reinforcement.

1.3 QUALITY ASSURANCE

- A. Perform Work in accordance with the Public Work's standard.
- B. Perform Work in accordance with the following:
 - 1. SDI-100-Standard Steel Frames.
 - 2. DHI - Door Hardware Institute - The Installation of Commercial Steel Doors and Steel Frames, Insulated Steel Doors in Wood Frames and Builder's Hardware.
 - 3. Fire Rated Doors, Panels and Frames:
 - a. Product Construction: ASTM E152. NFPA 252. UL 10B.
 - b. Product Installation: NFPA 80.

PART 2 PRODUCTS

2.1 STEEL DOOR FRAMES

- A. Manufacturers:
 - 1. Pioneer Industries.
 - 2. Republic Builders Products.
 - 3. Substitutions: Architect/Owner Approved Equal

2.2 COMPONENTS

- A. Exterior Frames: 14-gauge thick material, base metal thickness (galvanized).
- B. Interior Frames: 16-gauge thick material, base metal thickness.

2.3 ACCESSORIES

- A. Silencers: Resilient rubber fitted into drilled hole.

2.4 FABRICATION

- A. Fabricate frames with hardware reinforcement welded in place. Protect frame hardware preparations with mortar guard boxes.
- B. Configure exterior frames with profile to receive recessed weather-stripping.
- C. Fabricate frames, welded units, for all walls.
- D. Fabricate frames to suit masonry wall coursing with 4 inches head member.
- E. Prepare interior frames for silencers and install.
- F. Attach fire-rating label to each fire rated doorframe.

2.5 SHOP FINISHING

- A. Steel Sheet: Galvanized to ASTM A653/A653M G60.
- B. Primer: Baked.
- C. Shop Finish: Baked enamel.
- D. Coat inside of frame profile with bituminous coating.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify opening sizes and tolerances are acceptable.

3.2 INSTALLATION

- A. Install frames in accordance with SDI-100.
- B. Coordinate installation of frames with installation of hardware specified in Section 087100.
- C. Coordinate frames with masonry gypsum board wall construction for frame anchor placement.
- D. Install roll formed steel reinforcement channels between two abutting frames. Anchor to structure and floor.
- E. Install door louvers plumb and level (where indicated on drawings).
- F. Adjust door for smooth and balanced door movement.
- G. Tolerances:
 - 1. Maximum Diagonal Distortion: 1/16 inch, measured with straight edge, corner to corner.

3.3 SCHEDULE

- A. Refer to Drawings for Door Schedule and details.

4.0 GLAZING

- A. Vision panels 4"x24" with 1/4" safety glass.

END OF SECTION

SECTION 08 14 00

WOOD DOORS

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes wood doors, fire-rated and non-rated.

1.2 SUBMITTALS

- A. Shop Drawings: Indicate door and frame elevations, cutouts for glazing and hardware preparation.
- B. Samples: Submit two (2) of door veneer, illustrating wood grain, color and finish.

1.3 QUALITY ASSURANCE

- A. Perform work in accordance with the following:
 - 1. NWWDA I.S.1.
 - 2. Fire Door and Panel Construction: Conform to ASTM E152., NFPA 252., UL 10B.
 - 3. Installed Door and Panel Assembly: Conform to NFPA 80 for fire rated class as indicated on Drawings.

1.4 WARRANTY

- A. Furnish five (5) year manufacturer warranty to include delamination of veneer, warping beyond specified installation tolerances, defective materials, and telegraphing core construction.

PART 2 PRODUCTS

2.1 WOOD DOORS

- A. Manufacturers:
 - 1. VT Industries
 - 2. Graham
 - 3. Mohawk
 - 4. Eggers Industries
 - 5. Pinecrest Inc.
 - 6. Weyerhaeuser
 - 7. Substitutions: Architect/Owner Approved Equal.
- B. Product Description: Solid core wood doors, fire-rated, glazed design, wood veneer, factory-finished.
 - 1. Interior Doors: 1-3/4 inches thick, solid core, five-ply construction; fire-rated as indicated on Drawings; in any case not less than 1 hour, including frames.

2.2 COMPONENTS

- A. Core:
 - 1. Core Solid, Non-Rated: NWWDA, Type Solid particleboard mat formed, board core including lock blocks, vertical edge bands, and top and bottom rails.
 - 2. Core Solid Rated: Non-combustible mineral core.
- B. Flush Door Facing:
 - 1. Wood veneer: Comply with WDMA TR-8 requirements – Premium Oak species wood, rotary sliced; book match grain, for transparent finish.
 - 2. Adhesive: NWWDA, Type II-water resistant.

2.3 ACCESSORIES

- A. Glass Stops: Wood of same species as door facing conforming to UL requirements.

2.4 FABRICATION

- A. Fabricate non-rated doors in accordance with NWWDA I.S.1 requirement.
- B. Fabricate fire rated doors in accordance with NWWDA I.S.1 and To UL; Warnock Hersey requirements. Attach fire rating label to door edge.
- C. Astragals for Double Doors: Wood "T" shaped, recessed at face edge.
- D. Fabricate doors with hardware reinforcement blocking in place.
- E. Factory machine doors for finish hardware.
- F. Factory fit doors for frame opening dimensions identified on shop drawings.

2.5 FINISH

- A. Factory finish doors in accordance with approved sample.
- B. Seal door top edge with color sealer to match door facing.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Install doors in accordance with NWWDA I.S.1 requirement, and NFPA 80 requirements for fire rating label.
- B. Coordinate installation of glass and glazing.
- C. Install door louvers plumb and level.
- D. Coordinate installation of doors with installation of metal frames specified in Section 111910 Hollow Metal Doors, Frames, & Window Frames and hardware specified in Section 087100 Door Hardware. Glass specified in Section 088000 Glazing.
- E. Adjust door for smooth and balanced door movement.
- F. Tolerances:
 - 1. Conform to NWWDA requirements for fit and clearance tolerances and maximum diagonal distortion.

3.2 SCHEDULE

- A. Refer to Door and Frame Schedule on Drawings.
- B. Coordinate with Electrical and Fire protection drawings.

END OF SECTION

SECTION 08 71 00
DOOR HARDWARE

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:

1. Hardware for swinging Aluminum, Hollow Metal and Wood Door Openings.

B. Related Sections:

1. Section 01 25 13 – Product Substitution Procedures
2. Section 06 20 00 – Finish Carpentry
3. Section 08 11 13 – Hollow Metal Doors and Frames
4. Section 08 14 16 – Flush Wood Doors
5. Section 08 41 13 – Aluminum-Framed Entrances and Storefronts
6. Section 26 05 19 – Low Voltage Electrical Power Conductors and Cables

1.2 REFERENCES

A. Use the following references to properly detail, schedule, furnish and install finish hardware items.

1. NFPA 80 – Standard for Fire Doors and Other Opening Protectives (2007)
2. DHI Installation Guide for Doors and Hardware (1984)
3. DHI Sequence and Format for the Hardware Schedule (1996)
4. ANSI/BHMA A156.4 – Door Controls – Closers (2013)
5. ANSI/BHMA A156.2 – Bored and Preassembled Locks and Latches (2011)
6. ANSI/BHMA A156.13 – Mortise Locks and Latches Series 1000 (2012)
7. ANSI/BHMA A156.18 – Materials and Finishes (2012)

1.3 SUBMITTALS

A. Schedule:

1. Provide submittals in accordance with 01 33 00 – Submittal Procedures.
2. Provide hardware schedule in vertical format on 8-1/2-inch by 11-inch paper for electronic format. Conform to DHI publication Sequence and Format for Hardware Schedule using Architect's door numbers and hardware set numbers.
3. Provide elevation drawings for openings with electrical hardware and access control devices with each hardware schedule. Include illustration of opening, operational description, electrified hardware components, legend, approximate mounting location and size of enclosures, size and quantity of conductors, facility name and date.

B. Product Data: Provide one set of manufacturer's catalog and technical data for each hardware item used, highlighting design, function, fasteners, accessories, and options to facilitate review with each hardware schedule submitted.

C. Templates: Provide two sets of manufacturer's templating information for mortised and template hardware upon receipt of approved hardware schedule to the door and frame supplier(s). Include requirements for internal reinforcements required for surface mounted hardware.

D. Wiring Diagrams:

1. Four sets point-to-point diagrams specially developed for each opening that requires electrical hardware, with hardware delivery to jobsite. Reference elevation drawings submitted with hardware schedule using Architect's opening numbers. Provide full set to Stockton's Access Control department.

2. Three sets riser diagrams for openings requiring power supplies or access control. Include placement of power supplies, distance of wire runs from power supply, cable quantity and number and gauges of wires.
- E. Keying Schedule: Arrange meeting with Owner, Architect and finish hardware supplier to determine keying requirements immediately upon receipt of finish hardware schedule.

1.4 CLOSEOUT SUBMITTALS

- A. Furnish operations and maintenance manual in accordance with Section 01 78 28 – Operations and Maintenance Data and as follows:
1. Furnish one copy of manual at date of Substantial Completion in a 2-1/2-inch-thick binder labeled with project information, date and name and contact information for the hardware supplier.
 2. Include in manual:
 - a. Copy of approved hardware schedule, including door numbers and locations. Highlight fire rated door to aid in annual fire door inspection.
 - b. Copy of approved keying schedule.
 - c. Catalog data for each product.
 - d. As-installed “wiring diagrams” for each opening connected to power.
 - e. Parts list for locksets, exit devices, door closers, and auto door operators.
 - f. Installation templates and instructions.
 - g. Warranty information.
 - h. Name, address, and phone number of local representatives for each manufacturer.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Extra Materials:
1. Screws and Fasteners: Fifty of each screw and fastener required for general maintenance of hinges, locks, closers, exit devices, and sealing systems.
 2. Deliver to Owner remaining finish hardware fasteners and special installation tools upon completion of Project.

1.6 QUALITY ASSURANCE

- A. Supplier:
1. Furnish hardware from recognized supplier who has warehousing facility within 100 miles of project location, and who has actively supplied hardware for similar projects in the vicinity for a minimum of five years.
 2. Supplier shall employ an Architectural Hardware Consultant (AHC), as certified by Door and Hardware Institute, on staff full time to administer and supervise project.
- B. Installer: Install hardware using installers who have actively installed commercial door hardware for a minimum of five years, and are familiar with hardware installation of type required on this Project.
- C. Pre-Installation Meeting:
1. Prior to installation of hardware, arrange for manufacturer’s representatives of locksets, door closers, and exit devices to hold a jobsite meeting to instruct the installing personnel on the proper installation of their products.
 2. Send a letter of compliance, indicating when this meeting was held, and who was in attendance, to the Architect and Owner.
- D. Fire Rated Door Openings:
1. Comply with NFPA 80.

2. Furnish nationally recognized testing agency label or stamp on hardware for labeled openings.
3. Only labeled locks or latches or fire exit hardware can be used on fire rated openings.
4. Where UL requirements conflict with Drawings or Specifications, furnish hardware conforming to the UL requirements.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Delivery:

1. Jointly check in hardware, upon delivery to jobsite, against approved hardware schedule with hardware supplier. Record shortage or damage and replace or repair as necessary.
2. Deliver hardware to be installed during fabrication of doors and frames, to manufacturer.

B. Storage:

1. Store hardware in a secure, dry, temperature-controlled room on shelving to protect against loss, theft and damage.
2. Store items too long for shelving on pallet, off the floor.

C. Marking and Packaging:

1. Deliver hardware to jobsite in manufacturer's original packaging marked to correspond with approved hardware schedule with Architect's door numbers and hardware sets.
2. Mark all locksets, exit devices, cylinders, auxiliary hardware and key switches with keyset symbol.
3. Replace any wet or damaged packaging with new.

1.8 WARRANTY

A. Furnish warranties in accordance with Section 01 78 36 – Warranties. Extended or limited warranties shall be as follows:

1. Furnish minimum ten-year factory warranty on door closers, against defects in material and workmanship, from date of substantial completion.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. The following manufacturers were used in the hardware sets.

1. Hinges	Stanley	ST
2. Locks and Latchsets	Best	BE
3. Cylinders and Cores	Best	BE
4. Surface Door Closers	Dorma	DM
5. Automatic Operators	Stanley	ST
6. Exit Devices	Precision	PR
7. Overhead Stop/holders	Glynn Johnson	GJ
8. Protection Plates	Trimco	TR
9. Wall/Floor Stops	Trimco	TR
10. Electric Strikes	HES	HS
11. Thresholds and Gasketing	NGP	NA
12. Silencers	Trimco	TR

B. Submit requests for substitution in accordance with Section 01 25 13 Product Substitution Procedures and as follows:

1. Provide catalog data with product information highlighted or bubbled to facilitate review. Product must meet or exceed level or design intended and/or function established by specified products.
 - a. Locksets to be independently tested to exceed ANSI/BHMA Grade 1 standard by minimum five times.
 - b. Exit devices to be independently tested to minimum 10,000,000 cycles.

2.2 MATERIALS

A. Screws and Fasteners:

1. Provide manufacturer's recommended fasteners of proper type, material and finish.
2. Provide self-tapping screws for sweeps and stop applied weatherstripping.
3. Utilize through-bolts for the attachment of door closers and exit devices on non-reinforced doors only. Finish: match door face.
4. Exposed screw heads: Phillips type.
5. Provide fasteners (adhesive or sheet metal screws, for protection plates on fire rated mineral core doors, to meet wood door manufacturer's testing requirements.

B. Hinges:

1. Type:
 - a. Three-knuckle, full mortise, concealed bearing.
 - b. Furnish heavy weight hinges on heavy doors and doors expected to have high frequency use.
2. Quantity:
 - a. One pair of hinges for all doors up to 5 feet high. Furnish one additional hinge for every 2'-6" in height or fraction thereof.
3. Size:
 - a. For 1-3/4-inch-thick doors up to 3 feet wide: 4 1/2-inches high
 - b. For 1-3/4-inch-thick doors over 3 feet wide: 5-inches high
 - c. For all doors over 1-3/4-inches thick: 5-inches high
 - d. Size in width shall minimally clear door trim.
4. Application:
 - a. NRP (non-removable pin) at exterior doors and reverse bevel doors with locking hardware.
5. Acceptable manufacturers and types:

Stanley	McKinney
CB179	TCA714
CB168	TCA3786

C. Locksets:

1. Cylindrical Locks:
 - a. Conform to ANSI/BHMA A156.2, Series 4000 Operational Grade 1.
 - b. Latchbolt with appropriate throw for fire rated doors and pairs of doors in accordance with manufacturers listing.
 - c. Lock functions as specified in hardware schedule.
 - d. Lever design: 15C
 - e. Backset: 2-3/4-inch
 - f. Strike single door: ANSI 4-7/8-inch with proper lip length to minimally clear trim.
 - g. Strike pair of doors: flat lip strike sized to fit flush with face of door.
 - h. Furnish wrought strike box.
 - i. Acceptable manufacturers and types:

Best (Owner's Standard)
9K3 Series

2. Electronic Lock IDH Max® System Description:
 - a. Conform to ANSI/BHMA A156.2, Series 4000, Operational Grade 1.
 - b. UL listed for GYQS Electrically controlled single point locks or latches.
 - c. Reader integrated into lockset escutcheon.
 - d. Request to Exit (RQE) switch, door contact and latch status sensors inside lock case.
 - e. Weatherproof bezel and gasket to provide protection for outdoor use.
 - f. MS Magnetic Stripe option.
 - g. Include 1300 option to eliminate need for Panel Interface Module (PIM).
 - h. Oil impregnated stainless steel 3/4-inch anti-friction latchbolt.
 - i. Functions as specified in hardware schedule.
 - j. Acceptable manufacturer and type:

Best (Owner's Standard)
9KM Series

3. Keys & Keying

1. Cylinders: 7-pin, interchangeable core and keyed into a BEST Patented factory registered Masterkey System.
2. Provide construction cores and keys during construction period. Construction control and operating keys and cores are not part of permanent keying system or furnished on same keyway (or key section) as permanent keying system.
3. Permanent Keys and Cores: Prepare permanent cores and keys in accordance with keying schedule. Provide Grand Masterkeys, Masterkeys and other Security Keys.
4. Furnish keys in the following quantities:
 - a. 10 each Masterkeys per new Masterkey set.
 - b. 2 each Change keys each keyed core.
 - c. 10 each Construction Masterkeys.
 - d. 2 each Construction Control keys.
5. Install permanent cores in locksets.
6. Return construction cores to Hardware Supplier.
7. Proximity cards and magnetic stripe cards operate all power-operated doors. Must be ordered per Stockton's IT department to specify number range and facility code. 50 cards to be ordered.

D. Exit Devices:

1. UL-listed for fire at fire door assemblies, and UL listed for panic at non-rated door assemblies.
2. Size exit devices to proper door width and height.
3. Stainless Steel deadlocking 3/4-inch throw latch bolt.
4. LBR (less bottom rod) where scheduled to eliminate use of floor mounted strikes.
5. MLR (motorized latch retraction) where scheduled for reduced noise and lower current requirements. Provide power supply and power transfer.
6. Provide touch switch (TS) option with MLR devices.
7. Provide fire pins where LBR is schedule on fire rated doors.
8. Cylinders for exit devices with cylinder dogging or locking trim.
9. Strike: as recommended by manufacturer.
10. Lever design: To match lockset trim.
11. Acceptable manufacturers and types:

Precision
Apex 2000 Series

E. Surface Door Closers:

1. Conform to ANSI/BHMA A156.4 Grade 1.
2. Heavy duty cast aluminum body closers.
3. Furnish manufacturers recommended size, arms and configuration for door and frame application required.
4. Furnish brackets, spacers, support shoes, and plates for complete and proper installation.
5. Acceptable manufacturers and types:

Dorma	Sargent
8900 Series	350 Series

F. Overhead Doorstop:

1. Provide overhead stop or overhead stop/holder for interior doors as specified. Provide overhead stop for interior doors and at any door that swings more than 140 degrees before striking a wall, open against equipment, casework, sidelights, and/or where conditions do not allow a wall stop, or a floor stop presents a tripping hazard.
2. Where overhead holders are specified provide friction type at doors without a closer and positive type at doors with a closer.
3. Acceptable manufacturers:

ABH	Glynn Johnson	Rixson
9020 Series	90S	9-x36 Series

G. Protection Plates:

1. Where bottom rail allows, furnish 10-inch-high kick plates and 10-inch-high mop plates and 36-inch-high armor plates.
2. Material: 0.050-inch-thick stainless-steel plates with four beveled edges.
3. Countersink screw heads.
4. Width: 2-inch less door width on stop (push) side and 1-inch less door width on face (pull) side.
5. Both sides of doors.
6. Acceptable manufacturer and types:

Trimco	Burns	Rockwood
K0050	KP50	K1050

H. Door Stops:

1. Provide convex, cast, wall stops unless turn piece or push button on lockset handle makes contact with stop. Where contact is made provide concave wall stop.
2. Provide wedge type stop for doors with push/pulls.
3. Where wall stops cannot be used, provide universal dome type floor stops of the proper height.
4. Furnish fastener suitable for wall condition.
5. Acceptable manufacturers and types:

Type	Trimco	Burns	Rockwood
Wall-Convex	1270CX	560	400
Floor Stop	1211	510	441

I. Electric Strikes:

1. Comply with ANSI/BHMA A156.31, Grade 1.
2. Provide non-handed 24VDC electric strike suitable for door frame material and lock configuration scheduled.

3. Provide field selectable Fail Safe/Fail Secure modes.
4. Provide deadbolt strike where scheduled.
5. Include transformer and rectifier for complete installation.
6. Tie electric strikes into fire alarm where non-rated doors are scheduled to release with fire/sprinkler alarm condition.
7. Acceptable manufacturers:

HES
1500
9500

J. Power Transfers

1. Provide power transfer capable of accommodating sufficient number and gauge of wires to accommodate electric function of specified hardware.
2. Electric power transfer is to be located per manufacturer's template and UL requirements, unless interference with operation of door or other hardware item.
3. Acceptable manufacturer and type:

Precision	Securitron	ABH
EPT-12C	Equal	Equal

K. Thresholds and Gasketing:

1. Thresholds:
 - a. Returned closed ends at openings where threshold extends beyond frame face.
 - b. Silicone inserts at panic type thresholds.
 - c. Thresholds at exterior locations to be Thermal Break Thresholds.
 - d. Acceptable manufacturers and types:

Type	National Guard	Pemko
Bumper Saddle	896HD	2705
Saddle	425HD	1715

2. Gasketing:
 - a. Rigid jamb weatherstrip with replaceable silicone insert.
 - b. Nylon brush weatherstrip at Kitchen area.
 - c. Include self-adhesive two-sided tape in addition to manufacturer's standard fastener.
 - d. Meeting-stile gasketing required at exterior pairs of doors and doors in smoke partitions.
 - e. Flexible adhesive fire/smoke gasketing at "S" labeled openings.
 - f. Acceptable manufacturers and types:

Type	National Guard	Pemko	Reese
Rigid	700 NA	2891-PK	655
Flexible	2525	PK55	638CH

L. Silencers:

1. Grey rubber silencers with injector tool.
2. Three silencers at single doors and two silencers at pairs without door seal.
3. Acceptable manufacturers and types:

Trimco	Rockwood	Burns
1229A	608	500

2.3 FINISHES

A. Conform to ANSI/BHMA A156.18.

- | | | |
|--------------------|-----|-----------------------|
| 1. Exterior Hinges | 630 | Satin Stainless Steel |
| 2. Interior Hinges | 626 | Satin Chrome |

3. Locks and Latches	626	Satin Chrome
4. Exit Devices	626W	Satin Chrome Weatherized
5. Door Closers	689	Spray Painted Aluminum
6. Push/Pulls	630	Satin Stainless Steel
7. Protection Plates	630	Satin Stainless Steel
8. Stops and Holders	630	Satin Stainless Steel
9. Thresholds/Gasket Aluminum	AL	Anodized Mil Finished

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify doors and frames are plumb, square, level and true and free from defects that would prevent proper installation of finish hardware.
- B. Verify frames are securely anchored to floor.
- C. Verify power is run to doors requiring electrified hardware.
- D. Wash down masonry walls and complete painting and staining of doors and frames prior to installation of hardware.
- E. Verify fire rated openings have fire rating labels attached.
- F. Complete finish flooring at doorways.
- G. Correct conditions that inhibit a proper installation before continuing with work.

3.2 INSTALLATION

- A. Install hardware in compliance with the DHI publication, Installation Guide for Doors and Hardware.
- B. Drill and countersink items not factory prepared for fasteners.
- C. Mount closers on room-side of corridor doors, inside of exterior doors, and stair-side of stairway doors. Use necessary arms, brackets, spacers, and plates to accommodate auxiliary hardware and special applications.
- D. Install fire door assemblies to maintain clearances at door edge to frame and meeting edge of pairs of doors in compliance with NFPA 80, providing 1/8-inch clearance at the hinge edge, lock edge, head and between pairs. Provide maximum 3/4-inch undercut at door bottom. Where panic thresholds are used, undercut door to allow 1/8-inch clearance between door and threshold.
- E. Trim, cut, and notch thresholds and saddles neatly to minimally fit the profile of the door frame. Set thresholds in bed of mastic sealant, forming tight seal between threshold and surface to which set.
- F. Use only fasteners furnished by manufacturer for installation as recommended by manufacturer.
- G. Install blocking material for all wall mounted door stops at height appropriate to contact door trim.
- H. Install weather-strip prior to installation of door closers and exit devices. Do not cut or notch weather-strip.

- I. Termination of wiring: Ensure wiring is in place and is connected for proper operation of hardware.
- J. All power supplies to have installed sealed lead acid batteries minimum 7AH as supplied by Security Vendor.
- K. Power supplies not to be installed in ceilings, must be immediately accessible without a ladder supplied by Security Vendor.
- L. Power supplies to be on building emergency standby generator or backup power if available in building supplied by Security Vendor.

3.3 FIELD QUALITY CONTROL

- A. Verify doors open and close smoothly without rubbing or catching and have positive latching where scheduled. Verify fire rated doors are installed with clearances in compliance with NFPA 80.
- B. Test electrified hold open devices tied into fire alarm system to confirm release upon activation of fire alarm. Test electrified hardware and access control to verify systems operate as directed in mode of operation. Where hardware is found to be inoperable, repair or replace with new.

3.4 ADJUSTING AND CLEANING

- A. Upon substantial completion, make final adjustments to door closers and other items of hardware after balance of heating and ventilating equipment to ensure doors close and latch properly.
- B. Clean and polish all exposed hardware surfaces in accordance with manufacturer's recommended procedures.
- C. Clean or repair pencil or tool marks from adjacent surfaces damaged or soiled by work of this Section.
- D. Recycle cardboard boxes and paper products used in packaging and transport of finish hardware.

3.5 PROTECTION

- A. Remove hardware prior to painting or finishing door and frame. Wrap or mask exposed hardware that cannot be removed until date of substantial completion to avoid exposure to paint, solvents, and abuse.
- B. Repair or replace hardware damaged during construction at least two weeks prior to date of substantial completion.

3.6 SCHEDULES

- A. Should items of hardware not definitely specified be required for completion of the Work, furnish such items of type and quality comparable to adjacent hardware and appropriate for service required.
- B. Where items of hardware aren't definitely or correctly specified, are required for completion of the Work, a written statement of such omission, error, or other discrepancy to Architect, prior to date specified for receipt of bids for clarification by addendum; or furnish such items in the type and quality established by this specification, and appropriate to the service intended.

Manufacturer List

Code	Name
AB	ABH Manufacturing Inc.
BE	Best Access Systems
BY	By Related Section
DM	Dorma Door Controls
HS	HES
NA	National Guard
PR	BEST Precision Exit Devices
ST	BEST Hinges and Sliding
TR	Trimco

Option List

Code	Description
7/8"LTC	7/8" Lip-To-Center Strike
B4E-HEAVY-KP	BEVELED 4 EDGES - KICK PLATES
CSK	COUNTER SINKING OF KICK and MOP PLATES
S3	ANSI Strike Package
REX	Request to Exit
DPS	Door Position Switch

Finish List

Code	Description
26D	Satin Chrome
626	Satin Chromium Plated
630	Satin Stainless Steel
689	Aluminum Painted
GREY	Grey
US32D	Stainless Steel, Dull

Hardware Sets

Set #01 - Vestibule

Doors: BI-16A

1	Electric Strike	9600	630	HS
1	Magnetic/Prox Reader	Schlage MTMSK15		
1	REX	DS160 Assemblies		
1	DPS	184-12WG-W		
1	Reception Button			
1	Power Supply	BY GC's Security Vendor		BY
1	Credential Readers	CREDENTIAL READERS AS DIRECTED BY OWNER		BY
1	Lot access control wiring from door to data closet			

All labor to install, program, test, and document doors.

NOTE: Balance of hardware to remain. Verify new hardware with existing Frame/Door. Prep, patch and modify existing as required by GC. Operation: Door normally closed and locked. Presentation of valid credential to card reader allows authorized entry. Free egress at all times. Lock is fail secure, in the event of loss of power, door remains secured. Mechanical key override. Free egress at all times. All wiring and conduit by electrical contractor. Coordinate wiring with EC / GC / Security Contractor.

Set #02 - Corridor

Doors: BI-15A

1	Electric Strike	9600	630	HS
1	Magnetic/Prox Reader	Schlage MTMS15		
1	REX	DS160 Assemblies		
1	DPS	184-12WG-W		
1	Power Supply	BY GC's Security Vendor		BY
1	Credential Readers	CREDENTIAL READERS AS DIRECTED BY OWNER		BY
1	Lot access control wiring from door to data closet			
	All labor to install, program, test, and document doors.			

NOTE: Balance of hardware to remain. Verify new hardware with existing Frame/Door. Prep, patch and modify existing as required by GC. Operation: Door normally closed and locked. Presentation of valid credential to card reader allows authorized entry. Free egress at all times. Lock is fail secure, in the event of loss of power, door remains secured. Mechanical key override. Free egress at all times. All wiring and conduit by electrical contractor. Coordinate wiring with EC / GC / Security Contractor.

Set #03 - Closet

Doors: BI-15B

6	Butt Hinge	CB179 4.5" x 4.5"	26D	ST
2	Single Dummy	9K-01DT15C	626	BE
2	Overhead Stop	9020 Series	US32D	AB
2	Roller Latch	1559WB	626	TR
2	Silencer	1229A	GREY	TR

Set #04 - Access Control

Doors: BI-15J

6	Butt Hinge	CB179 4.5" x 4.5" NRP	26D	ST
1	Manual Flushbolt	3917-12	626	TR
	NOTE: Top Bolt Only			
1	Electromechanical Lock	9KM3-7DDEU15MS PATD 7/8"LTC	626	BE
	NOTE: PROVIDE TRACK 2			
2	Wall Bumper	1270CX	626	TR
1	Power Supply	BY GC's Security Vendor		BY
1	Power Transfer	EPT-5		PR
1	Meeting Stile Astragal	5070 CL		NA
1	Gasketing	5040 B @ Head & Jambs		NA
	IDH Lock			
	PTH Hinge			

1 Lot access control wiring from door to data closet
All labor to install, program, test, and document doors.

NOTE: Balance of hardware to remain. Verify new hardware with existing Frame/Door. Prep, patch and modify existing as required by GC. Operation: Door normally closed and locked. Presentation of valid credential to reader in electronic lockset unlocks lever to allow authorized entry. Lock is fail secure, in the event of loss of power, door remains secured. Mechanical key override. Free egress at all times. All wiring and conduit by electrical contractor. Coordinate wiring with EC / GC / Security Contractor.

Set #05 - Mailroom

Doors: BI-15F

3	Butt Hinge	CB179 4.5" x 4.5"	26D	ST
---	------------	-------------------	-----	----

1	Classroom Lockset	9K3-7R15C PATD S3	626	BE
1	Magnetic Holder	EM 504-24120	689	DM
1	Closer	8916 AF89	689	DM
1	Kick Plate	K0050 10" x 2" LDW B4E-Heavy CSK	630	TR
1	Gasketing	2525 C-17 17'		NA

NOTE: Verify new hardware with existing. Prep, patch or modify existing as required by GC.
 Operation: Door held open by magnetic holder. In the event of loss of power or activation of fire alarm, door will close and latch. Coordinate wiring with EC / GC / Security Contractor.

Set #06 - Restroom

Doors: BI-15D

3	Butt Hinge	CB179 4.5" x 4.5"	26D	ST
1	Privacy Set	9K3-0L15C S3	626	BE
1	Closer	8916 AF89	689	DM
1	Kick Plate	K0050 10" x 2" LDW B4E-Heavy CSK	630	TR
1	Mop Plate	KM050 10" x 1" LDW B4E CSK	630	TR
1	Wall Bumper	1270CX	626	TR
3	Silencer	1229A	GREY	TR

Set #07 - Storage

Doors: BI-15I, BI-15H

3	Butt Hinge	CB179 4.5" x 4.5"	26D	ST
1	Passage Set	9K3-0N15C S3	626	BE
1	Wall Bumper	1270CX	626	TR
3	Silencer	1229A	GREY	TR

NOTE: Verify new hardware with existing frame. Prep, patch or modify existing frame as required by GC.

Set #08 - Office, Storage

Doors: BI-15C, BI-15E

3	Butt Hinge	CB179 4.5" x 4.5"	26D	ST
1	Classroom Lockset	9K3-7R15C PATD S3	626	BE
1	Wall Bumper	1270CX	626	TR
3	Silencer	1229A	GREY	TR

Set #09 - Mailroom Office

Doors: BI-15

NOTE: No work required. All hardware to remain.

Opening List

Opening	Hdw Set	Opening Label	Door Type	Frame Type
BI-15	09			
BI-151	07			
BI-15A	02			
BI-15B	03			
BI-15C	08			
BI-15D	06			
BI-15E	08			
BI-15F	05			
BI-15H	07			
BI-15J	04			
BI-16A	01			

SECTION 09 21 16
GYPSUM BOARD ASSEMBLIES

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes gypsum board with joint treatment.

1.2 SYSTEM DESCRIPTION

- A. Conform to applicable code for fire rated assemblies and in conjunction with Drawings.

1.3 SUBMITTALS

- A. Product Data: Submit data on gypsum board, joint tape and joint compound.

1.4 QUALITY ASSURANCE

- A. Perform Work in accordance with ASTM C840.; GA-201 - Gypsum Board for Walls and Ceilings; GA-214 - Recommended Specification: Levels of Gypsum Board Finish.; GA-216 - Recommended Specifications for the Application and Finishing of Gypsum Board.

PART 2 PRODUCTS

2.1 GYPSUM BOARD ASSEMBLIES

- A. Manufacturers:
 - 1. G-P Gypsum Corp.
 - 2. National Gypsum Co.
 - 3. United States Gypsum Co.
 - 4. Substitutions: Architect/Owner Approved Equal.

2.2 COMPONENTS

- A. Gypsum Board Types: 5/8 inch thick, type "x" fire rated, and impact resistant (category 3 heavy duty), maximum available length in place; ends square cut, tapered edges; unless noted otherwise as follows:
 - 1. Moisture Resistant Type: ASTM C630.
 - 2. Abuse-Resistant Type (Category 3): ASTM D4977; ASTM D5420 (Category 2).
 - 3. Cement Board: ASTM D2394
 - 4. Exterior Sheathing – Dens-Glass Gold (or equal): ASTM D3273

2.3 ACCESSORIES

- A. Acoustic Sealant: Non-hardening, non-skinning, for use in conjunction with gypsum board.
- B. Corner Beads: Metal.
- C. Edge Trim: GA-216, Type LC bead.
- D. Joint Materials: ASTM C475; GA-201 and GA-216, reinforcing tape, joint compound, adhesive, and water.
- E. Fasteners: ASTM C1002 Type S12 hardened screws. and GA-216.
- F. Adhesive: ASTM C557. GA-216.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify site conditions are ready to receive work.

3.2 INSTALLATION

A. Gypsum Board:

1. Install gypsum board in accordance with GA-216 and GA-600.
2. Fasten gypsum board to furring or framing with screws.
3. Place control joints consistent with lines of building spaces as directed by Architect.
4. Place corner beads at external corners as indicated on Drawings. Use longest practical length. Place edge trim where gypsum board abuts dissimilar materials.
5. Seal cut edges and holes in moisture resistant gypsum board with sealant.

B. Joint Treatment:

1. Tape, fill, and sand exposed joints, edges, and corners to produce smooth surface ready to receive finishes.
2. Feather coats onto adjoining surfaces so camber is maximum 1/32 inch

- C. Tolerances: Maximum Variation from Flat Surface: 1/8inch in 10 feet in any direction.

PART 4 PAPER TYPE

- A. Paperless type gypsum board. All Gypsum Board is to be paper type only.

PART 5 CLARIFICATION

- A. All gypsum board is to be 5/8" type "X" fire dated impact from finish floor to 8'-0" above finish floor.
- B. All gypsum board above 8'-0" finish floor, up to be 5/8" type "X" fire rated for full height.

END OF SECTION

SECTION 09 22 16
NON-LOAD BEARING METAL FRAMING SYSTEM

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes metal stud framing and accessories at interior locations.
- B. Related Sections:
 - 1. Section 054000 - Cold-Formed Metal Framing.
 - 2. Section 092116 - Gypsum Board Assemblies.

1.2 REFERENCES

- A. ASTM International:
 - 1. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
 - 2. ASTM A591/A591M - Standard Specification for Steel Sheet, Electrolytic Zinc-Coated, for Light Coating Mass Applications.
 - 3. ASTM A653/A653M - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
 - 4. ASTM C645 - Standard Specification for Nonstructural Steel Framing Members.
 - 5. ASTM C754 - Standard Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products.
 - 6. ASTM C1002 - Standard Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases.
- B. National Association of Architectural Metal Manufacturers:
 - 1. NAAMM ML/SFA 540 - Lightweight Steel Framing Systems Manual.
- C. SSPC: The Society for Protective Coatings:
 - 1. SSPC Paint 20 - Zinc-Rich Primers (Type I - Inorganic and Type II - Organic).

1.3 SYSTEM DESCRIPTION

- A. Exterior Wall: Metal stud framing system infill, with batt insulation and interior gypsum board indicated on wall types (not required).
- B. Interior Walls: Metal stud framing system with batt type acoustic insulation and interior gypsum board indicated on wall types.
- C. Maximum Allowable Deflection: 1: 120 span.
- D. Wall System:
 - 1. Design to provide for movement of components without damage, failure of joint seals, undue stress on fasteners, or other detrimental effects when subject to seasonal or cyclic day/night temperature ranges.
 - 2. Design system to accommodate construction tolerances, deflection of building structural members, and clearances of intended openings.

1.4 SUBMITTALS

- A. Section 01 33 00 - Submittal Procedures: Submittal procedures.
- B. Shop Drawings:

1. Indicate prefabricated work, component details, stud layout, framed openings, anchorage to structure, type and location of fasteners, and accessories or items required of other related work.
 2. Describe method for securing studs to tracks, splicing, and for blocking and reinforcement to framing connections.
- C. Product Data: Submit data describing standard framing member materials and finish, product criteria, load charts, limitations.
- D. Manufacturer's Installation Instructions: Submit special procedures, perimeter conditions requiring special attention.

1.5 QUALITY ASSURANCE

- A. Perform Work in accordance with ASTM C754.
- B. Form, fabricate, install, and connect components in accordance with NAAMM ML/SFA 540.
- C. Furnish framing materials in accordance with SSMA - Product Technical Information.
- D. Maintain one copy of each document on site.

1.6 QUALIFICATIONS

- A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum three years documented experience.
 1. Framing Manufacturer: Current member of Steel Stud Manufacturers Association.
- B. Installer: Company specializing in performing Work of this section with minimum three years documented experience.
- C. Design structural elements under direct supervision of Professional Engineer experienced in design of this Work and licensed at Project location.

1.7 PRE-INSTALLATION MEETINGS

- A. Section 01 30 00 - Administrative Requirements: Pre-installation meeting.
- B. Convene minimum one week prior to commencing work of this section.

1.8 COORDINATION

- A. Section 01 30 00 - Administrative Requirements: Coordination and project conditions.

PART 2 PRODUCTS

2.1 METAL FRAMING SYSTEM

- A. Manufacturers:
 1. Clark Steel Framing Systems
 2. Dietrich Industries, Inc.
 3. Harrison Manufacturing Co.
 4. Marino/Ware
 5. Unimast Incorporated
 6. Substitutions: Architect/Owner Approved Equal.

2.2 COMPONENTS

- A. Framing System Components: ASTM C645.

- B. Studs: ASTM A653/A653M, non-load bearing rolled steel, channel shaped, punched for utility access, as indicated on wall types.
- C. Tracks and Headers: Same material and thickness as studs, bent leg retainer notched to receive studs [with provision for crimp locking to stud. Ceiling Runners: With extended leg retainer.
- D. Furring and Bracing Members: Of same material as studs; thickness to suit purpose.
- E. Fasteners: ASTM C1002, self drilling, self tapping screws.
- F. Sheet Metal Backing: 0.03 galvanized steel for reinforcement.
- G. Anchorage Devices: Power actuated.
- H. Acoustic Sealant: As specified in Section 09 21 16.
- I. Touch-Up Primer for Galvanized Surfaces: SSPC-Paint 20 Type II Organic.

2.3 FABRICATION

- A. Fabricate assemblies of framed sections to sizes and profiles required.
- B. Fit, reinforce, and brace framing members to suit design requirements.
- C. Fit and assemble in largest practical sections for delivery to site, ready for installation.

2.4 SHOP FINISHING

- A. Studs: Galvanize to G90, Z275 coating class.
- B. Tracks and Headers: Galvanize to G90, Z275 coating class.
- C. Accessories: Same finish as framing members.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Section 01 30 00 - Administrative Requirements: Coordination and project conditions.
- B. Verify rough-in utilities are in proper location.

3.2 INSTALLATION

- A. Align and secure top and bottom runners at 16 inches oc.
- B. Place two beads of acoustic sealant between runners and substrate, studs and adjacent construction to achieve vapor seal and acoustic seal.
- C. Fit runners under and above openings; secure intermediate studs to same spacing as wall studs.
- D. Install studs vertically at 16 inches oc.
- E. Align stud web openings horizontally.
- F. Secure studs to tracks using fastener method. Do not weld.
- G. Stud splicing not permissible.
- H. Fabricate corners using minimum of three studs.
- I. Double stud at wall openings, door and window jambs, not more than 2 inches (50 mm) from each side of openings.
- J. Brace stud framing system rigid.

- K. Coordinate erection of studs with requirements of door frames, window frames, install supports and attachments.
- L. Coordinate installation of wood bucks, anchors, and wood blocking with electrical and mechanical work to be placed within or behind stud framing.
- M. Blocking: Secure wood blocking to studs. [Secure steel channels to studs. Install blocking for support of plumbing fixtures, toilet partitions, wall cabinets, toilet accessories, hardware, opening frames.
- N. Refer to Drawings for indication of partitions extending to finished ceiling only and for partitions extending through ceiling to structure above. Maintain clearance under structural building members to avoid deflection transfer to studs. Install extended leg ceiling runners.
- O. Coordinate placement of insulation in stud spaces after stud frame erection.

3.3 ERECTION TOLERANCES

- A. Section 01 40 00 - Quality Requirements: Tolerances.
- B. Maximum Variation from Indicated Position: 1/8 inch in 10 feet.
- C. Maximum Variation from Plumb: 1/8 inch in 10 feet.

PART 4 MINIMUM CHANNEL SIZES

- 4.1 Interior 20-gauge (see plans for depth) at 16" O.C. at full height.
- 4.2 Exterior 18-gauge (see plans for depth) at 16" O.C. at full height (not required).

END OF SECTION

SECTION 09 30 00

CERAMIC TILE

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes ceramic, ceramic mosaic, quarry, tile for interior floor and wall applications; cementitious backer board as tile substrate; and thresholds at door openings.

1.2 SUBMITTALS

- A. Shop Drawings: Indicate patterned applications and thresholds.
- B. Product Data: Submit instructions for using grouts and adhesives.
- C. Samples: Submit mounted tile and grout on two plywood panels, 6 x 6 inch in size illustrating pattern, color variations, and grout joint size variations.

1.3 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: Submit recommended cleaning methods, cleaning materials, stain removal methods, and polishes and waxes.

1.4 QUALITY ASSURANCE

- A. Perform Work in accordance with TCA Handbook and ANSI A108.1 Series/A118.1 Series.
- B. Maintain one copy of each document on site.
- C. Manufacturer: Company specializing in manufacturing products specified in this section with minimum three years documented experience, and with service facilities within 100 miles of Project.
- D. Installer: Company specializing in performing Work of this section with minimum three documented experience approved by manufacturer.

1.5 ENVIRONMENTAL REQUIREMENTS

- A. Do not install adhesives in unventilated environment.
- B. Maintain ambient and substrate temperature of 50 degrees F
- C. Installation of mortar materials.

PART 2 PRODUCTS

2.1 TILE

- A. Manufacturers: All products same manufacturer.
 - 1. Dal-Tile

2. Substitutions: Architect/Owner Approved Equal.

2.2 COMPONENTS

- A. Ceramic Floor Tile: ANSI A137.1, conforming to the following:
 1. Manufacturer: Daltile
 2. Model: Marble Falls, Glazed Ceramic Tile
 3. Size: 18" x 18" x 5/16"
 4. Color: As selected by Owner.
 5. Substitutions: Architect/Owner Approved Equal.
- B. Ceramic Wall Tile: ANSI A137.1, conforming to the following:
 1. Manufacturer: Daltile
 2. Model: Marble Falls, Glazed Ceramic Tile
 3. Size: 5 1/4" x 8 1/2" x 5/16"
 4. Color: As selected by Owner.
 5. Substitutions: Architect/Owner Approved Equal.
- C. Base: Same as wall tile. Match tile for moisture absorption, surface finish, and color.
- D. Wainscot Cap: Bullnose tile to match wall tile.
- E. Grout Materials:
 1. Latex-Portland cement type as specified in ANSI A118.6; color as selected.
 2. Silicone Rubber Grout: Silicone sealant, moisture and mildew resistant type, complying with ANSI A118.6, color as selected use for shower floors and walls.
- F. Cementitious Backer Board: ANSI A118.9; High density, glass fiber reinforced, 5/8 inch thick; 2 inch wide coated glass fiber tape for joints and corners; manufactured by U.S.G.
- G. Tile Floor Edging: Square.

2.3 EXAMINATION

- A. Verify surfaces are ready to receive work.

2.4 PREPARATION

- A. Install cementitious backer board. Tape joints and corners, cover with skim coat of dry-set mortar to featheredge.

2.5 INSTALLATION

- A. Install tile, thresholds, and grout in accordance with applicable requirements of ANSI A108.1 through A108.10, and TCA Handbook recommendations.
- B. Cut and fit tile to penetrations through tile, leaving sealant joint space. Form corners and bases neatly. Align floor, base and wall joints. Sharp edges at all exposed corners will not be accepted.
- C. Place tile joints uniform in width, subject to variance in tolerance allowed in tile size. Make joints watertight, without voids, cracks, excess mortar, or excess grout.

- D. Grout tile joints. Use standard grout unless otherwise indicated.
- E. Floors:
 - 1. Over interior concrete substrates, install in accordance with TCA Handbook Method F113, dry-set or latex-portland cement bond coat F116, organic adhesive, with standard grout, unless otherwise indicated.
 - a. Where waterproofing membrane is indicated, install in accordance with TCA Handbook Method F122, with latex-portland cement grout.
- F. Showers And Bathtub Walls:
 - 1. At tiled shower receptors install in accordance with TCA Handbook Method B415, mortar bed floor, and W244, thin-set over cementitious backer unit walls.
 - 2. Grout with silicone rubber grout.
 - 3. Seal joints between tile work and other work with sealant.
- G. Wall Tile:
 - 1. Over cementitious backer units install in accordance with TCA Handbook Method W244, using membrane at toilet rooms, kitchens, locker rooms and W223, organic adhesive.
 - 2. Over gypsum wallboard metal studs install in accordance with TCA Handbook Method W243, thin-set with dry-set or latex-portland cement bond coat W223, thin-set with organic adhesive, unless otherwise indicated.
 - 3. Over interior concrete and masonry install in accordance with TCA Handbook Method W202, thin-set with dry-set or latex-portland cement bond coat.

END OF SECTION

SECTION 09 51 13
ACOUSTICAL CEILINGS

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes suspended metal grid ceiling system and acoustic tile.

1.2 SYSTEM DESCRIPTION

- A. Provide system capable of supporting imposed loads with deflection limited to 1:360.
- B. Installed System: Conform to UL rating for ceiling assemblies.
- C. Conform to applicable code for fire rated assembly and combustibility requirements.

1.3 SUBMITTALS

- A. Product Data: Submit manufacturer's product data.
- B. Samples: Submit ceiling tile suspension and all related accessories, including seismic struts.

1.4 QUALITY ASSURANCE

- A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum three years documented experience, and with service facilities within 100 miles of Project.
- B. Installer: Company specializing in performing Work of this section with minimum three years documented experience, approved by manufacturer.

1.5 ENVIRONMENTAL REQUIREMENTS

- A. Maintain uniform temperature of minimum 60 degrees F and maximum humidity acoustic unit installation.

PART 2 PRODUCTS

2.1 SUSPENDED ACOUSTICAL CEILINGS

- A. Manufacturers:
 - 1. USG (Basis of design)
 - 2. Substitutions: Architect/Owner Approved Equal.

2.2 COMPONENTS

- A. ACT-1, Acoustic Tiles: ASTM E1264 conforming to the following:
 - 1. Manufacturer: USG
 - 2. Model #: Radar Basic Acoustical Panels 2110.
 - 3. Nominal Size: 24 x 24 inches.
 - 4. Thickness: 5/8"
 - 5. NRC: 0.55
 - 6. CAC: 33
 - 7. Fire Resistance: Class A
 - 8. Color: White.
 - 9. Grid: DONN DXL Fire rated Grid System 15/16" & hold down clips.
 - a. Seismic: Installation to be in compliance with the manufacturer's requirements for a Standard Seismic Application, IBC Category "C".

- b. Accessories: Stabilizer bars, clips, splices, edge moldings, hold down clips, etc, as required for suspended grid system, seismic application.
 - c. Grid Materials: Commercial quality cold rolled steel with galvanized coating.
 - d. Grid Finish: Color as selected by Architect/Owner from all available standard & advantage colors.
 - e. Support Channels and Hangers: Galvanized steel, size and type to suit application and ceiling system flatness requirement specified.
10. Substitutions: Architect/Owner Approved Equal.
- B. ACT-2, Acoustic Tiles: ASTM E1264 conforming to the following:
- 1. Manufacturer: USG
 - 2. Model #: Radar Ceramic Acoustical Panels 56644.
 - 3. Nominal Size: 24 x 24 inches.
 - 4. Thickness: 5/8"
 - 5. NRC: 0.50
 - 6. CAC: 40
 - 7. Fire Resistance: Class A
 - 8. Color: White.
 - 9. Grid: DONN ZXLA 15/16" acoustical suspension system & hold down clips.
 - a. Seismic: Installation to be in compliance with the manufacturer's requirements for a Standard Seismic Application, IBC Category "C".
 - b. Accessories: Stabilizer bars, clips, splices, edge moldings, hold down clips, etc, as required for suspended grid system, seismic application.
 - c. Grid Materials: Commercial quality cold rolled steel with galvanized coating.
 - d. Grid Finish: Color as selected by Architect/Owner from all available standard & advantage colors.
 - e. Support Channels and Hangers: Galvanized steel, size and type to suit application and ceiling system flatness requirement specified.
 - 10. Substitutions: Architect/Owner Approved Equal.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify layout of hangers does not interfere with other work.

3.2 INSTALLATION

- A. Suspension System:
 - 1. Install system in accordance with ASTM C636, AND UL.
 - 2. Coordinate location of hangers with other work. Where components prevent regular spacing of hangers, reinforce system to span extra distance.
 - 3. Hang system independent of walls, columns, ducts, pipes and conduit.
 - 4. Locate system on room axis leaving equal border units according to reflected plan.
 - 5. Install edge molding at intersection of ceiling and vertical surfaces, using longest practical lengths.
 - 6. Install only in conditioned spaces.
- B. Acoustic Units:
 - 1. Install acoustic units' level, free from damage, twist, warp or dents.
- C. Tolerances: Variation from Flat and Level Surface: 1/8 inch in 10 feet.
- D. Match existing

END OF SECTION

SECTION 09 90 00
PAINTS AND COATINGS

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes surface preparation and field application of paints and other coatings.

1.2 SUBMITTALS

- A. Product Data: Submit data on finishing products and special coating.
- B. Samples: Submit two (2) paper chip samples, 2 inches x 2 inches in size illustrating range of colors and textures available for each surface finishing product scheduled.

1.3 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: Submit maintenance and cleaning instructions.

1.4 QUALITY ASSURANCE

- A. Surface Burning Characteristics:
 - 1. Fire Retardant Finishes: Maximum 25/450 flame spread/smoke developed index when tested in accordance with ASTM E84.
- B. Perform Work in accordance with State of New Jersey Public Work's standard.
- C. Maintain one copy of each document on site.

1.5 ENVIRONMENTAL REQUIREMENTS

- A. Store and apply materials in environmental conditions required by manufacturer's instructions.

PART 2 PRODUCTS

2.1 PAINTS AND COATINGS

- A. Manufacturers:
 - 1. Sherman Williams.
 - 2. Benjamin Moore.
 - 3. Pratt and Lambert.
 - 4. Substitutions: Architect/Owner Approved Equal.

2.2 COMPONENTS

- A. Coatings: Ready mixed except field catalyzed coatings of good flow and brushing properties, capable of drying or curing free of streaks or sags.
- B. Accessory Materials: Linseed oil, shellac, turpentine, paint thinners and other materials required to achieve finishes specified.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify substrate conditions are ready to receive Work.

- B. Measure moisture content of porous surfaces using electronic moisture meter. Do not apply finishes unless moisture content is less than 15 percent.

3.2 PREPARATION

- A. Correct minor defects and clean surfaces affecting work of this section.
- B. Remove electrical plates, hardware, light fixture trim, escutcheons, and fittings prior to preparing surfaces or applying finishes.
- C. Gypsum Board Surfaces: Fill minor defects with filler compound. Spot prime defects after repair.
- D. Galvanized Surfaces: Remove surface contamination and oils and wash with solvent. Apply coat of etching primer.
- E. Concrete and Unit Masonry Surfaces Scheduled to Receive Paint Finish: Remove foreign matter. Remove oil and grease with solution of tri-sodium phosphate, rinse well and allow to dry.
- F. Uncoated Steel and Iron Surfaces: Remove scale by wire brushing, sandblasting, and clean by washing with solvent. Apply treatment of phosphoric acid solution. Prime paint after repairs.
- G. Shop Primed Steel Surfaces: Sand and scrape to remove loose primer and rust. Clean surfaces with solvent. Prime bare steel surfaces.
- H. Exterior Wood Scheduled to Receive Paint Finish: Remove dust, grit, and foreign matter. Seal knots, pitch streaks, and sappy sections. Fill nail holes with tinted exterior paintable caulking compound after prime coat has been applied.

3.3 APPLICATION

- A. Sand wood surfaces lightly between coats to achieve required finish.
- B. Where clear finishes are required, tint fillers to match wood.
- C. Prime concealed surfaces of exterior woodwork with primer paint.
- D. Cleaning: As work proceeds, promptly remove finishes where spilled, splashed, or spattered.

3.4 SCHEDULE - INTERIOR SURFACES

- A. Plaster, Gypsum Board:
 - 1. One coat of alkyd primer sealer.
 - 2. Two coats latex enamel, Eggshell.

PART 4 MANUFACTURER PREPARATION & COATING RECOMMENDATIONS

4.1 SURFACE PREPARATION

- A. All existing painted areas should be thoroughly cleaned using the most practical and efficient method to remove dirt, dust, oils, fingerprints, graffiti and all other surface contaminants. Utilize proper and suitable cleaners as necessary to accomplish the task. Both the KrudKutter Gloss Off and KrudKutter Graffiti Remover can be considered as possible choices or architect approved equal.
- B. All painted block wall and metal frame areas should be further inspected, and possible loose or loosely adhering paint should be properly prepared and removed back to a firm substrate.
- C. The above recommendations supersede any conflicting items in PART 3.2 above.

4.2 SCHEDULE OF COATINGS

- A. Interior Metal Door Frames- Existing and painted with unknown coatings, possible peeling / bare metal areas:
 - 1. Spot primer for bare metal ONLY: S-W Pro Industrial Pro-Cryl WB Universal Primer B66-310 or Architect approved equal.
 - 2. Full overall primer for painted areas ONLY: S-W Adhesion Primer B51W8050 or Architect approved equal.
 - 3. Finish with (2) two coats of S-W ProClassic Interior WB Acrylic-Alkyd Semi-Gloss B34W850 or Architect/Owner approved equal.
- B. The above recommendations supersede any conflicting items in PART 3.5 above.

END OF SECTION

SECTION 10 00 00
MISCELLANEOUS SPECIALTIES

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes full height shades, markerboards, projection screens out.

1.2 SUBMITTALS

- A. Shop Drawings: Indicate component locations, dimensions, details of blocking and attachment, anchors, and finish as applicable for ALL items.
- B. Product Data: Submit data on Product, accessories.
- C. Samples: Submit two samples, illustrating surface finish and color as required by item.

1.3 CLOSEOUT SUBMITTALS

- A. Operating and Maintenance Data: Submit instructions for recharging fire extinguishers.

1.4 QUALITY ASSURANCE

- A. To conform with the warranties as stipulated by the individual manufacturer specified.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers:
1. As specified for each item.
 2. Substitutions: Architect/Owner Approved Equal

2.2 COMPONENTS

- A. FRP Wall Panels:
1. Provide and install new toilet FRP (“3/32”) fiberglass reenforced panels as manufactured by Marlite or approved equal. Premium grade. Colors and patterns as selected by Owner. Install as per manufacturers’ guide specification.
- B. Roll Down Shutter:
1. Provide and install roll down aluminum shutter, as indicated on the drawings. Shutter and accessories shall be installed as per manufacturers’ guide specification. Provide security locking device on service side (minimum size 5’-0’ wide x 4’x0” high).
 - a. Shutter as manufactured by Raynor or approved equal.
 - b. Unit to have built-in frame.
 - c. 1/2” horsepower unit (MGI operator).
 - d. Slat type as selected: 050 aluminum.
 - e. Color as selected, power coated.
 - f. Tie motor to breaker in electrical room.
 - g. Motor to be button operated with full safety features.
- C. Floor Finishes:
1. Provide and install at the new toilet 1/8”x12”x12” nonslip tile. Premium grade. Color as selected by Owner, manufactured by Excel or approved equal.
 2. LVT tile to match existing by Mohawk Group “Living Local” Collection or approved equal. Colors and patterns as selected by Owner.

3. Carpeting to match existing by Mohawk Group or approved equal.
- D. Electrical:
 1. Provide and install new electrical subpanel, switches, and outlets as indicated on drawings. Tie back into electrical room B1-14A.
- E. Kitchen Cabinets:
 1. Provide and install kitchen cabinets and countertops as indicated on the drawings. As manufactured by Richelieu Company or approved equal.
- F. ADA Accessories:
 1. Provide and install ADA Accessories as indicated on the drawings, including all facets, etc.
- G. Fire Extinguishers:
 1. Provide and install wall mounted 15lb ABC fire extinguishers by Fryer or approved equal. Field set, one in the mail room and one in the tenant space.

PART 3 EXECUTION

3.1 Examination

- A. Verify surfaces and internal wall blocking are ready to receive work and opening dimensions are as indicated on shop drawings and/or instructed by manufacturer

3.2 INSTALLATION

- A. Establish exact locations and layout in accordance with shop drawings.
- B. Secure units' level and plumb.

3.3 SPECIAL NOTE

- A. All items indicated in this section require the contractor to provide shop drawings.
- B. All items to be installed as per manufacturer's guide specifications.

END OF SECTION

SECTION 10 14 00
INTERIOR SIGNAGE

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes interior signs.

1.2 SUBMITTALS

- A. Section 01 33 00 - Submittal Procedures.
- B. Shop Drawings: Indicate sign styles, lettering font, foreground and background colors, locations, overall dimensions of each sign.
- C. Samples: Submit two signs of each sign type, to match specified sign sizes, illustrating type, style, letter font, and colors specified; method of attachment.
- D. Manufacturer's Installation Instructions: Submit installation template and attachment devices.

1.3 QUALIFICATIONS

- A. Manufacturer: Company specializing in manufacturing Products specified in this section with minimum three years documented experience.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Section 01 60 00 - Product Requirements.
- B. Package signs, labeled in name groups.
- C. Store adhesive attachment tape at ambient room temperatures.

1.5 ENVIRONMENTAL REQUIREMENTS

- A. Section 01 60 00 - Product Requirements: Environmental conditions affecting products on site.
- B. Do not install signs when ambient temperature is lower than recommended by manufacturer.
- C. Maintain this minimum temperature during and after installation of signs.

PART 2 PRODUCTS

2.1 INTERIOR SIGNS – Provide 1 sign per door; all doors, new, are to receive a minimum of 1 sign each. 4 new and 2 existing toilets.

- A. Manufacturers:
 - 1. Mohawk Sign Systems, Inc. **(Basis of Design)**
Contact: 518-842-5303
 - 2. Substitutions: Architect/Owner Approved Equal
- B. Product Description: Refer to drawings for additional information & requirements.

2.2 COMPONENTS

- A. Signs:
 - 1. Face Color: Color as selected by Owner
 - 2. Core Color: Color as selected by Owner
 - 3. Total Thickness: 1/8" minimum

4. Sign Dimensions: Restrooms: 6" x 8" ADA Room Sign
All other rooms: 5" x 5" ADA Room Sign
3.4" x 5" Business Card Sign
5. Character Font: As selected by Owner
6. All signs to have Grade II Braille Translation
7. All Signs to conform to ICC/ANSI A117.1 -2009
8. Coordinate with Owner for exact room names, numbers, & locations prior to construction.
9. Submit color choices and letter styles to Architect for selection
10. Refer to construction drawings for additional information & requirements.

2.3 ACCESSORIES

- A. Mounting Hardware: Chrome screws.
- B. Tape Adhesive: Double sided tape, permanent adhesive.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Section 01 30 00 - Administrative Requirements: Verification of existing conditions before starting work.

3.2 INSTALLATION

- A. Install signs after doors surfaces are finished; locations to be determined with Owner and Architect.
- B. Signs are to be wall mount, level, located adjacent to corresponding door location.
- C. Provide sign on each new door.

END OF SECTION

SECTION 10 28 00
TOILET ACCESSORIES

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes toilet and washroom accessories.

1.2 SUBMITTALS

- A. Product Data: Submit data on accessories describing size, finish, details of function, attachment methods.
- B. Samples: Submit two samples of each accessory, illustrating color and finish.

PART 2 PRODUCTS

2.1 TOILET AND BATH ACCESSORIES

- A. Manufacturers:
 - B. 1. Bradley Washroom Accessories
 - 2. Bobrick Washroom Accessories
 - 3. Bay West Washroom Accessories
 - 4. Rubbermaid Washroom Accessories
 - 5. Substitutions: Architect/Owner Approved Equal.

2.2 COMPONENTS

- A. Products listed on Drawings
- B. Furnish 3 sets of keys for each accessory to Owner. (as applicable)

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify exact location of accessories for installation.

3.2 PREPARATION

- A. Deliver inserts and rough-in frames to site. Provide templates and rough-in measurements.

3.3 INSTALLATION

- A. Install plumb and level, securely and rigidly anchored to substrate.
- B. Mounting Heights and Locations: As required by accessibility regulations; ICC/ANSI A117.1 - 2009
 - 1. Coordinate with Drawings.
 - 2. Coordinate all clearances and mounting locations prior to accessory installation and report any dimensional discrepancies or conflicts to the architect for review.

3.4 SCHEDULES

- A. Refer to Drawings for Schedule of accessories; model numbers and mounting heights.
- B. All toilet accessories shall be ADA accessible.

END OF SECTION

SECTION 12 35 30

CASEWORK

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes shop fabricated plastic laminate casework units and designated.

1.2 SUBMITTALS

- A. Shop Drawings: Indicate casework locations, scale plans, elevations, clearances required and finishes.
- B. Product Data: Submit data on component profiles, sizes, assembly methods, and schedule of finishes.
- C. Samples: Submit two panels, 4 x 4 inches in size illustrating cabinet, backsplash and countertop finish.
- D. Samples: Submit hardware samples.

1.3 QUALITY ASSURANCE

- A. Perform Work in accordance with Manufacturers Requirements.

1.4 ENVIRONMENTAL REQUIREMENTS

- A. Install after interior temperature and humidity are controlled and stabilized.

1.5 MANUFACTURER

- A. Manufacturer:
 - 1. Mastercraft Woodworking Co., Inc.
 - 2. Substitutions: Architect/Owner Approved Equal

PART 2 PRODUCTS

2.1 CABINETS

- A. Cabinet Construction:
 - 1. Design "Reveal Overlay Design" as defined by the Architectural Woodwork Institute.
 - 2. Joinery: Dowel Construction.
 - 3. Bases: Integral toe-base made of same material and finishes as cabinet.
 - 4. Tops and Bottoms: Full solid tops and bottoms of 3/4" particleboard. Semi-exposed surfaces to be covered with thermo-fused melamine with 1 mm PVC edge banding.
 - 5. Ends and Partitions: 3/4" particleboard construction. Exposed surfaces to be covered with melamine cabinet liner. Exposed edges to have 1 mm PVC edge banding.
 - 6. Adjustable Shelves: 1" particleboard with thermo-fused melamine surfaces and 1 mm PVC edge banding.
 - 7. Doors and Drawer Fronts: Overlay design constructed of 3/4" high-pressure vertical grade NEMA GP28 laminate exterior and high-pressure cabinet liner interior. All edges to have 3mm PVC edge banding.
 - 8. Drawers: Drawer box assembled with dowels spaced at 1 1/4". Constructed of 5/8" MDF with white melamine laminate on interior and exterior surface3s. Edges to have 1 mm PVC edge banding.

2.2 HARDWARE

- A. Hardware:
 - 1. Hinges: 2-3/4", five knuckle, overlay type, hospital tipped. .090-inch-thick steel.
 - 2. Pulls: 4-inch wire type.

3. Drawer Suspensions: Bottom mount, epoxy coated with 120-pound minimum load capacity.
4. Door Catches: Magnetic type with slotted screw adjustment.
5. Adjustable Shelf Support: Heavy-duty nylon shelf clips.
6. Locks: Five-tumbler cam type lock. Keyed different with master keying system.
7. Finishes: All available options from standard finishes.

2.3 COUNTERTOPS

- A. Countertops: Tops to be constructed of 1" thick plywood construction. *All exposed tops and sides to have plastic laminate finishes. Top dimensions shall be seamless. The choice of all standard plastic laminate styles to be provided to the architect for selection.
- B. As basis of design, all plastic laminate surfaces are to be as manufactured by "Wilsonart", model: High Wear Laminate, General Purpose (HGS) Type 107HW or an Architect/Owner Approved Equal. Styles and colors to be selected by Owner/Architect from all available standard options pertaining to this series.
- C. Backsplashes: Provide full height plastic laminate backsplash at all cabinets located against full height wall conditions (i.e.: kitchenette, employee break room area, etc.). Coordinate with architect for exact locations.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify adequacy of backing and location of mechanical and electrical outlets.

3.2 PREPARATION

- A. Install supplementary support framing.

3.3 INSTALLATION

- A. Set and secure casework in place rigid, plumb, and level.
- B. Provide cutouts for plumbing fixtures, appliances, and other fixtures and fittings.
- C. Use fixture attachments at concealed locations for wall mounted components.
- D. Use concealed joint fasteners to align and secure adjoining cabinet units and counter tops.
- E. Carefully scribe casework against other building materials, leaving gaps of 1/32 inches maximum. Use filler strips not additional overlay trim for this purpose.
- F. Secure cabinet and counter bases to walls and floor using appropriate anchorage depending on installation locations.
- G. Adjust moving or operating parts to function smoothly and correctly.
- H. Install backsplashes and end splashes.
- I. Installation shall be performed by the manufacturer's authorized representative and shall conform to the manufacturer's procedures.
- J. All connecting hardware, fillers, and closure panels shall be provided as required.
- K. Clean all casework upon completion.

PART 4 WARRANTY

- A. Warranty: All casework furnished under this section shall be guaranteed for a period of one year after final Certificate of Occupancy notice.

END OF SECTION

SECTION 210529 - HANGERS AND SUPPORTS FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Metal pipe hangers and supports.
2. Trapeze pipe hangers.
3. Metal framing systems.
4. Thermal hanger-shield inserts.
5. Fastener systems.
6. Equipment supports.

- B. Related Requirements:

1. Section 055000 "Metal Fabrications" for structural-steel shapes and plates for trapeze hangers for pipe and equipment supports.
2. Section 210516 "Expansion Fittings and Loops for Fire-Suppression Piping" for pipe guides and anchors.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

- B. Shop Drawings: Signed and sealed by a qualified professional engineer. Show fabrication and installation details and include calculations for the following:

1. Trapeze pipe hangers.
2. Metal framing systems.
3. Equipment supports.

- C. Delegated-Design Submittal: For trapeze hangers indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1. Detail fabrication and assembly of trapeze hangers.
2. Include design calculations for designing trapeze hangers.

1.4 INFORMATIONAL SUBMITTALS

- A. Welding certificates.

1.5 QUALITY ASSURANCE

- A. Structural-Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M.
- B. Pipe Welding Qualifications: Qualify procedures and operators according to 2015 ASME Boiler and Pressure Vessel Code, Section IX.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design trapeze pipe hangers and equipment supports.
- B. Structural Performance: Hangers and supports for fire-suppression piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
 - 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
 - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
 - 3. Design seismic-restraint hangers and supports for piping and equipment.
- C. NFPA Compliance: Comply with NFPA 13.
- D. UL Compliance: Comply with UL 203.

2.2 METAL PIPE HANGERS AND SUPPORTS

- A. Carbon-Steel Pipe Hangers and Supports:
 - 1. Description: Factory-fabricated components, NFPA approved, UL listed, or FM approved for fire-suppression piping support.
 - 2. Galvanized Metallic Coatings: Pregalvanized or hot-dip galvanized.
 - 3. Hanger Rods: Continuous-thread rod, nuts, and washer made of stainless steel.
- B. Copper Pipe and Tube Hangers:
 - 1. Description: Copper-coated-steel, factory-fabricated components, NFPA approved, UL listed, or FM approved for fire-suppression piping support.
 - 2. Hanger Rods: Continuous-thread rod, nuts, and washer made of stainless steel.

2.3 TRAPEZE PIPE HANGERS

- A. Description: MSS SP-58, Type 59, shop- or field-fabricated pipe-support assembly, made from structural-carbon-steel shapes, with NFPA-approved, UL-listed, or FM-approved carbon-steel hanger rods, nuts, saddles, and U-bolts.

2.4 METAL FRAMING SYSTEMS

- A. MFMA Manufacturer Metal Framing Systems:

- 1. Description: Shop- or field-fabricated pipe-support assembly, made of steel channels, accessories, fittings, and other components for supporting multiple parallel pipes.
- 2. Standard: Comply with MFMA-4, factory-fabricated components for field assembly.
- 3. Channels: Continuous slotted carbon steel channel with inturned lips.
- 4. Channel Width: Selected for applicable load criteria.
- 5. Channel Nuts: Formed or stamped nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
- 6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
- 7. Metallic Coating: Hot-dip galvanized.
- 8. Paint Coating: Green epoxy, acrylic, or urethane.

- B. Non-MFMA Manufacturer Metal Framing Systems:

- 1. Description: Shop- or field-fabricated pipe-support assembly, made of steel channels, accessories, fittings, and other components for supporting multiple parallel pipes.
- 2. Standard: Comply with MFMA-4, factory-fabricated components for field assembly.
- 3. Channels: Continuous slotted carbon steel channel with inturned lips.
- 4. Channel Width: Select for applicable load criteria.
- 5. Channel Nuts: Formed or stamped nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
- 6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
- 7. Metallic Coating: Hot-dip galvanized.
- 8. Paint Coating: Green epoxy, acrylic, or urethane.

2.5 THERMAL HANGER-SHIELD INSERTS

- A. Insulation-Insert Material: Water-repellent-treated, ASTM C533, Type I calcium silicate with 100-psi minimum compressive strength.
- B. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- C. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- D. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.6 FASTENER SYSTEMS

- A. Powder-Actuated Fasteners: NFPA-approved, UL-listed, or FM-approved threaded-steel stud, for use in hardened portland cement concrete, with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
- B. Mechanical-Expansion Anchors: NFPA-approved, UL-listed, or FM-approved, insert-wedge-type anchors, for use in hardened portland cement concrete; with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
 - 1. Indoor Applications: Stainless steel.
 - 2. Outdoor Applications: Stainless steel.

2.7 EQUIPMENT SUPPORTS

- A. Description: NFPA-approved, UL-listed, or FM-approved, welded, shop- or field-fabricated equipment support, made from structural-carbon-steel shapes.

2.8 MATERIALS

- A. Aluminum: ASTM B221.
- B. Carbon Steel: ASTM A1011/A1011M.
- C. Structural Steel: ASTM A36/A36M, carbon-steel plates, shapes, and bars; black and galvanized.
- D. Stainless Steel: ASTM A240/A240M.
- E. Grout: ASTM C1107/C1107M, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout, suitable for interior and exterior applications.
 - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping materials and installation, for penetrations through fire-rated walls, ceilings, and assemblies.
- B. Strength of Support Assemblies: Where not indicated, select sizes of components, so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.

3.2 INSTALLATION OF HANGERS AND SUPPORTS

- A. Metal Pipe-Hanger Installation: Comply with installation requirements of approvals and listings. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.
- B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-58. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.
 - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size, or install intermediate supports for smaller-diameter pipes as specified for individual pipe hangers.
 - 2. Field fabricate from ASTM A36/A36M carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.
- C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal strut systems.
- D. Thermal Hanger-Shield Installation: Install in pipe hanger or shield for insulated piping.
- E. Fastener System Installation:
 - 1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete, after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual. Install in accordance with approvals and listings.
 - 2. Install mechanical-expansion anchors in concrete, after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions. Install in accordance with approvals and listings.
- F. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.
- G. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- H. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- I. Install lateral bracing with pipe hangers and supports to prevent swaying.
- J. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms, and install reinforcing bars through openings at top of inserts.
- K. Load Distribution: Install hangers and supports, so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.

- L. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.
- M. Insulated Piping:
 - 1. Attach clamps and spacers to piping.
 - a. Piping Operating Above Ambient Air Temperature: Clamp may project through insulation.
 - b. Piping Operating Below Ambient Air Temperature: Use thermal hanger-shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
 - 2. Install MSS SP-58, Type 39 protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
 - a. MSS SP-58, Type 39 Option: Thermal hanger-shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
 - 3. Install MSS SP-58, Type 40 protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
 - a. MSS SP-58, Type 40 Option: Thermal hanger-shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
 - 4. Shield Dimensions for Pipe: Not less than the following:
 - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
 - b. NPS 4: 12 inches long and 0.06 inch thick.
 - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
 - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
 - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
 - 5. Pipes NPS 8 and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
 - 6. Thermal Hanger Shields: Install with insulation of same thickness as piping insulation.

3.3 INSTALLATION OF EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment, and make bearing surface smooth.
- C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.4 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:
 - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. Finish welds at exposed connections, so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

3.5 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.6 PAINTING

- A. Touchup:
 - 1. Clean field welds and abraded, shop-painted areas. Paint exposed areas immediately after erecting hangers and supports. Use same materials as those used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 - a. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas, and apply galvanizing-repair paint to comply with ASTM A780/A780M.

3.7 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with NFPA requirements for pipe-hanger selections and applications that are not specified in piping system Sections.

- C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finishes.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use carbon-steel pipe hangers and supports and attachments for general service applications.
- F. Use copper-plated pipe hangers and copper or stainless-steel attachments for copper piping and tubing.
- G. Use thermal hanger-shield inserts for insulated piping and tubing.
- H. Horizontal-Piping Hangers and Supports: Comply with NFPA requirements. Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
 - 2. Steel Pipe Clamps (MSS Type 4): For suspension of NPS 1/2 to NPS 24 if little or no insulation is required.
 - 3. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
 - 4. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.
 - 5. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.
 - 6. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
 - 7. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
 - 8. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
 - 9. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
- I. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
 - 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.
- J. Hanger-Rod Attachments: Comply with NFPA requirements.
- K. Building Attachments: Comply with NFPA requirements. Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Steel or Malleable-Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.

2. C-Clamps (MSS Type 23): For structural shapes.
 3. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
- L. Saddles and Shields: Comply with NFPA requirements. Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
 3. Thermal Hanger-Shield Inserts: For supporting insulated pipe.
- M. Comply with NFPA requirements for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- N. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.
- O. Use powder-actuated fasteners or mechanical-expansion anchors instead of building attachments where required in concrete construction.

END OF SECTION 210529

SECTION 211313 - WET-PIPE SPRINKLER SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Pipes, fittings, and specialties.
 - 2. Sprinklers.

1.3 DEFINITIONS

- A. Standard-Pressure Sprinkler Piping: Wet-pipe sprinkler system piping designed to operate at working pressure of 175-psig maximum.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
- B. Shop Drawings: For wet-pipe sprinkler systems.
 - 1. Include plans, elevations, sections, and attachment details.
 - 2. Include diagrams for power, signal, and control wiring.
- C. Delegated-Design Submittal: For wet-pipe sprinkler systems indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Sprinkler systems, or BIM model, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved.
- B. Qualification Data: For qualified Installer.

C. Design Data:

1. Approved Sprinkler Piping Drawings: Working plans, prepared according to NFPA 13, that have been approved by authorities having jurisdiction, including hydraulic calculations if applicable.

D. Welding certificates.

E. Field Test Reports:

1. Indicate and interpret test results for compliance with performance requirements and as described in NFPA 13. Include "Contractor's Material and Test Certificate for Aboveground Piping."
2. Fire-hydrant flow test report.

F. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For wet-pipe sprinkler systems and specialties to include in emergency, operation, and maintenance manuals.

1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Sprinkler Cabinets: Finished, wall-mounted, steel cabinet with hinged cover, and with space for minimum of six spare sprinklers plus sprinkler wrench. Include number of sprinklers required by NFPA 13 and sprinkler wrench. Include separate cabinet with sprinklers and wrench for each type of sprinkler used on Project.

1.8 QUALITY ASSURANCE

A. Installer Qualifications:

1. Installer's responsibilities include designing, fabricating, and installing sprinkler systems and providing professional engineering services needed to assume engineering responsibility. Base calculations on results of fire-hydrant flow test.
 - a. Engineering Responsibility: Preparation of working plans, calculations, and field test reports by a qualified professional engineer.

- B. Welding Qualifications: Qualify procedures and operators according to 2010 ASME Boiler and Pressure Vessel Code.

1.9 FIELD CONDITIONS

- A. Interruption of Existing Sprinkler Service: Do not interrupt sprinkler service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary sprinkler service according to requirements indicated:
 - 1. Notify Owner no fewer than five days in advance of proposed interruption of sprinkler service.
 - 2. Do not proceed with interruption of sprinkler service without Owner's written permission.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Sprinkler system equipment, specialties, accessories, installation, and testing shall comply with NFPA 13.
- C. Standard-Pressure Piping System Component: Listed for 175-psig minimum working pressure.
- D. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design wet-pipe sprinkler systems.
 - 1. Available fire-hydrant flow test records indicate the following conditions:
 - a. Date:
 - b. Time:
 - c. Performed by:
 - d. Location of Residual Fire Hydrant R:
 - e. Location of Flow Fire Hydrant F:
 - f. Static Pressure at Residual Fire Hydrant R:
 - g. Measured Flow at Flow Fire Hydrant F:
 - h. Residual Pressure at Residual Fire Hydrant R:
 - 2. Sprinkler system design shall be approved by authorities having jurisdiction.
 - a. Margin of Safety for Available Water Flow and Pressure: 10 percent, including losses through water-service piping, valves, and backflow preventers.
 - b. Sprinkler Occupancy Hazard Classifications:
 - 1) Office and Public Areas: Light Hazard.
 - 3. Minimum Density for Automatic-Sprinkler Piping Design:
 - a. Light-Hazard Occupancy: 0.10 gpm over 1500-sq. ft. area.
 - 4. Maximum protection area per sprinkler according to UL listing.
 - 5. Maximum Protection Area per Sprinkler:

a. Office Spaces: 225 sq. ft.

E. Seismic Performance: Sprinkler piping shall withstand the effects of earthquake motions determined according to NFPA 13 and ASCE/SEI 7. See Section 210548 "Vibration and Seismic Controls for Fire-Suppression Piping and Equipment."

2.2 STEEL PIPE AND FITTINGS

A. Standard-Weight, Black-Steel Pipe: ASTM A53/A53M, Type E, Grade B. Pipe ends may be factory or field formed to match joining method.

B. Black-Steel Pipe Nipples: ASTM A733, made of ASTM A53/A53M, standard-weight, seamless steel pipe with threaded ends.

C. Steel Couplings: ASTM A865/A865M, threaded.

D. Gray-Iron Threaded Fittings: ASME B16.4, Class 125, standard pattern.

E. Malleable- or Ductile-Iron Unions: UL 860.

F. Cast-Iron Flanges: ASME 16.1, Class 125.

G. Steel Flanges and Flanged Fittings: ASME B16.5, Class 150.

1. Pipe-Flange Gasket Materials: AWWA C110, rubber, flat face, 1/8 inch thick.

a. Class 125 and Class 250, Cast-Iron, Flat-Face Flanges: Full-face gaskets.

b. Class 150 and Class 300, Ductile-Iron or -Steel, Raised-Face Flanges: Ring-type gaskets.

2. Metal, Pipe-Flange Bolts and Nuts: Carbon steel unless otherwise indicated.

H. Steel Welding Fittings: ASTM A234/A234M and ASME B16.9.

1. Welding Filler Metals: Comply with AWS D10.12M/D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.

I. Grooved-Joint, Steel-Pipe Appurtenances:

1. Pressure Rating: 175-psig minimum.

2. Grooved-End Fittings for Steel Piping: ASTM A47/A47M, malleable-iron casting or ASTM A536, ductile-iron casting, with dimensions matching steel pipe.

3. Grooved-End-Pipe Couplings for Steel Piping: AWWA C606 and UL 213 rigid pattern, unless otherwise indicated, for steel-pipe dimensions. Include ferrous housing sections, EPDM-rubber gasket, and bolts and nuts.

J. Steel Pressure-Seal Fittings: UL 213, FM Global-approved, 175-psig pressure rating with steel housing, rubber O-rings, and pipe stop; for use with fitting manufacturers' pressure-seal tools.

1.

2.3 SPRINKLER PIPING SPECIALTIES

- A. Branch Outlet Fittings:
1. Standard: UL 213.
 2. Pressure Rating: 175-psig minimum.
 3. Body Material: Ductile-iron housing with EPDM seals and bolts and nuts.
 4. Type: Mechanical-tee and -cross fittings.
 5. Configurations: Snap-on and strapless, ductile-iron housing with branch outlets.
 6. Size: Of dimension to fit onto sprinkler main and with outlet connections as required to match connected branch piping.
 7. Branch Outlets: Grooved, plain-end pipe, or threaded.
- B. Flow Detection and Test Assemblies:
1. Standard: UL's "Fire Protection Equipment Directory" or FM Global's "Approval Guide."
 2. Pressure Rating: 175-psig minimum.
 3. Body Material: Cast- or ductile-iron housing with orifice, sight glass, and integral test valve.
 4. Size: Same as connected piping.
 5. Inlet and Outlet: Threaded or grooved.
- C. Branch Line Testers:
1. Standard: UL 199.
 2. Pressure Rating: 175 psig.
 3. Body Material: Brass.
 4. Size: Same as connected piping.
 5. Inlet: Threaded.
 6. Drain Outlet: Threaded and capped.
 7. Branch Outlet: Threaded, for sprinkler.
- D. Sprinkler Inspector's Test Fittings:
1. Standard: UL's "Fire Protection Equipment Directory" or FM Global's "Approval Guide."
 2. Pressure Rating: 175-psig minimum.
 3. Body Material: Cast- or ductile-iron housing with sight glass.
 4. Size: Same as connected piping.
 5. Inlet and Outlet: Threaded.
- E. Adjustable Drop Nipples:
1. Standard: UL 1474.
 2. Pressure Rating: 250-psig minimum.
 3. Body Material: Steel pipe with EPDM-rubber O-ring seals.
 4. Size: Same as connected piping.
 5. Length: Adjustable.
 6. Inlet and Outlet: Threaded.
- F. Flexible Sprinkler Hose Fittings:
1. Standard: UL 1474.
 2. Type: Flexible hose for connection to sprinkler, and with bracket for connection to ceiling grid.
 3. Pressure Rating: 175-psig minimum.
 4. Size: Same as connected piping, for sprinkler.

2.4 SPRINKLERS

- A. Listed in UL's "Fire Protection Equipment Directory" or FM Global's "Approval Guide."
- B. Pressure Rating for Automatic Sprinklers: 175-psig minimum.
- C. Sprinkler Finishes: Chrome plated.
- D. Sprinkler Escutcheons: Materials, types, and finishes for the following sprinkler mounting applications. Escutcheons for concealed, flush, and recessed-type sprinklers are specified with sprinklers.
 - 1. Ceiling Mounting: Chrome-plated steel, one piece, flat
 - 2. Sidewall Mounting: Chrome-plated steel, one piece, flat.
- E. Sprinkler Guards:
 - 1. Standard: UL 199.
 - 2. Type: Wire cage with fastening device for attaching to sprinkler.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Perform fire-hydrant flow test according to NFPA 13 and NFPA 291. Use results for system design calculations required in "Quality Assurance" Article.
- B. Report test results promptly and in writing.
- C. Install shutoff valve, check valve, pressure gauge, and drain at connection to water supply.

3.2 PIPING INSTALLATION

- A. Locations and Arrangements: Drawing plans, schematics, and diagrams indicate general location and arrangement of piping. Install piping as indicated on approved working plans.
 - 1. Deviations from approved working plans for piping require written approval from authorities having jurisdiction. File written approval with Architect before deviating from approved working plans.
 - 2. Coordinate layout and installation of sprinklers with other construction that penetrates ceilings, including light fixtures, HVAC equipment, and partition assemblies.
- B. Piping Standard: Comply with NFPA 13 requirements for installation of sprinkler piping.
- C. Install seismic restraints on piping. Comply with NFPA 13 requirements for seismic-restraint device materials and installation.
- D. Use listed fittings to make changes in direction, branch takeoffs from mains, and reductions in pipe sizes.

- E. Install unions adjacent to each valve in pipes NPS 2 and smaller.
- F. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.
- G. Install "Inspector's Test Connections" in sprinkler system piping, complete with shutoff valve, and sized and located according to NFPA 13.
- H. Install sprinkler piping with drains for complete system drainage.
- I. Install sprinkler control valves, test assemblies, and drain risers adjacent to standpipes when sprinkler piping is connected to standpipes.
- J. Install automatic (ball drip) drain valve at each check valve for fire-department connection, to drain piping between fire-department connection and check valve. Install drain piping to and spill over floor drain or to outside building.
- K. Install alarm devices in piping systems.
- L. Install hangers and supports for sprinkler system piping according to NFPA 13. Comply with requirements for hanger materials in NFPA 13.
- M. Install pressure gauges on riser or feed main, at each sprinkler test connection, and at top of each standpipe. Include pressure gauges with connection not less than NPS 1/4 and with soft-metal seated globe valve, arranged for draining pipe between gauge and valve. Install gauges to permit removal, and install where they are not subject to freezing.
- N. Fill sprinkler system piping with water.
- O. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 210517 "Sleeves and Sleeve Seals for Fire-Suppression Piping."
- P. Install escutcheons for piping penetrations of walls, ceilings, and floors.

3.3 JOINT CONSTRUCTION

- A. Install couplings, flanges, flanged fittings, unions, nipples, and transition and special fittings that have finish and pressure ratings same as or higher than system's pressure rating for aboveground applications unless otherwise indicated.
- B. Install unions adjacent to each valve in pipes NPS 2 and smaller.
- C. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.
- D. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- E. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.

- F. Flanged Joints: Select appropriate gasket material in size, type, and thickness suitable for water service. Join flanges with gasket and bolts according to ASME B31.9.
- G. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
- H. Steel-Piping, Cut-Grooved Joints: Cut square-edge groove in end of pipe according to AWWA C606. Assemble coupling with housing, gasket, lubricant, and bolts. Join steel pipe and grooved-end fittings according to AWWA C606 for steel-pipe joints.
- I. Steel-Piping, Roll-Grooved Joints: Roll rounded-edge groove in end of pipe according to AWWA C606. Assemble coupling with housing, gasket, lubricant, and bolts. Join steel pipe and grooved-end fittings according to AWWA C606 for steel-pipe grooved joints.

3.4 SPRINKLER INSTALLATION

- A. Install sprinklers in suspended ceilings in center of acoustical ceiling panels.
- B. Install dry-type sprinklers with water supply from heated space. Do not install pendent or sidewall, wet-type sprinklers in areas subject to freezing.
- C. Install sprinklers into flexible, sprinkler hose fittings, and install hose into bracket on ceiling grid.

3.5 IDENTIFICATION

- A. Install labeling and pipe markers on equipment and piping according to requirements in NFPA 13.
- B. Identify system components, wiring, cabling, and terminals.

3.6 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections.
 - 1. Leak Test: After installation, charge systems and test for leaks. Repair leaks and retest until no leaks exist.
 - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
 - 3. Flush, test, and inspect sprinkler systems according to NFPA 13, "Systems Acceptance" Chapter.
 - 4. Energize circuits to electrical equipment and devices.
 - 5. Coordinate with fire-alarm tests. Operate as required.

6. Coordinate with fire-pump tests. Operate as required.
7. Verify that equipment hose threads are same as local fire department equipment.

- B. Sprinkler piping system will be considered defective if it does not pass tests and inspections.
- C. Prepare test and inspection reports.

3.7 CLEANING

- A. Clean dirt and debris from sprinklers.
- B. Only sprinklers with their original factory finish are acceptable. Remove and replace any sprinklers that are painted or have any other finish than their original factory finish.

3.8 PIPING SCHEDULE

- A. Sprinkler specialty fittings may be used, downstream of control valves, instead of specified fittings.
- B. Standard-pressure, wet-pipe sprinkler system, NPS 2 and smaller, shall be the following:
 1. Standard-weight, black-steel pipe with threaded ends; uncoated, gray-iron threaded fittings; and threaded joints.

3.9 SPRINKLER SCHEDULE

- A. Use sprinkler types in subparagraphs below for the following applications:
 1. Rooms without Ceilings: Upright sprinklers.
 2. Rooms with Suspended Ceilings: Pendent sprinklers.
 3. Wall Mounting: Sidewall sprinklers.
- B. Provide sprinkler types in subparagraphs below with finishes indicated.
 1. Upright, Pendent, and Sidewall Sprinklers: Chrome plated in finished spaces exposed to view; rough bronze in unfinished spaces not exposed to view; wax coated where exposed to acids, chemicals, or other corrosive fumes.

END OF SECTION 211313

SECTION 220523 - GENERAL-DUTY VALVES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Brass ball valves.
2. Bronze ball valves.
3. Iron, single-flange butterfly valves.
4. Bronze swing check valves.
5. Iron swing check valves.
6. Iron swing check valves with closure control.
7. Bronze gate valves.
8. Iron gate valves.
9. Bronze globe valves.
10. Iron globe valves.
11. Chainwheels.

1.2 SUBMITTALS

- ##### A. Product Data: For each type of valve indicated.

1.3 QUALITY ASSURANCE

- ##### A. ASME Compliance: ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
- ##### B. NSF Compliance: NSF 61 for valve materials for potable-water service.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR VALVES

- ##### A. Refer to valve schedule articles for applications of valves.
- ##### B. Valve Pressure and Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.
- ##### C. Valve Sizes: Same as upstream piping unless otherwise indicated.
- ##### D. Valve Actuator Types:
1. Gear Actuator: For quarter-turn valves NPS 8 (DN 200) and larger.

2. Handwheel: For valves other than quarter-turn types.
3. Handlever: For quarter-turn valves NPS 6 (DN 150) and smaller except plug valves.
4. Chainwheel: Device for attachment to valve handwheel, stem, or other actuator; of size and with chain for mounting height, as indicated in the "Valve Installation" Article.

E. Valves in Insulated Piping: With 2-inch stem extensions and the following features:

1. Gate Valves: With rising stem.
2. Ball Valves: With extended operating handle of non-thermal-conductive material, and protective sleeve that allows operation of valve without breaking the vapor seal or disturbing insulation.
3. Butterfly Valves: With extended neck.

F. Valve-End Connections:

1. Flanged: With flanges according to ASME B16.1 for iron valves.
2. Solder Joint: With sockets according to ASME B16.18.
3. Threaded: With threads according to ASME B1.20.1.

2.2 BRASS BALL VALVES

A. One-Piece, Reduced-Port, Brass Ball Valves with Brass Trim:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Kitz Corporation.
2. Description:
 - a. Standard: MSS SP-110.
 - b. CWP Rating: 400 psig.
 - c. Body Design: One piece.
 - d. Body Material: Forged brass.
 - e. Ends: Threaded.
 - f. Seats: PTFE or TFE.
 - g. Stem: Brass.
 - h. Ball: Chrome-plated brass.
 - i. Port: Reduced.

B. Two-Piece, Full-Port, Brass Ball Valves with Brass Trim:

1. Manufacturers: Subject to compliance with requirements, [provide products by one of the following] [available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following]:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Crane Co.; Crane Valve Group; Jenkins Valves.
 - c. DynaQuip Controls.

- d. Flow-Tek, Inc.; a subsidiary of Bray International, Inc.
- e. Hammond Valve.
- f. Jamesbury; a subsidiary of Metso Automation.
- g. Jomar International, LTD.
- h. Kitz Corporation.
- i. Legend Valve.
- j. Marwin Valve; a division of Richards Industries.
- k. Milwaukee Valve Company.
- l. NIBCO INC.
- m. Red-White Valve Corporation.
- n. RuB Inc.

2. Description:

- a. Standard: MSS SP-110.
- b. SWP Rating: 150 psig.
- c. CWP Rating: 600 psig.
- d. Body Design: Two piece.
- e. Body Material: Forged brass.
- f. Ends: Threaded.
- g. Seats: PTFE or TFE.
- h. Stem: Brass.
- i. Ball: Chrome-plated brass.
- j. Port: Full.

C. Two-Piece, Regular-Port, Brass Ball Valves with Brass Trim:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. Hammond Valve.
- b. Jamesbury; a subsidiary of Metso Automation.
- c. Legend Valve.
- d. Marwin Valve; a division of Richards Industries.
- e. Milwaukee Valve Company.

2. Description:

- a. Standard: MSS SP-110.
- b. SWP Rating: 150 psig.
- c. CWP Rating: 600 psig.
- d. Body Design: Two piece.
- e. Body Material: Forged brass.
- f. Ends: Threaded.
- g. Seats: PTFE or TFE.
- h. Stem: Brass.
- i. Ball: Chrome-plated brass.
- j. Port: Regular.

2.3 BRONZE BALL VALVES

A. One-Piece, Reduced-Port, Bronze Ball Valves with Bronze Trim:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. American Valve, Inc.
 - b. Conbraco Industries, Inc.; Apollo Valves.
 - c. NIBCO INC.
2. Description:
 - a. Standard: MSS SP-110.
 - b. CWP Rating: 400 psig.
 - c. Body Design: One piece.
 - d. Body Material: Bronze.
 - e. Ends: Threaded.
 - f. Seats: PTFE or TFE.
 - g. Stem: Bronze.
 - h. Ball: Chrome-plated brass.
 - i. Port: Reduced.

B. Two-Piece, Full-Port, Bronze Ball Valves with Bronze Trim:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. American Valve, Inc.
 - b. Conbraco Industries, Inc.; Apollo Valves.
 - c. Crane Co.; Crane Valve Group; Crane Valves.
 - d. Hammond Valve.
 - e. Lance Valves; a division of Advanced Thermal Systems, Inc.
 - f. Legend Valve.
 - g. Milwaukee Valve Company.
 - h. NIBCO INC.
 - i. Red-White Valve Corporation.
 - j. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
2. Description:
 - a. Standard: MSS SP-110.
 - b. SWP Rating: 150 psig.
 - c. CWP Rating: 600 psig.
 - d. Body Design: Two piece.
 - e. Body Material: Bronze.
 - f. Ends: Threaded.
 - g. Seats: PTFE or TFE.
 - h. Stem: Bronze.

- i. Ball: Chrome-plated brass.
- j. Port: Full.

C. Two-Piece, Regular-Port, Bronze Ball Valves with Bronze Trim:

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. American Valve, Inc.
- b. Conbraco Industries, Inc.; Apollo Valves.
- c. Crane Co.; Crane Valve Group; Jenkins Valves.
- d. Crane Co.; Crane Valve Group; Stockham Division.
- e. DynaQuip Controls.
- f. Hammond Valve.
- g. Lance Valves; a division of Advanced Thermal Systems, Inc.
- h. Milwaukee Valve Company.
- i. NIBCO INC.

- 2. Description:

- a. Standard: MSS SP-110.
- b. SWP Rating: 150 psig.
- c. CWP Rating: 600 psig.
- d. Body Design: Two piece.
- e. Body Material: Bronze.
- f. Ends: Threaded.
- g. Seats: PTFE or TFE.
- h. Stem: Bronze.
- i. Ball: Chrome-plated brass.
- j. Port: Regular.

2.4 IRON, SINGLE-FLANGE BUTTERFLY VALVES

A. 200 CWP, Iron, Single-Flange Butterfly Valves with EPDM Seat and Aluminum-Bronze Disc:

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. ABZ Valve and Controls; a division of ABZ Manufacturing, Inc.
- b. Conbraco Industries, Inc.; Apollo Valves.
- c. Cooper Cameron Valves; a division of Cooper Cameron Corporation.
- d. Crane Co.; Crane Valve Group; Jenkins Valves.
- e. Crane Co.; Crane Valve Group; Stockham Division.
- f. DeZurik Water Controls.
- g. Flo Fab Inc.
- h. Hammond Valve.
- i. Kitz Corporation.
- j. Legend Valve.

- k. Milwaukee Valve Company.
- l. NIBCO INC.
- m. Norriseal; a Dover Corporation company.
- n. Red-White Valve Corporation.
- o. Spence Strainers International; a division of CIRCOR International, Inc.
- p. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

2. Description:

- a. Standard: MSS SP-67, Type I.
- b. CWP Rating: 200 psig.
- c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
- d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
- e. Seat: EPDM.
- f. Stem: One- or two-piece stainless steel.
- g. Disc: Aluminum bronze.

B. 200 CWP, Iron, Single-Flange Butterfly Valves with NBR Seat and Aluminum-Bronze Disc:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. ABZ Valve and Controls; a division of ABZ Manufacturing, Inc.
- b. Conbraco Industries, Inc.; Apollo Valves.
- c. Cooper Cameron Valves; a division of Cooper Cameron Corporation.
- d. Crane Co.; Crane Valve Group; Jenkins Valves.
- e. Crane Co.; Crane Valve Group; Stockham Division.
- f. DeZurik Water Controls.
- g. Flo Fab Inc.
- h. Hammond Valve.
- i. Kitz Corporation.
- j. Legend Valve.
- k. Milwaukee Valve Company.
- l. NIBCO INC.
- m. Norriseal; a Dover Corporation company.
- n. Red-White Valve Corporation.
- o. Spence Strainers International; a division of CIRCOR International, Inc.
- p. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

2. Description:

- a. Standard: MSS SP-67, Type I.
- b. CWP Rating: 200 psig.
- c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
- d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
- e. Seat: NBR.
- f. Stem: One- or two-piece stainless steel.
- g. Disc: Aluminum bronze.

C. 200 CWP, Iron, Single-Flange Butterfly Valves with EPDM Seat and Ductile-Iron Disc:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. ABZ Valve and Controls; a division of ABZ Manufacturing, Inc.
 - b. American Valve, Inc.
 - c. Conbraco Industries, Inc.; Apollo Valves.
 - d. Cooper Cameron Valves; a division of Cooper Cameron Corporation.
 - e. Crane Co.; Crane Valve Group; Center Line.
 - f. Crane Co.; Crane Valve Group; Stockham Division.
 - g. DeZurik Water Controls.
 - h. Flo Fab Inc.
 - i. Hammond Valve.
 - j. Kitz Corporation.
 - k. Legend Valve.
 - l. Milwaukee Valve Company.
 - m. Mueller Steam Specialty; a division of SPX Corporation.
 - n. NIBCO INC.
 - o. Norriseal; a Dover Corporation company.
 - p. Spence Strainers International; a division of CIRCOR International, Inc.
 - q. Sure Flow Equipment Inc.
 - r. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
2. Description:
 - a. Standard: MSS SP-67, Type I.
 - b. CWP Rating: 200 psig.
 - c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
 - d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
 - e. Seat: EPDM.
 - f. Stem: One- or two-piece stainless steel.
 - g. Disc: Nickel-plated or -coated ductile iron.

D. 200 CWP, Iron, Single-Flange Butterfly Valves with NBR Seat and Ductile-Iron Disc:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. ABZ Valve and Controls; a division of ABZ Manufacturing, Inc.
 - b. American Valve, Inc.
 - c. Conbraco Industries, Inc.; Apollo Valves.
 - d. Cooper Cameron Valves; a division of Cooper Cameron Corporation.
 - e. Crane Co.; Crane Valve Group; Center Line.
 - f. Crane Co.; Crane Valve Group; Stockham Division.
 - g. DeZurik Water Controls.
 - h. Flo Fab Inc.
 - i. Hammond Valve.

- j. Kitz Corporation.
- k. Legend Valve.
- l. Milwaukee Valve Company.
- m. Mueller Steam Specialty; a division of SPX Corporation.
- n. NIBCO INC.
- o. Norriseal; a Dover Corporation company.
- p. Spence Strainers International; a division of CIRCOR International, Inc.
- q. Sure Flow Equipment Inc.
- r. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

2. Description:

- a. Standard: MSS SP-67, Type I.
- b. CWP Rating: 200 psig.
- c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
- d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
- e. Seat: NBR.
- f. Stem: One- or two-piece stainless steel.
- g. Disc: Nickel-plated or -coated ductile iron.

2.5 BRONZE SWING CHECK VALVES

A. Class 125, Bronze Swing Check Valves with Bronze Disc:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. American Valve, Inc.
- b. Crane Co.; Crane Valve Group; Crane Valves.
- c. Crane Co.; Crane Valve Group; Jenkins Valves.
- d. Crane Co.; Crane Valve Group; Stockham Division.
- e. Hammond Valve.
- f. Kitz Corporation.
- g. Milwaukee Valve Company.
- h. NIBCO INC.
- i. Powell Valves.
- j. Red-White Valve Corporation.
- k. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
- l. Zy-Tech Global Industries, Inc.

2. Description:

- a. Standard: MSS SP-80, Type 3.
- b. CWP Rating: 200 psig.
- c. Body Design: Horizontal flow.
- d. Body Material: ASTM B 62, bronze.
- e. Ends: Threaded.
- f. Disc: Bronze.

B. Class 125, Bronze Swing Check Valves with Nonmetallic Disc:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Crane Co.; Crane Valve Group; Jenkins Valves.
 - c. Crane Co.; Crane Valve Group; Stockham Division.
 - d. Hammond Valve.
 - e. Kitz Corporation.
 - f. Milwaukee Valve Company.
 - g. NIBCO INC.
 - h. Red-White Valve Corporation.
 - i. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

2. Description:
 - a. Standard: MSS SP-80, Type 4.
 - b. CWP Rating: 200 psig.
 - c. Body Design: Horizontal flow.
 - d. Body Material: ASTM B 62, bronze.
 - e. Ends: Threaded.
 - f. Disc: PTFE or TFE.

2.6 IRON SWING CHECK VALVES

A. Class 125, Iron Swing Check Valves with Metal Seats:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Crane Co.; Crane Valve Group; Jenkins Valves.
 - c. Crane Co.; Crane Valve Group; Stockham Division.
 - d. Hammond Valve.
 - e. Kitz Corporation.
 - f. Legend Valve.
 - g. Milwaukee Valve Company.
 - h. NIBCO INC.
 - i. Powell Valves.
 - j. Red-White Valve Corporation.
 - k. Sure Flow Equipment Inc.
 - l. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
 - m. Zy-Tech Global Industries, Inc.

2. Description:
 - a. Standard: MSS SP-71, Type I.
 - b. CWP Rating: 200 psig.
 - c. Body Design: Clear or full waterway.
 - d. Body Material: ASTM A 126, gray iron with bolted bonnet.
 - e. Ends: Flanged.
 - f. Trim: Bronze.
 - g. Gasket: Asbestos free.

B. Class 125, Iron Swing Check Valves with Nonmetallic-to-Metal Seats:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Crane Co.; Crane Valve Group; Stockham Division.
2. Description:
 - a. Standard: MSS SP-71, Type I.
 - b. CWP Rating: 200 psig.
 - c. Body Design: Clear or full waterway.
 - d. Body Material: ASTM A 126, gray iron with bolted bonnet.
 - e. Ends: Flanged.
 - f. Trim: Composition.
 - g. Seat Ring: Bronze.
 - h. Disc Holder: Bronze.
 - i. Disc: PTFE or TFE.
 - j. Gasket: Asbestos free.

2.7 IRON SWING CHECK VALVES WITH CLOSURE CONTROL

A. Class 125, Iron Swing Check Valves with Lever- and Spring-Closure Control:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. NIBCO INC.
2. Description:
 - a. Standard: MSS SP-71, Type I.
 - b. CWP Rating: 200 psig.
 - c. Body Design: Clear or full waterway.
 - d. Body Material: ASTM A 126, gray iron with bolted bonnet.

- e. Ends: Flanged.
- f. Trim: Bronze.
- g. Gasket: Asbestos free.
- h. Closure Control: Factory-installed, exterior lever and spring.

B. Class 125, Iron Swing Check Valves with Lever- and Weight-Closure Control:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Crane Co.; Crane Valve Group; Jenkins Valves.
 - c. Crane Co.; Crane Valve Group; Stockham Division.
 - d. Hammond Valve.
 - e. Milwaukee Valve Company.
 - f. NIBCO INC.
 - g. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
2. Description:
 - a. Standard: MSS SP-71, Type I.
 - b. CWP Rating: 200 psig.
 - c. Body Design: Clear or full waterway.
 - d. Body Material: ASTM A 126, gray iron with bolted bonnet.
 - e. Ends: Flanged.
 - f. Trim: Bronze.
 - g. Gasket: Asbestos free.
 - h. Closure Control: Factory-installed, exterior lever and weight.

2.8 BRONZE GATE VALVES

A. Class 125, NRS Bronze Gate Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. American Valve, Inc.
 - b. Crane Co.; Crane Valve Group; Crane Valves.
 - c. Crane Co.; Crane Valve Group; Jenkins Valves.
 - d. Crane Co.; Crane Valve Group; Stockham Division.
 - e. Hammond Valve.
 - f. Kitz Corporation.
 - g. Milwaukee Valve Company.
 - h. NIBCO INC.
 - i. Powell Valves.
 - j. Red-White Valve Corporation.
 - k. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
 - l. Zy-Tech Global Industries, Inc.

2. Description:

- a. Standard: MSS SP-80, Type 1.
- b. CWP Rating: 200 psig.
- c. Body Material: ASTM B 62, bronze with integral seat and screw-in bonnet.
- d. Ends: Threaded or solder joint.
- e. Stem: Bronze.
- f. Disc: Solid wedge; bronze.
- g. Packing: Asbestos free.
- h. Handwheel: Malleable iron.

B. Class 125, RS Bronze Gate Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. American Valve, Inc.
- b. Crane Co.; Crane Valve Group; Crane Valves.
- c. Crane Co.; Crane Valve Group; Jenkins Valves.
- d. Crane Co.; Crane Valve Group; Stockham Division.
- e. Hammond Valve.
- f. Kitz Corporation.
- g. Milwaukee Valve Company.
- h. NIBCO INC.
- i. Powell Valves.
- j. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
- k. Zy-Tech Global Industries, Inc.

2. Description:

- a. Standard: MSS SP-80, Type 2.
- b. CWP Rating: 200 psig.
- c. Body Material: ASTM B 62, bronze with integral seat and screw-in bonnet.
- d. Ends: Threaded or solder joint.
- e. Stem: Bronze.
- f. Disc: Solid wedge; bronze.
- g. Packing: Asbestos free.
- h. Handwheel: Malleable iron.

2.9 IRON GATE VALVES

A. Class 125, NRS, Iron Gate Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. Crane Co.; Crane Valve Group; Crane Valves.
- b. Crane Co.; Crane Valve Group; Jenkins Valves.
- c. Crane Co.; Crane Valve Group; Stockham Division.

- d. Flo Fab Inc.
- e. Hammond Valve.
- f. Kitz Corporation.
- g. Legend Valve.
- h. Milwaukee Valve Company.
- i. NIBCO INC.
- j. Powell Valves.
- k. Red-White Valve Corporation.
- l. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
- m. Zy-Tech Global Industries, Inc.

2. Description:

- a. Standard: MSS SP-70, Type I.
- b. CWP Rating: 200 psig.
- c. Body Material: ASTM A 126, gray iron with bolted bonnet.
- d. Ends: Flanged.
- e. Trim: Bronze.
- f. Disc: Solid wedge.
- g. Packing and Gasket: Asbestos free.

B. Class 125, OS&Y, Iron Gate Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. Crane Co.; Crane Valve Group; Crane Valves.
- b. Crane Co.; Crane Valve Group; Jenkins Valves.
- c. Crane Co.; Crane Valve Group; Stockham Division.
- d. Flo Fab Inc.
- e. Hammond Valve.
- f. Kitz Corporation.
- g. Legend Valve.
- h. Milwaukee Valve Company.
- i. NIBCO INC.
- j. Powell Valves.
- k. Red-White Valve Corporation.
- l. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
- m. Zy-Tech Global Industries, Inc.

2. Description:

- a. Standard: MSS SP-70, Type I.
- b. CWP Rating: 200 psig.
- c. Body Material: ASTM A 126, gray iron with bolted bonnet.
- d. Ends: Flanged.
- e. Trim: Bronze.
- f. Disc: Solid wedge.
- g. Packing and Gasket: Asbestos free.

2.10 BRONZE GLOBE VALVES

A. Class 125, Bronze Globe Valves with Bronze Disc:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Crane Co.; Crane Valve Group; Stockham Division.
 - c. Hammond Valve.
 - d. Kitz Corporation.
 - e. Milwaukee Valve Company.
 - f. NIBCO INC.
 - g. Powell Valves.
 - h. Red-White Valve Corporation.
 - i. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
 - j. Zy-Tech Global Industries, Inc.
2. Description:
 - a. Standard: MSS SP-80, Type 1.
 - b. CWP Rating: 200 psig.
 - c. Body Material: ASTM B 62, bronze with integral seat and screw-in bonnet.
 - d. Ends: Threaded or solder joint.
 - e. Stem and Disc: Bronze.
 - f. Packing: Asbestos free.
 - g. Handwheel: Malleable iron.

B. Class 125, Bronze Globe Valves with Nonmetallic Disc:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Crane Co.; Crane Valve Group; Stockham Division.
 - c. NIBCO INC.
 - d. Red-White Valve Corporation.
2. Description:
 - a. Standard: MSS SP-80, Type 2.
 - b. CWP Rating: 200 psig.
 - c. Body Material: ASTM B 62, bronze with integral seat and screw-in bonnet.
 - d. Ends: Threaded or solder joint.
 - e. Stem: Bronze.
 - f. Disc: PTFE or TFE.
 - g. Packing: Asbestos free.
 - h. Handwheel: Malleable iron.

2.11 IRON GLOBE VALVES

A. Class 125, Iron Globe Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Crane Co.; Crane Valve Group; Crane Valves.
 - b. Crane Co.; Crane Valve Group; Jenkins Valves.
 - c. Crane Co.; Crane Valve Group; Stockham Division.
 - d. Hammond Valve.
 - e. Kitz Corporation.
 - f. Milwaukee Valve Company.
 - g. NIBCO INC.
 - h. Powell Valves.
 - i. Red-White Valve Corporation.
 - j. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
 - k. Zy-Tech Global Industries, Inc.
2. Description:
 - a. Standard: MSS SP-85, Type I.
 - b. CWP Rating: 200 psig.
 - c. Body Material: ASTM A 126, gray iron with bolted bonnet.
 - d. Ends: Flanged.
 - e. Trim: Bronze.
 - f. Packing and Gasket: Asbestos free.

2.12 CHAINWHEELS

A. Description: Valve actuation assembly with sprocket rim, brackets, and chain.

1. Brackets: Type, number, size, and fasteners required to mount actuator on valve.
2. Attachment: For connection to butterfly valve stems.
3. Sprocket Rim with Chain Guides: Ductile iron, of type and size required for valve. Include zinc coating.
4. Chain: Hot-dip, galvanized steel, of size required to fit sprocket rim.

PART 3 - EXECUTION

3.1 VALVE INSTALLATION

- A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- B. Locate valves for easy access and provide separate support where necessary.
- C. Install valves in horizontal piping with stem at or above center of pipe.

- D. Install valves in position to allow full stem movement.
- E. Install chainwheels on operators for butterfly gate and globe valves NPS 4 and larger and more than 96 inches above floor. Extend chains to 60 inches above finished floor.
 - 1. Install swing check valves for proper direction of flow and in horizontal position with hinge pin level.

3.2 ADJUSTING

- A. Adjust or replace valve packing after piping systems have been tested and put into service but before final adjusting and balancing. Replace valves if persistent leaking occurs.

3.3 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

- A. If valve applications are not indicated, use the following:
 - 1. Shutoff Service: Ball or butterfly valves.
 - 2. Throttling Service: Globe or ball valves.
 - 3. Pump-Discharge Check Valves:
 - a. NPS 2 (DN 50) and Smaller: Bronze swing check valves with bronze disc.
 - b. NPS 2-1/2 (DN 65) and Larger for Domestic Water: Iron swing check valves with lever and weight or with spring.
 - c. NPS 2-1/2 (DN 65) and Larger for Sanitary Waste and Storm Drainage: Iron swing check valves with lever and weight or spring.
- B. If valves with specified SWP classes or CWP ratings are not available, the same types of valves with higher SWP class or CWP ratings may be substituted.
- C. Select valves, except wafer types, with the following end connections:
 - 1. For Copper Tubing, NPS 2 (DN 50) and Smaller: Threaded ends except where solder-joint valve-end option is indicated in valve schedules below.
 - 2. For Copper Tubing, NPS 2-1/2 to NPS 4 (DN 65 to DN 100): Flanged ends except where threaded valve-end option is indicated in valve schedules below.
 - 3. For Copper Tubing, NPS 5 (DN 125) and Larger: Flanged ends.
 - 4. For Steel Piping, NPS 2 (DN 50) and Smaller: Threaded ends.
 - 5. For Steel Piping, NPS 2-1/2 to NPS 4 (DN 65 to DN 100): Flanged ends except where threaded valve-end option is indicated in valve schedules below.
 - 6. For Steel Piping, NPS 5 (DN 125) and Larger: Flanged ends.

3.4 LOW-PRESSURE, COMPRESSED-AIR VALVE SCHEDULE (150 PSIG OR LESS)

- A. Pipe NPS 2 (DN 50) and Smaller:
 - 1. Bronze and Brass Valves: May be provided with solder-joint ends instead of threaded ends.
 - 2. Ball Valves: Two piece, full port, brass with bronze trim.

3. Bronze Swing Check Valves: Class 125, bronze disc.
4. Bronze Gate Valves: Class 125, NRS.

B. Pipe NPS 2-1/2 (DN 65) and Larger:

1. Iron Valves, NPS 2-1/2 to NPS 4 (DN 65 to NPS 100): May be provided with threaded ends instead of flanged ends.
2. Iron, Single-Flange Butterfly Valves: 200 CWP, NBR seat, ductile-iron disc.
3. Iron Swing Check Valves: Class 125, metal seats.
4. Iron Gate Valves: Class 125, OS&Y.

3.5 HIGH-PRESSURE, COMPRESSED-AIR VALVE SCHEDULE (150 TO 200 PSIG)

A. Pipe NPS 2 (DN 50) and Smaller:

1. Bronze and Brass Valves: May be provided with solder-joint ends instead of threaded ends.
2. Ball Valves: Two piece, full port, brass with bronze trim.
3. Bronze Swing Check Valves: Class 125, bronze disc.
4. Bronze Gate Valves: Class 125, NRS.

B. Pipe NPS 2-1/2 (DN 65) and Larger:

1. Iron Valves, NPS 2-1/2 to NPS 4 (DN 65 to NPS 100): May be provided with threaded ends instead of flanged ends.
2. Iron, Single-Flange Butterfly Valves: 200 CWP, NBR seat, ductile-iron disc.
3. Iron Swing Check Valves: Class 125, metal seats.
4. Iron Gate Valves: Class 125, OS&Y.

3.6 DOMESTIC, HOT- AND COLD-WATER VALVE SCHEDULE

A. Pipe NPS 2 (DN 50) and Smaller:

1. Bronze and Brass Valves: May be provided with solder-joint ends instead of threaded ends.
2. Bronze Angle Valves: Class 125, bronze disc.
3. Ball Valves: Two piece, full port, brass with bronze trim.
4. Bronze Swing Check Valves: Class 125, bronze disc.
5. Bronze Gate Valves: Class 125, NRS.
6. Bronze Globe Valves: Class 125, bronze disc.

B. Pipe NPS 2-1/2 (DN 65) and Larger:

1. Iron Valves, NPS 2-1/2 to NPS 4 (DN 65 to NPS 100): May be provided with threaded ends instead of flanged ends.
2. Iron, Single-Flange Butterfly Valves: 200 CWP, NBR seat, ductile-iron disc.
3. Iron Swing Check Valves: Class 125, metal seats.
4. Iron Swing Check Valves with Closure Control: Class 125, lever and spring.
5. Iron Gate Valves: Class 125, OS&Y.
6. Iron Globe Valves: Class 125.

END OF SECTION 220523

SECTION 220529 - HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Metal pipe hangers and supports.
 - 2. Thermal hanger-shield inserts.
 - 3. Fastener systems.

1.3 INFORMATIONAL SUBMITTALS

- A. Welding certificates.

1.4 QUALITY ASSURANCE

- A. Structural-Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M.
- B. Pipe Welding Qualifications: Qualify procedures and operators according to 2015 ASME Boiler and Pressure Vessel Code, Section IX.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Hangers and supports for plumbing piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
 - 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
 - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
 - 3. Design seismic-restraint hangers and supports for piping and equipment and obtain approval from authorities having jurisdiction.

2.2 METAL PIPE HANGERS AND SUPPORTS

A. Carbon-Steel Pipe Hangers and Supports:

1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
2. Galvanized Metallic Coatings: Pregalvanized, hot-dip galvanized, or electro-galvanized.
3. Nonmetallic Coatings: Plastic coated or epoxy powder coated.
4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
5. Hanger Rods: Continuous-thread rod, nuts, and washer made of stainless steel.

B. Stainless-Steel Pipe Hangers and Supports:

1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
2. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
3. Hanger Rods: Continuous-thread rod, nuts, and washer made of stainless steel.

C. Copper Pipe and Tube Hangers:

1. Description: MSS SP-58, Types 1 through 58, copper-coated-steel, factory-fabricated components.
2. Hanger Rods: Continuous-thread rod, nuts, and washer made of stainless steel.

2.3 THERMAL HANGER-SHIELD INSERTS

- A. Insulation-Insert Material for Cold Piping: ASTM C552, Type II cellular glass with 100-psig minimum compressive strength and vapor barrier.
- B. Insulation-Insert Material for Hot Piping: ASTM C552, Type II cellular glass with 100-psig minimum compressive strength.
- C. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- D. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- E. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.4 FASTENER SYSTEMS

- A. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete, with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
- B. Mechanical-Expansion Anchors: Insert-wedge-type anchors, for use in hardened portland cement concrete, with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
 1. Indoor Applications: Zinc-coated steel.

2. Outdoor Applications: Stainless steel.

2.5 MATERIALS

- A. Aluminum: ASTM B221.
- B. Carbon Steel: ASTM A1011/A1011M.
- C. Structural Steel: ASTM A36/A36M carbon-steel plates, shapes, and bars; black and galvanized.
- D. Stainless Steel: ASTM A240/A240M.
- E. Grout: ASTM C1107/C1107M, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
 1. Properties: Nonstaining, noncorrosive, and nongaseous.
 2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping materials and installation, for penetrations through fire-rated walls, ceilings, and assemblies.
- B. Strength of Support Assemblies: Where not indicated, select sizes of components, so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.

3.2 HANGER AND SUPPORT INSTALLATION

- A. Metal Pipe-Hanger Installation: Comply with MSS SP-58. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.
- B. Thermal Hanger-Shield Installation: Install in pipe hanger or shield for insulated piping.
- C. Fastener System Installation:
 1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete, after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual.
 2. Install mechanical-expansion anchors in concrete, after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.
- D. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.

- E. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- F. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- G. Install lateral bracing with pipe hangers and supports to prevent swaying.
- H. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms, and install reinforcing bars through openings at top of inserts.
- I. Load Distribution: Install hangers and supports, so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- J. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.
- K. Insulated Piping:
 - 1. Attach clamps and spacers to piping.
 - a. Piping Operating Above Ambient Air Temperature: Clamp may project through insulation.
 - b. Piping Operating Below Ambient Air Temperature: Use thermal hanger-shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
 - 2. Install MSS SP-58, Type 39 protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
 - a. Option: Thermal hanger-shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
 - 3. Install MSS SP-58, Type 40 protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
 - a. Option: Thermal hanger-shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
 - 4. Shield Dimensions for Pipe: Not less than the following:
 - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
 - b. NPS 4: 12 inches long and 0.06 inch thick.
 - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
 - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
 - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.

5. Pipes NPS 8 and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
6. Thermal Hanger Shields: Install with insulation of same thickness as piping insulation.

3.3 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.4 PAINTING

- A. Touchup: Clean field welds and abraded, shop-painted areas. Paint exposed areas immediately after erecting hangers and supports. Use same materials as those used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas, and apply galvanizing-repair paint to comply with ASTM A780/A780M.

3.5 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-58 for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finishes.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use carbon-steel pipe hangers and supports and attachments for general service applications.
- F. Use stainless-steel pipe hangers and stainless-steel attachments for hostile environment applications.
- G. Use copper-plated pipe hangers and stainless-steel attachments for copper piping and tubing.
- H. Use padded hangers for piping that is subject to scratching.
- I. Use thermal hanger-shield inserts for insulated piping and tubing.
- J. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F pipes NPS 4 to NPS 24, requiring up to 4 inches of insulation.
3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes NPS 3/4 to NPS 36, requiring clamp flexibility and up to 4 inches of insulation.
4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 if little or no insulation is required.
5. Pipe Hangers (MSS Type 5): For suspension of pipes NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8.
7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.
11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.
12. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
14. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction occurs.
18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24, from single rod if horizontal movement caused by expansion and contraction occurs.
19. Complete Pipe Rolls (MSS Type 44): For support of pipes NPS 2 to NPS 42 if longitudinal movement caused by expansion and contraction occurs but vertical adjustment is unnecessary.
20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes NPS 2 to NPS 24 if small horizontal movement caused by expansion and contraction occurs and vertical adjustment is unnecessary.
21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 if vertical and lateral adjustment during installation, in addition to expansion and contraction, is required.

K. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.
- L. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment of up to 6 inches for heavy loads.
 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
 3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11 split pipe rings.
 4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
 5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.
- M. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel or Malleable-Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joint construction, to attach to top flange of structural shape.
 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 6. C-Clamps (MSS Type 23): For structural shapes.
 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
 11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:
 - a. Light (MSS Type 31): 750 lb.
 - b. Medium (MSS Type 32): 1500 lb.
 - c. Heavy (MSS Type 33): 3000 lb.
 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- N. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
 3. Thermal Hanger-Shield Inserts: For supporting insulated pipe.
- O. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41 roll hanger with springs.
 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load, and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load, and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.
 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load, and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.
 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.
 - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- P. Comply with MSS SP-58 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- Q. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.
- R. Use powder-actuated fasteners or mechanical-expansion anchors instead of building attachments where required in concrete construction.
- S. Use pipe-positioning systems in pipe spaces behind plumbing fixtures to support supply and waste piping for plumbing fixtures.

END OF SECTION 220529

SECTION 220553 - IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Equipment labels.
 - 2. Warning signs and labels.
 - 3. Pipe labels.
 - 4. Stencils.
 - 5. Valve tags.
 - 6. Warning tags.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- D. Valve numbering scheme.
- E. Valve Schedules: For each piping system to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

- A. Metal Labels for Equipment:
 - 1. Material and Thickness: Stainless steel, 0.025-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
 - 2. Letter Color: Black.
 - 3. Background Color: Stainless steel.

4. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
 5. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
 6. Fasteners: Stainless-steel self-tapping screws.
 7. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- B. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), and the Specification Section number and title where equipment is specified.
- C. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number, and identify Drawing numbers where equipment is indicated (plans, details, and schedules) and the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

2.2 WARNING SIGNS AND LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.
- B. Letter Color: Black.
- C. Background Color: White.
- D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- F. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
- G. Fasteners: Stainless-steel self-tapping screws.
- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- I. Label Content: Include caution and warning information plus emergency notification instructions.

2.3 PIPE LABELS

- A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction.

- B. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to cover full circumference of pipe and to attach to pipe without fasteners or adhesive.
- C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.
- D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings; also include pipe size and an arrow indicating flow direction.
 - 1. Flow-Direction Arrows: Integral with piping-system service lettering to accommodate both directions or as separate unit on each pipe label to indicate flow direction.
 - 2. Lettering Size: At least 1/2 inch for viewing distances up to 72 inches and proportionately larger lettering for greater viewing distances.

2.4 STENCILS

- A. Stencils for Piping:
 - 1. Lettering Size: At least 1/2 inch for viewing distances up to 72 inches and proportionately larger lettering for greater viewing distances.
 - 2. Stencil Material: Brass.
 - 3. Stencil Paint: Exterior, gloss, acrylic enamel in colors complying with recommendations in ASME A13.1 unless otherwise indicated. Paint may be in pressurized spray-can form.
 - 4. Identification Paint: Exterior, acrylic enamel in colors according to ASME A13.1 unless otherwise indicated. Paint may be in pressurized spray-can form.

2.5 VALVE TAGS

- A. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.
 - 1. Tag Material: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
 - 2. Fasteners: Brass wire-link chain or S-hook.
- B. Valve Schedules: For each piping system, on 8-1/2-by-11-inch bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.
 - 1. Valve-tag schedule shall be included in operation and maintenance data.

2.6 WARNING TAGS

- A. Description: Preprinted or partially preprinted accident-prevention tags of plasticized card stock with matte finish suitable for writing.
 - 1. Size: 3 by 5-1/4 inches minimum.

2. Fasteners: Brass grommet and wire.
3. Nomenclature: Large-size primary caption such as "DANGER," "CAUTION," or "DO NOT OPERATE."
4. Color: Safety yellow background with black lettering.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

3.2 GENERAL INSTALLATION REQUIREMENTS

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

3.3 EQUIPMENT LABEL INSTALLATION

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

3.4 PIPE LABEL INSTALLATION

- A. Stenciled Pipe Label Option: Stenciled labels may be provided instead of manufactured pipe labels, at Installer's option. Install stenciled pipe labels, complying with ASME A13.1, on each piping system.
 1. Identification Paint: Use for contrasting background.
 2. Stencil Paint: Use for pipe marking.
- B. Pipe Label Locations: Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:
 1. Near each valve and control device.
 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
 3. Near penetrations through walls, floors, ceilings, and inaccessible enclosures.
 4. At access doors, manholes, and similar access points that permit view of concealed piping.

5. Near major equipment items and other points of origination and termination.
 6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
 7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.
- C. Directional Flow Arrows: Arrows shall be used to indicate direction of flow in pipes, including pipes where flow is allowed in both directions.
- D. Pipe Label Color Schedule:
1. Domestic Water Piping
 - a. Background: Safety green.
 - b. Letter Colors: White.
 2. Sanitary Waste Piping:
 - a. Background Color: Safety black.
 - b. Letter Color: White.

3.5 VALVE-TAG INSTALLATION

- A. Install tags on valves and control devices in piping systems, except check valves, valves within factory-fabricated equipment units, shutoff valves, faucets, convenience and lawn-watering hose connections, and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.
- B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following subparagraphs:
1. Valve-Tag Size and Shape:
 - a. Cold Water: 1-1/2 inches, round.
 - b. Hot Water: 1-1/2 inches, round.
 2. Valve-Tag Colors:
 - a. Cold Water: Natural.
 - b. Hot Water: Natural.
 3. Letter Colors:
 - a. Cold Water: White.
 - b. Hot Water: White.

3.6 WARNING-TAG INSTALLATION

- A. Write required message on, and attach warning tags to, equipment and other items where required.

END OF SECTION 220553

SECTION 22 07 00

PLUMBING INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and General Provisions of Contract, including General and Supplementary Conditions, Division 1, and Division 22 of the Specification Sections, apply to work of this Section.

1.2 DESCRIPTION OF WORK:

- A. Contractor shall provide all materials, labor, tools, equipment, transportation and other facilities for the complete installation of pipe insulation for the piping systems listed herein.
- B. All hot pipes, tubing and fittings in traffic areas up to 6' in height shall be insulated for burn protection. All insulated pipe in traffic areas and mechanical rooms to be protected against mechanical damage with aluminum jacket.
- C. Drawings: The intent of the Specifications and Drawings is to have a "complete contract without extras". The bid drawings are schematic and should not be considered complete. Items not covered on the Drawings, or in this Section, yet are necessary for a "complete job" shall be considered incorporated in the Specifications.
- D. Coordination and Scheduling of Activities: This Contractor shall coordinate all of his work with that of the other Contractors, and with the Construction Manager.
- E. Within two weeks after award of this Contract, Contractor shall prepare a schedule showing the expected start and completion dates for this Contract and shall submit it to the Construction Manager for review.

1.3 QUALITY ASSURANCE:

- A. Provide equipment insulation and application materials with an independent or composite flame spread rating of 25 or less and a smoke development rating no higher than 50 when tested in accordance with ASTM E84, NFPA 255 or UL 723 unless specifically indicated otherwise.
- B. Certification of Tests: Permanently stamp shipping containers or materials with ASTM E84, NFPA 255, UL 723 flame spread and smoke developed rating.
- C. Ventilation: Comply with the requirements of ACGIH (American Conference of Governmental Industrial Hygienist; Threshold Limit Values).

1.4 REFERENCES:

- A. ASTM E84: Test for Surface Burning Characteristics of Building Materials.
- B. NFPA 255: Method of Test of Surface Burning Characteristics of Building Materials.
- C. UL 723: Tests of Surface Burning Characteristics of Building Materials.

1.5 SUBMITTALS:

- A. Submit product data including, but not limited to, the following:
 - 1. Manufacturer's name and product identification.
 - 2. Density in lbs. per cu. ft.
 - 3. Piping by system including insulation thickness in inches vs. sizes.

4. Thermal Conductivity in Btu/in./sq. ft./oF/hr. at 400oF mean temperature.
5. Perm rating in grains per hr. per sq. ft.
6. Minimum and maximum temperature limits in oF, if applicable.
7. Description of:
 - a. Adhesives.
8. Mechanical fasteners.
 - a. Application, finishing, and flashing materials and methods.
 - b. White PVC fitting covers (Zeston PVC Fitting and Jacket system).
 - c. Aluminum jacketing and fastening method.
 - d. Protective shields, saddles and inserts at hanger.
9. Insulation and Application Materials: Independent or Composite Fire Hazard Classification.

- B. All submittals shall be submitted in electronic (PDF) format with the exception of material and color samples.

1.6 DELIVERY, STORAGE AND HANDLING:

- A. Deliver materials to project site in manufacturer's containers with labels and seals intact.
- B. Store materials in original containers at not less than 60°F for at least 48 hours immediately before installation.

1.7 SCHEDULING:

- A. Schedule insulation application after pressure testing systems. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 SERVICE SCHEDULE

- A. Piping material and thickness shall be installed in conformance with the following service schedules: (See insulation schedule at end of section).

2.2 PIPE INSULATION SCHEDULE

A.	TAG	I -1
INSULATION		
- TYPE & MATERIAL		HEAVY DENSITY FIBERGLASS PIPE INSULATION WITH SELF-SEALING LAP
- FACING		WHITE KRAFT PAPER
- OPER. TEMP. RANGE, °F.		0 TO 850
- THERMAL CONDUCT., K		.24 @ 75°F. MEAN TEMP.
- FLAME SPREAD/SMOKE DEV.		25/50
FITTINGS		
- ELBOWS, TEES, FLANGES, ETC.		CUT & MITERED PIPE INSULATION OR MOLDED FIBERGLASS W/ PREMOLDED PVC COVER W/FIBERGLASS INSERT
- VALVES & STRAINERS		CUT & MITERED PIPE INSULATION MOLDED FIBERGLASS
JACKET		
- EXPOSED PIPE		PVC
- CONCEALED PIPE		NONE
- EXTERIOR PIPE		ALUMINUM
REMARKS		
		PROVIDE SHOP DRAWINGS
		PROVIDE DOUBLE THICK INSULATION ON PIPING IN OUTSIDE WALLS

PART 3 - EXECUTION

3.1 INSPECTION

- A. Examine areas and conditions under which mechanical insulation is to be installed. Do not proceed with work until unsatisfactory conditions have been corrected in manner acceptable to Installer.

3.2 INSTALLATION - GENERAL

- A. Apply insulation in accordance with the Schedule of Insulation at the end of this Section.
- B. Use only insulation and finish materials including adhesives, cements, and mastics which conform to the requirements of all local codes and ordinances.
- C. Fire resistant adhesive is highly flammable in liquid form. Eliminate welding,
- D. Apply insulation after all piping pressure tests, as described in Piping Installation Procedure, have been completed.

- E. Clean surfaces of loose scale, dirt, oil, and other foreign matter and dry prior to insulating.
- F. Apply insulation to completely cover piping surface. Do not insulate over weld certification stamps.
- G. "Exposed" as used in this section means exposed to view. "Concealed" means concealed to view such as in furred chases or above suspended ceiling. Penthouse and equipment rooms are considered exposed locations.
- H. Fill surface imperfections in the insulation such as chipped edges, small joints or cracks, and small voids or holes with appropriate insulation material and smooth with skim coat of hydraulic-setting insulating cement. Vapor barriers shall be continuous and unbroken at hanger installations.
- I. Fit inside diameter of insulation sections or segments to outside curvature of pipe or previous insulation layer.
- J. Where standard insulation shapes are not available, cut, score, or miter segments of appropriate block to fit contour of pipe. Stagger joints of adjoining segments. Fit insulation carefully and secure with No. 20 gage galvanized annealed steel wire. Finish with a smoothing coat of hydraulic-setting insulating cement.
- K. Insulate valves, strainer, fittings, and flanges with identical material, density, thickness, and surface finish as the piping insulation. All edges shall be filled with filler and finished with a smoothing coat of hydraulic-setting insulating cement.
- L. Insulate the entire surface of fittings and strainers. Insulate valves up to and including bonnets, unless authorized otherwise by Project Engineer. Do not cover removable valve bonnets.
- M. Insulate strainers to permit removal of the basket without disturbing the insulation of the strainer body. Strainer covers shall be molded and taped to upper section of insulation.
- N. Bevel the ends of pipe insulation adjacent to flanges to permit bolt removal. Provide a collar of sectional block insulation over the flanges and extend a minimum of 2 inches over the adjacent pipe insulation. Fasten with staples to permit easy removal. Prior to applying collar fill annular spaces with loose insulation.
- O. Insulate all piping through sleeves.
- P. Where pipelines pass through masonry walls or floors, completely fill the space between outside of pipe or insulation and the inside of the sleeve or framed opening with fibrous mineral wool or fiberglass pipe insulation.
- Q. For all insulated piping, cold and hot, supported on rollers, install minimum 120 degree segment rigid insulation and galvanized shields. Refer to Type P3 insulation.
- R. When it is unavoidable and hangers for cold lines must be installed directly on the pipe, insulate and finish the entire hanger and the rod for a length of not less than 12 inches above the pipe.
- S. For hot lines supported on rollers, provide pipe covering protection saddles and fill the hollow interior of saddles with insulating cement or fibrous glass.
- T. Insulate Dresser-type couplings and other gasketed joints in refrigerant systems in a manner to allow removal of insulation, without damage, for repair and leak-checking of couplings and gasketed joints.
- U. Apply insulation to completely cover metal surfaces.

- V. Cut, score, or miter insulation to fit shape and contour of ductwork and equipment. Where surfaces are flat, cylindrical, or regularly curved, use premolded blocks or segments.
- W. Where required, provide permanently fastened angles or plates to support insulation.
- X. Apply insulation on cover plates, heads and access openings as separate sections, with insulation cut back for access to boltheads and other fasteners.
- Y. Do not insulate over nameplates. Cut back insulation and line the insulation edges with 24 gage galvanized steel.
- Z. Surface Finish.
 - 1. Apply surface finish to present a tight, smooth appearance.
 - 2. Do not apply sealant or cement until all previous applications of cement and adhesives have thoroughly dried.
 - 3. Extend surface finish to protect all insulation surfaces. Prevent raw edges or ends of insulation from being exposed.
 - 4. Surface Finish (Indoor)
 - a. Concealed Pipe: No additional finish required.
 - b. Concealed Fittings, Valves, Flanges: Apply a skim coat of insulating cement to produce a smooth surface. After cement is dry, apply a light coat of fitting mastic. While mastic is still wet, wrap the fitting with fiberglass reinforcing cloth strips overlapping the preceding layer by 1 to 2 inches and adjoining pipe by 2 inches, and embedding the cloth into the mastic. When dry, apply a second coat of mastic over the entire fitting to a minimum wet thickness of 3/64 inch.
 - c. Exposed pipe and fittings: Apply one piece pre-molded PYC covers for fittings and piping. Tape joints between insulation and fitting cover with 2 inch pressure sensitive polyvinyl tape.
 - 5. Outdoor Exposed Piping
 - a. All outdoor exposed piping shall be painted with two coats of WB Armaflex Finish. Prior to applying the finish the insulation shall be wiped clean with denatured alcohol.
 - b. All outdoor exposed piping shall have the seams located on the lower half of the pipe.
 - c. Piping insulation shall be covered with Zeston 300 series PVC fitting covers and jacketing, 40 mil. thickness and treated for UV protection.

3.3 EXISTING INSULATION REPAIR

- A. Repair damaged sections of existing mechanical insulation, both previously damaged or damaged during this construction period. Use insulation of same thickness as existing insulation, install new jacket lapping and sealed over existing.

3.4 PROTECTION AND REPLACEMENT

- A. Replace damaged insulation which cannot be repaired satisfactorily, including units with vapor barrier damage and moisture saturated units.

- B. Protection - insulation Installer shall advise Contractor of required protection for insulation work during remainder of construction period, to avoid damage and deterioration.

3.5 PLUMBING PIPING INSULATION

A. Minimum Pipe Insulation

1. Thickness of Pipe Sizes

Service	Temp. °F	Insulation Type	Insulation Thickness for Pipe Sizes		
			Up to 1 1/4"	1 1/2" - 2"	Over 2"
Domestic Hot Water (DHWS&R)	170-180	I -1	1	2	2
Domestic Hot Water (DHWS&R)	140-170	I -1	1	1 1/2	2
Plant Water (PW)	45	I -1	1/2	1	1 1/2
Domestic cold water					

3.6 APPROVED INSULATION MANUFACTURERS:

- A. Owens Corning
- B. Knauf
- C. Certainteed
- D. Manville
- E. Substitutions: Architect/Owner Approved Equal

END OF SECTION

SECTION 221116 - DOMESTIC WATER PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Copper tube and fittings.
 - 2. Piping joining materials.
 - 3. Encasement for piping.
 - 4. Dielectric fittings.

1.3 ACTION SUBMITTALS

- A. Product Data:
 - 1. Pipe and tube.
 - 2. Fittings.
 - 3. Joining materials.
 - 4. Transition fittings.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Piping layout, or BIM model, drawn to scale, showing the items described in this Section, and coordinated with all building trades.
- B. System purging and disinfecting activities report.
- C. Field quality-control reports.

1.5 FIELD CONDITIONS

- A. Interruption of Existing Water Service: Do not interrupt water service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary water service according to requirements indicated:
 - 1. Notify Owner no fewer than five days in advance of proposed interruption of water service.
 - 2. Do not interrupt water service without Owner's written permission.

1.6 WARRANTY

- A. Manufacturer agrees to repair or replace all pipe and fittings that fail in materials or workmanship within 10 years from date of Substantial Completion.
 - 1. Warranty is to cover labor and material costs of repairing and/or replacing defective materials and repairing any incidental damage caused by failure of the piping system due to defects in materials or manufacturing.
 - 2. Warranty is to be in effect only upon submission by the Contractor to the manufacturer of valid pressure/leak documentation indicating that the system was tested and passed the manufacturer's pressure/leak test.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

- A. Potable-water piping and components shall comply with NSF 14, NSF 61, and NSF 372.

2.2 COPPER TUBE AND FITTINGS

- A. Drawn-Temper Copper Tube: ASTM B88, Type L.
- B. Annealed-Temper Copper Tube: ASTM B88, Type L.
- C. Cast-Copper, Solder-Joint Fittings: ASME B16.18, pressure fittings.
- D. Wrought-Copper, Solder-Joint Fittings: ASME B16.22, pressure fittings.
- E. Bronze Flanges: ASME B16.24, Class 150, with solder-joint ends.
- F. Cast Copper Unions: MSS SP-123, cast-copper-alloy, hexagonal-stock body, with ball-and-socket, metal-to-metal seating surfaces and solder-joint or threaded ends.
- G. Wrought Copper Unions: ASME B16.22.
- H. Copper-Tube, Mechanically Formed Tee Fitting: For forming T-branch on copper water tube.
 - 1. Description: Tee formed in copper tube in accordance with ASTM F2014.
- I. Grooved, Mechanical-Joint, Copper Tube Appurtenances:
 - 1. Grooved-End, Copper Fittings: ASTM B75 copper tube or ASTM B584 bronze castings.
 - 2. Grooved-End-Tube Couplings: To fit copper-tube dimensions; rigid pattern unless otherwise indicated; gasketed fitting, EPDM-rubber gasket, UL classified per NSF 61 and NSF 372, and rated for minimum 180 deg F, for use with ferrous housing and steel bolts and nuts; 300 psig minimum CWP pressure rating.
- J. Copper Tube, Pressure-Seal-Joint Fittings:
 - 1. Fittings: Cast-brass, cast-bronze, or wrought-copper with EPDM O-ring seal in each end.
 - 2. Minimum 200-psig working-pressure rating at 250 deg F.

K. Copper-Tube, Push-on-Joint Fittings:

1. Description:
 - a. Cast-copper fitting complying with ASME B16.18 or wrought-copper fitting complying with ASME B 16.22.
 - b. Stainless steel teeth and EPDM-rubber, O-ring seal in each end instead of solder-joint ends.

2.3 PIPING JOINING MATERIALS

A. Pipe-Flange Gasket Materials:

1. AWWA C110/A21.10, rubber, flat face, 1/8 inch thick or ASME B16.21, nonmetallic and asbestos free unless otherwise indicated.
2. Full-face or ring type unless otherwise indicated.

B. Metal, Pipe-Flange Bolts and Nuts: ASME B18.2.1, carbon steel unless otherwise indicated.

C. Solder Filler Metals: ASTM B32, lead-free alloys.

D. Flux: ASTM B813, water flushable.

E. Brazing Filler Metals: AWS A5.8M/A5.8, BCuP Series, copper-phosphorus alloys for general-duty brazing unless otherwise indicated.

F. Solvent Cements for Joining CPVC Piping and Tubing: ASTM F493.

G. Solvent Cements for Joining PVC Piping: ASTM D2564. Include primer according to ASTM F656.

H. Plastic, Pipe-Flange Gaskets, Bolts, and Nuts: Type and material recommended by piping system manufacturer unless otherwise indicated.

2.4 ENCASUREMENT FOR PIPING

A. Standard: ASTM A674 or AWWA C105/A21.5.

B. Form: Sheet or tube.

C. Color: Black or natural.

2.5 DIELECTRIC FITTINGS

A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.

B. Dielectric Unions:

1. Standard: ASSE 1079.
2. Pressure Rating: 125 psig minimum at 180 deg F.

3. End Connections: Solder-joint copper alloy and threaded ferrous.

PART 3 - EXECUTION

3.1 PIPING APPLICATIONS

- A. Transition and special fittings with pressure ratings at least equal to piping rating may be used in applications below unless otherwise indicated.
- B. Flanges and unions may be used for aboveground piping joints unless otherwise indicated.
- C. Fitting Option: Extruded-tee connections and brazed joints may be used on aboveground copper tubing.
- D. Aboveground domestic water piping, NPS 2 and smaller, shall be one of the following:
 1. Galvanized-steel pipe and nipples; galvanized, gray-iron threaded fittings; and threaded joints.
 2. Drawn-temper copper tube, ASTM B88, Type L; cast or wrought copper, solder-joint fittings; and soldered joints.

3.2 INSTALLATION OF PIPING

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of domestic water piping. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Install water-pressure-reducing valves downstream from shutoff valves.
- C. Install domestic water piping level and plumb.
- D. Install seismic restraints on piping. Comply with requirements for seismic-restraint devices.
- E. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- F. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- G. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.
- H. Install piping to permit valve servicing.
- I. Install nipples, unions, special fittings, and valves with pressure ratings the same as or higher than the system pressure rating used in applications below unless otherwise indicated.

- J. Install piping free of sags and bends.
- K. Install fittings for changes in direction and branch connections.
- L. Install PEX tubing with loop at each change of direction of more than 90 degrees.
- M. Install unions in copper tubing at final connection to each piece of equipment, machine, and specialty.
- N. Install pressure gauges on suction and discharge piping for each plumbing pump and packaged booster pump. Comply with requirements for pressure gauges in Section 220519 "Meters and Gages for Plumbing Piping."
- O. Install thermostats in hot-water circulation piping. Comply with requirements for thermostats in Section 221123 "Domestic Water Pumps."
- P. Install thermometers on inlet and outlet piping from each water heater. Comply with requirements for thermometers in Section 220519 "Meters and Gages for Plumbing Piping."
- Q. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."
- R. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."
- S. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

3.3 JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.
- C. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
- D. Brazed Joints for Copper Tubing: Comply with CDA's "Copper Tube Handbook," "Braze Joints" chapter.
- E. Soldered Joints for Copper Tubing: Apply ASTM B813, water-flushable flux to end of tube. Join copper tube and fittings according to ASTM B828 or CDA's "Copper Tube Handbook."

- F. Pressure-Sealed Joints for Copper Tubing: Join copper tube and pressure-seal fittings with tools and procedure recommended by pressure-seal-fitting manufacturer. Leave insertion marks on pipe after assembly.
- G. Push-on Joints for Copper Tubing: Clean end of tube. Measure insertion depth with manufacturer's depth gage. Join copper tube and push-on-joint fittings by inserting tube to measured depth.
- H. Extruded-Tee Connections: Form tee in copper tube according to ASTM F2014. Use tool designed for copper tube; drill pilot hole, form collar for outlet, dimple tube to form seating stop, and braze branch tube into collar.
- I. Joint Construction for Grooved-End Copper Tubing: Make joints according to AWWA C606. Roll groove ends of tubes. Lubricate and install gasket over ends of tubes or tube and fitting. Install coupling housing sections over gasket with keys seated in tubing grooves. Install and tighten housing bolts.
- J. Joint Construction for Grooved-End, Ductile-Iron Piping: Make joints according to AWWA C606. Cut round-bottom grooves in ends of pipe at gasket-seat dimension required for specified (flexible or rigid) joint. Lubricate and install gasket over ends of pipes or pipe and fitting. Install coupling housing sections over gasket with keys seated in piping grooves. Install and tighten housing bolts.
- K. Joint Construction for Grooved-End Steel Piping: Make joints according to AWWA C606. Square cut groove ends of pipe as specified. Lubricate and install gasket over ends of pipes or pipe and fitting. Install coupling housing sections over gasket with keys seated in piping grooves. Install and tighten housing bolts.
- L. Flanged Joints: Select appropriate asbestos-free, nonmetallic gasket material in size, type, and thickness suitable for domestic water service. Join flanges with gasket and bolts according to ASME B31.9.
- M. Joint Construction for Solvent-Cemented Plastic Piping: Clean and dry joining surfaces. Join pipe and fittings according to the following:
 - 1. Comply with ASTM F402 for safe-handling practice of cleaners, primers, and solvent cements. Apply primer.
 - 2. CPVC Piping: Join according to ASTM D2846/D2846M Appendix.
 - 3. PVC Piping: Join according to ASTM D2855.
- N. Joints for PEX Tubing, ASTM: Join according to ASTM F1807 for metal insert and copper crimp ring fittings and ASTM F1960 for cold expansion fittings and reinforcing rings.
- O. Joints for PEX Tubing, ASSE: Join according to ASSE 1061 for push-fit fittings.
- P. Joints for Dissimilar-Material Piping: Make joints using adapters compatible with materials of both piping systems.

3.4 INSTALLATION OF DIELECTRIC FITTINGS

- A. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.
- B. Dielectric Fittings for NPS 2 and Smaller: Use dielectric unions.

3.5 INSTALLATION OF HANGERS AND SUPPORTS

- A. Comply with requirements for seismic-restraint devices specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- B. Comply with requirements for hangers, supports, and anchor devices in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment."
- C. Install hangers for copper tubing with maximum horizontal spacing and minimum rod diameters, to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- D. Support horizontal piping within 12 inches of each fitting.
- E. Support vertical runs of copper tubing to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

3.6 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. When installing piping adjacent to equipment and machines, allow space for service and maintenance.
- C. Connect domestic water piping to exterior water-service piping. Use transition fitting to join dissimilar piping materials.
- D. Connect domestic water piping to water-service piping with shutoff valve; extend and connect to the following:
 - 1. Domestic Water Booster Pumps: Cold-water suction and discharge piping.
 - 2. Water Heaters: Cold-water inlet and hot-water outlet piping in sizes indicated, but not smaller than sizes of water heater connections.
 - 3. Plumbing Fixtures: Cold- and hot-water-supply piping in sizes indicated, but not smaller than that required by plumbing code.
 - 4. Equipment: Cold- and hot-water-supply piping as indicated, but not smaller than equipment connections. Provide shutoff valve and union for each connection. Use flanges instead of unions for NPS 2-1/2 and larger.

3.7 IDENTIFICATION

- A. Identify system components. Comply with requirements for identification materials and installation in Section 220553 "Identification for Plumbing Piping and Equipment."

3.8 ADJUSTING

- A. Perform the following adjustments before operation:
1. Close drain valves, hydrants, and hose bibbs.
 2. Open shutoff valves to fully open position.
 3. Open throttling valves to proper setting.
 4. Adjust balancing valves in hot-water-circulation return piping to provide adequate flow.
 - a. Manually adjust ball-type balancing valves in hot-water-circulation return piping to provide hot-water flow in each branch.
 - b. Adjust calibrated balancing valves to flows indicated.
 5. Remove plugs used during testing of piping and for temporary sealing of piping during installation.
 6. Remove and clean strainer screens. Close drain valves and replace drain plugs.
 7. Remove filter cartridges from housings and verify that cartridges are as specified for application where used and are clean and ready for use.
 8. Check plumbing specialties and verify proper settings, adjustments, and operation.

3.9 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
1. Piping Inspections:
 - a. Do not enclose, cover, or put piping into operation until it has been inspected and approved by authorities having jurisdiction.
 - b. During installation, notify authorities having jurisdiction at least one day before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:
 - 1) Roughing-in Inspection: Arrange for inspection of piping before concealing or closing in after roughing in and before setting fixtures.
 - 2) Final Inspection: Arrange for authorities having jurisdiction to observe tests specified in "Piping Tests" Subparagraph below and to ensure compliance with requirements.
 - c. Reinspection: If authorities having jurisdiction find that piping will not pass tests or inspections, make required corrections and arrange for reinspection.
 - d. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
 2. Piping Tests:
 - a. Fill domestic water piping. Check components to determine that they are not air bound and that piping is full of water.
 - b. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit a separate report for each test, complete with diagram of portion of piping tested.

- c. Leave new, altered, extended, or replaced domestic water piping uncovered and unconcealed until it has been tested and approved. Expose work that was covered or concealed before it was tested.
- d. Cap and subject piping to static water pressure of 50 psig above operating pressure, without exceeding pressure rating of piping system materials. Isolate test source and allow it to stand for four hours. Leaks and loss in test pressure constitute defects that must be repaired.
- e. Hydrostatic testing and documentation of test results for polypropylene piping to be in accordance with the manufacturer's instructions and submitted to the manufacturer upon successful completion per warranty requirements.
- f. Repair leaks and defects with new materials, and retest piping or portion thereof until satisfactory results are obtained.
- g. Prepare reports for tests and for corrective action required.

B. Domestic water piping will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

3.10 CLEANING

A. Clean and disinfect potable domestic water piping as follows:

1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
2. Use purging and disinfecting procedures prescribed by authorities having jurisdiction; if methods are not prescribed, use procedures described in either AWWA C651 or AWWA C652 or follow procedures described below:
 - a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
 - b. Fill and isolate system according to either of the following:
 - 1) Fill system or part thereof with water/chlorine solution with at least 50 ppm of chlorine. Isolate with valves and allow to stand for 24 hours.
 - 2) Fill system or part thereof with water/chlorine solution with at least 200 ppm of chlorine. Isolate and allow to stand for three hours.
 - c. Flush system with clean, potable water until no chlorine is in water coming from system after the standing time.
 - d. Repeat procedures if biological examination shows contamination.
 - e. Submit water samples in sterile bottles to authorities having jurisdiction.

B. Clean non-potable domestic water piping as follows:

1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
2. Use purging procedures prescribed by authorities having jurisdiction or; if methods are not prescribed, follow procedures described below:

- a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
 - b. Submit water samples in sterile bottles to authorities having jurisdiction. Repeat procedures if biological examination shows contamination.
- C. Prepare and submit reports of purging and disinfecting activities. Include copies of water-sample approvals from authorities having jurisdiction.
- D. Clean interior of domestic water piping system. Remove dirt and debris as work progresses.

END OF SECTION 221116

SECTION 221316 - SANITARY WASTE AND VENT PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Hubless, cast-iron soil pipe and fittings.
 - 2. PVC pipe and fittings.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Sustainable Design Submittals:
- C. Shop Drawings: For hubless, single-stack drainage system. Include plans, elevations, sections, and details.

1.4 INFORMATIONAL SUBMITTALS

- A. Seismic Qualification Certificates: For waste and vent piping, accessories, and components, from manufacturer.
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - 2. Detailed description of piping anchorage devices on which the certification is based and their installation requirements.
- B. Field quality-control reports.

1.5 FIELD CONDITIONS

- A. Interruption of Existing Sanitary Waste Service: Do not interrupt service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service according to requirements indicated:
 - 1. Notify Owner no fewer than five days in advance of proposed interruption of sanitary waste service.

2. Do not proceed with interruption of sanitary waste service without Owner's written permission.

1.6 WARRANTY

- A. Listed manufacturers to provide labeling and warranty of their respective products.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Components and installation shall be capable of withstanding the following minimum working pressure unless otherwise indicated:
 1. Soil, Waste, and Vent Piping: 10-foot head of water.
- B. Seismic Performance: Soil, waste, and vent piping and support and installation shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

2.2 PIPING MATERIALS

- A. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

2.3 HUBLESS, CAST-IRON SOIL PIPE AND FITTINGS

- A. Pipe and Fittings: ASTM A 888 or CISPI 301.
- B. Single-Stack Aerator Fittings: ASME B16.45, hubless, cast-iron aerator and deaerator drainage fittings.
- C. CISPI, Hubless-Piping Couplings:
 1. Standards: ASTM C 1277 and CISPI 310.
 2. Description: Stainless-steel corrugated shield with stainless-steel bands and tightening devices; and ASTM C 564, rubber sleeve with integral, center pipe stop.
- D. Heavy-Duty, Hubless-Piping Couplings:
 1. Standards: ASTM C 1277 and ASTM C 1540.
 2. Description: Stainless-steel shield with stainless-steel bands and tightening devices; and ASTM C 564, rubber sleeve with integral, center pipe stop.
- E. Cast-Iron, Hubless-Piping Couplings:
 1. Standard: ASTM C 1277.
 2. Description: Two-piece ASTM A 48/A 48M, cast-iron housing; stainless-steel bolts and nuts; and ASTM C 564, rubber sleeve with integral, center pipe stop.

2.4 PVC PIPE AND FITTINGS

- A. Comply with NSF 14, "Plastics Piping Systems Components and Related Materials," for plastic piping components. Include marking with "NSF-dwv" for plastic drain, waste, and vent piping and "NSF-sewer" for plastic sewer piping.
- B. Solid-Wall PVC Pipe: ASTM D 2665, drain, waste, and vent.
- C. Cellular-Core PVC Pipe: ASTM F 891, Schedule 40.
- D. PVC Socket Fittings: ASTM D 2665, made to ASTM D 3311, drain, waste, and vent patterns and to fit Schedule 40 pipe.
- E. Adhesive Primer: ASTM F 656.
- F. Solvent Cement: ASTM D 2564.

PART 3 - EXECUTION

3.1 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems.
 - 1. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations.
 - 2. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- E. Install piping to permit valve servicing.
- F. Install piping at indicated slopes.
- G. Install piping free of sags and bends.
- H. Install fittings for changes in direction and branch connections.
- I. Install piping to allow application of insulation.
- J. Install seismic restraints on piping.

- K. Make changes in direction for soil and waste drainage and vent piping using appropriate branches, bends, and long-sweep bends.
 - 1. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical.
 - 2. Use long-turn, double Y-branch and 1/8-bend fittings if two fixtures are installed back to back or side by side with common drain pipe.
 - a. Straight tees, elbows, and crosses may be used on vent lines.
 - 3. Do not change direction of flow more than 90 degrees.
 - 4. Use proper size of standard increasers and reducers if pipes of different sizes are connected.
 - a. Reducing size of waste piping in direction of flow is prohibited.
- L. Lay buried building waste piping beginning at low point of each system.
 - 1. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream.
 - 2. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements.
 - 3. Maintain swab in piping and pull past each joint as completed.
- M. Install soil and waste and vent piping at the following minimum slopes unless otherwise indicated:
 - 1. Building Sanitary Waste: 2 percent downward in direction of flow for piping NPS 3 and smaller; 2 percent downward in direction of flow for piping NPS 4 and larger.
 - 2. Horizontal Sanitary Waste Piping: 2 percent downward in direction of flow.
 - 3. Vent Piping: 1 percent down toward vertical fixture vent or toward vent stack.
- N. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
 - 1. Install encasement on underground piping according to ASTM A 674 or AWWA C105/A 21.5.
- O. Install aboveground copper tubing according to CDA's "Copper Tube Handbook."
- P. Install aboveground PVC piping according to ASTM D 2665.
- Q. Install underground PVC piping according to ASTM D 2321.
- R. Install engineered soil and waste and vent piping systems as follows:
 - 1. Combination Waste and Vent: Comply with standards of authorities having jurisdiction.
 - 2. Hubless, Single-Stack Drainage System: Comply with ASME B16.45 and hubless, single-stack aerator fitting manufacturer's written installation instructions.
 - 3. Reduced-Size Venting: Comply with standards of authorities having jurisdiction.

S. Plumbing Specialties:

1. Install backwater valves in sanitary waste gravity-flow piping.
2. Install cleanouts at grade and extend to where building sanitary drains connect to building sanitary sewers in sanitary waste gravity-flow piping.
3. Install drains in sanitary waste gravity-flow piping.

T. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.

U. Install sleeves for piping penetrations of walls, ceilings, and floors.

1. Comply with requirements for sleeves specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."

V. Install sleeve seals for piping penetrations of concrete walls and slabs.

1. Comply with requirements for sleeve seals specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."

W. Install escutcheons for piping penetrations of walls, ceilings, and floors.

1. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

3.2 JOINT CONSTRUCTION

A. Join hubless, cast-iron soil piping according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless-piping coupling joints.

B. Plastic, Nonpressure-Piping, Solvent-Cement Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:

1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.

3.3 INSTALLATION OF HANGERS AND SUPPORTS

A. Comply with requirements for seismic-restraint devices specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."

B. Comply with requirements for pipe hanger and support devices and installation specified in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment."

1. Install carbon-steel pipe hangers for horizontal piping in noncorrosive environments.
2. Install stainless-steel pipe hangers for horizontal piping in corrosive environments.
3. Install carbon-steel pipe support clamps for vertical piping in noncorrosive environments.
4. Install stainless-steel pipe support clamps for vertical piping in corrosive environments.

5. Vertical Piping: MSS Type 8 or Type 42, clamps.
 6. Install individual, straight, horizontal piping runs:
 - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
 - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
 - c. Longer Than 100 Feet if Indicated: MSS Type 49, spring cushion rolls.
 7. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
 8. Base of Vertical Piping: MSS Type 52, spring hangers.
- C. Install hangers for cast-iron soil piping, with maximum horizontal spacing and minimum rod diameters, to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- D. Install hangers for PVC piping, with maximum horizontal spacing and minimum rod diameters, to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- E. Support horizontal piping and tubing within 12 inches of each fitting and coupling.
- F. Support vertical runs of cast iron soil piping to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- G. Support vertical runs of PVC piping to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

3.4 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect soil and waste piping to exterior sanitary sewerage piping. Use transition fitting to join dissimilar piping materials.
- C. Connect waste and vent piping to the following:
 1. Plumbing Fixtures: Connect waste piping in sizes indicated, but not smaller than required by plumbing code.
 2. Plumbing Fixtures and Equipment: Connect atmospheric vent piping in sizes indicated, but not smaller than required by authorities having jurisdiction.
 3. Plumbing Specialties: Connect waste and vent piping in sizes indicated, but not smaller than required by plumbing code.
 4. Install test tees (wall cleanouts) in conductors near floor and floor cleanouts with cover flush with floor.
 5. Install horizontal backwater valves with cleanout cover flush with floor.
 6. Equipment: Connect waste piping as indicated.
 - a. Provide shutoff valve if indicated and union for each connection.
 - b. Use flanges instead of unions for connections NPS 2-1/2 and larger.

- D. Where installing piping adjacent to equipment, allow space for service and maintenance of equipment.
- E. Make connections according to the following unless otherwise indicated:
 - 1. Install unions, in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.
 - 2. Install flanges, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.

3.5 IDENTIFICATION

- A. Identify exposed sanitary waste and vent piping.
- B. Comply with requirements for identification specified in Section 220553 "Identification for Plumbing Piping and Equipment."

3.6 FIELD QUALITY CONTROL

- A. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.
 - 1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
 - 2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
- B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
- C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
- D. Test sanitary waste and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:
 - 1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired.
 - a. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
 - 2. Leave uncovered and unconcealed new, altered, extended, or replaced waste and vent piping until it has been tested and approved.
 - a. Expose work that was covered or concealed before it was tested.
 - 3. Roughing-in Plumbing Test Procedure: Test waste and vent piping except outside leaders on completion of roughing-in.

- a. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water.
 - b. From 15 minutes before inspection starts to completion of inspection, water level must not drop.
 - c. Inspect joints for leaks.
4. Finished Plumbing Test Procedure: After plumbing fixtures have been set and traps filled with water, test connections and prove they are gastight and watertight.
- a. Plug vent-stack openings on roof and building drains where they leave building. Introduce air into piping system equal to pressure of 1-inch wg.
 - b. Use U-tube or manometer inserted in trap of water closet to measure this pressure.
 - c. Air pressure must remain constant without introducing additional air throughout period of inspection.
 - d. Inspect plumbing fixture connections for gas and water leaks.
5. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
6. Prepare reports for tests and required corrective action.
- E. Clean interior of piping. Remove dirt and debris as work progresses.
- F. Protect sanitary waste and vent piping during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- G. Place plugs in ends of uncompleted piping at end of day and when work stops.
- H. Exposed PVC Piping: Protect plumbing vents exposed to sunlight with two coats of water-based latex paint.
- I. Repair damage to adjacent materials caused by waste and vent piping installation.

3.7 PIPING SCHEDULE

- A. Flanges and unions may be used on aboveground pressure piping unless otherwise indicated.
- B. Aboveground, soil and waste piping NPS 4 and smaller shall be any of the following:
1. Hubless, cast-iron soil pipe and fittings CISPI, hubless-piping couplings; and coupled joints.
 2. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
- C. Aboveground, vent piping NPS 4 and smaller shall be any of the following:
1. Hubless, cast-iron soil pipe and fittings; CISPI hubless-piping couplings; and coupled joints.
 2. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
- D. Underground, soil, waste, and vent piping NPS 4 and smaller shall be any of the following:

1. Hubless, cast-iron soil pipe and fittings; CISPI cast-iron hubless-piping couplings; and coupled joints.
2. Solid wall PVC pipe, PVC socket fittings, and solvent-cemented joints.

END OF SECTION 221316

SECTION 22 40 00

PLUMBING FIXTURES AND TRIM

PART 1 - GENERAL

1.1 SUMMARY OF ITEMS INCLUDED

- A. Extent of plumbing fixtures and trim work is indicated by drawings and by requirements of this section.
- B. Types of plumbing fixtures required for the project include the following:
 - 1. Water closets.
 - 2. Urinals.
 - 3. Lavatories.
 - 4. Specialty faucets.
- C. Refer to Division 26 sections for electrical connections to following plumbing fixtures, not work of this section.
 - 1. Sensor operated faucets.
 - 2. Sensor operated flush valves.

1.2 SUBMITTALS

- A. Product Data: Submit Product Data and installation instructions for each fixture, faucet, specialties, accessories, trim etc.
 - 1. Clearly indicate rated capacities of selected models of water coolers.
 - 2. Identify compliance with specified ANSI, UL, ASHRAE and State Standards, Codes and Listings.
- B. Shop Drawings: Submit rough-in drawings. Detail dimensions, rough-in requirements, required clearances and methods of assembly of components and anchorages. Coordinate requirements with Architectural Woodwork shop drawings for fixtures installed in countertops and cabinets. Furnish templates for use in woodwork shop.
- C. All submittals shall be submitted in electronic (PDF) format with the exception of material and color samples.

1.3 QUALITY ASSURANCE

- A. Plumbing code compliance: International Plumbing Code and conforming to the following flows.
 - 1. Lavatory faucets: .5 gpm.
 - 2. Sink faucets: 3 gpm.
 - 3. Water closets: 1.28 gal. per flush.
- B. Plumbing fixture standards: Comply with applicable portions of International Standard Plumbing Code pertaining to materials and installation of plumbing fixtures.
- C. Codes and Standards
 - 1. ANSI Standard A117.1: "Specifications for Making Buildings and Facilities Accessible To and Usable by Physically Handicapped People".
 - 2. Public Law 90-480: "Architectural Barriers Act of 1968".
 - 3. Public Law 101-336: "Americans with Disabilities Act".

4. ASHRAE Standard 18: "Method of Testing for Rating Drinking Water Coolers with Self-Contained Mechanical Refrigeration Systems."
5. ARI Standard 1010: "Drinking-Fountains and Self-Contained Mechanically-Refrigerated Drinking Water Coolers"
6. Public Law 90-480: "Architectural Barriers Act of 1968".
7. UL Standard 399: "Drinking Water Coolers".

1.4 DELIVERY, STORAGE AND HANDLING

- A. Store fixtures where environmental conditions are uniformly maintained within the manufacturer's recommended temperatures to prevent damage.
- B. Store fixtures and trim in the manufacturer's original shipping containers. Do not stack containers or store in such a manner that may cause damage to the fixture or trim.

1.5 SEQUENCE AND SCHEDULING

- A. Schedule rough-in installations with the installation of other building components.

PART 2 - PRODUCTS

2.1 PLUMBING FIXTURES

- A. General: Type, style, and material indicated, including stops, valves, faucets, strainers, wastes, escutcheons, faucets, bolts, screws, bushings, etc.
- B. Fixtures of same type must be furnished by single manufacturer.

2.2 MATERIALS

- C. Provide materials which have been selected for their surface flatness and smoothness. Exposed surfaces which exhibit pitting, seam marks, roller marks, foundry sand holes, stains, discoloration, or other surface imperfections on finished units are not acceptable.
- D. Fittings, trim and accessories to be copper or brass unless otherwise noted.
 1. Exposed or semi-exposed: Bright chrome-plated units.
 2. Escutcheons: Cast brass, bright chrome-plated with set screw.
- E. Vitreous china: High quality, free from fire cracks, spots, blisters, pinholes and specks, glaze exposed surfaces, and test for crazing resistance in accordance with ANSI/ASTM C 554.
- F. Manufacturer
 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, manufacturers specified.
 2. Fixtures: American Standard, Crane, Kohler, Eljer, Sloan.
 3. Flush valves: Sloan "Royal", Delany "Flushboy".
 4. Closet seats: Church, Beneke, Bemis.
 5. Chair carriers: Smith, Josam, Zurn.
 6. Supplies and traps: Fixture manufacturer or McGuire, Eastman Central D, Brass Craft, Bridgeport Brass.
 7. Catalog numbers are as noted.

8. Substitutions: Architect/Owner Approved Equal

2.2 PLUMBING FITTINGS, TRIM & ACCESSORIES

1. "WC-1 & WC-2" Water Closet (Flush Valve - Wall Hung) ADA Compliant mounting height
2. Bowl:
3. Refer to plumbing fixture schedule on drawings for "basis of design".
4. Vitreous china, water saver wall mounted, elongated. Barrier Free top inlet.
5. Flush valve:
6. Refer to plumbing fixture schedule on drawings for "basis of design".
7. Seat:
8. Open front elongated white solid plastic, no cover. Plastic covered self-sustaining check hinges. Church 295-CT, Beneke 523 SS/CH.
9. Refer to drawings for location of required raised seat heights.
10. Closet Carrier
11. Horizontal single closet fitting as noted on drawings similar to Smith 0210Y-M54.
12. Horizontal double closet fitting as noted on drawings similar to Smith 0208DY-M54.
13. Urinals "UR-1" (Handicapped ADA Compliant):
14. Urinal:
15. Refer to plumbing fixture schedule on drawings for "basis of design".
16. Wall hung vitreous china
17. Washdown flushing action
18. Top spud inlet
19. 2" NPT outlet flange
20. All mounting hardware included
21. Integral flushing rim
22. Flush Valve:
23. Refer to plumbing fixture schedule on drawings for "basis of design".
24. Lavatories "LAV-1" (Handicap ADA Compliant)
25. Lavatory:
26. Refer to plumbing fixture schedule on drawings for "basis of design".
27. Faucet:
28. Refer to plumbing fixture schedule on drawings for "basis of design".
29. Supplies:
30. McGuire 165 LK, 3/8" IPS x 3/8" OD flex, loose key, flexible risers. CP brass set screw escutcheons. CP brass nipple as required.
31. Trap:

32. McGuire 8902, 1-1/4" x 1-1/2" CP semi-cast brass P-trap, CO plug. Tubing drain to wall, CP brass set screw escutcheon. For handicap Offset Grid drain 7723.018.
33. Support:
34. Concealed armchair carrier, floor mounted.
35. Smith 700, Josam Series 17100, Wade W-521, Zurn Z1231, Josam C-356.
36. Safety covers (only required where traps are exposed):
37. A.D.A. covers for drain and supply lines for integral sink/ counters in toilet rooms R1008, R019, R603 and R605.
38. Manufacturers.
39. Plumberex "Handy Shield".
40. Brocar Products.
41. Truebro "Handi Lav Guard"
42. Substitutions: Architect/Owner Approved Equal.
43. EXECUTION
44. EXAMINATION
45. Verify all dimensions by field measurements. Verify that all plumbing fixtures may be installed in accordance with pertinent codes and regulations, the original design and the referenced standards.
46. Examine rough-in for potable water and waste piping systems to verify actual locations of piping connections prior to installing fixtures.
47. Examine walls, floors and cabinets for suitable conditions where fixtures are to be installed.
48. Do not proceed until unsatisfactory conditions have been corrected.
49. Coordinate lab sink installation with general contractor who is furnishing the sinks, faucets and tail pieces. Plumbing contractor responsible for connections, fittings and service to sinks.
50. INSTALLATION
51. Install plumbing fixtures level and plumb in accordance with fixture manufacturer's written instructions, rough-in drawings and pertinent codes and regulations, the original design and the referenced standards.
52. Comply with the installation requirements of ANSI A117.1, Public Law 90-480 and Public Law 101-336 with respect to plumbing fixtures for the physically handicapped.
53. Water closets flush valve handle on open side of fixtures.
54. Insulate water supply and drainpipes under wheelchair accessible lavatories and sinks.
55. Fasten plumbing fixtures securely to supports or building structure. Secure supplies behind or within wall construction to provide rigid installation.
56. Install a stop valve in an accessible location in the water connection to each fixture.
57. Install escutcheons at following locations:
58. Wall penetrations exposed finished locations.
59. Ceiling penetrations exposed finished locations.

60. Within cabinets and millwork.
61. Seal fixtures to walls and floors using silicone sealants or latex caulking. Match sealant color to fixture color.
62. Install traps o fixture outlets.
63. All exposed piping shall be chrome plated.
64. Water Hammer Arrestors – Install in upright position, location and sizes as shown on Hot & Cold-Water Piping in each toilet room and as indicated in accordance with PDI Standard WH-201.
65. FIELD QUALITY CONTROL
66. Test fixtures to demonstrate proper operation upon completion of installation and after units are water pressurized.
67. Inspect each installed unit for damage and operation, and that they are complete with trim, faucets, fittings and other specified components. Replace damaged or faulting operating fixtures. Replace washers and seals of leaking and dripping faucets, stops and traps.
68. CLEANING
69. Clean fixtures, trim and strainers using manufacturer's recommended cleaning methods and materials.
70. Remove faucet spouts and strainers, remove sediment and debris and reinstall.
71. Remove sediment and debris from drains.
72. PROTECTION
73. Provide protective covering for installed fixtures, and trim.
74. Do not allow use of fixtures for temporary facilities unless expressly approved in writing by the Owner.
75. MOUNTING HEIGHTS SCHEDULE
76. FIXTURE MOUNTING HEIGHT
77. Wheelchair Lavatories 34" floor to rim
78. Wheelchair Water Closet 17" - 19" floor to accessible rim
79. Urinals 17" to accessible to bowl rim.
80. SPARE PARTS
81. Furnish special wrenches and other devices necessary for servicing plumbing fixtures and trim to Owner with receipt in a quantity of one device for each 10 fixtures.
82. Furnish faucet repair kits complete with all necessary washers, springs, pins, retainers, packings, O-rings, sleeves and seats in a quantity of 1 kit for each 40 faucets.

END OF SECTION

SECTION 230529 - HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Metal pipe hangers and supports.
 - 2. Thermal-hanger shield inserts.
 - 3. Fastener systems.
 - 4. Equipment supports.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Sustainable Design Submittals:
- C. Shop Drawings: Show fabrication and installation details and include calculations for the following; include Product Data for components:
 - 1. Pipe hangers.
 - 2. Equipment supports.

1.4 INFORMATIONAL SUBMITTALS

- A. Welding certificates.

1.5 QUALITY ASSURANCE

- A. Structural-Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code, Section IX.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Hangers and supports for HVAC piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
 - 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
 - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
 - 3. Design seismic-restraint hangers and supports for piping and equipment and obtain approval from authorities having jurisdiction.

2.2 METAL PIPE HANGERS AND SUPPORTS

- A. Carbon-Steel Pipe Hangers and Supports:
 - 1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
 - 2. Galvanized Metallic Coatings: Pregalvanized, hot-dip galvanized, or electro-galvanized.
 - 3. Nonmetallic Coatings: Plastic coated, or epoxy powder-coated.
 - 4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
 - 5. Hanger Rods: Continuous-thread rod, nuts, and washer made of stainless steel.
- B. Copper Pipe and Tube Hangers:
 - 1. Description: MSS SP-58, Types 1 through 58, copper-plated steel, factory-fabricated components.
 - 2. Hanger Rods: Continuous-thread rod, nuts, and washer made of stainless steel.

2.3 THERMAL-HANGER SHIELD INSERTS

- A. Insulation-Insert Material for Hot Piping: ASTM C552, Type II cellular glass with 100-psi minimum compressive strength.
- B. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- C. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- D. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.4 FASTENER SYSTEMS

- A. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
- B. Mechanical-Expansion Anchors: Insert-wedge-type anchors for use in hardened portland cement concrete; with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
 - 1. Indoor Applications: Zinc-coated steel.
 - 2. Outdoor Applications: Stainless steel.

2.5 EQUIPMENT SUPPORTS

- A. Description: Welded, shop- or field-fabricated equipment support made from structural carbon-steel shapes.

2.6 MATERIALS

- A. Aluminum: ASTM B221.
- B. Carbon Steel: ASTM A1011/A1011M.
- C. Structural Steel: ASTM A36/A36M, carbon-steel plates, shapes, and bars; galvanized.
- D. Stainless Steel: ASTM A240/A240M.
- E. Threaded Rods: Continuously threaded. Zinc-plated or galvanized steel for indoor applications and stainless steel for outdoor applications. Mating nuts and washers of similar materials as rods.
- F. Grout: ASTM C1107/C1107M, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
 - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.

3.2 HANGER AND SUPPORT INSTALLATION

- A. Metal Pipe-Hanger Installation: Comply with MSS SP-58. Install hangers, supports, clamps, and attachments as required to properly support piping from the building structure.
- B. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.
- C. Fastener System Installation:
 - 1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual.
 - 2. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.
- D. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.
- E. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- F. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- G. Install lateral bracing with pipe hangers and supports to prevent swaying.
- H. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- I. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- J. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.
- K. Insulated Piping:
 - 1. Attach clamps and spacers to piping.
 - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
 - b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
 - 2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.

- a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
 - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
4. Shield Dimensions for Pipe: Not less than the following:
 - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
 - b. NPS 4: 12 inches long and 0.06 inch thick.
 - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
 - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
 - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
5. Pipes NPS 8 and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
6. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.3 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make bearing surface smooth.
- C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.4 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.5 PAINTING

- A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A780/A780M.

3.6 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-58 for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use carbon-steel pipe hangers and supports and attachments for general service applications.
- F. Use stainless steel pipe hangers and stainless steel attachments for hostile environment applications.
- G. Use copper-plated pipe hangers and copper or stainless steel attachments for copper piping and tubing.
- H. Use padded hangers for piping that is subject to scratching.
- I. Use thermal-hanger shield inserts for insulated piping and tubing.
- J. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
 - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F, pipes NPS 4 to NPS 24, requiring up to 4 inches of insulation.
 - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes NPS 3/4 to NPS 36, requiring clamp flexibility and up to 4 inches of insulation.
 - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 if little or no insulation is required.
 - 5. Pipe Hangers (MSS Type 5): For suspension of pipes NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
 - 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8.
 - 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
 - 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
 - 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
 - 10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.
 - 11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.

12. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
 13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
 14. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
 15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
 16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
 17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction might occur.
 18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24, from single rod if horizontal movement caused by expansion and contraction might occur.
 19. Complete Pipe Rolls (MSS Type 44): For support of pipes NPS 2 to NPS 42 if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is unnecessary.
 20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes NPS 2 to NPS 24 if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is unnecessary.
 21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- K. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.
- L. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
 3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
 4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
 5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.
- M. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joint construction, to attach to top flange of structural shape.

3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 6. C-Clamps (MSS Type 23): For structural shapes.
 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
 11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:
 - a. Light (MSS Type 31): 750 lb.
 - b. Medium (MSS Type 32): 1500 lb.
 - c. Heavy (MSS Type 33): 3000 lb.
 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- N. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
 3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.
- O. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41, roll hanger with springs.
 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.

7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.
8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.
 - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- P. Comply with MSS SP-58 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- Q. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.
- R. Use powder-actuated fasteners or mechanical-expansion anchors instead of building attachments where required in concrete construction.

END OF SECTION 230529

SECTION 230553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Equipment labels.
2. Pipe labels.
3. Duct labels.
4. Valve tags.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- D. Valve numbering scheme.
- E. Valve Schedules: For each piping system to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

- A. Metal Labels for Equipment:

1. Material and Thickness: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
2. Letter Color: Black.
3. Background Color: White.
4. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.

5. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
6. Fasteners: Stainless-steel self-tapping screws.
7. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

B. Plastic Labels for Equipment:

1. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.
2. Letter Color: Black.
3. Background Color: White.
4. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
5. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
6. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
7. Fasteners: Stainless-steel self-tapping screws.
8. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

C. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), and the Specification Section number and title where equipment is specified.

D. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number, and identify Drawing numbers where equipment is indicated (plans, details, and schedules) and the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

2.2 PIPE LABELS

A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction according to ASME A13.1.

B. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to cover full circumference of pipe and to attach to pipe without fasteners or adhesive.

C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.

D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings; also include pipe size and an arrow indicating flow direction.

1. Flow-Direction Arrows: Integral with piping system service lettering to accommodate both directions or as separate unit on each pipe label to indicate flow direction.
2. Lettering Size: At least 1/2 inch for viewing distances up to 72 inches and proportionately larger lettering for greater viewing distances.

2.3 DUCT LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.
- B. Letter Color: Black.
- C. Background Color: White.
- D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- F. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
- G. Fasteners: Stainless-steel self-tapping screws.
- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- I. Duct Label Contents: Include identification of duct service using same designations or abbreviations as used on Drawings; also include duct size and an arrow indicating flow direction.
 - 1. Flow-Direction Arrows: Integral with duct system service lettering to accommodate both directions or as separate unit on each duct label to indicate flow direction.

2.4 VALVE TAGS

- A. Description: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.
 - 1. Tag Material: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
 - 2. Fasteners: Brass wire-link chain or S-hook.
- B. Valve Schedules: For each piping system, on 8-1/2-by-11-inch bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.
 - 1. Valve-tag schedule shall be included in operation and maintenance data.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

3.2 GENERAL INSTALLATION REQUIREMENTS

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

3.3 EQUIPMENT LABEL INSTALLATION

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

3.4 PIPE LABEL INSTALLATION

- A. Pipe Label Locations: Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:
 - 1. Near each valve and control device.
 - 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
 - 3. Near penetrations and on both sides of through walls, floors, ceilings, and inaccessible enclosures.
 - 4. At access doors, manholes, and similar access points that permit view of concealed piping.
 - 5. Near major equipment items and other points of origination and termination.
 - 6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
 - 7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.
- B. Directional Flow Arrows: Arrows shall be used to indicate direction of flow in pipes, including pipes where flow is allowed in both directions.
- C. Pipe Label Color Schedule:
 - 1. Heating Water Piping: White letters on a safety-green background.
 - 2. Refrigerant Piping: Black letters on a safety-orange background.

3.5 DUCT LABEL INSTALLATION

- A. Install self-adhesive duct labels with permanent adhesive on air ducts in the following color codes:
 - 1. Blue: For cold-air supply ducts.
 - 2. Yellow: For hot-air supply ducts.
 - 3. Green: For exhaust-, outside-, relief-, return-, and mixed-air ducts.
- B. Stenciled Duct Label Option: Stenciled labels showing service and flow direction may be provided instead of plastic-laminated duct labels, at Installer's option.
- C. Locate labels near points where ducts enter into and exit from concealed spaces and at maximum intervals of 50 feet in each space where ducts are exposed or concealed by removable ceiling system.

3.6 VALVE-TAG INSTALLATION

- A. Install tags on valves and control devices in piping systems, except check valves, valves within factory-fabricated equipment units, shutoff valves, faucets, convenience and lawn-watering hose connections, and HVAC terminal devices and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.
- B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following subparagraphs:
 - 1. Valve-Tag Size and Shape:
 - a. Refrigerant: 1-1/2 inches, round.
 - b. Hot Water: 1-1/2 inches, round.
 - 2. Valve-Tag Colors:
 - a. Toxic and Corrosive Fluids: Black letters on a safety-orange background.
 - b. Flammable Fluids: Black letters on a safety-yellow background.
 - c. Combustible Fluids: White letters on a safety-brown background.
 - d. Potable and Other Water: White letters on a safety-green background.
 - e. Compressed Air: White letters on a safety-blue background.
 - f. Defined by User: White letters on a safety-purple background, black letters on a safety-white background, white letters on a safety-gray background, and white letters on a safety-black background

3.7 WARNING-TAG INSTALLATION

- A. Write required message on, and attach warning tags to, equipment and other items where required.

END OF SECTION 230553

SECTION 230593 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

- 1. Testing, Adjusting, and Balancing of Air Systems:
 - a. Variable volume air systems.
- 2. Testing, Adjusting, and Balancing of Hydronic Piping Systems:
 - a. Constant-flow hydronic systems.
- 3. Testing, adjusting, and balancing of equipment.
- 4. Sound tests.
- 5. Vibration tests.
- 6. Duct leakage tests verification.
- 7. Pipe leakage tests verification.
- 8. HVAC-control system verification.

1.3 DEFINITIONS

- A. AABC: Associated Air Balance Council.
- B. NEBB: National Environmental Balancing Bureau.
- C. TAB: Testing, adjusting, and balancing.
- D. TABB: Testing, Adjusting, and Balancing Bureau.
- E. TAB Specialist: An independent entity meeting qualifications to perform TAB work.
- F. TDH: Total dynamic head.
- G. UFAD: Underfloor air distribution.

1.4 PREINSTALLATION MEETINGS

- A. TAB Conference: Conduct a TAB conference at Project site after approval of the TAB strategies and procedures plan, to develop a mutual understanding of the details. Provide a minimum of 14 days' advance notice of scheduled meeting time and location.
 - 1. Minimum Agenda Items:
 - a. The Contract Documents examination report.
 - b. The TAB plan.
 - c. Needs for coordination and cooperation of trades and subcontractors.
 - d. Proposed procedures for documentation and communication flow.

1.5 ACTION SUBMITTALS

- A. Sustainable Design Submittals:

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: Within 30 days of Contractor's Notice to Proceed, submit documentation that the TAB specialist and this Project's TAB team members meet the qualifications specified in "Quality Assurance" Article.
- B. Contract Documents Examination Report: Within 30 days of Contractor's Notice to Proceed, submit the Contract Documents review report, as specified in Part 3.
- C. Strategies and Procedures Plan: Within 30 days of Contractor's Notice to Proceed, submit TAB strategies and step-by-step procedures, as specified in "Preparation" Article.
- D. System Readiness Checklists: Within 30 days of Contractor's Notice to Proceed, submit system readiness checklists, as specified in "Preparation" Article.
- E. Examination Report: Submit a summary report of the examination review required in "Examination" Article.
- F. Certified TAB reports.
- G. Sample report forms.
- H. Instrument calibration reports, to include the following:
 - 1. Instrument type and make.
 - 2. Serial number.
 - 3. Application.
 - 4. Dates of use.
 - 5. Dates of calibration.

1.7 QUALITY ASSURANCE

- A. TAB Specialists Qualifications, Certified by NEBB or TABB:
 - 1. TAB Field Supervisor: Employee of the TAB specialist and certified by NEBB or TABB.
 - 2. TAB Technician: Employee of the TAB specialist and certified by NEBB or TABB.
- B. Instrumentation Type, Quantity, Accuracy, and Calibration: Comply with requirements in ASHRAE 111, Section 4, "Instrumentation."
- C. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6.7.2.3 - "System Balancing."
- D. Code and AHJ Compliance: TAB is required to comply with governing codes and requirements of authorities having jurisdiction.

1.8 FIELD CONDITIONS

- A. Full Owner Occupancy: Owner will occupy the site and existing building during entire TAB period. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.
- B. Partial Owner Occupancy: Owner may occupy completed areas of building before Substantial Completion. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems designs that may preclude proper TAB of systems and equipment.
- B. Examine installed systems for balancing devices, such as test ports, gauge cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are applicable for intended purpose and are accessible.
- C. Examine the approved submittals for HVAC systems and equipment.
- D. Examine design data, including HVAC system descriptions, statements of design assumptions for environmental conditions and systems output, and statements of philosophies and assumptions about HVAC system and equipment controls.
- E. Examine ceiling plenums and underfloor air plenums used for HVAC to verify that they are properly separated from adjacent areas and sealed.

- F. Examine equipment performance data, including fan and pump curves.
 - 1. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
 - 2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems - Duct Design." Compare results with the design data and installed conditions.
- G. Examine system and equipment installations and verify that field quality-control testing, cleaning, and adjusting specified in individual Sections have been performed.
- H. Examine test reports specified in individual system and equipment Sections.
- I. Examine HVAC equipment and verify that bearings are greased, belts are aligned and tight, filters are clean, and equipment with functioning controls is ready for operation.
- J. Examine terminal units, such as variable-air-volume boxes, and verify that they are accessible and their controls are connected and functioning.
- K. Examine temporary and permanent strainers. Verify that temporary strainer screens used during system cleaning and flushing have been removed and permanent strainer baskets are installed and clean.
- L. Examine control valves for proper installation for their intended function of isolating, throttling, diverting, or mixing fluid flows.
- M. Examine heat-transfer coils for correct piping connections and for clean and straight fins.
- N. Examine system pumps to ensure absence of entrained air in the suction piping.
- O. Examine operating safety interlocks and controls on HVAC equipment.
- P. Examine control dampers for proper installation for their intended function of isolating, throttling, diverting, or mixing air flows.
- Q. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

3.2 PREPARATION

- A. Prepare a TAB plan that includes the following:
 - 1. Equipment and systems to be tested.
 - 2. Strategies and step-by-step procedures for balancing the systems.
 - 3. Instrumentation to be used.
 - 4. Sample forms with specific identification for all equipment.

- B. Perform system-readiness checks of HVAC systems and equipment to verify system readiness for TAB work. Include, at a minimum, the following:
 - 1. Airside:
 - a. Verify that leakage and pressure tests on air distribution systems have been satisfactorily completed.
 - b. Duct systems are complete with terminals installed.
 - c. Volume, smoke, and fire dampers are open and functional.
 - d. Clean filters are installed.
 - e. Fans are operating, free of vibration, and rotating in correct direction.
 - f. Variable-frequency controllers' startup is complete and safeties are verified.
 - g. Automatic temperature-control systems are operational.
 - h. Ceilings are installed.
 - i. Windows and doors are installed.
 - j. Suitable access to balancing devices and equipment is provided.
 - 2. Hydronics:
 - a. Verify leakage and pressure tests on water distribution systems have been satisfactorily completed.
 - b. Piping is complete with terminals installed.
 - c. Water treatment is complete.
 - d. Systems are flushed, filled, and air purged.
 - e. Strainers are pulled and cleaned.
 - f. Control valves are functioning in accordance with the sequence of operation.
 - g. Shutoff and balance valves have been verified to be 100 percent open.
 - h. Pumps are started and proper rotation is verified.
 - i. Pump gauge connections are installed directly at pump inlet and outlet flanges or in discharge and suction pipe prior to valves or strainers.
 - j. Variable-frequency controllers' startup is complete and safeties are verified.
 - k. Suitable access to balancing devices and equipment is provided.

3.3 GENERAL PROCEDURES FOR TESTING AND BALANCING

- A. Perform testing and balancing procedures on each system in accordance with the procedures contained in AABC's "National Standards for Total System Balance" or NEBB's "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems" and in this Section.
- B. Cut insulation, ducts, pipes, and equipment casings for installation of test probes to the minimum extent necessary for TAB procedures.
 - 1. After testing and balancing, patch probe holes in ducts with same material and thickness as used to construct ducts.
 - 2. After testing and balancing, install test ports and duct access doors that comply with requirements in Section 233300 "Air Duct Accessories."
 - 3. Where holes for probes are required in piping or hydronic equipment, install pressure and temperature test plugs to seal systems.
 - 4. Install and join new insulation that matches removed materials. Restore insulation, coverings, vapor barrier, and finish in accordance with Section 230713 "Duct Insulation,"

Section 230716 "HVAC Equipment Insulation," and Section 230719 "HVAC Piping Insulation."

- C. Mark equipment and balancing devices, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, with paint or other suitable, permanent identification material to show final settings.
- D. Take and report testing and balancing measurements in inch-pound (IP) units.

3.4 TESTING, ADJUSTING, AND BALANCING OF HVAC EQUIPMENT

- A. Test, adjust, and balance HVAC equipment indicated on Drawings, including, but not limited to, the following:
 - 1. VAV boxes
 - 2. Hot water reheat coils
 - 3. Split-system air conditioners.
 - 4. Heat pumps.

3.5 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

- A. Prepare test reports for both fans and outlets. Obtain manufacturer's outlet factors and recommended testing procedures. Crosscheck the summation of required outlet volumes with required fan volumes.
- B. Prepare schematic diagrams of systems' Record drawings duct layouts.
- C. For variable-air-volume systems, develop a plan to simulate diversity.
- D. Determine the best locations in main and branch ducts for accurate duct-airflow measurements.
- E. Check airflow patterns from the outdoor-air louvers and dampers and the return- and exhaust-air dampers through the supply-fan discharge and mixing dampers.
- F. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.
- G. Verify that motor starters are equipped with properly sized thermal protection.
- H. Check dampers for proper position to achieve desired airflow path.
- I. Check for airflow blockages.
- J. Check condensate drains for proper connections and functioning.
- K. Check for proper sealing of air-handling-unit components.

3.6 PROCEDURES FOR VARIABLE-VOLUME AIR SYSTEMS

- A. Adjust fans to deliver total indicated airflows within the maximum allowable fan speed listed by fan manufacturer.
 - 1. Measure total airflow.
 - a. Set outside-air, return-air, and relief-air dampers for proper position that simulates minimum outdoor-air conditions.
 - b. Where duct conditions allow, measure airflow by main Pitot-tube traverse. If necessary, perform multiple Pitot-tube traverses close to the fan and prior to any outlets, to obtain total airflow.
 - c. Where duct conditions are unsuitable for Pitot-tube traverse measurements, a coil traverse may be acceptable.
 - 2. Measure fan static pressures as follows:
 - a. Measure static pressure directly at the fan outlet or through the flexible connection.
 - b. Measure static pressure directly at the fan inlet or through the flexible connection.
 - c. Measure static pressure across each component that makes up the air-handling system.
 - d. Report artificial loading of filters at the time static pressures are measured.
 - 3. Review Contractor-prepared shop drawings and Record drawings to determine variations in design static pressures versus actual static pressures. Calculate actual system-effect factors. Recommend adjustments to accommodate actual conditions.
 - 4. Obtain approval from Owner for adjustment of fan speed higher or lower than indicated speed. Comply with requirements in HVAC Sections for air-handling units for adjustment of fans, belts, and pulley sizes to achieve indicated air-handling-unit performance.
 - 5. Do not make fan-speed adjustments that result in motor overload. Consult equipment manufacturers about fan-speed safety factors. Modulate dampers and measure fan-motor amperage to ensure that no overload occurs. Measure amperage in full-cooling, full-heating, economizer, and any other operating mode to determine the maximum required brake horsepower.
- B. Adjust volume dampers for main duct, submain ducts, and major branch ducts to indicated airflows.
 - 1. Measure airflow of submain and branch ducts.
 - 2. Adjust submain and branch duct volume dampers for specified airflow.
 - 3. Re-measure each submain and branch duct after all have been adjusted.
- C. Adjust air inlets and outlets for each space to indicated airflows.
 - 1. Set airflow patterns of adjustable outlets for proper distribution without drafts.
 - 2. Measure inlets and outlets airflow.
 - 3. Adjust each inlet and outlet for specified airflow.
 - 4. Re-measure each inlet and outlet after they have been adjusted.
- D. Verify final system conditions.

1. Re-measure and confirm that minimum outdoor, return, and relief airflows are within design. Readjust to design if necessary.
2. Re-measure and confirm that total airflow is within design.
3. Re-measure all final fan operating data, speed, volts, amps, and static profile.
4. Mark all final settings.
5. Test system in economizer mode. Verify proper operation and adjust if necessary.
6. Measure and record all operating data.
7. Record final fan-performance data.

3.7 GENERAL PROCEDURES FOR HYDRONIC SYSTEMS

- A. Prepare test reports for pumps, coils, and other equipment. Obtain approved submittals and manufacturer-recommended testing procedures. Crosscheck the summation of required coil and equipment flow rates with pump design flow rate.
- B. Prepare schematic diagrams of systems' Record drawings piping layouts.
- C. In addition to requirements in "Preparation" Article, prepare hydronic systems for testing and balancing as follows:
 1. Check expansion tank for proper setting.
 2. Check highest vent for adequate pressure.
 3. Check flow-control valves for proper position.
 4. Locate start-stop and disconnect switches, electrical interlocks, and motor controllers.
 5. Verify that motor controllers are equipped with properly sized thermal protection.
 6. Check that air has been purged from the system.
- D. Measure and record upstream and downstream pressure of each piece of equipment.
- E. Measure and record upstream and downstream pressure of pressure-reducing valves.
- F. Check settings and operation of automatic temperature-control valves, self-contained control valves, and pressure-reducing valves. Record final settings.
 1. Check settings and operation of each safety valve. Record settings.

3.8 PROCEDURES FOR CONSTANT-FLOW HYDRONIC SYSTEMS

- A. Adjust pumps to deliver total design flow.
 1. Measure total water flow.
 - a. Position valves for full flow through coils.
 - b. Measure flow by main flow meter, if installed.
 - c. If main flow meter is not installed, determine flow by pump TDH or known equipment pressure drop.
 2. Measure pump TDH as follows:

- a. Measure discharge pressure directly at the pump outlet flange or in discharge pipe prior to any valves.
 - b. Measure inlet pressure directly at the pump inlet flange or in suction pipe prior to any valves or strainers.
 - c. Convert pressure to head and correct for differences in gauge heights.
 - d. Verify pump impeller size by measuring the TDH with the discharge valve closed. Note the point on manufacturer's pump curve at zero flow, and verify that the pump has the intended impeller size.
 - e. With valves open, read pump TDH. Adjust pump discharge valve until design water flow is achieved. If excessive throttling is required to achieve desired flow, recommend pump impellers be trimmed to reduce excess throttling.
3. Monitor motor performance during procedures, and do not operate motor in an overloaded condition.
- B. Adjust flow-measuring devices installed in mains and branches to design water flows.
1. Measure flow in main and branch pipes.
 2. Adjust main and branch balance valves for design flow.
 3. Re-measure each main and branch after all have been adjusted.
- C. Adjust flow-measuring devices installed at terminals for each space to design water flows.
1. Measure flow at terminals.
 2. Adjust each terminal to design flow.
 3. Re-measure each terminal after it is adjusted.
 4. Position control valves to bypass the coil, and adjust the bypass valve to maintain design flow.
 5. Perform temperature tests after flows have been balanced.
- D. For systems with pressure-independent valves at terminals:
1. Measure differential pressure and verify that it is within manufacturer's specified range.
 2. Perform temperature tests after flows have been verified.
- E. For systems without pressure-independent valves or flow-measuring devices at terminals:
1. Measure and balance coils by either coil pressure drop or temperature method.
 2. If balanced by coil pressure drop, perform temperature tests after flows have been verified.
- F. Verify final system conditions as follows:
1. Re-measure and confirm that total water flow is within design.
 2. Re-measure final pumps' operating data, TDH, volts, amps, and static profile.
 3. Mark final settings.
- G. Verify that memory stops have been set.

3.9 PROCEDURES FOR AIR-COOLED CONDENSERS

- A. Verify proper rotation of fan(s).
- B. Measure and record entering- and leaving-air temperatures.
- C. Measure and record entering and leaving refrigerant pressures.
- D. Measure and record operating data of fan(s) and motor(s).

3.10 DUCT LEAKAGE TESTS

- A. Witness the duct leakage testing performed by Installer.
- B. Verify that proper test methods are used and that leakage rates are within specified limits.
- C. Report deficiencies observed.

3.11 PIPE LEAKAGE TESTS

- A. Witness the pipe pressure testing performed by Installer.
- B. Verify that proper test methods are used and that leakage rates are within specified limits.
- C. Report deficiencies observed.

3.12 HVAC CONTROLS VERIFICATION

- A. In conjunction with system balancing, perform the following:
 - 1. Verify HVAC control system is operating within the design limitations.
 - 2. Confirm that the sequences of operation are in compliance with Contract Documents.
 - 3. Verify that controllers are calibrated and function as intended.
 - 4. Verify that controller set points are as indicated.
 - 5. Verify the operation of lockout or interlock systems.
 - 6. Verify the operation of valve and damper actuators.
 - 7. Verify that controlled devices are properly installed and connected to correct controller.
 - 8. Verify that controlled devices travel freely and are in position indicated by controller: open, closed, or modulating.
 - 9. Verify location and installation of sensors to ensure that they sense only intended temperature, humidity, or pressure.
- B. Reporting: Include a summary of verifications performed, remaining deficiencies, and variations from indicated conditions.

3.13 TOLERANCES

- A. Set HVAC system's airflow rates and water flow rates within the following tolerances:

1. Supply, Return, and Exhaust Fans and Equipment with Fans: Plus or minus 10 percent. If design value is less than 100 cfm, within 10 cfm.
 2. Air Outlets and Inlets: Plus or minus 10 percent. If design value is less than 100 cfm, within 10 cfm.
 3. Heating-Water Flow Rate: Plus or minus 10 percent. If design value is less than 10 gpm, within 10 percent.
- B. Maintaining pressure relationships as designed shall have priority over the tolerances specified above.

3.14 PROGRESS REPORTING

- A. Initial Construction-Phase Report: Based on examination of the Contract Documents as specified in "Examination" Article, prepare a report on the adequacy of design for system-balancing devices. Recommend changes and additions to system-balancing devices, to facilitate proper performance measuring and balancing. Recommend changes and additions to HVAC systems and general construction to allow access for performance-measuring and -balancing devices.
- B. Status Reports: Prepare monthly progress reports to describe completed procedures, procedures in progress, and scheduled procedures. Include a list of deficiencies and problems found in systems being tested and balanced. Prepare a separate report for each system and each building floor for systems serving multiple floors.

3.15 FINAL REPORT

- A. General: Prepare a certified written report; tabulate and divide the report into separate sections for tested systems and balanced systems.
1. Include a certification sheet at the front of the report's binder, signed and sealed by the certified testing and balancing engineer.
 2. Include a list of instruments used for procedures, along with proof of calibration.
 3. Certify validity and accuracy of field data.
- B. Final Report Contents: In addition to certified field-report data, include the following:
1. Pump curves.
 2. Fan curves.
 3. Manufacturers' test data.
 4. Field test reports prepared by system and equipment installers.
 5. Other information relative to equipment performance; do not include Shop Drawings and Product Data.
- C. General Report Data: In addition to form titles and entries, include the following data:
1. Title page.
 2. Name and address of the TAB specialist.
 3. Project name.
 4. Project location.

5. Architect's name and address.
 6. Engineer's name and address.
 7. Contractor's name and address.
 8. Report date.
 9. Signature of TAB supervisor who certifies the report.
 10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.
 11. Summary of contents, including the following:
 - a. Indicated versus final performance.
 - b. Notable characteristics of systems.
 - c. Description of system operation sequence if it varies from the Contract Documents.
 12. Nomenclature sheets for each item of equipment.
 13. Data for terminal units, including manufacturer's name, type, size, and fittings.
 14. Notes to explain why certain final data in the body of reports vary from indicated values.
 15. Test conditions for fans performance forms, including the following:
 - a. Settings for outdoor-, return-, and exhaust-air dampers.
 - b. Conditions of filters.
 - c. Cooling coil, wet- and dry-bulb conditions.
 - d. Heating coil, dry-bulb conditions.
 - e. Face and bypass damper settings at coils.
 - f. Fan drive settings, including settings and percentage of maximum pitch diameter.
 - g. Settings for pressure controller(s).
 - h. Other system operating conditions that affect performance.
 16. Test conditions for pump performance forms, including the following:
 - a. Variable-frequency controller settings for variable-flow hydronic systems.
 - b. Settings for pressure controller(s).
 - c. Other system operating conditions that affect performance.
- D. System Diagrams: Include schematic layouts of air and hydronic distribution systems. Present each system with single-line diagram and include the following:
1. Quantities of outdoor, supply, return, and exhaust airflows.
 2. Water and steam flow rates.
 3. Duct, outlet, and inlet sizes.
 4. Pipe and valve sizes and locations.
 5. Terminal units.
 6. Balancing stations.
 7. Position of balancing devices.
- E. Air-Handling-Unit Test Reports: For air-handling units, include the following:
1. Unit Data:
 - a. Unit identification.
 - b. Location.

- c. Make and type.
 - d. Model number and unit size.
 - e. Manufacturer's serial number.
 - f. Unit arrangement and class.
 - g. Discharge arrangement.
 - h. Sheave make, size in inches, and bore.
 - i. Center-to-center dimensions of sheave and amount of adjustments in inches.
 - j. Number, make, and size of belts.
 - k. Number, type, and size of filters.
2. Motor Data:
- a. Motor make, and frame type and size.
 - b. Horsepower and speed.
 - c. Volts, phase, and hertz.
 - d. Full-load amperage and service factor.
 - e. Sheave make, size in inches, and bore.
 - f. Center-to-center dimensions of sheave and amount of adjustments in inches.
3. Test Data (Indicated and Actual Values):
- a. Total airflow rate in cfm.
 - b. Total system static pressure in inches wg.
 - c. Fan speed.
 - d. Inlet and discharge static pressure in inches wg.
 - e. For each filter bank, filter static-pressure differential in inches wg.
 - f. Preheat-coil static-pressure differential in inches wg.
 - g. Cooling-coil static-pressure differential in inches wg.
 - h. Heating-coil static-pressure differential in inches wg.
 - i. List for each internal component with pressure-drop, static-pressure differential in inches wg.
 - j. Outdoor airflow in cfm.
 - k. Return airflow in cfm.
 - l. Outdoor-air damper position.
 - m. Return-air damper position.

3.16 VERIFICATION OF TAB REPORT

- A. Owner shall randomly select measurements, documented in the final report, to be rechecked. Rechecking shall be limited to the lesser of either 10 percent of the total measurements recorded or the extent of measurements that can be accomplished in a normal 8-hour business day.
- B. If rechecks yield measurements that differ from the measurements documented in the final report by more than the tolerances allowed, the measurements shall be noted as "FAILED."
- C. If the number of "FAILED" measurements is greater than 20 percent of the total measurements checked during the final inspection, the TAB shall be considered incomplete and shall be rejected.

- D. If recheck measurements find the number of failed measurements noncompliant with requirements indicated, proceed as follows:
 - 1. TAB specialists shall recheck all measurements and make adjustments. Revise the final report and balancing device settings to include all changes; resubmit the final report and request a second final inspection. All changes shall be tracked to show changes made to previous report.
 - 2. If the second final inspection also fails, Owner may pursue others Contract options to complete TAB work.
- E. Prepare test and inspection reports.

3.17 ADDITIONAL TESTS

- A. Within 90 days of completing TAB, perform additional TAB to verify that balanced conditions are being maintained throughout and to correct unusual conditions.
- B. Seasonal Periods: If initial TAB procedures were not performed during near-peak summer and winter conditions, perform additional TAB during near-peak summer and winter conditions.

END OF SECTION 230593

SECTION 23 33 00
AIR DUCT ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Manual volume dampers.
2. Control dampers.
3. Fire dampers.
4. Flange connectors.
5. Duct silencers.
6. Turning vanes.
7. Duct-mounted access doors.
8. Flexible connectors.
9. Flexible ducts.
10. Duct Accessory Hardware.

B. Related Sections:

1. Division 28 Section "Fire Alarm" for duct-mounted fire and smoke detectors.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated.

1. For duct silencers, include pressure drop and dynamic insertion loss data. Include breakout noise calculations for high transmission loss casings.

B. Shop Drawings: For duct accessories. Include plans, elevations, sections, details and attachments to other work.

1. Detail duct accessories fabrication and installation in ducts and other construction. Include dimensions, weights, loads, and required clearances, and method of field assembly into duct systems and other construction. Include the following:
 - a. Special fittings.
 - b. Manual volume damper installations.
 - c. Control damper installations.
 - d. Fire-damper and smoke-damper damper installations, including sleeves; and duct-mounted access doors and remote damper operators.
 - e. Wiring Diagrams: For power, signal, and control wiring.

C. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which ceiling-mounted access panels and access doors required for access to duct accessories are shown and coordinated with each other, using input from Installers of the items involved.

D. Source quality-control reports.

E. Operation and Maintenance Data: For air duct accessories to include in operation and maintenance manuals.

F. All submittals shall be submitted in electronic (PDF) format with the exception of material and color samples.

1.4 QUALITY ASSURANCE

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with AMCA 500-D testing for damper rating.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- B. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
 - 1. Galvanized Coating Designation: G90.
 - 2. Exposed-Surface Finish: Mill phosphatized.
- C. Stainless-Steel Sheets: Comply with ASTM A 480/A 480M, Type 304, and having a No. 2 finish for concealed ducts and 4B finish for exposed ducts.
- D. Aluminum Sheets: Comply with ASTM B 209, Alloy 3003, Temper H14; with mill finish for concealed ducts and standard, 1-side bright finish for exposed ducts.
- E. Extruded Aluminum: Comply with ASTM B 221, Alloy 6063, Temper T6.
- F. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.
- G. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.2 MANUAL VOLUME DAMPERS

- A. Low-Leakage, Steel, Manual Volume Dampers:
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Air Balance Inc.; a division of Mestek, Inc.
 - b. American Warming and Ventilating; a division of Mestek, Inc.
 - c. Flexmaster U.S.A., Inc.
 - d. McGill AirFlow LLC.
 - e. METALAIRE, Inc.
 - f. Nailor Industries Inc.
 - g. Pottorff; a division of PCI Industries, Inc.
 - h. Ruskin Company.
 - i. Trox USA Inc.
 - j. Vent Products Company, Inc.
 - k. Substitutions: Architect/Owner Approved Equal
 - 2. Low-leakage rating, with linkage outside airstream, and bearing AMCA's Certified Ratings Seal for both air performance and air leakage.
 - 3. Suitable for horizontal or vertical applications.
 - 4. Frames:
 - a. Hat shaped.
 - b. Galvanized or Stainless-steel channels, 0.064 inch thick.
 - c. Mitered and welded corners.
 - d. Flanges for attaching to walls and flangeless frames for installing in ducts.
 - 5. Blades:

- a. Multiple blade.
 - b. Parallel- or opposed-blade design.
 - c. Stiffen damper blades for stability.
 - d. Galvanized or Stainless, roll-formed steel, 0.064 inch thick.
6. Blade Axles: Galvanized steel or Stainless steel.
7. Bearings:
- a. Oil-impregnated bronze.
 - b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
8. Blade Seals: Neoprene.
9. Jamb Seals: Cambered stainless steel.
10. Tie Bars and Brackets: Galvanized steel.
11. Accessories:
- a. Include locking device to hold multiple-blade dampers in a fixed position without vibration and with position indicator.

B. Jackshaft:

- 1. Size: 1-inch diameter.
- 2. Material: Galvanized-steel pipe rotating within pipe-bearing assembly mounted on supports at each mullion and at each end of multiple-damper assemblies.
- 3. Length and Number of Mountings: As required to connect linkage of each damper in multiple-damper assembly.

C. Damper Hardware:

- 1. Zinc-plated, die-cast core with dial and handle made of 3/32-inch-thick zinc-plated steel, and a 3/4-inch hexagon locking nut.
- 2. Include center hole to suit damper operating-rod size.
- 3. Include elevated platform for insulated duct mounting.

2.3 CONTROL DAMPERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- 1. American Warming and Ventilating; a division of Mestek, Inc.
- 2. Arrow United Industries; a division of Mestek, Inc.
- 3. Cesco Products; a division of Mestek, Inc.
- 4. Duro Dyne Inc.
- 5. Flexmaster U.S.A., Inc.
- 6. Greenheck Fan Corporation.
- 7. Lloyd Industries, Inc.
- 8. M&I Air Systems Engineering; Division of M&I Heat Transfer Products Ltd.
- 9. McGill AirFlow LLC.
- 10. METALAIRE, Inc.
- 11. Metal Form Manufacturing, Inc.
- 12. Nailor Industries Inc.
- 13. NCA Manufacturing, Inc.
- 14. Ruskin Company.
- 15. Vent Products Company, Inc.
- 16. Young Regulator Company.
- 17. Substitutions: Architect/Owner Approved Equal

B. Low-leakage rating, with linkage outside airstream, and bearing AMCA's Certified Ratings Seal for both air performance and air leakage.

C. Frames:

1. Hat shaped.
2. Galvanized steel channels, 0.064 inch thick.
3. Mitered and welded corners.

D. Blades:

1. Multiple blade with maximum blade width of 8 inches.
2. Parallel-blade design.
3. Galvanized steel.
4. 0.064 inch thick.
5. Blade Edging: Closed-cell neoprene edging.
6. Blade Edging: Inflatable seal blade edging, or replaceable rubber seals.

E. Blade Axles: 1/2-inch-diameter; galvanized steel; blade-linkage hardware of zinc-plated steel and brass; ends sealed against blade bearings.

1. Operating Temperature Range: From minus 40 to plus 200 deg F.

F. Bearings:

1. Oil-impregnated bronze.
2. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
3. Thrust bearings at each end of every blade.

2.4 FLANGE CONNECTORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Ductmate Industries, Inc.
2. Nexus PDQ; Division of Shilco Holdings Inc.
3. Ward Industries, Inc.; a division of Hart & Cooley, Inc.

B. Description: Add-on or roll-formed, factory-fabricated, slide-on transverse flange connectors, gaskets, and components.

C. Material: Galvanized steel.

D. Gage and Shape: Match connecting ductwork.

2.5 TURNING VANES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Ductmate Industries, Inc.
2. Duro Dyne Inc.
3. METALAIRE, Inc.
4. SEMCO Incorporated.
5. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
6. Substitutions: Architect/Owner Approved Equal
- 7.

B. Manufactured Turning Vanes for Metal Ducts: Curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.

1. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.

C. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 2-3, "Vanes and Vane Runners," and 2-4, "Vane Support in Elbows."

D. Vane Construction: Double wall.

2.6 DUCT-MOUNTED ACCESS DOORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. American Warming and Ventilating; a division of Mestek, Inc.
 2. Cesco Products; a division of Mestek, Inc.
 3. Ductmate Industries, Inc.
 4. Flexmaster U.S.A., Inc.
 5. Greenheck Fan Corporation.
 6. McGill AirFlow LLC.
 7. Nailor Industries Inc.
 8. Pottorff; a division of PCI Industries, Inc.
 9. Ventfabrics, Inc.
 10. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
 11. Substitutions: Architect/Owner Approved Equal
 - 12.
- B. Duct-Mounted Access Doors: Fabricate access panels according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 2-10, "Duct Access Doors and Panels," and 2-11, "Access Panels - Round Duct."
1. Door:
 - a. Double wall, rectangular.
 - b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
 - c. Vision panel.
 - d. Hinges and Latches: 1-by-1-inch butt or piano hinge and cam latches.
 - e. Fabricate doors airtight and suitable for duct pressure class.
 2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
 3. Number of Hinges and Locks:
 - a. Access Doors Less Than 12 Inches Square: No hinges and two sash locks.
 - b. Access Doors up to 18 Inches Square: Two hinges and two sash locks.
 - c. Access Doors up to 24 by 48 Inches: Three hinges and two compression latches with outside and inside handles.

2.7 FLEXIBLE CONNECTORS - DOWNDRAFT

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Ductmate Industries, Inc.
 2. Duro Dyne Inc.
 3. Ventfabrics, Inc.
 4. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
 5. Substitutions: Architect/Owner Approved Equal
- B. Materials: Flame-retardant or noncombustible fabrics.
- C. Coatings and Adhesives: Comply with UL 181, Class 1.
- D. Metal-Edged Connectors: Factory fabricated with a fabric strip 5-3/4 inches wide attached to 2 strips of 2-3/4-inch-wide, 0.028-inch-thick, galvanized sheet steel. Provide metal compatible with connected ducts.
- E. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.
1. Minimum Weight: 26 oz./sq. yd.
 2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
 3. Service Temperature: Minus 40 to plus 200 deg F.

- F. Thrust Limits: Combination coil spring and elastomeric insert with spring and insert in compression, and with a load stop. Include rod and angle-iron brackets for attaching to fan discharge and duct.
 1. Frame: Steel, fabricated for connection to threaded rods and to allow for a maximum of 30 degrees of angular rod misalignment without binding or reducing isolation efficiency.
 2. Outdoor Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
 6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
 7. Coil Spring: Factory set and field adjustable for a maximum of 1/4-inch movement at start and stop.

2.8 FLEXIBLE DUCTS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 1. Flexmaster U.S.A., Inc.
 2. McGill AirFlow LLC.
 3. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
 4. Substitutions: Architect/Owner Approved Equal
- B. Insulated, Flexible Duct: UL 181, Class 1, 2-ply vinyl film supported by helically wound, spring-steel wire; fibrous-glass insulation; polyethylene aluminized vapor-barrier film.
 1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
 2. Maximum Air Velocity: 4000 fpm.
 3. Temperature Range: Minus 10 to plus 160 deg F.
 4. Insulation R-value: Comply with ASHRAE/IESNA 90.1-2004.
- C. Flexible Duct Connectors:
 1. Clamps: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action in sizes 3 through 18 inches, to suit duct size.

2.9 2.10 DUCT ACCESSORY HARDWARE

- A. A. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct-insulation thickness.
- B. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.

2.10 FIRE DAMPERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. Air Balance Inc.; a division of Mestek, Inc.
 2. Arrow United Industries; a division of Mestek, Inc.
 3. McGill AirFlow LLC.
 4. METALAIRE, Inc.
 5. Ruskin Company.
 6. Vent Products Company, Inc.
 7. Substitutions: Architect/Owner Approved Equal
- B. Type: Static and dynamic; rated and labeled according to UL 555 by an NRTL.
- C. Closing rating in ducts up to 4-inch wg static pressure class and minimum 4000-fpm velocity.
- D. Fire Rating: 1-1/2 hours.

- E. Frame: Curtain type with blades inside airstream Curtain type with blades outside airstream Multiple-blade type Curtain type with blades outside airstream except when located behind grille where blades may be inside airstream; fabricated with roll-formed, 0.034-inch- thick galvanized steel; with mitered and interlocking corners.
- F. Mounting Sleeve: Factory- or field-installed, galvanized sheet steel.
 - 1. Minimum Thickness: 0.052 or 0.138 inch thick, as indicated, and of length to suit application.
 - 2. Exception: Omit sleeve where damper-frame width permits direct attachment of perimeter mounting angles on each side of wall or floor; thickness of damper frame must comply with sleeve requirements.
- G. Mounting Orientation: Vertical or horizontal as indicated.
- H. Blades: Roll-formed, interlocking, 0.034-inch- thick, galvanized sheet steel. In place of interlocking blades, use full-length, 0.034-inch- thick, galvanized-steel blade connectors.
- I. Horizontal Dampers: Include blade lock and stainless-steel closure spring.
- J. Heat-Responsive Device: Replaceable, 165 deg F rated, fusible links.
- K. Heat-Responsive Device: resettable link and switch package, factory installed, 165 deg F rated.

PART 3 - EXECUTION

3.1 INSPECTION

- A. Examine areas and conditions under which duct accessories will be installed. Do not proceed with work until unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.
- B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, and stainless-steel accessories in stainless-steel ducts.
- C. Install control dampers at inlet of exhaust fans or exhaust ducts as close as possible to exhaust fan unless otherwise indicated.
- D. Install volume dampers at points on supply, return, and exhaust systems at a minimum of two duct widths where branches extend from larger ducts. Where dampers are installed in ducts having duct liner, install dampers with hat channels of same depth as liner, and terminate liner with nosing at hat channel.
 - 1. Install steel volume dampers in steel ducts.
- E. Set dampers to fully open position before testing, adjusting, and balancing.
- F. Install test holes at fan inlets and outlets and elsewhere where required for testing and balancing purposes.
- G. Install fire and smoke dampers according to UL listing.
- H. Connect ducts to duct silencers rigidly.
- I. Install duct access doors on sides of ducts to allow for inspecting, adjusting, and maintaining accessories and equipment at the following locations:
 - 1. On both sides of duct coils.
 - 2. Upstream from duct filters.
 - 3. At outdoor-air intakes and mixed-air plenums.
 - 4. At drain pans and seals.

5. Downstream from manual volume dampers, control dampers, backdraft dampers, and equipment.
6. Adjacent to and close enough to fire or smoke dampers, to reset or reinstall fusible links. Access doors for access to fire or smoke dampers having fusible links shall be pressure relief access doors and shall be outward operation for access doors installed upstream from dampers and inward operation for access doors installed downstream from dampers.
7. At each change in direction and at maximum 50-foot spacing.
8. Upstream from turning vanes.
9. Upstream or downstream from duct silencers.
10. Control devices requiring inspection.
11. Elsewhere as indicated.

J. Install access doors with swing against duct static pressure.

K. Access Door Sizes:

1. One-Hand or Inspection Access: 8 by 5 inches.
2. Two-Hand Access: 12 by 6 inches.
3. Head and Hand Access: 18 by 10 inches.
4. Head and Shoulders Access: 21 by 14 inches.
5. Body Access: 25 by 14 inches.
6. Body plus Ladder Access: 25 by 17 inches.

L. Label access doors according to Division 23 Section "Identification for HVAC Piping and Equipment" to indicate the purpose of access door.

M. Install flexible connectors to connect ducts to equipment.

N. Connect terminal units to supply ducts directly. Do not use flexible ducts to change directions.

O. Connect diffusers to ducts with maximum 72-inch lengths of flexible duct clamped or strapped in place.

P. Connect flexible ducts to metal ducts with draw bands.

Q. For fans developing static pressures of 5-inch wg and higher, cover flexible connectors with loaded vinyl sheet held in place with metal straps.

R. Install thrust limits at centerline of thrust, symmetrical on both sides of equipment. Attach thrust limits at centerline of thrust and adjust to a maximum of 1/4-inch movement during start and stop of fans.

S. Install turning vanes in square or rectangular 90-degree elbows in supply and exhaust air systems, and elsewhere as indicated.

T. Coordinate with other work, including ductwork, as necessary to interface installation of duct accessories properly with other work.

3.3 FIELD QUALITY CONTROL

A. General – Operate installed duct accessories to demonstrate compliance with requirements. Test for air leakage while system is operating. Repair or replace faulty accessories, as required to obtain proper operation and leakproof performance.

B. Tests and Inspections:

1. Operate dampers to verify full range of movement.
2. Inspect locations of access doors and verify that purpose of access door can be performed.
3. Operate fire, smoke, and combination fire and smoke dampers to verify full range of movement and verify that proper heat-response device is installed.
4. Inspect turning vanes for proper and secure installation.
5. Operate remote damper operators to verify full range of movement of operator and damper.
6. Furnish and install control dampers to match material of duct system.

3.4 DUCT TEST HOLES

- A. Where ducts are insulated, neatly cut a 3-inch-wide strip of insulation away from hole site.
- B. Drill holes in ducts, casings and plenums not exceeding 12-inches o.c. in locations as directed by Balancing Agency.
- C. Use snap-in plugs for low and medium pressure systems, with material gauges of 14 through 26.
- D. Use instrument test holes for HEPS filter casings, high pressure and Class 1 systems, and all other low and medium pressure systems.
- E. Reinstall cut away insulation and cover with 4-inch-wide duct tape. Identify plug and instrument hole locations on insulate ducts as “test holes” for future reference and use.
- F. Provide openings in ductwork where required to accommodate thermometers and controllers. Provide pitot tube openings where required for testing of systems.
- G. Plugs: Low density polyethylene, snap-in type for 3/8-inch hole.
- H. Test Holes: Instrument test holes, sized to suit insulation thickness with flat gasket, screw cap and connection hardware in material to suit ductwork. Use concave gaskets for round duct.
- I. Where it is necessary for pipes, hangers, conduits or other devices to penetrate ductwork, obtain engineer’s acceptance of the location. Provide an airfoil of the proper design and increase duct size as required to satisfy each individual condition. Provide gaskets, flanges and apply sealant to make opening airtight.

END OF SECTION

SECTION 233346 - FLEXIBLE DUCTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

- 1. Insulated flexible ducts.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Sustainable Design Submittals:
- C. Shop Drawings: For flexible ducts.
 - 1. Include plans showing locations and mounting and attachment details.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which ceiling-mounted access panels and access doors required for access to duct accessories are shown and coordinated with each other, using input from installers of the items involved.

PART 2 - PRODUCTS

2.1 ASSEMBLY DESCRIPTION

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

- C. Comply with the Air Diffusion Council's "ADC Flexible Air Duct Test Code FD 72-R1."
- D. Comply with ASTM E96/E96M, "Test Methods for Water Vapor Transmission of Materials."

2.2 INSULATED FLEXIBLE DUCTS

- A. Insulated, Flexible Duct: UL 181, Class 1, black polymer film supported by helically wound, spring-steel wire; fibrous-glass insulation; polyethylene vapor-barrier film.
 - 1. Pressure Rating: 4-inch wg positive and 0.5-inch wg negative.
 - 2. Maximum Air Velocity: 4000 fpm.
 - 3. Temperature Range: Minus 20 to plus 175 deg F.
 - 4. Insulation R-Value: R-8.

2.3 FLEXIBLE DUCT CONNECTORS

- A. Clamps: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action in sizes 3 through 18 inches, to suit duct size.
- B. Non-Clamp Connectors: Liquid adhesive plus tape.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install flexible ducts according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.
- B. Install in indoor applications only. Flexible ductwork should not be exposed to UV lighting.
- C. Install duct test holes where required for testing and balancing purposes.
- D. Installation:
 - 1. Install ducts fully extended.
 - 2. Do not bend ducts across sharp corners.
 - 3. Bends of flexible ducting shall not exceed a minimum of one duct diameter.
 - 4. Avoid contact with metal fixtures, water lines, pipes, or conduits.
 - 5. Install flexible ducts in a direct line, without sags, twists, or turns.
- E. Supporting Flexible Ducts:
 - 1. Suspend flexible ducts with bands 1-1/2 inches wide or wider and spaced a maximum of 48 inches apart. Maximum centerline sag between supports shall not exceed 1/2 inch per 12 inches.
 - 2. Install extra supports at bends placed approximately one duct diameter from center line of the bend.

3. Ducts may rest on ceiling joists or truss supports. Spacing between supports shall not exceed the maximum spacing per manufacturer's written installation instructions.
4. Vertically installed ducts shall be stabilized by support straps at a maximum of 72 inches o.c.

END OF SECTION 233346

SECTION 23 37 00
AIR OUTLETS AND INLETS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes ceiling- mounted diffusers, registers, and grilles.
- B. Related Sections include the following:
 - 1. Division 10 Section "Louvers and Vents" for fixed and adjustable louvers and wall vents, whether or not they are connected to ducts.
 - 2. Division 23 Section "Duct Accessories" for fire and smoke dampers and volume-control dampers not integral to diffusers, registers, and grilles.

1.3 SUBMITTALS

- A. Product Data: For each product indicated, include the following:
 - 1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
 - 2. Diffuser, Register, and Grille Schedule: Indicate Drawing designation, room location, quantity, model number, size, and accessories furnished.
- B. Retain first paragraph and subparagraphs below if Drawings do not include detailed plans or if Project involves unusual coordination requirements.
- C. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:
 - 1. Ceiling suspension assembly members.
 - 2. Method of attaching hangers to building structure.
 - 3. Size and location of initial access modules for acoustical tile.
 - 4. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
 - 5. Duct access panels.
- D. Samples for Initial Selection: For diffusers, registers, and grilles with factory-applied color finishes.
- E. Samples for Verification: For diffusers, registers, and grilles, in manufacturer's standard sizes to verify color selected.
- F. All submittals shall be submitted in electronic (PDF) format with the exception of material and color samples.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, products specified.
 - 2. Products: Subject to compliance with requirements, provide one of the products specified.
 - 3. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, manufacturers specified.

4. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.2 GRILLES AND REGISTERS

A. Return Register:

1. Products:
 - a. Kreuger
 - b. Titus; Per Drawing Schedule
 - c. Anemostat, a Mestek Company.
 - d. METALAIRE, Inc., Metal Industries Inc.
 - e. Tuttle & Bailey.
 - f. Substitutions: Architect/Owner Approved Equal
2. Material: Aluminum.
3. Finish: Baked enamel, white.
4. Face Blade Arrangement: 0° Fixed horizontal spaced 3/4 inch apart.
5. Frame: 1-1/4 inches wide.
6. Mounting Frame: Plaster.
7. Mounting: Surface.
8. Damper Type: Adjustable opposed-blade assembly.
9. Accessories: Volume damper.

2.3 CEILING DIFFUSER OUTLETS

A. Rectangular and Square Ceiling Diffuser:

1. Products:
 - a. Kreuger
 - b. Titus; per schedule.
 - c. Anemostat, a Mestek Company.
 - d. METALAIRE, Inc., Metal Industries Inc
 - e. Tuttle & Bailey.
 - f. Substitutions: Architect/Owner Approved Equal
2. Material: Aluminum.
3. Finish: Baked enamel, white
4. Face Size: Per Schedule.
5. Face Style: Multi Vane
6. Mounting: Surface or to match ceiling.
7. Pattern: Adjustable.
8. Dampers: Opposed blade lever or key operated.
9. Accessories:
 - a. Equaling grid.
 - b. Sectorizing baffles.
 - c. Operating rod extension.

2.4 VARIABLE AIR VOLUME SUPPLY DIFFUSERS

- A. Variable air volume diffusers shall be AnemoTherm diffusers (or approved equal), Model ATHC (heating/cooling) plaque type ceiling diffuser. The diffuser size shall be nominal 24" x 24", with a minimum 18" square appearance panel. The horizontal air discharge pattern shall be 360° type.
- B. The diffusers shall be self-contained, and not require any external electrical or pneumatic connections. The damper shall consist of a spun, round aluminum disk that moves to change the effective free area of the diffuser to modulate flow. The damper shall include a perimeter seal. Each VAV diffuser shall incorporate one or more thermo-powered sensing elements that modulate the diffuser damper in response to the room temperature as sensed by the induced flow across the sensing element(s). The setpoints shall be factory pre-set at 74° F, but shall be field adjustable from 72°-78° F.

- C. VAV diffusers shall consist of multiple thermo-powered sensors that monitor the supply air temperature and index the diffuser into the heating or cooling mode. With the supply air temperature less than 68° F, the diffuser shall enter the direct acting cooling mode, and shall modulate the diffuser damper in response to the cooling setpoint. With the supply air temperature greater than 78° F, the diffuser shall enter the reverse acting heating mode, and shall modulate the diffuser damper in response to the heating setpoint. Diffuser shall be true VAV for both heating and cooling modes, and shall have independently adjustable setpoints for heating and cooling.
- D. The diffusers shall be constructed of aluminum and shall be designed to integrate with the specified ceiling system type. The diffuser shall consist of a back pan and a removable, heavy gauge appearance panel attached to the back pan. Room temperature setpoint adjustments shall be made by removing the panel, and rotating the appropriate thermo-powered sensor(s). No tools shall be required.
- E. The appearance panel shall have aerodynamic, rigid, hemmed edges around the perimeter and shall be a single piece construction. The panel shall be flat, smooth, and shall be free of any welding or forming blemishes. Holes or plug buttons in the panel are not acceptable.
- F. Provide blank-off baffles to obtain 1-, 2-, or 3-way blow patterns as shown on drawings.

SOURCE QUALITY CONTROL

- A. Verification of Performance: Rate diffusers, registers, and grilles according to ASHRAE 70, "Method of Testing for Rating the Performance of Air Outlets and Inlets."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Coordination: Coordinate the location of grilles, registers and diffusers with other trades. Examine areas and conditions under which inlets and outlets are to be installed. Do not proceed with work until unsatisfactory conditions have been corrected.
 - 1. Examine architectural floor plans, reflected ceiling plans and elevations and arrange for duct taps to be so placed that the installation of air outlets will present a uniform relationship with architectural features, lighting, sprinkler heads, speakers and smoke detectors.
 - 2. Adjust the face and rear bars of supply registers to provide a diffusion pattern such that the terminal velocity point is approximately 70 percent of the "room" width and 5 to 6 feet above the finished floor, at a velocity of 20 to 50 fpm.
 - 3. On projects with reflected ceiling plans, locate outlets to conform to that plan.
- B. Examine areas where diffusers, registers, and grilles are to be installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.

3.2 INSTALLATION

- A. Install diffusers, registers, and grilles level and plumb.
- B. Ceiling-Mounted Outlets and Inlets: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practicable. For units installed in lay-in ceiling panels, locate units in the center of panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.
- C. Install diffusers, registers, and grilles with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

3.3 ADJUSTING

- A. After installation, adjust diffusers, registers, and grilles to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION

SECTION 26 05 00
COMMON WORK RESULTS FOR ELECTRICAL

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Sleeves for raceways and cables.
 - 2. Sleeve seals.
 - 3. Grout.
 - 4. Common electrical installation requirements.

1.2 DEFINITIONS

- A. EPDM: Ethylene-propylene-diene terpolymer rubber.

1.3 SUBMITTALS

- A. Product Data: For sleeve seals.

1.4 COORDINATION

- A. Coordinate arrangement, mounting, and support of electrical equipment:
 - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.
 - 2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
 - 3. To allow right of way for piping and conduit installed at required slope.
 - 4. So, connecting raceways, cables, wire ways, cable trays, and busways will be clear of obstructions and of the working and access space of other equipment.
- B. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.
- C. Coordinate location of access panels and doors for electrical items that are behind finished surfaces or otherwise concealed. Access doors and panels are specified in Division 08 Section "Access Doors and Frames."
- D. Coordinate sleeve selection and application with selection and application of fire stopping specified in Division 07 Section "Penetration Fire stopping. “.”"

PART 2 - PRODUCTS

2.1 SLEEVES FOR RACEWAYS AND CABLES

- A. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- B. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- C. Sleeves for Rectangular Openings: Galvanized sheet steel.
 - 1. Minimum Metal Thickness:
 - a. For sleeve cross-section rectangle perimeter less than 50 inches and no side more than 16 inches, thickness shall be 0.052 inch
 - b. For sleeve cross-section rectangle perimeter equal to, or more than, 50 inches and 1 or more sides equal to, or more than, 16 inches, thickness shall be 0.138 inch

2.2 SLEEVE SEALS

- A. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and raceway or cable.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Metraflex Co.
 - d. Pipeline Seal and Insulator, Inc.
 - e. Substitutions: Architect/Owner Approved Equal
 - 2. Sealing Elements: EPDM interlocking links shaped to fit surface of cable or conduit. Include type and number required for material and size of raceway or cable.
 - 3. Pressure Plates: Stainless steel. Include two for each sealing element.
 - 4. Connecting Bolts and Nuts: Stainless steel of length required to secure pressure plates to sealing elements. Include one for each sealing element.

2.3 GROUT

- A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

PART 3 - EXECUTION

3.1 COMMON REQUIREMENTS FOR ELECTRICAL INSTALLATION

- A. Comply with NECA 1.
- B. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- C. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- D. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both electrical equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.
- E. Right of Way: Give to piping systems installed at a required slope.

3.2 SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Electrical penetrations occur when raceways, cables, wireways, cable trays, or busways penetrate concrete slabs, concrete or masonry walls, or fire-rated floor and wall assemblies.
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- D. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.
- E. Cut sleeves to length for mounting flush with both surfaces of walls.
- F. Extend sleeves installed in floors 2 inches above finished floor level.
- G. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and raceway or cable, unless indicated otherwise.
- H. Seal space outside of sleeves with grout for penetrations of concrete and masonry

1. Promptly pack grout solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect grout while curing.
 - I. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants."
 - J. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway and cable penetrations. Install sleeves and seal raceway and cable penetration sleeves with firestop materials. Comply with requirements in Division 07 Section "Penetration Firestopping."
 - K. Roof-Penetration Sleeves: Seal penetration of individual raceways and cables with flexible boot-type flashing units applied in coordination with roofing work.
 - L. Aboveground, Exterior-Wall Penetrations: Seal penetrations using steel pipe sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
 - M. Underground, Exterior-Wall Penetrations: Install cast-iron pipe sleeves. Size sleeves to allow for 1-inch annular clear space between raceway or cable and sleeve for installing mechanical sleeve seals.
- 3.3 SLEEVE-SEAL INSTALLATION
- A. Install to seal exterior wall penetrations.
 - B. Use type and number of sealing elements recommended by manufacturer for raceway or cable material and size. Position raceway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between raceway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.
- 3.4 FIRESTOPPING
- A. Apply firestopping to penetrations of fire-rated floor and wall assemblies for electrical installations to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 07 Section "Penetration Firestopping."

END OF SECTION

SECTION 260519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Copper building wire.
 - 2. Metal-clad cable, Type MC.
 - 3. Fire-alarm wire and cable.
 - 4. Connectors and splices.

1.3 DEFINITIONS

- A. PV: Photovoltaic.
- B. RoHS: Restriction of Hazardous Substances.
- C. VFC: Variable-frequency controller.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Sustainable Design Submittals:
- C. Product Schedule: Indicate type, use, location, and termination locations.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For manufacturer's authorized service representative.
- B. Field quality-control reports.

1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Member company of NETA.

1. Testing Agency's Field Supervisor: Certified by NETA to supervise on-site testing.

PART 2 - PRODUCTS

2.1 COPPER BUILDING WIRE

- A. Description: Flexible, insulated and uninsulated, drawn copper current-carrying conductor with an overall insulation layer or jacket, or both, rated 600 V or less.
- B. Standards:
 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
 2. RoHS compliant.
 3. Conductor and Cable Marking: Comply with wire and cable marking according to UL's "Wire and Cable Marking and Application Guide."
- C. Conductors: Copper, complying with ASTM B3 for bare annealed copper and with ASTM B8 for stranded conductors.
- D. Conductor Insulation:
 1. Type THHN and Type THWN-2: Comply with UL 83.
- E. Shield:
 1. Type TC-ER: Cable designed for use with VFCs, with oversized crosslinked polyethylene insulation, spiral-wrapped foil plus 85 percent coverage braided shields and insulated full-size ground wire and sunlight- and oil-resistant outer PVC jacket.

2.2 METAL-CLAD CABLE, TYPE MC

- A. Description: A factory assembly of one or more current-carrying insulated conductors in an overall metallic sheath.
- B. Standards:
 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
 2. Comply with UL 1569.
 3. RoHS compliant.
 4. Conductor and Cable Marking: Comply with wire and cable marking according to UL's "Wire and Cable Marking and Application Guide."
- C. Circuits:
 1. Single circuit and multicircuit with color-coded conductors.
 2. Power-Limited Fire-Alarm Circuits: Comply with UL 1424.

- D. Conductors: Copper, complying with ASTM B3 for bare annealed copper and with ASTM B8 for stranded conductors.
- E. Ground Conductor: Insulated.
- F. Conductor Insulation:
 - 1. Type TFN/THHN/THWN-2: Comply with UL 83.
- G. Armor: Steel or aluminum, interlocked.
- H. Jacket: PVC applied over armor.

2.3 FIRE-ALARM WIRE AND CABLE

- A. General Wire and Cable Requirements: NRTL listed and labeled as complying with NFPA 70, Article 760.
- B. Signaling Line Circuits: Twisted, shielded pair, size as recommended by system manufacturer.
 - 1. Circuit Integrity Cable: Twisted shielded pair, NFPA 70, Article 760, Classification CI, for power-limited fire-alarm signal service Type FPL. NRTL listed and labeled as complying with UL 1424 and UL 2196 for a two-hour rating.
- C. Non-Power-Limited Circuits: Solid-copper conductors with 600-V rated, 75 deg C, color-coded insulation, and complying with requirements in UL 2196 for a two-hour rating.
 - 1. Low-Voltage Circuits: No. 16 AWG, minimum, in pathway.
 - 2. Line-Voltage Circuits: No. 12 AWG, minimum, in pathway.
 - 3. Multiconductor Armored Cable: NFPA 70, Type MC, copper conductors, Type TFN/THHN conductor insulation, copper drain wire, copper armor with outer jacket with red identifier stripe, NTRL listed for fire-alarm and cable tray installation, plenum rated.

2.4 CONNECTORS AND SPLICES

- A. Description: Factory-fabricated connectors, splices, and lugs of size, ampacity rating, material, type, and class for application and service indicated; listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
- B. Jacketed Cable Connectors: For steel and aluminum jacketed cables, zinc die-cast with set screws, designed to connect conductors specified in this Section.
- C. Lugs: One piece, seamless, designed to terminate conductors specified in this Section.
 - 1. Material: Copper.
 - 2. Termination: Compression.

PART 3 - EXECUTION

3.1 CONDUCTOR MATERIAL APPLICATIONS

A. Feeders:

1. Copper; solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
2. Copper for feeders smaller than No. 4 AWG; copper or aluminum for feeders No. 4 AWG and larger. Conductors shall be solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.

B. Branch Circuits:

1. Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
2. Copper. Solid for No. 12 AWG and smaller; stranded for No. 10 AWG and larger.

C. Power-Limited Fire Alarm and Control: Solid for No. 12 AWG and smaller.

3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

A. Exposed Feeders: Type THHN/THWN-2, single conductors in raceway.

B. Feeders Concealed in Ceilings, Walls, Partitions, and Crawlspace: Type THHN/THWN-2, single conductors in raceway or Metal-clad cable, Type MC.

C. Exposed Branch Circuits, Including in Crawlspace: Type THHN/THWN-2, single conductors in raceway.

D. Branch Circuits Concealed in Ceilings, Walls, and Partitions: Type THHN/THWN-2, single conductors in raceway or Metal-clad cable, Type MC.

E. Cord Drops and Portable Appliance Connections: Type SO, hard service cord with stainless steel, wire-mesh, strain relief device at terminations to suit application.

3.3 INSTALLATION, GENERAL

A. Conceal cables in finished walls, ceilings, and floors unless otherwise indicated.

B. Complete raceway installation between conductor and cable termination points according to Section 260533 "Raceways and Boxes for Electrical Systems" prior to pulling conductors and cables.

C. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.

D. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.

- E. Install exposed cables parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- F. Support cables according to Section 260529 "Hangers and Supports for Electrical Systems."
- G. Complete cable tray systems installation according to Section 260536 "Cable Trays for Electrical Systems" prior to installing conductors and cables.

3.4 INSTALLATION OF FIRE-ALARM WIRE AND CABLE

- A. Comply with NECA 1 and NFPA 72.
- B. Wiring Method: Install wiring in metal pathway according to Section 270528.29 "Hangers and Supports for Communications Systems."
 - 1. Install plenum cable in environmental airspaces, including plenum ceilings.
 - 2. Fire-alarm circuits and equipment control wiring associated with fire-alarm system shall be installed in a dedicated pathway system.
 - a. Cables and pathways used for fire-alarm circuits, and equipment control wiring associated with fire-alarm system, may not contain any other wire or cable.
 - 3. Fire-Rated Cables: Use of two-hour, fire-rated fire-alarm cables, NFPA 70, Types MI and CI, is permitted.
 - 4. Signaling Line Circuits: Power-limited fire-alarm cables shall not be installed in the same cable or pathway as signaling line circuits.
- C. Wiring within Enclosures: Separate power-limited and non-power-limited conductors as recommended by manufacturer. Install conductors parallel with or at right angles to sides and back of the enclosure. Bundle, lace, and train conductors to terminal points with no excess. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with fire-alarm system to terminal blocks. Mark each terminal according to system's wiring diagrams. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.
- D. Cable Taps: Use numbered terminal strips in junction, pull, and outlet boxes; cabinets; or equipment enclosures where circuit connections are made.
- E. Color-Coding: Color-code fire-alarm conductors differently from the normal building power wiring. Use one color-code for alarm circuit wiring and another for supervisory circuits. Color-code audible alarm-indicating circuits differently from alarm-initiating circuits. Use different colors for visible alarm-indicating devices. Paint fire-alarm system junction boxes and covers red.
- F. Risers: Install at least two vertical cable risers to serve the fire-alarm system. Separate risers in close proximity to each other with a minimum one-hour-rated wall, so the loss of one riser does not prevent receipt or transmission of signals from other floors or zones.

- G. Wiring to Remote Alarm Transmitting Device: 1-inch conduit between the fire-alarm control panel and the transmitter. Install number of conductors and electrical supervision for connecting wiring as needed to suit monitoring function.

3.5 CONNECTIONS

- A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.
- B. Make splices, terminations, and taps that are compatible with conductor material.
 - 1. Use oxide inhibitor in each splice, termination, and tap for aluminum conductors.
- C. Wiring at Outlets: Install conductor at each outlet, with at least 6 inches of slack.

3.6 IDENTIFICATION

- A. Identify and color-code conductors and cables according to Section 260553 "Identification for Electrical Systems."
- B. Identify each spare conductor at each end with identity number and location of other end of conductor, and identify as spare conductor.

3.7 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

3.8 FIRESTOPPING

- A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Section 078413 "Penetration Firestopping."

3.9 FIELD QUALITY CONTROL

- A. Administrant for Tests and Inspections:
 - 1. Owner will engage qualified testing agency to administer and perform tests and inspections.
 - 2. Engage qualified testing agency to administer and perform tests and inspections.
 - 3. Engage factory-authorized service representative to administer and perform tests and inspections on components, assemblies, and equipment installations, including connections.
 - 4. Administer and perform tests and inspections.

B. Tests and Inspections:

1. After installing conductors and cables and before electrical circuitry has been energized, test service entrance and feeder conductors for compliance with requirements.
2. Perform each of the following visual and electrical tests:
 - a. Inspect exposed sections of conductor and cable for physical damage and correct connection according to the single-line diagram.
 - b. Test bolted connections for high resistance using one of the following:
 - 1) A low-resistance ohmmeter.
 - 2) Calibrated torque wrench.
 - 3) Thermographic survey.
 - c. Inspect compression-applied connectors for correct cable match and indentation.
 - d. Inspect for correct identification.
 - e. Inspect cable jacket and condition.
 - f. Insulation-resistance test on each conductor for ground and adjacent conductors. Apply a potential of 500-V dc for 300-V rated cable and 1000-V dc for 600-V rated cable for a one-minute duration.
 - g. Continuity test on each conductor and cable.
 - h. Uniform resistance of parallel conductors.
3. Initial Infrared Scanning: After Substantial Completion, but before Final Acceptance, perform an infrared scan of each splice in conductors No. 3 AWG and larger. Remove box and equipment covers so splices are accessible to portable scanner. Correct deficiencies determined during the scan.
 - a. Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
 - b. Record of Infrared Scanning: Prepare a certified report that identifies switches checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.
4. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each switch 11 months after date of Substantial Completion.

C. Cables will be considered defective if they do not pass tests and inspections.

D. Prepare test and inspection reports to record the following:

1. Procedures used.
2. Results that comply with requirements.
3. Results that do not comply with requirements, and corrective action taken to achieve compliance with requirements.

END OF SECTION 260519

SECTION 260526 - GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes grounding and bonding systems and equipment.
- B. Section includes grounding and bonding systems and equipment.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Sustainable Design Submittals:

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Plans showing dimensioned locations of grounding features specified in "Field Quality Control" Article, including the following:
 - 1. Test wells.
 - 2. Ground rods.
 - 3. Ground rings.
 - 4. Grounding arrangements and connections for separately derived systems.
- B. Qualification Data: For testing agency and testing agency's field supervisor.
- C. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For grounding to include in emergency, operation, and maintenance manuals.
 - 1. Include the following:
 - a. Plans showing as-built, dimensioned locations of system described in "Field Quality Control" Article, including the following:

- 1) Test wells.
- 2) Ground rods.
- 3) Ground rings.
- 4) Grounding arrangements and connections for separately derived systems.

1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Certified by NETA.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with UL 467 for grounding and bonding materials and equipment.

2.2 MANUFACTURERS

2.3 CONDUCTORS

- A. Insulated Conductors: Copper wire or cable insulated for 600 V unless otherwise required by applicable Code or authorities having jurisdiction.
- B. Bare Copper Conductors:
 1. Solid Conductors: ASTM B3.
 2. Stranded Conductors: ASTM B8.
 3. Tinned Conductors: ASTM B33.
 4. Bonding Cable: 28 kcmil, 14 strands of No. 17 AWG conductor, 1/4 inch in diameter.
 5. Bonding Conductor: No. 4 or No. 6 AWG, stranded conductor.
 6. Bonding Jumper: Copper tape, braided conductors terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.
 7. Tinned Bonding Jumper: Tinned-copper tape, braided conductors terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.
- C. Grounding Bus: Predrilled rectangular bars of annealed copper, 1/4 by 4 inches in cross section, with 9/32-inch holes spaced 1-1/8 inches apart. Stand-off insulators for mounting shall comply with UL 891 for use in switchboards, 600 V and shall be Lexan or PVC, impulse tested at 5000 V.

2.4 CONNECTORS

- A. Listed and labeled by an NRTL acceptable to authorities having jurisdiction for applications in which used and for specific types, sizes, and combinations of conductors and other items connected.
- B. Welded Connectors: Exothermic-welding kits of types recommended by kit manufacturer for materials being joined and installation conditions.
- C. Bus-Bar Connectors: Mechanical type, cast silicon bronze, solderless compression-type wire terminals, and long-barrel, two-bolt connection to ground bus bar.
- D. Bus-Bar Connectors: Compression type, copper or copper alloy, with two wire terminals.
- E. Beam Clamps: Mechanical type, terminal, ground wire access from four directions, with dual, tin-plated or silicon bronze bolts.
- F. Cable-to-Cable Connectors: Compression type, copper or copper alloy.
- G. Cable Tray Ground Clamp: Mechanical type, zinc-plated malleable iron.
- H. Conduit Hubs: Mechanical type, terminal with threaded hub.
- I. Ground Rod Clamps: Mechanical type, copper or copper alloy, terminal with hex head bolt.
- J. Lay-in Lug Connector: Mechanical type, copper rated for direct burial terminal with set screw.
- K. Service Post Connectors: Mechanical type, bronze alloy terminal, in short- and long-stud lengths, capable of single and double conductor connections.
- L. Signal Reference Grid Clamp: Mechanical type, stamped-steel terminal with hex head screw.
- M. Straps: Solid copper, Rated for 600 A.
- N. Tower Ground Clamps: Mechanical type, copper or copper alloy, terminal two-piece clamp.
- O. U-Bolt Clamps: Mechanical type, copper or copper alloy, terminal listed for direct burial.
- P. Water Pipe Clamps:
 - 1. Mechanical type, two pieces with stainless-steel bolts.
 - a. Material: Tin-plated aluminum.
 - b. Listed for direct burial.
 - 2. U-bolt type with malleable-iron clamp and copper ground connector.

2.5 GROUNDING ELECTRODES

- A. Ground Rods: Copper-clad steel, sectional type; 3/4 inch by 10 feet.

- B. Chemical-Enhanced Grounding Electrodes: Copper tube, straight or L-shaped, charged with nonhazardous electrolytic chemical salts.
 - 1. Termination: Factory-attached No. 4/0 AWG bare conductor at least 48 inches long.
 - 2. Backfill Material: Electrode manufacturer's recommended material.
- C. Ground Plates: 1/4 inch thick, hot-dip galvanized.

PART 3 - EXECUTION

3.1 APPLICATIONS

- A. Conductors: Install solid conductor for No. 8 AWG and smaller, and stranded conductors for No. 6 AWG and larger unless otherwise indicated.
- B. Underground Grounding Conductors: Install bare copper conductor, No. 2/0 AWG minimum.
 - 1. Bury at least 30 inches below grade.
 - 2. Duct-Bank Grounding Conductor: Bury 12 inches above duct bank when indicated as part of duct-bank installation.
- C. Grounding Conductors: Green-colored insulation with continuous yellow stripe.
- D. Isolated Grounding Conductors: Green-colored insulation with more than one continuous yellow stripe. On feeders with isolated ground, identify grounding conductor where visible to normal inspection, with alternating bands of green and yellow tape, with at least three bands of green and two bands of yellow.
- E. Grounding Bus: Install in electrical equipment rooms, in rooms housing service equipment, and elsewhere as indicated.
 - 1. Install bus horizontally, on insulated spacers 2 inches minimum from wall, 6 inches above finished floor unless otherwise indicated.
 - 2. Where indicated on both sides of doorways, route bus up to top of door frame, across top of doorway, and down; connect to horizontal bus.
- F. Conductor Terminations and Connections:
 - 1. Pipe and Equipment Grounding Conductor Terminations: Bolted connectors.
 - 2. Underground Connections: Welded connectors except at test wells and as otherwise indicated.
 - 3. Connections to Ground Rods at Test Wells: Bolted connectors.
 - 4. Connections to Structural Steel: Welded connectors.

3.2 EQUIPMENT GROUNDING

- A. Install insulated equipment grounding conductors with all feeders and branch circuits.

- B. Install insulated equipment grounding conductors with the following items, in addition to those required by NFPA 70:
 - 1. Feeders and branch circuits.
 - 2. Lighting circuits.
 - 3. Receptacle circuits.
 - 4. Single-phase motor and appliance branch circuits.
 - 5. Three-phase motor and appliance branch circuits.
 - 6. Flexible raceway runs.
 - 7. Armored and metal-clad cable runs.
 - 8. Busway Supply Circuits: Install insulated equipment grounding conductor from grounding bus in the switchgear, switchboard, or distribution panel to equipment grounding bar terminal on busway.
 - 9. X-Ray Equipment Circuits: Install insulated equipment grounding conductor in circuits supplying x-ray equipment.

- C. Air-Duct Equipment Circuits: Install insulated equipment grounding conductor to duct-mounted electrical devices operating at 120 V and more, including air cleaners, heaters, dampers, humidifiers, and other duct electrical equipment. Bond conductor to each unit and to air duct and connected metallic piping.

- D. Water Heater, Heat-Tracing, and Antifrost Heating Cables: Install a separate insulated equipment grounding conductor to each electric water heater and heat-tracing cable. Bond conductor to heater units, piping, connected equipment, and components.

- E. Isolated Grounding Receptacle Circuits: Install an insulated equipment grounding conductor connected to the receptacle grounding terminal. Isolate conductor from raceway and from panelboard grounding terminals. Terminate at equipment grounding conductor terminal of the applicable derived system or service unless otherwise indicated.

- F. Isolated Equipment Enclosure Circuits: For designated equipment supplied by a branch circuit or feeder, isolate equipment enclosure from supply circuit raceway with a nonmetallic raceway fitting listed for the purpose. Install fitting where raceway enters enclosure, and install a separate insulated equipment grounding conductor. Isolate conductor from raceway and from panelboard grounding terminals. Terminate at equipment grounding conductor terminal of the applicable derived system or service unless otherwise indicated.

- G. Poles Supporting Outdoor Lighting Fixtures: Install grounding electrode and a separate insulated equipment grounding conductor in addition to grounding conductor installed with branch-circuit conductors.

3.3 INSTALLATION

- A. Grounding Conductors: Route along shortest and straightest paths possible unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.

- B. Ground Bonding Common with Lightning Protection System: Comply with NFPA 780 and UL 96 when interconnecting with lightning protection system. Bond electrical power system ground directly to lightning protection system grounding conductor at closest point to electrical

service grounding electrode. Use bonding conductor sized same as system grounding electrode conductor, and install in conduit.

- C. Ground Rods: Drive rods until tops are 2 inches below finished floor or final grade unless otherwise indicated.
 - 1. Interconnect ground rods with grounding electrode conductor below grade and as otherwise indicated. Make connections without exposing steel or damaging coating if any.
 - 2. Use exothermic welds for all below-grade connections.
 - 3. For grounding electrode system, install at least three rods spaced at least one-rod length from each other and located at least the same distance from other grounding electrodes, and connect to the service grounding electrode conductor.

- D. Test Wells: Ground rod driven through drilled hole in bottom of handhole. Handholes are specified in Section 260543 "Underground Ducts and Raceways for Electrical Systems," and shall be at least 12 inches deep, with cover.
 - 1. Install at least one test well for each service unless otherwise indicated. Install at the ground rod electrically closest to service entrance. Set top of test well flush with finished grade or floor.

- E. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance except where routed through short lengths of conduit.
 - 1. Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate any adjacent parts.
 - 2. Bonding to Equipment Mounted on Vibration Isolation Hangers and Supports: Install bonding so vibration is not transmitted to rigidly mounted equipment.
 - 3. Use exothermic-welded connectors for outdoor locations; if a disconnect-type connection is required, use a bolted clamp.

- F. Grounding and Bonding for Piping:
 - 1. Metal Water Service Pipe: Install insulated copper grounding conductors, in conduit, from building's main service equipment, or grounding bus, to main metal water service entrances to building. Connect grounding conductors to main metal water service pipes; use a bolted clamp connector or bolt a lug-type connector to a pipe flange by using one of the lug bolts of the flange. Where a dielectric main water fitting is installed, connect grounding conductor on street side of fitting. Bond metal grounding conductor conduit or sleeve to conductor at each end.
 - 2. Water Meter Piping: Use braided-type bonding jumpers to electrically bypass water meters. Connect to pipe with a bolted connector.
 - 3. Bond each aboveground portion of gas piping system downstream from equipment shutoff valve.

- G. Bonding Interior Metal Ducts: Bond metal air ducts to equipment grounding conductors of associated fans, blowers, electric heaters, and air cleaners. Install tinned bonding jumper to bond across flexible duct connections to achieve continuity.

- H. Grounding for Steel Building Structure: Install a driven ground rod at base of each corner column and at intermediate exterior columns at distances not more than 60 feet apart.
- I. Connections: Make connections so possibility of galvanic action or electrolysis is minimized. Select connectors, connection hardware, conductors, and connection methods so metals in direct contact are galvanically compatible.
 - 1. Use electroplated or hot-tin-coated materials to ensure high conductivity and to make contact points closer in order of galvanic series.
 - 2. Make connections with clean, bare metal at points of contact.
 - 3. Make aluminum-to-steel connections with stainless-steel separators and mechanical clamps.
 - 4. Make aluminum-to-galvanized-steel connections with tin-plated copper jumpers and mechanical clamps.
 - 5. Coat and seal connections having dissimilar metals with inert material to prevent future penetration of moisture to contact surfaces.

3.4 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- C. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- D. Perform tests and inspections.
- E. Tests and Inspections:
 - 1. After installing grounding system but before permanent electrical circuits have been energized, test for compliance with requirements.
 - 2. Inspect physical and mechanical condition. Verify tightness of accessible, bolted, electrical connections with a calibrated torque wrench according to manufacturer's written instructions.
 - 3. Test completed grounding system at each location where a maximum ground-resistance level is specified, at service disconnect enclosure grounding terminal, at ground test wells, and at individual ground rods. Make tests at ground rods before any conductors are connected.
 - a. Measure ground resistance no fewer than two full days after last trace of precipitation and without soil being moistened by any means other than natural drainage or seepage and without chemical treatment or other artificial means of reducing natural ground resistance.
 - b. Perform tests by fall-of-potential method according to IEEE 81.
 - 4. Prepare dimensioned Drawings locating each test well, ground rod and ground-rod assembly, and other grounding electrodes. Identify each by letter in alphabetical order, and key to the record of tests and observations. Include the number of rods driven and

their depth at each location, and include observations of weather and other phenomena that may affect test results. Describe measures taken to improve test results.

- F. Grounding system will be considered defective if it does not pass tests and inspections.
- G. Prepare test and inspection reports.
- H. Report measured ground resistances that exceed the following values:
 - 1. Power and Lighting Equipment or System with Capacity of 500 kVA and Less: 10 ohms.
 - 2. Power and Lighting Equipment or System with Capacity of 500 to 1000 kVA: 5 ohms.
 - 3. Power and Lighting Equipment or System with Capacity More Than 1000 kVA: 3 ohms.
 - 4. Power Distribution Units or Panelboards Serving Electronic Equipment: 3 ohm(s).
 - 5. Substations and Pad-Mounted Equipment: 5 ohms.
 - 6. Manhole Grounds: 10 ohms.
- I. Excessive Ground Resistance: If resistance to ground exceeds specified values, notify Architect promptly and include recommendations to reduce ground resistance.

END OF SECTION 260526

SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Steel slotted support systems.
2. Aluminum slotted support systems.
3. Nonmetallic slotted support systems.
4. Conduit and cable support devices.
5. Support for conductors in vertical conduit.
6. Structural steel for fabricated supports and restraints.
7. Mounting, anchoring, and attachment components, including powder-actuated fasteners, mechanical expansion anchors, concrete inserts, clamps, through bolts, toggle bolts, and hanger rods.
8. Fabricated metal equipment support assemblies.

- B. Related Requirements:

1. Section 260548.16 "Seismic Controls for Electrical Systems" for products and installation requirements necessary for compliance with seismic criteria.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for the following:
 - a. Slotted support systems, hardware, and accessories.
 - b. Clamps.
 - c. Hangers.
 - d. Sockets.
 - e. Eye nuts.
 - f. Fasteners.
 - g. Anchors.
 - h. Saddles.
 - i. Brackets.

2. Include rated capacities and furnished specialties and accessories.
- B. Shop Drawings: For fabrication and installation details for electrical hangers and support systems.
1. Hangers. Include product data for components.
 2. Slotted support systems.
 3. Equipment supports.
 4. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.
- C. Delegated-Design Submittal: For hangers and supports for electrical systems.
1. Include design calculations and details of hangers.
 2. Include design calculations for seismic restraints.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plan(s) and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
1. Suspended ceiling components.
 2. Ductwork, piping, fittings, and supports.
 3. Structural members to which hangers and supports will be attached.
 4. Size and location of initial access modules for acoustical tile.
 5. Items penetrating finished ceiling, including the following:
 - a. Luminaires.
 - b. Air outlets and inlets.
 - c. Speakers.
 - d. Sprinklers.
 - e. Access panels.
 - f. Projectors.
- B. Seismic Qualification Data: Certificates, for hangers and supports for electrical equipment and systems, accessories, and components, from manufacturer.
1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- C. Welding certificates.

1.5 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M.
- B. Welding Qualifications: Qualify procedures and personnel according to the following:
 - 1. AWS D1.1/D1.1M.
 - 2. AWS D1.2/D1.2M.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design hanger and support system.
- B. Seismic Performance: Hangers and supports shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
- C. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame Rating: Class 1.
 - 2. Self-extinguishing according to ASTM D635.

2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Steel Slotted Support Systems: Preformed steel channels and angles with minimum 13/32-inch-diameter holes at a maximum of 8 inches o.c. in at least one surface.
 - 1. Standard: Comply with MFMA-4 factory-fabricated components for field assembly.
 - 2. Material for Channel, Fittings, and Accessories: Galvanized steel
 - 3. Channel Width: Selected for applicable load criteria.
 - 4. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
 - 5. Nonmetallic Coatings: Manufacturer's standard PVC, polyurethane, or polyester coating applied according to MFMA-4.
 - 6. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
 - 7. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Aluminum Slotted Support Systems: Extruded-aluminum channels and angles with minimum 13/32-inch-diameter holes at a maximum of 8 inches o.c. in at least one surface.
 - 1. Standard: Comply with MFMA-4 factory-fabricated components for field assembly.
 - 2. Channel Material: 6063-T5 aluminum alloy.
 - 3. Fittings and Accessories Material: 5052-H32 aluminum alloy.
 - 4. Channel Width: Selected for applicable load criteria

5. Nonmetallic Coatings: Manufacturer's standard PVC, polyurethane, or polyester coating applied according to MFMA-4.
 6. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
 7. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Nonmetallic Slotted Support Systems: Structural-grade, factory-formed, glass-fiber-resin channels and angles with minimum 13/32-inch- diameter holes at a maximum of 8 inches o.c., in at least one surface.
1. Standard: Comply with MFMA-4 factory-fabricated components for field assembly.
 2. Channel Width: Selected for applicable load criteria.
 3. Fittings and Accessories: Products provided by channel and angle manufacturer and designed for use with those items.
 4. Fitting and Accessory Materials: Same as those for channels and angles, except metal items may be stainless steel.
 5. Rated Strength: Selected to suit applicable load criteria.
 6. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- D. Conduit and Cable Support Devices: Stainless-steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- E. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for nonarmored electrical conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body shall be made of malleable iron.
- F. Structural Steel for Fabricated Supports and Restraints: ASTM A36/A36M steel plates, shapes, and bars; black and galvanized.
- G. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
1. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 2. Mechanical-Expansion Anchors: Insert-wedge-type, stainless steel, for use in hardened portland cement concrete, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 3. Concrete Inserts: Steel or malleable-iron, slotted support system units are similar to MSS Type 18 units and comply with MFMA-4 or MSS SP-58.
 4. Clamps for Attachment to Steel Structural Elements: MSS SP-58 units are suitable for attached structural element.
 5. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM F3125/F3125M, Grade A325.
 6. Toggle Bolts: Stainless-steel springhead type.
 7. Hanger Rods: Threaded steel.

2.3 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

- A. Description: Welded or bolted structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.
- B. Materials: Comply with requirements in Section 055000 "Metal Fabrications" for steel shapes and plates.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with the following standards for application and installation requirements of hangers and supports, except where requirements on Drawings or in this Section are stricter:
 - 1. NECA 1.
 - 2. NECA 101
 - 3. NECA 102.
 - 4. NECA 105.
 - 5. NECA 111.
- B. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping materials and installation for penetrations through fire-rated walls, ceilings, and assemblies.
- C. Comply with requirements for raceways and boxes specified in Section 260533 "Raceways and Boxes for Electrical Systems."
- D. Maximum Support Spacing and Minimum Hanger Rod Size for Raceways: Space supports for EMT, IMC, and RMC as required by NFPA 70. Minimum rod size shall be 1/4 inch in diameter.
- E. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted or other support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
 - 1. Secure raceways and cables to these supports with two-bolt conduit clamps.
- F. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1-1/2-inch and smaller raceways serving branch circuits and communication systems above suspended ceilings, and for fastening raceways to trapeze supports.

3.2 SUPPORT INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this article.
- B. Raceway Support Methods: In addition to methods described in NECA 1, EMT, IMC and RMC may be supported by openings through structure members, according to NFPA 70.

- C. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.
- D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
 - 1. To Wood: Fasten with lag screws or through bolts.
 - 2. To New Concrete: Bolt to concrete inserts.
 - 3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
 - 4. To Existing Concrete: Expansion anchor fasteners.
 - 5. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inches thick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inches thick.
 - 6. To Steel: Welded threaded studs complying with AWS D1.1/D1.1M, with lock washers and nuts.
 - 7. To Light Steel: Sheet metal screws.
 - 8. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate by means that comply with seismic-restraint strength and anchorage requirements.
- E. Drill holes for expansion anchors in concrete at locations and to depths that avoid the need for reinforcing bars.

3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Comply with installation requirements in Section 055000 "Metal Fabrications" for site-fabricated metal supports.
- B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
- C. Field Welding: Comply with AWS D1.1/D1.1M.

3.4 CONCRETE BASES

- A. Construct concrete bases of dimensions indicated, but not less than 4 inches larger in both directions than supported unit, and so anchors will be a minimum of 10 bolt diameters from edge of the base.
- B. Use 3000 psi, 28-day compressive-strength concrete.
- C. Anchor equipment to concrete base as follows:

1. Place and secure anchorage devices. Use supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
2. Install anchor bolts to elevations required for proper attachment to supported equipment.
3. Install anchor bolts according to anchor-bolt manufacturer's written instructions.

3.5 PAINTING

- A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A780.

END OF SECTION 260529

SECTION 260533 - RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Metal conduits and fittings.
 - 2. Nonmetallic conduits and fittings.
 - 3. Metal wireways and auxiliary gutters.
 - 4. Surface raceways.
 - 5. Boxes, enclosures, and cabinets.

1.3 DEFINITIONS

- A. ARC: Aluminum rigid conduit.
- B. GRC: Galvanized rigid steel conduit.
- C. IMC: Intermediate metal conduit.

1.4 ACTION SUBMITTALS

- A. Product Data: For surface raceways, wireways and fittings, floor boxes, hinged-cover enclosures, and cabinets.
- B. Sustainable Design Submittals:
- C. Shop Drawings: For custom enclosures and cabinets. Include plans, elevations, sections, and attachment details.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Conduit routing plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of items involved:
 - 1. Structural members in paths of conduit groups with common supports.
 - 2. HVAC and plumbing items and architectural features in paths of conduit groups with common supports.

- B. Qualification Data: For professional engineer.
- C. Seismic Qualification Data: Certificates, for enclosures, cabinets, and conduit racks and their mounting provisions, including those for internal components, from manufacturer.
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
 - 4. Detailed description of conduit support devices and interconnections on which the certification is based and their installation requirements.
- D. Source quality-control reports.

PART 2 - PRODUCTS

2.1 METAL CONDUITS AND FITTINGS

- A. Metal Conduit:
 - 1. Listing and Labeling: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. GRC: Comply with ANSI C80.1 and UL 6.
 - 3. ARC: Comply with ANSI C80.5 and UL 6A.
 - 4. IMC: Comply with ANSI C80.6 and UL 1242.
 - 5. EMT: Comply with ANSI C80.3 and UL 797.
 - 6. FMC: Comply with UL 1; zinc-coated steel or aluminum.
 - 7. LFMC: Flexible steel conduit with PVC jacket and complying with UL 360.
- B. Metal Fittings:
 - 1. Comply with NEMA FB 1 and UL 514B.
 - 2. Listing and Labeling: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 3. Fittings, General: Listed and labeled for type of conduit, location, and use.
 - 4. Conduit Fittings for Hazardous (Classified) Locations: Comply with UL 1203 and NFPA 70.
 - 5. Fittings for EMT:
 - a. Material: Steel or die-cast.
 - b. Type: Setscrew or compression.
 - 6. Expansion Fittings: PVC or steel to match conduit type, complying with UL 651, rated for environmental conditions where installed, and including flexible external bonding jumper.
 - 7. Coating for Fittings for PVC-Coated Conduit: Minimum thickness of 0.040 inch, with overlapping sleeves protecting threaded joints.

- C. Joint Compound for IMC, GRC, or ARC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

2.2 NONMETALLIC CONDUITS AND FITTINGS

A. Nonmetallic Conduit:

- 1. Listing and Labeling: Nonmetallic conduit shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- 2. Fiberglass:
 - a. Comply with NEMA TC 14.
 - b. Comply with UL 2515 for aboveground raceways.
 - c. Comply with UL 2420 for belowground raceways.
- 3. ENT: Comply with NEMA TC 13 and UL 1653.
- 4. RNC: Type EPC-40-PVC complying with NEMA TC 2 and UL 651 unless otherwise indicated.
- 5. LFNC: Comply with UL 1660.
- 6. Rigid HDPE: Comply with UL 651A.
- 7. Continuous HDPE: Comply with UL 651A.
- 8. Coilable HDPE: Preassembled with conductors or cables, and complying with ASTM D3485.
- 9. RTRC: Comply with UL 2515A and NEMA TC 14.

B. Nonmetallic Fittings:

- 1. Fittings, General: Listed and labeled for type of conduit, location, and use.
- 2. Fittings for ENT and RNC: Comply with NEMA TC 3; match to conduit or tubing type and material.
 - a. Fittings for LFNC: Comply with UL 514B.
- 3. Solvents and Adhesives: As recommended by conduit manufacturer.

2.3 METAL WIREWAYS AND AUXILIARY GUTTERS

- A. Description: Sheet metal, complying with UL 870 and NEMA 250, Type 1 unless otherwise indicated, and sized according to NFPA 70.
 - 1. Metal wireways installed outdoors shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Fittings and Accessories: Include covers, couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.
- C. Wireway Covers: Screw-cover type unless otherwise indicated.

- D. Finish: Manufacturer's standard enamel finish.

2.4 NONMETALLIC WIREWAYS AND AUXILIARY GUTTERS

- A. Listing and Labeling: Nonmetallic wireways and auxiliary gutters shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Description: Fiberglass polyester, extruded and fabricated to required size and shape, without holes or knockouts. Cover shall be gasketed with oil-resistant gasket material and fastened with captive screws treated for corrosion resistance. Connections shall be flanged and have stainless-steel screws and oil-resistant gaskets.
- C. Description: PVC, extruded and fabricated to required size and shape, and having snap-on cover, mechanically coupled connections, and plastic fasteners.
- D. Fittings and Accessories: Couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings shall match and mate with wireways as required for complete system.
- E. Solvents and Adhesives: As recommended by conduit manufacturer.

2.5 SURFACE RACEWAYS

- A. Listing and Labeling: Surface raceways and tele-power poles shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Surface Metal Raceways: Galvanized steel with snap-on covers complying with UL 5. Manufacturer's standard enamel finish.
- C. Surface Nonmetallic Raceways: Two- or three-piece construction, complying with UL 5A, and manufactured of rigid PVC with texture and color selected by Architect from manufacturer's standard colors. Product shall comply with UL 94 V-0 requirements for self-extinguishing characteristics.

2.6 BOXES, ENCLOSURES, AND CABINETS

- A. General Requirements for Boxes, Enclosures, and Cabinets: Boxes, enclosures, and cabinets installed in wet locations shall be listed for use in wet locations.
- B. Sheet Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- C. Cast-Metal Outlet and Device Boxes: Comply with NEMA FB 1, aluminum, Type FD, with gasketed cover.
- D. Nonmetallic Outlet and Device Boxes: Comply with NEMA OS 2 and UL 514C.
- E. Metal Floor Boxes:

1. Material: Cast metal or sheet metal.
 2. Type: Semi-adjustable.
 3. Shape: Rectangular.
 4. Listing and Labeling: Metal floor boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- F. Nonmetallic Floor Boxes: Nonadjustable, rectangular.
1. Listing and Labeling: Nonmetallic floor boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- G. Luminaire Outlet Boxes: Nonadjustable, designed for attachment of luminaire weighing 50 lb. Outlet boxes designed for attachment of luminaires weighing more than 50 lb shall be listed and marked for the maximum allowable weight.
- H. Paddle Fan Outlet Boxes: Nonadjustable, designed for attachment of paddle fan weighing 70 lb.
1. Listing and Labeling: Paddle fan outlet boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- I. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- J. Cast-Metal Access, Pull, and Junction Boxes: Comply with NEMA FB 1 and UL 1773, cast aluminum with gasketed cover.
- K. Box extensions used to accommodate new building finishes shall be of same material as recessed box.
- L. Device Box Dimensions: 4 inches square by 2-1/8 inches deep
- M. Hinged-Cover Enclosures: Comply with UL 50 and NEMA 250, Type 1 with continuous-hinge cover with flush latch unless otherwise indicated.
1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
 2. Nonmetallic Enclosures: Plastic.
 3. Interior Panels: Steel; all sides finished with manufacturer's standard enamel.
- N. Cabinets:
1. NEMA 250, Type 1 galvanized-steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel.
 2. Hinged door in front cover with flush latch and concealed hinge.
 3. Key latch to match panelboards.
 4. Metal barriers to separate wiring of different systems and voltage.
 5. Accessory feet where required for freestanding equipment.
 6. Nonmetallic cabinets shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

PART 3 - EXECUTION

3.1 RACEWAY APPLICATION

- A. Indoors: Apply raceway products as specified below unless otherwise indicated:
1. Exposed, Not Subject to Physical Damage: EMT
 2. Exposed, Not Subject to Severe Physical Damage: EMT
 3. Exposed and Subject to Severe Physical Damage: RMC Raceway locations include the following:
 - a. Loading dock.
 - b. Corridors used for traffic of mechanized carts, forklifts, and pallet-handling units.
 - c. Mechanical rooms.
 - d. Gymnasiums.
 4. Concealed in Ceilings and Interior Walls and Partitions: EMT
 5. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): FMC, except use LFMC in damp or wet locations.
 6. Damp or Wet Locations: IMC
 7. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4 stainless steel or nonmetallic in institutional and commercial kitchens and damp or wet locations.
- B. Minimum Raceway Size: 3/4-inch trade size.
- C. Raceway Fittings: Compatible with raceways and suitable for use and location.
1. Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings unless otherwise indicated. Comply with NEMA FB 2.10.
 2. PVC Externally Coated, Rigid Steel Conduits: Use only fittings listed for use with this type of conduit. Patch and seal all joints, nicks, and scrapes in PVC coating after installing conduits and fittings. Use sealant recommended by fitting manufacturer and apply in thickness and number of coats recommended by manufacturer.
 3. EMT: Use setscrew or compression fittings. Comply with NEMA FB 2.10.
 4. Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.
- D. Install nonferrous conduit or tubing for circuits operating above 60 Hz. Where aluminum raceways are installed for such circuits and pass through concrete, install in nonmetallic sleeve.
- E. Do not install aluminum conduits, boxes, or fittings in contact with concrete or earth.
- F. Install surface raceways only where indicated on Drawings.
- G. Do not install nonmetallic conduit where ambient temperature exceeds 120 deg F.

3.2 INSTALLATION

- A. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for hangers and supports.
- B. Comply with NECA 1 and NECA 101 for installation requirements except where requirements on Drawings or in this article are stricter. Comply with NECA 102 for aluminum conduits. Comply with NFPA 70 limitations for types of raceways allowed in specific occupancies and number of floors.
- C. Do not install raceways or electrical items on any "explosion-relief" walls or rotating equipment.
- D. Do not fasten conduits onto the bottom side of a metal deck roof.
- E. Keep raceways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.
- F. Complete raceway installation before starting conductor installation.
- G. Arrange stub-ups so curved portions of bends are not visible above finished slab.
- H. Install no more than the equivalent of three 90-degree bends in any conduit run except for control wiring conduits, for which fewer bends are allowed. Support within 12 inches of changes in direction.
- I. Make bends in raceway using large-radius preformed ells. Field bending shall be according to NFPA 70 minimum radii requirements. Use only equipment specifically designed for material and size involved.
- J. Conceal conduit within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
- K. Support conduit within 12 inches of enclosures to which attached.
- L. Raceways Embedded in Slabs:
 - 1. Run conduit larger than 1-inch trade size, parallel or at right angles to main reinforcement. Where at right angles to reinforcement, place conduit close to slab support. Secure raceways to reinforcement at maximum 10-foot intervals.
 - 2. Arrange raceways to cross building expansion joints at right angles with expansion fittings.
 - 3. Arrange raceways to keep a minimum of 2 inches of concrete cover in all directions.
 - 4. Do not embed threadless fittings in concrete unless specifically approved by Architect for each specific location.
- M. Stub-Ups to Above Recessed Ceilings:
 - 1. Use EMT, IMC, or RMC for raceways.
 - 2. Use a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.

- N. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.
- O. Coat field-cut threads on PVC-coated raceway with a corrosion-preventing conductive compound prior to assembly.
- P. Raceway Terminations at Locations Subject to Moisture or Vibration: Use insulating bushings to protect conductors including conductors smaller than No. 4 AWG.
- Q. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install bushings on conduits up to 1-1/4-inch trade size and insulated throat metal bushings on 1-1/2-inch trade size and larger conduits terminated with locknuts. Install insulated throat metal grounding bushings on service conduits.
- R. Install raceways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus 1/4 turn more.
- S. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure to assure a continuous ground path.
- T. Cut conduit perpendicular to the length. For conduits 2-inch trade size and larger, use roll cutter or a guide to make cut straight and perpendicular to the length.
- U. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb tensile strength. Leave at least 12 inches of slack at each end of pull wire. Cap underground raceways designated as spare above grade alongside raceways in use.
- V. Surface Raceways:
 - 1. Install surface raceway with a minimum 2-inch radius control at bend points.
 - 2. Secure surface raceway with screws or other anchor-type devices at intervals not exceeding 48 inches and with no less than two supports per straight raceway section. Support surface raceway according to manufacturer's written instructions. Tape and glue are not acceptable support methods.
- W. Install raceway sealing fittings at accessible locations according to NFPA 70 and fill them with listed sealing compound. For concealed raceways, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces. Install raceway sealing fittings according to NFPA 70.
- X. Install devices to seal raceway interiors at accessible locations. Locate seals so no fittings or boxes are between the seal and the following changes of environments. Seal the interior of all raceways at the following points:
 - 1. Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
 - 2. Where an underground service raceway enters a building or structure.
 - 3. Conduit extending from interior to exterior of building.
 - 4. Conduit extending into pressurized duct and equipment.

5. Conduit extending into pressurized zones that are automatically controlled to maintain different pressure set points.
 6. Where otherwise required by NFPA 70.
- Y. Comply with manufacturer's written instructions for solvent welding RNC and fittings.
- Z. Expansion-Joint Fittings:
1. Install in each run of aboveground RNC that is located where environmental temperature change may exceed 30 deg F and that has straight-run length that exceeds 25 feet. Install in each run of aboveground RMC and EMT conduit that is located where environmental temperature change may exceed 100 deg F and that has straight-run length that exceeds 100 feet.
 2. Install type and quantity of fittings that accommodate temperature change listed for each of the following locations:
 - a. Outdoor Locations Not Exposed to Direct Sunlight: 125 deg F temperature change.
 - b. Outdoor Locations Exposed to Direct Sunlight: 155 deg F temperature change.
 - c. Indoor Spaces Connected with Outdoors without Physical Separation: 125 deg F temperature change.
 - d. Attics: 135 deg F temperature change.
 3. Install fitting(s) that provide expansion and contraction for at least 0.00041 inch per foot of length of straight run per deg F of temperature change for PVC conduits. Install fitting(s) that provide expansion and contraction for at least 0.000078 inch per foot of length of straight run per deg F of temperature change for metal conduits.
 4. Install expansion fittings at all locations where conduits cross building or structure expansion joints.
 5. Install each expansion-joint fitting with position, mounting, and piston setting selected according to manufacturer's written instructions for conditions at specific location at time of installation. Install conduit supports to allow for expansion movement.
- AA. Flexible Conduit Connections: Comply with NEMA RV 3. Use a maximum of 36 inches of flexible conduit for recessed and semi-recessed luminaires, equipment subject to vibration, noise transmission, or movement; and for transformers and motors.
1. Use LFMC in damp or wet locations subject to severe physical damage.
 2. Use LFMC or LFNC in damp or wet locations not subject to severe physical damage.
- BB. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to center of box unless otherwise indicated.
- CC. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surfaces to provide a flat surface for a raintight connection between box and cover plate or supported equipment and box.
- DD. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.
- EE. Locate boxes so that cover or plate will not span different building finishes.

- FF. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for the purpose.
- GG. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.
- HH. Set metal floor boxes level and flush with finished floor surface.
- II. Set nonmetallic floor boxes level. Trim after installation to fit flush with finished floor surface.

3.3 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

3.4 FIRESTOPPING

- A. Install firestopping at penetrations of fire-rated floor and wall assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

3.5 PROTECTION

- A. Protect coatings, finishes, and cabinets from damage and deterioration.
 - 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
 - 2. Repair damage to PVC coatings or paint finishes with matching touchup coating recommended by manufacturer.

END OF SECTION 260533

SECTION 262726 - WIRING DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Standard-grade receptacles, 125 V, 20 A.
 - 2. GFCI receptacles, 125 V, 20 A.
 - 3. SPD receptacles, 125 V, 20 A.
 - 4. Toggle switches, 120/277 V, 20 A.
 - 5. Occupancy sensors.
 - 6. Wall plates.

1.3 DEFINITIONS

- A. AFCI: Arc-fault circuit interrupter.
- B. BAS: Building automation system.
- C. EMI: Electromagnetic interference.
- D. GFCI: Ground-fault circuit interrupter.
- E. Pigtail: Short lead used to connect a device to a branch-circuit conductor.
- F. RFI: Radio-frequency interference.
- G. SPD: Surge protective device.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: List of legends and description of materials and process used for premarking wall plates.
- C. Samples: One for each type of device and wall plate specified, in each color specified.

1.5 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For wiring devices to include in all manufacturers' packing-label warnings and instruction manuals that include labeling conditions.

PART 2 - PRODUCTS

2.1 GENERAL WIRING-DEVICE REQUIREMENTS

- A. Wiring Devices, Components, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
- B. Comply with NFPA 70.
- C. RoHS compliant.
- D. Comply with NEMA WD 1.
- E. Devices that are manufactured for use with modular plug-in connectors may be substituted under the following conditions:
 - 1. Connectors shall comply with UL 2459 and shall be made with stranding building wire.
 - 2. Devices shall comply with requirements in this Section.
- F. Devices for Owner-Furnished Equipment:
 - 1. Receptacles: Match plug configurations.
 - 2. Cord and Plug Sets: Match equipment requirements.
- G. Device Color:
 - 1. Wiring Devices Connected to Normal Power System: As selected by Owner unless otherwise indicated or required by NFPA 70 or device listing.
 - 2. Wiring Devices Connected to Essential Electrical System: Red.
 - 3. SPD Devices: Blue.
 - 4. Isolated-Ground Receptacles: As specified above, with orange triangle on face.
- H. Wall Plate Color: For plastic covers, match device color
- I. Source Limitations: Obtain each type of wiring device and associated wall plate from single source from single manufacturer.

2.2 STANDARD-GRADE RECEPTACLES, 125 V, 20 A

- A. Duplex Receptacles, 125 V, 20 A:
 - 1. Description: Two pole, three wire, and self-grounding.
 - 2. Configuration: NEMA WD 6, Configuration 5-20R.
 - 3. Standards: Comply with UL 498 and FS W-C-596.

- B. Isolated-Ground Duplex Receptacles, 125 V, 20 A:
 - 1. Description: Straight blade; equipment grounding contacts shall be connected only to green grounding screw terminal of the device and with inherent electrical isolation from mounting strap. Isolation shall be integral to receptacle construction and not dependent on removable parts. Two pole, three wire, and self-grounding.
 - 2. Configuration: NEMA WD 6, Configuration 5-20R.
 - 3. Standards: Comply with UL 498 and FS W-C-596.

- C. Tamper-Resistant Duplex Receptacles, 125 V, 20 A:
 - 1. Description: Two pole, three wire, and self-grounding. Integral shutters that operate only when a plug is inserted in the receptacle.
 - 2. Configuration: NEMA WD 6, Configuration 5-20R.
 - 3. Standards: Comply with UL 498 and FS W-C-596.
 - 4. Marking: Listed and labeled as complying with NFPA 70, "Tamper-Resistant Receptacles" Article.

- D. Weather-Resistant Duplex Receptacle, 125 V, 20 A:
 - 1. Description: Two pole, three wire, and self-grounding. Integral shutters that operate only when a plug is inserted in the receptacle. Square face.
 - 2. Configuration: NEMA WD 6, Configuration 5-20R.
 - 3. Standards: Comply with UL 498.
 - 4. Marking: Listed and labeled as complying with NFPA 70, "Receptacles in Damp or Wet Locations" Article.

- E. Tamper- and Weather-Resistant Duplex Receptacles, 125 V, 20 A:
 - 1. Description: Two pole, three wire, and self-grounding. Integral shutters that operate only when a plug is inserted in the receptacle. Square face.
 - 2. Configuration: NEMA WD 6, Configuration 5-20R.
 - 3. Standards: Comply with UL 498.
 - 4. Marking: Listed and labeled as complying with NFPA 70, "Tamper-Resistant Receptacles" and "Receptacles in Damp or Wet Locations" articles.

2.3 GFCI RECEPTACLES, 125 V, 20 A

- A. Duplex GFCI Receptacles, 125 V, 20 A:
 - 1. Description: Integral GFCI with "Test" and "Reset" buttons and LED indicator light. Two pole, three wire, and self-grounding.
 - 2. Configuration: NEMA WD 6, Configuration 5-20R.
 - 3. Type: Feed through.
 - 4. Standards: Comply with UL 498, UL 943 Class A, and FS W-C-596.

- B. Tamper-Resistant Duplex GFCI Receptacles, 125 V, 20 A:

1. Description: Integral GFCI with "Test" and "Reset" buttons and LED indicator light. Two pole, three wire, and self-grounding. Integral shutters that operate only when a plug is inserted in the receptacle.
2. Configuration: NEMA WD 6, Configuration 5-20R.
3. Type: Feed through.
4. Standards: Comply with UL 498, UL 943 Class A, and FS W-C-596.
5. Marking: Listed and labeled as complying with NFPA 70, "Tamper-Resistant Receptacles" Article.

C. Tamper- and Weather-Resistant, GFCI Duplex Receptacles, 125 V, 20 A:

1. Description: Integral GFCI with "Test" and "Reset" buttons and LED indicator light. Two pole, three wire, and self-grounding. Integral shutters that operate only when a plug is inserted in the receptacle. Square face.
2. Configuration: NEMA WD 6, Configuration 5-15R.
3. Type: Feed through.
4. Standards: Comply with UL 498 and UL 943 Class A.
5. Marking: Listed and labeled as complying with NFPA 70, "Tamper-Resistant Receptacles" and "Receptacles in Damp or Wet Locations" articles.

2.4 SPD RECEPTACLES, 125 V, 20 A

A. Duplex SPD Receptacles, 125 V, 20 A:

1. Description: Two pole, three wire, and self-grounding. Integral SPD in line to ground, line to neutral, and neutral to ground. LED indicator light.
2. SPD Components: Multiple metal-oxide varistors; with a nominal clamp-level rating of 400 V and minimum single transient pulse energy dissipation of 240 J, according to IEEE C62.41.2 and IEEE C62.45.
3. Active SPD Indication: Visual and audible, with light visible in face of device to indicate device is "active" or "no longer in service."
4. Configuration: NEMA WD 6, Configuration 5-20R.
5. Standards: Comply with NEMA WD 1, UL 498, UL 1449, and FS W-C-596.

B. Isolated-Ground Duplex SPD Receptacles, 125 V, 20 A:

1. Description: Two pole, three wire, and self-grounding. Integral SPD in line to ground, line to neutral, and neutral to ground. LED indicator light.
2. SPD Components: Multiple metal-oxide varistors; with a nominal clamp-level rating of 400 V and minimum single transient pulse energy dissipation of 240 J, according to IEEE C62.41.2 and IEEE C62.45.
3. Active SPD Indication: Visual and audible, with light visible in face of device to indicate device is "active" or "no longer in service."
4. Grounding: Equipment grounding contacts shall be connected only to green grounding screw terminal of the device and with inherent electrical isolation from mounting strap. Isolation shall be integral to receptacle construction and not dependent on removable parts.
5. Configuration: NEMA WD 6, Configuration 5-20R.
6. Standards: Comply with UL 498, UL 1449, and FS W-C-596.

2.5 CORD AND PLUG SETS

- A. Match voltage and current ratings and number of conductors to requirements of equipment being connected.
- B. Cord: Rubber-insulated, stranded-copper conductors, with Type SOW-A jacket; with green-insulated grounding conductor and ampacity of at least 130 percent of the equipment rating.
- C. Plug: Nylon body and integral cable-clamping jaws. Match cord and receptacle type for connection.

2.6 TOGGLE SWITCHES, 120/277 V, 20 A

- A. Single-Pole Switches, 120/277 V, 20 A:
 - 1. Standards: Comply with UL 20 and FS W-S-896.
- B. Two-Pole Switches, 120/277 V, 20 A:
 - 1. Comply with UL 20 and FS W-S-896.
- C. Three-Way Switches, 120/277 V, 20 A:
 - 1. Comply with UL 20 and FS W-S-896.
- D. Four-Way Switches, 120/277 V, 20 A:
 - 1. Standards: Comply with UL 20 and FS W-S-896.

2.7 OCCUPANCY SENSORS

- A. Wall Switch Sensor Light Switch, Dual Technology:
 - 1. Description: Switchbox-mounted, combination lighting-control sensor and conventional switch lighting-control unit using dual (ultrasonic and passive infrared) technology.
 - 2. Standards: Comply with UL 20.
 - 3. Rated 960 W at 120 V ac for tungsten lighting, 10 A at 120 V ac or 10 A at 277 V ac for fluorescent or LED lighting, and 1/4 hp at 120 V ac.
 - 4. Adjustable time delay of 10 minutes.
 - 5. Able to be locked to Manual-On mode.
 - 6. Automatic Light-Level Sensor: Adjustable from 2 to 200 fc.
 - 7. Connections: Provisions for connection to BAS.
 - 8. Connections: RJ-45 communications outlet.
 - 9. Connections: Integral wireless networking.

2.8 WALL PLATES

- A. Single Source: Obtain wall plates from same manufacturer of wiring devices.
- B. Single and combination types shall match corresponding wiring devices.
 - 1. Plate-Securing Screws: Metal with head color to match plate finish.
 - 2. Material for Finished Spaces: Steel with white baked enamel, suitable for field painting.

3. Material for Unfinished Spaces: Galvanized steel
 4. Material for Damp Locations: Cast aluminum with spring-loaded lift cover, and listed and labeled for use in wet and damp locations.
- C. Wet-Location, Weatherproof Cover Plates: NEMA 250, complying with Type 3R, weather-resistant, die-cast aluminum with lockable cover.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with NECA 1, including mounting heights listed in that standard, unless otherwise indicated.
- B. Coordination with Other Trades:
1. Protect installed devices and their boxes. Do not place wall finish materials over device boxes, and do not cut holes for boxes with routers that are guided by riding against outside of boxes.
 2. Keep outlet boxes free of plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other material that may contaminate the raceway system, conductors, and cables.
 3. Install device boxes in brick or block walls so that the cover plate does not cross a joint unless the joint is troweled flush with the face of the wall.
 4. Install wiring devices after all wall preparation, including painting, is complete.
- C. Conductors:
1. Do not strip insulation from conductors until right before they are spliced or terminated on devices.
 2. Strip insulation evenly around the conductor using tools designed for the purpose. Avoid scoring or nicking of solid wire or cutting strands from stranded wire.
 3. The length of free conductors at outlets for devices shall comply with NFPA 70, Article 300, without pigtails.
 4. Existing Conductors:
 - a. Cut back and pigtail, or replace all damaged conductors.
 - b. Straighten conductors that remain and remove corrosion and foreign matter.
 - c. Pigtail existing conductors is permitted, provided the outlet box is large enough.
- D. Device Installation:
1. Replace devices that have been in temporary use during construction and that were installed before building finishing operations were complete.
 2. Keep each wiring device in its package or otherwise protected until it is time to connect conductors.
 3. Do not remove surface protection, such as plastic film and smudge covers, until the last possible moment.
 4. Connect devices to branch circuits using pigtails that are not less than 6 inches in length.

5. When there is a choice, use side wiring with binding-head screw terminals. Wrap solid conductor tightly clockwise, two-thirds to three-fourths of the way around terminal screw.
6. Use a torque screwdriver when a torque is recommended or required by manufacturer.
7. When conductors larger than No. 12 AWG are installed on 15- or 20-A circuits, splice No. 12 AWG pigtails for device connections.
8. Tighten unused terminal screws on the device.
9. When mounting into metal boxes, remove the fiber or plastic washers used to hold device-mounting screws in yokes, allowing metal-to-metal contact.

E. Receptacle Orientation:

1. Install ground pin of vertically mounted receptacles down, and on horizontally mounted receptacles to the right.
2. Install hospital-grade receptacles in patient-care areas with the ground pin or neutral blade at the top.

F. Device Plates: Do not use oversized or extra-deep plates. Repair wall finishes and remount outlet boxes when standard device plates do not fit flush or do not cover rough wall opening.

G. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical and with grounding terminal of receptacles on top. Group adjacent switches under single, multigang wall plates.

H. Adjust locations of floor service outlets and service poles to suit arrangement of partitions and furnishings.

3.2 GFCI RECEPTACLES

- A. Install non-feed-through GFCI receptacles where protection of downstream receptacles is not required.

3.3 IDENTIFICATION

- A. Identify each receptacle with panelboard identification and circuit number. Use hot, stamped, or engraved machine printing with black-filled lettering on face of plate, and durable wire markers or tags inside outlet boxes.
- B. Essential Electrical System: Mark receptacles supplied from the essential electrical system to allow easy identification using a self-adhesive label.

3.4 FIELD QUALITY CONTROL

- A. Test Instruments: Use instruments that comply with UL 1436.
- B. Test Instrument for Receptacles: Digital wiring analyzer with digital readout or illuminated digital-display indicators of measurement.

- C. Perform the following tests and inspections:
 - 1. In healthcare facilities, prepare reports that comply with NFPA 99.
 - 2. Test Instruments: Use instruments that comply with UL 1436.
 - 3. Test Instrument for Receptacles: Digital wiring analyzer with digital readout or illuminated digital-display indicators of measurement.

- D. Tests for Receptacles:
 - 1. Line Voltage: Acceptable range is 105 to 132 V.
 - 2. Percent Voltage Drop under 15-A Load: A value of 6 percent or higher is unacceptable.
 - 3. Ground Impedance: Values of up to 2 ohms are acceptable.
 - 4. GFCI Trip: Test for tripping values specified in UL 1436 and UL 943.
 - 5. Using the test plug, verify that the device and its outlet box are securely mounted.
 - 6. Tests shall be diagnostic, indicating damaged conductors, high resistance at the circuit breaker, poor connections, inadequate fault-current path, defective devices, or similar problems. Correct circuit conditions, remove malfunctioning units and replace with new ones, and retest as specified above.

- E. Wiring device will be considered defective if it does not pass tests and inspections.

- F. Prepare test and inspection reports.

END OF SECTION 262726

SECTION 26 51 00
INTERIOR LIGHTING

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes the following:
 - 1. Interior lighting fixtures, lamps, and ballasts.
 - 2. Emergency lighting units.
 - 3. Lighting fixture supports.

1.2 SUBMITTALS

- A. Product Data: For each type of lighting fixture, arranged in order of fixture designation. Include data on features, accessories, finishes.
- B. Shop Drawings: Show details of nonstandard or custom lighting fixtures. Indicate dimensions, weights, methods of field assembly, components, features, and accessories.
- C. Product Certificates: For each type of ballast for bi-level and dimmer-controlled fixtures, signed by product manufacturer.
- D. Field quality-control test reports.

1.3 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NFPA 70.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In Interior Lighting Fixture Schedule where titles below are column or row headings that introduce lists, the following requirements apply to product selection:
 - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, manufacturers specified.
 - 2. Substitutions are subject to Architect/Owner approval.

2.2 LIGHTING FIXTURES

- A. LED Fixtures: Refer to drawing for "basis of design".
- B. Metal Parts: Free of burrs and sharp corners and edges.
- C. Sheet Metal Components: Steel, unless otherwise indicated. Form and support to prevent warping and sagging.
- D. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.
- E. Reflecting surfaces shall have minimum reflectance as follows, unless otherwise indicated:
 - 1. White Surfaces: 85 percent.
 - 2. Specular Surfaces: 83 percent.
 - 3. Diffusing Specular Surfaces: 75 percent.

4. Laminated Silver Metallized Film: 90 percent.

F. Plastic Diffusers, Covers, and Globes:

1. Acrylic Lighting Diffusers: 100 percent virgin acrylic plastic. High resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
 - a. Lens Thickness: At least 0.125 inch minimum unless different thickness is indicated.
 - b. UV stabilized.

2.3 BALLASTS

A. Refer to drawing for "basis of design".

2.4 EMERGENCY LIGHTING UNITS

A. Refer to drawing for "basis of design".

1. Battery: Sealed, maintenance-free, lead-acid type.
2. Charger: Fully automatic, solid-state type with sealed transfer relay.
3. Operation: Relay automatically turns lamp on when power supply circuit voltage drops to 80 percent of nominal voltage or below. Lamp automatically disconnects from battery when voltage approaches deep-discharge level. When normal voltage is restored, relay disconnects lamps from battery, and battery is automatically recharged and floated on charger.
4. Test Push Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
5. LED Indicator Light: Indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.

2.5 LAMPS

A. Refer to drawing for "basis of design".

2.6 LIGHTING FIXTURE SUPPORT COMPONENTS

- A. Comply with Division 26 Section "Hangers and Supports for Electrical Systems" for channel- and angle-iron supports, and nonmetallic channel and angle supports.
- B. Single-Stem Hangers: 1/2-inch steel tubing with swivel ball fittings and ceiling canopy. Finish same as fixture.
- C. Twin-Stem Hangers: Two, 1/2-inch steel tubes with single canopy designed to mount a single fixture. Finish same as fixture.
- D. Wires: ASTM A 641/A 641M, Class 3, soft temper, zinc-coated steel, 12 gage.
- E. Wires for Humid Spaces: ASTM A 580/A 580M, Composition 302 or 304, annealed stainless steel, 12 gage.
- F. Rod Hangers: 3/16-inch minimum diameter, cadmium-plated, threaded steel rod.
- G. Hook Hangers: Integrated assembly matched to fixture and line voltage and equipped with threaded attachment, cord, and locking-type plug.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Lighting fixtures: Set level, plumb, and square with ceilings and walls. Install lamps in each fixture.
- B. Comply with NFPA 70 for minimum fixture supports.
- C. Adjust amiable lighting fixtures to provide required light intensities.
- D. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

3.2 FIELD QUALITY CONTROL

- A. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery and retransfer to normal.
- B. Prepare a written report of tests, inspections, observations, and verifications indicating and interpreting results. If adjustments are made to lighting system, retest to demonstrate compliance with standards.

END OF SECTION