

Developing Tile Drain P Filters

Vermont Agricultural Water Quality Partnership, Scientific Advisory Committee

Date: May 2, 2022

Presented by: Dave Braun

Funding acknowledgement

Three projects are presented that have been funded wholly or in part by the United States Environmental Protection Agency under assistance agreements to NEIWPCC in partnership with the Lake Champlain Basin Program (LCBP). NEIWPCC manages LCBP's personnel, contract, grant, and budget tasks and provides input on the program's activities through a partnership with the LCBP Steering Committee.

The contents of this presentation do not necessarily reflect the views and policies of NEIWPCC, the LCBP Steering Committee, or the EPA, nor does NEIWPCC, the LCBP Steering Committee or the EPA endorse trade names or recommend the use of commercial products mentioned in this document.

Tile drainage primer

Tile drainage changes the hydrologic behavior of a field, enhancing infiltration and ground water transmission while reducing surface runoff.



Tile drainage offers many benefits, both agronomic and environmental.

In fields otherwise too wet to farm efficiently, tile drainage enables:

- Increased crop yields
- Timely equipment access
- Timely application of conservation measures
- Reduced soil erosion and compaction
- Reduced surface runoff

Downside:

- Tile drainage provides a direct conduit from fields to receiving waters.
- Tile drainage can contribute significant amounts of P and N to surface waters

Tile drainage primer

Research accelerated when links were made between the “re-eutrophication” of western Lake Erie and no-till / tile drained agriculture




JBT11 monitoring station




manhole

outlet

Electromagnetic flowmeter at JBT11



ACT4 manhole, 12/3/18



ACT3 tile outlet, 10/8/19



Annual mean P concentrations in tile discharge¹

	[TP] (µg/L)	[TDP] (µg/L)
Range	45 – 1,166	23 – 762
Median	185	90
Mean	260	141

TP concentrations in JBW tile drainage comparable to ranges observed in NY, OH, WI, Quebec, and Ontario

Median Jewett Br. [TP] = 390 µg/L
 St. Albans Bay target: [TP] = 17 µg/L

1. Calculated by site as total annual P load / total discharge volume

Annual areal P loads in tile discharge

	Areal TP load (kg/ha/yr)	Areal TDP load (kg/ha/yr)
Range	0.12 – 1.12	0.083 – 0.56
Median	0.54	0.20
Mean	0.56	0.27
95% C.I.	0.37 – 0.74	0.17 – 0.38

TP loads in JBW tile drainage comparable to loads observed in tile drainage elsewhere:

Quebec (LCB) = 0.61 kg/ha/yr
 Ohio = 0.28 – 0.92 kg/ha/yr

BMPs for P in Tile Drainage

- Eliminate surface inlets
- Change depth/spacing of drainage lines
- Reduce rates of manure/nutrient applications
- Adjust timing of manure/nutrient applications
- Reduction in preferential flow paths (e.g., shallow tillage)
- Drainage water management/conservation drainage
- **Drainage water treatment with P sorbing media**

Vermont NRCS's Conservation Practice Standard:


Phosphorus Removal System (Code 782) (Under Evaluation)

- Overly general technical requirements need work.
- However, this practice standard establishes the basis for implementing and funding these P removal systems through EQIP.

Questions we are asking in designing P filters:


- Mass of P to be removed
- Influent P concentrations—How low can we go? Is it worth it?
- Longevity
- Cost effectiveness
- Eventual disposition of the media (replacement, removal, or leave in place)

Stone's first attempt, on a farm in Franklin, VT







Filter B:
Limestone "bedding sand"

Filter A:
Drinking water treatment residuals




Our second attempt began in the garage





File: O:\PROJ\18-006\18-006_CIP tile monitoring & treatment\CAD\Survey.dwg

#	Date	Drawn	Chk'd	App'd	Description
1	07/14/2021				Drawn On: 07/14/2021
2					Drawn By: MLS
3	07/15/2021				Checked On: 07/15/2021
4					Checked By: DCB
5					Project No.: 18-006



LCBP TILE MONITORING & TREATMENT
ST. ALBANS P FILTER
AS-BUILT PLAN
ST. ALBANS VERMONT

SECRET 1

Adding stone in filter trench



Spreading and raking in activated alumina and iron



Comparison of P filters at site JBT05

P loading (2017-2018): mean TP = 168 ug/L, TP load =14 kg/yr, 77% dissolved

Design:

- Upflow media filter
- 50 ft long x 5 ft wide x 2.1 ft depth of P reactive media
- Residence time of water in filter should be almost an hour
- No power or moving parts; just hydraulics and large quantities of filter media

	Filter A	Filter B
Media	60 tons of ½-inch Swanton black shale	55 tons of ½-inch Swanton black shale (90% by vol.), 2700 lb. of activated alumina (8% by vol.), and 2000 lb. elemental iron (2% by vol.)
Total cost	\$4,000	\$10,000

View down filter outlet manhole



Customized autosampler installation in filter outlet manhole




St. Albans P filter performance (full report coming soon)

Substantial P removal from both filters:

Filter A (Swanton black only):
31% TP and 25% TDP Removal

Filter B (Swanton black + AA + iron):
48% TP and 45% TDP Removal




Dorset Park stormwater pond P filters in South Burlington



Dorset Park stormwater pond P filters



Filter media



1/2" Swanton black shale



drinking water treatment residuals



iron shavings




activated alumina

Filter media






- NOTES:
- DRAWING ON SHEET 2 IS ROTATED 90 DEGREES COUNTER-CLOCKWISE FROM DRAWING ON SHEET 1
 - ALTHOUGH SHOWN WITH SOLID LINES, ALL PIPES ARE BURIED UNLESS OTHERWISE NOTED.
 - **T** LABELS ARE RISER STRUCTURE FACE LABELS CORRESPONDING TO DETAILS ON SHEET 3.
 - **A** LABELS ARE FILTER BOX LABELS CORRESPONDING TO FILTER MEDIA TABLE ON THIS SHEET



Filter	Media	Additive by volume
A	5.4 cubic yards 1/2" shale + 1100 lb. 3/16" AA	13.6%
B	6.0 cubic yards 1/2" shale	NA
C	5.4 cubic yards 1/2" shale + 88 gal. DWTR	7.5%
D	5.4 cubic yards 1/2" shale + 1800 lb. CC-1107 iron	7.6%

AS-BUILT DRAWINGS

#	DATE	DRWN	CHK'D	APP'D	DESCRIPTION



STONE ENVIRONMENTAL
 535 Stone Cutters Way / Montpelier / VT / 05602 / USA
 802.229.4541 / info@stone-env.com / www.stone-env.com

DORSET PARK STORMWATER POND P FILTER
 FILTER LAYOUT
 SOUTH BURLINGTON VERMONT

SHEET NO. **2**

Data from the pond study are trickling in




Early findings:

1. Encouraged by substantial filter flow rates, up to 18 gpm (68 L/min) to date, though may need to reduce flow rates to achieve adequate residence time for treatment.
2. Poor P removal seen in all filters at low influent P concentrations ($\leq 40 \mu\text{g/L}$)
3. Significant P removal ($\sim 40\%$) in all filters during a high flow period with high inflow P concentrations ($100 \mu\text{g/L}$)
4. Filter D (iron shavings) thus far achieving the lowest P concentrations

Lake Carmi tile drain P filters (construction planned for August)

Objectives:

- To reduce P loading from tile drains to Lake Carmi
- To refine the P filter design to improve performance, improve constructability, and reduce cost
- To demonstrate use of tile drain P filters to farmers



Filter	Swanton black shale	Activate alumina	Iron shavings
Filter 1	80%	17%	3%
Filter 2	80%	14%	6%
Filter 3	90%	7%	3%
Filter 4	90%	4%	6%

Some lessons learned to date

- Avoid poorly constructed tile drains (especially with holes)
- Upflow/lateral flow design is better than downflow
- Selected media must have high hydraulic conductivity
- Use perforated, rigid pipe (SDR35) for distribution and collection
- While it should be possible to design filters for most sites, avoid drains with submerged outlets if possible
- Local crushed black shale amended with zero valent iron is looking good





Thank you.

Contact: dbraun@stone-env.com




Jewett Brook Watershed tile drains—TP concentrations

★ High outlier at JBT13 on May 16, 2017: TP=35,295 µg/L





FILTER CROSS SECTION
Horizontal Scale: 1"=10'
Vertical Scale: 1"=2.5'



#	DATE	DRWN	CHK'D	APP'D	DESCRIPTION

STONE ENVIRONMENTAL
535 Stone Cutters Way / Montpelier / VT / 05602 / USA
802.229.4541 / info@stone-env.com / www.stone-env.com

DORSET PARK STORMWATER POND P FILTER
FILTER SECTION AND RISER DETAILS
SOUTH BURLINGTON VERMONT

3