# What a Civil Engineer Should Do Before Resurfacing Sierra Del Mar's Roads – Why Didn't the Board Choose to do this?

## —and Why It Protects Our Community**

Before any community invests hundreds of thousands of dollars into resurfacing its roads, a qualified civil engineer must follow a professional, step-by-step process. These tasks are not optional — they are standard industry practice. When they're skipped, communities pay more, roads fail sooner, and residents lose trust in their Board.

Below is the full list of tasks a civil engineer performs and the benefits each one delivers to Sierra Del Mar homeowners.

### 1. Comprehensive Roadway Condition Survey

**What the Engineer Does:**

Evaluates every street for cracking, potholes, rutting, drainage failures, and past utility cuts

Documents problem areas with photos and maps

**Why It Matters:**

- Reveals the true health of our roads
- Ensures resurfacing isn't done blindly or uniformly
- Identifies where deeper structural repair is required

### 2. Pavement Core Sampling (Full-Depth Cores)

**What the Engineer Does:**

Drills core samples that show all pavement layers

Sends them to a lab to analyze thickness, bonding, and material integrity

**Why It Matters:**

- Confirms whether resurfacing is appropriate or unsafe
- Prevents expensive premature failure caused by hidden weaknesses
- Provides the data needed to design a proper resurfacing plan

### 3. Laboratory Testing of Asphalt and Base Materials

**What the Engineer Tests:**

Asphalt density, air voids, binder content, gradation

Subbase and soil strength beneath the pavement

**Why It Matters:**

- Tells us whether the road has the strength to accept new asphalt
- Ensures the repair strategy matches actual conditions, not assumptions
- Protects the community's long-term investment

### 4. Drainage and Water Flow Evaluation

**What the Engineer Looks At:**

Gutters, swales, slope, ponding areas, catch basins

**Why It Matters:**

- Poor drainage is the #1 enemy of pavement
- Resurfacing without fixing drainage guarantees early failure
- Protects against water infiltration, cracking, and base erosion

### 5. Traffic Load Analysis

**What the Engineer Analyzes:**

Vehicle counts, speeds, and heavy truck loads

Impact of waste trucks, delivery trucks, and service vehicles

**Why It Matters:**

- Ensures the pavement design can handle real-world loads
- Prevents rutting and structural cracking
- Extends pavement life 15–30% with proper design

### 6. Structural Evaluation (FWD Testing)

**What the Engineer Does:**

Uses a Falling Weight Deflectometer to measure pavement stiffness and support

**Why It Matters:**

- Identifies weak zones invisible at the surface
- Determines correct overlay thickness
- Ensures we don't overspend or underspend on asphalt

### 7. Utility and Subsurface Conflict Review

**What the Engineer Checks:**

Locations of water, sewer, electrical, telecom, and past trenching

**Why It Matters:**

- Prevents resurfacing over unstable utility patches
- Reduces the chance of future collapses, sinking, or cracking
- Helps coordinate repairs before paving begins

### 8. Development of Resurfacing Options

**What the Engineer Produces:**

Side-by-side comparisons of milling, overlay, or reconstruction

Asphalt thickness design

Cost, lifespan, and maintenance projections

**Why It Matters:**

- Gives homeowners transparency and real choices
- Bases decisions on science rather than convenience
- Ensures the Board selects the most cost-effective long-term solution

### 9. Creation of Specifications & Construction Documents

**What the Engineer Writes:**

Detailed specifications for asphalt mix design, compaction, milling depth

Plans, schedules, traffic management, and quality-control measures

**Why It Matters:**

- Forces contractors to bid on an identical, clearly defined scope
- Eliminates ambiguity, shortcuts, and surprise change orders
- Protects the community during construction

### 10. Contractor Bid Review & Selection Support

**What the Engineer Does:**

Evaluates contractor qualifications, equipment, pricing, and past performance

Identifies low-bid risks or unrealistic proposals

**Why It Matters:**

- Ensures Sierra Del Mar hires a qualified, reputable contractor
- Reduces the risk of poor workmanship or inflated costs
- Protects homeowners' money and expectations

### 11. On-Site Construction Oversight

**What the Engineer Monitors:**

Milling depth, asphalt temperature, compaction levels

Correct material use and adherence to specifications

**Why It Matters:**

- Prevents "corner-cutting" by contractors
- Ensures the new road reaches its full design life
- Documents every stage for transparency and accountability

\Why Engineer

### 12. Final Report & Maintenance Strategy

**What the Engineer Delivers:**

Final inspection and documentation of all completed work

A long-term maintenance plan (crack sealing, patching cycles, seal coat schedule)

**Why It Matters:**

- Extends pavement life by 5–10 years with simple maintenance
- Helps the community budget intelligently
- Ensures all work is recorded and transparent

## Bottom Line for Sierra Del Mar

**A proper civil-engineering process protects homeowners, ensures transparency, and prevents the community from making costly mistakes that could have been avoided with professional planning and testing.**