


Sprinkler Head Schedule					
Symbol	Count	Thread	KF	Description	Temp
○	22	3/4"	11.2	VICTAULIC V3403 FL-SR BRASS UPRIGHT	200°F
●	268	3/4"	8.0	VICTAULIC V3401 FL-SR BRASS UPRIGHT	200°F
○	23	3/4"	16.8	VICTAULIC V4702 ESFR BRASS PENDENT	200°F
313 = Total Number of Heads This Sheet					



KEY PLAN
NO SCALE

SEE SHEET FP2

SEE SHEET FP4

1 PLAN VIEW
1/8" = 1'-0"

EXISTING SPRINKLER ZONES #26 AND #27 ARE TO BE SUPPLIED FROM NEW UNDC SUPPLY IN NEW SOUTH ADDITION.
THE MAJORITY OF ZONE 26 & 27 ARE DESIGNATED AS MANUFACTURING WITH SOME LOW-PILED STORAGE.
PER NFPA-13 REQUIREMENTS, A DRAFT CURTAIN IS REQUIRED TO SEPARATE ESFR SPRINKLERS FROM STANDARD-RESPONSE SPRINKLERS.