

SMARTKORNERS / Outside - 90 Degree Corner	Duration in days	Labor Hours	**Labor Cost	Material	Total Cost
Hang Drywall 8' Sheet (SmartKorners)		0.17	\$11.46	\$32.00	
Finished		0	\$0.00	\$0.00	
Total	1/4 hour	0.17	\$11.46	\$32.00	\$43.46

TRADITIONAL METHOD / Outside - 90 Degree Corner	Duration in days	Labor Hours	**Labor Cost	Material	Total
Hang board & trim edges.		0.17	\$11.46	\$15.00	
Install corner bead		0.17	\$11.46	\$7.00	
Apply first coat of joint compound. Dry time 1-2 days.	2	0.17	\$11.46	\$10.00	
Sand		0.17	\$11.46	\$2.00	
Apply second coat of joint compound. Dry time 1-2 days.	1	0.17	\$11.46	\$10.00	
Sand		0.17	\$11.46	\$2.00	
Apply finish coat of joint compound. Dry time 1 day.	1	0.17	\$11.46	\$5.00	
Sand & touch up		0.17	\$11.46	\$3.00	
Total	4	1.36	\$91.66	\$54.00	\$145.66

SMARTKORNERS / Inside - 90 Degree Corner	Duration in days	Labor Hours	**Labor Cost	Material	Total Cost
Hang Drywall 8' Sheet (SmartKorners)		0.17	\$11.46	\$32.00	
Finished		0	\$0.00	\$0.00	
Total		0.17	\$11.46	\$32.00	\$43.46
Total Days	0.25				

TRADITIONAL METHOD / Inside - 90 Degree Corner	Duration in days	Labor Hours	**Labor Cost	Material	Total
Hang board		0.17	\$11.46	15.00	
Tape inside corner		0.17	\$11.46	4.50	
Apply first coat of joint compound. Dry time 1-2 days.		0.17	\$11.46	10.00	
Sand		0.17	\$11.46	2.00	
Apply second coat of joint compound. Dry time 1-2 days.		0.17	\$11.46	5.00	
Sand		0.17	\$11.46	2.00	
Apply finish coat of joint compound. Dry time 1 day.		0.17	\$11.46	5.00	
Sand & touch up		0.17	\$11.46	3.00	
Total		1.36	\$91.66	46.50	\$138.16
Total Days	4				

****LABOR HOURS ARE BASED ON ILLINOIS PERVAING WAGE****

